

THE
PRINCIPLES OF CHEMISTRY

BY
D. MENDELÉEFF
MENDELÉEV

TRANSLATED FROM THE RUSSIAN (FIFTH EDITION) BY

GEORGE KAMENSKY, A.R.S.M.

OF THE IMPERIAL MINT, ST PETERSBURG

EDITED BY

A. J. GREENAWAY, F.I.C.

SUB-EDITOR OF THE JOURNAL OF THE CHEMICAL SOCIETY

LONDON
LONGMANS, GREEN, AND CO.
AND NEW YORK: 15 EAST 16th STREET
1891

540
M53p
TK15
v. 1

PREFACE

TO THE

ENGLISH TRANSLATION

IN presenting to the scientific world an English translation of the text-book of Chemistry written by the great master of the Periodic Law, we feel that no apology is necessary, for it was in preparing the first edition of this book that the author was led to those considerations which resulted in the discovery of that law, and, moreover, the book is quite unique in its treatment of its subject.

In order to convey as nearly and clearly as possible the exact meaning of the author, it has been our endeavour to give, as far as the genius of the two languages permits, a literal rendering of the original work. Some exception may no doubt be taken to some of the sentences, but it was felt on the whole that it would be better to have some inelegance of language rather than to risk the loss of the exact shade of meaning that the author had intended to convey.

We have not considered ourselves at liberty to make any alterations in the matter of the work, save the omission of two notes referring to the meaning of Russian words, and of some details referring to the waters of the streams near St. Petersburg, which required local knowledge to be of any utility. It has, however, been necessary to make a considerable change in the

illustrations, as electro-types of the figures in the original could not be obtained.

Since the publication of the Russian fifth edition, Professor Mendeléeff has issued some appendices to the work, which will be found printed at the end of Volume II. We have to express our thanks to the Managers of the Royal Institution for permission to reprint the lecture delivered at the Royal Institution by Professor Mendeléeff (Appendix I.), and to the Council of the Chemical Society for permission to reprint the Faraday lecture which forms Appendix II.

In conclusion, we would express our gratitude to Professor Kinch for the aid so kindly given in revising the sheets for the press.

G. K.

A. J. G.

October, 1891.

AUTHOR'S PREFACE

TO

THE FIFTH EDITION

THIS work was written during the years 1868-1870, its object being to acquaint the student not only with the methods of observation, the experimental facts, and the laws of chemistry, but also with the aspect of this science towards the invariable substance of varying matter. If the facts themselves include the person who observes them, then how much more inevitable is the reflection of personality in giving an account of methods and of philosophical speculations? For the same reason there will inevitably be much that is subjective in every objective exposition of science. And as an individual production is only significant in virtue of that which has preceded and which surrounds it, so it essentially resembles a mirror which in reflecting exaggerates the size and clearness of neighbouring objects, and causes a person near it to see reflected most plainly those objects which are on the side to which it is directed. Although I have endeavoured to make my book a true mirror directed towards the domains of chemical transformations, yet involuntarily those influences near to me have been the most clearly reflected, the most brightly illuminated, and have tinted the entire work with their colouring. In this way the chief peculiarity of the book has been determined. Experimental and practical data occupy their place, but the philo-

sophical principles of our science form the chief theme of the work. In former times sciences, like bridges, could only be built up by supporting them on a few deep abutments and long girders. In addition to the exposition of the principles of chemistry, it has been my desire to show how science has now been built up like a suspension bridge, supported by the united strength of a number of slender, but firmly-fixed, threads, which individually are of little strength, and has thus been carried over difficulties which before appeared impassable. In comparing the science of the past, the present, and the future, in placing the particulars of its restricted experiments side by side with its aspirations for unbounded and infinite truth, and in restraining myself from yielding to a bias towards following the most attractive representation, I have endeavoured to incite in the reader a spirit of inquiry, which, unsatisfied with speculative reasonings alone, should subject every idea to experiment, excite the habit of stubborn work, necessitate a knowledge of the past, and a search for fresh threads to complete the bridge over the bottomless unknown. Experience proves that it is possible by this means to avoid two equally pernicious extremes, the Utopian—a visionary contemplation which proceeds from a current of thought only—and the realistic stagnation which is content with bare facts. In sciences like chemistry, which treat of ideas as well as of the substances of nature, experience demonstrates at every step that the work of the past has availed much, and that without it it would be impossible to advance ‘into the ocean of the unknown.’ We are compelled to value their history, to cast aside classical illusions, and to engage in a work which not only gives mental satisfaction but is also practically useful.¹

¹ Chemistry, like every other science, is at once a means and an end. It is a means of attaining certain practicable aspirations. Thus, by its assistance, the obtaining of matter in its various forms is facilitated; it shows new possibilities of availing ourselves of the forces of nature, indicates the methods of preparing many substances, points out their properties, etc. In this sense chemistry is closely connected with the work of the manufacturer and the artisan, its sphere is active, and is a means of promoting general welfare. Besides this honourable vocation, chemistry has another. With it, as with every other elaborated science, there are many lofty aspirations, the contemplation of which serves to inspire its workers and partisans. This contemplation comprises not only the principal data

Thus the desire to direct those thirsting for truth to the pure source of the science of the forces acting throughout nature forms

of the science, but also the generally-accepted deductions, and also hypotheses, which refer to phenomena as yet but imperfectly known. In this latter sense scientific contemplation varies much with times and persons, it bears the stamp of creative power, and comprehends the highest branch of scientific progress. In that pure enjoyment experienced on approaching to the ideal, in that eagerness to draw aside the veil from the hidden truth, and even in that discord which exists between the various workers, we ought to see the surest pledges of further scientific success. Science thus advances, discovering new truths, and at the same time obtaining practical results. The edifice of science not only requires material but also a plan, and necessitates the work of preparing the materials, putting them together, working out the plans and the symmetrical proportions of the various parts. To conceive, understand, and grasp the whole symmetry of the scientific edifice, including its unfinished portions, is equivalent to tasting that enjoyment only conveyed by the highest forms of beauty and truth. Without the material, the plan alone is but a castle in the air, a mere possibility, whilst the material without a plan is but useless matter; all depends on the concordance of the materials with the plan and execution, and the general harmony thereby attained. In the work of science, the artisan, architect, and creator are very often one and the same individual, but sometimes, as in other walks of life, there is a difference between them; sometimes the plan is preconceived, sometimes it follows the preparation and accumulation of the raw material. Free access to the edifice of science is not only allowed to those who devised the plan, worked out the detailed drawings, prepared the materials, or piled up the brick-work, but also to all those who are desirous of making a close acquaintance with the plan, and wish to avoid dwelling in the vaults or in the garrets where the useless lumber is stored.

Knowing how contented, free, and joyful is life in the realms of science, one fervently wishes that many would enter their portals. On this account many pages of this treatise are unwittingly stamped with the earnest desire that the habits of chemical contemplation which I have endeavoured to instil into the minds of my readers will incite them to the further study of science. Science will then flourish in them and by them, on a fuller acquaintance not only with that little which is enclosed within the narrow limits of my work, but with the further learning which they must imbibe in order to make themselves masters of our science and partakers in its further advancement.

Those who enlist in the cause of science have no reason to fear when they remember the urgent need for practical workers in the spheres of agriculture, arts, and manufacture. By summoning adherents to the work of theoretical chemistry, I am confident that I call them to a most useful labour, to the habit of dealing correctly with nature and its laws, and to the possibility of becoming truly practical men. In order to become actual chemists, it is necessary for beginners to be well and closely acquainted with three important branches of chemistry—analytical, organic, and theoretical. That part of chemistry which is dealt with in this treatise is only the groundwork of the edifice. For the learning and development of chemistry in its truest and fullest sense, beginners ought, in the first place, to turn their attention to the practical work of analytical chemistry; in the second place, to practical and theoretical acquaint-

the first and most important aim of this book. The time has arrived when a knowledge of physics and chemistry forms as important a part of education as that of the classics did two centuries ago. In those days the nations which excelled in classical learning stood foremost, just as now the most advanced are those which are superior in the knowledge of the natural sciences. I also wished to show in an elementary treatise on chemistry the palpable advantages gained by the application of the periodic law, which I first saw in its entirety in the year 1869 when I was engaged in writing the first edition of this book, in which, indeed, the law was first enunciated. Then, however, this law was not established so firmly as now, when so many of its consequences have been verified by the researches of numerous chemists, and especially by Roscoe, Lecoq de Boisbaudran, Nilson, Brauner, Thorpe, Carnelley, Laurie, Winkler, and others. As the entire scheme of this work² is subjected to the law of periodicity, which may be illustrated in a

ance with some special chemical question, studying the original treatises of the investigators of the subject (at first, under the direction of experienced teachers), because in working out particular facts the faculty of judgment and of correct criticism becomes sharpened; in the third place, to a knowledge of current scientific questions through the special chemical journals and papers, and by intercourse with other chemists. The time has come to turn aside from visionary contemplation, from platonic aspirations, and from classical verbosity, and to enter the regions of actual labour for the common weal, and to prove that the study of science is not only an excellent education for youth, but that it instils the virtues of labour and truth, and creates solid national wealth, material and mental, which without it would be unattainable. Science, which deals with the infinite, is itself without bounds.

² I recommend those who are commencing to study chemistry with my book *to first learn only what is printed in the large type*, because in that part I have endeavoured to concentrate all the fundamental, indispensable knowledge required for the study of chemistry. In the footnotes, printed in small type (which I advise being read only after the large text has been mastered), certain details are discussed; they are either further examples, or debatable questions on existing ideas which I thought indispensable to lay before those entering into the sphere of science, or certain historical and technical details which might be withdrawn from the fundamental portion of the book. Without intending to attain in my treatise to the completeness of a work of reference, I have still endeavoured to express the principal developments of science as they concern the chemical elements viewed in that aspect in which they appeared to me after long continued study of the subject and participation in the contemporary advance of knowledge.

tabular form by placing the elements in series, groups, and periods, two such tables are given at the end of this preface.

In this fifth edition I have not altered any essential feature of the original work, but have enlarged it in two directions. First, the doctrine of chemical equilibria, originally introduced by Berthollet and Henri Sainte-Claire Deville, is discussed more fully and minutely than in the earlier editions, as it has during recent years been established on a much firmer footing; and, second, the descriptive data referring to the elements have been increased by many new facts.

D. MENDELEEFF.

TABLE I.
Distribution of the Elements in Groups and Series

Group	I.	II.	III.	IV.	V.	VI.	VII.	VIII.
Series 1 . .	H	—	—	RH ₄	RH ₃	RH ₂	RH	Hydrogen compounds.
„ 2 . .	Li .	Be .	B .	C .	N .	O .	F .	
„ 3 . .	. Na	. Mg	. Al	. Si	. P	. S	. Cl	
„ 4 . .	K .	Ca .	Sc .	Ti .	V .	Cr .	Mn .	Fe . Co . Ni . Cu
„ 5 . .	. (Cu)	. Zn	. Ga	. Ge	. As	. Se	. Br	
„ 6 . .	Rb .	Sr .	Y .	Zr .	Nb .	Mo .	— .	Ru . Rb . Pd . Ag
„ 7 . .	. (Ag)	. Cd	. In	. Sn	. Sb	. Te	. I	
„ 8 . .	Cs .	Ba .	La .	Ce .	Di? .	— .	— .	— — — —
„ 9 . .	. —	. —	. —	. —	. —	. —	. —	
„ 10 . .	— .	— .	Yb .	— .	Ta .	W .	— .	Os . Ir . Pt . Au
„ 11 . .	. (Au)	. Hg	. Tl	. Pb	. Bi	. —	. —	
„ 12 . .	— .	— .	— .	Th .	— .	U .	— .	
	R ₂ O	R ₂ O ₂	R ₂ O ₃	R ₂ O ₄	R ₂ O ₅	R ₂ O ₆	R ₂ O ₇	Higher oxides.
	—	RO	—	RO ₂	—	RO ₃	—	RO ₄

TABLE III.
THE PERIODICITY OF THE ELEMENTS

The Elements	Their Properties in the Free State				The Composition of the Saline Oxides	The Properties of the Saline Oxides		Small Periodic Series
	<i>t</i>	<i>a</i>	<i>d</i>	$\frac{A}{n}$		$\frac{2A + n \cdot 16}{n}$	$\frac{2A + n \cdot 16}{n}$	
	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
Hydrogen	< -200°	—	< 0.002	20	H 1	1 = n	—	1
Lithium	180°	—	6.50	12	Li 7	1†	0.917	1
Potassium	(300°)	—	1.04	5.6	K 39	—	2.0	2
Boron	(1800°)	—	2.6	4.1	B 11	—	3.04	3
Carbon	> 2500°	—	< 2.0	3	C 12	—	3.4	4
Nitrogen	—208°	—	< 0.7	20	N 14	1	1.34	5
Oxygen	< -200°	—	< 1.0	16	O 16	1	1.61	6
Fluorine	—	—	—	19	F 19	—	—	—
Sodium	93°	0.71	0.98	28	Na 23	1†	—	—
Magnesium	500°	0.37	1.71	11	Mg 24	1†	—	—
Aluminium	900°	0.23	2.9	11	Al 27	—	—	—
Silicon	(1200°)	0.08	2.8	12	Si 28	—	—	—
Phosphorus	41°	1.38	2.2	14	P 31	1	—	—
Sulphur	113°	1.07	2.67	16	S 32	1	—	—
Chlorine	—75°	—	1.3	35	Cl 35.5	1	—	—
Potassium	88°	0.84	0.87	45	K 39	1†	—	—
Calcium	(800°)	—	1.8	26	Ca 40	—	—	—
Scandium	—	—	(2.1)	(18)	Sc 45	—	—	—
Titanium	(2500°)	—	(5.1)	(9.1)	Ti 48	—	—	—
Vanadium	(2000°)	—	5.6	23	V 51	—	—	—
Chromium	(2000°)	—	5.5	50	Cr 52	—	—	—
Manganese	(1400°)	—	7.5	79	Mn 55	—	—	—
Iron	(1400°)	0.12	7.8	72	Fe 56	—	—	—
Cobalt	(1400°)	0.18	8.8	59	Co 59	—	—	—
Nickel	1250°	0.17	8.7	59	Ni 59	—	—	—
Copper	1083°	0.20	8.6	73	Cu 63	1†	—	—
Zinc	435°	—	7.1	92	Zn 65	—	—	—
Galium	—	—	5.00	12	Ga 70	—	—	—
Germanium	900°	—	5.17	13	Ge 72	—	—	—
Arsenic	500°	0.00	5.7	13	As 75	—	—	—
Selenium	217°	—	4.8	16	Se 79	—	—	—
Bromine	—7°	—	9.1	23	Br 80	1	—	—
Iodine	30°	—	1.5	67	I 127	1†	—	—
Strontium	(300°)	—	2.5	35	Sr 87	—	—	—
Yttrium	—	—	(8.1)	(26)	Y 89	—	—	—
Zirconium	(1500°)	—	4.1	22	Zr 90	—	—	—
Niobium	—	—	7.1	13	Nb 94	—	—	—
Molybdenum	—	—	8.6	12	Mo 96	—	—	—
Ruthenium	(2000°)	0.10	12.2	8.1	Ru 101	—	—	—
Rhodium	(1900°)	0.09	12.1	8.9	Rh 104	—	—	—
Palladium	1500°	0.12	11.4	8.9	Pd 106	—	—	—
Silver	960°	0.11	10.5	10	Ag 108	—	—	—
Cadmium	780°	0.01	8.0	13	Cd 112	—	—	—
Indium	170°	0.16	7.4	14	In 113	—	—	—
Tin	230°	0.23	7.3	16	Sn 118	—	—	—
Antimony	423°	0.12	0.7	13	Sb 126	—	—	—
Tellurium	445°	0.17	0.4	20	Te 127	—	—	—
Iodine	114°	—	4.9	26	I 127	1	—	—
Cesium	27°	—	1.98	71	Cs 133	1†	—	—
Barium	—	—	3.76	36	Ba 137	—	—	—
Lanthanum	(900°)	—	0.1	23	La 139	—	—	—
Cerium	(700°)	—	0.1	21	Ce 140	—	—	—
Praseodymium	(800°)	—	0.5	22	Pr 141	—	—	—
Ytterbium	—	—	(6.0)	(25)	Yb 173	—	—	—
Tantalum	—	—	10.1	18	Ta 182	—	—	—
Tungsten	(1500°)	—	19.1	9.6	W 184	—	—	—
Osmium	(2400°)	0.07	22.5	8.5	Os 191	—	—	—
Iridium	2000°	0.07	22.4	8.0	Ir 193	—	—	—
Platinum	1775°	0.05	21.5	9.2	Pt 196	—	—	—
Gold	1063°	0.14	10.2	10	Au 197	—	—	—
Mercury	357°	—	13.6	15	Hg 200	—	—	—
Thallium	294°	0.51	11.8	17	Tl 203	—	—	—
Lead	327°	0.23	11.3	18	Pb 206	—	—	—
Bismuth	268°	0.14	9.8	21	Bi 208	—	—	—
Thorium	—	—	11.1	21	Th 232	—	—	—
Uranium	(800°)	—	18.7	13	U 240	—	—	—

Throughout the table the values included in brackets are estimated values.

[1] The melting points (*t*) of the elements. Platinum taken as 1775° (Vielle).

[2] The mean coefficient (*a*) of linear expansion of the solid elements from 0° to 100°, chiefly according to Fizeau's data. The figures are given in millionth parts. For example, for bismuth the mean expansion of one metre for 1° (*a*) = 0.000014.

[3] The specific gravity (*d*) of the elements in a solid or liquid state. The sp. gr. given in brackets have not yet been observed, but are probable on the basis of the periodic law.

[4] The mean atomic volumes of the elements in a solid or liquid state.

[5] Shows the composition of the molecules of the hydrogen and organo-metallic compounds. If an element gives both a hydrogen compound and an organo-metallic compound, the figure is given in thick type, and if the hydrogen compound is unknown in ordinary type. For example, a thick type 3 stands before Sb, which signifies that SbH₃, Sb(CH₃)₃, Sb(C₂H₅)₃, &c., are known. The ordinary type 4 before Pb shows that Pb(CH₃)₄, Pb(C₂H₅)₄, are known, but that a hydrogen compound of lead is not known.

[6] In this column the sign placed between some of the symbols indicates that there are unknown intermediate elements according to the periodic system, and the figure indicates the number of such unknown elements. Thus between Di and Yb there are 14 elements wanting. It is probable that certain of the rare elements which have been discovered, but are as yet insufficiently investigated, enter into these interspaces.

[7] Shows the composition of the saline oxides forming bases, acids, and salts (therefore the oxides CO and H₂O, which do not directly form salts, do not enter into this category). For convenience of comparison, the composition of all the oxides is expressed by R₂O_n, where *n* varies from 1 to 8. Thus, as the figures 1 and 3 stand against Au, it signifies that gold gives oxides Au₂O and Au₂O₃, and as 2 and 4 stands against Pb, it means that Pb₂O, or PbO, and Pb₂O₄, or PbO₂, are known. The oxides giving salts, and known in a free state, like Au₂O₃, PbO, and PbO₂, &c., are given in black type. For example, the figures 2, 4, 5, 6 stand against Sb, indicating that the oxides Sb₂O₃ and Sb₂O₅, or Sb₂O₄, are known in a free state and in black type. The oxide Sb₂O₃, which does not exist in a free state, gives the hydrate H₂SbO₄ and salts of dichloric acid; the formula Sb₂O₅ also corresponds with the thiosulphates M₂Sb₂O₅. The symbol † affixed to a number shows that the oxide is markedly basic, and the sign * that it is markedly acidic.

[8] The specific gravity (*d'*) of the higher saline oxides in a solid state. For example, the figure standing against W corresponds to W₂O₇, or WO₃.

[9] The molecular volume of the higher saline oxides, taking (for the sake of comparison) their formulae as R₂O_n. These figures are obtained by dividing the weights 2A + n · 16 (this is the weight corresponding with the formula R₂O_n) by the specific gravity given in the preceding column.

[10] The volumes of an equivalent of oxygen in the higher oxides. The magnitude of this volume (V) is found by subtracting twice the volume of the element (column 4) from the volume (column 9) of the higher oxide R₂O_n, and dividing this difference by the number (*n*) of atoms of oxygen in the higher oxide (column 7). Negative values show that the volume of the oxide is less than the volume of the element contained in it.

[11] The numbers of the small periods, or series, given in order to indicate the even and the uneven series.

Distribution of the Elements in Periods

Groups	Higher Salt-forming Oxides	Typical or 1st small Period	Large Periods				
			1st	2nd	3rd	4th	5th
I.	R ₂ O	Li = 7	K 39	Rb 85	Cs 133	—	—
II.	RO	Be = 9	Ca 40	S 87	Ba 137	—	—
III.	R ₂ O ₃	B = 11	Sc 44	Y 89	La 138	Yb 173	—
IV.	RO ₂	C = 12	Ti 48	Zr 90	Ce 140	—	Th 232
V.	R ₂ O ₅	N = 14	V 51	Nb 94	—	Ta 182	—
VI.	RO ₃	O = 16	Cr 52	Mo 96	—	W 184	Ur 240
VII.	R ₂ O ₇	F = 19	Mn 55	—	—	—	—
VIII.	{		Fe 56	Ru 103	—	Os 191	—
			Co 58·5	Rh 104	—	Ir 193	—
			Ni 59	Pd 106	—	Pt 196	—
I.	R ₂ O	H = 1. Na = 23	Cu 63	Ag 108	—	Au 198	—
II.	RO	Mg = 24	Zn 65	Cd 112	—	Hg 200	—
III.	R ₂ O ₃	Al = 27	Ga 70	In 113	—	Tl 204	—
IV.	RO ₂	Si = 28	Ge 72	Sn 118	—	Pb 206	—
V.	R ₂ O ₅	P = 31	As 75	Sb 120	—	Bi 208	—
VI.	RO ₃	S = 32	Se 79	Te 125	—	—	—
VII.	R ₂ O ₇	Cl = 35·5	Br 80	I 127	—	—	—
		2nd small Period	1st	2nd	3rd	4th	5th

CONTENTS

	PAGE
TRANSLATORS' PREFACE	v
AUTHOR'S PREFACE TO THE FIFTH EDITION	vii
TABLE OF THE DISTRIBUTION OF THE ELEMENTS IN GROUPS AND SERIES	xii
TABLE OF THE ATOMIC WEIGHTS OF THE ELEMENTS. DISTRIBUTION OF THE ELEMENTS IN PERIODS	xiii
INTRODUCTION	1
CHAPTER	
I. ON WATER AND ITS COMPOUNDS	40
II. THE COMPOSITION OF WATER. HYDROGEN	112
III. OXYGEN AND THE CHIEF ASPECTS OF ITS SALINE COMBINATIONS .	151
IV. OZONE AND HYDROGEN PEROXIDE. DALTON'S LAW	197
V. NITROGEN AND AIR	221
VI. THE COMPOUNDS OF NITROGEN WITH HYDROGEN AND OXYGEN .	243
VII. MOLECULES AND ATOMS. THE LAWS OF GAY-LUSSAC AND AVOGADRO-GERHARDT	292
VIII. CARBON AND THE HYDROCARBONS	326
IX. COMPOUNDS OF CARBON WITH OXYGEN AND NITROGEN	367

CHAPTER	PAGE
X. SODIUM CHLORIDE. BERTHOLLET'S LAWS. HYDROCHLORIC ACID .	406
XI. THE HALOGENS: CHLORINE, BROMINE, IODINE, AND FLUORINE .	453
XII. SODIUM	505
XIII. POTASSIUM, RUBIDIUM, CÆSIUM, AND LITHIUM. SPECTRUM ANALYSIS.	535
XIV. THE VALENCY AND SPECIFIC HEAT OF THE METALS. MAGNESIUM, CALCIUM, STRONTIUM, BARIUM, AND BERYLLIUM	572

Erratum.

Page 91, line 4 from foot, *for* Prinsep *read* Pierson.

540

115: p

± 15

v. 2

	PAGE
TABLE OF THE PERIODICITY OF THE ELEMENTS	i
CHAPTER	
XV. THE GROUPING OF THE ELEMENTS AND THE PERIODIC LAW	1
XVI. ZINC, CADMIUM, AND MERCURY	86
XVII. BORON, ALUMINIUM, AND THE ANALOGOUS METALS OF THE THIRD GROUP	57
XVIII. SILICON AND THE OTHER ELEMENTS OF THE FOURTH GROUP	93
XIX. PHOSPHORUS AND THE OTHER ELEMENTS OF THE FIFTH GROUP	144
XX. SULPHUR, SELENIUM, AND TELLURIUM	193
XXI. CHROMIUM, MOLYBDENUM, TUNGSTEN, URANIUM, AND MANGANESE	265
XXII. IRON, COBALT, AND NICKEL	302
XXIII. THE PLATINUM METALS	346
XXIV. COPPER, SILVER, AND GOLD	371
APPENDIX	
I. AN ATTEMPT TO APPLY TO CHEMISTRY ONE OF THE PRINCIPLES OF NEWTON'S NATURAL PHILOSOPHY	417
II. THE PERIODIC LAW OF THE CHEMICAL ELEMENTS (THE FARADAY LECTURE)	435

APPENDIX

	PAGE
III. NOTE ON THE DISCOVERY OF HYDRO-NITROUS ACID, N_3H	455
INDEX OF AUTHORITIES	463
SUBJECT INDEX	471
TABLE OF THE ATOMIC WEIGHTS OF THE ELEMENTS. DISTRIBUTION OF THE ELEMENTS IN PERIODS	487

Errata.

Page 17 line 26 from top *et seq.*, for Nillson read Nilson.

„ 34 „ 26 „ foot, for Nillson read Nilson.

„ 141 „ 14 „ top, for Picini read Piccini.

„ 414 „ 13 „ foot, for Giles' read Gelis.

PRINCIPLES OF CHEMISTRY



INTRODUCTION

CHEMISTRY is concerned with the study ¹ of the homogeneous substances

¹ The investigation of a substance or phenomenon of nature consists (*a*) in determining the relation of the thing under investigation to that which is already known, either from former studies, or from experiment, or from the consciousness of the common surroundings of life—that is, in determining and expressing the quality of the unknown by the aid of that which is known; (*b*) in measuring all that which can be subjected to measurement, and thereby denoting the quantitative relation of that under investigation to that already known and its relation to the categories of time, space, temperature, mass, &c.; (*c*) in determining the position held by the thing under investigation in the system of the things known, guided by both qualitative and quantitative data; (*d*) in finding, from the quantities which have been measured, the empirical (visible) dependence (function, or ‘law,’ as it is sometimes termed) of variable factors—for instance, the dependence of the composition of the substance on its properties, of temperature on time, of time on locality, &c.; (*e*) in framing hypotheses or propositions as to the actual cause and true nature of the relation between that studied (measured or observed) and that which is known or the categories of time, space, &c.; (*f*) in verifying the logical consequences of the hypotheses by experiment; and (*g*) in advancing a theory which shall account for the nature of the properties of that studied in its relations with things already known and with those conditions or categories among which it exists. It is certain that it is only possible to thus study, when we have taken as a basis some incontestable fact which is self-evident to our understanding; as, for instance, number, time, space, movement, or mass. The determination of such primary or fundamental conceptions (categories), although not excluded from the possibility of investigation, frequently does not subject itself to our present mode of scientific generalisation. Hence it follows in the investigation of anything, there always remains something which is recognised without investigation, or admitted as a known factor. The axioms of geometry may be taken as an example. Thus in the science of biology it is necessary to admit the faculty of organisms for multiplying themselves, as a conception whose meaning is yet unknown. Thus in the study of chemistry the notion of elements must be recognised without hardly any further analysis. However, by first investigating that which is visible and subject to direct observation by the organs of the senses, we may hope that, first, hypotheses will be arrived at, and afterwards theories of that which has now to be placed at the basis of our investigations. The minds of the ancients strove to at once seize the very fundamental categories of investigation, whilst all the successes of recent knowledge are based on the above-cited method of investigation without the determination of ‘the beginning of all beginnings.’ By following this inductive method, the *exact sciences*

or material² of which all the objects of the universe are made up, with the transformations of these substances into each other, and with the phenomena³ which accompany such transformations. Every chemical

have already succeeded in becoming acquainted with certainty with much of the invisible world, which directly is imperceptible to the organs of sense (for example, the molecular movement of all bodies, the composition of the heavenly luminaries, the paths of their movement, the necessity for the existence of substances which cannot be subjected to experiment, &c.), and have verified the knowledge thus obtained, and employed it for increasing the interests of human life; and therefore it may be safely said that *the inductive method of investigation* is a more perfect mode of acquiring knowledge than the deductive method alone (starting from a little of the unknown accepted as incontestable to arrive at the much which is visible and observable) by which the ancients strove to embrace the universe. By investigating the universe by an inductive method (endeavouring from the much which is observable to arrive at a little which may be verified and is indubitable) the new science refuses to recognise dogma as truth, but through *reason*, by a slow and laborious method of investigation, strives for and attains to true deductions.

² A substance or material is that which occupies space and has weight. That is, which presents a mass which is attracted by the earth and by other masses of material, and of which the *objects* of nature are composed, and through which the movements and *phenomena* of nature are accomplished. It is easy to find out by examining and investigating, by various methods, the objects met with in nature and in the arts, that some of them are homogeneous, whilst others are composed of a mixture of several homogeneous substances. This is most clearly seen in solid substances. The metals used in the arts (for example, gold, iron, copper) should be distinguished for their homogeneity, otherwise they are brittle and unfit for many uses. Homogeneous matter exhibits similar properties in all its parts. By breaking up a homogeneous substance we obtain parts which, although different in form, resemble each other in their properties. Glass, the best qualities of sugar, marble, &c., are examples of homogeneous substances. But examples of non-homogeneous substances are much more frequent in nature and the arts. Thus the majority of the rocks are not homogeneous. In porphyries bright pieces of a mineral called 'orthoclase' are often seen strewn amongst the dark mass of the rock. In ordinary red granite it is easy to distinguish large pieces of orthoclase mixed with dark semi-transparent quartz and flexible laminae of mica. Nor are plants and animals homogeneous. Thus leaves are composed of a skin, fibre, pulp, sap, and a green colouring matter. This is clearly seen by examining under a microscope a thin slice cut off a leaf. As an example of those non-homogeneous substances which are produced artificially, gunpowder may be cited, which is prepared by mixing together known proportions of sulphur, nitre, and charcoal. Many liquids, also, are not homogeneous, as may be observed by the aid of the microscope, when drops of blood are seen to consist of a colourless liquid in which red corpuscles, invisible to the naked eye owing to their small size, are floating about. It is these corpuscles which give blood its peculiar colour. Milk is also a transparent liquid, in which microscopical drops of fat are floating, and which rise to the top when milk is left at rest, forming cream. When the fat is beaten up (churned) the separate drops collect into one mass. It is possible to extract from every non-homogeneous substance those homogeneous substances of which it is made up. Thus orthoclase may be separated from porphyry by breaking it off. So also gold is extracted from gold-bearing sand by washing away the mixture of clay and sand. Chemistry deals only with the homogeneous substances met with in nature, or extracted from natural or artificial non-homogeneous substance. The various mixtures found in nature form the subjects of other natural sciences—as geognosy, botany, zoology, anatomy, &c.

³ All those events which are accomplished by substances in time, are termed 'phenomena.' Phenomena in themselves form the fundamental subject of the study of physics. Movement is the primary and most generally understood form of phenomenon, and therefore we endeavour to reason about other phenomena as clearly as when dealing with move-

change or reaction,⁴ as it is called, can only take place under a condition of most intimate and close contact of the reacting substances,⁵ and is determined by the forces proper to the smallest invisible particles (molecules) of matter. We must distinguish three chief classes of chemical transformations.

1. *Combination* is a reaction in which the union of two substances yields a new one, or in general terms, from a given number of substances a lesser number is produced. Thus, by heating a mixture of iron and sulphur⁶ a single new substance is produced, iron sulphide, in which the constituent substances cannot be distinguished even by the highest magnifying power. Before the reaction, the iron could be separated from the mixture by a magnet, and the sulphur by dissolving it in certain oily liquids;⁷ in general, before combination they might be mechanically separated from each other, but after combination both substances penetrate into each other, and are then neither mechanically separable nor individually distinguishable. As a rule, reactions of direct combination are accompanied by an evolution of heat, and the common case of combustion, evolving heat, consists in the combination of combustible substances with a portion (oxygen) of the atmosphere,

ment. Therefore, mechanics, which treats of movement, forms the fundamental science of natural philosophy, and all other sciences endeavour to reduce the phenomena with which they are concerned to mechanical principles. Astronomy was the first to take to this path of reasoning, and succeeded in many cases in reducing astronomical to purely mechanical phenomena. Chemistry and physics, physiology and biology are proceeding in the same direction.

⁴ The verb 'to react' means to act or change chemically.

⁵ If a phenomenon proceeds at visible or measurable distances (as, for instance, magnetic attraction or gravity) it cannot be ascribed to chemical phenomena, which are only accomplished at distances immeasurably small and undistinguishable to the eye or the microscope; that is to say, which belong to the number of purely molecular phenomena. When a change of material is accomplished within a substance without visible motion or the interference of foreign matters (for instance, when new wine 'ages' by keeping, and acquires a peculiar aroma), it may be classed as a chemical phenomenon; but the ordinary cases of chemical reaction are accomplished by the mutual action of different substances which, previously free, on reaction mutually permeate each other.

⁶ For this purpose a piece of iron may be made red hot in a smith's furnace, and then placed in contact with a lump of sulphur, when iron sulphide will be obtained as a molten liquid, the combination being accompanied by a visible increase in the glow of the iron. Or else iron filings are mixed with powdered sulphur in the proportion of 5 parts of iron to 3 parts of sulphur, and the mixture placed in a glass tube, which is then partially heated. Combination does not commence without the aid of external heat, but when once started in any portion of the mixture it extends throughout the entire mass, because the portion first heated evolves sufficient heat in forming iron sulphide to raise the adjacent parts of the mixture to the temperature required for starting the reaction. The rise in temperature thus obtained is so high as to soften the glass tube.

⁷ Sulphur is slightly soluble in many thin oils; it is very soluble in carbon bisulphide and in some other liquids. Iron is insoluble in carbon bisulphide, and therefore the sulphur can be dissolved away from the iron.

the gases and vapours contained in the smoke being the products of combination.

2. Reactions of *decomposition* are cases the reverse to those of combination, that is, in which one substance gives two or, in general, a given number of substances a greater number. Thus, by heating wood (and also coal and many animal or vegetable substances) without access to air, a combustible gas, a watery liquid, tar, and carbon are obtained. It is in this way that tar, lighting gas, and charcoal are prepared on a large scale.⁸ All limestones, for example, flagstones, chalk, or marble, are decomposed by heating to redness into lime and a peculiar gas called carbonic anhydride. A similar decomposition, taking place, however, at a much lower temperature, proceeds with the green copper carbonate which enters into the composition of malachite. This example will be studied more in detail presently. Whilst heat is evolved in the ordinary reactions of combination, it is, on the contrary, consumed in the reactions of decomposition.

3. The third class of chemical reactions—where the number of acting substances is equal to the number of substances formed—consists, as it were, of an association of decomposition and combination. If, for instance, two compounds A and B are taken and they react on each other to form the substances C and D, then supposing that A is decomposed into D and E, and that E combines with B to form C, we have a reaction in which two substances A, or D E, and B were taken and two others C, or E B, and D were produced. Such reactions ought to be placed under the general term of reactions of '*rearrangement*,' and the particular case where two substances give two fresh ones, reactions of '*substitution*.'⁹ Thus, if a piece of iron be immersed in a solution of blue vitriol (copper sulphate), copper is formed—or, rather,

⁸ Decomposition of this kind is termed 'dry distillation' because, as in distillation, the substance is heated and vapours are given off which, on cooling, condense into liquids. In general, decomposition, in absorbing heat, presents much in common to a physical change of state—such as, for example, that of a liquid into a gas. Deville likened complete decomposition to boiling, and compared partial decomposition, when a portion of a substance is not decomposed in the presence of its products of decomposition (or dissociation), to evaporation.

⁹ A reaction of rearrangement may in certain cases take place with one substance only; that is to say, a substance may by itself change into a new isomeric form. Thus, for example, if hard yellow sulphur be heated to a temperature of 250° and then poured into cold water it gives, on cooling, a soft, brown variety. Ordinary phosphorus, which is transparent, poisonous, and phosphorescent in the dark (in air), gives, after being heated at 270° (in an atmosphere incapable of supporting combustion, such as steam), an opaque, red, and non-poisonous isomeric variety, which is not phosphorescent. Cases of isomerism point out the possibility of an internal rearrangement in a substance, and are the result of an alteration in the grouping of the same elements, just as a certain number of balls may be grouped in figures and forms of different shapes and of various properties.

separated out, and green vitriol (iron sulphate, which only differs from the blue vitriol in that the iron has replaced the copper) is obtained in solution. In this manner iron may be coated with copper, so also copper with silver ; such reactions are frequently made use of in practice.

The majority of the chemical changes accomplished in nature and the arts are very complicated, as they consist of an association of many separate and simultaneous combinations, decompositions, and replacements. In this natural complexity of chemical phenomena is discovered the chief reason why for so many centuries chemistry did not exist as an exact science ; that is to say, that although many chemical changes were known and made use of,¹⁰ yet their real nature was unknown, nor could they be foreseen or directed at will. Another reason for the tardy progress of chemical knowledge is the participation of gaseous substances, especially air, in many reactions. The true comprehension of air as a ponderable substance, and of gases in general as peculiar elastic and dispersive states of matter, was only arrived at in the sixteenth and seventeenth centuries, and it was only after this that the transformations of substances could form a science. Up to that time, without understanding the invisible and yet ponderable gaseous and vaporous states of substances, it was impossible to form any fundamental chemical evidence, because gases escaped from notice between the acting and resultant substances. It is easy from the impression conveyed to us by the phenomena we observe to form the opinion that matter is created and destroyed : a whole mass of trees burn, and there only remains a little charcoal and ash, whilst from one small seed there grows little by little a majestic tree. In one case matter seems to be destroyed, and in the other to be created. This conclusion is arrived at because the formation or consumption of gases, being under the circumstances invisible to the eye, is not noted. When wood burns it undergoes a chemical change into gaseous products, which escape as smoke. A very simple experiment will prove this. By collecting the smoke it may be observed that it contains gases which differ entirely from air, being incapable of supporting combustion or respiration. These gases may be weighed, and it will then be seen that their weight exceeds that of the wood taken. This increase in weight arises from the fact that, in burning, the component parts of the wood combine with a portion of the air ; in like manner iron increases in weight by rusting. In burning gunpowder its substance is not destroyed, but only converted into gases and smoke. So also in the growth of a tree ; the seed does not

¹⁰ Thus the ancients knew how to convert the juice of grapes containing the saccharine principle (glucose) into wine or vinegar, or how to extract metals from the ores which are found in the earth's crust, and how to prepare glass from earthy substances.

increase in mass of itself and from itself, but it grows because it absorbs gases from the atmosphere and sucks water and substances dissolved therein from the earth through its roots. The sap and solid substances which give plants their form are produced from these absorbed gases and liquids by complicated chemical processes. The gases and liquids are converted into solid substances by the plants themselves. Plants not only do not increase in size, but die, in a gas which does not contain the constituents of air. When moist substances dry they decrease in weight; when water evaporates we know that it does not disappear, but will return from the atmosphere as rain, dew, and snow. When water is absorbed by the earth, it does not disappear there for ever, but accumulates somewhere underground, from whence it afterwards flows forth as a spring. Thus matter does not disappear and is not created, but only undergoes various physical and chemical transformations—that is to say, changes its locality and form. Matter remains on the earth in the same quantity as before; in a word it is, as far as we are concerned, everlasting. It was difficult to submit this simple and primary truth of chemistry to investigation, but when once made clear it rapidly spread, and now seems as natural and simple as many truths which have been acknowledged for ages. Mariotte and other savants of the seventeenth century already suspected the existence of the law of the indestructibility of matter, but they made no efforts to express it or to apply it to the ends of science. The experiments by means of which this simple law was arrived at were made during the latter half of the last century by the founder of contemporary chemistry, LAVOISIER, the French Academician and mayor. The numerous experiments of this savant were conducted with the aid of the balance, which is the only means of directly and accurately determining the quantity of matter.

Lavoisier found, by weighing all the substances, and even the apparatus, used in every experiment, and then weighing the substances obtained after the chemical change, that the sum of the weights of the substances formed was always equal to the sum of the weights of the substances taken; or, in other words: MATTER IS NOT CREATED AND DOES NOT DISAPPEAR, or that, *matter is everlasting*. This expression naturally includes a hypothesis, but our only aim in using it is to concisely express the following lengthy period—That in all experiments, and in all the investigated phenomena of nature, it has never been observed that the weight of the substances formed was less or greater (as far as accuracy of weighing permits) than the weight of the substances originally taken, and as weight is proportional to mass¹¹ or

¹¹ The idea of the mass of matter was first shaped into an exact form by Galileo (died 1642), and more especially by Newton (born 1643, died 1727), in the glorious epoch of the

quantity of matter, it follows that no one has ever succeeded in observing a disappearance of matter or its appearance in fresh quantities. The law of the indestructibility of matter endows all chemical investigations with exactitude, as, on its basis, an equation may be formed for every chemical reaction. If in any reaction the weights of the substances taken be designated by the letters A, B, C, &c., and the weights of the substances formed by the letters M, N, O, &c., then

$$A + B + C + \dots = M + N + O + \dots$$

Therefore, should the weight of one of the acting or resultant substances be unknown, it may be determined by solving the equation. The chemist, in applying the law of the indestructibility of matter, must never lose sight of any one of the acting or resultant substances. Should such an oversight be made, it will at once be remarked from the sum of the weights of the substances taken being unequal to the sum of the weights of the substances formed. All the progress made by chemistry during the end of the last, and in the present, century is entirely and immovably founded on the law of the indestructibility of matter. It is absolutely necessary in beginning the study of chemistry to become familiar with the simple truth which is expressed by this law, and for this purpose several examples elucidating its application will now be cited.

1. It is well known that iron rusts in damp air,¹² and that when heated to redness in air it becomes coated with scoria (oxide), having, like rust, the appearance of an earthy substance resembling some of the iron ores from which metallic iron is extracted. If the iron is weighed before and after the formation of the scoria or rust, it will be found that the metal has increased in weight during the operation.¹³ It

development of the principles of inductive reasoning enunciated by Bacon and Descartes in their philosophical treatises. Shortly after the death of Newton, Lavoisier, whose fame in natural philosophy should rank with that of Galileo and Newton, was born on August 26, 1743. The death of Lavoisier occurred during the Reign of Terror of the French Revolution, when he, together with twenty-six other chief farmers of the revenue, was guillotined on May 8, 1794, at Paris, but his works and thoughts have made him immortal.

¹² By covering iron with an enamel, or varnish, or with unrustable metals (such as nickel), or a coating of paraffin, or other similar substances, it is protected from the air and moisture, and so kept from rusting.

¹³ Such an experiment may easily be made by taking the finest (unruined) iron filings (ordinary filings must be first washed in ether, dried, and passed through a very fine sieve). The filings thus obtained are capable of burning directly in air (by oxidising or forming rust), especially when they hang (are attracted) on a magnet. A compact piece of iron does not burn in air, but spongy iron glows and smoulders like tinder. In making the experiment, a horse-shoe magnet is fixed, with the poles downwards, on one arm of a rather sensitive balance, and the iron filings are applied to the magnet (on a

can easily be proved that this increase in weight and formation of earthy substances from the metal is accomplished at the expense of the atmosphere, and mainly, as Lavoisier proved, at the expense of that portion which is called oxygen, and, as will afterwards be explained, supports combustion. In fact, in a vacuum, or in gases which do not contain oxygen, for instance, in hydrogen or nitrogen, the iron neither rusts nor becomes coated with scoria. Had the iron not been weighed, the participation of the oxygen of the atmosphere in its transformation into an earthy substance might have easily passed unnoticed, as was formerly the case, when phenomena like the above were, for this reason, misunderstood. It is evident from the law of the indestructibility of matter that as the iron increases in weight in its conversion into rust, the latter must be a more complex substance than the iron itself, and its formation is due to a reaction of combination. Were not this chemical change studied in regard to mass, and did we not know of the ponderability of air, and of its capacity to take part in the phenomena of combustion, we might form an entirely wrong opinion about it, and might, for instance, consider rust to be a simpler substance than iron; and explain the formation of rust as the removal of something from the iron. Such, indeed, was the general opinion prior to Lavoisier, when it was held that iron contained a certain unknown substance called 'phlogiston,' and that rust was iron deprived of this supposed substance.

2. Copper carbonate (in the form of a powder, or as the well-known green mineral called 'malachite,' which is used for making ornaments, or as an ore for the extraction of copper) changes into a black substance called 'copper oxide' when heated to redness.¹⁴ This black

sheet of paper) so as to form a beard about the poles. The balance pan should be exactly under the filings on the magnet, in order that any which might fall from it should not alter the weight. The filings, having been weighed, are set light to by applying the flame of a candle; they easily take fire, and go on burning by themselves, forming rust. When the combustion is ended, it will be clear that the iron has increased in weight; from $5\frac{1}{2}$ parts by weight of iron filings taken, there are obtained, by complete combustion, $7\frac{1}{2}$ parts by weight of rust. Consequently, if about 5 grams of filings be applied to the magnet, the increase in weight will be clearly seen by the weights that are required to restore equilibrium. This experiment proceeds so easily and quickly that it may be conveniently demonstrated, as a proof of the increase of weight at the expense of air and of its transformation into the solid iron-rust.

¹⁴ For the purpose of experiment, it is most convenient to take copper carbonate, prepared by the experimenter himself, by adding a solution of sodium carbonate to a solution of copper sulphate. The precipitate (deposit) so formed is collected on a filter, washed, and dried. The decomposition of copper carbonate into copper oxide is effected by so moderate a heat that it may be accomplished in a glass vessel heated by a lamp. For this purpose a thin glass tube, closed at one end, and called a 'test tube,' may be employed, or else a vessel called a 'retort.' The experiment is carried on, as described in the third example above, by collecting the carbonic anhydride over a water bath, as will be afterwards explained.

substance is also obtained by heating copper to redness in air—that is, it is the scoria or oxidation product of copper. The weight of the black oxide of copper left is less than that of the copper carbonate originally taken, and therefore we consider the reaction which occurred to have been one of decomposition, and that by it something was separated from the green copper carbonate, and in fact by closing the orifice of the vessel in which the copper carbonate is heated with a well-fitting cork, through which a gas delivery tube¹⁵ passes whose end is immersed under water, it will be observed that on heating, a gas is formed which bubbles through the water. This gas can be easily collected, as will presently be described, and it will be found to essentially differ from air in many respects; for instance, a burning taper is extinguished in it as if it had been plunged into water. If weighing had not proved to us that some substance had been separated, the formation of the gas might easily have escaped our notice, for it is colourless and transparent like air, and is therefore evolved without any striking feature. The carbonic acid gas evolved may be weighed¹⁶ and it will be seen that the sum of the weights of the black copper

¹⁵ Gas delivery tubes are usually made of glass tubing as prepared at glass works. It is made of various diameters and thicknesses. If of small diameter and thickness, a glass tube is easily bent by heating in a gas jet or the flame of a spirit lamp, and may also be easily divided at a given point by making a deep scratch with a file and then breaking the tube at this point with a sharp jerk. These properties, together with their impermeability, transparency, hardness, and regularity of bore, makes glass tubes most useful in experiments with gases. Naturally they might be replaced by straws, india-rubber, metallic, or other tubes, but these are more difficult to fix on to a vessel, and are not entirely impervious to gases. A glass gas delivery tube may be hermetically fixed into a vessel by fitting it into a perforated cork, which should be soft and free from flaws, and fixing the cork into the orifice of the vessel. Sometimes the cork is previously soaked in paraffin, or it is replaced by an india-rubber cork.

¹⁶ Gases, like all other substances, may be weighed, but, owing to their extreme lightness and the difficulty of dealing with them in large masses, they can only be weighed by very sensitive balances; that is, in such as, with a considerable load, indicate a very small difference in weight—for example, a centigram or milligram with a load of 1,000 grams. In order to weigh a gas, a glass globe furnished with a stop-cock (which must not leak in any part, and therefore must be kept well lubricated) is first of all exhausted of air by an air-pump (a Sprengel pump is the best). The stop-cock is then closed, and the exhausted globe weighed. As the pressure of the atmosphere acts on the walls of the globes, they should be thick. Glass is found to bear the strain of the inequality of the exterior and interior pressures best. If the gas to be weighed is then let into the globe, its weight can be determined from the increase in the weight of the globe. It is necessary, however, that the temperature and pressure of the air about the balance should remain constant for both weighings, as the weight of the globe in air will (according to the laws of hydrostatics) vary with its density. The volume of the air displaced, and its weight, must therefore be determined by observing the temperature, density, and moisture of the atmosphere during the time of experiment. This will be partly explained later, but may be studied more in detail by physics. Owing to the complexity of all these operations, the mass of a gas is usually determined from its volume and density, or the weight of one volume.

oxide and carbonic acid gas is equal to the weight of the copper carbonate¹⁷ originally taken, and thus by carefully following out the various stages of all chemical reactions we arrive at a confirmation of the law of the indestructibility of matter.

3. Red mercury oxide (which is formed as mercury scoria by heating mercury in air) is decomposed like copper carbonate (only by heating more slowly and at a somewhat higher temperature), with the formation of the peculiar gas, oxygen. For this purpose the mercury oxide is placed in a glass tube or retort,¹⁸ to which, by means of a cork, a gas delivery tube is attached. This tube is bent downwards, as shown




FIG. 1.—Apparatus for the decomposition of red mercury oxide.

in the drawing (Fig. 1). The open end of the gas delivery tube is immersed in a vessel filled with water, called a pneumatic trough.¹⁹ When

¹⁷ The copper carbonate should be dried before weighing, as otherwise—besides copper oxide, and carbonic anhydride—water will be obtained in the decomposition. Water forms a part of the composition of malachite, and has therefore to be taken into consideration. The water produced in the decomposition may be all collected by absorbing it in sulphuric acid or calcium chloride, as will be described further on. In order to dry a salt it must be heated at about 100° until its weight remains constant, or be placed under an air pump over sulphuric acid, as will also be presently described. As water is met with almost everywhere, and as it is absorbed by many substances, the possibility of its presence should never be lost sight of.

¹⁸ As the decomposition of red oxide of mercury requires so high a temperature, near redness, as to soften ordinary glass, it is necessary for the experiment to take a retort (or test tube) made of infusible (German) glass, which is able to stand high temperatures without softening. For the same reason, the lamp used must give a strong heat and a large flame, capable of embracing the whole bottom of the retort, which should be as small as possible for the convenience of the experiment.

¹⁹ The pneumatic trough may naturally be made of any material (china, earthenware, or metal, &c.), but usually a glass one, as shown in the drawing, is used, as it allows the progress of experiment being better observed. For this reason, as well as the ease with which they are kept clean, and from the fact also that glass is not acted on by many sub-

the gas begins to be evolved in the retort it is obliged, having no other outlet, to escape through the gas delivery tube into the water in the pneumatic trough, and therefore its evolution will be rendered visible by the bubbles coming from this tube. In heating the retort containing the mercury oxide, the air contained in the apparatus is first partly expelled, owing to its expansion by heat, and then the peculiar gas called 'oxygen' is evolved, and may be easily collected as it comes off. For this purpose a vessel (an ordinary cylinder, as in the drawing) is filled quite full with water and its mouth closed; it is then inverted and placed in this position under the water in the trough; the mouth is then opened. The cylinder will remain full of water—that is, the water will remain at a higher level in it than in the sur-

stances which affect other materials (for instance, metals), glass vessels of all kinds—such as retorts, test tubes, cylinders, beakers, flasks, globes, &c.—are preferred to any other for chemical experiments. Glass vessels may be heated without any danger if the following precautions be observed: 1st, they should be made of thin glass, as otherwise they are liable to crack from the bad heat-conducting power of glass; 2nd, they should be surrounded by a liquid or with sand (Fig. 2), or sand bath as it is called; or else should




FIG. 2.—Apparatus for distilling under a diminished pressure liquids which decompose at their boiling points under the ordinary pressure. The apparatus in which the liquid is distilled is connected with a large globe from which the air is pumped out; the liquid is heated, and the receiver cooled.

stand in a current of hot gases without touching the fuel from which they proceed, or in the flame of a smokeless lamp. A common candle or lamp forms a deposit of soot on a cold object placed in their flames. The soot interferes with the transmission of heat, and so a glass vessel when covered with soot often cracks. And for this reason spirit lamps, which burn with a smokeless flame, or gas burners of a peculiar construction, are used. In the Bunsen burner the gas is mixed with air, and burns with a non-luminous and smokeless flame. On the other hand, if an ordinary lamp (petroleum or benzine) does not smoke it may be used for heating a glass vessel without danger, provided the glass is placed well above the flame in the current of hot gases. In all cases, the heating should be begun very carefully by raising the temperature by degrees, and not all at once, or the glass will break.

rounding vessel, owing to the atmospheric pressure. The atmosphere presses on the surface of the water in the trough, and prevents the water from flowing out of the cylinder. The mouth of the cylinder is placed over the end of the gas delivery tube,²⁰ and the bubbles issuing from it will rise into the cylinder and displace the water contained in it. Gases are generally collected in this manner. When a sufficient quantity of gas has accumulated in the cylinder it can be clearly shown that it is not air, but another gas which is distinguished by its capacity for vigorously supporting combustion. In order to show this, the cylinder is closed, under water, and removed from the bath; its mouth is then turned upwards, and a smouldering taper plunged into it. As is well known, a smouldering taper will be extinguished in air, but in the gas which is given off from red mercury oxide it burns clearly and vigorously, showing the capacity this gas has for vigorously supporting combustion, and thus enabling it to be distinguished from air. It may be observed in this experiment that, besides the formation of oxygen, metallic mercury is formed, and, being volatilised at the high temperature required for the reaction, condenses on the cooler parts of the retort as a mirror or in globules. Thus two substances, mercury and oxygen, are obtained by heating red mercury oxide. In this reaction, from one substance two are produced—that is, decomposition ensues. The means of collecting and investigating gases were already known before Lavoisier's time, but he first showed the real part they played in the processes of many chemical changes which before his era were either wrongly understood (as will be afterwards explained) or were not explained at all, but only observed in their superficial aspects. This experiment on red mercury oxide has a special significance in the history of chemistry contemporary with Lavoisier, because the oxygen gas which is here evolved is contained in the atmosphere, and plays a most important part in nature, especially in the respiration of animals, in combustion in air, and in the formation of rusts or scorïæ (earths, as they were then called) from metals—that is, of earthy substances, like the ores from which metals are extracted. The law of the indestructibility of matter could not be discovered or confirmed by the balance until the part played by the atmosphere as regards the participation of its oxygen in the numerous chemical phenomena, known either from the everyday experiences of life (combustion, respiration) or from the researches of

²⁰ In order to avoid the necessity of holding the cylinder, its open end is widened (and also ground so that it may be closely covered with a ground-glass plate when needful), and placed on a stand below the level of the water in the bath. This stand is called 'the bridge.' It has several circular openings cut through it, and the gas delivery tube is placed under one of these, and the cylinder for collecting the gas over it.

previous observers (the transformations of the metals into their earths or oxides), had been explained.

4. In order to illustrate by experiment one more example of chemical change and the application of the law of the indestructibility of matter, we will take some common table salt and lunar caustic, which is well known from its use in cauterising wounds. By taking a clear solution of each and mixing them together, it will at once be remarked that a solid white substance is formed, which settles to the bottom of the vessel, and is insoluble in water. This substance may be separated from the solution by filtering; it is then found to be an entirely different substance from either of those taken originally in the solutions. This is evident from the fact that it does not dissolve in water. On evaporating the liquid which passed through the filter, it will be found to contain a new substance unlike either table salt or lunar caustic, but, like them, soluble in water. Thus table salt and lunar caustic, two substances soluble in water, being taken, by their mutual chemical action produced two new substances, one insoluble in water, and the other remaining in solution. Here, from two substances two others are obtained, consequently there occurred a reaction of substitution. The water served only to convert the acting substances into a liquid and mobile state. If the lunar caustic and salt be dried²¹ and weighed, and if about $58\frac{1}{2}$ parts by weight—for instance, grams²²—of salt and 170 grams of lunar caustic be taken, then $143\frac{1}{2}$ grams of insoluble silver chloride and 85 grams of sodium nitrate will be obtained. The sum of the weights of the acting and resultant substances are seen to be similar and equal to $228\frac{1}{2}$ grams, as necessarily follows from the law of the indestructibility of matter.

²¹ Drying is necessary in order to remove any water which may be held in the salts (see Note 17). If the original and resultant substances be dried, then the water employed for solution, and which is removed in drying, may be taken in indefinite quantities.

²² The exact weights of the acting and resulting substances are determined with the greatest difficulty, not only from the possible inexactitude of the balance (every weighing is only correct within the limits of the sensitiveness of the balance) and weights used in weighing, not only from the difficulty in making corrections for the weight of air displaced by the vessels holding the substances weighed and by the weights themselves, but also from the hygroscopic nature of many substances (and vessels) causing absorption of moisture from the atmosphere, and from the difficulty in not losing any of the substance to be weighed in the many operations (filtering, evaporating, and drying, &c.) which have to be gone through before arriving at a final result. All these circumstances have to be taken into consideration in exact researches, and their elimination requires very many special precautions which are impracticable in preliminary experiments; these arrive within only a certain comparatively rough proximity to those weights (expressed by chemical formulæ) which (all with a certain, definite, and inevitable error) correspond with reality.

Having accepted the truth of the above law, the question involuntarily arises whether there is any limit to the various chemical transformations, or are they unrestricted in number—that is to say, is it possible from a given substance to obtain an equivalent quantity of all other substances? In other words, does there exist a perpetual and infinite change of one kind of material into all other kinds, or is the cycle of these transformations limited? This is the second essential problem of Chemistry, a question of quality of matter, and one, it is evident, which is more complicated than the question of quantity. It cannot be resolved by a mere superficial glance at the subject. Indeed, on seeing how all the varied forms and colours of plants are built up from air and the elements of the soil, and how metallic iron can be transformed into dyes, such as inks and Prussian blue, we might be led to think that there is no end to the qualitative changes to which matter is susceptible. But, on the other hand, the everyday experiences of life compel us to acknowledge that food cannot be made out of a stone, or gold out of copper. Thus a definite answer can only be looked for in a close and diligent study of the subject, and the problem has been resolved in different ways at different times. In ancient times the opinion most generally held was that everything visible was composed of four elements—Air, Water, Earth, and Fire. The origin of this doctrine can be traced far back into the confines of Asia, whence it was handed down to the Greeks, and most fully expounded by Empedocles, who lived before 460 B.C. By accepting so small a number of elements it was easy to arrive at the conclusion that the cycle of chemical changes was, if not infinite, at all events most extensive. This doctrine was not arrived at by the results of exact research, but was only founded on the speculations of philosophers. It apparently owes its origin to the clear division of bodies into gases (like air), liquids (like water), and solids (like the earth). It seems that the Arabs were the first who tried to solve the question by means of experiment, and they introduced, through Spain, the taste for the study of similar problems into Europe, where from that time there appear many adepts in chemistry, which was considered as an unholy art, and called ‘alchemy.’ As the alchemists were ignorant of any exact or strict law which could guide them in their researches, they resolved the question of the transformation of substances in a most varied manner. Their chief service to chemistry was that they made a number of experiments, and discovered many new chemical transformations; but it is well known how they solved the fundamental problem of chemistry. Their view may be taken as a positive acknowledgment of the infinite transmutability of matter, for they aimed at

discovering the Philosopher's Stone, capable of converting everything into gold and diamonds, and of making the old young again. This solution of the question was afterwards most decidedly refuted, but it must not, for this reason, be thought that the hopes held by the alchemists were only the fruit of their imaginations. On the contrary, the first chemical experiments might well lead them to their conclusion. They took, for instance, the bright metallic mineral galena, and they extracted metallic lead from it. Thus they saw that from a metallic substance which is unfitted for use they could obtain another metallic substance which is ductile and valuable for many uses in the arts. Furthermore, they took this lead and obtained silver, a still more valuable metal, from it. Thus they might easily conclude that it was possible to ennoble metals by means of a whole series of transmutations—that is to say, to obtain from them those which are more and more precious. Having got silver from lead, they only aimed at getting gold from silver. The mistake they made was that they never weighed or measured the substances used or produced in their experiments. Had they done so, they would have learnt that the weight of the lead was much less than that of the galena from which it was obtained, and the weight of the silver infinitesimal compared with that of the lead. Had they looked more closely into the process of the extraction of the silver from lead (and now silver is chiefly obtained from the lead ores) they would have seen that the lead does not change into silver, but that it only contains a certain small quantity of it, and this amount having once been separated from the lead it cannot by any further operation give more. The silver which the alchemists extracted from the lead was in the lead, and was not obtained by a chemical change of the lead itself. This is now well known from experiment, but the first view of the nature of the process was very likely to be erroneous.²³ The methods of research adopted by the alchemists could not but give little

²³ Besides which, in the majority of cases, the first judgment on most subjects which do not repeat themselves in everyday experience under various aspects, but always in one form, or only at intervals and infrequently, is usually untrue. Thus the daily evidence of the rising of the sun and stars evokes the erroneous idea that the heavens move and the earth stands still. This apparent truth is far from being the real truth, and is even contradictory to it. Similarly, an ordinary mind and everyday experience concludes that iron is incombustible, whereas it burns not only as filings, but even as wire, as we shall afterwards see. With the progress of knowledge very many primitive prejudices have been obliged to give way to true ideas which have been verified by experiment. In ordinary life we often reason at first sight with perfect truth, only because we are taught a right judgment by our daily experience. It is a necessary consequence of the nature of our minds to reach the attainment of truth through elementary and often erroneous reasoning and through experiment, and it would be very wrong to expect a knowledge of truth from a simple mental effort. Naturally, experiment itself cannot give truth, but it gives the means of destroying erroneous representations whilst confirming those which are true in all their consequences.

success, for they groped in the dark, making all kinds of mixtures and experiments, without setting themselves clear and simple questions whose answers would aid them to make further progress. Thus they did not form one exact law, but, nevertheless, they left numerous and useful experimental data as an inheritance to chemistry; they studied, in particular, the transformations proper to metals, and for this reason chemistry was for long afterwards entirely confined to the study of metallic substances.

In their researches, the alchemists frequently made use of two chemical processes which are now termed 'reduction' and 'oxidation.' The rusting of metals, and in general their conversion from a metallic into an earthy form, is called 'oxidation,' whilst the extraction of a metal from an earthy substance is called 'reduction.' A large number of metals—for instance, iron, lead, and tin—are oxidised by heating in air alone, and may be again reduced by heating with carbon. Such oxidised metals are found in the earth, and form the majority of metallic ores. The metals, such as tin, iron, and copper, may be extracted from these ores by heating them together with carbon. All these processes were well studied by the alchemists. It was afterwards shown that all earths and minerals are formed of similar metallic rusts or oxides, or of their combinations. Thus the alchemists knew of two forms of chemical changes: the oxidation of metals and the reduction of the oxides so formed into metals. The explanation of the nature of these two classes of chemical phenomena was the means for the discovery of the most important chemical laws. The first hypothesis on their nature is due to Becker, and more particularly to Stahl, a surgeon to the King of Prussia. Stahl writes in his '*Fundamenta Chymię*,' 1723, that all substances consist of an imponderable fiery substance called 'phlogiston' (*materia aut principium ignis non ipse ignis*) and of another element having particular properties for each substance. The greater the capacity of a body for oxidation, or the more combustible it is, the richer it is in phlogiston. Carbon contains it in great abundance. In oxidation or combustion phlogiston is emitted, and in reduction it is consumed or enters into combination. Carbon reduces earthy substances because it is rich in phlogiston, and gives up a portion of its phlogiston to the substance reduced. Thus Stahl supposed metals to be compound substances consisting of phlogiston and an earthy substance or oxide. This hypothesis is distinguished for its very great simplicity, and for this and other reasons it acquired many supporters.²⁴

²⁴ It is true that Stahl was acquainted with a fact which directly disproved his hypothesis. It was already known (from the experiments of Geber, and more especially of Ray, in 1630) that metals increase in weight by oxidation, whilst, according to Stahl's

Lavoisier proved by means of the balance that every case of rusting of metals or oxidation, or of combustion, is accompanied by an increase in weight at the expense of the atmosphere. He formed, therefore, the natural opinion that the heavier substance is more complex than the lighter one.²⁵ The following remarkable experiment was made by Lavoisier in 1774, and gave indubitable support to his opinion, which was in many respects contradictory to Stahl's doctrine. Lavoisier

hypothesis, they should decrease in weight, because phlogiston is separated by oxidation. Stahl speaks on this point as follows:—'I know well that metals, in their transformation into earths, increase in weight. But not only does this fact not disprove my theory, but, on the contrary, confirms it, for phlogiston is lighter than air, and, in combining with substances, strives to lift them, and so decreases their weight; consequently, a substance which has lost phlogiston must be heavier.' This argument, it will be seen, is founded on an improper understanding of the properties of gases, regarding them as having no weight and as not being attracted by the earth, or else on a confused idea of phlogiston itself, as it was first defined as imponderable. The conception of imponderable phlogiston tallies well with the habit and methods of the last century, when recourse was often had to imponderable fluids for explaining a large number of phenomena. Heat, light, magnetism, and electricity were explained as being peculiar imponderable fluids. In this sense the doctrine of Stahl corresponds entirely with the spirit of his age. If heat be now regarded as movement or energy, then phlogiston also should be considered in this light. In fact, in combustion, of coals, for instance, heat and energy are evolved, and not combined in the coal, although the oxygen and coal do combine. Consequently, the doctrine of Stahl contains the essence of a true representation of the evolution of energy, but naturally this evolution is only a consequence of the combination going on between the coal and oxygen. As regards the history of chemistry prior to Lavoisier, besides Stahl's work (to which reference has been made above), Priestley's *Experiments and Observations on Different Kinds of Air*, London, 1790, and also Scheele's *Opuscula Chimica et Physica*, Lips., 1788-89, 2 vols., must be recommended as the two leading works of the English and Scandinavian chemists showing the condition of chemical learning before the propagation of Lavoisier's views. A most interesting memoir on the history of phlogiston is that of Rodwell, in the *Philosophical Magazine*, 1868, in which it is shown that the idea of phlogiston dates very far back, that Basil Valentine (1394-1415), in the *Cursus Triumphalis Antimonii Paracelsus* (1493-1541), in his work, *De Rerum Natura*, Glauber (1604-1668), and especially John Joachim Becher (1625-1682), in his *Physica Subterranea*, all referred to phlogiston, but under different names.

²⁵ An Englishman, named Mayow, who lived a whole century before Lavoisier (in 1666), understood certain phenomena of oxidation in their true aspect, but was not able to develop his views with clearness, or make his doctrine a universal inheritance, or express it by instructive experiments; he, therefore, cannot be considered, like Lavoisier, as the founder of contemporary chemical learning. Science is a universal heritage, and therefore it is only just to give the highest honour in science, not to those who first enunciate a certain truth, but to those who are first able to convince others of its authenticity and establish it for the general welfare. It should be observed, with reference to scientific discoveries, that they are rarely made all at once, but, as a rule, the first teachers do not succeed in convincing others of the truth they have discovered; with time, however, the store of materials for its demonstration increases, and other teachers come forward, possessing every means for making the truth apparent to all. They are rightly considered as the founders; but it must not be forgotten they are entirely indebted to the labours and mass of data accumulated by many others. Such was Lavoisier, and such are all the great founders of science. They are the enunciators of all past and present learning, and their names will always be revered by posterity.

poured four ounces of pure mercury into a glass retort (fig. 3), whose neck was bent as shown in the drawing and dipped into the vessel R S, also full of mercury. The projecting end of the neck was covered with a glass bell jar P. The weight of all the mercury taken, and the volume of air remaining in the apparatus, namely, that in the upper portion of the retort, and under the bell-jar, were determined before beginning the experiment. In this experiment it was most important to know the volume of air in order to learn what part it played in the oxidation of the mercury, because, according to Stahl, phlogiston is emitted into the air, whilst, according to Lavoisier, the mercury in




FIG. 3.—Lavoisier's apparatus for determining the composition of air and the reason of metals increasing in weight when they are calcined in air.

oxidising absorbs a portion of the air ; and consequently it was absolutely necessary to determine whether the amount of air increased or decreased in the oxidation of the metal. It was, therefore, most important to measure the volume of the air in the apparatus both before and after the experiment. For this purpose it was necessary to know the total capacity of the retort, the volume of the mercury poured into it, the volume of the bell-jar above the level of the mercury, and also the temperature and pressure of the air at the time of its measurement. The volume of air held in the apparatus and isolated from the surrounding atmosphere could be determined from these data. Having arranged his apparatus in this manner, Lavoisier heated the retort holding the mercury for a period of twelve days at a temperature near the boiling point of mercury. The mercury became covered with a quantity of small red scales ; that is, it was oxidised or converted into an earth. This substance is the same mercury oxide which has already been mentioned (example 3). After the lapse of twelve days the apparatus was cooled, and it was then seen that the volume of the air in the apparatus had diminished during the time of the experiment. This result was in exact contradiction to Stahl's hypothesis. Out of 50 cubic inches of air originally taken, there only remained 42.

Lavoisier's experiment led to other no less important results. The weight of the air taken decreased by as much as the weight of the mercury increased in oxidising ; that is, the portion of the air was not destroyed, but only combined with mercury. This portion of the air may be again separated from the mercury oxide, and has, as we saw (example 3), properties different from those of air. That portion of the air which remained in the apparatus and did not combine with the mercury does not oxidise metals, and cannot support either combustion or respiration, so that a lighted taper is immediately extinguished if it be dipped into the gas which remains in the bell-jar. 'It is extinguished in the remaining gas as if it had been plunged into water,' writes Lavoisier in his memoirs. This gas is called 'nitrogen.' Thus air is not a simple substance, but consists of two gases, oxygen and nitrogen, and therefore the opinion that air is an elementary substance is erroneous. The oxygen of the air is absorbed in combustion and the oxidation of metals, and the earths produced by the oxidation of metals are substances composed of oxygen and a metal. By mixing the oxygen with the nitrogen the same air as was originally taken is re-formed. The existence of compound substances was incontestably proved by these experiments. It has also been shown by direct experiment that on reducing an oxide with carbon, the oxygen contained in the oxide is transferred to the carbon, and gives the same gas as is obtained by the combustion of carbon in air. Therefore this gas is a compound of carbon and oxygen, just as the earthy oxides are composed of metals and oxygen.

The many examples of the formation and decomposition of substances which are met with convince us that the majority of substances with which we have to deal are compounds made up of several other substances. By heating chalk (or else copper carbonate, as in the second example) we obtain lime and the same carbonic acid gas which is produced by the combustion of carbon. On bringing lime into contact with this gas and water, at the ordinary temperature, we again obtain the compound carbonate of lime, or chalk. Therefore chalk is a compound. So also are those substances from which it may be built up. Carbonic anhydride is formed by the combination of carbon and oxygen ; and lime is produced by the oxidation of a certain metal called 'calcium.' By breaking up substances in this manner into their component parts, we arrive at last at such as are indivisible into two or more substances by any means whatever, and which cannot be formed from other substances. All we can do is to make such substances combine together or act on other substances. Substances which cannot be formed from or decomposed into others are termed *simple substances* (elements). Thus

all homogeneous substances may be classified into simple and compound substances. This view was introduced and established as a scientific fact during the lifetime of Lavoisier. The number of these elements is very small in comparison with the number of compound substances which are formed by them. At the present time, only seventy elements are known with certainty to exist. Some of them are very rarely met with in nature, or are found in very small quantities, whilst others are yet doubtful. The number of elements with whose compounds we commonly deal in everyday life is very small. Elements cannot be transmuted into one another—at least up to now not a single case of such a transformation has been met with; it may therefore be said that, as yet, it is impossible to transmute one metal into another. And as yet, notwithstanding the number of assays which have been made in this direction, no fact has been discovered which could in any way support the idea of the complexity of those indubitably-known elements²⁶—such as oxygen, iron, sulphur, &c. Therefore, from its conception, an element is not susceptible to reactions of decomposition.²⁷

²⁶ Many ancient philosophers admitted the existence of one elementary form of matter. This idea still appears in our times, in the constant efforts which are made to reduce the number of the elements; to prove, for instance, that bromine contains chlorine or that chlorine contains oxygen. Many methods, founded both on experiment and theory, have been tried to prove the compound nature of the elements. All labour in this direction has as yet been in vain, and the assurance that elementary matter is not so homogeneous (single) as the mind would desire in its first transport of rapid generalisation is strengthened from year to year. At all events, there are as yet no experimental or theoretical evidences of the compound nature of our elements. With the methods and evidence now at our disposal it is impossible to even imagine the possibility of a method by which the different elements could be formed from one elementary material. Cases of isomerism and of polymerism of compound substances certainly show the possibility of the formation, from one and the same elements, of substances with different properties, but every change of this kind is completely levelled and nullified by a certain rise in temperature by which every isomeride and polymeride is converted into one variety and changes its original properties. All our knowledge shows that iron and other elements remain, even at such a high temperature as there exists in the sun, as different substances, and are not converted into one common material. Admitting, even mentally, the possibility of one elementary form of matter, a method must be imagined by which it could give rise to the various elements, as also the *modus operandi* of their formation from one material. If it be said that this diversitude only takes place at low temperatures, as is observed with isomerides, then there would be reason to expect, if not the transition of the various elements into one particular and more stable form, at least the mutual transformation of some into others. But nothing of the kind has yet been observed, and the alchemist's hope to manufacture (as Berthollet puts it) elements has no foundation of fact or theory.

²⁷ The weakest point in the idea of elements is the negative character of the determinative signs given them by Lavoisier, and from that time ruling in chemistry. They do *not* decompose, they do *not* change into one another. But it must be remarked that elements form the limiting horizon of our knowledge of matter, and it is always difficult to determine a positive side on the borderland of what is known. But all the same, it is not for all, at all events for the majority, of those having the properties of metals, there is a series of positive common signs (they possess a particular appearance and lustre

The quantity, therefore, of each element remains constant in all chemical changes ; which fact may be deduced as a consequence of the law of the indestructibility of matter, and of the conception of elements themselves. Thus the equation expressing the law of the indestructibility of matter acquires a new and still more important signification. If we know the quantities of the elements which occur in the acting, it may be compound, substances, and if from these substances there proceed, by means of chemical changes, a series of new compound substances, then the latter will together contain the same quantity of each of the elements as there originally existed in the reacting substances. The essence of chemical change is embraced in the study of how, and with what substances, each element is combined before and after change.

In order to be able to express various chemical changes by equations, it has been agreed to represent each element by the first or some two letters of its (Latin) name. Thus, for example, oxygen is represented by the letter O ; nitrogen by N ; mercury (hydrargyrum) by Hg ; iron (ferrum) by Fe ; and so on for all the elements, as is seen in the tables on page 24. A compound substance is represented by placing the symbols representing the elements of which it is made up side by side. For example, red mercury oxide is represented by HgO , which shows that it is composed of oxygen and mercury. Besides this, the symbol of every element corresponds with a certain relative quantity of it by weight, called its 'combining' weight, or the weight of an atom; so that the chemical formula of a compound substance not only designates the nature of the elements of which it is composed, but also their quantitative proportion. Every chemical process may be expressed by an equation composed of the formulæ corresponding with those substances which take part in it and are produced by it. The amount by weight of the elements in every chemical equation must be equal on both sides of the equation, because no element is either formed or destroyed in a chemical change.

On pages 24, 25, and 26 a list of the elements, with their symbols and combining or atomic weights, is given, and we shall see afterwards on what basis the atomic weights of elements are determined. At present we will only point out that a compound containing the elements A and B is designated by the formula A^nB^m , where m and n are the coefficients or multiples in which the combining weights of the

they conduct an electric current without decomposing) which allow them to be distinguished at a glance from other kinds of matter. Besides, there is no doubt (from the results of spectrum analysis) that the elements are distributed as far as the most distant stars, and that they support the highest attainable temperatures without decomposing.

elements enter into the composition of the substance. If we represent the combining weight of the substance A by a and that of the substance B by b , then the composition of the substance A^nB^m will be expressed thus : it contains na parts by weight of the substance A and mb parts by weight of the substance B, and consequently in 100 parts of our compound there is contained $\frac{na}{na+mb} 100$ percentage parts by weight of the substance A and $\frac{mb}{na+mb} 100$ of the substance B. It is evident that

as a formula shows the relative amounts of all the elements contained in a compound, the actual weights of the elements contained in a given weight of a compound may be calculated from its formula. For example, the formula NaCl of table salt shows (as $\text{Na}=23$ and $\text{Cl}=35.5$), that 58.5 lbs. of salt contain 23 lbs. of sodium and 35.5 lbs. of chlorine, and that 100 parts of it contain 39.3 per cent. of sodium and 60.7 per cent. of chlorine.

What has been said above clearly limits the province of chemical changes, because from substances of a given kind there can be obtained only such as contain the same elements. But, notwithstanding this primary limitation, the number of possible combinations is infinitely great. Only a comparatively small number of compounds have yet been described or subjected to research, and any one working in this direction may easily discover new compounds which had not before been obtained. It often happens, however, that such newly-discovered compounds were foreseen by chemistry, whose object is the apprehension of that uniformity which rules over the multitude of compound substances, and whose aim is the comprehension of those laws which govern their formation and properties. When once the conception of elements had been established, the most intimate object of chemistry was the determination of the properties of compound substances on the basis of the determination of the quantity and kind of elements of which they are composed ; the investigation of the elements themselves ; the determination of what compound substances can be formed from each element and the properties which these compounds show ; and the apprehension of the nature of the connection between the elements in different compounds. An element thus serves as the starting point, and is taken as the primary conception under which all other bodies are embraced.

When we state that a certain element enters into the composition of a given compound (when we say, for instance, that mercury oxide contains oxygen) we do not mean that it contains oxygen as a gaseous substance, but only desire to express those transformations which mercury oxide is capable of making ; that is, we wish to say that it is

possible to obtain oxygen from mercury oxide, and that it can give up oxygen to various other substances ; in a word, we desire only to express those transformations of which mercury oxide is capable. Or, more concisely, it may be said that the *composition* of a compound is the expression of those transformations of which it is capable. It is useful in this sense to make a clear distinction between the conception of an element as a *separate* homogeneous substance, and as a *material* but invisible *part* of a compound. Mercury oxide does not contain two simple bodies, a gas and a metal, but two elements, mercury and oxygen, which, when free, are a gas and a metal. Neither mercury as a metal nor oxygen as a gas is contained in mercury oxide ; it only contains the substance of these elements, just as steam only contains the substance of ice, but not ice itself, or as corn contains the substance of the seed but not the seed itself. The existence of an element may be recognised without knowing it in the uncombined state, but only from an investigation of its combinations, and from the knowledge that it gives, under all possible conditions, substances which are unlike other known combinations of substances. Fluorine is an example of this kind. It was for a long time unknown in a free state, and was, nevertheless, recognised as an element because its combinations with other elements were known, and their difference from all other similar compound substances was determined. In order to grasp the difference between the conception of the visible form of an element as we know it in the free state, and of the intrinsic element (or 'radicle,' as Lavoisier called it) contained in the visible form, it should be remarked that compound substances also combine together forming yet more complex compounds, and that they evolve heat in the process of combination. The original compound may often be extracted from these new compounds by exactly the same methods as elements are extracted from their corresponding combinations. Besides, many elements exist under various visible forms whilst the intrinsic element contained in these various forms is something which is not subject to change. Thus carbon appears as charcoal, graphite, and diamond, but yet the element carbon alone contained in each is one and the same. Carbonic anhydride contains carbon, and not charcoal, or graphite, or the diamond.

Elements alone, although not all of them, have the peculiar lustre, opacity, malleability, and the great heat and electrical conductivity which are proper to metals and their mutual combinations. But elements are far from all being *metals*. Those which do not possess the physical properties of metals are called *non-metals* (or *metalloids*). It is, however, impossible to draw a strict line of demarcation between metals and non-metals, there being many intermediary substances.

Thus graphite, from which pencils are manufactured, is an element with the lustre and other properties of a metal ; but charcoal and the diamond, which are composed of the same substance as graphite, do not show any metallic properties. Both classes of elements are clearly distinguished in definite examples, but in particular cases the distinction is not clear and cannot serve as a basis for the exact division of the elements into two groups.

At all events, the conception of elements forms the basis of chemical knowledge, and if we give a list of them at the very beginning of our work, it is that we wish to symbolise the condition of the contemporary information on the subject. Altogether about seventy elements are now authentically known, but many of them are so rarely met with in nature, and have been obtained in such small quantities, that we possess but a very insufficient knowledge of them. The substances most widely distributed in nature contain a very small number of elements. These elements have been more completely studied than the others because a greater number of investigators have been able to carry on experiments and observations on them. The elements most widely distributed in nature are :—

Hydrogen,	H = 1.	In water, and animal and vegetable organisms.
Carbon,	C = 12.	In organisms, coal, limestones.
Nitrogen,	N = 14.	In air and in organisms.
Oxygen,	O = 16.	In air, water, earth. It forms the greater part of the mass of the earth.
Sodium,	Na = 23.	In common salt and in many minerals.
Magnesium,	Mg = 24.	In sea-water and in many minerals.
Aluminium,	Al = 27.	In minerals and clay.
Silicon,	Si = 28.	In sand, minerals, and clay.
Phosphorus,	P = 31.	In bones, ashes of plants, and soil.
Sulphur,	S = 32.	In pyrites, gypsum, and in sea-water.
Chlorine,	Cl = 35.5.	In common salt, and in the salts of sea-water.
Potassium,	K = 39.	In minerals, ashes of plants, and in nitre.
Calcium,	Ca = 40.	In limestones, gypsum, and in organisms.
Iron,	Fe = 56.	In the earth, iron ores, and in organisms.

Beside these, the following elements, although not very largely distributed in nature, are all more or less well known from their applications to the requirements of everyday life or the arts, either in a free state or in their compounds :—

Lithium,	Li = 7.	In medicine (Li_2CO_3), and in photography (LiBr).
Boron,	B = 11.	As Borax, $\text{B}_4\text{Na}_2\text{O}_7$, and as boric anhydride, B_2O_3 .

Fluorine,	F =19.	As fluor spar, CaF_2 , and as hydrofluoric acid, HF .
Chromium,	Cr =52.	As chromic anhydride, CrO_3 , and potassium dichromate, $\text{K}_2\text{Cr}_2\text{O}_7$.
Manganese,	Mn=55.	As manganese peroxide, MnO_2 , and potassium permanganate, MnKO_4 .
Cobalt,	Co=59.	In smalt and blue glass.
Nickel,	Ni=59.	For electro-plating other metals.
Copper,	Cu=63.	The well-known red metal.
Zinc,	Zn=65.	Used for the plates of batteries, roofing, &c.
Arsenic,	As=75.	White arsenic, As_2O_3 .
Bromine,	Br =80.	A brown volatile liquid ; sodium bromide, NaBr .
Strontium,	Sr =87.	In coloured fires (SrN_2O_6).
Silver,	Ag=108.	The well-known white metal.
Cadmium,	Cd=112.	In alloys. Yellow paint (CdS).
Tin,	Sn=118.	The well-known metal.
Antimony,	Sb=122.	In alloys such as type metal.
Iodine,	I =127.	In medicine and photography ; free, and as KI .
Barium,	Ba=137.	"Permanent white," and as an adulterant in white lead, and in heavy spar, BaSO_4 .
Platinum,	Pt =196.	Well-known metals.
Gold,	Au=197.	
Mercury,	Hg=200.	
Lead,	Pb =207.	
Bismuth,	Bi =208.	In medicine and fusible alloys.
Uranium,	U =240.	In green fluorescent glass.

The compounds of the following metals and semi-metals have fewer applications, but are well known, and are somewhat frequently met with in nature, although in small quantities :—

Beryllium,	Be=9.	Palladium, Pd=106.
Titanium,	Ti =48.	Cerium, Ce =140.
Vanadium,	V =51.	Tungsten, W =184.
Selenium,	Se =78.	Osmium, Os=193.
Zirconium,	Zr =90.	Iridium, Ir=195.
Molybdenum,	Mo=96.	Thallium, Tl=204.

The following rare metals are still more seldom met with in nature and are not yet applied to the arts, but have been studied somewhat fully :—

Scandium, Sc=44.	Indium, In=113.
Gallium, Ga=68.	Tellurium, Te=125.
Germanium, Ge=72.	Cæsium, Cs=132.
Rubidium, Rb=85.	Lanthanum, La'=138.
Yttrium, Y=89.	Didymium, Di=143.
Niobium, Nb=94.	Ytterbium, Yb=173.
Ruthenium, Ru=104.	Tantalum, Ta=182.
Rhodium, Rh=104.	Thorium, Th=234.

Besides these 66 elements there have been discovered :—Erbium, Terbium, Samarium, Thullium, Holmium, Mosandrium, Phillipium, Vesbium, Actinium, and several others. But their properties and combinations, owing to their extreme rarity, are very little known, and even their existence as independent substances ²⁸ is doubtful.

It has been incontestably proved from observations on the spectra of the heavenly bodies that many of the most common elements (such as H, Na, Mg, Fe) occur on the far distant stars. This fact confirms the belief that those forms of matter which appear on the earth as elements are widely distributed over the entire universe. But why, in nature, the mass of some elements should be greater than that of others we do not yet know.

The capacity of each element to combine with one or another element, and to form compounds with them which are in a greater or less degree prone to give new and yet more complex substances, forms the fundamental character of each element. Thus sulphur easily combines with the metals, oxygen, chlorine, or carbon, forming stable substances, whilst gold and silver enter into combinations with difficulty, and form unstable compounds, which are easily decomposed by heat. Compounds, and also elements, may be divided into two classes—those which easily enter into many different chemical changes, and those which enter into but few combinations, which are characterised by their small capacity for the direct formation of new, more complex substances. The cause or force which induces substances to enter into chemical change must be considered, as also the cause which holds different substances in combination—that is, which endues the substances formed with their particular degree of stability. This cause or force is called *affinity* (*affinitus*, *affinité*, *verwandtschaft*), or chemical affinity.²⁹

²⁸ It may be that some of them are compounds of other already-known elements. Pure and incontestably independent compounds of these substances are unknown, and some of them have not even been separated but are only supposed to exist from the results of spectroscopic researches. There can be no mention of such contestable and doubtful elements in a short general handbook of chemistry.

²⁹ This word, first introduced, if I mistake not, into chemistry by Glauber, is based on the idea of the ancient philosophers that combination can only take place when the sub-

As this force must be regarded as exclusively an attractive force, like gravity, many writers (for instance, Bergmann at the end of the last, and Berthollet at the beginning of this, century) supposed affinity to be essentially similar to the universal force of gravity, from which it only differs in that the latter acts at observable distances whilst affinity only evinces itself at the smallest possible distances. But chemical affinity cannot be entirely identified with the universal attraction of gravity, which acts at observable distances and which is dependent only on mass and distance, and not on the quality of the material on which it acts, whilst it is by the quality of matter that affinity is most forcibly influenced. Neither can it be entirely identified with cohesion, which gives to homogeneous solid substances their crystalline form, elasticity, hardness, ductility, and other properties, and to liquids their surface, drop formation, capillarity, and other properties, because affinity acts between the component parts of a substance and cohesion on a substance in its homogeneity, although both act at imperceptible distances (by contact) and have much in common. Chemical force, which makes one substance penetrate into another, cannot be entirely identified with even those attracting forces which make different substances adhere to each other, or hold together (as when two plane-polished surfaces of solid substances are brought into close contact), or which cause liquids to soak into solids, or adhere to their surfaces, or gases and vapours to condense on the surfaces of solids. These forces must not be confounded with chemical forces, which cause one substance to penetrate into the substance of another and to form a new substance, which is not the case with cohesion. But it is evident that the forces which determine cohesion form a connecting-link between mechanical and chemical forces, because they only act by intimate contact and between different kinds of matter. For a long time, and especially during the first half of this century, chemical attraction and chemical forces were identified with electrical forces. There is certainly an intimate relation between them, for electricity is evolved in chemical reactions, and it, in its turn, has a powerful influence on chemical processes—for instance, compounds are decomposed by the action of an electrical current. But the exactly similar relation which exists between chemical phenomena and the phenomena of heat (heat being developed by chemical phenomena, and heat being able to decompose compounds) only proves the unity of the forces of nature, the capability of one force to produce and to be trans-

stances combining have something in common—a medium. As is generally the case, another idea evolved itself in antiquity, and has lived until now, side by side with the first, to which it is exactly contradictory; this considers union as dependent on contrast, on polar difference, on an effort to fill up a want.

formed into others. Therefore the identification of chemical force with electricity will not bear experimental proof.³⁰ As of all the (molecular) phenomena of nature which act on substances at immeasurably small distances, the phenomena of heat are at present the best (comparatively) known, having been reduced to the simplest fundamental principles of mechanics (of energy, equilibrium, and movement), which, since Newton, have been subjected to strict mathematical analysis, it is quite natural that an effort, which has been particularly pronounced during recent years, should have been made to bring chemical phenomena into strict correlation with, and under the theory founded on, the already investigated phenomena of heat, without, however, aiming at any identification of chemical with heat phenomena. The true nature of chemical force is still a secret to us, just as is the nature of the universal force of gravity, and yet without knowing what gravity really is, by applying mechanical conceptions, astronomical phenomena have been subjected not only to exact generalisation but to the detailed prediction of a number of particular facts ; and so, also, although the true nature of chemical affinity may be unknown, there is reason to hope for considerable progress in chemical science by applying the laws of mechanics to chemical phenomena by means of the mechanical theory of heat. But as yet this portion of chemistry has been but little worked at, and therefore, while forming a current problem of the science, it is treated more fully in that particular

³⁰ Especially conclusive are those cases of so-called *metalepsis* (Dumas, Laurent). Chlorine, in combining with hydrogen, forms a very stable substance, called 'hydrochloric acid,' which is split up by the action of an electrical current into chlorine and hydrogen, the chlorine appearing at the positive and the hydrogen at the negative pole. From this electro-chemists considered hydrogen to be an electro-positive and chlorine an electro-negative element, and that they are held together in virtue of their opposite electric charges. It appears, however, from *metalepsis*, that chlorine can replace hydrogen (and reversely hydrogen replaces chlorine) in its compounds without in any way changing the grouping of the other elements, or altering their chief chemical properties. Thus the capacity of acetic acid to form salts is not altered by replacing its hydrogen by chlorine. Here an electro-positive element is replaced by an electro-negative element, which is quite contrary to the electrical theory of the origin of chemical attraction, which has thus been entirely overthrown by the facts of *metalepsis*. We must remark, whilst considering this subject, that the explanation suggesting electricity as the origin of chemical phenomena is unsound in that it strives to explain one class of phenomena whose nature is almost unknown by another class which is no better known. It is most instructive to remark that together with the electrical theory of chemical attraction there arose and survives a view which explains the galvanic current as being a transference of chemical action through the circuit—*i.e.*, regards the origin of electricity as being a chemical one. It is evident that the connection is very intimate, but both kinds of phenomena are independent and represent different forms of molecular (atomic) movement, whose real nature is not yet understood. Nevertheless, the connection between the phenomena of both categories is not only in itself very instructive, but it extends the applicability of the general idea of the unity of the forces of nature, conviction of the truth of which has held so important a place in the science of the last ten years.

province which is termed either 'theoretical' or 'physical' chemistry, or, better still, *chemical mechanics*. As this province of chemistry requires a knowledge not only of the various homogeneous substances which have yet been obtained and of the chemical transformations which they undergo, but also of the phenomena (of heat and other kinds) by which these transformations are accompanied, it is only possible to enter on the study of chemical mechanics after an acquaintance with the fundamental chemical conceptions and substances which form the subject of this book.³¹

³¹ I consider that in an elementary textbook of chemistry, like the present, it is only possible and advisable to mention, in reference to chemical mechanics, a few general ideas and some particular examples referring more especially to gases, whose mechanical theory must be regarded as the most complete. The molecular mechanics of liquids and solids is as yet in embryo, and contains much that is disputable; for this reason, chemical mechanics has made less progress in relation to these substances. It may not be superfluous to here remark, with respect to the conception of chemical affinity, that up to the present time gravity, electricity, and heat have been respectively applied to its elucidation. Efforts have also been made to introduce the luminiferous ether into theoretical chemistry, and should that connection between the phenomena of light and electricity which was established by Maxwell be worked out more in detail, doubtless these efforts to elucidate all or a great deal by the aid of luminiferous ether will yet again appear in theoretical chemistry. An independent chemical mechanics of the material particles of matter, and of their internal (atomic) changes, would, in my opinion, arise as the result of these efforts. Just as the progress made in chemistry in the time of Lavoisier was reflected over all natural science, so there is reason to think that an independent chemical mechanics would shed a new light on all molecular mechanics, which must be considered as the fundamental problem of the exact sciences in our times. Two hundred years ago Newton laid the foundation of a truly scientific theoretical mechanics of external visible movement, and erected the edifice of celestial mechanics on this foundation. One hundred years ago Lavoisier arrived at the first fundamental law of the internal mechanics of invisible particles of matter. This subject is far from having been developed into a harmonious whole, because it is much more difficult, and, although many details have been completely investigated, it does not possess any starting points. Newton was possible only after Copernicus and Kepler, who had discovered the exterior empirical simplicity of celestial phenomena. Lavoisier and Dalton may, in respect to the chemical mechanics of the molecular world, be compared to Copernicus and Kepler. But a Newton has not yet appeared in the molecular world; when he does, I think that he will find the fundamental laws of the mechanics of the invisible movements of matter more easily and more quickly in the chemical structure of matter than in physical phenomena (of electricity, heat, and light), for these latter are accomplished by already-disposed particles of matter, whilst it is now clear that the problem of chemical mechanics mainly lies in the apprehension of those movements which are invisibly accomplished by the smallest atoms of matter. The general laws of mechanics, established by Newton, will probably serve as starting points for molecular mechanics, but the independence of its range becomes more evident when chemical molecules are compared with the celestial systems, such as the solar system. Chemical atoms may be regarded as separate members of such systems (as, for instance, the sun, planets, comets, and other heavenly bodies), whilst the ether of light may be likened to the cosmic dust which without doubt is distributed throughout space. The present condition of molecular mechanics is, to a certain extent, copied from celestial mechanics, but there is nothing to prove the entire similarity of both worlds, although it appears to the mind that, starting from the primary elements of the unity of creation, such a representation is the most likely.

As the chemical changes to which substances are liable proceed from internal forces proper to these substances, as chemical phenomena certainly consist of movements of material parts (from the laws of the indestructibility of matter and of elements), and as the investigation of mechanical and physical phenomena proves the law of the *indestructibility of forces*, or the conservation of energy—that is, the possibility of the transformation of one kind of movement into another (of visible or mechanical into invisible or physical)—we are inevitably obliged to acknowledge the presence in substances (and especially in the elements of which all others are composed) of a store of *chemical energy* or invisible movement inducing them to enter into combinations. If heat be evolved in a reaction, it means that a portion of chemical energy is transformed into heat;³² if heat be absorbed in a reaction,³³ that it is

³² The theory of heat gave the idea of a store of internal movement or energy, and therefore with it, it became necessary to acknowledge chemical energy, but there is no foundation whatever for identifying heat energy with chemical energy. It may be supposed, but not positively affirmed, that heat movement is proper to molecules and chemical movements to atoms, but that as molecules are made up of atoms, the movement of the one passes to the other, and that for this reason heat strongly influences reaction and appears or disappears (is absorbed) in reactions. These relations, which are apparent and hardly subject to doubt on general lines, still present much that is doubtful in detail, because all forms of molecular and atomic movement are able to pass into each other. On broad general lines it must be acknowledged that as mechanical energy can entirely pass into heat energy (but the reverse transition is accomplished only partially, according to the second law of heat), so also heat energy may pass into chemical energy, but it is doubtful, and even unlikely, that chemical energy passes altogether into heat energy. Therefore, the heat evolved in chemical reactions cannot serve as the total measure of chemical energy, more especially as there are a number of reactions of combination in which heat is absorbed; for instance, the combination of charcoal with sulphur is accompanied by an absorption of heat—probably because the molecules of charcoal are complex, and those of carbon bisulphide less so, and the breaking up of the complex molecules of charcoal requires a large absorption of heat (whose measure we do not know)—and whilst the combination of charcoal with sulphur is accompanied by an evolution of heat, yet we only observe the difference of these two heat effects.

³³ The reactions which take place (at the ordinary or at a high temperature) directly between substances may be clearly divided into exothermal, which are accompanied by an evolution of heat, and endothermal, which are accompanied by an absorption of heat. It is evident that the latter require a source of heat. They are determined either by the directly surrounding medium (as in the formation of carbon bisulphide from charcoal and sulphur, or in decompositions which take place at high temperatures), or else by a simultaneously proceeding secondary reaction. So, for instance, hydrogen sulphide is decomposed by iodine in the presence of water at the expense of the heat which is evolved by the solution in water of the hydrogen iodide produced. This is the reason why this reaction, as exothermal, only takes place in the presence of water; otherwise it would be accompanied by a cooling effect. As in the combination of dissimilar substances, the bonds existing between the molecules and atoms of the homogeneous substances have to be broken asunder, whilst in reactions of rearrangement the formation of any one substance proceeds parallel with the formation of another, and, as in reactions, a series of physical and mechanical changes take place, it is impossible to separate the heat directly depending on a given reaction from the total sum of the observed heat effect. For this

partly transformed (rendered latent) into chemical energy. The store of force or energy going to the formation of new compounds may, after several combinations, accomplished with an absorption of heat, at last diminish to such a degree that indifferent compounds will be obtained, although these sometimes, by combining with energetic elements or compounds, give more complex compounds, which may be capable of entering into chemical combination. Among elements gold, platinum, and nitrogen have but little energy, whilst potassium, oxygen, and chlorine have a very marked degree of energy. When dissimilar substances enter into combination they often form substances of diminished energy. Thus sulphur and potassium when heated easily burn in air, but when combined together their compound is neither inflammable nor burns in air like its component parts. Part of the energy of the potassium and of the sulphur was evolved in their combination in the form of heat. Just as in the passage of substances from one physical state into another a portion of their store of heat is absorbed or evolved, so in combinations or decompositions and in every chemical process, there occurs a change in the store of chemical energy, and at the same time an evolution or absorption of heat.³⁴

For the comprehension of chemical phenomena in a mechanical sense *i.e.*, in the study of the *modus operandi* of chemical phenomena – it is at the present time most important to consider: (1) the facts gathered from stoichiometry, or that part of chemistry which treats of the quantitative relation, by weight or volume, of the reacting substances; (2) the distinction between the different forms and classes of chemical reactions; (3) the study of the changes in properties produced by alteration in composition; (4) the study of the phenomena which accompany chemical transformation; (5) a generalisation of the conditions under which reactions occur. As regards stoichiometry, this branch of chemistry has been worked out most thoroughly, and embraces laws (of Dalton, Avogadro-Gerhardt, and others) which bear so deeply on all parts of chemistry that its entire contemporary standing may be

reason, thermo-chemical data are very complex, and cannot by themselves give the key to many chemical problems, as it was at first supposed they might. They ought to form a part of chemical mechanics, but alone they do not constitute it.

³⁴ As chemical reactions are effected by heating, so the heat absorbed by substances before decomposition or change of state, and called 'specific heat,' goes in many cases to the preparation, if it may be so expressed, of reaction, even when the limit of the temperature of reaction is not attained. The molecules of a substance A, which is able to react on a substance B below a temperature t by being heated from a somewhat lower temperature to t , undergoes that change which had to be arrived at for the formation of A B. This idea is often extended; for instance, it is supposed that a given substance in its passage from a liquid to a gaseous state gives chemically or materially new, lighter, and simpler molecules (is depolymerised, according to De Haen).

characterised as the epoch of their circumstantial application to particular cases. The expression of the quantitative (volumetric or gravimetric) composition of substances now forms the most important problem of chemical research, and therefore the entire further exposition of the subject is subordinate to stoichiometrical laws. All other branches of chemistry are clearly subordinate to this most important portion of chemical knowledge. Even the very signification of reactions of combination, decomposition, and rearrangement, acquired, as we shall see, a particular and new character under the influence of the progress of exact ideas concerning the quantitative relations of substances entering into chemical changes. Furthermore, in this sense there arose a new—and, up to then, unknown—division of compound substances into *definite* and *indefinite* compounds. Even at the beginning of this century, Berthollet had not made this distinction. But Prout showed that a number of compounds contain the substances of which they are composed and into which they break up, in exact definite proportions by weight, which are unalterable under any conditions. Thus, for example, red mercury oxide contains sixteen parts by weight of oxygen for every 200 parts by weight of mercury, which is expressed by the formula HgO . But in an alloy of copper and silver one or the other metal may be added at will, and in an aqueous solution of sugar, the relative proportion of the sugar and water may be altered and nevertheless a homogeneous whole with the sum of the independent properties will be obtained—*i.e.*, in these cases there was indefinite chemical combination. Although in nature and chemical practice the formation of indefinite compounds (such as alloys and solutions) plays as essential a part as the formation of definite chemical compounds, yet, as the stoichiometrical laws at present apply chiefly to the latter, all facts concerning indefinite compounds suffer from inexactitude, and it is only during recent years that the attention of chemists has been directed to this province of chemistry.

In chemical mechanics it is, from a qualitative point of view, very important to clearly distinguish at the very beginning between *reversible* and *non-reversible reactions*. One or several substances capable of reacting on each other at a certain temperature produce substances which at the same temperature either can or cannot give back the original substances. For example, salt dissolves in water at the ordinary temperature, and the solution so obtained is capable of breaking up at the same temperature, leaving salt and separating the water by evaporation. Carbon bisulphide is formed from sulphur and carbon at the same temperature at which it can be resolved into sulphur and carbon. Iron, at a certain temperature, separates hydrogen from water, forming iron oxide, which,

in contact with hydrogen at the same temperature, is able to produce iron and water. It is evident that if two substances, A and B, give two others C and D, and the reaction be reversible, then C and D will form A and B, and, consequently, by taking a definite mass of A and B, or a corresponding mass of C and D, we shall obtain, in each case, all four substances—that is to say, there will be a state of *chemical equilibrium* between the reacting substances. By increasing the mass of one of the substances we obtain a new condition of equilibrium, so that reversible reactions present a means of studying the *influence of mass* on the *modus operandi* of chemical changes. Many of those reactions which occur with very complicated compounds or mixtures may serve as examples of non-reversible reactions. Thus many of the compound substances of animal and vegetable organisms are broken up by heat, but cannot be re-formed from their products of decomposition at any temperature. Gunpowder, as a mixture of sulphur, nitre, and carbon, on burning, forms gases from which the original substances cannot be re-formed at any temperature. In order to obtain them, recourse must be had to an indirect method of *combination at the moment of separation*. If A does not under any circumstances combine directly with B, it does not imply that it cannot give a compound A B. For A can often combine with C and B with D, and if C has a great affinity for D, then the reaction of A C on B D produces not only C D, but also A B. As on the formation of C D, the substances A and B (previously in A C and B D) are left in a peculiar state of separation, it is supposed that their mutual combination occurs because they meet together in this *nascent state* at the moment of separation (*in statu nascendi*). Thus chlorine does not directly combine with charcoal, graphite, or the diamond, nevertheless there are compounds of chlorine with carbon and many of them are distinguished by their stability. They are obtained during the action of chlorine on hydrocarbons, as the separation products from the direct action of chlorine on hydrogen. Chlorine takes up the hydrogen, and the freed carbon at the moment of its separation enters into combination with another portion of the chlorine, so that in the end the chlorine is combined with both the hydrogen and the carbon.³⁵

³⁵ It is possible to imagine that the cause of a great many of such reactions is, that substances taken in a separate state, for instance, charcoal, present a complex molecule composed of separate atoms of carbon which are fastened together (united, as is usually said) by a considerably affinity; for atoms of the same kind, just like atoms of different kinds, possess a mutual affinity. The affinity of chlorine for carbon, although unable to break this bond asunder, may be sufficient to form a stable compound with already separate atoms of carbon. Such a view of the subject presents a hypothesis which, although dominant at present, is without sufficiently firm foundation. Were the matter

As regards those phenomena which accompany chemical action, the most important circumstance in reference to chemical mechanics is that not only do chemical processes produce a mechanical displacement (a visible disturbance), heat, light, electrical potential and current ; but that all these agents are themselves capable of changing and governing chemical transformations. This reciprocity or reversibility naturally depends on the fact that all the phenomena of nature are only different kinds and forms of visible and invisible (molecular) movement. First sound, and then light, was shown to consist of vibratory movements, as the laws of physics have proved and developed beyond a doubt. Then, the connection between heat and mechanical motion and work has ceased to be a supposition, but has become a known fact, and the mechanical equivalent of heat (424 kilogrammetres of mechanical work correspond with one kilogram unit of heat or Calorie) gives a mechanical measure for heat phenomena. Although the mechanical theory of electrical phenomena cannot be considered so fully developed as the theory of heat, nevertheless there can be no doubt but that the electrical state of substances, and electric or galvanic currents, represent a peculiar form of motion ; more especially as both statical and dynamical electricity are produced by mechanical means (in common electrical machines or in Gramme or other dynamos), and, as conversely, a current (in electric motors) can produce mechanical motion, as heat produces motion in heat (steam, gas, or air) engines. Thus by passing a current through the poles of a Gramme dynamo it may be made to revolve, and, conversely, by revolving it an electrical current is produced, which demonstrates the reversibility of electricity into mechanical motion. Therefore, chemical mechanics must look for the fundamental lines of its advancement in the correlation of chemical with physical and mechanical phenomena. But this subject, owing to its complexity and comparative novelty, has not yet been subjected to a harmonious theory, or even to a satisfactory hypothesis, and therefore we shall avoid lingering over it.

A chemical change in a certain direction is accomplished not only as simple as it appears to be, according to this hypothesis, one would expect, for instance, that the compounds of carbon with chlorine would be easily decomposable by reason of the supposed considerable affinity of the separate atoms of carbon, which should therefore tend to mutual combination and the formation of charcoal. It is evident, however, that not only does reaction itself consist of movements, but that in the compound formed (in the molecules) the elements (atoms) forming it are in harmonious stable movement (like the planets in the solar system), and this movement will affect the stability and capacity for reaction, and therefore these depend not only on the affinity of the participating substances, but also on the conditions of reaction which change the state of movement of the elements in the molecules, as well as on the nature, form, and intensity of those movements which the elements have in their given state. In a word, the mechanical side of chemical action must be exceedingly complex.

by reason of the difference of masses, the composition of the substances concerned, the distribution of their parts, and their affinity or chemical energy, but also by reason of the *conditions* under which the substances occur, and these conditions differ for every particular reaction. In order that a certain chemical reaction may take place between substances which are capable of reacting on each other, it is often necessary to have recourse to conditions which are sometimes very different from those in which the substances usually occur in nature. For example, not only is the presence of air (oxygen) necessary for the combustion of charcoal, but the latter must also be heated to redness. The red-hot portion of the charcoal burns—*i.e.*, combines with the oxygen of the atmosphere—and in doing so evolves heat, which heats the adjacent parts of charcoal, which are thus able to burn. Just as the combustion of charcoal is dependent on its being heated to redness, so also every chemical reaction only takes place under certain physical, mechanical, or other conditions. The following are the chief conditions which exert an influence on the progress of chemical reactions.

(a) *Temperature*.—Chemical reactions of combination only take place within certain definite limits of temperature, and cannot be accomplished outside these limits. As examples we may cite, not only that the combustion of charcoal begins at a red heat, but also that chlorine and salt only combine with water at a temperature below 0° . These compounds cannot be formed at a higher temperature, for they are then wholly or partially broken up into their component parts. A certain rise in temperature is necessary to start combustion. In certain cases the effect of this rise may be explained as causing one of the reacting bodies to change from a solid into a liquid or gaseous form. The transference into a fluid form facilitates the progress of the reaction, because it aids the intimate contact of the particles acting on each other. Another reason, to which must be ascribed the chief influence of heat in exciting chemical action, is that the physical cohesion, or the internal chemical union, of homogeneous particles is thereby weakened, and therefore the separation of the particles of the substances taken, and their transference into new compounds, is rendered easier. When a reaction absorbs heat—as in decomposition, where the heat is transformed into latent chemical energy—the reason why heat is necessary is self-evident.

It is most important to observe the effect of an elevation of temperature on all compounds, as there is reason to believe that they are all decomposed at a more or less high temperature. We have already seen examples of this in describing the decomposition of mercury oxide

into mercury and oxygen, and the decomposition of wood under the influence of heat. Many substances are decomposed at a very moderate temperature ; for instance, the fulminating salt which is employed in cartridges is decomposed at a little above 120° . The majority of those compounds which make up the mass of animal and vegetable matters are decomposed at 250° . On the other hand, there is reason to think that at a very low temperature no reaction whatever can take place. Thus plants cease to carry on their chemical processes during the winter. Every chemical reaction requires certain limits of temperature for its accomplishment, and, doubtless, many of the chemical changes observed by us cannot take place in the sun, where the temperature is very high, or on the moon, where it is very low.

The influence of heat on reversible reactions is particularly instructive. If, for instance, a compound which is capable of being reproduced from its products of decomposition be heated up to the temperature at which decomposition begins, the decomposition of a mass of the substance contained in a definite volume is not immediately completed. Only a certain fraction of the substance is decomposed, the other portion remaining unchanged, and if the temperature be raised, the quantity of the substance decomposed increases ; furthermore, for a given volume the ratio between the part decomposed and the part unaltered corresponds with each definite rise in temperature until it reaches that at which the compound is entirely decomposed. This partial decomposition under the influence of heat is called *dissociation*. It is possible to distinguish between the temperatures at which dissociation begins and ends. Should dissociation proceed at a certain temperature, yet should the product or products of decomposition not remain in contact with the still undecomposed portion of the compound, then decomposition will go on to the end. Thus limestone is decomposed in a limekiln into lime and carbonic anhydride, because the latter is carried off by the draught of the furnace. But if a certain mass of limestone be enclosed in a definite volume—for instance, in a gun barrel—which is then sealed up, and heated to redness, then, as the carbonic anhydride cannot escape, a certain proportion only of the limestone will be decomposed for every increment of heat (rise in temperature) higher than that at which dissociation begins. Decomposition will cease when the carbonic anhydride evolved presents a maximum *dissociation pressure* corresponding with each rise in temperature. If the pressure be increased by increasing the quantity of gas, then combination begins afresh ; if the pressure be diminished decomposition will recommence. Decomposition in this case is exactly similar to evaporation ; if the steam given off by evaporation cannot escape, its

pressure will reach a maximum corresponding with the given temperature, and then evaporation will cease. Should steam be added it will be condensed in the liquid; if its quantity be diminished—*i.e.*, if the pressure be lessened, the temperature being constant—then evaporation will go on. We shall afterwards discuss more fully these phenomena of dissociation, which were first discovered by Henri St. Claire Deville. We will only remark that the products of decomposition re-combine with greater facility the nearer their temperature is to that at which dissociation begins, or, in other words, that the initial temperature of dissociation is near to the initial temperature of combination.

(b) *The influence of an electric current*, and of electricity in general, on the progress of chemical transformations is very similar to the influence of heat. The majority of compounds which conduct electricity are decomposed by the action of a galvanic current, and there being great similarity in the conditions under which decomposition and combination proceed, combination often proceeds under the influence of electricity. Electricity, like heat, must be regarded as a peculiar form of molecular motion, and all that which refers to the influence of heat also refers to the phenomena produced by the action of an electrical current, only with this difference, that a substance can be separated into its component parts with much greater ease by electricity, as the process goes on at the ordinary temperature. The most stable compounds may be decomposed by this means, and a most important fact is then observed—namely, that the component parts appear at the different poles or electrodes by which the current passes through the substance. Those substances which appear at the positive pole (anode) are called ‘electro-negative,’ and those which appear at the negative pole (cathode, that in connection with the zinc of an ordinary galvanic battery) are called ‘electro-positive.’ The majority of non-metallic elements, such as chlorine, oxygen, &c., and also acids and substances analogous to them, belong to the first group, whilst the metals, hydrogen, and analogous products of decomposition appear at the negative pole. Chemistry is indebted to the decomposition of compounds by the electric current for many most important discoveries. Many elements have been discovered by this method, the most important being potassium and sodium. Lavoisier and the chemists of his time were not able to decompose the oxygen compounds of these metals, but Davy showed that they might be decomposed by an electric current, the metals sodium and potassium appearing at the negative pole.

(c) Certain unstable compounds are also decomposed by *the action of light*. Photography is based on this property in certain substances (for instance, in the salts of silver). The mechanical energy of those vibra-

tions which determine the phenomena of light is very small, and therefore only certain, and these generally unstable, compounds can be decomposed by light—at least under ordinary circumstances. But there is one class of chemical phenomena dependent on the action of light which forms as yet an unsolved problem in chemistry—these are the processes accomplished in plants under the influence of light. Here there take place most unexpected decompositions and combinations, which are often unattainable by artificial means. For instance, carbonic anhydride, which is so stable under the influence of heat and electricity, is decomposed, and evolves oxygen in plants under the influence of light. In other cases, light decomposes unstable compounds, such as are usually easily decomposed by heat and other agents. Chlorine combines with hydrogen under the influence of light, which shows that combination, as well as decomposition, can be determined by its action, as was likewise the case with heat and electricity.

(d) *Mechanical effects* exert, like the foregoing agents, an action both on the process of chemical combination and of decomposition. Many substances are decomposed by friction or by a blow—as, for example, the compound called iodide of nitrogen (which is composed of iodine, nitrogen, and hydrogen), and silver fulminate. Mechanical friction causes sulphur to burn at the expense of the oxygen contained in potassium chlorate.

(e) Besides the various conditions which have been enumerated above, the progress of chemical reactions is accelerated or retarded by the *condition of contact* in which the reacting bodies occur. Other conditions remaining constant, the rate of progress of a chemical reaction is accelerated by increasing the number of points of contact. It will be enough to point out the fact that sulphuric acid does not absorb ethylene under ordinary conditions of contact, but only after continued shaking, by which means the number of points of contact is greatly increased. To ensure full action between solids, it is necessary to reduce them to very fine powder and to mix them as thoroughly as possible, as by this means their reaction is greatly accelerated. M. Spring, the Belgian chemist, has shown that finely-powdered solids which do not react on each other at the ordinary temperature may undergo reaction under an increased pressure. Thus, under a pressure of 6,000 atmospheres, sulphur combines with many metals at the ordinary temperature, and the powders of many metals form alloys. It is evident that an increase in the number of points or surfaces must be regarded as the chief cause producing reaction, which is doubtless accomplished in solids, as in liquids and gases, in virtue of an internal movement or mobility of the particles, which movement, although in different degrees

and forms, must exist in all the states of matter. It is very important to direct attention to the fact that the internal movement or condition of the parts of the particles of matter must be different on the surface of a substance from what it is inside ; because in the interior of a substance similar particles are acting on all sides of every particle, whilst at the surface they only act on one side. Therefore, the condition of a substance at its surfaces of contact with other substances must be more or less modified by them—it may be in a manner similar to that caused by an elevation of temperature. These considerations throw some light on the action in the large class of *contact reactions* ; that is, such as seem to proceed from the mere presence (contact) of certain special substances. Porous or powdery substances are very prone to act in this way, especially spongy platinum and charcoal. For example, sulphurous anhydride does not combine directly with oxygen, but this reaction takes place in the presence of spongy platinum.⁵⁶

The above general and introductory chemical conceptions cannot be thoroughly grasped in their true sense without a knowledge of the particular facts of chemistry to which we shall now turn our attention. It was, however, absolutely necessary to become acquainted on the very threshold with such fundamental principles as the laws of the indestructibility of matter and of the conservation of energy, as it is only by their acceptance, and under their direction and influence, that the examination of particular facts can give practical and fruitful results.

⁵⁶ Contact phenomena are separately considered in detail in the work of Professor Konovaloff (1884). In my opinion, one must consider that the state of the internal movements of the atoms in molecules is modified at the points of contact of substances, and this state determines chemical reactions, and therefore, that reactions of combination, decomposition, and rearrangement are accomplished by contact. Professor Konovaloff showed that a number of substances under certain conditions of their surfaces act by contact ; for instance, powdery silica (from the hydrate) acts just like platinum, decomposing certain compound ethers. As reactions are only accomplished under close contact, it is probable that those modifications in the distribution of the atoms in molecules which come about by contact phenomena prepare the way for them. By this the rôle of contact phenomena is considerably extended. By such phenomena the fact should be explained why a mixture of hydrogen and oxygen yields water (explodes) at different temperatures according to the kind of heated substance which transmits this temperature. In chemical mechanics, phenomena of this kind have great importance, but as yet they have been but little studied.

CHAPTER I

ON WATER AND ITS COMPOUNDS

WATER is found almost everywhere in nature, and in all three physical states. As vapour, water occurs in the atmosphere, and in this form it is distributed over the entire surface of the earth. The vapour of water in condensing, by cooling, forms snow, rain, hail, dew, and fog. One cubic metre (or 1,000,000 cubic centimetres, or 1,000 litres, or 35·316 cubic feet) of air can contain at 0° only 4·8 grams of water, at 20° about 17·0 grams, at 40° about 50·7 grams; but ordinary air only contains about 60 per cent. of the possible moisture. Air containing less than 40 per cent. of the possible moisture is felt to be dry, and air which contains more than 80 per cent. of the possible moisture is considered as already damp.¹ Water in the liquid state, in falling as rain

¹ In practice, the chemist has to continually deal with gases, and gases are often collected over water; in which case a certain amount of water passes into vapour, and this vapour mingles with the gases. It is therefore most important that he should be able to calculate the amount of water or of *moisture in air and other gases*. Let us consider the relations in volume and weight which exist in this case. Let us imagine a cylinder standing in a mercury bath, and filled with a dry gas whose volume equals v , temperature t° , and pressure or tension h mm. (h millimetres of the column of mercury at 0°). We will introduce water into the cylinder in such a quantity that a small part remains in the liquid state, and consequently that the gas will be saturated with aqueous vapour; the volume of the gas will then increase (if a larger quantity of water be taken some of the gas will be dissolved in it, and the volume may therefore be diminished). We will further suppose that the temperature remains constant after the addition of the water; then the pressure (as the volume increases the mercury in the cylinder falls, consequently the pressure is increased) and the volume is increased. In order to investigate the phenomenon we will artificially increase the pressure, and reduce the volume to the original volume v . Then the pressure or tension will prove greater than h , namely $h+f$, which means that by the introduction of aqueous vapour the tension of the gas is increased. The researches of Dalton, Gay-Lussac, and Regnault showed that this increase is equal to the maximum pressure which is proper to the aqueous vapour at the temperature at which the observation is made. The maximum pressure for all temperatures may be found in the tables made from observations on the tension of aqueous vapour. The quantity f will be equal to this maximum pressure of aqueous vapour. This may be expressed thus: the maximum tension of aqueous vapour (and of all other vapours) saturating a space in a vacuum or in any gas is the same. This rule is known as *Dalton's law*. Thus we have a volume of dry gas v , under a pressure h , and a volume of moist gas, saturated with vapour, under a pressure $h+f$. The volume v of the dry gas under a pressure $h+f$ occupies, according to the law of Mariotte, a

and snow, soaks into the soil and collects together into springs, lakes, rivers, seas, and oceans. It is absorbed from the soil by the roots of

volume $\frac{vh}{h+f}$; consequently the volume occupied by the aqueous vapour under the pressure $h+f$ equals $v - \frac{vh}{h+f}$, or $\frac{vf}{h+f}$. Thus the volumes of the dry gas and of the moisture which occurs in it, at a pressure $h+f$, are in the ratio $f:h$. And, therefore, if the aqueous vapour saturates a space at a pressure n , the volumes of the dry air and of the moisture which is contained in it are in the ratio $n-f:f$, where f is the pressure of the vapour according to the tables of vapour tension. Thus, if a volume N of a gas saturated with moisture be measured at a pressure H , then the volume of the gas, when dry, will be equal to $N \frac{H-f}{H}$, because the volume N requires to be divided into parts which are in the ratio $H-f:f$. In fact, the entire volume N must be to the volume of dry gas x as H is to $H-f$; therefore, $N:x = H:H-f$, from which $x = N \frac{H-f}{H}$. Under any other pressure—for instance, 760 mm.—the volume of dry gas will be $x \frac{H-f}{760}$, or $\frac{H-f}{760}$

and thus we obtain the following practical rule: If a volume of a gas saturated with aqueous vapour be measured at a pressure H mm., then the volume of dry gas contained in it will be obtained by finding the volume corresponding with the pressure H , less the pressure due to the aqueous vapour at the temperature of observation. For example, 37.5 cubic centimetres of air saturated with aqueous vapour was measured at a temperature of 15.3° , and under a pressure of 747.3 mm. of mercury (at 0°). What will be the volume of dry gas at 0° and 760 mm.? The pressure of aqueous vapour corresponding with 15.3° is equal to 12.9 mm., and therefore the volume of dry gas at 15.3° and 747.3 mm. is equal to $37.5 \times \frac{747.3 - 12.9}{747.3}$; at 760 mm. it will be equal to $37.5 \times \frac{734.4}{760}$; and at 0° the volume of dry gas will be $37.5 \times \frac{734.4}{760} \times \frac{273}{273 - 15.3} = 34.31$ c.c.

From this rule may also be calculated what fraction of a volume of gas is occupied by moisture under the ordinary pressure at different temperatures; for instance, at 30° C $f=31.5$, consequently 100 volumes of a moist gas or air, at 760 mm., contain a volume of aqueous vapour $100 \times \frac{31.5}{760}$, or 4.110; also it is found that at 0° there is contained 0.61 p.c. by volume, at 10° 1.21 p.c., at 20° 2.29 p.c., and at 50° up to 12.11 p.c. From this it may be judged how great an error might be made in the volumetric determination of gases were the moisture not taken into consideration. From this it is also evident how great are the variations in volume of the atmosphere when it loses or gains aqueous vapour, which again explains a number of atmospheric phenomena (winds, variation of pressure, precipitations, storms, &c.).

If aqueous vapour does not saturate a gas, then it is indispensable that the degree of moisture should be known in order to determine the volume of dry gas from the volume of moist gas. The preceding ratio gives the maximum quantity of water which can be held in a gas, and the degree of moisture shows what fraction of this maximum quantity occurs in a given case, when the vapour does not saturate the space occupied by the gas. Consequently, if the degree of moisture equals 50 p.c.—that is, half the maximum—then the volume of dry gas at 760 mm. is equal to the volume of dry gas at 760 mm. multiplied by $\frac{h-0.5f}{760}$, or, in general, by $\frac{h-rf}{760}$, where r is the degree of moisture. If, therefore, it is required to measure the volume of a moist gas, it must either be entirely dried or quite saturated with moisture, or else the degree of moisture determined. The first and last methods are inconvenient, and therefore recourse is usually had to the second. For this purpose water is introduced into the cylinder holding the gas to be measured; it is left for a certain time so that the gas may become saturated,

plants, which, when fresh, contain from 40 to 80 per cent. of water by weight. Animals contain about the same amount of water. In a

the precaution being taken that a portion of the water remains in a liquid state; then the volume of the moist gas is determined, from which that of the dry gas may be calculated. In order to find the *weight of the aqueous vapour* in a gas it is necessary to know the weight of a cubic measure at 0° and 760 mm. Knowing that one cubic centimetre of air under these circumstances weighs 0.001293 gram, and that the density of aqueous vapour is 0.62, we find that one cubic centimetre of aqueous vapour at 0° and 760 mm. weighs 0.0008 gram, and at a temperature t° and pressure h the weight of one cubic centimetre will be $0.0008 \times \frac{h}{760} \times \frac{273}{273+t}$. We already know that v volumes of a gas

at a temperature t° pressure h contain $v \times \frac{f}{h}$ volumes of aqueous vapour which saturate it, therefore the weight of the aqueous vapour held in v volumes of a gas will be $\frac{v \times f}{h} \times 0.0008 \times \frac{h}{760} \times \frac{273}{273+t}$, or $v \times 0.0008 \times \frac{f}{760} \times \frac{273}{273+t}$.

Consequently, the weight of the water which is held in one volume of a gas is only dependent on the temperature and not on the pressure. This also signifies that evaporation proceeds to an equal extent in air as in a vacuum, or, in general terms (this is *Dalton's law*), vapours and gases diffuse into each other as if into a vacuum. In a given space there enters, at a given temperature, a constant quantity of vapour whatever be the pressure of the gas filling that space. If the degree of moisture equals r then the weight of the vapour in v cubic centimetres will be $p = v \times 0.0008 \times \frac{fr}{760} \times \frac{273}{273+t}$ grams.

From this it is clear that if the weight of the vapour held in a given volume of a gas be known, it is easy to determine the degree of moisture $r = \frac{p}{v \times 0.0008} \times \frac{760}{t} \times \frac{273+t}{273}$.

On this is founded the very exact determination of the degree of moisture of air by the weight of water contained in a given volume. It is easy to calculate from the preceding formula the number of grams of water contained at all pressures in one cubic metre or million centimetres of air saturated with vapour at various temperatures; for example, at 80° $f = 31.5$, therefore $p = 1000000 \times 0.0008 \times \frac{31.5}{760} \times \frac{273}{273+80}$ or 29.84 grams.

The laws of Mariotte, Dalton, and Gay-Lussac, which are here applied to gases and vapours, are not entirely exact, but are approximately true. Were they quite exact, a mixture of several liquids, having a certain vapour pressure, would be able to give vapours of a very great pressure, which is not the case. In fact the pressure of aqueous vapour is slightly less in a gas than in a vacuum, and the weight of aqueous vapour held in a gas is slightly less than it should be according to Dalton's law, as was shown by the experiments of Regnault and others. This means that the tension of the vapour is less in air than in a vacuum, which also is the reason why the weight of vapour is less than the theoretical weight. The difference between the pressure of vapours in air and in a vacuum does not, however, exceed $\frac{1}{10}$ of the total pressure of the vapours, and therefore in practice the application of Dalton's law may be followed. This *decrement in vapour tension* which occurs in the intermixture of vapours and gases, although small, indicates that there is then already, so to speak, a beginning of chemical change. The essence of the matter is that in this case there occurs as on contact (see preceding footnote) an alteration in the movements of the atoms in the molecules, and therefore also a change in the movement of the molecules themselves.'

In the uniform intermixture of air and other gases with aqueous vapour, and in the capacity of water to pass into vapour and form a uniform mixture with air, we may perceive an instance of a physical phenomenon which is analogous to chemical phenomena, forming indeed a transition from one class of phenomena to the other. Between water and dry air there exists a kind of affinity which obliges the water to saturate the

solid state water appears as snow, ice, or in an intermediate form between these two, which is seen on mountains covered with perpetual snow. The water of rivers,² springs, oceans and seas, lakes, and wells air. But such a homogeneous mixture is formed (almost) independently of the nature of the gas in which evaporation takes place; even in a vacuum the phenomenon occurs in exactly the same way as in a gas, and therefore it is not the property of the gas, nor its relation to water, but the property of the water itself, which obliges it to evaporate, and therefore in this case chemical affinity is not yet acting—at least its action is not clearly pronounced. That it does, however, play a certain part is seen from the deviation from Dalton's law.

² In falling through the atmosphere, water dissolves the gases of the atmosphere, nitric acid, ammonia, organic compounds, salts of sodium, magnesium, and calcium, and mechanically washes out a mixture of dust and microbes which are suspended in the atmosphere. The amount of these and certain other constituents is very variable. Even in the beginning and end of the same rainfall, a variation which is often very considerable may be remarked. Thus, for example, Bunsen found that rain collected at the beginning of a shower contained 3·7 grams of ammonia per cubic metre, whilst that collected at the end of the same shower contained only 0·64 gram. The water of the entire shower contained an average of 1·47 grams of ammonia per cubic metre. In the course of a year rain supplies an acre of ground with up to 5½ kilos of nitrogen in a combined form. Marchand found in one cubic metre of snow water 15·63, and in one cubic metre of rain water 10·07, grams of sodium sulphate. Angus Smith showed that after a thirty-hours' fall at Manchester the rain still contained 34·3 grams of salts per cubic metre. A considerable amount of organic matter, namely 25 grams per cubic metre, has been found in rain water. The total amount of solid matter in rain water reaches 50 grams per cubic metre. Rain water contains generally very little carbonic acid, whilst stream water contains a considerable quantity of it. In considering the nourishment of plants, it is necessary to keep in view the substances which are carried into the soil by rain.

River water, which is accumulated from springs and sources fed by atmospheric water, contains from 50 to 1,600 parts by weight of salts in 1,000,000 parts. The amount of solid matter, per 1,000,000 parts by weight, contained in the chief rivers is as follows:—the Don 124, the Loire 135, the St. Lawrence 170, the Rhone 182, the Dnieper 187, the Danube from 117 to 234, the Rhine from 158 to 317, the Seine from 190 to 432, the Thames at London from 400 to 450, in its upper parts 387, and in its lower parts up to 1,617, the Nile 1,580, the Jordan 1,052. The Neva is characterised by the remarkably small amount of solid matter it contains. From the investigations of Prof. G. K. Trupp, a cubic metre of Neva water contains 32 grams of incombustible and 23 grams of organic matter, or altogether about 55 grams. This is one of the purest waters which is known in rivers. The large amount of impurities in river water, and especially of organic impurity produced by pollution with putrid matter, makes the water of many rivers unfit for use.

The chief part of the soluble substances in river water consists of the calcium salts. 100 parts of the solid residues contain the following amounts of calcium carbonate—from the water of the Loire 53, from the Thames about 50, the Elbe 55, the Vistula 65, the Danube 65, the Rhine from 55 to 75, the Seine 75, the Rhone from 82 to 94. The Neva contains 40 parts of calcium carbonate per 100 parts of saline matter. The considerable amount of calcium carbonate held by stream water is very easily explained from the fact that water which contains carbonic acid in solution easily dissolves calcium carbonate, which occurs all over the earth. Besides calcium carbonate and sulphate, river water contains magnesium, silica, chlorine, sodium, potassium, aluminium, nitric acid, and manganese. The presence of salts of phosphoric acid has not yet been determined with exactitude for all rivers, but the presence of nitrates has been proved with certainty in almost all kinds of well-investigated river water. The quantity of calcium phosphate does not exceed 0·4 gram in the river of the Dnieper, and the Don does not contain more

contains various substances in solution, mostly salts—that is, substances resembling common table salt in their physical properties and

than 5 grams. The water of the Seine contains about 15 grams of nitrates, and the Rhone about 8 grams. The amount of ammonia is much less; thus in the water of the Rhine about 0.5 gram in June, and 0.2 gram in October; the water of the Seine contains the same amount. This is less than in rain water. Notwithstanding this insignificant quantity, the water of the Rhine alone, which is not so very large a river, carries 16,245 kilograms of ammonia into the ocean every day. The difference between the amount of ammonia in rain and river water depends on the fact that the soil through which the rain water passes is able to withhold the ammonia. (Soil can also absorb many other substances, such as phosphoric acid, potassium salts, &c.)

The water of springs, rivers, wells, and in general of those localities from which it is taken for drinking purposes, may be very injurious to the health if it contains much organic pollution—all the more, as in such water the lower organisms (bacteria) may rapidly develop, and these organisms often serve as the carriers or causes of infectious diseases. Thanks to the work of Pasteur, Koch, and many others, this province of research has made considerable progress during the past ten years, and has shown the possibility of investigating even the number and properties of the germs held by water, because those pathogenic bacteria which produce sickness, such as typhoid fever, Siberian plague, &c., have been distinguished. In bacteriological researches, a gelatinous medium, enabling the germs to develop and multiply, is prepared with gelatin and water, which has previously been heated several times, at intervals, to 100° (it is thus rendered sterile—that is to say, all the germs in it are killed). The water to be investigated is added to this prepared medium in a definite and small quantity (it is sometimes diluted with sterilised water to facilitate the calculation of the number of germs), it is protected from dust (which contains germs), and is left at rest until whole families of lower organisms are developed from each germ. These families (colonies) are visible to the naked eye (as spots), they may be counted, and by examining them under the microscope and observing the number of organisms they produce, their significance may be determined. The majority of bacteria are harmless, but there decidedly are pathogenic bacteria whose presence is one of the causes of malady, and of the spreading of certain diseases. The number of bacteria in one cubic centimetre of water sometimes attains the immense figures of hundreds of thousands and millions. Certain well, spring, and river waters contain very few bacteria, and are free from disease-producing bacteria under ordinary circumstances. By boiling water, the bacteria in it are killed, but the organic matter necessary for their nourishment remains in the water. The best kinds of water for drinking purposes do not contain more than 300 bacteria in a cubic centimetre.

The presence in water of every residue of destroyed organisms may be partly judged from the amount of combined nitrogen, as all organisms contain nitrogen compounds. It is most essential to distinguish and determine nitrogen in the form of organic matter, and in the form of oxides (nitric acid). The former is not separated, on heating, from water by the action of reducing agents, such as sulphurous anhydride, whilst the nitrogen which occurs as oxide is evolved by this means. Thus on adding hydrochloric acid and ferrous chloride to water, the nitrogen of the nitric acid gives oxide of nitrogen, which may be determined. The presence of nitric acid indicates that the organic matter in water has already been oxidised. Water which contains more than 1 part of nitrogen (in this form) in a million parts is considered as injurious, and should not be used. Frankland found about 1.8 parts of nitrogen in an oxidised form, and from 0.22 to 0.5 part in organic combinations in the water of the Thames at London.

The amount of gases dissolved in river water is much more constant than that of its solid constituents. One litre, or 1,000 c.c., of water contains 40 to 55 c.c. of gas measured at normal temperature and pressure. In winter the amount of gas is greater than in summer or autumn. Allowing that a litre contains 50 c.c. of gases, it may be admitted that these consist, on the average, of 20 vols. of nitrogen, 20 vols. of carbonic

chief chemical transformations. Further, the quantity and nature of these salts differ in different waters.³ Everybody knows that there

anhydride (proceeding in all likelihood from the soil and not from the atmosphere), and of 10 vols. of oxygen. If the total amount of gases be less, the constituent gases are still in about the same proportion; in many cases, however, carbonic anhydride predominates. The water of many deep and rapid rivers contains less carbonic anhydride, which shows their rapid formation from atmospheric water and that they have not succeeded, during a long and slow course, in absorbing a greater quantity of carbonic anhydride. Thus, for instance, the water of the Rhine, near Strasburg, according to Deville, contains 8 c.c. of carbonic anhydride, 16 c.c. of nitrogen, and 7 c.c. of oxygen per litre. From the researches of Prof. M. R. Kapoustin and his pupils, it appears that in determining the quality of a water for drinking purposes, it is most important to investigate the composition of the dissolved gases.

⁵ *Spring water* is formed from rain water percolating through the soil. Naturally a part of the rain water is evaporated straightway from the surface of the earth and from the vegetation on it. It has been shown that out of 100 parts of water falling on the earth only 36 parts flow to the ocean; the remaining 64 are evaporated, or percolate far underground. The collection of water by means of ponds, common wells, or artesian wells is dependent on the presence of subterranean water. After flowing underground along some impervious strata, water comes out at the surface in many places as springs, whose temperature is determined by the depth from which the water has flowed. Springs penetrating to a great depth may become considerably heated, and this is why hot mineral springs, with a temperature of up to 80° and higher, are often met with. For instance, there is one Caucasian spring whose temperature is 90°. Most likely in this case the water is heated owing to its penetrating near a rock formation which is heated by volcanic action. The composition of spring water is most varied. When a spring water contains substances which endow it with a peculiar taste, and especially if these substances are such as are only found in minute quantities or not at all in river and other flowing waters, then the spring water is termed a *mineral water*. Many such waters are employed for medicinal purposes. Mineral waters are classed according to their composition into—(a) saline waters, which often contain a large amount of common salt; (b) alkaline waters, which contain sodium carbonate; (c) bitter waters, which contain magnesia; (d) chalybeate waters, which hold iron carbonate in solution; (e) aerated waters, which are rich in carbonic anhydride; (f) sulphuretted waters, which contain hydrogen sulphide. Sulphuretted waters may be recognised by their smell of rotten eggs, and by their giving a black precipitate with lead salts, and also by their tarnishing silver objects. Aerated waters, which contain an excess of carbonic anhydride, effervesce in the air, have a sharp taste, and redden litmus paper. Saline waters leave a large residue of soluble solid matter on evaporation, and have a salt taste. Chalybeate

	Calcium salts	Sodium chloride	Sodium sulphate	Sodium carbonate	Potassium iodide and bromide	Other Potassium salts	Iron carbonate	Magnesium salts	Silica	Carbonic anhydride	Sulphuretted hydrogen	Total solid contents
I.	1,928	—	152	—	—	24	—	448	152	1,300	80	2,609
II.	816	386	1,239	26	—	43	9	257	46	1,485	—	2,812
III.	1,085	1,430	1,105	—	4	90	—	187	65	1,326	11	3,950
IV.	343	3,783	16	3,431	—	14	—	251	112	2,883	—	7,950
V.	3,406	15,049	—	—	2	—	17	1,587	229	—	76	20,290
VI.	352	3,145	—	95	35	50	1	260	11	20	—	3,970
VII.	308	1,036	2,583	1,261	—	—	4	178	75	—	—	5,451
VIII.	1,726	9,480	—	—	40	120	26	208	40	—	—	11,790
IX.	551	2,040	1,150	999	—	1	30	209	50	2,740	—	4,070
X.	285	558	279	3,813	—	—	7	45	45	2,268	—	5,031
XI.	340	910	Iron and aluminium sulphates :					1,020 1,660	940	190	2,550 330	(Sulphuric and hydrochloric acids)

are salt, fresh, iron, and other waters. The presence of about $3\frac{1}{2}$ per cent. of salts renders sea-water ⁴ heavy and bitter to the taste. Fresh water also contains salts, only in a comparatively small quantity. Their presence may be easily proved by simply evaporating water in a vessel. By evaporation the water passes away as vapour, whilst the salts are left behind. This is why a crust (incrustation), consisting of salts, previously in solution, is deposited on the insides of kettles or boilers, and other vessels in which water is boiled. Running water (rivers, &c.) is charged with salts, owing to its being formed from the collection of rain water percolating through the soil. While percolating the water dissolves certain parts of the soil. Thus water which filters or passes through saline or calcareous soils becomes charged with salts or contains calcium carbonate (chalk). Rain water and snow are much purer than river or spring water. This is because snow and rain are only condensed aqueous vapour, and salts do not pass into the vapour.

waters have an inky taste, and are coloured black by an infusion of galls; on being exposed to the air they usually give a brown precipitate. Generally, the character of mineral waters is mixed. In the table on page 45 are given the analysis of certain mineral springs which are known for their medicinal properties. The quantity of the substances is expressed in millionths by weight—that is, in grams per cub. metre or milligrams per litre.

I. Sergieffsky, a sulphur water, Gov. of Samara (temp. 8° C.), analysis by Clause. II. Geléznovodskya water source No. 10, near Patigorsk, Caucasus (temp. 22.5°), analysis by Fritzsche. III. Aleksandroffsky, alkaline-sulphur source, Patigorsk (temp. 46.5°), average of analyses by Herman Zinin and Fritzsche. IV. Bougountouksky, alkaline source, No. 17, Essentoukah, Caucasus (temp. 21.6°), analysis by Fritzsche. V. Saline water, Staro-Russi, Gov. of Novgorod, analysis by Nelubin. VI. Water from artesian well at the factory of state papers, St. Petersburg, analysis by Struve. VII. Sprüdel, Carlsbad (temp. 83.7°), analysis by Berzelius. VIII. Krütznach spring (Elisenquelle), Prussia (temp. 8.8°), analysis by Bauer. IX. Eau de Seltz, Nassau, analysis by Henry. X. Vichy water, France, analysis by Berthier and Puvy. XI. Paramo de Ruiz, New Granada, analysis by Levy; it is distinguished by the amount of free acids.

⁴ *Sea-water* contains more non-volatile saline constituents than the usual kinds of fresh water. This is explained by the fact that the waters flowing into the sea supply it with salts, and whilst a large quantity of vapour is given off from the surface of the sea, the salts remain behind. Even the specific gravity of sea-water differs considerably from that of pure water. It is generally about 1.02, but in this and also in respect to the amount of salts contained, samples of sea-water from different localities and from different depths offer rather remarkable variations. It will be sufficient to point out that one cubic metre of water from the undermentioned localities contains the following quantity in grams of solid constituents:—Gulf of Venice 19,122, Leghorn Harbour 24,312, Mediterranean, near Cetta, 37,655, the Atlantic Ocean from 32,585 to 35,695, the Pacific Ocean from 35,233 to 34,708. In closed seas which do not communicate, or are in very distant communication, with the ocean, the difference is often still greater. Thus the Caspian Sea contains 6,300 grams; the Black Sea and Baltic 17,700. Common salt forms the chief constituent of the saline matter of sea- or ocean-water; thus in one cubic metre of sea-water there are 25,000–31,000 grams of common salt, 2,600–6,000 grams of magnesium chloride, 1,200–7,000 grams of magnesium sulphate, 1,500–6,000 grams of calcium sulphate, and 10–700 grams of potassium chloride. The small amount of organic matter and of the salts of phosphoric acid in sea-water is very remarkable.

Nevertheless, in passing through the atmosphere, rain and snow succeed in catching the dust held in it, and dissolve air, which is found in every water. The dissolved gases of the atmosphere are partly disengaged, as bubbles from water on heating, and water after long boiling is quite freed from them.

In general terms water is called pure when it is clear and free from insoluble particles held in suspension and visible to the naked eye, from which it may be freed by filtration through charcoal, sand, or porous (natural or artificial) stones, and when it possesses a clean fresh taste. It depends on the absence of any tastable, decomposing organic matter, on the quantity of air⁵ and atmospheric gases in solution, and on the presence of mineral substances to the amount of about 300 grams per ton (or cubic metre, or, what is the same, 300 milligrams to a kilogram or litre of water), and of not more than 100 grams of organic matter.⁶ Such water is suitable for drinking and every practical

⁵ The taste of water is greatly dependent on the quantity of dissolved gases it contains. On boiling, these gases are given off, and it is well known that, even when cooled, boiled water has, until it has succeeded in absorbing gaseous substances from the atmosphere, quite a different taste from fresh water containing a considerable amount of gas. The dissolved gases, especially oxygen and carbonic anhydride, have an important influence on the health. The following instance is very instructive in this respect. The Grenelle artesian well at Paris, at the first period of its opening, supplied a water which had an injurious effect on animals and people. It appeared that this water did not contain oxygen, and in general was very poor in gases. As soon as it was made to fall in a cascade, by which it absorbed air, it proved entirely fit for consumption. In long sea voyages by steamer sometimes fresh water is not taken or only taken in a small quantity because it spoils by keeping, and becomes putrid from the organic matter it contains undergoing decomposition. Fresh water may be obtained directly from sea-water by distillation. The distilled water no longer contains sea salts, and is therefore fit for consumption, but it is very tasteless and has the properties of boiled water. In order to render it palatable certain salts, which are usually held in fresh water, are added to it, and it is made to flow in thin streams exposed to the air in order that it may become saturated with the component parts of the atmosphere—that is, absorb gases.

⁶ *Hard water* is such as contains much mineral matter, and especially a large proportion of calcium salts. Such water, owing to the amount of lime it contains, does not form a lather with soap, prevents vegetables boiled in it from softening properly, and forms a great deal of incrustation on vessels in which it is boiled. Owing to its high degree of hardness, it is injurious for drinking purposes, which is evident from the fact that in many large cities the death-rate decreased after introducing a soft water in the place of a hard water. *Putrid water* contains a considerable quantity of decomposing organic matter, chiefly vegetable, but in populated districts, especially in towns, chiefly animal remains. Such water acquires an unpleasant smell and taste, by which stagnant bog water and the water of certain wells in inhabited districts are particularly characterised. Such water is especially harmful at a period of epidemic. It may be partially purified by passing through charcoal, which retains the putrid and certain organic substances, and also certain mineral substances. Turbid water may be purified to a certain extent by the addition of alum, which aids, after standing some time, the formation of a sediment. Condry's fluid (potassium permanganate) is another means for purifying putrid water. A solution of this substance, even if very diluted, is of a red colour; on adding it to a putrid water, the permanganate oxidises and destroys the organic matter. When added to water in such a quantity as to impart to it an almost imperceptible rose

application, but evidently it is not pure in a chemical sense. A *chemically pure water* is necessary not only for scientific purposes, as an independent substance having constant and definite properties, and as the chief component of all forms of water which play such an important part in nature, but also for many practical purposes—for instance, in photography and in the preparation of medicines—because many properties of substances in solution are changed by the impurities of natural waters. Water is usually purified by distillation, because the solid substances in solution are not transformed into vapours in this process. Such *distilled water* is prepared by chemists and in laboratories by boiling water in closed metallic boilers or stills, and causing the steam produced to pass into a condenser—that is, through tubes (which should be made of tin, or, at all events, tinned, as water and its impurities do not act on tin) surrounded by cold water, and in which the steam, being cooled, condenses into water which is collected⁷ in a

colour it destroys much of the organic substances it contains. It is especially salutary to add a small quantity of Condyl's fluid to impure water in times of epidemic.

The presence in water of one gram per litre, or 1,000 grams per cubic metre, of any substance whatsoever renders it unfit and even injurious for consumption by animals, and this whether organic or mineral matter predominate. The presence of 1 p.c. of chlorides makes water quite salt, and produces thirst instead of assuaging it. The presence of magnesium salts is most unpleasant; they have a disagreeable bitter taste, and in fact impart to sea water its peculiar taste. A large amount of nitrates is only found in impure water, and is usually injurious, as they may indicate the presence of decomposing organic matter.

⁷ Distilled water may be prepared, or distillation in general carried on, either in a




FIG. 4.—Distillation by means of a metallic still. The liquid in C is heated by the fire F. The vapours rise through the head A and pass by the tube T to the worm S placed in a vessel R, through which a current of cold water flows by means of the tubes D and P.

receiver. By standing exposed to the atmosphere, however, the water in time absorbs air, and dust carried in the air, and ceases to be entirely pure. However, the amount of impurities in distilled water is so small that they have hardly any effect on the properties of the water, and it is fit for many purposes. Nevertheless, in distillation, water retains, besides air, a certain quantity of volatile impurities (especially organic) and the walls of the distillation apparatus are partly corroded by the water, and a portion, although small, of their substance renders the water not entirely pure, thus a sediment is obtained on evaporation.⁸

Still, for certain physical and chemical researches it is necessary to have completely pure water. To obtain it a solution of potassium permanganate is added to distilled water until it all becomes tinted light rose colour. By this means the organic matter in the water is destroyed (converted into gases or non-volatile substances). An excess

metal still with worm condenser (fig. 4), or on a small scale in the laboratory in a glass retort (fig. 5) heated by a lamp (see footnote 19, Introduction). Fig. 5 illustrates the main parts of the usual glass laboratory apparatus used for distillation. The steam




FIG. 5.—Distillation from a glass retort. The neck of the retort fits into the inner tube of the Liebig's condenser. The space between the inner and outer tube of the condenser is filled with cold water, which enters by the tube *g* and flows out at *f*.

issuing from the retort (on the right-hand side) passes through a glass tube surrounded by a larger tube, through which a stream of cold water passes, by which the steam is condensed and trickles into a receiver (on the left-hand side).

⁸ One of Lavoisier's first memoirs (1770) referred to this question. He investigated the formation of the earthy residues in the distillation of water in order to prove whether it was possible, as was affirmed, to convert water into earth, and he found that the residue was produced by the action of water on the walls of the vessel holding it, and not from the water itself. He proved this to be the case by direct weighing.

of potassium permanganate does no harm, because in the next distillation it is left behind in the distillation apparatus. The next distillation should then be from a platinum retort with a platinum receiver. Platinum is a metal which is not in any way changed either by air or water, and therefore nothing passes from it into the water. The water obtained in the receiver still contains air. It must then be boiled for a long time, and afterwards cooled in a vacuum under the receiver of an air pump. Pure water on evaporation does not give any sediment, does not in the least change, however long it be kept, and if air have no access to it does not putrefy like water only once distilled or impure; and it does not give bubbles of gas on heating, nor does it change the colour of a solution of potassium permanganate. These are a few signs by which the complete purity of water may be recognised.

Water, purified as above described, has constant *physical* and *chemical properties*. For instance, it is of such water only that one cubic centimetre weighs one gram at 4° C. *-i.e.*, it is only such pure water whose specific gravity equals 1 at 4° C.⁹ Water in a solid state forms crystals of the hexagonal system¹⁰ which are seen in snow, which

⁹ Taking the generally-accepted specific gravity of water at its greatest density—*i.e.* at 4° as 1—it has been shown by experiment that the specific gravity of water at different temperatures is as follows:—

At	—	5°	.	.	.	0.99929	At	30	.	.	.	0.99577
„		0°	.	.	.	0.99987	„	40°	.	.	.	0.99236
„	+	10°	.	.	.	0.99974	„	50°	.	.	.	0.98817
„		15°	.	.	.	0.99916	„	80°	.	.	.	0.97192
„		20°	.	.	.	0.99826	„	100°	.	.	.	0.95854

Water at 4° is taken as the basis for reducing measures of length to measures of weight and volume. The *metric, decimal, system* of measures of weights and volumes is generally employed in science. The starting point of this system is the metre (39.37 inches) divided into decimetres (=0.1 metre), centimetres (=0.01 metre), millimetres (=0.001 metre), and micrometres (=one millionth of a metre). A cubic decimetre is called a *litre*, and is used for the measurement of volumes. The weight of a litre of water at 4° in a vacuum is called a kilogram. One thousandth part of a kilogram, or one cubic centimetre, of water weighs one *gram*. It is divided into decigrams, centigrams, and milligrams (=0.001 gram). An English pound equals 453.59 grams. The great advantage of this system is that it is a decimal one, and that it is universally adopted in science and in most international relations. *All the measures cited in this work are metrical.* The units most often used in science are:—Of length, the centimetre; of weight, the gram; of time, the second; of temperature, the degree Celsius or Centigrade.

¹⁰ As solid substances appear in independent, regular, crystalline forms which are dependent, judging from their cleavage or lamination (in virtue of which mica breaks up into laminae and Iceland spar, &c., into pieces bounded by faces inclined to each other at angles which are definite for each substance), on an inequality of attraction (cohesion hardness) in different directions which intersect at definite angles; therefore, the determination of crystalline forms offers one of the most important external marks

generally consists of star-like clusters of several crystals, and also in the half-melted scattered ice floating on rivers in spring time. At characterising separate, definite chemical compounds. The elements of crystallography which comprise a special science, should therefore be familiar to all who desire to work




FIG. 6.—Example of the form belonging to the regular system. Combination of an octahedron and a cube. The former predominates. Alum, fluor spar, suboxide of copper, and others.




FIG. 7.—Rhombic Dodecahedron of the regular system. Garnet.




FIG. 8.—Hexagonal prism terminated by hexagonal pyramids. Quartz, &c.




FIG. 9.—Rhombohedron, Calc spar, &c.




FIG. 10.—Rhombic system. Desmine.




FIG. 11.—Triclinic pyramid.




FIG. 12.—Triclinic system. Albite, &c.

in scientific chemistry. In this work we shall only have occasion to speak of a few crystalline forms, some of which are shown in Figs. 6 to 12.

this time of the year the ice splits up into spars or prisms, bounded by angles proper to substances crystallising in the hexagonal system. The temperatures at which water passes from one state to another are taken as fixed points on the thermometer scale; namely, the zero corresponds with the temperature of melting ice, and the temperature of the steam disengaged from water boiling at the normal barometer pressure (that is 760 millimetres measured at 0° , at the latitude of 45° , at the sea level) is taken as 100° of the Celsius scale. Thus, the fact that water liquefies at 0° and boils at 100° is taken as one of its properties as a definite chemical compound. The weight of one cubic metre of water at 4° is 1,000 kilos, at 0° it is 999.8 kilos. The weight of a cubic metre of ice at 0° is less—namely, 917 kilos; the weight of a cubic metre of water vapour at 760 mm. pressure and 100° is only 0.60 kilos; the density of the vapour compared with air = 0.62, and compared with hydrogen = 9.

These data briefly enumerate the physical properties of water as a separate substance. As a supplement to this it may be added that water is a mobile liquid, colourless, transparent, without taste or smell, &c. It is unnecessary to dwell on these properties here, as water is familiar to all; other properties will also be pointed out in describing less known substances. Its latent heat of vaporisation is 534 units. of liquefaction 79 units of heat.¹¹ The large amount of heat stored up in water

¹¹ Of all known liquids, water exhibits the greatest *cohesion* of particles. Indeed, it ascends to a greater height in capillary tubes than other liquids; for instance, two and a half times as high as alcohol, nearly three times as high as ether, and to a much greater height than oil of vitriol, &c. In a tube of two millimetres diameter, water at 0° ascends 15.3 millimetres, counting from the level of the liquid to two-thirds of the height of the meniscus, and at 100° it rises 12.5 millimetres. The cohesion varies very uniformly with the temperature; thus at 50° the height of the capillary column equals 13.9 millimetres—that is, the mean between the columns at 0° and 100° . This uniformity is not destroyed even on approaching the freezing point, and gives reason to think that at high temperatures cohesion will vary as uniformly as at ordinary temperatures; that is, the difference between the columns at 0° and 100° being 2.8 millimetres, the height of the column at 500° should be $15.2 - (5 \times 2.8) = 1.2$ millimetres. Consequently, at these high temperatures the cohesion between the particles of water would be almost *nil*. Only certain solutions (sal ammoniac and lithium chloride), and these only with a great excess of water, rise higher than pure water in capillary tubes. The great cohesion of water doubtless determines many of both its physical and chemical properties.

The quantity of heat required to raise the temperature of one part by weight of water from 0° to 1° , *i.e.*, by 1° C., is called the *unit of heat* or calorie; the *specific heat of liquid water* at 0° is taken as equal to unity. The variation of this specific heat with a rise in temperature is inconsiderable in comparison with the variation exhibited by the specific heats of other liquids. According to Ettinger, the specific heat of water at $20^{\circ} = 1.016$, at $50^{\circ} = 1.039$, and at $100^{\circ} = 1.073$. The specific heat of water is greater than that of all other known liquids; for example, the specific heat of alcohol at 0° is 0.5475—*i.e.*, the quantity of heat which raises 55 parts of water 1° raises 100 parts of alcohol 1° . The specific heat of oil of turpentine at 0° is 0.4106, of ether 0.529, of acetic acid 0.5274, of mercury 0.033. This means that water is the best condenser of

vapour and also in liquid water (for its specific heat is greater than that of other liquids) renders it available in both forms for heating

absorber of heat. This property of water has an important significance in practice and in nature. Water impedes rapid cooling or heating; it tempers cold and heat. The specific heats of ice and aqueous vapour are much less than that of water; namely that of ice is 0.504, and of steam 0.48.

With an increase in pressure equal to one atmosphere, the compressibility of water is 0.000047, of mercury 0.00000352, of ether 0.00012 at 0°, of alcohol at 13° 0.000095. The addition of various substances to water generally simultaneously decreases its compressibility and cohesion. The compressibility of other liquids increases with a rise of temperature, but for water it decreases up to 53° and then increases like other liquids.

The *expansion of water by heat* (Note 9) also exhibits many peculiarities which are not found in other liquids. The expansion of water at low temperatures is very small compared with other liquids; at 4° it reaches even 0, and at 100° it is equal to 0.0008; below 4° it is negative—*i.e.*, water on cooling then expands, and does not decrease in volume. In passing into a solid state, the specific gravity of water decreases; at 0° one c.c. of water weighs 0.999888 gram, and one c.c. of ice at the same temperature weighs only 0.9175 gram. The ice formed, however, contracts on cooling like the majority of other substances. Thus 100 volumes of ice are produced from 92 volumes of water—that is, water expands considerably on freezing, which fact determines a number of natural phenomena. The freezing point of water falls with an increase in pressure (0.007° per atmosphere), because in freezing water expands (Thomson), whilst with substances which contract in solidifying the melting point rises with an increase in pressure; thus, for paraffin it is at one atmosphere 46° and at 100 atmospheres 49°.

When liquid water passes into vapour, the cohesion of its particles must be destroyed, as the particles are removed to such a distance from each other that their mutual attraction no longer exhibits any influence. As the cohesion of aqueous particles varies at different temperatures, the quantity of heat which is expended in overcoming this cohesion—or the *latent heat of evaporation*—for this reason alone will be different at different temperatures. The quantity of heat which is consumed in the transformation of one part by weight of water, at different temperatures, into vapour was determined by Regnault with great accuracy. His researches showed that one part by weight of water taken at 0°, in passing into vapour having a temperature t° , consumes $606.5 + 0.305t$ units of heat, at 50° 621.7, at 100° 637.0, at 150° 652.2, and at 200° 667.5. But this quantity includes also the quantity of heat required for heating the water from 0° to t° —*i.e.*, besides the latent heat of evaporation, also that heat which is used in heating the water in a liquid state to a temperature t° . On deducting this amount of heat, we obtain the latent of evaporation of water as 606.5 at 0°, 571 at 50°, 534 at 100°, 494 at 150°, and only 453 at 200°, which shows that the conversion of water at different temperatures into vapour at a constant temperature requires very different quantities of heat. This is chiefly dependent on the difference of the cohesion of water at different temperatures; the cohesion is greater at low than at high temperatures, and therefore at low temperatures a greater quantity of heat is required to overcome the cohesion. On comparing these quantities of heat, it will be observed that they decrease rather uniformly, namely their difference between 0° and 100° is 72, and between 100° and 200° is 81 units of heat. From this we may conclude that this variation will be approximately the same for high temperatures also, and therefore that no heat would be required for the conversion of water into vapour at a temperature of about 400°–600°. At this temperature, water passes into vapour whatever be the pressure (see chap. II. The absolute boiling point of water, according to Dewar, is 370°, the critical pressure 196 atmospheres). It must here be remarked that water, in presenting a greater cohesion, requires a larger quantity of heat for its conversion into vapour than other liquids. Thus alcohol consumes 208, ether 90, turpentine 70, units of heat in their conversion into vapour.

The whole amount of heat which is consumed in the conversion of water into vapour is not used in surmounting the cohesion—that is, in internal work accomplished in the

purposes. The chemical reactions which water undergoes, and by means of which it is formed, are so numerous, and so closely allied to

liquid. A part of this heat is employed in moving the aqueous particles; in fact, aqueous vapour at 100° occupies a volume 1,650 times greater than that of water (at the ordinary pressure), consequently a portion of the heat or work is employed in lifting the aqueous particles, in overcoming pressure, or in external work, which may be usefully employed and which is so employed in steam engines. In order to determine this work we will first separately consider all the factors necessary for this calculation, and we will then make a deduction from the comparison of these factors.

The maximum *pressure* or *tension* of *aqueous vapour* at different temperatures has been determined with great exactitude by many observers. The observations of Regnault in this respect, as on those preceding, deserve special attention from their comprehensiveness and accuracy. The pressure or tension of aqueous vapour at various temperatures is given in the adjoining table, and is expressed in millimetres of the barometric column having a temperature of 0° .

Temperature	Tension	Temperature	Tension
-20°	0.9	70°	233.3
-10°	2.1	90°	525.4
0°	4.6	100°	760.0
$+10^{\circ}$	9.1	105°	906.4
15°	12.7	110°	1075.4
20°	17.4	115°	1269.4
25°	23.5	120°	1491.3
30°	31.5	150°	3581.0
50°	92.0	200°	11689.0

The table shows the boiling points of water at different pressures. Thus on the summit of Mont Blanc, where the average pressure is about 424 mm., water boils at 84.4° . In a rarefied atmosphere water boils at even the ordinary temperature, but in evaporating it absorbs heat from the neighbouring parts, and therefore it becomes cold and may even freeze if the pressure does not exceed 4.6 mm., and especially if the vapour be rapidly absorbed as it is formed. Oil of vitriol, which absorbs the aqueous vapour, is used for this purpose. Thus ice may be obtained artificially at the ordinary temperature with the aid of an air-pump. This table of the tension of aqueous vapour also shows the temperature of water contained in a closed boiler if the pressure of the steam formed be known. Thus at a pressure of five atmospheres (a pressure of five times the ordinary atmospheric pressure—*i.e.*, $5 \times 760 = 3,800$ mm.) the temperature of the water would be 152° . The table also shows the pressure produced on a given surface by steam on issuing from a boiler. Thus steam having a temperature of 152° exerts a pressure of 517 kilos. on a piston whose surface equals 100 sq. c.m., for the pressure of one atmosphere on one sq. c.m. equals 1,033 kilos., and steam at 152° has a pressure of five atmospheres. As a column of mercury 1 mm. high exerts a pressure of 1.35959 grams on a surface of 1 sq. c.m., therefore the pressure of aqueous vapour at 0° corresponds with a pressure of 6.25 grams per square centimetre. The pressures for all temperatures may be calculated in a similar way, and it will be found that at 100° it is equal to 1,033.28 grams. This means that if a cylinder be taken whose sectional area equals 1 sq. c.m., and if water be poured into it and it be closed by a piston weighing 1,033 grams, then on heating it in a vacuum to 100° no steam will be formed, because the steam cannot overcome the pressure of the piston; and if at 100° 534 units of heat be transmitted to each unit of weight of water, then the whole of the water will be converted into vapour having the same temperature; and so also for every other temperature. The question now arises, To what height does the piston rise under these circumstances; that is, in other words, What is the volume occupied by the steam under a known pressure? For this we must know

the reactions of many other substances, that it is impossible to describe the majority of them at this early stage of chemical exposition. Afterwards we shall become acquainted with many of them, but at present we shall only cite certain compounds formed by water. In order to see clearly the nature of the various kinds of compounds formed by

the weight of a cubic centimetre of steam at various temperatures. It has been shown by experiment that the density of steam, which does not saturate a space, varies very inconsiderably at all possible pressures, and is nine times the density of hydrogen under similar conditions. Steam which saturates a space varies in density at different temperatures, but this difference is very small, and its average density with reference to air is 0.64. We will employ this figure in our calculation, and will calculate what volume the steam occupies at 100°. One cubic centimetre of air at 0° and 760 mm. weighs 0.001293 gram, at 100° and under the same pressure it will weigh $\frac{0.001293}{1.368}$ or about

0.000946 gram, and consequently one cubic centimetre of steam whose density is 0.64 will weigh 0.000605 gram at 100°, and therefore one gram of aqueous vapour will occupy a volume of about 1,653 c.c. Consequently, the piston in the cylinder of 1 sq. c.m. sectional area, and in which the water occupied a height of 1 c.m., will be raised 1,653 c.m. on the conversion of this water into steam. This piston, as has been mentioned, weighs 1,033 grams, therefore the *external work of the steam*—that is, that work which the water does in its conversion into steam at 100°—is equal to lifting a piston weighing 1,033 grams to a height of 1,653 c.m., or 17.07 kilogram-metres of work—*i.e.*, is capable of lifting 17 kilograms 1 metre, or 1 kilogram 17 metres. One gram of water requires for its conversion into steam 534 gram units of heat or 0.534 kilogram units of heat—*i.e.*, the quantity of heat absorbed in the evaporation of one gram of water is equal to the quantity of heat which is capable of heating 1 kilogram of water 0.534°. Each unit of heat, as has been shown by accurate experiment, is capable of doing 424 kilogram-metres of work. Therefore, in evaporating, one gram of water expends $424 \times 0.534 =$ (almost) 226 kilogram-metres of work. The external work was found to be only 17 kilogram-metres, therefore 209 kilogram-metres are expended in overcoming the internal cohesion of the aqueous particles, and consequently about 92 p.c. of the heat or work consumed goes in overcoming the internal cohesion. The following figures are thus calculated approximately:—

Temperature	Total work of evaporation in Kilogram-metres	External work of vapour in Kilogram-metres	Internal work of vapour
0°	255	13	242
50°	242	15	227
100°	226	17	209
150°	209	19	190
200°	192	20	172

Thus it will be remarked from this table that the work necessary for overcoming the internal cohesion of water in its passage into vapour decreases with the rise in temperature; this is in connection with the decrease of cohesion with a rise in temperature, and, in fact, the variations which take place in this case are very similar to those which are observed in the heights to which water rises in capillary tubes at different temperatures. It is evident, therefore, that the amount of external—or, as it is termed, useful—work which water can supply by its evaporation is very small compared with the amount which it expends in its conversion into vapour.

In considering certain physico-mechanical properties of water, I had in view not only their importance for theory and practice, but also their purely chemical significance, for it is evident from the above considerations that in even a physical change of state the greatest part of the work accomplished goes in overcoming cohesion, and that chemical cohesion, or affinity, is an enormous internal energy.

water we will begin with the most feeble, which are determined by purely mechanical superficial properties of the reacting substances.¹²

Water is mechanically attracted by many substances ; it adheres to their surfaces just as dust adheres to objects, and one polished glass adheres to another. Such attraction is termed 'moistening,' 'soaking,' or 'absorption of water.' Thus water moistens clean glass and adheres to its surface, is absorbed by the soil, sand, and clay, and does not flow away from them but lodges itself between their particles. Similarly, water soaks into a sponge, cloth, hair, or paper, &c., but fat and greasy substances in general are not moistened. Attraction of this kind does not alter the physical or chemical properties of water. For instance, under these circumstances water, as is known from everyday experience, may be expelled from objects by drying. Water which is in any way held mechanically may be dislodged by mechanical means, by friction, pressure, centrifugal force, &c. Thus water is squeezed from wet cloth by pressure or centrifugal machines. But objects which in practice are called dry (because they do not wet people's hands) often still contain moisture, as may be proved by heating the object in a glass tube closed at one end. By placing a piece of paper, dry earth, or any similar object (especially porous substances) in such a glass tube, and heating that part of the tube where the object is situated, it will be remarked that water condenses on the cooler portions of the tube. The presence of such absorbed, or, as it is termed, 'hygroscopic,' water is generally best recognised in non-volatile substances by drying at 100°,

¹² When it is necessary to heat a considerable mass of liquid in different vessels, it would be very uneconomical to make use of metallic vessels and to construct a separate fire grate under each one; such cases are continually met with in practice. A considerable mass of water, for instance, may have to be heated for making solutions, or it may be required to expel volatile liquids from different vessels at intermittent periods; as, for instance, alcohol from partially fermented liquors, &c. In such cases one boiler or vessel containing water is made use of. Steam from this boiler is introduced into the liquid, or, in general, into the vessel which it is required to heat. The steam, in condensing and passing into a liquid state, parts with its latent heat, and as this is very considerable a small quantity of steam will produce a considerable heating effect. If it be required, for instance, to heat 1,000 kilos. of water from 20° to 50°, which requires approximately 30,000 units of heat, steam heated to 100° is passed into the water from a boiler. Each kilogram of water at 50° contains about 50 units of heat, and each kilogram of steam at 100° contains 637 units of heat; therefore, each kilogram of steam in cooling to 50° gives up 587 units of heat, and consequently 52 kilos of steam are capable of accomplishing the required heating of 1,000 kilos. of water from 20° to 50°. Water is very often applied for heating in chemical practice. For this purpose metallic vessels or pans, called 'water-baths,' are made use of. They are closed by a cover formed of concentric rings lying on each other. The objects—such as beakers, evaporating basins, retorts, &c.—containing liquids are placed on these rings, and the water in the bath is heated. The steam given off heats the bottom of the vessels to be heated, and thus accomplishes the evaporation or distillation or other required process. A water-bath may also be used for heating a vessel directly immersed in the water.

or under the receiver of an air-pump and over substances which attract water chemically. By weighing a substance before and after drying, it is easy to determine the amount of hygroscopic water from the loss in weight.¹³ Only in this case the amount of water must be judged with

¹⁵ In order to dry any substance at about 100° —that is, at the boiling point of water (hygroscopic water passes off at this temperature)—an apparatus called a ‘drying-oven’ is employed. It consists of a double copper box; water is poured into the space between the internal and external boxes, and the oven is then heated over a stove or by any other means, or else steam from a boiler is passed between the walls of the two boxes. When the water boils, the temperature inside the inner box will be approximately 100° C. The substance to be dried is placed inside the oven, and the door is closed. Several holes are cut in the door to allow the free passage of air, which carries off the aqueous vapour by the chimney on the top of the oven. Often, however, desiccation is carried on in copper ovens heated directly over a lamp (fig. 13). In this case any desired




FIG. 13.—Drying oven, composed of brazed copper. It is heated by a lamp. The object to be dried is placed on the gauze inside the oven. The thermometer indicates the temperature.

temperature may be obtained, which is determined by a thermometer fixed in a special orifice. There are substances which only part with their water at a much higher temperature than 100° , and then such air baths are very useful. In order to directly determine the amount of water in a substance which does not part with anything except water at a red heat, the substance is placed in a bulb tube. By first weighing the tube empty and then with the substance to be dried in it, the weight of the substance taken may be found. The tube is then connected on one side with a gas-holder full of air, which, on opening a stop-cock, passes first through a flask containing sulphuric acid, and then into a vessel containing lumps of pumice stone moistened with sulphuric acid. In passing through these vessels the air is thoroughly dried, having given up all its moisture to the sulphuric acid. Thus dry air will pass into the bulb tube, and as hygroscopic water is entirely given up from a substance in dry air at even the ordinary temperature, and still

care, because the loss in weight may sometimes proceed from the decomposition of the substance itself, with disengagement of gases or vapour. In making exact weighings the hygroscopic capacity of substances—that is, their capacity to absorb moisture—must be continually kept in view, as otherwise the weight will be untrue from the presence of moisture. The quantity of moisture absorbed depends on the degree of moisture of the atmosphere (that is, on the tension of the aqueous vapour in it) in which a substance is situated. In an entirely dry atmosphere, or in a vacuum, the hygroscopic water is expelled, being converted into vapour; therefore, if we have the means of *drying gases* (or a vacuum)—that is, of removing the aqueous vapour from them—objects impregnated with water may be entirely dried by placing them in such a desiccated atmosphere. The process is aided by heat, as it increases the tension of the aqueous vapour. Phosphoric anhydride (a white powder), liquid sulphuric acid, solid and porous calcium chloride, or the white powder of ignited copper sulphate are most generally employed in drying gases. They absorb the moisture contained in air and all gases to a considerable, but not unlimited, extent. Phosphoric anhydride and calcium chloride deliquesce, become damp, sulphuric acid changes from an oily thick liquid into a more mobile liquid, and ignited copper sulphate becomes blue; after which changes these substances partly lose their capacity of holding water, and can, if it be in excess, even give up their water to the atmosphere. We may remark that the order in which these substances are placed above corresponds with the order in which they stand in respect to their capacity for absorbing moisture. Air dried by calcium chloride still contains a certain amount of moisture, which it can give up to sulphuric acid. The most complete desiccation takes place with phosphoric anhydride. Water is also removed from many substances by placing them in a basin over a vessel containing a substance absorbing water under a glass bell.¹⁴ The bell, like the receiver of an air pump, should be hermetically closed.

more rapidly on heating, the moisture given up by the substance in the tube will be carried off by the air passing through it. This damp air then passes through a U-shaped tube full of pieces of pumice stone moistened with sulphuric acid, which absorbs all the moisture given off from the substance in the bulb tube. Thus all the water expelled from the substance will collect in the U tube, and so, if this be weighed before and after, the difference will show the quantity of water expelled from the substance. If only water (and not any gases) come over, the increase of the weight of the U tube will be equal to the decrease in the weight of the bulb tube.

¹⁴ Instead of under a glass bell, drying over sulphuric acid is often carried on in a desiccator composed of a wide-mouthed low glass vessel, closed by a well-fitting ground-glass stopper. Sulphuric acid is poured over the bottom of the desiccator, and the substance to be dried is placed on a glass stand above the acid. A lateral glass tube with a stop-cock is often fused into the desiccator in order to connect it with an air pump, and so allow drying under a diminished pressure, when the moisture evaporates more rapidly.

In this case desiccation takes place ; because sulphuric acid, for instance, first dries the air in the bell by absorbing its moisture, the substance to be dried then parts with its moisture to the dry air, from which it is again absorbed by the sulphuric acid, &c. Desiccation proceeds still better under the receiver of an air pump, for then the aqueous vapour is formed more quickly than in a bell full of air.

From what has been said above, it is evident that the transference of moisture to gases and the absorption of hygroscopic moisture present great resemblance to, but still are not, chemical combinations with water. Water, when combined as hygroscopic water, does not lose its properties and does not form new substances.¹⁵

The attraction of water for substances which dissolve in it is of a different character. In the solution of substances in water there proceeds a peculiar kind of indefinite combination ; there is formed a new homogeneous substance from the two substances taken. But here also the bond connecting the substances is very unstable. Water containing different substances in solution boils at a temperature near to its usual boiling point, and acquires properties which are closely allied to the properties of water itself and of the substances dissolved in it. Thus, from the solution of substances which are lighter than water itself, there are obtained solutions of a less density than water—as, for example, in the solution of alcohol in water : whilst a heavier substance in dissolving in water gives it a higher specific gravity. Thus salt water is heavier than fresh.¹⁶

We will consider *aqueous solutions* somewhat fully, because, among other reasons, solutions are constantly being formed on the earth and in the waters of the earth, in plants and in animals, in chemical practice and in the arts, and these solutions play an important part in the chemical transformations which are everywhere taking place, not only because water is everywhere met with, but chiefly because a substance in solution presents the most propitious conditions for the process of chemical changes, which require a mobility of parts and an intimate

¹⁵ Chapuy, however, determined that in wetting 1 gram of charcoal with water 7 units of heat are evolved, and on pouring carbon bisulphide over 1 gram of charcoal as much as 24 units of heat are evolved. Alumina (1 gram), when moistened with water, evolves $2\frac{1}{2}$ calories. This indicates that even in respect to evolution of heat moistening already presents a transition towards exothermal combinations (those evolving heat in their formation), like solutions.

¹⁶ Strong acetic acid ($C_2H_4O_2$), whose specific gravity at 15° is 1.055, does not become lighter on the addition of water (a lighter substance, sp. gr. = 0.999), but heavier, so that a solution of 80 parts of acetic acid and 20 parts of water has a specific gravity of 1.074, and even a solution of equal parts of acetic acid and water (50 p.c.) has a sp. gr. of 1.065, which is still greater than that of acetic acid itself. This shows the high degree of contraction which takes place on solution. In fact, solutions—and, in general, liquids—on mixing with water, decrease in volume.

contact. In dissolving, a solid substance acquires a mobility of parts, and a gas loses its elasticity, and therefore reactions often take place in solutions which do not proceed in the undissolved substances. Further, a substance, distributed in water, evidently breaks up (or 'disintegrates')—that is, becomes more like a gas and acquires a greater mobility of parts. All these considerations require that in describing




FIG. 14.—Method of transferring a gas into a cylinder filled with mercury and whose open end is immersed under the mercury in a bath having two glass sides. The apparatus containing the gas is represented on the right. Its upper extremity is furnished with a tube extending under the cylinder. The lower part of the vessel communicates with a vertical tube. If mercury be poured into this tube, the pressure of the gas in the apparatus is increased, and it passes through the gas-conducting tube into the cylinder, where it displaces the mercury, and can be measured or subjected to the action of absorbing agents, such as water

the properties of substances, particular attention should be paid to their relation to water as a solvent.

Everybody knows that water dissolves many substances. Salt, sugar, alcohol, and a number of other substances, by dissolving in water form with it homogeneous liquids. To clearly show the solubility of gases in water a gas should be taken which has a high co-efficient of solubility—for instance, ammonia. This is introduced into a bell (or cylinder, as in fig. 14), which is previously filled with mercury and stands in a mercury bath. If water be then introduced into the cylinder, the mercury will rise, owing to the water dissolving the ammonia gas. If the column of mercury be less than the barometric

column, and if there be sufficient water to dissolve the gas, all the ammonia will be absorbed by the water. The water is introduced into the cylinder by a glass pipette, with a bent end. Its bent end is put into water, and the air is sucked out from the upper end. When full of water, its upper end is closed with the finger, and the bent end placed in the mercury bath under the orifice of the cylinder. The water will then be forced from the pipette by the atmospheric pressure, and will rise to the surface of the mercury in the cylinder owing to its lightness. The solubility of a gas like ammonia may be demonstrated by taking a flask full of the gas, and closed by a cork with a tube passing through it. On placing the tube under water, the water will rise into the flask (this may be accelerated by heating the flask), and begin to play like a fountain inside it. Both the rising of the mercury and the fountain clearly show the considerable affinity of water for ammonia gas, and the force acting in this dissolution is rendered evident. For both the homogeneous intermixture of gases (diffusion) and the process of solution a certain period of time is required, which depends, not only on the surface of the participating substances, but also on their nature. This is seen from experiment. Prepared solutions of different substances heavier than water, such as salt or sugar, are poured into tall jars. Pure water is then most carefully poured into these jars (through a funnel) on to the top of the solutions, so as not to disturb the lower stratum, and the jars are then left undisturbed. The line of demarcation between the solution and the pure water will be visible, owing to their different co-efficients of refraction. Notwithstanding that the solutions taken are heavier than water, after some time complete intermixture will ensue. Gay-Lussac convinced himself of this fact by this particular experiment, which he conducted in the cellars under the Paris Astronomical Observatory. These cellars are well known as the locality where numerous interesting researches have been conducted, because, owing to their depth under ground, they have a uniform temperature during the whole year; the temperature does not change during the day, and this was indispensable for the experiments on the diffusion of solutions, in order that no doubt in their results should arise from a daily change of temperature (the experiment lasted several months), which would set up currents in the liquids and intermix their strata. Notwithstanding the uniformity of the temperature, the substance in solution in time ascended into the water and distributed itself uniformly through it, proving that there exists between water and a substance dissolved in it a particular kind of attraction or striving for mutual interpenetration in opposition to the force of gravity. Further, this effort, or rate of diffusion, is different for salt or sugar or for

various other substances. Consequently, in solution there acts a peculiar force, as in actual chemical combinations, and solution is determined by a peculiar kind of movement (by the chemical energy of a substance) which is proper to the substance dissolved and to the solvent.

Graham made a series of experiments similar to those above described, and he showed that the *rate of diffusion*¹⁷ in water is very variable—that is, a uniform distribution (under perfect rest, and with such an arrangement of the strata of the solutions that uniformity takes place in opposition to gravity) of a substance in the water dissolving it is attained in different periods of time with different solutions. Graham compared diffusive capacity with volatility. There are substances which diffuse easily, and there are others which diffuse with difficulty, just as there are more or less volatile substances. Seven hundred cubic centimetres of water was poured into a jar, and by means of a syphon (or a pipette) 100 cub. centimetres of a solution containing 10 grams of a substance was cautiously poured in so as to occupy the lower portion of the jar. After the lapse of several days, successive layers of 50 cubic centimetres were taken from the top downwards, and the quantity of substance dissolved in the different layers determined. Thus, common table salt, after fourteen days, gave the following amounts (in milligrams) in the respective layers, beginning from the top: 104, 120, 126, 198, 267, 340, 429, 535, 654, 766, 881, 991, 1,090, 1,187, and 2,266 in the remainder; whilst albumin in the same time gave, in the first seven layers, a very small amount, and beginning from the eighth layer, 10, 15, 47, 113, 343, 855, 1,892, and in the remainder 6,725 milligrams. Thus, the diffusive power of a solution depends on time and on the nature of the substance dissolved, which fact may serve, not only for the explanation of the process of solution, but also in distinguishing one substance from another. Graham showed that substances which rapidly diffuse through liquids are able to rapidly pass through membranes and crystallise, whilst substances which diffuse slowly and do not crystallise are *colloids*, that is, resemble glue, and penetrate through

¹⁷ The researches of Graham, Fick, Nernst, and others showed that the quantity of a dissolved substance which is transmitted (rises) from one stratum of liquid to another in a vertical cylindrical vessel is not only proportional to the time and to the sectional area of the cylinder, but also to the amount and nature of the substance dissolved in a stratum of liquid, so that each substance has its corresponding co-efficient of diffusion. The cause of the diffusion of solutions must be considered as essentially the same as the cause of the diffusion of gases—that is, as dependent on movements which are proper to their molecules; but here most probably those purely chemical, although feebly-developed, forces, which incline the substances dissolved to the formation of definite compounds, also play their part.

a membrane slowly, and form jellies; that is, occur in insoluble forms.¹⁸

¹⁸ The rate of diffusion—like the rate of transmission—through membranes, or *dialysis* (which plays an important part in the vital processes of organisms and also in technical work), presents, according to the researches of Graham, a sharply-defined change in passing from such crystallisable substances as the majority of salts and acids to substances which are capable of giving jellies (gum, gelatin, &c.). The former diffuse into solutions and pass through membranes much more rapidly than the latter, and Graham therefore distinguishes between *crystalloids*, which diffuse rapidly, and *colloids*, which diffuse slowly. On breaking solid colloids into pieces, a total absence of cleavage is remarked. The fracture of such substances is like that of glue or glass. It is termed a 'conchoidal' fracture. Almost all the substances of which animal and vegetable bodies consist are colloids, and this is, at all events, partly the reason why animals and plants have such varied forms, which have no resemblance to the crystalline forms of the majority of mineral substances. The colloid solid substances in organisms—that is, in animals and plants—are usually soaked with water, and take most peculiar forms, of networks, of granules, of hairs, of mucous, shapeless masses, &c., which are quite different from the forms taken by crystalline substances. When colloids separate out from solutions, or from a molten state, they present a form which is similar to that of the liquid from which they were formed. Glass may be taken as the best example of this. Colloids are distinguishable from crystalloids, not only by the absence of crystalline form, but by many other properties which admit of clearly distinguishing both these classes of solids, as was shown by the above-mentioned English scientific man, Graham. Nearly all colloids are capable of passing, under certain circumstances, from a soluble into an insoluble state. The best example is shown by white of eggs (albumin) in the raw and soluble form, and in the hard-boiled and insoluble form. The majority of colloids, on passing into an insoluble form in the presence of water, give substances having a gelatinous appearance, which is familiar to every one in starch, solidified glue, jelly, &c. Thus gelatin, or common carpenter's glue, when soaked in water, swells up into an insoluble jelly. If this jelly be heated, it melts, and is then soluble in water, but on cooling it again forms a jelly which is insoluble in water. One of the properties which distinguish colloids from crystalloids is that the former pass very slowly through a membrane, whilst the latter penetrate very rapidly. This may be shown by taking a cylinder, open at both ends, and by covering its lower end with a bladder or with vegetable parchment (unsized paper immersed for two or three minutes in a mixture of sulphuric acid and half its volume of water, and then washed), or any other membranous substance (all such substances are themselves colloids in an insoluble form). The membrane must be firmly tied to the cylinder, so as not to leave any opening. Such an apparatus is called a *dialyser* (fig. 15), and the process of separation of crystalloids from colloids by means of such a membrane is termed *dialysis*. An aqueous solution of a crystalloid or colloid, or a mixture of both, is poured into the dialyser, which is then placed in a vessel containing water, so that the bottom of the membrane is covered with water. Then, after a certain period of time, the crystalloid passes through the membrane, whilst the colloid, if it does pass through at all, does so at an incomparably slower rate. The crystalloid




FIG. 15. - Dialyser. Apparatus for the separation of substances which pass through a membrane from those which do not. Description in text.

If it be desired to increase the rate of solution, recourse must be had to stirring, shaking, or some such mechanical movement, obliging the solution formed round the given substance to rise upwards if the solution be heavier than the solvent. But if once a uniform solution is formed, it will remain uniform if the temperature be uniform, no matter how heavy the dissolved substance is, or how long the solution be left at rest, which fact again shows the presence of a force holding together the particles of the body dissolved and of the solvent.¹⁹

naturally passes through into the water until the solution attains the same strength on both sides of the membrane. By replacing the outside water with fresh water, a fresh quantity of the crystalloid may be separated from the dialyser. While a crystalloid is passing through the membrane, a colloid remains almost entirely in the dialyser, and therefore a mixed solution of these two kinds of substances may be separated from each other by a dialyser. The study of the properties of colloids, and of the phenomena of their passage through membranes, should elucidate much respecting the phenomena which are accomplished in organisms.

¹⁹ The formation of solutions may be considered in two aspects, from a physical and from a chemical point of view, and it is more evident in solutions than in any other department of chemistry that these provinces of natural science are allied together in a most intimate manner. On one hand solutions form a particular aspect of a physico-mechanical interpenetration of homogeneous substances, and a juxtaposition of the molecules of the substance dissolved and of the solvent, similar to the juxtaposition which is exhibited in homogeneous substances. From this point of view this diffusion of solutions is exactly similar to the diffusion of gases, with only this difference, that the nature and store of energy is different in gases from what it is in liquids, and that in liquids there is considerable friction whilst in gases there is comparatively little. The penetration of a dissolved substance into water is likened to evaporation, and solution to the formation of vapour. This resemblance was clearly expressed even by Graham. In recent years the Dutch chemist, Van't Hoff, has developed this view of solutions in great detail, having shown (in a memoir in the *Transactions of the Swedish Academy of Science*, Part 21, No. 17, 'Lois de l'équilibre chimique dans l'état dilué, gazeux au dissous,' 1886), that for dilute solutions the *osmotic pressure* follows the same laws (of Boyle, Mariotte, Gay-Lussac, and Avogadro-Gerhardt) as for gases. The osmotic pressure of a substance dissolved in water is determined by means of membranes which allow the passage of water, but not of a substance dissolved in it, through them. This property is found in animal protoplasmic membranes and in porous substances covered with an amorphous precipitate such as is obtained by the action of copper sulphate on potassium ferrocyanide (Pfeifer Traube). If, for instance, a one p.c. solution of sugar be placed in such a vessel, which is then closed and placed in water, then the water passes through the walls of the vessel and increases the pressure by 50 mm. of the barometric column. If the pressure be artificially increased inside the vessel, then the water will be expelled through the walls. The osmotic pressure of dilute solutions determined in this manner (from observations made by Pfeifer and De Vries) was shown to follow the same laws as those of the pressure of gases; for instance, by doubling or increasing the quantity of a salt (in a given volume) n times, the pressure is doubled or increases n times. One of the extreme consequences of the resemblance of osmotic pressure to gaseous pressure is that the concentration of a uniform solution varies in parts which are heated or cooled. Soret (1881) indeed observed that a solution of copper sulphate containing 17 parts of the salt at 20° only contained 14 parts after heating the upper portion of the tube to 80° for a long period of time. This aspect of solution, which is now being very carefully and fully worked out, may be called the *physical* side. Its other aspect is purely *chemical*, for solution does not take place between any two substances, but requires a

In the consideration of the process of solution, besides the conception of diffusion, another fundamental conception is necessary, namely, that of the *saturated solutions*.

special and particular attraction infinity between them. A vapour or gas permeates into any other vapour or gas, but a salt which dissolves in water may not be in the least soluble in alcohol, and is quite insoluble in mercury. In considering solution as a manifestation of chemical forces (and of chemical energy), it must be acknowledged that they are here developed to so feeble an extent that the definite compounds (that is, those formed according to the law of multiple proportions) which are formed between water and a soluble substance dissociate at even the ordinary temperature, forming a homogeneous system—that is, one where both the compound and the products into which it decomposes (water and the aqueous compound) occur in a liquid state. The chief difficulty in the comprehension of solutions depends on the fact that the mechanical theory of the structure of liquids has not yet been so fully developed as the theory of gases, and solutions are liquids. The conception of solutions as liquid dissociated definite chemical compounds is based on the following considerations: (1) that there exist certain undoubtedly definite chemical crystalline compounds (such as H_2SO_4 , H_2O ; or NaCl , $10\text{H}_2\text{O}$; or CaCl_2 , $6\text{H}_2\text{O}$; &c.) which melt on a certain rise of temperature, and then form real solutions; (2) that metallic alloys in a molten condition are real solutions, but on cooling they often give entirely distinct and definite crystalline compounds, which are recognised by the properties of alloys; (3) that between the solvent and the substance dissolved there are formed, in a number of cases, many undoubtedly definite compounds, such as compounds with water of crystallisation; (4) that the physical properties of solutions, and especially their specific gravities (a property which is very accurately observable), vary with a change in composition, and in such a manner as the formation of one or several definite but dissociating compounds would require. Thus, for example, on adding water to fuming sulphuric acid its density is observed to decrease until it attains the definite composition H_2SO_4 , or $\text{SO}_3 + \text{H}_2\text{O}$, when the specific gravity increases, although on further diluting with water it again falls. Further (Mendeléeff, *The Investigation of Aqueous Solutions from their Specific Gravities*, 1887), the increase in specific gravity (ds), with the augmentation (dp) of the percentage amount of a substance dissolved, varies in all well-known solutions with the percentage amount of the substance dissolved, so that a rectilinear dependence is obtained (i.e., $\frac{ds}{dp} = A + Bp$) between the limits of

definite compounds which must be acknowledged to exist in solutions; this would be expected to be the case from the dissociation hypothesis. So, for instance, from H_2SO_4 to $\text{H}_2\text{SO}_4 - \text{H}_2\text{O}$ (both these substances exist as definite compounds in a free state), the fraction $\frac{ds}{dp} = 0.0729 - 0.000749p$ (where p is the percentage amount of H_2SO_4). For alcohol $\text{C}_2\text{H}_6\text{O}$, whose aqueous solutions have been more accurately investigated than all others, three definite compounds must be acknowledged in its solutions, $\text{C}_2\text{H}_6\text{O} + 12\text{H}_2\text{O}$, $\text{C}_2\text{H}_6\text{O} + 3\text{H}_2\text{O}$, and $3\text{C}_2\text{H}_6\text{O} + \text{H}_2\text{O}$.

The two aspects of solution above mentioned, and the hypotheses which have as yet been applied to the examination of solutions, although they have partially different starting points, yet will doubtless in time lead to a general theory of solutions, because the same common laws govern both physical and chemical phenomena, inasmuch as the properties and movements of molecules, which determine physical properties, are dependent on the movements and properties of atoms, which determine chemical mutual actions. For details of the questions dealing with the theories of solution recourse must now be had to special memoirs and to works on theoretical (physical) chemistry; for this subject forms one of special interest at the present epoch of the development of our science. In working out chiefly the chemical side of solutions I consider it to be necessary to reconcile the two aspects of the question; this seems to me to be all the more possible, as the physical side is limited to dilute solutions only, whilst the chemical side deals mainly with strong solutions.

Just as damp air may be added to any quantity of dry air it be desired, so also a solvent liquid may be taken in an indefinitely large quantity and yet a uniform solution will be obtained. But more than a definite quantity of aqueous vapour cannot be introduced into a certain volume of air at a certain temperature. The excess above the point of saturation will remain in the liquid form.²⁰ The relation between water and substances dissolved in it is similar. More than a definite quantity of a substance cannot, at a certain temperature, dissolve in a given quantity of water; the excess does not unite with the water. Just as air or a gas becomes saturated with vapour, so water becomes saturated with a substance dissolved in it. If an excess of a

²⁰ A juxtaposition of (chemically or physically) reacting substances taken in various states—for instance, some solid, others liquid or gaseous—is termed a heterogeneous system. Up to now it is only systems of this kind which can be subjected to detailed examination in the sense of the mechanical theory of heat. Solutions present liquid homogeneous systems, which as yet are subjected to investigation with difficulty.

In the case of limited solution of liquids in liquids, *the difference between the solvent and the substance dissolved* is clearly seen. The former (that is, the solvent) may be added in an unlimited quantity, and yet the solution obtained will always be uniform, whilst of the substance dissolved there can only be taken a definite saturating proportion. We will take water and common (sulphuric) ether. On shaking the ether with the water it will be remarked that a portion of it dissolves in the water, forming a solution. If the ether be taken in such a quantity that it saturates the water and a portion of it remains undissolved, then this remaining portion will act as a solvent, and water will diffuse through it and also form a saturated solution of water in the ether taken. Thus two saturated solutions will be obtained. One solution will contain ether dissolved in water, and the other solution will contain water dissolved in ether. These two solutions will arrange themselves in two layers, according to their density; the ethereal solution of water will be on the top, as the lightest, and the aqueous solution of ether at the bottom, as the heaviest. If the upper ethereal solution be poured off from the aqueous solution, any quantity of ether may be added to it; this shows that the dissolving substance is ether. If water be added to it, it is no longer dissolved in it; this shows that water saturates the ether—here water is the substance dissolved. If we act in the same manner with the lower layer, we shall find that water is the solvent and ether the substance dissolved. By taking different amounts of ether and water, the degree of solubility of ether in water, and of water in ether, may be easily determined. Thus, for example, in the above case it is found that water approximately dissolves $\frac{1}{10}$ of its volume of ether, and ether dissolves a very small quantity of water. Let us imagine that the liquid poured in dissolves a considerable amount of water, and that water dissolves a considerable amount of the liquid. For instance, let us imagine that the saturation of 100 parts of water require 80 parts of the liquid, and that 100 parts of the liquid would require 125 parts of water for its saturation. What would then take place if the liquid be poured in water? Two layers could not be formed, because the saturated solutions would resemble each other, and therefore they would intermix in all proportions. Indeed, in the saturated aqueous solution there would be 0·8 parts of the liquid taken to 1 part of water, and in the solution of water in the liquid taken there would be on saturation 1 part of water to 0·8 parts of the liquid. There would be no line of demarcation between the layers of the liquids, or, in other words, they would intermix in all proportions. This is, consequently, a case of a phenomena where two liquids present considerable co-efficients of solubility in each other, but where it is impossible to say what these co-efficients are, because it is impossible to obtain a saturated solution.

substance be added to water which is already saturated with it, it will remain in its original state, and will not spread through the water. The quantity of a substance (either by volume with gases, or by weight with solids and liquids) which is capable of saturating 100 parts of water is called the *co-efficient of solubility* or the *solubility*. In 100 grams of water at 15° , there can be dissolved not more than 35.86 grams of common salt. Consequently, its solubility at 15° is equal to 35.86.²¹ It is most

²¹ The solubility, or co-efficient of solubility, of a substance is determined by various methods. Either a solution is expressly prepared with a clear excess of the soluble substance and saturated at a given temperature, and the quantity of water and of the substance dissolved in it determined by evaporation, desiccation, or other means; or else, as is done with gases, known quantities of water and of the soluble substance are taken, and the amount remaining undissolved is determined.

The solubility of a gas in water is determined by means of an apparatus called an *absorptiometer* (fig. 16). It consists of an iron stand *f*, on which an india-rubber ring rests. A wide glass tube is placed on this ring, and is pressed down on it by the ring *h* and the screws *i i*. The tube is thus firmly fixed on the stand. A cock *r*, communicating with a funnel *r*, passes into the lower part of the stand. Mercury can be poured into the wide tube through this funnel, which is therefore made of steel, as copper would be affected by the mercury. The upper ring *h* is furnished with a




FIG. 16.—Bunsen's absorptiometer. Apparatus for determining the solubility of gases in liquids.

important to turn attention to the *existence of the solid insoluble substances of nature*, because on them depends the shape of the

cover *p*, which can be firmly pressed down on to the wide tube, and hermetically closes it by means of an india-rubber ring. The tube *rr* can be raised at will, and so by pouring mercury into the funnel the height of the column of mercury, which produces pressure inside the apparatus, can be increased. The pressure can also be diminished at will, by letting mercury out through the cock *r*. A graduated tube *e*, containing the gas and liquid to be experimented on, is placed inside the wide tube. This tube is graduated in millimetres for determining the pressure, and it is calibrated for volumes, so that the number of volumes occupied by the gas and liquid dissolving it can be easily calculated. This tube can also be easily removed from the apparatus. To the right of the figure, the lower portion of this tube when removed from the apparatus is shown. It will be observed that its lower end is furnished with a male screw *b*, fitting in a nut *a*. The lower surface of the nut *a* is covered with india-rubber, so that on screwing up the tube its lower end presses upon the india-rubber, and thus hermetically closes the whole tube, for its upper end is fused up. The nut *a* is furnished with arms *c c*, and in the stand *f* there are corresponding spaces, so that when the screwed-up internal tube is fixed into stand *f*, the arms *c c* fix into these spaces cut in *f*. This enables the internal tube to be fixed on to the stand *f*. When the internal tube is fixed in the stand, the wide tube is put into its right position, and mercury and water are poured into the space between the two tubes, and communication is opened between the inside of the tube *e* and the mercury between the interior and exterior tubes. This is done by either revolving the interior tube *e*, or by a key turning the nut about the bottom part of *f*. The tube *e* is filled with gas and water as follows: the tube is removed from the apparatus, filled with mercury, and the gas to be experimented on is passed into it. The volume of the gas is measured, the temperature and pressure determined, and the volume it would occupy at 0° and 760 mm. calculated. A known volume of water is then introduced into the tube. The water must be previously boiled, so as to be quite freed from air in solution. The tube is then closed by screwing it down on to the india-rubber on the nut. It is then fixed on to the stand *f*, mercury and water are poured into the intervening space between it and the exterior tube, which is then screwed up and closed by the cover *p*, and the whole apparatus is left at rest for some time, so that the tube *e*, and the gas in it, may attain the same temperature as that of the surrounding water, which is marked by a thermometer *k* tied to the tube *e*. The interior tube is then again closed by revolving it in the nut, the cover *p* again shut, and the whole apparatus is shaken in order that the gas in the tube *e* may entirely saturate the water. After several shakings, the tube *e* is again opened by revolving it in the nut, and the apparatus is left at rest for a certain time; it is then closed and again shaken, and so on until the volume of gas does not diminish after a fresh shaking—that is, until saturation ensues. Observations are then made of the temperature, the height of the mercury in the interior tube, and the level of the water in it, and also of the level of the mercury and water in the exterior tube. All these data are necessary in order to calculate the pressure under which the solution of the gas takes place, and what volume of gas remains undissolved, and also the quantity of water which serves as the solvent. By varying the temperature of the surrounding water, the amount of gas dissolved at various temperatures may be determined. Bunsen, Carius, and many others determined the solution of various gases in water, alcohol, and certain other liquids, by means of this apparatus. If in a determination of this kind it is found that *n* cubic centimetres of water at a pressure *h* dissolve *m* cubic centimetres of a given gas, measured at 0° and 760 mm., when the temperature under which solution took place was *t*° and pressure *h* mm., then it follows that at the temperature *t* the *co-efficient of solubility of the gas* in 1 volume of the liquid will be equal to $\frac{m}{n} \times \frac{760}{h}$.

This formula is very clearly understood from the fact that the co-efficient of solubility of gases is that quantity measured at 0° and 760 mm., which is absorbed at a pressure

substance of the earth's surface, and of plants and animals. There is so much water on the earth's surface, that were the surface of substances formed of soluble matters it would constantly change, and however substantial their forms might be, mountains, river banks and sea shores, plants and animals, or the habitations and coverings of men, could not exist for any length of time.²²

of 760 mm. by one volume of a liquid. If n cubic centimetres of water absorb m cubic centimetres of a gas, then one cubic centimetre absorbs $\frac{m}{n}$. If $\frac{m}{n}$ c.c. of a gas are absorbed under a pressure of h mm., then, according to the law of the variation of solubility of a gas with the pressure, there would be dissolved, under a pressure of 760 mm., a quantity varying in the same ratio to $\frac{m}{n}$ as 760 : h . In determining the residual volume of gas its moisture (note 1) must be taken into consideration.

Below are given the number of grams of several substances saturating 100 grams of water—that is, their co-efficients of solubility by weight at three different temperatures:—

		At 0°	At 20°	At 100°
Gases	Oxygen, O ₂	$\frac{4}{1000}$	$\frac{4}{1000}$	—
	Carbonic anhydride, CO ₂	$\frac{35}{100}$	$\frac{100}{100}$	—
	Ammonia, NH ₃	90·0	51·8	7·8
Liquids	Phenol, C ₆ H ₆ O	4·9	5·2	∞
	Amyl alcohol, C ₅ H ₁₂ O	4·4	2·9	—
	Sulphuric acid, H ₂ SO ₄	∞	∞	∞
	Gypsum, CaSO ₄ , 2H ₂ O	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{1}{8}$
Solids	Alum, AlKSO ₈ , 12H ₂ O	3·3	15·4	357·5
	Anhydrous sodium sulphate, Na ₂ SO ₄	4·5	20	43
	Common Salt, NaCl	35·7	36·0	39·7
	Nitre, KNO ₃	13·3	31·7	246·0

Sometimes a substance is so slightly soluble that it may be considered as insoluble. Many such substances are met with both in solids and liquids, and such a gas as oxygen, although it does dissolve, does so in so small a proportion by weight that it might be considered as zero did not the solubility of even so little oxygen play an important part in nature (as in the respiration of fishes) and were not an infinitesimal quantity of a gas by weight so easily measured by volume. The sign ∞, which stands on a line with sulphuric acid in the above table, indicates that it intermixes with water in all proportions. There are many such cases among liquids, and everybody knows, for instance, that spirit (absolute alcohol) can be mixed in any proportion with water. Common corn spirit (vodka) is a mixture of about fifty parts by weight of pure spirit to 100 parts by weight of water.

²² Just as the existence must be admitted of substances which are completely undecomposable (chemically) at the ordinary temperature—for there are substances which are entirely non-volatile at such a temperature (as wood and gold), although capable of decomposing (wood) or volatilising (gold) at a higher temperature—so also the existence must be admitted of substances which are totally insoluble in water without some degree of change in their state. Although mercury is partially volatile at the ordinary temperature, there is no reason to think that it and other metals are soluble in water, alcohol, or other similar liquids. However, mercury forms solutions, as it dissolves other metals. On the other hand, there are many substances found in nature which are so very slightly soluble in water, that in ordinary practice they may be considered as insoluble (for example, barium sulphate). For the comprehension of that general plan according to which a change of state of substances (combined or dissolved, solid, liquid, or gaseous)

Substances which are easily soluble in water bear a certain resemblance to it. Thus sugar and salt in many of their superficial features remind one of ice. Metals, which are not soluble in water, have no points in common with it, whilst on the other hand they dissolve each other in a molten state, forming alloys, just as oily substances dissolve each other; for example, tallow is soluble in petroleum and in olive oil, although they are all insoluble in water. From this it is evident that the *analogy of substances forming a solution* plays an important part, and as aqueous and all other solutions are liquids, there is good reason to believe that in the process of solution solid and gaseous substances change in a physical sense, passing into a liquid state. These considerations elucidate many points of solution—as, for instance, the variation of the co-efficient of solubility with the temperature and the evolution or absorption of heat in the formation of solutions.

The solubility—that is, the quantity of a substance necessary for saturation—*varies with the temperature*, and, further, with an increase in temperature the solubility of solid substances generally increases, and that of gases decreases; this might be expected, as solid substances by heating, and gases by cooling, approach to a liquid or dissolved state.²³ A graphic method is often employed to express the variation of solubility with temperature. On the axes of abscissæ or on a horizontal line, temperatures are marked out and perpendiculars are raised corresponding with each temperature, whose length is determined by the solubility of the salt at that temperature expressing, for instance, one part by weight of a salt in 100 parts of water by one unit of length, such as a millimetre. By joining the summits of the perpendiculars, a curve is obtained which expresses the degree of solubility at different temperatures. For solids, the curve is generally an ascending one—i.e., recedes from the horizontal line with the rise in temperature. These curves clearly show by their inclination the degree of rapidity of increase in solubility with the temperature. Having determined several points

takes place, it is very important to make a distinction at this boundary line (on approaching zero of decomposition, volatility, or solubility) between an insignificant amount and zero, but the present methods of research and the data at our disposal at the present time do not yet touch such questions. It must be remarked, besides, that water in a number of cases does not dissolve a substance as such, but acts on it chemically and forms a soluble substance. Thus glass and many rocks, especially if taken as powder, are chemically changed by water, but are not directly soluble in it.

²³ Beilby (1883) experimented on paraffin, and found that one cubic decimetre of solid paraffin at 21° weighed 874 grams, and when liquid, at its melting-point 38°, 783 grams, at 49°, 775 grams, and at 60°, 767 grams, from which the weight of a litre of liquefied paraffin would be 795·4 grams at 21° if it could remain liquid at that temperature. By dissolving solid paraffin in lubricating oil at 21° Beilby found that 795·6 grams occupy one cubic decimetre, from which he concluded that the solution contained liquefied paraffin.

of a curve—that is, having made a determination of the solubility for several temperatures—the solubility at intermediary temperatures may be determined from the sinuosity and form of the curve so formed; in this way the empirical law of solubility may be followed.²⁴ The results of research have shown that the solubility of certain salts—as, for example, common table salt—varies comparatively little with the temperature; whilst for other substances the solubility increases by equal amounts for equal increments of temperature. So, for example, for the saturation of

²⁴ Gay-Lussac was the first to have recourse to such a graphic method of expressing solubility, and he considered, in accordance with the general opinion, that by joining up the summits of the ordinates in one harmonious curve it is possible to express the entire change of solubility with the temperature. Now, there are many reasons for doubting the accuracy of such an admission, for there undoubtedly are critical points in curves of solubility (for example, of sodium sulphate, as shown further on), and it may be that definite compounds of dissolved substances with water, in decomposing within known limits of temperature, give critical points more often than would be imagined; it may even be, indeed, that instead of a continuous curve, solubility should be expressed—if not always, then not unfrequently—by straight or broken lines. According to Ditte, the solubility of sodium nitrate, NaNO_3 , is expressed by the following figures per 100 parts of water:—

0°	4°	10°	15°	21°	29°	36°	51°	68°
66·7	71·0	76·3	80·6	85·7	92·9	99·4	13·6	125·1

According to my opinion (1881), these data should be expressed with exactitude by a straight line, $67·5 - 0·87t$, which entirely agrees with the results of experiment. According to this the figure expressing the solubility of the salt at 0° exactly coincides with the composition of a definite chemical compound— $\text{NaNO}_3, 7\text{H}_2\text{O}$. The experiments made by Ditte showed that all saturated solutions between 0° and $-15·7$ have such a composition, and that at the latter temperature the solution completely solidifies into one homogeneous whole. Ditte shows, in the first place, that the solubility of sodium nitrate is expressed by a broken straight line, and, in the second place, confirms the idea, which I had already traced, that in solutions we have definite chemical compounds in a state of dissociation. In recent times (1888) Étard discovered a similar phenomenon in many of the sulphates. Brandes, in 1830, shows a diminution in solubility below 100° for manganese sulphate. The percentage by weight (*i.e.*, per 100 parts of the solution, and not of water) of saturation for ferrous sulphate, FeSO_4 , from -2° to $+65 = 13·5 + 0·3784t$ —that is, the solubility of the salt increases. The solubility remains constant from 65° to 98° (according to Brandes the solubility then increases; this divergence of opinion requires proof), and from 98° to 150° it falls as $= 104·35 - 0·6685t$. Hence, at about $+156^\circ$ the solubility should = 0, and this has been confirmed by experiment. I observe, on my side, that Étard's formula gives 38·1 p.c. of salt at 65° and 38·8 p.c. at 92°, and this maximum amount of salt in the solution very nearly corresponds with the composition $\text{FeSO}_4, 14\text{H}_2\text{O}$, which requires 37·6 p.c. Thus, in this case, as in that of sodium nitrate, the formation of a definite solution may be presupposed. From what has been said, it is evident that the data concerning solubility require a new method of investigation, which, in the first place, should have in view the entire scale of solubility—from the formation of completely solidified solutions (cryohydrates, which we shall speak of presently) to the separation of salts from their solutions, if this is accomplished at a higher temperature (for manganese and cadmium sulphates there is an entire separation, according to Étard), or to the formation of a constant solubility (for potassium sulphate the solubility, according to Étard, remains constant from 163° to 220° and equals 24·9 p.c.); and, in the second place, should endeavour to apply the conception of definite compounds existing in solutions to constant and critical solutions, corresponding with a maximum of solubility or of its limits. From these aspects solution should present a new and particular interest.

100 parts of water by potassium chloride there is required at 0° , 29.2 parts, at 20° , 34.7, at 40° , 40.2, at 60° , 45.7 ; and so on, for every 10° the solubility increases by 2.75 parts by weight of the salt. Therefore the solubility of potassium chloride in water may be expressed by a direct equation : $a = 29.2 + 0.275t$, where a represents the solubility at t° . For other salts, more complicated equations are required. For example, for nitre : $a = 13.3 + 0.574t + 0.01717t^2 + 0.0000036t^3$, which shows that when $t = 0^{\circ}$ $a = 13.3$, when $t = 10^{\circ}$ $a = 20.8$, and when $t = 100^{\circ}$ $a = 246.0$.

Curves of solubility give the means of judging with accuracy the *amount of a salt separated* by the cooling to a known extent of a solution saturated at a given temperature. For instance, if 200 parts of a solution of potassium chloride in water saturated at a temperature of 60° be taken, and it be asked how much of the salt will be separated by cooling the solution to 0° , if its solubility at $60^{\circ} = 45.7$ and at $0^{\circ} = 29.2$? The answer is obtained in the following manner : At 60° a saturated solution contains 45.7 parts of potassium chloride per 100 parts by weight of water, consequently 145.7 parts by weight of the solution contains 45.7 parts, or, by proportion, 200 parts by weight of the solution contains 62.7 parts of the salt. The amount of salt remaining in solution at 0° is calculated as follows : In 200 grams taken there will be 137.3 grams of water ; consequently, this amount of water is capable of holding only 40.1 grams of the salt, and therefore in lowering the temperature from 60° to 0° there should separate from the solution $62.7 - 40.1 = 22.6$ grams of the dissolved salt.

The difference in the solubility of salts, &c., with a rise or fall of temperature is often taken advantage of, especially in technical work, for the separation of salts in intermixture from each other. Thus a mixture of potassium and sodium chlorides (this mixture is met with in nature at Stassfurt) is separated from a saturated solution by subjecting it alternately to boiling (evaporation) and cooling. The sodium chloride separates out in proportion to the amount of water expelled from the solution by boiling, and is removed, whilst the potassium chloride separates out on cooling, as the solubility of this salt rapidly decreases with a lowering in temperature. Nitre, sugar, and many other soluble substances are purified (refined) in a similar manner.

Although in the majority of cases the solubility of solids increases with the temperature, yet just as there are substances whose volume diminishes with a rise in temperature (for example, water from 0° to 4°), so there are not a few solid substances whose solubilities fall on heating. Glauber's salt, or sodium sulphate, historically forms a particu-

larly instructive example of the case in question. If this salt be taken in an ignited state (deprived of its water of crystallisation), then its solubility in 100 parts of water varies with the temperature in the following manner : at 0° , 5 parts of the salt form a saturated solution ; at 20° , 20 parts of the salt, at 33° more than 50 parts. As will be seen, the solubility increases with the temperature, as is the case with nearly all salts ; but starting from 33° it suddenly diminishes, and at a temperature of 40° , there dissolves less than 50 parts of the salt, at 60° only 45 parts of the salt, and at 100° about 43 parts of the salt in 100 parts of water. This phenomenon may be traced to the following facts : Firstly, that this salt forms various compounds with water, as will be afterwards explained ; secondly, that at 33° the compound $\text{Na}_2\text{SO}_4 + 10\text{H}_2\text{O}$ formed from the solution at lower temperatures, melts ; and thirdly, that on evaporation at a temperature above 33° there separates out an anhydrous salt, Na_2SO_4 . It will be seen from this example how complicated such a seemingly simple phenomenon as solution really is ; and all data concerning solutions lead to the same conclusion. This complexity becomes evident in investigating the *heat of solution*. If solution consisted of a physical change only, then in the solution of gases there would be evolved—and in the solution of solids, there would be absorbed—so much heat as answers to the change of state ; but in reality a large amount of heat is always evolved in solution, depending on the fact that in the process of solution there is accomplished an act of chemical combination, accompanied by an evolution of heat. Seventeen grams of ammonia (this weight corresponds with its formula NH_3), in passing from a gaseous into a liquid state, evolve 4,400 units of heat (latent heat) ; that is, the quantity of heat necessary to raise the temperature of 4,400 grams of water 1° . The same quantity of ammonia, in dissolving in an excess of water, evolves twice as much heat—namely 8,800 units—showing that the combination with water is accompanied by the evolution of 4,400 units of heat. Further, the chief part of this heat is separated in dissolving in small quantities of water, so that 17 grams of ammonia, in dissolving in 18 grams of water (this weight corresponds with its composition H_2O), evolve 7,535 units of heat, and therefore the formation of the solution $\text{NH}_3 + \text{H}_2\text{O}$ evolves 3,135 units of heat beyond that due to the change of state. As in the solution of gases, the heat of liquefaction (of physical change of state) and of chemical combination with water are both positive (+), therefore in the *solution of gases* in water a *heat effect* is always observed. This phenomenon is different in the solution of solid substances, because their passage from a solid to a liquid state is accompanied by an absorption

of heat (negative, — heat), whilst their chemical combination with water is accompanied by an evolution of heat (+ heat); consequently, their sum may either be a cooling effect, when the positive (chemical) portion of heat is less than the negative (physical), or it may be, on the contrary, a heating effect. This is actually the case. 124 grams of sodium thiosulphate (employed in photography) $\text{Na}_2\text{S}_2\text{O}_3 \cdot 5\text{H}_2\text{O}$ in melting (at 18°) absorbs 9,700 units of heat, but in dissolving in a large quantity of water at the ordinary temperature it absorbs 5,700 units of heat, which shows the evolution of heat (about + 4,000 units), notwithstanding the cooling effect observed in the process of solution, in the act of the chemical combination of the salt with water.²⁵ But in

²⁵ The latent heat of fusion is determined at the temperature of fusion, whilst solution takes place at the ordinary temperature, and one must think that at this temperature the latent heat would be different, just as the latent heat of evaporation varies with the temperature (see note 11, p. 52). Besides which, in solution there occurs a disunion (disintegration) of the particles of both the solvent and the substance dissolved, which in its mechanical aspect resembles evaporation, and which therefore must consume much heat. The heat emitted during the solution of a solid must be therefore considered (Personne) as composed of three factors—(1) positive, the effect of combination; (2) negative, the effect of transference into a liquid state; and (3) negative, the effect of disintegration. In the solution of a liquid by a liquid the second factor is removed; and therefore if the heat evolved in combination is greater than that absorbed in disintegration a heating effect is observed, and in the reverse case a cooling effect; and, indeed, sulphuric acid, alcohol, and many liquids evolve heat in dissolving in each other. But the solution of chloroform in carbon bisulphide (Bussy and Binet), or of phenol (or aniline) in water (Alexéeff), produces cold. In the solution of a small quantity of water in acetic acid (Abasheff), or hydrocyanic acid (Bussy and Binet), or amyl alcohol (Alexéeff), cold is produced, whilst in the solution of these substances in an excess of water heat is evolved.

The fullest information concerning the solution of liquids in liquids has been gathered by W. T. Alexéeff (1883–1885), still these data are far from being sufficient to resolve the mass of problems respecting this subject. He showed that two liquids which dissolve in each other, intermix together in all proportions at a certain temperature. Thus the solubility of phenol, $\text{C}_6\text{H}_5\text{O}$, in water, and the converse, is limited up to 70° , whilst above this temperature they intermix in all proportions. This is seen from the following figures, where p is the percentage amount of phenol and t the temperature at which the solution becomes cloudy—that is, that at which it is saturated:—

$p = 7.12$	10.20	15.31	26.15	28.55	36.70	48.86	61.15	71.97
$t = 1^\circ$	45°	60°	67°	67°	67°	65°	53°	20°

It is exactly the same in the solution of benzene, aniline, and other substances in molten sulphur. Alexéeff discovered a similar complete intermixture for solutions of secondary butyl alcohol in water at about 107° ; at lower temperatures the solubility is not only limited, but between 50° and 70° it is at its minimum, both for solutions of the alcohol in water and for water in the alcohol; and at a temperature of 5° both solutions exhibit a fresh change in their scale of solubility, so that a solution of the alcohol in water which is saturated between 5° and 40° will become cloudy when heated to 60° . In the solution of liquids in liquids, Alexéeff observed a lowering in temperature (an absorption of heat) and an absence of change in specific heat (calculated for the mixture) much more frequently than had been done by previous observers. As regards his affir-

most cases solid substances in dissolving in water evolve heat, notwithstanding the passage into a liquid state, which indicates so considerable an evolution of (+) heat in the act of combination with water that it exceeds the absorption of (−) heat dependent on the passage into a liquid state. Thus, for instance, calcium chloride, CaCl_2 , magnesium sulphate, MgSO_4 , and many other salts in dissolving evolve heat; for example, 60 grams of magnesium sulphate evolves about 10,000 units of heat. Therefore, *in the solution of solid bodies* there is produced either a cooling²⁶ or a heating²⁷ effect, according to the difference of the reacting affinities. When they are considerable—that is, when water is with difficulty separated from the resultant solution, and only with a rise of temperature (such substances absorb water)—then much heat is evolved in the process of solution, just as in many reactions of direct combination, and therefore a considerable heating of the solution is observed. Of such a kind, for instance, is the solution

mation (in the sense of a mechanical and not a chemical representation of solutions) that substances in solutions preserve their physical states (as gases, liquids, or solids), it is very doubtful, for it would necessitate admitting the presence of ice in water or its vapour. His theory starts from an unsupported hypothesis—which is, however, held by many—that the sizes (weights) of the molecules of one and the same substance are very different in different physical states. At present the weight of gaseous molecules is determined from the freezing of solutions (see later), and therefore it must either be admitted that solutions contain gaseous molecules or else that the weight of liquid molecules is the same as that of gaseous molecules, which is far simpler and more probable.

From what has been said above, it will be clear that even in so very simple a case as solution, it is impossible to calculate the heat emitted by chemical action alone, and that the chemical process cannot be separated from the physical and mechanical.

²⁶ The cooling effect produced in the solution of solids (and also in the expansion of gases and in evaporation) is applied to the *production of low temperatures*. Ammonium nitrate is very often used for this purpose; in dissolving in water it absorbs 77 units of heat per each part by weight. On evaporating the solution thus formed, the solid salt is re-obtained. The application of the various *freezing mixtures* is based on the same principle. Snow or broken ice frequently enters into the composition of these *mixtures*, advantage being taken of its latent heat of fusion in order to obtain the lowest possible temperature (without altering the pressure or employing heat, as in other methods of obtaining a low temperature). For laboratory work recourse is most often had to a mixture of three parts of snow and one part of common salt, which causes the temperature to fall from 0° to -21°C . Potassium thiocyanate, KCNS , mixed with water ($\frac{3}{4}$ by weight of the salt) gives a still lower temperature. By mixing ten parts of crystalline calcium chloride, $\text{CaCl}_2 \cdot 6\text{H}_2\text{O}$, with seven parts of water, the temperature may even fall from 0° to -55° .

²⁷ The heat which is evolved in solution, or even in the dilution of solutions, is also sometimes made use of in practice. Thus caustic soda (NaHO), in dissolving or on the addition of water to a strong solution of it, evolves so much heat that it can replace fuel. In a steam boiler, which has been previously heated to the boiling point, another boiler is placed containing caustic soda, and the exhaust steam is made to pass through the latter; the formation of steam then goes on for a somewhat long period of time without any other heating. Norton makes use of this for smokeless street boilers.

of sulphuric acid (oil of vitrol H_2SO_4), and of caustic soda (NaHO), &c., in water.²⁸

Solution exhibits a reverse reaction ; that is to say, if the water be expelled from a solution, the substance originally taken is re-obtained. But it must be borne in mind that the expulsion of the water taken for solution is not accomplished with equal facility throughout, because water has different degrees of chemical affinity for the substance dissolved. Thus, if a solution of sulphuric acid, which mixes with water in all proportions, be heated, it will be found that very different degrees of heat are required to expel the water. When it is in a large

²⁸ The temperatures obtained by mixing monohydrated sulphuric acid, H_2SO_4 , with different quantities of water, are shown on the lowest curve in fig. 17, the relative proportions of both substances being expressed in percentages by weight along the horizontal axis.




FIG. 17.—Curves expressing the contraction, quantity of heat, and rises of temperature produced by mixing sulphuric acid with water. Percentage of H_2SO_4 is given along the axis of abscissae.

zontal axis. The greatest rise of temperature is 149° . It corresponds with the greatest evolution of heat (given on the middle curve) corresponding with a definite volume (100 c. c.) of the solution produced. The top curve expresses the degree of contraction, which also corresponds with 100 volumes of the solution produced. The greatest contraction, as also the greatest rise of temperature, corresponds with the formation of a trihydrate, $\text{H}_2\text{SO}_4 \cdot 2\text{H}_2\text{O}$ ($= 73.1$ p.c. H_2SO_4), which very likely repeats itself in a similar form in other solutions, although all the phenomena (of contraction, evolution of heat, and rise of temperature) are very complex and are dependent on many circumstances. One would think, however, judging from the above examples, that all other influences are feebler in their action than chemical attraction, especially when it is so considerable as between sulphuric acid and water.

excess, water already begins to come off at a temperature slightly above 100° , but if it be in but a small proportion there is such a relation between it and the sulphuric acid that at 120° , 150° , 200° , and even at 300° , water is still held by the sulphuric acid. The bond between the remaining quantity of water and the sulphuric acid is evidently stronger than the bond between the sulphuric acid and the excess of water. The force acting in solutions is consequently of different intensity, starting from so feeble an attraction that the properties of water—as, for instance, its power of evaporation—are but very little changed, and ending with cases of strong attraction between the water and the substance dissolved in or chemically combined with it. In consideration of the very important signification of the phenomena, and of the cases of the breaking up of solutions with separation of water or of the substance dissolved from them, we shall further discuss them separately, after having acquainted ourselves with certain peculiarities of the solution of gases and of solid bodies.

The solubility of gases, which is usually measured by the volume of gas²⁹ (at 0° and 760 mm. pressure) per 100 volumes of water, varies not only with the nature of the gas (and also of the solvent), and with the temperature, but also with the pressure, because gases themselves change their volumes considerably with the pressure. As might be expected, (1) gases which are easily liquefied (by pressure and cold) are more soluble than those which are liquefied with difficulty. Thus, in 100 volumes of water there dissolve at 0° and 760 mm. only two volumes of hydrogen, three volumes of carbonic oxide, four volumes of oxygen, &c., for these are gases which are liquefied with difficulty; whilst

²⁹ If a volume of gas v be measured under a pressure of h mm. of mercury (at 0°) and at a temperature t° Centigrade, then, according to the laws of Boyle, Mariotte, and of Gay-Lussac combined, its volume at 0° and 760 mm. will equal the product of v into 760 divided by the product of h into $1 + at^{\circ}$, where a is the co-efficient of expansion of gases, which is equal to 0.00367. The weight of the gas will be equal to its volume at 0° and 760 mm. multiplied by its density referred to air and by the weight of one volume of air at 0° and 760 mm. The weight of one litre of air under these conditions being 1.293 grams. If the density of the gas be given in relation to hydrogen this must be divided by 14.4 to bring it in relation to air. If the gas be measured when saturated with aqueous vapour, then it must be reduced to the volume and weight of the gas when dry, according to the rules given in Note 1. If the pressure be determined by a column of mercury having a temperature t , then by dividing the height of the column by $1 + 0.00018t$ the corresponding height at 0° is obtained. If the gas be enclosed in a tube in which a liquid stands above the level of the mercury, the height of the column of the liquid being = H and its density = D , then the gas will be under a pressure which is equal to the barometric pressure less $\frac{HD}{13.59}$, where 13.59 is the density of mercury. By

these methods the *quantity of a gas* is determined, and its observed volume reduced to normal conditions or to parts by weight. The physical data concerning vapours and gases must be continually kept in sight in dealing with and measuring gases. The student must become perfectly familiar with the calculations relating to gases.

there dissolve 180 volumes of carbonic anhydride, 130 of nitrous oxide, and 437 of sulphurous anhydride, for these are gases which are rather easily liquefied. (2) The solubility of a gas is diminished by heating, which is easy to understand from what has been said previously—that the elasticity of a gas becomes greater as it is further removed from a liquid state. Thus 100 volumes of water at 0° dissolve 2.5 volumes of air, and at 20° only 1.7 volumes. For this reason cold water, when brought into a warm room, parts with a portion of the gas dissolved in it.³⁰ (3) The quantity of the gas dissolved varies directly with the pressure. This rule is called the *law of Henry and Dalton*, and is applicable to those gases which are little soluble in water. Therefore a gas is separated from its solution in water in a vacuum, and water saturated with a gas under great pressure parts with it if the pressure be diminished. Thus many mineral springs are saturated underground with carbonic anhydride under the great pressure of the column of water above them. On coming to the surface, the water of these springs boils and foams in giving up the excess of dissolved gas. Sparkling wines and aerated waters are saturated under pressure with the same gas. They hold the gas so long as they are in a well-corked vessel. When the cork is removed and the liquid comes in contact with air at a less pressure, part of the gas, unable to remain in solution at a lesser pressure, is separated as foam with the hissing sound familiar to all. It must be remarked that the law of Henry and Dalton belongs to the class of *approximate laws*, like the laws of gases (Gay-Lussac's and Mariotte's) and many others—that is, it expresses only a portion of a complex phenomenon, the limit towards which the phenomenon aims. The matter is rendered complicated from the influence of the degree of solubility and of affinity of the dissolved gas for water. Gases which are little soluble—for instance, hydrogen, oxygen, and nitrogen—follow the law of Henry and Dalton the most closely. Carbonic anhydride exhibits a decided deviation from the law, as is seen from the determinations of Wroblewski (1882). He showed that at 0° a cubic centimetre of water absorbs 1.8 cubic centimetres of the gas under a pressure of one atmosphere; under 10 atmospheres, 16 cubic centimetres (and not 18, as it should be according to the law); under 20 atmospheres,

³⁰ According to Bunsen, 100 volumes of water under a pressure of one atmosphere absorb the following volumes of gas (measured at 0° and 760 mm.) :—

	1	2	3	4	5	6	7	8	9	10
0°	4.11	2.03	1.93	179.7	3.3	130.5	437.1	688.6	5.4	104960
10°	3.25	1.61	1.93	118.5	2.6	92.0	358.6	513.8	4.1	81280
20°	2.84	1.40	1.93	90.1	2.3	67.0	290.5	362.2	3.5	65400

1, oxygen; 2, nitrogen; 3, hydrogen; 4, carbonic anhydride; 5, carbonic oxide; 6, nitrous oxide; 7, hydrogen sulphide; 8, sulphurous anhydride; 9, marsh gas; 10, ammonia.

26.6 cubic centimetres (instead of 36) ; and under 30 atmospheres, 33.7 cubic centimetres.³¹ However, as the researches of Sechenoff show, the absorption of carbonic anhydride within certain limits of change of pressure, and at the ordinary temperature, by water—and even by solutions of salts which are not chemically changed by it, or do not form compounds with it—very closely follows the law of Henry and Dalton, so that the chemical bond between this gas and water is so feeble that the breaking up of the solution with separation of the gas is accomplished by a decrease of pressure alone.³² The case is different if a considerable affinity exists between the dissolved gas and water. Then it might even be expected that the gas would not be entirely separated from water in a vacuum, as should be the case with gases according to the law of Henry and Dalton. Such gases—and, in general, all which are very soluble—exhibit a distinct deviation from the law of Henry and Dalton. As examples, ammonia and hydrochloric acid gas may be taken. The former is separated by boiling and decrease of pressure, while the latter is not, but they both deviate distinctly from the law.

Pressure in mm. of mercury	Ammonia dissolved in 100 grams of water at 0°	Hydrochloric acid gas dissolved in 100 grams of water at 0°
	Grams	Grams
100	28.0	65.7
500	69.2	78.2
1,000	112.6	85.6
1,500	165.6	—

It will be remarked, for instance, from this table that whilst the pres-

³¹ These figures show that the co-efficient of solubility decreases with an increase of pressure, notwithstanding that the carbonic anhydride approaches a liquid state. And, indeed, liquefied carbonic anhydride does not intermix with water, and does not exhibit a rapid increase in solubility at its temperature of liquefaction. This indicates, in the first place, that solution does not consist in liquefaction, and in the second place that the solubility of a substance is determined by a peculiar attraction of water for the substance dissolving. Wroblewski even considers it possible to admit that a dissolved gas retains its properties as a gas. This he deduces from his experiments, which showed that the rate of diffusion of gases in a solvent is, for gases of different densities, inversely proportional to the square roots of their densities, just as the velocities of movement of gaseous molecules (see Note 34 on p. 80). Wroblewski showed the affinity of water, H_2O , for carbonic anhydride, CO_2 , from the fact that on expanding moist compressed carbonic anhydride (compressed at 0° under a pressure of 10 atmospheres) he obtained (a fall in temperature takes place from the expansion) a very unstable definite crystalline compound, $CO_2 \cdot 8H_2O$.

³² As, according to the researches of Roscoe and his collaborators, ammonia exhibits a considerable deviation at low temperatures from the law of Henry and Dalton, whilst at 100° the deviation is small, it would appear that the dissociating influence of temperature tells on all gaseous solutions; that is, at high temperatures, the solutions of all gases will follow the law, and at lower temperatures there will in all cases be a deviation from it.

sure increased 10 times, the solubility of ammonia only increased $4\frac{1}{2}$ times.

A number of examples of such cases of the absorption of gases by liquids might be cited which do not in any way, even approximately, agree with the laws of solubility. Thus, for instance, carbonic anhydride is absorbed by a solution of caustic potash in water, and if there be sufficient caustic potash it is not separated from the solution by a decrease of pressure. This is a case of more intimate chemical combination. A less completely studied, but similar and clearly chemical, correlation appears in certain cases of the solution of gases by water, and we shall afterwards take an example of this in the solution of hydrogen iodide; but first we will stop to consider a remarkable application of the law of Henry and Dalton³³ in the case of the solution of a mixture of two gases, and this we must do all the more because the phenomena which then take place cannot be foreseen without a clear theoretical representation of the nature of gases.³⁴

³³ The ratio between the pressure and the amount of gas dissolved was discovered by Henry in 1805, and Dalton in 1807 pointed out the adaptability of this law to cases of gaseous mixtures, introducing the conception of partial pressures which is absolutely necessary for a right comprehension of Dalton's law. The conception of partial pressures essentially enters into that of the diffusion of vapours in gases (footnote 1); for the pressure of damp air is equal to the sum of the pressures of dry air and of the aqueous vapour in it, and it is admitted as a sequence to Dalton's law that evaporation in dry air takes place as in a vacuum. It is, however, necessary to remark that the volume of a mixture of two gases (or vapours) is only approximately equal to the sum of the volumes of its constituents (the same, naturally, also refers to their pressures)—that is to say, in mixing gases a change of volume occurs, which, although small, is quite apparent when carefully measured. For instance, in 1888 Brown showed that on mixing various volumes of sulphurous anhydride (SO_2) with carbonic anhydride (at equal pressures of 760 mm. and equal temperatures) a decrease of pressure of 3.9 millimetres of mercury was observed. The possibility of a chemical action in similar mixtures is evident from the fact that equal volumes of sulphurous and carbonic anhydrides at -19° form, according to Pictet's researches in 1888, a liquid having the signs of a chemical compound, or a solution similar to that given when sulphurous anhydride and water combine into an unstable chemical whole.

³⁴ The origin of the now generally-accepted kinetic theory of gases, according to which they are animated by a rapid progressive movement, is very ancient (Bernoulli and others in the last century had already developed a similar representation), but it was only generally accepted after the mechanical theory of heat had been established, and after the work of Krönig (1855), and especially after its mathematical side had been worked out by Clausius and Maxwell. The pressure, elasticity, diffusion, and internal friction of gases, the laws of Boyle, Mariotte, and of Gay-Lussac and Avogadro-Gerhardt are not only explained (deduced) by the kinetic theory of gases, but also expressed with perfect exactitude; thus, for example, the magnitude of the internal friction of different gases was foretold with exactitude by Maxwell, by applying the theory of probabilities to the concussion of gaseous particles. The kinetic theory of gases must therefore be considered as one of the most brilliant acquisitions of the latter half of the present century. The velocity of the progressive movement of the gaseous particles of a gas, one cubic centimetre of which weighs d grams, is found, according to the theory, to be equal to the square root of the product of $3pDg$ divided by d , where p is the pressure under which

The law of partial pressures is as follows :—The solubility of gases in intermixture with each other does not depend on the influence of the total pressure acting on the mixture, but on the influence of that portion of the total pressure which is due to the volume of each given gas in the mixture. Thus, for instance, if oxygen and carbonic anhydride were mixed in equal volumes and exerted a pressure of 760 millimetres,

d is determined expressed in centimetres of the mercury column, D the weight of a cubic centimetre of mercury in grams ($D=13\cdot59$, $\mu=76$, consequently the normal pressure = 1.033 grams on a sq. c. m.), and g the acceleration of gravity in centimetres ($g=980\cdot5$, at the sea level and long. 45° , = 981.92 at St. Petersburg; in general it varies with the longitude and altitude of the locality). Therefore, at 0° the velocity of hydrogen is 1,843, and of oxygen 461, metres per second. This is the average velocity, and (according to Maxwell and others) it is probable that the velocities of individual particles are different, that is, they occur in, as it were, different conditions of temperature, which is very important to take into consideration in the investigation of many phenomena proper to matter. It is evident from the above determination of the velocity of gases, that different gases at the same temperature and pressure have average velocities, which are inversely proportional to the square roots of their densities; this is also shown by direct experiment on the flow of gases through a fine orifice, or through a porous wall. This dissimilar velocity of flow for different gases is frequently taken advantage of in chemical researches (see Chap. II. and also Chap. VII. on the law of Avogadro-Gerhardt) in order to separate two gases having different densities and velocities. The difference of the velocity of flow of gases also determines the phenomenon cited in the following footnote for demonstrating the existence of an internal movement in gases.

If for a certain mass of a gas which fully and exactly follows the laws of Mariotte and Gay-Lussac the temperature t and the pressure p be simultaneously changed, then the entire change would be expressed by the equation $pv=C(1+at)$, or, what is the same, $pv=RT$, where $T=t+273$ and C and R are constants which vary not only with the units of measurement but with the nature of the gas and its mass. But as there are discrepancies from both the fundamental laws of gases (which will be spoken of in the following chapter), and as, on the one hand, a certain attraction between the gaseous molecules must be admitted, and on the other hand it must be acknowledged that the gaseous molecules themselves occupy a portion of a space, therefore for ordinary gases, within any considerable variation of pressure and temperature, recourse should be had to Van der Waal's formula—

$$\left(p + \frac{a}{v^2}\right) (v-p) = R(1-at)$$

where a is the true co-efficient of expansion of gases. As the actual co-efficient of expansion of air at the atmospheric pressure and between temperatures of 0° and $100^\circ=0\cdot00367$, when determined from the change of pressure (according to Regnault's data) and when determined from the change of volume = $0\cdot00368$ (according to Mendelëff and Kayander), and for other gases there is a discrepancy, although not a large one (see the following chapter), which is considerable at high pressures and for great densities, therefore that co-efficient of expansion should be taken which all gases have at low pressures. This quantity is approximately $0\cdot00367$.

The formula of Van der Waal has an especially important significance in the case of the passage of a gas into a liquid state, because the fundamental properties of both gases and liquids are equally well expressed, although only in their general features, by it.

The further development of the questions referring to the subjects here touched on, which are of especial interest for the theories of solutions, must be looked for in special memoirs and works on theoretical and physical chemistry. A small part of this subject will be partially considered in the footnotes of the following chapter.

then water would dissolve so much of each of these gases as would be dissolved if each separately exerted a pressure of half an atmosphere, and in this case, at 0° one cubic centimetre of water would dissolve 0.02 cubic centimetre of oxygen and 0.90 cubic centimetre of carbonic anhydride. If the pressure of a gaseous mixture equals h , and in n volumes of the mixture there be a volumes of a given gas, then its solution will proceed as though this gas were dissolved under a pressure $\frac{h \times a}{n}$. That portion of the pressure under influence of which the solution proceeds is termed the 'partial' pressure.

In order to represent to oneself the cause of the law of partial pressures, an explanation must be given of the fundamental properties of gases. Gases are elastic and disperse in all directions. All that is known of gases obliges one to think that these fundamental properties of gases are due to a rapid progressive movement, in all directions, which is proper to their smallest particles (molecules).³⁵ These molecules in impinging against an obstacle produce a pressure. The greater the number of molecules impinging against an obstacle in a given time, the greater the pressure. The pressure of a separate gas or of a gaseous mixture depends on the sum of the pressures of all the molecules, on the number of blows in a unit of time on a unit of surface, and on the mass and velocity (or the *vis viva*) of the impinging molecules. To the obstacle all molecules (although different in nature) are alike; it is submitted to a pressure due to the sum of their *vis viva*. But, in a chemical action such as the solution of gases, on the contrary, the

³⁵ Although the actual movement of gaseous molecules, which is acknowledged by the kinetic theory of gases, cannot be seen, yet its existence may be rendered evident by taking advantage of the difference in the velocities which undoubtedly belongs to different gases which are of different densities under equal pressures. The molecules of a light gas must move more rapidly than the molecules of a heavier gas in order to produce the same pressure. Let us take, therefore, two gases—hydrogen and air; the former is 14.4 times lighter than the latter, and hence the molecules of hydrogen must move almost four times more quickly than air (more exactly 3.8, according to the formula given in the preceding footnote). Consequently, if air occurs inside a porous cylinder and hydrogen outside, then in a given time the volume of hydrogen which succeeds in entering the cylinder will be greater than the volume of air leaving the cylinder, and therefore the pressure inside the cylinder will rise until the gaseous mixture (of air and hydrogen) attains an equal density both inside and outside the cylinder. If now the experiment be reversed and air surround the cylinder, and hydrogen be inside the cylinder, then more gas will leave the cylinder than enters it, and hence the pressure inside the cylinder will be diminished. In these considerations we have replaced the idea of the number of molecules by the idea of volumes. We shall learn afterwards that equal volumes of different gases contain an equal number of molecules (the law of Avogadro-Gerhardt), and therefore instead of speaking of the number of molecules we can speak of the number of volumes. If the cylinder be partially immersed in water the rise and fall of the pressure can be observed, and consequently the experiment can be rendered self-evident.

nature of the impinging molecules plays the most important part. In impinging against a liquid, a portion of the gas enters into the liquid itself, and is held by it so long as other gaseous molecules impinge against the liquid exert a pressure on it. As regards the solubility of a given gas, for the number of blows it makes on the surface of a liquid, it is immaterial whether other molecules of gases impinge side by side with it or not. Therefore, the solubility of a given gas will be proportional, not to the total pressure of a gaseous mixture, but to that portion of it which is due to the given gas separately. Further, the saturation of a liquid by a gas depends on the fact that the molecules of gases that have entered into a liquid do not remain at rest in it, although they enter in a harmonious kind of movement with the molecules of the liquid, and therefore they throw themselves off from the surface of the liquid (just like its vapour if the liquid be volatile). If in a unit of time an equal number of molecules penetrate into (leap into) a liquid and leave (or leap out of) a liquid, it is saturated. It is a case of mobile equilibrium, and not of rest. Therefore, if the pressure be diminished, the number of molecules departing from the liquid will exceed the number of molecules entering into the liquid, and a fresh state of mobile equilibrium only takes place under a fresh equality of the number of molecules departing from and entering into the liquid. Thus are explained the main features of the solution, and furthermore of that special (chemical) attraction (penetration and harmonious movement) of a gas for a liquid, which determines both the measure of solubility and the degree of stability of the solutions produced.

The consequences of the law of partial pressures are exceedingly numerous and important. All liquids in nature are in contact with the atmosphere. The atmosphere, as we shall afterwards see more fully, consists of an intermixture of gases, chiefly four in number—oxygen, nitrogen, carbonic anhydride, and aqueous vapour. 100 volumes of air contain, approximately, 78 volumes of nitrogen, and about 21 volumes of oxygen; the quantity of carbonic anhydride, by volume, does not exceed 0.05. Under ordinary circumstances, the quantity of aqueous vapour is much greater, but it varies with the moisture of the atmosphere. Consequently, the solution of nitrogen in a liquid in contact with the atmosphere will proceed under a partial pressure equal to $\frac{78}{100} \times 760$ mm. if the atmospheric pressure equal 760 mm.; consequently, under a pressure of 600 mm. of mercury, the solution of oxygen will proceed under a partial pressure of about 160 mm., and the solution of carbonic anhydride only under the very small pressure of 0.4 mm. Therefore, although the amount of nitrogen in air is

large, yet, as the solubility of oxygen in water is twice that of the nitrogen in water, the proportion of oxygen dissolved in water will be greater than its proportion in air. It is easy to calculate what quantity of each of the gases will be contained in water, and we will take the most simple case, and calculate what quantity of oxygen, nitrogen, and carbonic anhydride will be dissolved from air having the above composition at 0° and 760 mm. pressure. Under a pressure of 760 mm. 1 cubic centimetre of water dissolves 0.0203 cubic centimetre of nitrogen, or under the partial pressure of 600 mm. it will dissolve $0.0203 \times \frac{600}{760}$, or 0.0160 cubic centimetre; of oxygen $0.0411 \times \frac{600}{760}$, or 0.0086 cubic centimetre; of carbonic anhydride $1.8 \times \frac{0.4}{760}$ or 0.00095 cubic centimetre;

consequently, 100 cubic centimetres of water will contain at 0° altogether 2.55 cubic centimetres of atmospheric gases, and 100 volumes of air dissolved in water will contain about 62 p.c. of nitrogen, 34 p.c. of oxygen, and 4 p.c. of carbonic anhydride. The water of rivers, wells, &c., usually contains more carbonic anhydride. This proceeds from the oxidation of organic substances falling in the water. The amount of oxygen, however, dissolved in water appears to be actually about $\frac{1}{3}$ the dissolved gases, whilst air contains only $\frac{1}{5}$ of it by volume.

According to the law of partial pressures, whatever gas be dissolved in water will be expelled from the solution in an atmosphere of another gas. This depends on the fact that gases dissolved in water escape from it in a vacuum, because the pressure is nil. An atmosphere of another gas acts like a vacuum on a gas dissolved in water. Separation then proceeds, because the molecules of the dissolved gas no longer impinge upon the liquid, are not dissolved in it, and those previously held in solution depart from the liquid in virtue of their elasticity.³⁶ For the same

³⁶ Here there may be, properly speaking, two cases: either the atmosphere surrounding the solution may be limited, or it may be proportionally so vast as to be unlimited, like the earth's atmosphere. If a gaseous solution be brought into an atmosphere of another gas which is limited—for instance, as in a closed vessel—then a portion of the gas held in solution will be expelled, and thus pass over into the atmosphere surrounding the solution, and will evince its partial pressure. Let us imagine that water saturated with carbonic anhydride at 0° and under the ordinary pressure be brought into an atmosphere of a gas which is not absorbed by water; for instance, that 10 c.c. of an aqueous solution of carbonic anhydride be introduced into a vessel holding 10 c.c. of such a gas. The solution will contain 18 c.c. of carbonic anhydride. The expulsion of this gas goes on until a state of equilibrium is arrived at. The liquid will then contain a certain amount of carbonic anhydride, which is retained under the partial pressure of that gas which has been expelled. Now, how much gas will remain in the liquid and how much will pass over into the surrounding atmosphere? In order to solve this problem, let us suppose that x cubic centimetres of carbonic anhydride are retained in the solution. It is evident that the amount of carbonic anhydride which passed over into the surrounding atmosphere will be $18 - x$, and the total volume of gas will be $10 + 18 - x$ or $28 - x$ cubic centimetres. The partial pressure under

reason a gas may be entirely expelled from a gaseous solution by boiling—at least, in many cases when it does not form particularly stable compounds with water. In fact the surface of the boiling liquid will be occupied by aqueous vapour, and therefore all the pressure acting on the gas will belong to the aqueous vapour. Consequently, the partial pressure of the dissolved gas will be very inconsiderable. For this, and for no other reason, *a gas separates from a solution on boiling the liquid holding it*. At the boiling point of water the solubility of gases in water is still sufficiently great for a considerable quantity of a gas to remain in solution. The gas dissolved in the liquid is carried away, together with the aqueous vapour; if boiling be continued for a long time, then in the end all the gas will be separated.³⁷

which the carbonic anhydride is then dissolved will be (supposing that the common pressure remains constant the whole time) equal to $\frac{18-x}{28-x}$, consequently there is not in solution 18 c.c of carbonic anhydride (as would be the case were the partial pressure equal to the atmospheric pressure), but only $18 \frac{18-x}{28-x}$, which is equal to x , and consequently we obtain the equation $18 \frac{18-x}{28-x} = x$, hence $x = 8.69$. Again, where the atmosphere into which the gaseous solution is introduced is not only that of another gas but also unlimited, then the gas dissolved will, on passing over from the solution, diffuse itself through this atmosphere, and from its limitedness produce an infinitely small pressure in the unlimited atmosphere. Consequently, no gas can be retained in solution under this infinitely small pressure, and it will be entirely expelled from the solution. For this reason water saturated with a gas which is not contained in air, will be entirely deprived of the dissolved gas if left exposed to air. Water also passes off from a solution into the atmosphere, and it is evident that there might be such a case as a constant proportion between the quantity of water vaporised and the quantity of a gas expelled from a solution, so that not the gas alone, but the entire gaseous solution, would pass off. A similar case is exhibited in solutions which are not decomposed by heat (such as those of hydrogen chloride and iodide), as will afterwards be considered.

³⁷ However, in those cases when the variation of the co-efficient of solubility with the temperature is not sufficiently great, and when a known quantity of aqueous vapour and of the gas passes off from a solution at the boiling point, an atmosphere may be obtained having the same composition as the liquid itself. In this case the amount of gas passing over into such an atmosphere will not be greater than that held by the liquid, and therefore such a gaseous solution will distil over without change, and without altering its composition during the whole period of boiling or distillation. The solution will then represent, like a solution of hydriodic acid in water, a liquid which is not changed by distillation, while the pressure under which this distillation takes place remains constant. Thus in all its aspects solution presents gradations from the most feeble affinities to examples of intimate chemical combination. The amount of heat evolved in the solution of equal volumes of different gases is in distinct relation with these variations of stability and solubility of different gases. 22.3 litres of the following gases (at 760 mm. pressure) evolve the following number of (gram) units of heat in dissolving in a large mass of water; carbonic anhydride 5,600, sulphurous anhydride 7,700, ammonia 8,800, hydrochloric acid 17,400, and hydriodic acid 19,400. The two last-named gases, which are not expelled from their solution by boiling, evolve approximately twice as much heat as such gases as ammonia, which are separated from their solutions by boiling, whilst gases which are only slightly soluble evolve less heat than the latter gases.

It is evident that the conception of the partial pressures of gases should not only be applied to the formation of solutions, but also to all cases of chemical action of gases. Especially numerous are its applications to the physiology of respiration, for in these cases it is only the oxygen of the atmosphere that acts.³⁸

The solution of *solids*, whilst depending only in a small measure on the pressure under which solution takes place (because solids and liquids are almost incompressible), is very clearly dependent on the temperature. In the great majority of cases the solubility of solids in water increases with the temperature; and further, the rapidity of solution increases also. The latter is determined by the rapidity of diffusion of the solution formed into the remainder of the water. The solution of a solid in water, although it is as with gases, a physical passage into a liquid state, is determined, however, by its chemical affinity for water; which is particularly clear from the fact that in solution there occurs a diminution in volume, a change in the boiling point of water, a change in the tension of its vapour, in the freezing point, and in many similar properties. Were solution a physical, and not a chemical, phenomenon, it would naturally be accompanied by an increase and not by a diminution of volume, because generally in melting a solid increases in volume (its density diminishes). *Contraction* is the usual phenomenon accompanying solution, and takes place even in the addition of solutions to water,³⁹ and in the solution

³⁸ Among the numerous researches concerning this subject, certain results obtained by Paul Bert are cited in Chapter III., and here we will point out that Prof. Sechenoff, in his researches on the absorption of gases by liquids, very fully investigated the phenomena of the solution of carbonic anhydride in solutions of various salts, and arrived at many important results, which showed that, on the one hand, in the solution of carbonic anhydride in solutions of salts on which it is capable of acting chemically (for example, sodium carbonate, borax, ordinary sodium phosphate), there is not only an increase of solubility, but also a distinct deviation from the law of Henry and Dalton; and, on the other hand, that solutions of salts which are not acted on by carbonic anhydride (for example, the chlorides, nitrates, and sulphates) absorb less of it, by reason of the competition of the already dissolved salt, and follow the law of Henry and Dalton, but all the same show undoubted signs of a chemical action between the salt, water, and carbonic anhydride. Sulphuric acid (whose co-efficient of absorption is 92 vols. per 100), when diluted with water, absorbs less and less carbonic anhydride, until the hydrate $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$ (co-eff. of absorption then equals 66 vols.) is formed; then on further addition of water the solubility again rises until a solution of 100 p.c. of water is obtained.

³⁹ Kremers made this observation in the following simple form:—He took a narrow-necked flask, with a mark on the narrow part (like that on a litre flask which is used for accurately measuring liquids), poured water into it, and then inserted a funnel, having a fine tube which reached to the bottom of the flask. Through this funnel he carefully poured a solution of any salt, and (having removed the funnel) allowed the liquid to attain a definite temperature (in a water bath); he then filled the flask up to the mark with water. In this manner two layers of liquid were obtained, the heavy saline solution

of liquids in water,⁴⁰ just as happens in the combination of substances when evidently new substances are produced.⁴¹ The contraction which takes place in solution is, however, very small, a fact which depends on the small compressibility of solids and liquids, and on the insignificance of the compressing force acting in solution.⁴² The change of volume which takes place in the solution of solids and liquids, or the alteration in specific gravity⁴³ corresponding with it, depends on peculiarities of the dissolving substances, and of water, and, in the majority of cases, is not proportional to the quantity of the substance dis-

below and water above. The flask was then shaken in order to accelerate diffusion, and it was observed that the volume became less if the temperature remained constant. This can be proved by calculation, if the specific gravity of the solutions and water be known. Thus at 15° one c.c. of a 20 p.c. solution of common salt weighs 1.1500 grams, hence 100 grams occupy a volume of 86.96 c.c. As the sp.gr. of water at 15° = 0.99916, therefore 100 grams of water occupy a volume of 100.08 c.c. The sum of the volumes is 187.04 c.c. On mixing, 200 grams of a 10 p.c. solution are obtained. Its specific gravity is 1.0725 (at 15° and referred to water at its maximum density), hence the 200 grams will occupy a volume of 186.48 c.c. The contraction is consequently equal to 0.56 c.c.

⁴⁰ The contractions produced in the case of the solution of sulphuric acid in water are shown in the diagram Fig. 17 (page 76). Their maximum is 10.1 c.c. per 100 c.c. of the solution formed. A maximum contraction of 4.15 at 0°, 3.78 at 15°, and 3.50 at 30°, takes place in the solution of 46 parts by weight of anhydrous alcohol in 54 parts of water. This signifies that if, at 0°, 46 parts by weight of alcohol be taken per 54 parts by weight of water, then the sum of their separate volumes will be 104.15, and after mixing their total volume will be 100.

⁴¹ This subject will be considered later in this work, and we shall then see that the contraction produced in reactions of combination (of solids or liquids) is very variable in its amount, and that there are, although very rare, reactions of combination in which contraction does not take place, or when an increase of volume is produced.

⁴² The compressibility of solutions of common salt is less, according to Grassi, than that of water. At 18° the compression of water per million volumes = 48 vols. for a pressure of one atmosphere; for a 15 p.c. solution of common salt it is 32, and for a 24 p.c. solution 26 vols. Similar determinations were made by Brown (1887) for saturated solutions of sal ammoniac (38 vols.), alum (46 vols.), common salt (27 vols.), and sodium sulphate at +1°, when the compressibility of water = 47 per million volumes. This investigator also showed that substances which dissolve with an evolution of heat and with an increase in volume (as, for instance, sal-ammoniac) are partially separated from their saturated solutions by an increase of pressure (this experiment was especially convincing in the case of sal-ammoniac), whilst the solubility of substances which dissolve with an absorption of heat or diminution in volume increases, although very slightly, *with an increase of pressure*. Sorby observed the same phenomenon with common salt (1863).

⁴³ The most trustworthy data relating to the variation of the specific gravity of solutions with a change of their composition and temperature, are collected and discussed in my work cited in footnote 19. The practical (for the amount of a substance in solution is determined by the aid of the specific gravities of solutions, both in works and in laboratory practice) and the theoretical (for specific gravity can be more accurately observed than other properties, and because a variation in specific gravity governs the variation of many other properties) interest of this subject, besides the strict rules and laws to which it is liable, make one wish that this province of data concerning solutions may soon be enriched by further observations of as accurate a nature as possible. Their collection does not present any great difficulty, although requiring much time and attention.

solved,⁴⁴ showing the existence of a chemical action between the solvent and the substance dissolved which is of the same nature as in all other forms of chemical relation.⁴⁵

Although an alteration of the external pressure does not usually decompose solutions of solids, nevertheless the feeble development of

⁴⁴ Inasmuch as the degree of change exhibited in many properties on the formation of solutions, is not large, so, owing to the insufficient accuracy of observations, a proportionality between this change and a change of composition may, in a first rough approximation and especially within narrow limits of change of composition, easily be imagined in cases where it does not even exist. The conclusion of Michel and Kraft is particularly instructive in this respect; in 1854, on the basis of their incomplete researches, they supposed the increment of the specific gravity of solutions to be proportional to the increment of a salt in a given volume of a solution, which is only true for determinations of specific gravity which are exact to the second decimal place—an accuracy insufficient even for technical determinations. Accurate measurements do not confirm a proportionality either in this case or in many others where a ratio has been generally accepted; as, for example, for the rotatory power (with respect to the plane of polarisation) of solutions, and for their capillarity, &c. Nevertheless, such a method is not only still made use of, but even has its advantages when applied to solutions within a limited scope—as, for instance, very weak solutions, and for a first acquaintance with the phenomena accompanying solution, and also as a means for facilitating the application of mathematical analysis to the investigation of the phenomenon of solution. Judging by the results obtained in my researches on the specific gravity of solutions, I think that in many cases it would be nearer the truth to take the change of properties as proportional, not to the amount of a substance dissolved, but, to the product of this quantity and the amount of water in which it is dissolved; all the more so as many chemical relations vary in proportion to the reacting masses, and a similar ratio has been established for many phenomena of attraction studied by mechanics. This product is easily arrived at when the quantity of water in the solutions to be compared is constant, as is shown in investigating the fall of temperature in the formation of ice (*see* footnote 49, p. 90).

⁴⁵ All the different forms of chemical reaction may be said to take place in the process of solution. (1) *Combinations* between the solvent and the substance dissolved, which are more or less stable (more or less dissociated). This form of reaction is the most probable, and is that most often observed. (2) Reactions of *substitution* or of *double decomposition* between the molecules. Thus it may be supposed that in the solution of sal-ammoniac, NH_4Cl , the action of water produces ammonia, NH_4HO , and hydrochloric acid, HCl , which are dissolved in the water and simultaneously attract each other. As these solutions and many others do indeed exhibit signs which are sometimes indisputable of similar double decompositions (thus solutions of sal-ammoniac yield a certain amount of ammonia), it is probable that this form of reaction is more often met with than is generally thought. (3) Reactions of *isomerism* or *replacement* are also probably met with in solution, all the more as here molecules of different kinds come into intimate contact, and it is very likely that the configuration of the atoms in the molecules under these influences is somewhat different from what it was in its original and isolated state. One is led to this supposition especially from observations made on solutions of substances which rotate the plane of polarisation (and observations of this kind are very sensitive with respect to the atomic structure of molecules), because they show, for example (according to Schneider, 1881), that strong solutions of malic acid rotate the plane of polarisation to the right, whilst its ammonium salts in all degrees of concentration rotate the plane of polarisation to the left. (4) Reactions of *decomposition* under the influences of solution are not only rational of themselves, but have in recent years been recognised by Arrhenius, Ostwald, and others, particularly on the basis of electrolytical determinations. If a portion of the molecules of a solution occur in a condition of decomposition, the other portion may occur in a yet more complex state of combination,

the chemical affinities acting in solutions of solids becomes evident from those multifarious methods by which *their solutions are decomposed*, whether they be saturated or not. On heating (absorption of heat), on cooling, and by internal forces alone, aqueous solutions in many cases separate into their components or their definite compounds. The water contained in solutions is removed from them as vapour, or, by freezing, in the form of ice,⁴⁶ but the *tension of the vapour of water*⁴⁷ held in solution is less than that of water in a free

just as the velocity of the movement of different gaseous molecules may be far from being the same (*see* Note 84, p. 80).

It is, therefore, very probable that the reactions taking place in solution vary both quantitatively and qualitatively with the mass of water in the solution, and the great difficulty in arriving at a lasting decision on the question as to the nature of the chemical relations which take place in the process of solution will be understood, and if besides this the existence of a physical process, like the sliding between and interpenetration of two homogeneous liquids, be also recognised in solution, then the complexity of the problem as to the actual nature of solutions, which is now to the fore, appears in its true light. However, the efforts which are now being applied to the solution of this problem are so numerous and of such varied aspect that they will offer the coming investigators a vast mass of material towards the construction of a complete theory of solution.

For my part, I think that the study of the physical properties of solutions (and especially of weak ones) which now reigns, cannot give any fundamental and complete solution of the problem whatever (although it should add much to both the provinces of physics and chemistry), but that, parallel with it, should be undertaken the study of the influence of temperature, and especially of low temperatures, the application to solutions of the mechanical theory of heat, and the comparative study of the chemical properties of solutions. The beginning of all this is already established, but it is impossible to consider in so short an exposition of chemistry the further efforts of this kind which have been made up to the present date.

⁴⁶ If solutions are regarded as being in a state of dissociation (*see* footnote 19, p. 64) it would be expected that they would contain free molecules of water, which form one of the products of the decomposition of those definite compounds whose formation is the cause of solution. In separating as ice or vapour, water makes, with a solution, a heterogeneous system (made up of substances in different physical states) similar, for instance, to the formation of a precipitate or volatile substance in reactions of double decomposition.

⁴⁷ If the substance dissolved is non-volatile (like salt or sugar), or only slightly volatile, then the whole of the tension of the vapour given off belongs to the water, but if a solution of a volatile substance—for instance, a gas or a volatile liquid—evaporates, then only a proportion of the pressure belongs to the water, and the whole pressure observed consists of the sum of the pressures of the vapours of the water and of the substance dissolved. The majority of researches bear on the first case, which will be spoken of presently, and the observations of D. P. Konovoloff (1881) refer to the second case. He showed that in the case of two volatile liquids, mutually soluble in each other, forming two layers of saturated solutions (for example, ether and water, note 20, p. 66), both solutions have an equal vapour tension (in the case in point the tension of both is equal to 431 mm. of mercury at 19.8°). Further, he found that for solutions which are formed in all proportions, the tension is either greater (solutions of alcohol and water) or less (solutions of formic acid) than that which answers to the rectilinear change (proportional to the composition) from the tension of water to the tension of the substance dissolved; thus the tension, for example, of a 70 p.c. solution of formic acid is less, at all

state, and *the temperature of the formation of ice* from solutions is lower than 0° . Further, both the diminution of vapour tension and the lowering of the freezing point proceed, at least in dilute solutions, almost in proportion to the amount of a substance dissolved.⁴⁸ Thus, if per 100 grams of water there be in solution 1, 5, 10 grams of common salt (NaCl), then at 100° the vapour tension of the solutions decreases by 4, 21, 43 mm. of the barometric column, against 760 mm., or the vapour tension of water, whilst the freezing points are -0.58° , -2.91° , and -6.10° respectively. The above figures⁴⁹ are almost proportional

temperatures, than the tension of water and of formic acid itself. Thus, in this case the tension of a solution is never equal to the sum of the tension of the dissolving liquids, as Regnault already showed when he distinguished this case from that in which a mixture of liquids, which are insoluble in each other, evaporates. From this it is evident that a mutual action occurs in solution, which diminishes the vapour tensions proper to the individual substances, as would be expected on the supposition of the formation of compounds of the dissolving substances in solutions, because the elasticity then always diminishes.

⁴⁸ This amount is usually expressed by the weight of the substance dissolved per 100 parts by weight of water. Probably it would be better to express it by the quantity of the substance in a definite volume of the solution—for instance, in a litre. I speak in detail of the different methods of expressing the composition of solutions in the work mentioned in note 19, p. 64.

⁴⁹ The variation of the vapour tension of solutions has been investigated by many. The best known researches are those of Willner (1858–1860) and of Tamman (1887). The researches on the temperature of the formation of ice from various solutions are also very numerous; Blagden (1788), Rüchardt (1861), and De Coppet (1871) established the beginning, but this kind of investigation takes its chief interest from the work of Raoult, begun in 1882 on aqueous solutions, and afterwards continued for solutions in various other easily-frozen liquids—for instance, benzene, C_6H_6 (melts at 4.96°), acetic acid, $C_2H_4O_2$ (16.75°), and others. An especially important interest is attached to these investigations of Raoult on the lowering of the freezing point, because he took solutions of many well-known carbon-compounds and discovered a simple relation between the molecular weight of the substances and the temperature of crystallisation of the solvent, which enabled this kind of research to be applied to the investigation of the nature of substances. We shall meet with the application of Raoult's results later on, and at present will only cite the deduction arrived at from these results. The solution of one-hundredth part of that molecular gram weight which corresponds with the formula of a substance dissolved (for example, NaCl=58.5, C_2H_6O =46, &c.) in 100 parts of a solvent lowers the freezing point of its solution in water 0.185° , in benzene 0.49° , and in acetic acid 0.39° , or twice as much as with water. And as in weak solutions the fall of freezing point is proportional to the amount of the substance dissolved, it follows that the fall of freezing point for all other solutions may be calculated from this rule. So, for instance, the weight which corresponds with the formula of acetone, C_3H_6O , is 58; a solution containing 2.42, 6.22, and 12.35 grams of acetone per 100 grams of water forms ice (according to the determinations of Beckmann) at 0.770° , 1.930° , and 3.820° , and these figures show that with a solution containing 0.58 grams of acetone per 100 of water the fall of the temperature of the formation of ice will be 0.185° , 0.180° , and 0.179° . It must be remarked that the law of proportionality between the fall of temperature of the formation of ice, and the composition of a solution, is in general only approximate, and is only applicable to weak solutions.

We will here remark that the theoretical interest of this subject was strengthened on the discovery of the connection existing between the fall of tension, the fall of the

to the amounts of salt in solution (1, 5, and 10 per 100 of water). Furthermore, it has been shown by experiment that the ratio of the diminution of vapour tension to the vapour tension of water at different temperatures in a given solution is an almost constant quantity,⁵⁰ and

temperature of the formation of ice, of osmotic pressure (Van't Hoff, note 19), and of the electrical conductivity of solutions, and we will therefore supplement what we have already said on the subject by some short remarks on the method of investigating the phenomenon, and on its theoretical results.

In order to determine the *temperature of the formation of ice* (or of crystallisation of other solvents), a known solution is prepared and poured into a cylindrical vessel surrounded by a second similar vessel, leaving a layer of air between the two, which, being a bad conductor, prevents any rapid change of temperature. The bulb of a sensitive and corrected thermometer is immersed in the solution, and also a bent platinum wire for stirring the solution; the whole is then cooled (by immersing the apparatus in a freezing mixture), and the temperature at which ice begins to separate observed. If the temperature at first falls slightly lower, nevertheless, it becomes constant when ice begins to form. By then allowing the liquid to get just warm, and then again observing the temperature of the formation of ice, an exact determination may be arrived at. If there be a large mass of solution, the formation of the first crystals may be accelerated by dropping a small lump of ice into the solution already partially over-cooled. This only imperceptibly changes the composition of the solution. The observation should be made at the point of formation of only a very small amount of crystals, as otherwise the composition of the solution will become altered from their separation. Every precaution must be taken to prevent the access of moisture to the interior of the apparatus, which might also alter the composition of the solution or properties of the solvent (for instance, when using acetic acid).

The very great theoretical interest of these observations on the fall of the temperature of the formation of ice, which are essentially very simple, dates from the time when Van't Hoff (note 19) showed that their consequences are in complete accord with those derived from observations on osmotic pressure. These latter showed that a molecular (expressed by formulæ) quantity of a substance evinces an osmotic pressure in a solution, which is equal to the atmospheric pressure (when $i = 1$), or which is greater than it by i times. The magnitude i , determined from osmotic observations on aqueous solutions, is also obtained from observations on the fall of the temperature of the formation of ice, if the fall corresponding with a solution containing 1 gram of a substance per 100 parts water be multiplied by the molecular weight (according to the formula of the substance, and expressing the weight of a molecule) of the substance dissolved, and divided by 18.5. Thus from the above data for acetone, it is seen that with a solution containing 1 gram, the fall of temperature of the formation of ice equals 0.318° , and after multiplying by the molecular weight (58), and dividing by 18.5, we have $i = 1$. With sugar and many other substances (among salts, magnesium sulphate, for instance), with carbonic anhydride, &c., both methods give a figure which is nearly unity. For potassium and sodium chlorides, potassium iodide, nitre, and others, i is greater than 1 but less than 2; for sulphuric and hydrochloric acids, sodium and calcium nitrates, and others, i is nearly 2; for solutions of barium and magnesium chlorides, potassium carbonate and dichromate, i , according to both methods, is greater than 2 but less than 3. The further investigation of this subject should show whether these conclusions are entirely general, and would probably explain better than they do now those remarkable correlations which are arrived at with the present data.

⁵⁰ This fact, which was established by Gay-Lussac, Prinsep, and v. Babo, is confirmed by the latest observations, and enables us to express not only the fall of tension ($p - p'$) itself, but its ratio to the tension of water $\left(\frac{p - p'}{p}\right)$. It is to be remarked that in the absence of any chemical action, the fall of tension is either very small, or does not

that for every (dilute) solution the ratio between the diminution of vapour tension and of the freezing point is also a sufficiently constant quantity.⁵¹

The diminution of the vapour tension of solutions explains the rise in boiling point through the solution of solid non-volatile bodies in water. The temperature of a vapour is the same as that of the solution from which it is generated, and therefore it follows that the aqueous vapour given off from a solution will be superheated. A saturated solution of common salt boils at 108.4° , a solution of 335 parts of nitre in 100 parts of water at 115.9° , and a solution of 325 parts of potassium chloride in 100 parts of water at 179° , if the temperature of ebullition be determined by immersing the thermometer bulb in the liquid itself. This is another proof of the bond which exists between water and the substance dissolved. And this bond is seen still more clearly in those cases (for example, in the solution of nitric or formic acid in water) where the solution boils at a higher temperature than either water or the volatile substance dissolved in it. For this reason the solutions of certain gases—for instance, hydriodic or hydrochloric acid—boil above 100° .

The separation of ice from solutions⁵² explains both the phenomenon, well known to seamen, that the ice formed from salt water gives fresh water, and also the fact that by freezing, just as by evaporation, a solution is obtained which is richer in salts than before. This is taken advantage of in cold countries for obtaining a liquor from seawater, which is then evaporated for the extraction of salt.

On the removal of part of the water from a solution (by evaporation or the separation of ice), there should be obtained a saturated solution, and then the substance dissolved should separate out. Solutions saturated at a certain temperature should also separate out a corresponding part of the substance dissolved if they be reduced, by cooling,⁵³ to a

exist at all (note 33), and is not proportional to the quantity of the substance added. As a rule, the tension is then equal, according to the law of Dalton, to the sum of the tensions of the substances taken. Therefore, liquids which are insoluble in each other (for example, water and chloride of carbon) present a tension equal to the sum of their individual tensions, and therefore such a mixture boils at a lower temperature than the more volatile liquid (Magnus, Regnault).

⁵¹ If, in our example, the fall of tension be divided by the tension of water, a figure is obtained which is nearly 105 times less than the magnitude of the fall of temperature of formation of ice. This correlation was theoretically deduced by Goldberg, on the basis of the application of the mechanical theory of heat, and is repeated by many investigated solutions.

⁵² Fritzsche showed that solutions of certain colouring matters yield colourless ice, which clearly proves the passage of water only into a solid state, without any intermixture of the substance dissolved, although the possibility of the admixture in certain other cases cannot be denied.

⁵³ As the solubility of certain substances (for example, conine, cerium sulphate, and others) decreases with a rise of temperature (between certain limits—see, for example,

temperature at which the water can no longer hold the former quantity of the substance in solution. If this separation, by cooling a saturated solution or by evaporation, take place slowly, *crystals* of the substance dissolved are in many cases formed; and this is the method by which crystals of soluble salts are usually obtained. Certain solids very easily separate out from their solutions in perfectly-formed crystals, which may attain very large dimensions. Such are nickel sulphate, alum, sodium carbonate, chrome-alum, copper sulphate, potassium ferri-cyanide, and a whole series of other salts. The most remarkable circumstance in this is that many solids in separating out from an aqueous solution retain a portion of water, forming crystallised solid substances which contain water. A portion of the water previously in the solution remains in the separated crystals. The water which is thus retained is called the *water of crystallisation*. Alum, copper sulphate, Glauber's salt, and magnesium sulphate contain such water, but neither sal-ammoniac, nor table salt, nor nitre, nor potassium chlorate, nor silver nitrate, nor sugar, contains any water of crystallisation. One and the same substance may separate out from a solution with or without water of crystallisation, according to the temperature at which the crystals are formed. Thus common salt in crystallising from its solution in water at the ordinary or a higher temperature does not contain water of crystallisation. But if its separation from the solution takes place at a low temperature, namely below -5° , then the crystals contain 38 parts of water in 100 parts. Crystals of the same substance which separate out at different temperatures may contain different amounts of water of crystallisation. This proves to us that a solid dissolved in water may form various compounds with it, differing in their properties and composition, and capable of appearing in a solid separate form like many ordinary definite compounds. This is indicated by the numerous properties and phenomena connected with solutions, and gives reason for thinking that there exist in solutions themselves such compounds of

note 24), so these substances do not separate from their saturated solutions on cooling but on heating. Thus a solution of manganese sulphate, saturated at 70° , becomes cloudy on further heating. The point at which a substance separates from its solution with a change of temperature gives an easy means of determining the co-efficient of solubility, and this was taken advantage of by Prof. Alexéeff for determining the solubility of many substances. The phenomenon and method of observation is here essentially the same as in the determination of the temperature of formation of ice. If a solution of a substance which separates out on heating be taken (for example, the sulphate of calcium or manganese), then at a certain fall of temperature ice will separate out from it, and at a certain rise of temperature the salt will separate out. From this example, and from general considerations, it is clear that the separation of a substance dissolved from a solution should present a certain analogy to the separation of ice from a solution. In both cases, a heterogeneous system of a solid and a liquid is formed from a homogeneous (liquid) system.

the substance dissolved, and the solvent or compounds similar to them, only in a liquid partly decomposed form. Even the *colour of solutions* may often confirm this opinion. Copper sulphate forms crystals having a blue colour and containing water of crystallisation. If the water of crystallisation be removed by heating the crystals to redness, a colourless anhydrous substance is obtained (a white powder). From this it may be seen that the blue colour belongs to the compound of the copper salt with water. Solutions of copper sulphate are all blue, and consequently they contain a compound similar to the compound formed by the salt with its water of crystallisation. Crystals of cobalt chloride when dissolved in an anhydrous liquid—like alcohol, for instance—give a blue solution, but when they are dissolved in water a red solution is obtained. Crystals from the aqueous solution, according to Professor Potilizin, contain six times as much water ($\text{CoCl}_2 \cdot 6\text{H}_2\text{O}$) for a given weight of the salt, as those violet crystals ($\text{CoCl}_2 \cdot \text{H}_2\text{O}$) which are formed by the evaporation of an alcoholic solution.

That solutions contain particular compounds with water is further shown by the phenomena of supersaturated solutions, of so-called cryohydrates, of solutions of certain acids having constant boiling points, and the properties of compounds containing water of crystallisation whose data it is indispensable to keep in view in the consideration of solutions.

The phenomenon of supersaturated solutions consists in the following:—On the refrigeration of a saturated solution of certain salts,⁵⁴ if the liquid be brought under certain conditions, the excess of the solid may sometimes remain in solution and not separate out. A great number of substances, and especially sodium sulphate, Na_2SO_4 , or Glauber's salt, easily form supersaturated solutions. If boiling water be saturated with this salt, and the solution be poured off from any remaining undissolved salt, and, the boiling being still continued, the vessel holding the solution be well closed by cotton wool, or by fusing up the vessel, or by covering the solution with a layer of oil, then it will be found that this saturated solution does not separate out any Glauber's salt whatever on cooling down to the ordinary or even to a much lower temperature; although without the above precautions a salt separates out on cooling, in the form of crystals which contain water of

⁵⁴ Those salts which separate out with water of crystallisation form supersaturated solutions with the greatest facility, and the phenomenon is much more common than was before imagined. The first data were given in the last century by Loewitz, in St. Petersburg. Numerous researches have proved that supersaturated solutions do not differ from ordinary solutions in any of their essential properties. The variation of specific gravity, vapour tension, formation of ice, &c., take place according to the ordinary laws.

crystallisation to the amount of $\text{Na}_2\text{SO}_4, 10\text{H}_2\text{O}$ —that is, 180 parts of water for 142 parts of anhydrous salt. The supersaturated solution may be moved about or shaken inside the vessel holding it, and no crystallisation will take place; the salt remains in the solution in as large an amount as at a higher temperature. If the vessel holding the supersaturated solution be opened and crystals of Glauber's salt be thrown in, crystallisation suddenly takes place.⁵⁵ A considerable rise in temperature is noticed during this rapid separation of crystals, which is explained by the salt, previously in a liquid state, passing into a solid state, by which, as is known, latent heat is evolved. This somewhat resembles the fact that water may be cooled below 0° (even to -10°) if it be left at rest, under certain circumstances, and evolves heat in suddenly crystallising. Although from this point of view there is a resemblance, yet in reality the phenomenon of supersaturated solutions is much more complicated. Thus, on cooling, a saturated solution of Glauber's salt deposits crystals containing $\text{Na}_2\text{SO}_4, 7\text{H}_2\text{O}$,⁵⁶ or 126 parts

⁵⁵ Inasmuch as air, as has been shown by direct experiment, contains, although in very small quantities, minute crystals of salts, and among them of sodium sulphate, air can bring about the crystallisation of a saturated solution of sodium sulphate in an open vessel, but it has no effect on saturated solutions of certain other salts; for example, lead acetate. According to the observations of De Boisbaudran, Gernez, and others, isomorphous salts (analogous in composition) are capable of evoking crystallisation. Thus, a supersaturated solution of nickel sulphate crystallises by contact with crystals of sulphates of other metals analogous to it, such as those of magnesium, cobalt, copper, and manganese. The crystallisation of a supersaturated solution, brought about by the contact of a minute crystal, starts from it in rays with a definite velocity, and it is evident that the crystals as they form propagate the crystallisation in definite directions. This phenomenon recalls the evolution of organisms from germs. An attraction of similar molecules ensues, and they dispose themselves in definite similar forms.

⁵⁶ In these days a view is very generally accepted, which regards supersaturated solutions as homogeneous systems, which pass into heterogeneous systems (composed of a liquid and a solid substance), in all respects exactly resembling the passage of water cooled below its freezing point into ice and water, or the passage of crystals of rhombic sulphur into monoclinic crystals, and of the monoclinic crystals into rhombic. Although many phenomena of supersaturation are thus clearly understood, yet the spontaneous formation of the unstable hepta-hydrated salt (with $7\text{H}_2\text{O}$), in the place of the more stable deca-hydrated salt (with mol. $10\text{H}_2\text{O}$), indicates a property of a saturated solution of sodium sulphate which obliges one to admit that it has a different structure from an ordinary solution. Stcherbacheff affirms, on the basis of his researches, that a solution of the deca-hydrated salt gives, on evaporation, without the aid of heat, the deca-hydrated salt, whilst after heating above 33° it forms a supersaturated solution and the hepta-hydrated salt, which gives reason for thinking that the state of salts in supersaturated solutions is different from that in ordinary solutions. But in order that this view should be accepted, some signs must be discovered distinguishing solutions (which are, according to this view, isomeric) containing the hepta-hydrated salt from those containing the deca-hydrated salt, and all efforts made in this direction (the study of the properties of the solutions) have given negative results. Further, according to this view, one would expect that all supersaturated solutions would contain particular forms of crystallohydrates, and, although this is possible, yet up to now nothing of the kind has been observed,

of water per 142 parts of anhydrous salt, and not 180 parts of water, as in the above-mentioned salt. Further, the crystals containing $7\text{H}_2\text{O}$ are distinguished for their instability; if they stand in contact not only with crystals of $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$, but with many other substances, they immediately become opaque, forming a mixture of anhydrous and deca-hydrated salts. It is evident that between water and a soluble substance there may be established different kinds of greater or less stable equilibrium, of which solutions form one aspect.⁵⁷

and one must think that the connection with the fusibility of the deca-hydrated salt (and of all salts which easily give supersaturated solutions and are capable of forming several crystallohydrates), and with that decomposition (formation of the anhydrous salt) which the deca-hydrated salt suffers on melting—plays its part here. As some crystallohydrates of salts (alums, sugar of lead, calcium chloride) melt without decomposing, whilst others (like $\text{Na}_2\text{SO}_4 \cdot \text{H}_2\text{O}$) are decomposed, then it may be that the latter are only in a state of equilibrium at a higher temperature than their melting point. Did experiment show that the hepta-hydrated salt began to crystallise below 33° , and that then only the crystals grow, then all the data concerning supersaturated solutions of sodium sulphate could be explained exclusively in the sense of a super-cooling effect. At present, however, these questions, notwithstanding the mass of research to which they have been subjected, cannot be considered as fully resolved. It may here be observed that in melting crystals of the deca-hydrated salt, there is formed, besides the solid anhydrous salt, a saturated solution giving the hepta-hydrated salt, so that this passage from the deca- to the hepta-hydrated salt, and the reverse, takes place with the formation of the anhydrous (or it may be, mono-hydrated) salt.

The researches of Pickering (1887) on the amount of heat which is evolved in the solution of hydrous and anhydrous salts at different temperatures, give reason to think that at a certain temperature no heat will be evolved in the combination with water; that is, that probably such a combination will not take place. Thus 106 grams (the molecular weight in grams) of anhydrous sodium carbonate, Na_2CO_3 , in dissolving in 7,200 grams ($= 400\text{H}_2\text{O}$) of water, evolve 4,300 calories at 4° , 5,300 at 16° , and 5,850 calories at 25° (in other cases the heat evolved in solution also increases with a rise of temperature). If, however, the crystallo-hydrate, $\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O}$, be taken, then (for the same quantity of anhydrous salt) an absorption of heat is observed; at $4^\circ - 16,250$, at $16^\circ - 16,150$, and at $25^\circ - 16,300$ calories. As in this case a portion of the heat absorbed is due to the fact that the water of crystallisation taken in a solid state appears in a liquid state, Pickering subtracts the latent heat of liquefaction of ice, and obtains in the given case at $4^\circ - 1,700$, at $16^\circ - 600$, and at $28^\circ - 0$ calories. From this, the heat of the formation of the crystallo-hydrate, or the heat evolved by the combination of Na_2CO_3 with $10\text{H}_2\text{O}$, may be calculated (by subtracting the former quantities from the first). At 4° it is equal to $+6,000$, at $16^\circ +5,900$, at $25^\circ +5,850$ calories; that is, it distinctly decreases, although but slightly, with the rise of temperature. It may be that for Na_2SO_4 at 33° the heats of the formation of $+10\text{H}_2\text{O}$ and $7\text{H}_2\text{O}$ differ but very slightly.

⁵⁷ *Emulsions*, like milk, are composed of a solution of glutinous or like substances, or of oily liquids suspended in a liquid in the form of drops, which are clearly visible under a microscope, and form an example of a mechanical formation which resembles solutions. But the difference from solutions is here evident. There are, however, solutions which approach very near to emulsions in the facility with which the substance dissolved separates from them. It has long been known, for example, that a particular kind of Prussian blue, $\text{KFe}_2(\text{CN})_6$, dissolves in pure water, but, on the addition of the smallest quantity of either of a number of salts, it curdles and becomes quite insoluble. If copper sulphide (CuS), cadmium sulphide (CdS), arsenic sulphide (As_2S_3), and many other metallic sulphides, be obtained by a method of double decomposition (by precipi-

Solutions of salts on refrigeration below 0° deposit ice or crystals (which then usually contain water of crystallisation) of the salt dissolved, and on arriving by this means at a certain degree of concentration they solidify in their entire mass. These solidified masses are termed *cryohydrates*. My researches on solutions of common salt (1868) showed that its solution solidifies when it reaches a composition $\text{NaCl} + 10\text{H}_2\text{O}$ (180 parts of water per 58.5 parts of salt), which takes place at about -23° . The solidified solution melts at the same temperature, and both the portion melted and the remainder preserve the above composition. Guthrie (1874–1876) obtained the cryohydrates of many salts, and he showed that certain of them are formed at comparatively low temperatures, whilst others (for instance, corrosive sublimate, alums, potassium chlorate, and various colloids) are formed on a slight cooling, to -2° or even before, and that these contain a very large amount of water. One can easily imagine that these two series of cryohydrates differ considerably from each other, but the insufficiency of the existing data⁵⁸ does not permit of a true judgment being formed. Nevertheless, in the case of common salt, the cryo-

tating salts of these metals by hydrogen sulphide), and be then carefully washed (by allowing the precipitate to settle, pouring off the liquid, and again adding sulphuretted hydrogen water), then, as was shown by Schulze, Spring, Prost, and others, the previously insoluble sulphides pass into transparent (for mercury, lead, and silver, reddish brown; for copper and iron, greenish brown; for cadmium and indium, yellow; and for zinc, colourless) solutions, which may be preserved (the weaker they are the longer they keep) and even boiled, but which, nevertheless, in time become curdled—that is, settle in an insoluble form, and then sometimes become crystalline and quite incapable of re-dissolving. Graham and others observed the power shown by colloids (*see note 18*) of forming similar *hydrosols or solutions of gelatinous colloids*, and, in describing alumina and silica, we shall have occasion to speak of such solutions once more.

In the existing state of our knowledge concerning solution, such solutions may be looked on as a transition between emulsion and ordinary solutions, but no fundamental judgment can be formed about them until a study has been made of their relations to ordinary solutions (the solutions of even soluble colloids freeze immediately on cooling below 0° , and, according to Guthrie, do not form cryohydrates), and to supersaturated solutions, with which they have certain points in common.

⁵⁸ Offer (1880) concludes, from his researches on cryohydrates, that they are simple mixtures of ice and salts, having a constant melting point, just as there are alloys having a constant point of fusion, and solutions of liquids with a constant boiling point (*see note 60*). This does not, however, explain in what form a salt is contained, for instance, in the cryohydrate, $\text{NaCl} + 10\text{H}_2\text{O}$. At temperatures above -10° common salt separates out in anhydrous crystals, and at temperatures near -10° , in combination with water of crystallisation, $\text{NaCl} + 2\text{H}_2\text{O}$, and, therefore, it is very improbable that at still lower temperatures it would separate without water. If the possibility of the solidified cryohydrate containing $\text{NaCl} + 2\text{H}_2\text{O}$ and ice be admitted, then it is not clear why one of these substances does not melt before the other. If alcohol does not extract water from the solid mass, leaving the salt behind, this does not prove the presence of ice, because alcohol also takes up water from the crystals of many hydrated substances (for instance, from $\text{NaCl} + 2\text{H}_2\text{O}$) at about their melting-points. Besides which, a simple observation on the cryohydrate, $\text{NaCl} + 10\text{H}_2\text{O}$, shows that with the most careful cooling it does not

hydrate with 10 molecules of water, and in the case of sodium nitrate, the cryohydrate⁵⁹ with 7 molecules of water (*i.e.*, 126 parts of water per 85 of salt) should be accepted as established substances, capable of passing from a solid to a liquid state and conversely; and therefore it may be thought that in cryohydrates we have solutions which are not only undecomposable by cold, but also have a definite composition which would present a fresh case of definite equilibrium between the solvent and the substance dissolved.

The formation of definite but unstable compounds in the process of solution becomes evident from the phenomena of a marked decrease of vapour tension, or from the rise of the temperature of ebullition which occurs in the solution of certain volatile liquids and gases in water. As an example, we will take hydriodic acid, HI, a gas which liquefies on a very considerable reduction of temperature, giving a liquid which boils at -20° . A solution of it containing 57 p.c. of hydriodic acid is distinguished by its great stability. If it be evaporated by heating, the hydriodic acid volatilises together with the water in the same proportions as they occur in the solution, so that the gas passes off together with the aqueous vapour, and therefore such a solution may be distilled unchanged, for the distillate will contain the same proportion of hydriodic acid and water as was originally taken. The solution boils at a higher temperature than water. The physical properties of the gas and water in this case already disappear; there is formed a stable compound between water and the gas, a new substance which has its definite boiling point. To put it more correctly, this is not the temperature of ebullition, but the temperature at which the compound formed decomposes, forming the vapours of the products of dissociation, which, on cooling, re-combine. The above-described aqueous solution boils at 127° . Should a less amount of hydriodic acid be dissolved in water than the above, then, on heating such a solution, water only will at first be distilled over, until the solution attains the above-mentioned composition; it will then distil over unaltered. If more hydriodic acid be passed into such a solution a fresh quantity of the gas will dissolve, which, however, may be very easily removed. It must not, however, be thought that those forces which determine the

on the addition of ice deposit ice, which would occur if ice in intermixture with the salt were formed on solidification.

I may add with regard to cryohydrates that, in investigating aqueous solutions of alcohol (note 19), I concluded, on the basis of the specific gravity, that a compound, $C_2H_6O + 12H_2O$, existed, and a solution of this composition completely solidifies on cooling to -20° , forming well-formed crystals, which melt at about -18° , as was shown by observations made by W. E. Tischenko and myself. This definite compound reminds one of cryohydrates in many respects.

⁵⁹ See note 24.

formation of ordinary gaseous solutions play no part whatever in the formation of a solution having a definite boiling point; that they do act is shown from the fact that such constant gaseous solutions vary in their composition under different pressures.⁶⁰ Therefore, it is not at

⁶⁰ For this reason (the want of entire constancy of the composition of constant boiling solutions with a change of pressure) many deny the existence of definite hydrates formed by volatile substances—for instance, by hydrochloric acid and water. They generally argue as follows: If there did exist a constancy of composition, then it would not be altered by a change of pressure. But the distillation of constant boiling hydrates is undoubtedly accompanied (judging by the vapour densities determined by Bineau), like the distillation of sal-ammoniac, sulphuric acid, &c., by an entire decomposition of the previous compound—that is, these substances do not exist in a state of vapour, but their products of decomposition (hydrochloric acid and water) are gases at the temperature of volatilisation, which dissolve in the volatilised and condensed liquids; but the solubility of gases in liquids depends on the pressure, and, therefore, the composition of constant boiling solutions may, and even ought to, vary with a change of pressure, and, further, the smaller the pressure and the lower the temperature of volatilisation, the more likely is a true compound to be obtained. According to the researches of Roscoe and Dittmar (1859), the constant boiling solution of hydrochloric acid proved to contain 18 p.c. of hydrochloric acid at a pressure of 3 atmospheres, 20 p.c. at 1 atmosphere, and 23 p.c. at $\frac{1}{10}$ of an atmosphere. On passing air through the solution until its composition became constant (*i.e.*, forcing the excess of aqueous vapour or of hydrochloric acid to pass away with the air), then acid was obtained containing about 20 p.c. at 100°, about 23 p.c. at 50°, and about 25 p.c. at 0°. From this it is seen that by decreasing the pressure and lowering the temperature of evaporation one arrives at the same limit, where the composition should be taken as $\text{HCl} + 6\text{H}_2\text{O}$, which requires 25.26 p.c. of hydrochloric acid. Fuming hydrochloric acid contains more than this.

The most important fact in evidence of the existence of definite compounds in acids boiling at a constant temperature is the fall of tension. The gas loses its tension, does not follow the law of Henry and Dalton with a diminution of pressure; its solution only parts with water; the vapour tension of a volatile liquid in solution is less than its own or that of the water combined with it. This loss of tension is a loss of movement brought about by the action of the attraction existing between the water and the substance dissolved. In the case already considered, as in the case of formic acid in the researches of D. P. Kononoff (note 47), the constant boiling solution corresponds with a minimum tension—that is, with a boiling point higher than that of either of the component elements. But there is another case of constant boiling solutions similar to the case of the solution of propyl alcohol, $\text{C}_3\text{H}_7\text{O}$, when a solution, undecomposed by distillation, boils at a lower point than that of the more volatile liquid. However, in this case also, if there be solution, the possibility cannot be denied of the formation of a definite compound in the form $\text{C}_3\text{H}_7\text{O} - \text{H}_2\text{O}$, and the tension of the solution is not equal to the sum of tensions of the components. There are possible cases of constant boiling mixtures even when there is no solution nor any loss of tension, and consequently no chemical action, because the amount of liquids that are volatilised is determined by the product of the vapour densities into their vapour tensions (Wanklyn), in consequence of which liquids whose boiling point is above 100°—for instance, turpentine and ethereal oils in general—when distilled with aqueous vapour, pass over at a temperature below 100°. Consequently, it is not in the constancy of composition and boiling point (temperature of decomposition) that the signs of a clear chemical action should be seen in the above-described solutions of acids, but in the great loss of tension, which completely resembles the loss of tension observed, for instance, in the perfectly-definite combinations of substances with water of crystallisation (*see* later, note 65). Sulphuric acid, H_2SO_4 , as we shall learn later, is also decomposed by distillation, like $\text{HCl} + 6\text{H}_2\text{O}$, and exhibits, moreover, all the signs of a

every, but only at the ordinary, atmospheric pressure that a constant boiling solution of hydriodic acid will contain 57 p.c. of the gas. At another pressure the proportion of water and hydriodic acid will be different. It varies, however, judging from observations made by Roscoe, very little for considerable variations of pressure. This variation in composition directly indicates that pressure exerts an influence on the formation of unstable chemical compounds which are easily dissociated (with formation of a gas), just as it influences the solution of gases, only the latter is influenced to a more considerable degree than the former.⁶¹ Hydrochloric, nitric, and other acids form *solutions having definite boiling points*, like that of hydriodic acid. They show further the common property, if containing but a small proportion of water, that they *fume in air*. Strong solutions of nitric, hydrochloric, hydriodic, and other gases are even termed 'fuming acids.' The fuming liquids contain a definite compound, whose temperature of ebullition (decomposition) is higher than 100° , and contain also an excess of the volatile substance dissolved, which (the substance) exhibits a capacity to combine with water and form a hydrate, whose vapour tension is less than that of aqueous vapour. On evaporating in air, this dissolved substance meets the atmospheric moisture and forms a visible vapour (fumes) with it, which consists of the above-mentioned compound. The attraction or affinity which binds, for instance, hydriodic acid with water is evinced not only in the evolution of heat and the diminution of vapour tension (rise of boiling point), but also in many purely chemical relations. Thus hydriodic acid is produced from iodine and hydrogen sulphide in the presence of water, but unless water is present this reaction does not take place.⁶²

definite chemical compound. The study of the variation of the specific gravities of solutions as dependent on their composition (*see* note 19) shows that phenomena of a similar kind, although of different dimensions, take place in the formation of both H_2SO_4 from H_2O and SO_2 , and of $\text{HCl} + 6\text{H}_2\text{O}$ (or of aqueous solutions analogous to it) from HCl and H_2O .

⁶¹ The essence of the matter may be thus represented. A substance A , either gaseous or easily volatile, forms with a certain quantity of water, $n\text{H}_2\text{O}$, a definite complex compound $A_n\text{H}_2\text{O}$, which is stable up to a temperature t° higher than 100° . At this temperature it is decomposed into two substances, $A + \text{H}_2\text{O}$. Both boil below t° at the ordinary pressure, and therefore at t° they distil over and re-combine in the receiver. But if a part of the substance $A_n\text{H}_2\text{O}$ is decomposed or volatilised, there still remains a portion of undecomposed liquid in the vessel, which can partially dissolve one of the products of decomposition, and that in quantity varying with the pressure and temperature, and therefore the solution at a constant boiling point will have a slightly-different composition at different pressures.

⁶² For solutions of hydrochloric acid in water there are still greater differences in reactions. For instance, strong solutions decompose antimony sulphide (forming hydrogen sulphide, H_2S), and precipitate common salt from its solutions whilst weak solutions do not act thus.

Many compounds containing water of crystallisation are solid substances (when melted they are already solutions—*i.e.*, liquids); furthermore, they are capable of being formed from solutions, as is ice or aqueous vapour. I propose calling them *crystallo-hydrates*. Inasmuch as the direct presence of ice or aqueous vapour cannot be admitted in solutions (for these are liquids), although the presence of water may be, so also there is no basis for acknowledging the presence in solutions of substances in an already-existing state of combination with water of crystallisation, although they are obtained from solutions as such.⁶³ It is evident that such substances present one of the many forms of equilibrium between water and a substance dissolved in it. This form, however, reminds one, in all respects, of solutions—that is, aqueous compounds which are more or less easily decomposed, with separation of water and the formation of a less aqueous or an anhydrous compound. In fact, there are not a few crystals containing water which lose a part of their water at the ordinary temperature. Of such a kind, for instance, are the crystals of soda, or sodium carbonate, which, when separated from an aqueous solution at the ordinary temperature, are quite transparent; but when left exposed to air, lose a portion of their water, becoming opaque, and, in the process, lose their crystalline appearance, although preserving their original form. This process of the separation of water at the ordinary temperature is termed the *efflorescence* of crystals. Efflorescence takes place more rapidly under the receiver of an air pump, and especially at a gentle heat. This breaking up of a crystal is dissociation at the ordinary temperature. Solutions are decomposed in exactly the same manner.⁶⁴ The tension of the aqueous vapour, which is given off from

⁶³ Supersaturated solutions give an excellent proof in this respect. Thus a solution of copper sulphate generally crystallises in penta-hydrated crystals, $\text{CuSO}_4 + 5\text{H}_2\text{O}$, and its saturated solution gives such crystals if it be brought into contact with the minutest possible crystal of the same kind. But, according to the observations of Lecoq de Boisbandran, if a crystal of ferrous sulphate (an isomorphous salt, *see* note 55), $\text{FeSO}_4 + 7\text{H}_2\text{O}$, be placed in a saturated solution of copper sulphate, then crystals of hepta-hydrated salt, $\text{CuSO}_4 + 7\text{H}_2\text{O}$, are obtained. It is evident that neither the penta- nor the hepta-hydrated salt is contained as such in the solution. The solution presents its own particular liquid form of equilibrium.

⁶⁴ Efflorescence, like every evaporation, proceeds from the surface. Inside crystals which have effloresced there is usually found a non-effloresced mass, so that the majority of effloresced crystals of washing soda show, in their fracture, a transparent nucleus coated by an effloresced, opaque, powdery mass. It is a remarkable circumstance in this respect that efflorescence proceeds in a completely regular and uniform manner, so that the angles and planes of similar crystallographic character effloresce simultaneously, and in this respect the crystalline form determines those parts of crystals where efflorescence starts, and the order in which it continues. In solutions evaporation also proceeds from the surface, and the first crystals which appear on its reaching the required degree of saturation are also formed at the surface. After falling to the bottom the crystals naturally continue to grow (*see* Chap. X.).

crystallo-hydrates is naturally, as with solutions, less than the vapour tension of water itself ⁶⁵ at the same temperature, and therefore many anhydrous salts which are capable of combining with water absorb aqueous vapour from moist air; that is, they act like a cold body on which water is deposited from steam. It is on this that the desiccation of gases is based, and it must further be remarked in this respect that certain substances—for instance, potassium carbonate (K_2CO_3) and calcium chloride ($CaCl_2$)—not only absorb the water necessary for the formation of a solid crystalline compound, but also give solutions, or *deliquesce*, as it is termed, in moist air. Many crystals do not effloresce in the least at the ordinary temperature; for example, copper sulphate, which may be preserved for an indefinite length of time without efflorescing, but when placed under the receiver of an air pump, if efflorescence be once started, it goes on at the ordinary temperature. The temperature at which the entire separation of water from crystals takes place varies considerably, not only for different substances but also for different portions of the contained water. Very often the temperature at which dissociation begins is very much higher than the boiling point of water. So, for example, copper sulphate, which contains 36 p.c. of water, gives up 28.8 p.c. at 100° , and the remaining quantity, namely 7.2 p.c., only at 240° . Alum, out of the 45.5 p.c. of water which it contains, gives up 18.9 p.c. at 100° , 17.7 p.c. at 120° , 7.7 p.c. at 180° , and 1 p.c. at 280° ; it only loses the last quantity (1 p.c.) at their temperature of decomposition. These examples clearly show that the annexation of water of crystallisation is accompanied by a rather profound, although, in comparison with instances which we shall consider later, still incon-

⁶⁵ According to Lescœur (1883), at 100° a thick solution of barium hydroxide, BaH_2O_2 , on first depositing crystals (with $-H_2O$) has a tension of about 630 mm. (instead of 760 mm., the tension of water), which decreases (because the solution evaporates) to 45 mm., when all the water is expelled from the crystals, $BaH_2O_2 + H_2O$, which are formed, but they also lose water (dissociate, effloresce at 100°), leaving the hydroxide, BaH_2O , which is perfectly undecomposable at 100° —that is, does not part with water. At 73° (the tension of water is then 265 mm.) a solution, containing $33H_2O$, on crystallising has a tension of 230 mm.; the crystals $BaH_2O + 8H_2O$, which separate out, have a tension of 160 mm.; on losing water they give $BaH_2O_2 + H_2O$. This substance does not decompose at 73° , and therefore its tension = 0. Müller-Erzbach (1884) determines the tension (with reference to liquid water) by placing similar long tubes with water and the substances experimented with in a desiccator, the rate of loss of water giving the relative tension. Thus, at the ordinary temperature, crystals of sodium phosphate, $Na_2HPO_4 + 12H_2O$, present a tension of 0.7 compared with water, until they lose $5H_2O$, then 0.4 until they lose $5H_2O$ more, and on losing the last equivalent of water the tension falls to 0.04 compared with water. It is clear that the different molecules of water are held by an unequal force. Out of the five molecules of water in copper sulphate the two first are comparatively easily separated, even at the ordinary temperature (but only after several days in a desiccator, according to Latchinoff); the next two are more difficultly separated, and the last equivalent is held firmly, even at 100° .

siderable, change of its properties. In certain cases the water of crystallisation is only given off when the solid form of the substance is destroyed : when the crystals melt on heating. The crystals are then said *to melt in their water of crystallisation*. Further, after the separation of the water, a solid substance remains behind, so that by further heating it acquires a solid form. This is seen most clearly in crystals of sugar of lead or lead acetate, which melt in their water of crystallisation at a temperature of $56\cdot25^\circ$, and in so doing begin to lose water. On reaching a temperature of 100° the sugar of lead solidifies, having lost all its water ; and then at a temperature of 280° the anhydrous and solidified salt again melts. Sodium acetate ($\text{C}_2\text{H}_3\text{NaO}_2, 3\text{H}_2\text{O}$) melts at 58° (but resolidifies only on contact with a crystal, otherwise it may remain liquid even at 0° ; as the temperature does not change during solidification, the melted salt can be used for obtaining a constant temperature of 58°). According to Jeannel, the latent heat of fusion is about 28 calories, and, according to Pickering, the heat of solution is 35 calories. When melted, this salt boils at 123° that is, the tension of the aqueous vapour given off then equals the atmospheric pressure.

It is most important to recognise in respect to the water of crystallisation that its ratio to the quantity of the substance with which it is combined is always a constant quantity. However often we may prepare copper sulphate, we shall always find $36\cdot14$ p.c. of water in its crystals, and these crystals always lose four-fifths of their water at 100° , and one-fifth of the whole amount of the water contained remains in the crystals at 100° , and is only expelled from them at a temperature of about 240° . The determination of the amount of water of crystallisation is easily made if a weighed quantity of crystals is dried in an air or other bath. What has been said about crystals of copper sulphate refers also to crystals of every other substance which contain water of crystallisation. It is impossible to here increase either the relative proportion of the salt or of the water, without changing the homogeneity of the substance. If once a portion of the water be lost— for instance, if once efflorescence takes place—a mixture is obtained, and not a homogeneous substance, namely a mixture of a substance deprived of water with a substance which has not yet lost water—*i.e.*, decomposition has already commenced. This constant ratio is an example of the fact that in chemical compounds the quantity of the component parts is quite definite ; that is, it is an example of the so-called *definite chemical compounds*. They may be distinguished from solutions, and from all other so-called indefinite chemical compounds, in that at least one, and sometimes both, of the component parts may be added in a large quantity to an indefinite chemical compound without destroying

its homogeneity, as in solutions, whilst it is impossible to add any one of the component parts to a definite chemical compound without destroying the homogeneity of the entire mass. Definite chemical compounds only decompose at a certain rise in temperature ; on a lowering in temperature they do not, at least with very few exceptions, yield their components like solutions which form ice or compounds with water of crystallisation. This obliges one to consider that solutions contain water as water,⁶⁶ although it may sometimes be in a very small quantity. Therefore solutions which are capable of entirely solidifying (for instance, cryohydrates and crystallo-hydrates *i.e.*, compounds with water of crystallisation which are capable of melting or the compound of $84\frac{1}{2}$ parts of sulphuric acid, H_2SO_4 , with $15\frac{1}{2}$ parts of water, H_2O , or $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$, or H_4SO_3) appear as true definite chemical compounds. If, then, we imagine such a definite compound in a liquid state, and admit that it partially decomposes in this state, separating water—not as ice or vapour (for then the system would be heterogeneous, including substances in different physical states), but in a liquid form, when the system will be homogeneous—then we shall form an idea of a solution as an unstable, decomposing fluid equilibrium between water and the substance dissolved. Just as the component elements may be added to a gaseous mixture without destroying its homogeneity, so both the solvent may be added to a solution (the solution will then be obtained diluted, and no longer presenting a definite composition), and also the substance dissolved may be added (with a solid and a saturated solution a supersaturated solution will be obtained), which may, however, owing to the force of the cohesion of its parts, separate out from the solution in a crystallised form. In adding the solvent, or the substance dissolved, without destruction of the homogeneity of the whole, we altered their relative quantity (the proportion of the acting masses), by which there will be an alteration, both in the quantity of the water, forming one of the products of dissociation, and also of the relative quantity of one or many of the definite compounds between the water and the substance dissolved. Owing to this change, there occurs an alteration in the properties of a solution (contraction, change of vapour tension, &c.) ; not in the sense of a purely mechanical change in the proportion of the components (as in the intermixture of non reacting

⁶⁶ Such a phenomenon frequently presents itself in purely chemical action. For instance, let a liquid substance *A* give, with another liquid substance *B*, under the conditions of an experiment, a mere minute quantity of a solid or gaseous substance *C*. This small quantity will separate out (pass away from the sphere of action, as Berthollet expressed it), and the remaining masses of *A* and *B* will again give *C*; consequently, under these conditions, action will go on to the end. Such, it seems to me, is the action in solutions when they yield ice or vapour indicating the presence of water.

gases), but in the sense of an alteration in the quantity of those definite liquid chemical compounds which are determined by the chemical attraction between water and the substance dissolved in it, and by their capacity for forming with it *diverse* compounds,⁶⁷ which is seen in the capacity of one substance to form with water many various *crystallohydrates*, or compounds with water of crystallisation, showing diverse and independent properties. From these considerations, *solutions*⁶⁸ may be regarded as *fluid, unstable, definite chemical compounds in a state of dissociation*.⁶⁹

⁶⁷ Certain substances are capable of forming only one compound, others several, and these of the most varied degrees of stability. The compounds of water are instances of this kind. In solutions of sulphuric acids (*see* note 19), for example, the existence must be acknowledged of several different definite compounds. Many of these have not yet been obtained in a free state, and it may be that they cannot be obtained in any other but a liquid form—that is, dissolved; just as there are many undoubted definite compounds which only exist in one physical state. Among the hydrates such instances occur. The compound $\text{CO}_2 + 8\text{H}_2\text{O}$ (*see* note 31), according to Wroblewski, only occurs in a solid form. Hydrates like $\text{H}_2\text{S} + 12\text{H}_2\text{O}$ (De Forerand and Villard), $\text{HBr} + \text{H}_2\text{O}$ (Roozeboom), can only be accepted on the basis of a decrease of tension, but present themselves as very transient substances, incapable of existing in a stable free state. Even sulphuric acid, H_2SO_4 , itself, which undoubtedly is a definite compound, fumes in a liquid form, evolving the anhydride, SO_3 —that is, exhibits a very unstable equilibrium. The crystallohydrates of chlorine, $\text{Cl}_2 + 8\text{H}_2\text{O}$, of hydrogen sulphide, $\text{H}_2\text{S} + 12\text{H}_2\text{O}$ (it is formed at 0° , and is completely decomposed at $+1^\circ$, as then 1 vol. of water only dissolves 4 vols. of hydrogen sulphide, while at 0.1° it dissolves about 100 vols.), and of many other gases, are instances of hydrates which are very unstable.

⁶⁸ Of such a kind are also other indefinite chemical compounds; for example, metallic alloys. These are solid substances or solidified solutions of metals. They also contain definite compounds, and may contain an excess of one of the metals. According to the experiments of Laurie (1888), the alloys of zinc with copper in respect to the electromotive force in galvanic batteries behave just like zinc if the proportion of copper in the alloy does not exceed a certain percentage—that is, until a definite compound is attained—for then there are yet particles of free zinc; but if a copper surface be taken, and it be covered by only one-thousandth part of its area of zinc, then only the zinc will act in a galvanic battery.

⁶⁹ According to the above supposition, the condition of solutions in the sense of the kinetic hypothesis of matter (that is, on the supposition of an internal movement of molecules and atoms) may be represented in the following form:—In a homogeneous liquid—for instance, water—the molecules occur in a certain state of, although mobile, still stable, equilibrium. When a substance *A* dissolves in water, its molecules form with several molecules of water, systems $A_n\text{H}_2\text{O}$, which are so unstable that when surrounded by molecules of water they decompose and re-form, so that *A* passes from one mass of molecules of water to another, and the molecules of water which were at this moment in harmonious movement with *A* in the form of the system $A_n\text{H}_2\text{O}$, in the next instant may have already succeeded in getting free. The addition of water or of molecules of *A* may either only alter the number of free molecules, which in their turn enter into systems $A_n\text{H}_2\text{O}$, or they may introduce conditions for the possibility of building up new systems $A_m\text{H}_2\text{O}$, where *m* is either greater or less than *n*. If in the solution the relation of the molecules be the same as in the system $A_m\text{H}_2\text{O}$, then the addition of fresh molecules of water or of *A* would be followed by the formation of new molecules $A_n\text{H}_2\text{O}$. The relative quantity, stability, and composition of these systems or definite compounds will vary in one or another solution. Such a view of solutions came to me from a most intimate study of the variation of their specific gravities, to which my book, cited in note 19, is

In regarding solutions from this point of view they come under the head of those definite compounds which chemistry mainly treats of.⁷⁰ For this reason we will direct our particular attention to one side of the subject under consideration, which touches on the essential property

devoted. Definite compounds, An_1H_2O and Am_1H_2O , existing in a free—for instance, solid—form, may in certain cases be held in solutions in a dissociated state (although but partially); they are similar in their structure to those definite substances which are formed in solutions, but nothing obliges one to think that it is such systems as, for instance, $Na_2SO_4 + 10H_2O$, or $Na_2SO_4 + 7H_2O$, or Na_2SO_4 , that are contained in solutions. The comparatively more stable systems An_1H_2O which exist in a free state and change their physical state must present, although within certain limits of temperature, an entirely harmonious kind of movement of A with n_1H_2O ; the property also and state of systems AnH_2O and AmH_2O , occurring in solutions, is that they are in a liquid form, although partially dissociated. Substances A_1 , which give solutions, are distinguished by the fact that they can form such unstable systems AnH_2O , but besides them they can give other much more stable systems An_1H_2O . Thus ethylene, C_2H_4 , in dissolving in water, probably forms a system $C_2H_4nH_2O$, which easily splits up into C_2H_4 and H_2O , but it also gives the system of alcohol, $C_2H_4.H_2O$ or C_2H_6O , which is comparatively stable. Thus oxygen can dissolve in water, and it can combine with it, forming peroxide of hydrogen. Turpentine, $C_{10}H_{16}$, does not dissolve in water, but it combines with it in a comparatively stable hydrate. In other words, the chemical structure of hydrates, or of the definite compounds which are contained in solutions, is distinguished not only by its original peculiarities but also by a diversity of stability. A similar structure to hydrates must be acknowledged in crystallo-hydrates. On melting they give actual (real) solutions. As substances which give crystallo-hydrates, like salts, are capable of forming a number of diverse hydrates, and as the greater the number of molecules of water (n) they (AnH_2O) contain the lower is the temperature of their formation, and as the more easily they decompose the more water they hold, therefore, in the first place, the isolation of hydrates holding much water existing in aqueous solutions may be soonest looked for at low temperatures (although, perhaps, in certain cases they cannot exist in the solid state); and secondly, the stability also of such higher hydrates will be at a minimum under the ordinary circumstances of the occurrence of liquid water. Hence a further more detailed investigation of cryohydrates (note 58) may help to the elucidation of the nature of solutions. But it may be foreseen that certain cryohydrates will, like metallic alloys, present solidified mixtures of ice with the salts themselves and their more stable hydrates, and others will be definite compounds.

⁷⁰ The above representation of solutions, &c., considering them as a particular state of definite compounds, excludes the independent existence of indefinite compounds; by this means that unity of chemical conception is obtained which cannot be arrived at by admitting the physico-mechanical conception of indefinite compounds. The gradual transition from typical solutions (as of gases in water, and of weak saline solutions) to sulphuric acid, and from it and its definite, but yet unstable and liquid, compounds, to clearly definite compounds, such as salts and their crystallo-hydrates, is so imperceptible, that by denying that solutions pertain to the number of definite but dissociating compounds, we risk denying the definiteness of the atomic composition of such substances as sulphuric acid or of molten crystallo-hydrates. I repeat, however, that for the present the theory of solutions cannot be considered as firmly established. The above opinion about them is nothing more than a hypothesis which endeavours to satisfy those comparatively limited data which we have for the present about solutions, and of those cases of their transition into definite compounds. By submitting solutions to the Daltonic conception of atomism, I hope that we may not only attain to a general harmonious chemical doctrine, but also that new motives for investigation and research will appear in the problem of solutions, which must either confirm the proposed theory or replace it by another fuller and truer one.

of definite compounds as a class to whose number solutions should (or at least, may) be referred.

We saw above that copper sulphate loses four-fifths of its water at 100° and the remainder at 240° . This means that there are two definite compounds of water with the anhydrous salt. Washing soda or carbonate of sodium, Na_2CO_3 , separates out as crystals, $\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O}$, containing 62.9 p.c. of water by weight, from its solutions at the ordinary temperature. When a solution of the same salt deposits crystals at a low temperature, about -20° , then these crystals contain 71.8 parts of water per 28.2 parts of anhydrous salt. Further, the crystals are obtained together with ice, and are left behind when it melts. If ordinary soda, with 62.9 p.c. of water, be cautiously melted in its own water of crystallisation, there remains a salt, in a solid state, containing only 14.5 p.c. of water, and a liquid is obtained which contains the solution of a salt which separates out crystals at 34° , which contain 46 p.c. of water and do not effloresce in air. Lastly, if a supersaturated solution of soda be prepared, then at temperatures below 8° it deposits crystals containing 54.3 p.c. of water. Thus there are known as many as five compounds of anhydrous soda with water; and they are dissimilar in their properties and crystalline form, and even in their solubility. We will mention that the greatest amount of water in the crystals corresponds with a temperature of 20° , and the smallest to the highest temperature. There is apparently no relation between the above quantities of water and the salts, but this is only because in each case the amount of water and anhydrous salt was given in percentages, but if it be calculated for one and the same quantity of anhydrous salt, or of water, a great regularity will be observed in the amounts of the component parts in all these compounds. It appears that for 106 parts of anhydrous salt in the crystals separated out at -20° there are 270 parts of water; in the crystals obtained at 15° there are 180 parts of water; in the crystals obtained from a supersaturated solution 126 parts, in the crystals which separate out at 34° , 90 parts, and the crystals with the smallest amount of water, 18 parts. On comparing these quantities of water it may be easily seen that they are in simple proportion to each other, for they are all divisible by 18, and are in the ratio 15 : 10 : 7 : 5 : 1. Naturally, direct experiment, however carefully it be conducted, is hampered with errors, but taking these inevitable errors into consideration, it will be seen that for a given quantity of an anhydrous substance there occur, in several of its compounds with water, quantities of water which are in very simple multiple proportion. This is observed in, and is common to, all definite chemical compounds. This rule is called *the law of multiple proportions*. It was discovered

by Dalton, and will be evolved in detail in the further exposition in this work. For the present we will only state that the law of definite composition enables the composition of substances to be expressed by formulae, and the law of multiple proportions permits the application of co-efficients in a weight of whole numbers, in formulae. Thus the formula, $\text{Na}_2\text{CO}_3, 10\text{H}_2\text{O}$, directly shows that in this crystallo-hydrate there are 180 parts of water to 106 parts by weight of the anhydrous salt, because the formula of soda, Na_2CO_3 , directly answers to a weight of 106, and the formula of water to 18 parts, by weight, which are here taken 10 times.

In the above examples of the combinations of water, we saw the gradually-increasing intensity of the bond between water and a substance with which it forms a homogeneous compound. There is a series of such compounds with water, in which the water is held with very great force, and is only given up at a very high temperature, and sometimes cannot be separated by any degree of heat without the entire decomposition of the substance. In these compounds there is generally no outward sign whatever of their containing water. A perfectly new substance is formed from an anhydrous substance and water, in which sometimes the properties of neither one nor the other substance are observable. In the majority of cases, a considerable amount of heat is evolved in the formation of such compounds with water. Sometimes the heat evolved is so intense that a red heat is produced and light is emitted. It is hardly to be wondered at, after this, that stable compounds are formed by such a combination. Their decomposition requires great heat; a large amount of work is necessary to separate them into their component parts. All such compounds are definite, and, generally, completely and clearly definite. The number of such definite compounds with water or *hydrates*, in the narrow sense of the word, is generally inconsiderable for each anhydrous substance; in the greater number of cases, there is formed only one such combination of a substance with water, one hydrate, having so great a stability. The water contained in these compounds is often called *water of constitution* — *i.e.*, water which enters into the structure or composition of the given substance. By this it is desired to express, that in other cases the molecules of water are as it were separate from the molecules of that substance with which it is combined. It is supposed that in the formation of hydrates this water, even in the smallest particles, forms one complete whole with the anhydrous substance. Many examples of the formation of such hydrates might be cited. The most familiar example in practice is the hydrate of lime, or so-called ‘slaked’ lime. Lime is prepared by burning limestone, by which the carbonic anhydride

is expelled from it, and there remains a white stony mass, which is dense, compact, and rather tenacious. Lime is usually sold in this form, and bears the name of 'quick' or 'unslaked' lime. If water be poured over such lime, a great rise in temperature is remarked either directly, or after a certain time. The whole mass becomes hot, part of the water is evaporated, the stony mass in absorbing water crumbles into powder, and if the water be taken in sufficient quantity and the lime be pure and well burnt, not a particle of the original stony mass is left—it all crumbles into powder. If the water be in excess, then naturally a portion of it remains and forms a solution. This process is called 'slaking' lime. Slaked lime is used in practice in intermixture with sand as mortar. Slaked lime is a definite hydrate of lime. If it is dried at 100° it retains 24.3 p.c. of water. This water can only be expelled at a temperature above 400° , and then quicklime is re-obtained. The heat evolved in the combination of lime with water is so intense that it can set fire to wood, sulphur, gunpowder, &c. Even on mixing lime with ice the temperature rises to 100° . If lime be melted with a small quantity of water in the dark, a luminous effect is observed. But, nevertheless, water may still be separated from this hydrate.⁷¹ If phosphorus be burnt in dry air, a white substance called 'phosphoric anhydride' is obtained. It combines with water with such energy, that the experiment must be conducted with great caution. A red heat is produced in the formation of the compound, and it is impossible to separate the water from the resultant hydrate at any temperature. The hydrate formed by phosphoric anhydride is a substance which is totally undecomposable into its original component parts by this action of heat. Almost as energetic a combination occurs when sulphuric anhydride, SO_3 , combines with water, forming its hydrate, sulphuric acid, H_2SO_4 . In both cases definite compounds are produced, but the latter substance, as a liquid, and capable of decomposition by heat, giving off the vapour of its volatile anhydride even at the ordinary temperature, forms an evident link with solutions, and, with an excess of water, it gives, as a soluble substance, a true solution. If 80 parts of sulphuric anhydride retain 18 parts of water, this water cannot be separated from the anhydride, even at a temperature of 300° . It is only by the addition of phosphoric anhydride, or by a series of chemical transformations, that this water can be separated from its compound with sulphuric anhydride. Oil of vitriol,

⁷¹ In combining with water one part by weight of lime evolves 245 units of heat. A high temperature is obtained, because the specific heat of the resulting product is small. Sodium oxide, Na_2O , in reacting on water, H_2O , and forming caustic soda (sodium hydroxide), NaHO , evolves 552 units of heat for each part by weight of sodium oxide.

or sulphuric acid, is such a compound. If a larger proportion of water be taken, it will combine with the H_2SO_4 ; for instance, if 36 parts of water per 80 parts of sulphuric anhydride be taken, a compound is formed which crystallises in the cold, and melts at $+8^\circ$, whilst oil of vitriol does not solidify at even -30° . If still more water be taken, the oil of vitriol will dissolve in the remaining quantity of water. An evolution of heat takes place, not only on the addition of the water of constitution, but in a less degree on further additions of water.⁷² And therefore there is no distinct boundary, but only a gradual transition, between those chemical phenomena which are expressed in the formation of solutions and those which take place in the formation of the most stable hydrates.⁷³

⁷² The diagram given in note 28 shows the evolution of heat on the mixture of sulphuric acid, or mono-hydrate (H_2SO_4 , *i.e.* $\text{SO}_3 + \text{H}_2\text{O}$), with different quantities of water per 100 vols. of the resultant solution. Per 98 grams of sulphuric acid (H_2SO_4) there are evolved, on the addition of 18 grams of water, 6,379 units of heat; with double or three times the quantity of water 9,418 and 11,137 units of heat, and with an infinitely large quantity of water 17,860 units of heat, according to the determinations of Thomsen. He also showed that when H_2SO_4 is formed from SO_3 (=80) and H_2O (=18), 21,308 units of heat are evolved per 98 parts by weight of the resultant sulphuric acid.

⁷³ Thus, for different hydrates the stability with which they hold water is very dissimilar. Certain hydrates hold water very loosely, and in combining with it evolve little heat. From other hydrates the water cannot be separated by any degree of heat, even if they are formed from anhydrides (*i.e.*, anhydrous substances) and water with little evolution of heat; for instance, acetic anhydride in combining with water evolves an inconsiderable amount of heat, but the water cannot then be expelled from it. If the hydrate (acetic acid) formed by this combination be strongly heated it either volatilises without change, or decomposes into new substances, but it does not again yield the original substances—*i.e.*, the anhydride and water. Here is an instance which gives the reason for calling the water entering into the composition of the hydrate, water of constitution. Such, for example, is the water entering into the so-called caustic soda or sodium hydroxide (*see* note 71). But there are hydrates which easily part with their water; yet this water cannot be considered as water of crystallisation, not only because sometimes such hydrates have no crystalline form, but also because, in perfectly analogous cases, very stable hydrates are formed, which are capable of particular kinds of chemical reactions, as we shall learn afterwards. In a word, there is not a distinct boundary either between the water of hydrates and of crystallisation, or between solution and hydration.

It must be observed that in separating from an aqueous solution, many substances, without having a crystalline form, hold water in the same unstable state as in crystals; only this water cannot be termed 'water of crystallisation' if the substance which separates out has no crystalline form. The hydrates of alumina and silica are examples of such unstable hydrates. If these substances are separated from an aqueous solution by a chemical process, then they always contain water, and when dried at a definite temperature, so that the hygroscopic water may pass off, these substances hold water in a definite proportion. The formation of a new chemical compound containing water is here particularly evident, for alumina and silica in an anhydrous state have properties differing from those they show when combined with water, and do not combine directly with it. The entire series of colloids on separating from water form similar compounds with it, which have the aspect of solid substances generally, without crystalline structure. Besides which, colloids retain water in other different states (*see* notes 57

We have thus considered many aspects and degrees of combination of various substances with water, or instances of the compounds of water, when it and other substances form new homogeneous substances, which in this case will evidently be complex—*i.e.*, made up of different substances—and although they are homogeneous, yet it must be admitted that in them there exist those component parts which entered into their composition, inasmuch as these parts may be re-obtained from them. It must not be imagined that water really exists in hydrate of lime, any more than that ice or steam exists in water. When we say that water occurs in the composition of a certain hydrate, we only wish to point out that there are chemical transformations in which it is possible to obtain that hydrate by means of water, and other transformations in which this water may be separated out from the hydrate. This is all simply expressed by the words, that water enters into the composition of this hydrate. If a hydrate be formed by feeble bonds, and be decomposed at even the ordinary temperature, then the water appears as one of the products of dissociation, which in all likelihood is the case in solutions; and forms the fundamental distinction between them and other hydrates in which the water is combined with greater stability and forms a solid substance.

and 18 $\frac{1}{2}$, and most often form gelatinous masses. Water is held in a considerable quantity in solidified glue or boiled albumin. It cannot be expelled from them by pressure; hence, in this case there has ensued some kind of combination of the substance with water. This water, however, is easily separated by drying; but not the whole of it, a portion being retained, and this portion belongs, as they say, to the hydrate, although in this case it is very difficult, if possible, to obtain definite compounds. The absence of any distinct boundary lines between solutions, crystallo-hydrates, and ordinary hydrates above referred to, is very clearly seen in such examples.

CHAPTER II

THE COMPOSITION OF WATER, HYDROGEN

THE question now arises, Is not *water* itself a *compound substance*? Cannot it be formed by the mutual combination of some component parts? Cannot it be broken up into its component parts? There cannot be the least doubt that if it does split up, and if it is a compound, then it is a *definite* one characterised by the stability of the union between those component parts from which it is formed. From the fact alone that water passes into all physical states as a homogeneous whole, without in the least varying in its properties and without splitting up into its component parts (neither solutions nor many hydrates can be distilled—they are split up), we must already conclude, from this fact alone, that if water is a compound then it is a stable and definite chemical compound. Like many other great discoveries in the province of chemistry, it is to the end of the last century that we are indebted for the important discovery that water is not a simple substance, that it is composed of two substances like a number of other compound substances. This was proved by two of the methods by which the compound nature of bodies may be determined as self-evident; by analysis and by synthesis—that is, by a method of the decomposition of water into, and of the formation of water from, its component parts. In 1781 Cavendish first obtained water by burning hydrogen in oxygen, both of which gases were already known to him. He concluded from this that water was composed of two substances. But he did not make more accurate experiments, which would have shown the relative quantities of the component parts in water, and which would have determined its complex nature with certainty. Although his experiments were the first, and although the conclusion he drew from them was true, yet such novel ideas as the complex nature of water are not easily recognised so long as there is no series of researches which entirely and indubitably proves the truth of such a conclusion. The fundamental experiments which proved the complexity of water by the method of synthesis, and of its formation from other substances, were made in 1789 by Monge,

Lavoisier, Fourcroy, and Vauquelin. They obtained four ounces of water by burning hydrogen, and found that water consists of 15 parts of hydrogen and 85 parts of oxygen. It was also proved that the weight of water formed was equal to the sum of the weights of the component parts entering into its composition ; consequently, water contains all the matter entering into oxygen and hydrogen. The complexity of water was proved in this manner by a method of synthesis. But we will turn to its analysis --*i.e.*, to its decomposition into its component parts. The analysis may be more or less complete. Either both component parts may be obtained in a separate state, or else only one is separated and the other is converted into a new compound in which its amount may be determined by weighing. This will be a reaction of substitution, such as is often taken advantage of for analysis. The first analysis of water was thus conducted in 1784 by Lavoisier and Meusnier. The apparatus they arranged consisted of a glass retort containing water, naturally purified, and whose weight had been previously determined. The neck of the retort was inserted into a porcelain tube, placed inside an oven, and heated to a red heat by charcoal. Iron filings, which decompose water at a red heat, were placed inside this tube. The end of the tube was connected with a worm, for condensing any water which might pass through the tube undecomposed. This condensed water was collected in a separate flask. The gas formed by the decomposition was collected over a water bath in a bell jar. The aqueous vapour in passing over the red-hot iron was decomposed, and a gas was formed from it whose weight could be determined from its volume, its density being known. Besides the water which passed through the tube unaltered, a certain quantity of water disappeared in the experiment, and this quantity, in the experiments of Lavoisier and Meusnier, was equal to the weight of the gas which was collected in the bell jar plus the increase in weight of the iron filings. Hence the water was decomposed into a gas, which was collected in the bell jar, and a substance, which combined with the iron ; consequently, it is composed of these two component parts. This was the first analysis of water ever made ; but here only one (and not both) of the gaseous component parts of water was collected separately. Both the component parts of water can, however, be simultaneously obtained in a free state. For this purpose the decomposition is brought about by a galvanic current or by heat, as we shall learn directly.¹

¹ The first experiments of the synthesis and decomposition of water did not afford, however, an entirely convincing proof that water was composed of hydrogen and oxygen only. Davy, who investigated the decomposition of water by the galvanic current, thought for a long time that, besides the gases, an acid and alkali were also obtained.

Water is a bad conductor of electricity—that is, pure water does not transmit a feeble current ; but if any salt or acid be dissolved in it, then its conductivity increases, and *on the passage of a current* through acidified water *it is decomposed* into its component parts. Some sulphuric acid is generally added to the water. By immersing platinum plates (electrodes) in this water (platinum is chosen because it is not acted on by acids, whilst many other metals are chemically acted on by acids), and connecting them with a galvanic battery, it will be observed that bubbles of gas appear on these plates. The gas which separates is called *detonating gas*,² because, on approaching a light, it very easily explodes.³ What takes place is as follows :—First, the water, by the action of the current, is decomposed into two gases. The mixture of these gases forms detonating gas. When detonating gas is brought into contact with an incandescent substance—for instance, a lighted taper—the gases re-combine, forming water, the combination being accompanied by a great evolution of heat, and therefore the vapour of the water formed expands considerably, which it does very rapidly, and as a consequence of which an explosion takes place—that is, sound and increase of pressure, and atmospheric commotion, as in the explosion of gunpowder.

In order to discover what gases are obtained by the decomposition of water, the gases which separate at each electrode must be collected separately. For this purpose a V-shaped tube is taken ; one of its ends is open, and the other fused up. A platinum wire, terminating inside the tube in a plate, is fused into the closed end ;

He was only convinced of the fact that water contains nothing but hydrogen and oxygen by a long series of researches, which showed him that the appearance of an acid and alkali in the decomposition of water proceeds from the presence of impurities (especially from the presence of ammonium nitrate) in water. A final understanding of the composition of water is obtained from the determination of the quantities of the component parts which enter into its composition. It will be seen from this how many data are necessary for proving the composition of water—that is, of the transformations of which it is capable. What has been said of water refers to all other compounds ; the investigation of each one, the entire proof of its composition, can only be obtained by the juxtaposition of a large mass of data referring to it.

² This gas is collected in a voltameter.

³ In order to observe this explosion without the slightest danger, it is best to proceed in the following manner. Some soapy water is prepared, so that it easily forms soap bubbles, and it is poured into an iron trough. In this water, the end of a gas-conducting tube is immersed. This tube is connected with any suitable apparatus, in which detonating gas is evolved. Soap bubbles, full of this gas, are then formed. If the apparatus in which the gas is produced be then removed (otherwise the explosion might travel into the interior of this apparatus), and a lighted taper be brought to the soap bubbles, a very sharp explosion takes place. The bubbles should be small to avoid any danger ; ten, each about the size of a pea, suffice to give a sharp report, like a pistol shot.

the closed end is entirely filled with water ⁴ acidified with sulphuric acid, and another platinum wire, terminating in a plate, is immersed in the open end. If a current from a galvanic battery be now passed through the wires an evolution of gases will be observed, and the gas which is obtained in the open branch mixes with the air, while that in the closed branch accumulates above the water. As this gas accumulates it displaces the water, which continues to descend in the closed and ascend into the open branch of the tubes. When the water, in this way, reaches the top of the open end, the passage of the current is stopped, and the gas which was evolved from one of the electrodes only is obtained in the apparatus. By this means it is easy to prove that a particular gas appears at each electrode. If the closed end be connected with the negative pole -*i.e.*, with that joined to the zinc—then the gas collected in the apparatus is capable of burning. This may be demonstrated by the following experiment:—The bent tube is taken off the stand, and its open end stopped up with the thumb and inclined in such a manner that the gas passes from the closed to the open end. It will then be found, on applying a lighted lamp or taper, that the gas burns. This combustible gas is *hydrogen*. If the same experiment be carried on with a current passing in the opposite direction—that is, if the closed end be joined up with the positive pole (*i.e.*, with the carbon, copper, or platinum), then the gas which is evolved from it does not burn of itself, but it supports combustion very vigorously, so that in it a smouldering taper immediately bursts into flame. This gas, which is collected on the anode or positive pole, is *oxygen*, which is obtained, as we saw before (in the Introduction), from mercury oxide and is contained in air.

Thus in the decomposition of water oxygen appears at the positive pole and hydrogen at the negative pole, so that detonating gas will be a mixture of them both. Hydrogen burns in air from the fact that in doing so it re-forms water, with the oxygen of the air. Detonating gas explodes from the fact that the hydrogen burns in the oxygen mixed with it. It is very easy to measure the relative quantities of one and the other gas which are evolved in the decomposition of water. For this purpose a funnel is taken, whose orifice is closed by a cork through which two platinum wires pass. These wires are connected with a battery. Acidified water is poured into the funnel, and a glass cylinder full of water is placed over the end of each wire (fig. 18). On passing a current, hydrogen and oxygen collect in these cylinders,

⁴ In order to fill the tube with water, it is turned up, so that the closed end points downwards and the open end upwards, and water acidified with sulphuric acid is poured into it.

and it will easily be seen that two volumes of hydrogen are evolved for every one volume of oxygen. This signifies that, in decomposing, water gives two volumes of hydrogen and one volume of oxygen.




FIG. 18.—Decomposition of water by the galvanic current, for determining the relation between the volumes of hydrogen and oxygen.

Water is also decomposed into its component parts by *the action of heat*. At the melting point of silver (960°), and in its presence, water is decomposed and the oxygen absorbed by the molten silver, which dissolves it so long as it is liquid. But directly the silver solidifies the oxygen is expelled from it. However, this experiment is not entirely convincing; it might be thought that in this case the decomposition of the water did not proceed from the action of heat, but from the action of the silver on water—that silver decomposes water, taking up the oxygen. It is impossible to directly show the decomposition of water by the action of heat, because the component parts of water, if they remain

together, re-combine with a fall of temperature, and give water back again. For instance, if steam be passed through a red-hot tube, whose internal temperature attains $1,000^{\circ}$, then a portion⁵ of the water decomposes into its component parts, forming detonating gas. But on passing into the cooler portions of the apparatus this detonating gas again reunites and forms water. The hydrogen and oxygen obtained combine together at a lower temperature.⁶ Apparently the problem—

⁵ As water is formed by the combination of oxygen and hydrogen, the reaction evolving much heat, and as it can also be decomposed, therefore this reaction is a reversible one (*see* Introduction), and consequently at a high temperature the decomposition of water cannot be complete—it is limited by the opposite reaction. Strictly speaking, it is not known how much water is decomposed at a given temperature, although many efforts (Bunsen, and others) have been made in various directions to solve this question. Not knowing the coefficient of expansion, and the specific heat of gases at such high temperatures, renders all calculations (from observations of the pressure on explosion) doubtful.

⁶ Grove, about 1840, observed that a platinum wire fused in the flame of detonating gas—that is, having acquired the temperature of the formation of water—and having formed a molten drop at its end which fell into water, evolved detonating gas—that is, decomposed water. It therefore follows that water already decomposes at the temperature of its formation. At that time, this formed a scientific paradox; this we shall unravel only with the development of the conceptions of dissociation, introduced into science by Henri Sainte-Claire Deville, about 1850. These conceptions form an important epoch in science, and their development is one of the problems of contemporary chemistry. The essence of the matter is that, at high temperatures, water exists but also decomposes, just as a volatile liquid, at a certain temperature, exists both as a liquid and

to show the decomposability of water at high temperatures is unattainable. It was considered as such before Henri Sainte-Claire Deville (in the fifties) introduced the conception of dissociation into chemistry, as of a change of chemical state resembling evaporation, if decomposition be likened to boiling, and before he had demonstrated the decomposability of water by the action of heat in an experiment which will presently be described. In order to demonstrate clearly the *dissociation* of water, or its decomposability by heat, at a temperature approaching that at which it is formed (as a volatile liquid, at a given temperature, can be either in a liquid or vaporous condition) it was necessary to separate the hydrogen from the oxygen at a high temperature, without allowing the mixture to cool. Deville took advantage of the difference between the densities of hydrogen and oxygen.

A wide porcelain tube *P* (fig. 19) is placed in a furnace giving a




FIG. 19. Decomposition of water by the action of heat, and the separation of the hydrogen formed by its permeating through a porous tube.

strong heat (it should be heated with small pieces of good coke). In this tube there is inserted a second tube *T*, of less diameter, and made of unglazed earthenware and therefore porous. The ends of the tube are luted to the wide tube, and two tubes, *c* and *c'*, are inserted into the ends, as shown in the drawing. With this arrangement it is possible for a gas to pass into the annular space between the walls of the two tubes, from whence it can be collected. Steam from

as a vapour. Similarly as a volatile liquid saturates a space, attaining its maximum tension, so also the products of dissociation have their maximum tension, and once that is attained decomposition ceases, just as evaporation ceases. Under like conditions, if the vapour be allowed to escape (and therefore its partial pressure be diminished), evaporation recommences, so also if the products of decomposition be removed, decomposition again continues. These simple conceptions of dissociation introduce infinitely varied consequences into the mechanism of chemical reactions, and therefore we shall have occasion to return to them very often.

a retort or flask is passed through the tube *D*, into the internal porous tube *T*. This steam on entering the red hot space is decomposed into hydrogen and oxygen. The densities of these gases are very different, hydrogen being sixteen times lighter than oxygen. Light gases, as we saw above, penetrate through porous surfaces very much more rapidly than denser gases, and therefore the hydrogen passes through the pores of the tube into the annular space very much more rapidly than the oxygen. The hydrogen which separates out into the annular space can only be collected when this space does not contain any oxygen. If any air remains in this space, then the hydrogen which separates out will combine with its oxygen and form water. For this reason a gas incapable of supporting combustion—for instance, nitrogen—is previously passed in the annular space. Thus the nitrogen is passed through the tube *C*, and the hydrogen, separated from the steam, is collected through the tube *C'*, and will be partly mixed with nitrogen. A certain portion of the nitrogen will penetrate through the pores of the unglazed tube into the interior of the tube *T*. The oxygen will remain in this tube, and the volume of the remaining oxygen will be half that of the volume of hydrogen which separates out from the annular space. Part of the oxygen will also penetrate through the pores of the tube; but, as was said before, a much smaller quantity than the hydrogen, and as the density of oxygen is sixteen times greater than that of hydrogen, the volume of oxygen which passes through the porous walls will be four times less than the volume of hydrogen (the quantities of gases passing through porous walls are inversely proportional to the square roots of their densities). The oxygen which separates out into the annular space will combine, at a certain fall of temperature, with the hydrogen; but as each volume of oxygen only requires two volumes of hydrogen, whilst at least four volumes of hydrogen will pass through the porous walls for every volume of oxygen that passes, therefore, part of the hydrogen will remain free, and can be collected from the annular space. A corresponding quantity of oxygen remaining from the decomposition of the water can be collected from the internal tube.

The decomposition of water is produced much more easily by a method of substitution, taking advantage of the affinity of substances for the oxygen or the hydrogen of water. If a substance be added to water, which takes up the oxygen and replaces the hydrogen—then we shall obtain the latter gas from the water. Thus with sodium, water gives hydrogen, and with chlorine, which takes up the hydrogen, oxygen is obtained.

Hydrogen is evolved from water by many metals, which are capable

of forming oxides (rusts or earths, as Stahl called them) in air—that is, which are capable of burning or combining with oxygen. The capacity of metals for combining with oxygen, and therefore for decomposing water, or for the evolution of hydrogen, is very dissimilar.⁷ Among metals, potassium and sodium have the greatest energy in this respect. The first occurs in potash, the second in soda. They are both lighter than water, soft, and easily change in air. By bringing one or the other of them in contact with water at the ordinary temperature,⁸ a quantity of

⁷ In order to demonstrate the difference of the affinity of oxygen for different elements, it is enough to compare the amounts of heat which are evolved in their combination with 16 parts by weight of oxygen; in the case of sodium (when Na_2O is formed, or 46 parts of Na combine with 16 parts of oxygen, according to Beketoff) 100,000 calories (or units of heat) are evolved, for hydrogen (when water, H_2O , is formed) 69,000 calories, for iron (when the oxide, FeO , is formed) 69,000, and if the oxide Fe_2O_3 is formed, 64,000 calories, for zinc (ZnO is formed) 86,000 calories, for lead (when PbO is formed) 51,000 calories, for copper (when CuO is formed) 38,000 calories, and for mercury (HgO is formed) 31,000 calories.

These figures cannot correspond directly with the magnitude of the affinities, for the physical and mechanical side of the matter is very different in the different cases. Hydrogen is a gas, and, in combining with oxygen, gives a liquid; consequently it changes its physical state, and, in doing so, evolves heat. But zinc and copper are solids, and, in combining with oxygen, give solid oxides. The oxygen, previously a gas, now passes into a solid or liquid state, and, therefore, also must have given up its store of heat in forming oxides. As we shall afterwards see, the degree of contraction (and consequently of mechanical work) was different in the different cases, and therefore the figures expressing the heat of combination cannot directly depend on the affinities, on the loss of internal energy previously in the elements. Nevertheless, the figures above cited correspond; in a certain degree, with the order in which the elements stand in respect to their affinity for oxygen, as may be seen from the fact that the mercury oxide, which evolves the least heat (among the above examples), is the least stable, is easily decomposed, giving up its oxygen; whilst sodium, the formation of whose oxide is accompanied by the greatest evolution of heat, is able to decompose all the other oxides, taking up their oxygen. In order to generalise the connection between affinity and the evolution and the absorption of heat, which is evident in its general features, and was firmly established by the researches of Favre and Silberman (about 1840), and then of Thomsen (in Denmark) and Berthelot (in France), many investigators, especially the one last mentioned, established the *law of maximum work*. This states that only those chemical reactions take place of their own accord in which the greatest amount of chemical (latent, potential) energy is transformed into heat. But, in the first place, we are not able, judging from what has been said above, to distinguish that heat which corresponds with purely chemical action from the sum total of the heat observed in a reaction (in the calorimeter); in the second place, there are evidently endothermal reactions which proceed under the same circumstances as exothermal (carbon burns in the vapour of sulphur with absorption of heat, whilst in oxygen it evolves heat); and, in the third place, there are reversible reactions, which when taking place in one direction evolve heat, and when taking place in the opposite direction absorb it; and, therefore, the principle of maximum work in its elementary form is not supported by science. But the subject continues to be developed, and will probably lead to a general law, such as thermal chemistry does not at present possess.

⁸ If a piece of metallic sodium be thrown into water, it floats on it (owing to its lightness), keeps in a state of continual movement (owing to the evolution of hydrogen on all sides), and immediately decomposes the water, evolving hydrogen, which can be

hydrogen, corresponding with the amount of the metal taken, may be directly obtained. One gram of hydrogen, occupying a volume of 11.16 litres at 0° and 760 mm., is evolved per 39 grams of potassium, or 23 grams of sodium. The phenomenon may be observed in the following way : a solution of sodium in mercury— or ‘sodium amalgam,’ as it is generally called—is poured into a vessel containing water, and owing to its weight sinks to the bottom ; the sodium held in the mercury then acts on the water like pure sodium, liberating hydrogen. The mercury does not act here, and the same amount of it as was taken for dissolving the sodium is obtained in the residue. The hydrogen is evolved little by little in the form of bubbles, which pass through the liquid.

Beyond the hydrogen evolved and a solid substance, which remains in solution (it may be obtained by evaporating the resultant solution), no other products are here obtained. Consequently, from the two substances (water and sodium) taken, the same number of new substances (hydrogen and the substance dissolved in water) have been obtained, from which we may conclude that the reaction which here takes place is a reaction of double decomposition or of substitution. The substances taken were, sodium in a free state, and water, which consists of two gases, hydrogen and oxygen. The products obtained were, hydrogen in the free state and a solid, which is nothing else but the so-called caustic soda (sodium hydroxide), which is made up of sodium, oxygen, and half of the hydrogen contained in the water. Therefore, the substitution took place between the hydrogen and the sodium, namely half of the hydrogen in the water was replaced by the sodium, and was evolved in a free state. On this basis it may be said that caustic soda is nothing else but water, in which half the hydrogen is replaced by metallic sodium. The reaction which takes place

lighted. This experiment may, however, lead to an explosion should the sodium stick to the walls of the vessel, and begin to act on the limited mass of water immediately adjacent to it (probably in this case NaHO forms with Na , Na_2O , which acts on the water, evolving much heat and rapidly forming steam), and the experiment should therefore be carried on with caution. The decomposition of water by sodium may be better demonstrated, and with greater safety, in the following manner. Into a glass cylinder filled with mercury, and immersed in a mercury bath, water is first introduced, which will, owing to its lightness, rise to the top, and then a piece of sodium wrapped in paper is introduced with forceps into the cylinder. The metal rises through the mercury to the surface of the water, on which it remains, and evolves hydrogen, which collects in the cylinder, and may be tested after the experiment has been completed. The safest method of making this experiment is, however, as follows. The sodium (cleaned from the naphtha in which it is kept) is either wrapped in fine copper gauze and held by forceps, or else held in forceps at the end of which a small copper cage is attached, and is then held under water. The evolution of hydrogen goes on quietly, and it may be collected in a bell jar and then lighted.

may be expressed by the equation : $\text{H}_2\text{O} + \text{Na} = \text{NaHO} + \text{H}$; the meaning of this is clear from what has been already said.⁹

Sodium and potassium act on water at the ordinary temperature. Other heavier metals only act on it with a rise of temperature, and then not so rapidly or vigorously. Thus magnesium and calcium only liberate hydrogen from water at its boiling point, and zinc and iron only at a red heat, whilst a whole series of heavy metals, such as copper, lead, mercury, silver, gold, and platinum, do not in the least decompose water at any temperature, and do not replace its hydrogen.

From this it is clear that hydrogen may be obtained by the decomposition of steam by the action of iron (or zinc) with a rise of temperature. The experiment is conducted in the following manner : pieces of iron (filings, nails, &c.), are laid in a porcelain tube, which is then

⁹ This reaction is vigorously exothermal. If a sufficient quantity of water be taken the whole of the sodium hydroxide, NaHO , formed is dissolved, and about 42,500 units of heat are evolved per 23 grams of sodium taken. As 40 grams of sodium hydroxide are produced, and they in dissolving, judging from direct experiment, evolve about 10,000 calories ; therefore, without an excess of water, and without the formation of a solution, the reaction $\text{Na} + \text{H}_2\text{O} = \text{H} + \text{NaHO}$ would evolve about 32,500 calories. We shall afterwards learn that hydrogen contains in its smallest isolable particles H_2 and not H , and therefore it follows that the reaction should be written thus— $2\text{Na} + 2\text{H}_2\text{O} = \text{H}_2 + 2\text{NaHO}$, and it then corresponds with an evolution of heat of +65,000 calories. And as N. N. Beketoff showed that Na_2O , or anhydrous oxide of sodium, forms the hydrate, or sodium hydroxide (caustic soda), 2NaHO , with water, evolving about 35,500 calories, therefore the reaction $2\text{Na} + \text{H}_2\text{O} = \text{H}_2 + \text{Na}_2\text{O}$ corresponds to 29,500 calories. This quantity of heat is less than that which is evolved in combining with water, in the formation of caustic soda, and therefore it is not to be wondered at that the hydrate, NaHO , is always formed and not the anhydrous substance Na_2O . That such a conclusion, which agrees with facts, is inevitable is also seen from the fact that, according to Beketoff, the anhydrous sodium oxide, Na_2O , acts directly on hydrogen, with separation of sodium $\text{Na}_2\text{O} + \text{H} = \text{NaHO} + \text{Na}$. This reaction is accompanied by an evolution of heat equal to about 3,000 calories, because $\text{Na}_2\text{O} + \text{H}_2\text{O}$ gives, as we saw, 35,500 calories and $\text{Na} + \text{H}_2\text{O}$ evolves 32,500 calories. However, an opposite reaction also takes place— $\text{NaHO} + \text{Na} = \text{Na}_2\text{O} + \text{H}$ (both with the aid of heat)—consequently, in this case heat is absorbed. In this we see an example of calorimetric calculations and the small use of the law of maximum work for the general phenomena of reversible reactions, to which the case just considered belongs. But it must be remarked that all reversible reactions evolve or absorb but little heat, and judging from what has been said in Note 6 (and in Note 25 of Chap. I.), the reason of the discrepancy between the law of maximum work and reality must before all be looked for in the fact that we have no means of separating the heat which corresponds with the purely chemical process from the sum total of the heat observed, and as the structure of a number of substances is altered by heat alone and also by contact, we can scarcely hope that the time approaches when such a distinction will be possible. A heated substance, in point of fact, has no longer the original energy of its atoms—that is, the act of heating not only alters the store of movement of the molecules but also of the atoms forming the molecules, in other words, it makes the beginning of or preparation for chemical change. From this it must be concluded that thermo-chemistry, or the study of the heat accompanying chemical transformations, cannot be identified with chemical mechanics. Thermo-chemical data form a part of it, but they alone cannot give it.

subjected to a strong heat and steam passed through it. The steam, coming into contact with the iron, gives up its oxygen to it, and thus the hydrogen is set free and passes out at the other end of the tube together with undecomposed steam. This method, which is historically very significant,¹⁰ is practically inconvenient, as it requires a rather high temperature. Further, this reaction, as a reversible one (a red-hot mass of iron decomposes a current of steam, forming oxide and hydrogen; and a mass of oxide of iron, heated to redness in a stream of hydrogen, forms iron and steam), does not proceed in virtue of the comparatively small difference between the affinity of oxygen for iron (or zinc), and for hydrogen, but only because the hydrogen escapes, as it is formed, in virtue of its elasticity.¹¹ If the oxygen compounds—that is, the oxides—which are obtained from the iron or zinc, be able to pass into solution, then the affinity acting in solution is added, and the reaction may become non-reversible, and proceed with comparatively much greater facility.¹² As the oxides of iron and zinc, by themselves

¹⁰ The composition of water, as we saw above, was determined by passing steam over red-hot iron; the same method has been used for making hydrogen for filling balloons. An oxide having the composition Fe_3O_4 is formed in the reaction, so that it is expressed by the equation $3\text{Fe} + 4\text{H}_2\text{O} = \text{Fe}_3\text{O}_4 + 8\text{H}$. It is very important to remark that this reaction is reversible. By heating the scoria in a current of hydrogen, water and iron are obtained. From this it follows, from the principle of chemical equilibria, that if there be taken iron and hydrogen, and also oxygen, but in such a quantity that it is insufficient for combination with both substances, then it will divide itself between the two; part of it will combine with the iron and the other part with the hydrogen, but a portion of both will remain in an uncombined state. Here again (*see* note 9) the reversibility is connected with the small heat effect, and here again both reactions (direct and reverse) proceed at a red heat. But if, in the above-described reaction, the hydrogen escapes as it is evolved, then its partial pressure does not increase with its formation, and therefore all the iron can be oxidised by the water, which could not take place were the iron and water heated to the temperature of reaction in a closed vessel. In this we see the elements of that influence of mass to which we shall have occasion to return later.

¹¹ Therefore, if iron and water be placed in a closed space, decomposition of the water will proceed on heating to the temperature at which the reaction $3\text{Fe} + 4\text{H}_2\text{O} = \text{Fe}_3\text{O}_4 + 8\text{H}$ commences; but it ceases, does not go on to the end, because the conditions for a reverse reaction are attained, and a state of equilibrium will ensue after the decomposition of a certain quantity of water. Judging from what has been said in Note 9, something of the same kind takes place if the iron be replaced by sodium, only then the mass of the water decomposed will be greater, and equilibrium will ensue, with the formation of the hydrate, NaHO , and not of anhydrous oxide, Na_2O —that is, the water will remain in the form of hydrate only. With copper and lead there will be no decomposition, either at the ordinary or at a high temperature, because the affinity of these metals for oxygen is much less than that of hydrogen.

¹² In general, if reversible as well as non-reversible reactions can take place between substances acting on each other, then, judging by our present knowledge, the non-reversible reactions take place in the majority of cases, which obliges one to acknowledge the action, in this case, of comparatively strong affinities. The reaction, $\text{Zn} + \text{H}_2\text{SO}_4 = \text{H}_2 + \text{ZnSO}_4$, which takes place in solutions at the ordinary temperature, is scarcely reversible under these conditions, but at a certain high temperature it becomes reversible,

insoluble in water, are capable of combining with (have an affinity for) acid oxides (as we shall afterwards fully consider), and form saline and soluble substances, with acids, or hydrates having acid properties, hence by the action of such hydrates, or of their aqueous solutions,¹³ iron and zinc are able to liberate hydrogen with great ease at the ordinary temperature—that is, they act on solutions of acids just as sodium acts on water.¹⁴ Sulphuric acid, or oil of vitriol, H_2SO_4 , is usually chosen

because at this temperature zinc sulphate and sulphuric acid split up, and the action must take place between the water and zinc. From the preceding proposition results proceed which are in some cases verified by experiment. If the action of zinc or iron on a solution of sulphuric acid presents a non-reversible reaction, then we may by this means obtain hydrogen in a very compressed state, and compressed hydrogen will not act on solutions of sulphates of the above-named metals. This is verified in reality as far as was possible in the experiments to keep up the compression or pressure of the hydrogen. Those metals which do not evolve hydrogen with acids, on the contrary, should, at least at an increase of pressure, be displaced by hydrogen. And in fact Brunner showed that gaseous hydrogen displaces platinum and palladium from the aqueous solutions of their chlorine compounds, but not gold, and Beketoff succeeded in showing that silver and mercury, under a considerable pressure, are separated from the solutions of certain of their compounds by means of hydrogen. Reaction already commences under a pressure of six atmospheres, if a weak solution of silver sulphate be taken; with a stronger solution a much greater pressure is required, however, for the separation of the silver.

¹⁵ For the same reason, many metals in acting on solutions of the alkalis displace hydrogen. Aluminium acts particularly clearly in this respect, because its oxide gives a soluble compound with alkalis. For the same reason tin, in acting on hydrochloric acid, evolves hydrogen, and silicon does the same with hydrofluoric acid. It is evident that in such cases the sum of all the affinities plays a part; for instance, taking the action of zinc on sulphuric acid, we have the affinity of zinc for oxygen (forming zinc oxide, ZnO), the affinity of its oxide for sulphuric anhydride, SO_3 (forming zinc sulphate, ZnSO_4), and the affinity of the resultant salt, ZnSO_4 , for water. It is only the first-named affinity that acts in the reaction between water and the metal, if no account is taken of those forces (of a physico-mechanical character) which act between the molecules (for instance, the cohesion between the molecules of the oxide) and those forces (of a chemical character) which act between the atoms forming the molecule, for instance, between the atoms of hydrogen giving the molecule H_2 containing two atoms. I consider it necessary to remark, that the hypothesis of the affinity or endeavour of heterogeneous atoms to enter into a common system and in harmonious movement (*i.e.*, to form a compound molecule) must inevitably be in accordance with the hypothesis of forces inducing homogeneous atoms to form complex molecules (for instance, H_2), and to build up the latter into solid or liquid substances, in which the existence of an attraction between the homogeneous particles must certainly be admitted. Therefore, those forces which bring about solution must also be taken into consideration. These are all forces of one and the same series, and in this may be seen the great difficulties surrounding the study of molecular mechanics and its province—chemical mechanics.

¹⁴ The representation given above of the cause of the easy action of iron or zinc on sulphuric acid, naturally forms a hypothesis which explains only what is observed. It is only at first sight that this hypothesis exhibits any similarity to the hypothesis of *predisposing affinity* which reigned in past times. According to that, it was supposed that reaction takes place (and hydrogen is evolved) by reason of the affinity for the sulphuric acid of the oxide of zinc which might be produced, and that decomposition could not take place without this. The influence of a force in respect to a substance which has not been produced, but which is capable of being formed, is not clear. In the representation introduced by me, it is acknowledged that zinc already acts on water by

for this purpose ; from it the hydrogen is displaced by many metals with incomparably greater facility than directly from water, and such a displacement is accompanied by the evolution of a large amount of heat.¹⁵ By the action of zinc or iron on sulphuric acid, hydrogen is evolved, because the metal replaces it. When the hydrogen in sulphuric acid is replaced by a metal, a substance is obtained which is called a salt of sulphuric acid or a sulphate. Thus, by the action of zinc on sulphuric acid, hydrogen and zinc sulphate, ZnSO_4 , are obtained. The latter is a solid substance, soluble in water. In order that the action of the metal on the acid should go on regularly, and to the end, it is necessary that the acid should be diluted with water, which dissolves the salt as it is formed ; otherwise the salt covers the metal, and hinders the acid from attacking it. Usually the acid is diluted with from three to five times its volume of water, and the metal is covered with this solution. In order that the metal should act rapidly on the acid, it should present a large surface, so that a maximum amount of the reacting substances may come into contact in a given time. For this purpose the zinc is used as strips of sheet zinc, or in the granulated form (that is, zinc which has been poured from a certain height, in a molten state, into water). The iron should be in the form of wire, nails, filings, or cuttings.

The usual method of obtaining hydrogen is as follows : A certain quantity of granulated zinc is put into a double-necked, or Woulfe's, bottle. Into one neck a funnel is placed, reaching to the bottom of the bottle, so that the liquid poured in may prevent the hydrogen from

itself, even at the ordinary temperature, but that the action is limited by small masses and only proceeds at the surface. In reality, zinc, in the form of a very fine powder, or so called 'zinc dust,' is capable of decomposing water with the formation of oxide (hydrated) and hydrogen. The oxide formed acts on sulphuric acid, water then dissolves the salt produced, and the action continues because one of the products of the action of water on zinc, zinc oxide, is removed from the surface. One might naturally imagine that the reaction does not proceed directly between the metal and water, but between the metal and the acid, but such a simple representation, which we shall cite afterwards, hides the mechanism of the reaction, and does not permit of its actual complexity being seen.

¹⁵ According to Thomsen the reaction between zinc and a very weak solution of sulphuric acid evolves about 38,000 calories (zinc sulphate being formed) per 65 parts by weight of zinc ; and 56 parts by weight of iron—which combine, like 65 parts by weight of zinc, with 16 parts by weight of oxygen—evolve about 25,000 calories (forming ferrous sulphate, FeSO_4). Paracelsus observed the action of metals on acids in the seventeenth century ; but it was not until the eighteenth century that Lémery determined that the gas which is evolved in this action is a particular one which differs from air and is capable of burning. Even Boyle confused it with air. Cavendish determined the chief properties of the gas discovered by Paracelsus. At first it was called 'inflammable air' ; later, when it was recognised that in burning it gives water, it was called hydrogen, from the Greek words for water and generator.

escaping through it. The gas escapes through a special gas-conducting tube, which is firmly fixed, by a cork, into the other neck, and which ends in a water bath (fig. 20), under the orifice of a glass cylinder full




FIG. 20.—Apparatus for the preparation of hydrogen from zinc and sulphuric acid.

of water.¹⁶ If sulphuric acid be now poured into the Woulfe's bottle, it will soon be seen that bubbles of a gas are evolved, which is hydrogen.

¹⁶ As laboratory experiments with gases require a certain preliminary knowledge, we will describe certain *practical methods for the preparation and collection of gases*. When in laboratory practice an intermittent supply of hydrogen (or other gas which is evolved without the aid of heat) is required the apparatus represented in fig. 21 is the




FIG. 21.—A very convenient apparatus for the preparation of gases obtained without heat. It may also replace an aspirator or gasometer.

most convenient. It consists of two bottles, having orifices at the bottom, in which corks with tubes are placed, and these tubes are connected by an india-rubber tube (sometimes furnished with a spring clamp). Zinc is placed in one bottle, and dilute sul-

The first part of the gas evolved should not be collected, as it is mixed with the air originally in the apparatus. This precaution

phuric acid in the other. The neck of the former is closed by a cork, which is fitted with a gas-conducting tube with a stop-cock. If the two bottles are put in communication with each other and the cock be opened, the acid will flow to the zinc and evolve hydrogen. If the cock be closed, the hydrogen will force out the acid from the bottle containing the zinc, and the action will cease. Or the vessel containing the acid may be placed at a lower level than that containing the zinc, when all the liquid will flow into it, and in order to start the action the acid vessel may be placed on a higher level than the other, and the acid will flow to the zinc. Such an arrangement presents the simplest form of a continuously-acting apparatus, which is of great use in chemical work. It can also be employed for collecting gases (as an aspirator or gasometer).

In laboratory practice, however, other forms of apparatus are generally employed for




FIG. 22.—Constant-acting aspirator. The tube *d* should be long (over 32 feet).

exhausting, collecting, and holding gases. We will here cite the most usual forms. An *aspirator* usually consists of a vessel furnished with a stop-cock at the bottom. A stout

should be taken in the preparation of all gases. Time must be allowed for the gas evolved to displace all the air from the apparatus, other-

cork, through which a glass tube passes, is fixed into the neck of this vessel. If the vessel be filled up with water to the cork and the bottom stop-cock be opened, then the water will run out and draw gas in. For this purpose the glass tube is connected with the apparatus from which it is desired to pump out or exhaust the gas.

The aspirator represented in fig. 22 may be recommended for its continuous action. It consists of a tube *d* which widens out at the top, the lower part being long and narrow. In the expanded upper portion *c*, two tubes are sealed; one, *e*, for drawing in the gas, whilst the other, *b*, is connected to the water supply *w*. The amount of water supplied through the tube *b* must be less than the amount which can be carried off by the tube *d*. Owing to this the water in the tube *d* will flow through it in cylinders alternating with cylinders of gas, which will be thus carried away. The gas which is drawn through may be collected from the end of the tube *d*, but this form of pump is usually employed where the air or gas aspirated is not to be collected. If the tube *d* is of considerable length, say 40 ft. or more, a very fair vacuum will be produced, the amount of which is shown by the gauge *g*; it is often used for filtering under reduced pressure, as shown in the figure. If water be replaced by mercury, and the length of the tube *d* be greater than 760 mm., the aspirator may be employed as an air-pump, and all the air may be exhausted from a limited space; for instance, by connecting *g* with a hollow sphere.

Gasholders are often used for collecting and holding gases. They are made of glass, copper, or tin plate. The usual form is shown in fig. 23. The lower vessel *B* is made

hermetically tight — *i.e.*, impervious to gases—and is filled with water. A funnel is attached to this vessel (on several supports). The vessel *B* communicates with the bottom of the funnel by a stop-cock *b* and a tube *a*, reaching to the bottom of the vessel *B*. If water be poured into the funnel and the stop-cocks *a* and *b* opened, the water will run through *a*, and the air escape from the vessel *B* by *b*. A glass tube *f* runs up the side of the vessel *B*, with which it communicates at the top and bottom, and shows the amount of water and gas the gasholder contains. In order to fill the gasholder with a gas, it is first filled with water, the cocks *a*, *b* and *e* are closed, the nut *d* unscrewed, and the end of the tube conducting the gas from the apparatus in which it is generated is passed into *d*. As the gas fills the gasholder, the water runs out at *d*. If the pressure of a gas be not greater than the atmospheric pressure and it be required to collect it in the gasholder, then the cock *e* is put into communication with the space containing the gas. Then, having opened the orifice *d*, the gasholder acts like an aspirator; the gas will pass through *e*, and the water run out at *d*. If




Fig. 23.—Gasholder.

the cocks be closed, the gas collected in the gasholder may be easily preserved and transported. If it be desired to transfer this gas into another vessel, then a gas-conducting tube is attached to *e*, the cock *a* opened, *b* and *d* closed, and then the gas will pass out at *e*, owing to its pressure in the apparatus being greater than the atmospheric pressure

wise in testing the combustibility of the hydrogen an explosion may occur from the formation of detonating gas (the mixture of the oxygen of the air with the hydrogen).¹⁷

Hydrogen, which is contained in water, and which therefore can be obtained from it, is also contained in many other substances,¹⁸ and may be obtained from them. As examples of this, it may be mentioned (1) that a mixture of formate of sodium, CHNaO_2 , and caustic soda, NaHO , when heated to redness, forms sodium carbonate, Na_2CO_3 , and hydrogen, H_2 ; ¹⁹ (2) that a number of organic substances are decomposed at a red heat, forming hydrogen, among other gases, and thus it is that hydrogen is contained in ordinary lighting gas.

Charcoal itself liberates hydrogen from steam at a high temperature; ²⁰ but the reaction which here takes place is distinguished by a certain complexity, and will therefore be considered later.

owing to the pressure of the water poured into the funnel. If it be required to fill a cylinder or flask with the gas, it is filled with water and inverted in the funnel, and the stop-cocks *b* and *a* opened. Then water will run through *a*, and the gas will escape from the gasholder into the cylinder through *b*.

¹⁷ When it is required to prepare hydrogen in large quantities for filling balloons, copper vessels or wooden casks lined with lead are employed; they are filled with scrap iron, over which dilute sulphuric acid is poured. The hydrogen generated from a number of casks is carried through lead pipes into special casks containing water (in order to cool the gas) and lime (in order to remove acid fumes). To avoid loss of gas all the points are made hermetically tight with a paste of plaster or tar. In order to fill his gigantic balloon (of 25,000 cubic metres capacity), Giffard, in 1878, constructed a complicated apparatus for giving a continuous supply of hydrogen, in which a mixture of sulphuric acid and water was continually run into vessels containing iron, and from which the solution of iron sulphate formed was continually drawn off. When coal gas, extracted from coal, is employed for filling balloons it should be as light, or as rich in hydrogen, as possible. For this reason, only the last portions of the gas coming from the retorts are collected, and, besides this, it is then sometimes passed through red-hot vessels, in order to decompose the hydrocarbons as much as possible; charcoal is deposited in the red-hot vessels, and hydrogen remains as gas. Coal gas may be yet further enriched in hydrogen, and consequently rendered lighter, by passing it over an ignited mixture of charcoal and lime.

¹⁸ Of the metals, only a very few combine with hydrogen (for example, sodium), and give substances which are easily decomposed. Of the non-metals, the halogens (fluorine, chlorine, bromine, and iodine) most easily form their unique hydrogen compounds; of these the hydrogen compound of chlorine, and still more that of fluorine, is stable, whilst those of bromine and iodine are easily decomposed, especially the latter. The other non-metals—for instance, sulphur, carbon, and phosphorus—give hydrogen compounds of different composition and properties, but they are all less stable than water. The number of the carbon compounds of hydrogen is enormous, but there are very few among them which are not decomposed, with separation of the carbon and hydrogen, at a red heat.

¹⁹ The reaction expressed by the equation $\text{CNaHO}_2 + \text{NaHO} = \text{CNa}_2\text{O}_5 + \text{H}_2$ may be effected in a glass vessel, like the decomposition of copper carbonate or mercury oxide (*see* Introduction); it is non-reversible, and takes place without the presence of water, and therefore Pictet (*see* later) made use of it to obtain hydrogen under great pressure.

²⁰ The reaction between charcoal and superheated steam is a double one—that is, there may be formed either carbonic oxide, CO (according to the equation $\text{H}_2\text{O} + \text{C} = \text{H}_2 + \text{CO}$), or

The properties of hydrogen.—Hydrogen presents us with an example of a gas which at first sight does not differ from air. It is not surprising, therefore, that Paracelsus, having discovered that an aëriiform substance is obtained by the action of metals on sulphuric acid, did not quite determine its difference from air. In fact, hydrogen, like air, is colourless, and has no smell;²¹ but a more intimate acquaintance with its properties proves it to be entirely different from air. The first sign which distinguishes hydrogen from air is its combustibility. This property is so easily observed that it is the one to which recourse is usually had in order to recognise hydrogen, if it is evolved in a reaction, although there are many other combustible gases. But before speaking of the combustibility and other chemical properties of hydrogen, we will first describe the physical properties of this gas, as we did in the case of water. It is easy to show that hydrogen is one of the lightest gases.²² If passed into the bottom of a flask full of air,

carbonic anhydride CO_2 (according to the equation $2\text{H}_2\text{O} + \text{C} = 2\text{H}_2 + \text{CO}_2$), and the resulting mixture is called *water-gas*; we shall speak of it in describing the oxides of carbon.

²¹ Hydrogen obtained by the action of zinc or iron on sulphuric acid generally smells of hydrogen sulphide (like rotten eggs), which it contains in admixture. As a rule such hydrogen is not so pure as that obtained by the action of an electric current or of sodium on water. The impurity of the hydrogen depends on the impurities contained in the zinc, or iron, and sulphuric acid, and on secondary reactions which take place simultaneously with the main reaction. Thus iron sulphide gives hydrogen sulphide ($\text{FeS} + \text{H}_2\text{SO}_4 = \text{H}_2\text{S} + \text{FeSO}_4$). However, the hydrogen obtained in this manner may be easily freed from the impurities it contains: some of them—namely those having acid properties—are absorbed by caustic soda, and therefore may be removed by passing the hydrogen through a solution of this substance; another series of impurities is absorbed by a solution of mercuric chloride; and, lastly, a third series is absorbed by a solution of potassium permanganate. The hydrogen may be dried by passing it over sulphuric acid or calcium chloride. The substances serving for purifying the hydrogen are either placed in Woulfe's bottles, or in tubes containing pumice stone moistened with the purifying agent. The surface of contact is then greater, and the purification proceeds more rapidly. If it be desired to procure completely *pure hydrogen*, it is sometimes obtained by the decomposition of water (previously boiled to expel all air, and mixed with pure sulphuric acid), by the galvanic current. Only the gas evolved at the negative electrode is collected. Or else, an apparatus like that which gives detonating gas is used, only the positive electrode being immersed under mercury containing zinc in solution. The oxygen which is evolved at this electrode then immediately, at the moment of its evolution, combines with the zinc, and this compound dissolves in the sulphuric acid and forms zinc sulphate, which remains in solution, and therefore the hydrogen generated will be quite free from oxygen.

²² An inverted beaker is attached to one arm of the beam of a rather sensitive balance, and its weight counterpoised by weights in the pan attached to the other arm. If the beaker be then filled with hydrogen it rises, owing to the air being replaced by hydrogen. Thus, at the ordinary temperature of a room, a litre of air weighs about 1.2 grams, and on replacing the air by hydrogen a decrease in weight of about 1 gram per litre is obtained. Moist hydrogen is heavier than dry—for aqueous vapour is nine times heavier than hydrogen. In filling balloons it is usually calculated that (it being impossible to have perfectly dry hydrogen or to obtain it quite free from air) the lifting force is equal to 1 kilogram ($\approx 1,000$ grams) per cubic metre ($\approx 1,000$ litres).

hydrogen will not remain in it, but, owing to its lightness, rapidly escapes and mixes with the atmosphere. If, however, a cylinder whose orifice is turned downwards be filled with hydrogen, it will not escape, or, more correctly, it will only slowly mix with the atmosphere. This may be demonstrated by the fact that a lighted taper sets fire to the hydrogen at the orifice of the cylinder, and is itself extinguished inside the cylinder. Hence hydrogen, being itself combustible, does not support combustion. The great lightness of hydrogen is taken advantage of for balloons. Ordinary coal gas, which is often also used for the same purpose, is only about twice as light as air, whilst hydrogen is $14\frac{1}{2}$ times lighter than air. A very simple experiment with soap bubbles very well illustrates the application of hydrogen for filling balloons. Charles, of Paris, showed the lightness of hydrogen in this way, and constructed a balloon filled with hydrogen almost simultaneously with Montgolfier. One litre of hydrogen²³ at 0° and 760 mm. pressure weighs

²³ The density of hydrogen in relation to the air has been determined by accurate experiments. The first determination, made by Lavoisier, was not entirely exact; taking the density of air as unity, he obtained 0.0769 for that of hydrogen—that is, hydrogen as thirteen times lighter than air. Later determinations have corrected this figure, the most accurate determinations being due to Thomsén, who obtained the figure 0.0693; Berzelius and Dulong, who obtained 0.0688; and Dumas and Bunsen, who obtained 0.06945. But the most exact determination of all is, without doubt, due to Regnault. He took two spheres of considerable capacity, which contained equal volumes of air (thus avoiding the necessity of any correction for weighing them in air). Both spheres were attached to the scale pans of a balance. One was sealed up, and the other first weighed empty and then full of hydrogen. Thus, knowing the weight of the hydrogen filling the sphere, and the capacity of the sphere, it was easy to find the weight of a litre of hydrogen; and, knowing the weight of a litre of air at the same temperature and pressure, it was easy to calculate the density of hydrogen. Regnault, by these experiments, found the average density of hydrogen to be 0.06926 in relation to air, or including the necessary corrections 0.06949.

In this book I shall always refer the densities of all gases to hydrogen, and not to air; therefore, for the sake of clearness, I will cite the weight of a litre of dry pure hydrogen in grams at a temperature t° and under a pressure H (measured in millimetres of mercury at 0°, in long. 45°). The weight of a litre of hydrogen

$$= 0.08958 \times \frac{H}{760} \times \frac{1}{1 + 0.00367t} \text{ gram.}$$

For aëronauts it is very useful to know, besides this, the weight of the air at different heights, and I therefore insert the adjoining table, constructed on the basis of Glaisher's

Pressure	Temperature	Moisture	Height	Weight of the air
760 m.m.	15° C.	60 p.c.	0 mètres	1222 kilos.
700 "	11.0° "	64 "	690 "	1141 "
650 "	7.6° "	64 "	1300 "	1078 "
600 "	4.3° "	63 "	1960 "	1008 "
550 "	+ 1.0° "	62 "	2660 "	931 "
500 "	— 2.4° "	58 "	3420 "	857 "
450 "	— 5.8° "	52 "	4250 "	781 "
400 "	— 9.1° "	44 "	5170 "	708 "
350 "	— 12.5° "	36 "	6190 "	624 "
300 "	— 15.9° "	27 "	7360 "	542 "
250 "	— 19.2° "	18 "	8720 "	457 "

1,000 cubic metres

0.089578 gram ; that is, hydrogen is almost $14\frac{1}{2}$ (more exactly, 14.43) times lighter than air. It is the lightest of all gases. The small density of hydrogen determines many remarkable properties which it shows ; thus, hydrogen flows exceedingly rapidly from fine orifices, its molecules (Chap. I.) being endued with the greatest velocity of movement.²⁴ At pressures somewhat higher than the atmospheric pressure, all other gases exhibit a greater compressibility and co-efficient of expansion than they should according to the laws of Mariotte and Gay-Lussac ; whilst hydrogen, on the contrary, is less compressed than should follow from the law of Mariotte,²⁵ and with a rise of pressure it expands slightly

data, for the temperature and moisture of the atmospheric strata in clear weather. All the figures are given in the metrical system—1000 millimetres = 39.37 inches, 1000 kilograms = 2204.3375 lbs., 1000 cubic metres = 35316.5 cubic feet. The starting temperature at the earth's surface is taken as = 15° C., its moisture 60 p.c., pressure 760 millimetres. The pressures are taken as indicated by an *aneroid barometer*, assumed to be corrected at the sea level and at long. 45°.

Although the figures of this table are calculated with every possible care from average data, yet they can only be taken for an elementary judgment of the matter, for in every separate case the conditions, both at the earth's surface and in the atmosphere, will differ from those here taken. In calculating the height to which a balloon can ascend, it is evident that the density of gas in relation to air must be known. This density for ordinary coal gas is from 0.6 to 0.35, and for hydrogen with its ordinary contents of moisture and air from 0.1 to 0.15.

Hence, for instance, it may be calculated that a balloon of 1000 cubic metres capacity filled with pure hydrogen, and weighing (the envelope, tackle, people, and ballast) 727 kilograms, will ascend to a height of not much more than 4250 metres.

²⁴ If a cracked flask be filled with hydrogen and its neck immersed under water or mercury, then the liquid will rise up into the flask, owing to the hydrogen passing through the cracks about 3.8 times quicker than the air is able to pass through these cracks into the flask. The same thing may be better seen if, instead of a flask, a tube whose end is closed by a porous substance, such as graphite, unglazed earthenware, or a gypsum plate, be employed.

²⁵ According to Boyle and Mariotte's law, for a given gas at a constant temperature the volume decreases by as many times as the pressure increases ; that is, this law requires that the product of the volume v and the pressure p for a given gas should be a constant quantity : $pv = C$, a constant quantity which does not vary with a change of pressure. In reality this equation does very nearly and exactly express the observed relation between the volume and pressure, but only within comparatively small variations of pressure, density, and volume. If these variations be in any degree considerable, the quantity pv proves to be dependent on the pressure, and it either increases or diminishes with an increase of pressure. In the former case the compressibility is less than it should be according to Mariotte's law, in the latter case it is greater. We will call the first case a positive discrepancy (because then $d(pv) / d(p)$ is greater than zero), and the second case a negative discrepancy (because then $d(pv) / d(p)$ is less than zero). Determinations made by myself, M. L. Kirpicheff, and Hemilian showed that all known gases at low pressures, when considerably rarefied, present positive discrepancies. On the other hand it appears from the researches of Cailletet, Natterer, and Amagat that all gases under great pressures (when the volume obtained is 500–1000 times less than under the atmospheric pressure) also present positive discrepancies. Thus under a pressure of 2700 atmospheres air is compressed, not 2700 times, but only 800, and hydrogen 1000 times. Hence the positive kind of discrepancy is, so to say, normal to gases. And this is easily understood. Did a gas follow Mariotte's law, or were it compressed to a

less than at the atmospheric pressure.²⁶ However, hydrogen, like air and many other gases which are permanent at the ordinary tem-

greater extent than is shown by this law, then under great pressures it would attain a density greater than that of solid and liquid substances, which is in itself improbable and even impossible by reason of the fact that solid and liquid substances are themselves but little compressible. For instance, a cubic centimetre of oxygen at 0° and under the atmospheric pressure weighs about 0.0014 gram, and at a pressure of 3000 atmospheres (this pressure is attained in guns) it would, if it followed Mariotte's law, weigh 4.2 grams—that is, would be about four times heavier than water—and at a pressure of 10000 atmospheres it would be heavier than mercury. Besides this, positive discrepancies are probable in the sense that the molecules of a gas themselves must occupy a certain volume. Admitting that Mariotte's law only applies to the intermolecular space still we find the necessity of positive discrepancies. If we designate the volume of the molecules of a gas by b (like Van der Waals, see Chap. I. note 34), then it must be expected that $p(v-b) = C$. Hence $pv = C + bp$, which expresses a positive discrepancy. Supposing that for hydrogen $pv = 1000$, at a pressure of one metre of mercury, according to the results of Regnault's, Amagat's, and Natterer's experiments, we obtain b as approximately 0.7 to 0.9.

Thus the increase of pv with the increase of pressure must be considered as the normal law of the compressibility of gases. Hydrogen presents such a positive compressibility at all pressures, for it presents positive discrepancies from Mariotte's law, according to Regnault, at all pressures above the atmospheric pressure. Hence hydrogen is, so to say, a sample gas. No other gas behaves so simply with a change of pressure. All other gases at pressures from 1 to 30 atmospheres present negative discrepancies—that is, they are then compressed to a greater degree than should follow from Mariotte's law, as was shown by the determinations of Regnault, which were verified when repeated by myself and Boguzsky. Thus, for example, on changing the pressure from 4 to 20 metres of mercury—that is, on increasing the pressure five times—the volume only decreased 4.93 times when hydrogen was taken, and 5.06 when air was taken.

The discrepancies from the law of Boyle and Mariotte for considerable pressures (from 1 to 3000 atmospheres) are well expressed (for constant temperatures) by the above-mentioned formula of Van der Waals (Chap. I. Note 34); Clausius' formula is more closely approximate, but as it and Van der Waals' formula also do not in any way express the existence of positive discrepancies from the law at low pressures, and as, according to the above-mentioned determinations made by myself, Kirpicheff, and Hemilian and verified (by two methods) by K. D. Kraevitch, they are proper to all gases (even to those which are easily compressed into a liquid state, such as carbonic and sulphurous anhydrides); therefore these formulæ, whilst accurately interpreting the phenomena of condensation and even of liquefaction, do not answer in the case of a high rarefaction of gases—that is, to that instance where a gas approaches to a condition of maximum dispersion of its molecules, and perhaps presents a passage towards the substance termed 'luminiferous ether' which fills up interplanetary and interstellar space. If we suppose that gases are rarefiable to a definite limit only, having attained which they (like solids) do not alter in volume with a decrease of pressure, then on the one hand the passage of the atmosphere at its upper limits into a homogeneous ethereal medium becomes comprehensible, and on the other hand it would be expected that gases would, in a state of high rarefaction (*i.e.*, when small masses of gases occupy large volumes, or when furthest removed from a liquid state) present positive discrepancies from Boyle and Mariotte's law. Our present acquaintance with this province of highly rarefied gases is most limited, and its further development promises to elucidate much in respect to natural phenomena. To the three states of matter (solid, liquid, and gaseous) it is evident a fourth must be yet added, the ethereal or ultra-gaseous (as Crookes proposed), understanding by this matter in its highest possible state of rarefaction.

²⁶ The law of Gay-Lussac states that all gases in all conditions present one coefficient of expansion 0.00367; that is, when heated from 0° to 100° they expand like air; namely, a thousand volumes of a gas measured at 0° will occupy 1367 volumes at 100°.

perature, does not pass into a liquid state under a very considerable pressure,²⁷ but is compressed into a lesser volume than would

Regnault, about 1850, showed that Gay-Lussac's law is not entirely correct, and that different gases, and also one and the same gas at different pressures, have not quite the same coefficients of expansion. Thus the expansion of air between 0 and 100° is 0·367 under the ordinary pressure of one atmosphere, and at three atmospheres it is 0·371, the expansion of hydrogen is 0·366, and of carbonic anhydride 0·37. Regnault, however, did not directly determine the change of volume between the 0° and 100°, but measured the variation of tension with the change of temperature; but as gases do not entirely follow Mariotte's law, therefore the change of volume cannot be directly judged by the variation of tension. The investigations carried on by myself and Kayander, about 1870, showed the direct variation of volume on heating from 0° to 100°. These investigations confirmed Regnault's conclusion that Gay-Lussac's law is not entirely correct, and further showed (1) that the expansion per volume from 0° to 100° under a pressure of one atmosphere, for air = 0·368, for hydrogen = 0·367, for carbonic anhydride = 0·373, for hydrogen bromide = 0·386, &c.; (2) that for gases which are more compressible than should follow from Mariotte's law the expansion by heat increases with the pressure—for example, for air at a pressure of three and a half atmospheres, it equals 0·371, for carbonic anhydride at one atmosphere it equals 0·373, at three atmospheres 0·389, and at eight atmospheres 0·413; (3) that for gases which are less compressible than should follow from Mariotte's law, the expansion by heat decreases with an increase of pressure—for example, for hydrogen at one atmosphere 0·367, at eight atmospheres 0·369, for air at a quarter atmosphere 0·370, at one atmosphere 0·368; and hydrogen like *air* (and all gases) is less compressed at *low pressures* than should follow from Mariotte's law (air at higher pressures than the atmospheric pressure gives a contrary result), as investigations made by myself, aided by Kirpicheff and Hemilian, showed. Hence, hydrogen, starting from zero to the highest pressures, exhibits a gradually, although only slightly, varying coefficient of expansion, whilst for air and other gases at the atmospheric and higher pressures, the coefficient of expansion increases with the increase of pressure, so long as their compressibility is greater than should follow from Mariotte's law. But when at considerable pressures, this kind of discrepancy passes into the normal (see Note 25), then the coefficient of expansion of all gases decreases with an increase of pressure, as is seen from the researches of Amagat. The difference between the two coefficients of expansion, for a constant pressure and for a constant volume, is explained by these relations. Thus, for example, for air at a pressure of one atmosphere the true coefficient of expansion (the volume varying at constant pressure) = 0·00368 (according to Mendeléeff and Kayander) and the variation of tension (at a constant volume, according to Regnault) = 0·00367.

²⁷ Permanent gases are such as cannot be liquefied by an increase of pressure alone. With a rise of temperature, all gases and vapours become permanent gases. As we shall afterwards learn, carbonic anhydride becomes a permanent gas at temperatures above 31°, and at lower temperatures it has a maximum tension, and may be liquefied by pressure alone.

The *liquefaction* of gases, accomplished by Faraday (*see Ammonia*) and others, in the first half of this century, showed that a number of substances are capable, like water, of taking all three physical states, and that there is no essential difference between vapours and gases, the only distinction being that the boiling points (or the temperature at which the tension = 760 mm.) of liquids lie above the ordinary temperature, and those of liquefied gases below, and consequently a gas is a superheated vapour, or vapour heated above the boiling point, or removed from saturation, rarefied, having a lower tension than that maximum which is proper to a given temperature and substance. We will here cite, as we did for water (p. 54), the *maximum tensions* of certain liquids and gases at various temperatures, because they may be taken advantage of for obtaining constant temperatures by changing the pressure at which boiling or the formation of

follow from Mariotte's law.²⁸ From this it may be concluded that the absolute boiling point of hydrogen, and of gases resembling

saturated vapours takes place. The temperatures (according to the air thermometer) are placed on the left, and the tension in millimetres of mercury (at 0°) on the right, hand side of the equations. Carbon bisulphide, CS_2 , 0°=127·9; 10°=198·5; 20°=298·1; 30°=431·6; 40°=617·5; 50°=857·1. Chlorobenzene, $\text{C}_6\text{H}_5\text{Cl}$, 70°=97·9; 80°=141·8; 90°=208·4; 100°=292·8; 110°=402·6; 120°=542·8; 130°=719·0. Aniline, $\text{C}_6\text{H}_7\text{N}$, 150°=283·7; 160°=387·0; 170°=515·6; 180°=677·2; 185°=771·5. Methyl salicylate, $\text{C}_8\text{H}_8\text{O}_5$, 180°=249·4; 190°=330·9; 200°=432·4; 210°=557·5; 220°=710·2; 224°=779·9. Mercury, Hg, 300°=246·8; 310°=304·9; 320°=373·7; 330°=454·4; 340°=548·6; 350°=658·0; 359°=770·9. Sulphur, S, 395°=300; 423°=500; 448°=700; 452°=800; 459°=900. These figures (Ramsay and Young) show the possibility of fixing constant temperatures in the vapours of boiling liquids. The tension of liquefied gases is expressed in atmospheres. Sulphurous anhydride, SO_2 , -50°=0·4; -20°=0·6; -10°=1; 0°=1·5; +10°=2·3; 20°=3·2; 30°=5·3. Ammonia, NH_3 , -40°=0·7; -30°=1·1; -20°=1·8; -10°=2·8; 0°=4·2; +10°=6·0; 20°=8·4. Carbonic anhydride, CO_2 , -115°=0·033; -80°=1; -60°=2·1; -50°=3·9; -40°=6·8; -30°=10; -20°=23; 0°=35; +10°=46; 20°=58. Nitrous oxide, N_2O , -125°=0·033; -92°=1; -80°=1·9; -50°=7·6; -20°=23·1; 0°=36·1; +20°=55·3. Ethylene, C_2H_4 , -140°=0·033; -130°=0·1; -103°=1; -40°=13; -1°=42. Air, -191°=1; -158°=14; -140°=39. Nitrogen, N_2 , -203°=0·085; -193°=1; -160°=14; -146°=32. The methods of liquefying gases (by pressure and cold) will be described under ammonia, nitrous oxide, sulphurous anhydride, and in later footnotes. We will now turn our attention to the fact that the evaporation of volatile liquids, under various, and especially under low, pressures, gives an easy means for obtaining *low temperatures*. Thus liquefied carbonic anhydride, under the ordinary pressure, reduces the temperature to -80°, and when it evaporates in an atmosphere rarefied (in an air-pump) to 25 mm. (0·033 atmospheres) the temperature, judging by the above-cited figures, falls to -115° (Dewar). Even the evaporation of liquids of common occurrence, under low pressures easily attainable in an air-pump, may produce low temperatures, which may be again taken advantage of for obtaining still lower temperatures. Water boiling in a vacuum becomes cold, and under a pressure of less than 4·5 mm. it freezes, because its tension at 0° is 4·5 mm. A sufficiently low temperature may be obtained by forcing fine streams of air through common ether, or liquid carbon bisulphide, CS_2 , or methyl chloride, CH_3Cl , and other similar volatile liquids. In the adjoining table are given, for certain gases, (1) the number of atmospheres necessary for their liquefaction at 15°, and (2) the boiling points of the resultant liquids under a pressure of 760 mm.

	C_2H_4	N_2O	CO_2	H_2S	AsH_3	NH_3	HCl	CH_3Cl	C_2N_2	SO_2
(1)	42	31	52	10	8	7	25	4	4	3
(2)	-103°	-92°	-80°	-74°	-58°	-38°	-35°	-24°	-21°	-10°

²⁸ Natterer's determinations (1851-1854), together with Amagat's results (1880-1888), show that the compressibility of hydrogen, under high pressures, may be expressed by the following figures:—

p	=	1	100	1000	2500
v	=	1	0·0107	0·0019	0·0013
$p v$	=	1	1·07	1·9	3·25
s	=	0·11	10·3	58	85

where p = the pressure in metres of mercury, v = the volume, if the volume taken under a pressure of 1 metre = 1, and s the weight of a litre of hydrogen at 20° in grams. If hydrogen followed Mariotte's law, then under a pressure of 2500 metres, one litre would contain not 85, but 265, grams. It is evident from the above figures that the weight of a litre of the gas approaches a limit as the pressure increases, which is doubtless the density of the gas when liquefied, and therefore the weight of a litre of liquid hydrogen will probably be near 100 grams (density about 0·1, being less than that of all other liquids).

it,²⁹ lies very much below the ordinary temperature ; that is, that the liquefaction of this *gas* is only possible at low temperatures, and under

²⁹ Cagniard de Latour, on heating ether in a closed tube to about 190°, observed that at this temperature the liquid is transformed into vapour occupying the original volume—that is, having the same density as the liquid. The further investigations made by Drion and myself, showed that every liquid has such an *absolute boiling point*, above which it cannot exist as a liquid and is transformed into a dense gas. In order to grasp the true signification of this absolute boiling temperature, it must be remembered that the liquid state is characterised by a cohesion of its particles which does not exist in vapours and gases. The cohesion of liquids is expressed in their capillary phenomena (the breaks in a column of liquid, drop formation, and rise in capillary tubes, &c.), and the product of the density of a liquid into the height to which it rises in a capillary tube (of a definite diameter) may serve as the measure of the magnitude of cohesion. Thus, in a tube of 2 mm. diameter, water at 15° rises (the height being corrected for the meniscus) 14·8 mm., and ether at t° to a height $5\cdot85 - 0\cdot028 t^{\circ}$ mm. The cohesion of a liquid is lessened by heating, and therefore the capillary heights are also diminished. It has been shown by experiment that this decrement is proportional to the temperature, and hence by the aid of capillary observations we are able to form an idea that at a certain rise of temperature the cohesion may become = 0. For ether, according to the above formula, this would happen at 191°. If the cohesion disappear from a liquid it becomes a gas, for cohesion is the only point of difference between these two states. A liquid in evaporating and overcoming the force of cohesion absorbs heat. Therefore, the absolute boiling point was defined by me (1861) as that temperature at which (a) a liquid cannot exist as a liquid, but forms a gas which cannot pass into a liquid state under any pressure whatever; (b) cohesion = 0; and (c) the latent heat of evaporation = 0.

These ideas were but little spread until Andrews (1869) explained the matter from another aspect. Starting from gases, he discovered that carbonic anhydride cannot be liquefied by any degree of compression at temperatures above 31°, whilst at lower temperatures it can be liquefied. He called this temperature the *critical temperature*. It is evident that it is the same as the absolute boiling point. We shall afterwards designate it by *tc*. At low temperatures a gas which is subjected to a pressure greater than its maximum tension (Note 27) is completely transformed into a liquid, which, in evaporating, gives a saturated vapour which possesses this maximum tension; whilst at temperatures above *tc* the pressure to which the gas is subjected may increase indefinitely. However, under these conditions the volume of the gas does not change indefinitely but approaches a definite limit (*see* Note 28)—that is, it resembles in this respect a liquid or a solid which is altered but little in volume by pressure. The volume which a liquid or gas occupies at *tc* is termed the *critical volume*, which corresponds with the *critical pressure*, which we will designate by *pc* and express in atmospheres. It is evident from what has been said that the discrepancies from Mariotte and Boyle's law, the absolute boiling point, the density in liquid and compressed gaseous states, and the properties of liquids, must all be intimately connected together. We will consider these relations in one of the following notes. At present we will supplement the above observations by the values of *tc* and *pc* for certain liquids and gases which have been investigated in this respect—

t.c.			p.c.		
N ₂	—	146°	33	H ₂ S	+ 108°
CO	—	140°	39	C ₂ N ₂	+ 124°
O ₂	—	119°	50	NH ₃	+ 181°
CH ₄	—	100°	50	CH ₃ Cl	+ 141°
NO	—	98°	71	SO ₂	+ 155°
C ₂ H ₄	+	10°	51	C ₃ H ₁₀	+ 192°
CO ₂	+	32°	77	C ₄ H ₁₀ O	+ 199°
N ₂ O	+	53°	75	CHCl ₃	+ 268°
C ₂ H ₂	+	37°	68	CS ₂	+ 278°
HCl	+	52°	86	C ₆ H ₆	+ 292°

great pressures.³⁰ This conclusion was verified (1879) by the experiments of Pictet and Cailletet.³¹ They compressed gases at a

³⁰ This conclusion was arrived at by me in 1870 (Ann. Phys. Chem. 141, 623).

³¹ Pictet, in his researches, effected the direct liquefaction of many gases which up to that time had not been liquefied. He employed the apparatus used for the manufacture of ice on a large scale, employing the vaporisation of liquid sulphurous anhydride which may be liquefied by pressure alone. This anhydride is a gas which is transformed into a liquid at the ordinary temperature under a pressure of several atmospheres (*see* Note 27), and boils at -10° at the ordinary atmospheric pressure. This liquid, like all others, boils at a lower temperature under a diminished pressure, and by continually pumping out the gas which comes off by means of a powerful air-pump its boiling point falls as low as -75° . Consequently, if we on the one hand force liquid sulphurous anhydride into a vessel, and on the other hand pump out the gas from the same vessel by powerful air-pumps, then the liquefied gas will boil in the vessel, and cause the temperature in it to fall to -75° . If a second vessel is placed inside this vessel, then another gas may be easily liquefied in it at the low temperature produced by the boiling liquid sulphurous anhydride. Pictet in this manner easily liquefied carbonic anhydride, CO_2 (at -60° under a pressure of from four to six atmospheres). This gas is more refractory to liquefaction than sulphurous anhydride, but for this reason it gives on evaporating a still lower temperature than can be attained by the evaporation of sulphurous anhydride. A temperature of -80° may be obtained by the evaporation of liquid carbonic anhydride at a pressure of 760 mm., and in an atmosphere rarefied by a powerful pump the temperature falls to -140° . By employing such low temperatures, it was possible, with the aid of pressure, to liquefy the majority of the other gases. It is evident that special pumps which are capable of rarefying gases are necessary to reduce the pressure in the chambers in which the sulphurous and carbonic anhydride boil; and that, in order to re-condense the resultant gases into liquids, special force pumps are required for pumping the liquid anhydrides into the refrigerating chamber. Thus, in Pictet's apparatus (fig. 24), the carbonic anhydride was liquefied by the aid of the pumps E F, which com-




FIG. 24.—General arrangement of the apparatus employed by Pictet for liquefying gases.

very low temperature, and then allowed them to expand, either by directly decreasing the pressure or by allowing them to escape into the air, by which means the temperature fell still lower, and then, just as steam when rapidly rarefied³² deposits liquid water in the form of a

pressed the gas (at a pressure of 4-6 atmospheres) and forced it into the tube K, vigorously cooled by being surrounded by boiling liquid sulphurous anhydride, which was condensed in the tube C by the pump B, and rarefied by the pump A. The liquefied carbonic anhydride flowed down the tube K into the tube H, in which it was subjected to a low pressure by the pump E, and thus gave a very low temperature of about 140° . The pump E carried off the vapour of the carbonic anhydride, and conducted it to the pump F, by which it was again liquefied. The carbonic anhydride thus made an entire circuit—that is, it passed from a rarefied vapour of small tension and low temperature into a compressed and cooled gas, which was transformed into a liquid, which again vaporised and produced a low temperature.

Inside the wide inclined tube H, where the carbonic acid evaporated, was placed a second and narrow tube M containing hydrogen, which was evolved in the vessels L from a mixture of sodium formate and caustic soda ($\text{CHO}_2\text{Na} + \text{NaHO} = \text{Na}_2\text{CO}_3 + \text{H}_2$). This mixture gives hydrogen on heating the vessel L. This vessel and the tube M were made of thick copper, and could withstand great pressures. They were, besides, hermetically connected together and closed up. Thus the hydrogen which was evolved had no outlet, accumulated in a limited space, and its pressure increased in proportion to the amount of it evolved. The magnitude of this pressure was recorded on a metallic manometer R attached to the end of the tube M. As the hydrogen in this tube was submitted to a very low temperature and a powerful pressure, there were all the necessary conditions for its liquefaction. When the pressure in the tube H became steady—*i.e.*, when the temperature had fallen to -140° , and the manometer R indicated a pressure of 650 atmospheres in the tube M—then this pressure did not rise with a further evolution of hydrogen in the vessel L. This served as an indication that the tension of the vapour of the hydrogen had attained a maximum corresponding with -110° , and that consequently all the excess of the gas was condensed to a liquid. Pictet convinced himself of this by opening the cock N, when the liquid hydrogen rushed out from the orifice. But, on leaving a space where the pressure was equal to 650 atmospheres, and coming into contact with air under the ordinary pressure, the liquid or powerfully-compressed hydrogen expanded, began to boil, absorbed still more heat, and became still colder. In doing so a portion of the liquid hydrogen, according to Pictet, passed into a solid state, and did not fall in drops into a vessel placed under the outlet N, but as pieces of solid matter, which struck against the sides of the vessel like shot and immediately vaporised. Thus, although it was impossible to see and keep the liquefied hydrogen, still it was admitted that it passed not only into a liquid, but also into a solid, state, because Pictet in his experiments obtained other gases which had not previously been liquefied, especially oxygen and nitrogen, in a liquid and solid state. Pictet supposed that liquid and solid hydrogen have the properties of a metal, like iron.

³² At the same time (1879) as Pictet was working on the liquefaction of gases in Switzerland, Caillietet, in Paris, was occupied on the same subject, and his results, although not so convincing as Pictet's, still showed that the majority of gases, previously unliquefied, were capable of passing into a liquid state. Caillietet subjected gases to a pressure of several hundred atmospheres in thin glass tubes (fig. 25); he then cooled the compressed gas as far as possible by surrounding it with a freezing mixture; a cock was then rapidly opened for the outlet of mercury from the tube containing the gas, which consequently rapidly and vigorously expanded. This rapid expansion of the gas would produce great cold, just as the rapid compression of a gas evolves heat and causes a rise in temperature. This cold was produced at the expense of the gas itself, for in rapidly expanding its particles were not able to absorb heat from the walls of the tube, and in cooling a portion of the expanding gas was transformed into liquid. This

fog, hydrogen in expanding forms a fog, thus indicating its passage into a liquid state. But as yet it has been impossible to preserve this liquid, even for a short time, to determine its properties, notwithstanding the employment of a temperature of -200° and a pressure of 200 atmospheres,³³ although by these means the gases of the atmosphere may be kept in a liquid state for a long time. This is naturally dependent on the fact that the absolute boiling point of hydrogen lies lower than that of all other known gases, which is related to the extreme lightness of hydrogen.³⁴

was seen from the formation of cloud-like drops, like a fog, which rendered the gas opaque. Thus Cailletet proved the possibility of the liquefaction of gases, but he did not isolate the liquids. The method of Cailletet allows the passage of gases into liquids being observed with greater facility and simplicity than Pictet's method, which requires a very complicated and expensive apparatus.




FIG. 25.—Cailletet's apparatus for liquefying gases.

The methods of Pictet and Cailletet were afterwards improved by Olszewski, Wroblewski, Dewar, and others. In order to obtain a still lower temperature they employed liquid ethylene or nitrogen instead of carbonic acid gas, whose evaporation at low pressures produces a much lower temperature (to -200°). They also improved on the methods of determining such low temperatures, but the methods were not essentially altered; they obtained nitrogen and oxygen in a liquid, and nitrogen even in a solid, state, but no one has yet succeeded in seeing hydrogen in a liquid form.

³³ The investigations of C. Wroblewski in Cracow clearly proved that Pictet could not have obtained liquid hydrogen in the interior of his apparatus, and that if he did obtain it, it could only have been at the moment of its outrush due to the fall in temperature following its sudden expansion. Pictet calculated that he obtained a temperature of -140° , but in reality it hardly fell below -120° , judging from the latest data for the vaporisation of carbonic anhydride under low pressure. The difference lies in the method of determining low temperatures. Judging from other properties of hydrogen (*see* Note 34), one would think that its absolute boiling point lies far below -120° , and even -140° (according to the calculation of Sarrau, on the basis of its compressibility, at -174°). But even at -200°

(if the methods of determining such low temperatures be correct) hydrogen does not give a liquid even under a pressure of several hundred atmospheres. However, on expansion a fog is formed and a liquid state attained, but the liquid does not separate.

³⁴ After the conception of the absolute temperature of ebullition (*tc*, note 29) had been worked out (about 1870), and its connection with the deviations from Mariotte's law had become evident, and especially after the liquefaction of permanent gases, general attention was turned to the development of the fundamental conceptions of the gaseous and liquid states of matter. Some investigators directed their energies to the further study of vapours (for instance, Ramsay and Young), gases (for instance, Amagat), and liquids (for instance, Zaencheffsky, Nadeschdin, and others), especially to liquids near *tc* and *pc*; others (for instance, Konvaloff and De Haen) endeavoured to discover the relation between liquids under ordinary conditions (removed from *tc* and *pc*) and gases,

Although a substance which passes with great difficulty into a liquid state by the action of physico-mechanical forces, hydrogen loses

while a third class of investigators (Van der Waals, Clausius, and others), starting from the already generally-accepted principles of the mechanical theory of heat and the kinetic theory of gases, and having made the self-evident proposition of the existence in gases of those forces which clearly act in liquids, deduced the connection between the properties of one and the other. It would be out of place in an elementary handbook like the present to enunciate the whole mass of conclusions arrived at by this method, but it is necessary to give an idea of the results of Van der Waals' considerations, for they explain the gradual uninterrupted passage from a liquid into a gaseous state in the simplest form, and, although the deduction cannot be considered as complete and decisive (*see* note 25), nevertheless it penetrates so deeply into the essence of the matter that its signification is not only reflected in a great number of physical investigations, but also in the province of chemistry, where instances of the passage of substances from a gaseous to a liquid state are so common, and where the very processes of dissociation, decomposition, and combination must be identified with a change of physical state of the participating substances.

For a *given quantity* (weight, mass) of a *definite substance*, its state is expressed by three variables—volume v , pressure (elasticity, tension) p , and temperature t . Although the compressibility—[*i.e.*, $d(v)/d(p)$ —of liquids is small, still it is clearly expressed, and varies not only with the nature of liquids but also with their pressure and temperature (at *tc* the compressibility of liquids is very considerable). Although gases, according to Mariotte's law, with small variations of pressure, are uniformly compressed, nevertheless the dependence of their volume v on t and p is very complex. The same applies to the coefficient of expansion [$=d(v)/d(t)$, or $d(p)/d(t)$], which also varies with t and p , both for gases (*see* Note 26), and for liquids (at *tc* it is very considerable, and often exceeds that of gases, 0.00367). Hence the *equation of state* must include three variables— v , p , and t . For a so-called perfect (ideal) gas, or for inconsiderable variation of density, the elementary expression $pv = Ra(t + at)$, or $pv = R(273 + t)$ should be accepted, where R is a constant varying with the mass and nature of a gas, as expressing this dependence, because it includes in itself the laws of Gay-Lussac and Mariotte, for at a constant pressure the volume varies proportionally to $1 + at$, and when t is constant the product of tv is constant. In its simplest form the equation may be expressed thus:

$$pv = RT;$$

where T denotes what is termed the absolute temperature, or the ordinary temperature + 273—that is, $T = t + 273$.

Starting from the supposition of the existence of an attraction or internal pressure (expressed by a) proportional to the square of the density (or inversely proportional to the square of the volume), and of the existence of a volume or length of path (expressed by b) of gaseous molecules, Van der Waals gives for gases the following more complex equation of state:—

$$\left(p + \frac{a}{v^2}\right)(v - b) = 1 + 0.00367t;$$

if at 0° under a pressure $p = 1$ (for instance, under the atmospheric pressure), the volume (for instance, a litre) of a gas or vapour be taken as 1, and therefore v and b be expressed by the same units as p and a . The deviations from both the laws of Mariotte and Gay-Lussac are expressed by the above equation. Thus, for hydrogen a must be taken as infinitely small, and $b = 0.0009$, judging by the data for 1000 and 2500 metres pressure (Note 28). For other permanent gases, for which (Note 28) I showed (about 1870) from Regnault's and Natterer's data, a decrement of pv , followed by an increment, which was confirmed (about 1880) by fresh determinations made by Amagat, this phenomena may be expressed in definite magnitudes of a and b (although Van der Waals' formula is not applicable for minimum pressures) with sufficient accuracy for contemporary requirements. It is evident that Van der Waals' formula can also express the difference of the

its gaseous state (that is, its elasticity, or the physical energy of its molecules, or their rapid progressive movement) with comparative ease

coefficients of expansion of gases with a change of pressure, and according to the methods of determination (Note 26). Besides this, Van der Waals' formula shows that at temperatures above $273\left(\frac{8a}{27b} - 1\right)$ only one actual volume (gaseous) is possible, whilst at lower temperatures, by varying the pressure, three different volumes—liquid, gaseous, and partly liquid partly saturated-vaporous—are possible. It is evident that the above temperature is the absolute boiling point—that is, $(tc) = 273\left(\frac{8a}{27b} - 1\right)$. It is found under the condition that all three possible volumes (the three roots of Van der Waals' cubic equation) are then similar and equal ($vc = 3b$). The pressure in this case (pc) = $\frac{a}{27b^2}$. These ratios between the constants a and b and the conditions of *critical state*—i.e. (tc) and (pc) —give the possibility of determining the one magnitude from the other. Thus for ether (Note 29), $(tc) = 193^\circ$, $(tp) = 40$, from whence $a = 0.0307$, $b = 0.00533$. From whence $(vc) = 0.016$. That mass of ether which at a pressure of one atmosphere at 0° occupies one volume—for instance, a litre—occupies, according to the above-mentioned condition, this critical volume. And as the density of the vapour of ether compared with hydrogen = 37, and a litre of hydrogen at 0° and under the atmospheric pressure weighs 0.0896 grams, then a litre of ether vapour weighs 3.32 grams; therefore, in a critical state (at 193° and 40 atmospheres), 3.32 grams occupy 0.016 litres, or 16 c.c.; therefore 1 gram occupies a volume of about 5 c.c., and the weight of 1 c.c. of ether will then be 0.21. According to the investigations of Ramsay and Young (1887), the critical volume of ether was approximately such at about the absolute boiling point, but the compressibility of the liquid is so great that the slightest change of pressure or temperature acts considerably on the volume. But the investigations of the above savants gave another indirect demonstration of the true composition of Van der Waals' equation. They also found for ether that the isochords, or the lines of equal volumes, are generally straight lines if the temperatures and pressures vary. For instance, the volume of 10 c.c. for 1 gram of ether corresponds with pressures (expressed in metres of mercury) equal to $0.135t - 3.3$ (for instance, at 180° and 21 metres pressure, at 280° and 34.5 metres pressure). The rectilinear form of the isochord (then $v = a$ constant quantity) is a direct result of Van der Waals' formula.

When, in 1883, I demonstrated that the specific gravity of liquids decreases in proportion to the rise of temperature [$S_t = S_0 - Kt$ or $S_t = S_0(1 - Kt)$], or that the volumes increase in inverse proportion to the binomial $1 - Kt$, that is, $V_t = V_0(1 - Kt)^{-1}$, where K is the modulus of expansion, which varies with the nature of the liquid (an exactitude of the same kind as that by which for gases the volumes increase proportionately to the binomial $1 + at$), then, in general, not only does a connection arise between gases and liquids with respect to a change of volume, but also it would appear possible, by availing oneself of Van der Waals' formula, to judge, from the phenomena of the expansion of liquids, as to their transition into vapour, and to connect together all the principal properties of liquids, which up to this time had not been considered to be in direct dependence. Thus Thorpe and Rücker found that $2(tc) + 273 = 1/K$, where K is the modulus of expansion in the above-mentioned formula. For example, the expansion of ether is expressed with sufficient accuracy from 0° to 100° by the equation $S_t = 0.736(1 - 0.00154t)$, or $V_t = 1(1 - 0.00154t)^{-1}$, where 0.00154 is the modulus of expansion, and therefore $(tc) = 188^\circ$, or by direct observation 193° . For silicon tetrachloride, $SiCl_4$, the modulus equals 0.00136, from whence $(tc) = 231^\circ$, and by experiment 230° . On the other hand, D. P. Konovoloff, admitting that the external pressure p in liquids is insignificant when compared with the internal (a in Van der Waals' formula), and that the work in the expansion of liquids is proportional to their temperature (as in gases), directly deduced, from Van der Waals' formula, the above-mentioned formula for the expansion of liquids, $V_t = 1/(1 - Kt)$, and

under the influence of chemical attraction,³⁵ which is not only shown from the fact that hydrogen and oxygen (two permanent gases) form liquid water, but also from many phenomena of the absorption of hydrogen.

Hydrogen is vigorously condensed by certain solids; for example, by charcoal and by spongy platinum. If a piece of freshly-ignited charcoal be introduced into a cylinder full of hydrogen standing in a mercury bath, then the charcoal absorbs as much as twice its volume of hydrogen. Spongy platinum condenses still more hydrogen. But *palladium*, a grey metal which occurs with platinum, absorbs more hydrogen than any other metal. Graham showed that when heated to a red heat and cooled in an atmosphere of hydrogen, palladium retains as much as 600 volumes of hydrogen. When once absorbed it retains the hydrogen at the ordinary temperature, and only parts with it when heated to a red heat.³⁶ This capacity of certain dense metals for the absorption of hydrogen explains the property of hydrogen of passing through metallic tubes.³⁷ It is termed *occlusion*, and presents a

also the magnitude of the latent heat of evaporation, cohesion, and compressibility under pressure. In this way Van der Waals' formula embraces the gaseous, critical, and *liquid states* of substances, and shows the connection between them. On this account, although Van der Waals' formula cannot be considered as perfectly general and accurate, yet it is not only very much more exact than $p v = R T$ but is also more comprehensive, because it applies to both gases and liquids. Further research will naturally give further proximity to truth, and will show the connection between composition and the constants (a and b); but a great scientific progress is seen in this form of the equation of state.

Clausius (in 1880), taking into consideration the variability of a , in Van der Waals' formula, with the temperature, gave the following equation of state:—

$$\left(p + \frac{a}{T(v+c)^2}\right)(v-b) = R T.$$

Sarrau applied this formula to Amagat's data for hydrogen, and found $a = 0.0551$, $c = -0.00043$, $b = 0.00089$, and therefore calculated its absolute boiling point as -174° , and $(pc) = 99$ atmospheres. But as similar calculations for oxygen (-105°), nitrogen (-124°), and marsh gas (-76°) gave tc higher than it really is, therefore the absolute boiling point of hydrogen must lie below -174° .

³⁵ This and a number of similar cases clearly show how great are the internal chemical forces compared with physical and mechanical forces.

³⁶ The capacity of palladium to absorb hydrogen, and in so doing to increase in volume, may be easily demonstrated by taking a sheet of palladium varnished on one side, and using it as a cathode. The hydrogen which is evolved by the action of the current is retained by the unvarnished surface, as a consequence of which the sheet curls up. By attaching a pointer (for instance, a quill) to the end of the sheet this bending effect is rendered strikingly evident, and on reversing the current (when oxygen will be evolved and combine with the absorbed hydrogen, forming water) it may be shown that on losing the hydrogen the palladium regains its original form.

³⁷ Deville discovered that iron and platinum become pervious to hydrogen at a red heat. He speaks of this in the following terms:—'The permeability of such homogeneous substances as platinum and iron is quite different from the passage of gases through such non-compact substances as clay and graphite. The permeability of metals depends

similar phenomenon to solution ; it is based on the capacity of metals of forming unstable easily dissociating compounds³⁸ with hydrogen similar to those which salts form with water.

At the ordinary temperature hydrogen very feebly and rarely enters into chemical reaction. The capacity of gaseous hydrogen for reaction becomes evident only under a change of circumstances—by compression, heating, or the action of light, or at the moment of its evolution. However, under these circumstances it *combines* directly with only a very few of the elements. Hydrogen combines directly with oxygen, sulphur, carbon, potassium, and certain other elements, but it does not combine directly with either the majority of the metals or with nitrogen, phosphorus, &c. Compounds of hydrogen with certain elements on which it does not act directly are, however, known ; they are not obtained by a direct method, but by reactions of decomposition, or of double decomposition, of other hydrogen compounds. The property of hydrogen of combining with oxygen at a red heat determines its combustibility. We have already seen that hydrogen easily takes fire, and that it then

on their expansion, brought about by heat, and proves that metals and alloys have a certain porosity.' However, Graham proved that it is only hydrogen which is capable of passing through the above-named metals in this manner. Oxygen, nitrogen, ammonia, and many other gases, only permeate through in extremely minute quantities. Graham showed that at a red heat about 500 c.c. of hydrogen pass per minute through a surface of one square metre of platinum 1.1 mm. thick, but that with other gases the amount transmitted is hardly perceptible. Indiarubber has the same capacity for allowing the transference of hydrogen through its substance (*see* Chap. III.), but at the ordinary temperature one square metre, 0.014 mm. thick, transmits only 127 c.c. of hydrogen per minute. In the experiment on the decomposition of water by heat in porous tubes, the clay tube may be exchanged for a platinum one with advantage. Graham showed that by placing a platinum tube containing hydrogen under these conditions, and surrounding it by a tube containing air, the transference of the hydrogen may be observed by the decrease of pressure in the platinum tube. In one hour almost all the hydrogen (97 p.c.) had passed from the tube, without being replaced by air. It is evident that the occlusion and passage of hydrogen through metals capable of occluding it are not only intimately connected together, but are dependent on the capacity of metals to form compounds of various degrees of stability with hydrogen—like salts with water.

³⁸ Palladium, as it appeared on further investigation, gives a definite compound, Pd_2H (*see* further) with hydrogen ; but what was most instructive was the investigation of sodium hydride, Na_2H , which clearly showed that the origin and properties of such compounds are in entire accordance with the conceptions of dissociation. In the chapter devoted to sodium we shall therefore speak more fully of this substance.

Being a gas which is difficult to condense, hydrogen is little soluble in water and other liquids. At 0° a hundred volumes of water dissolve 1.9 volumes of hydrogen, and alcohol 6.9 volumes measured at 0° and 760 mm. Molten iron absorbs hydrogen, but in solidifying, it expels it. The solution of hydrogen by metals is to a certain degree based on its affinity for metals, and must be likened to the solution of metals in mercury and to the formation of alloys. In its chemical properties hydrogen, as we shall see later, has much of a metallic character. Pictet (*see* Note 31) even affirms that liquid hydrogen has metallic properties. The metallic properties of hydrogen are also evinced in the fact that it is a good conductor of heat, which is not the case with other gases (Magnus).

burns with a pale—that is, non-luminous—flame.³⁹ Hydrogen does not combine with the oxygen of the atmosphere at the ordinary temperature; but this combination takes place at a red heat,⁴⁰ and is accompanied by the evolution of much heat. The product of this combination is water—that is, a compound of oxygen and hydrogen. This is the *synthesis of water*, and we have already noticed its analysis or decomposition into its component parts. The synthesis of water may be very easily observed if a cold glass bell jar be placed over a burning hydrogen flame, and, better still, if the hydrogen flame be lighted in the tube of a condenser. The water will condense in drops as it is formed on the walls of the condenser and trickle down.⁴¹

Light does not aid the combination of hydrogen and oxygen, so that a mixture of these two gases does not change when exposed to the action of light; but an electric spark acts just like a flame, and this is taken advantage of for inflaming a mixture of oxygen and hydrogen, or detonating gas, inside a vessel, as will be explained in the following chapters. As hydrogen (and oxygen also) is condensed by spongy platinum, by which a rise of temperature ensues, and as platinum acts by contact (p. 38), therefore hydrogen also combines with oxygen, under the influence of platinum, as Döbereiner showed. If spongy platinum be thrown into a mixture of hydrogen and oxygen, an explosion takes place. If a mixture of the gases be passed over spongy platinum, combination also ensues, and the platinum becomes red-hot.⁴²

³⁹ If it be desired to obtain a perfectly colourless hydrogen flame, it must issue from a platinum nozzle, as the glass end of a gas-conducting tube imparts a yellow tint to the flame, owing to the presence of sodium in the glass.

⁴⁰ Let us imagine that a stream of hydrogen passes along a tube, and let us mentally divide this stream into several parts, consecutively passing out from the orifice of the tube. The first part is lighted—that is, brought to a state of incandescence, in which state it combines with the oxygen of the atmosphere. A considerable amount of heat is evolved in the combination. The heat evolved then, so to say, ignites the second part of hydrogen coming from the tube, and, therefore, when once ignited, the hydrogen continues to burn, if there be a continual supply of it, and if the atmosphere in which it burns be unlimited and contains oxygen.

⁴¹ The combustibility of hydrogen may be shown by the direct decomposition of water by sodium. If a pellet of sodium be thrown into a cup containing water, then it floats on the water and evolves hydrogen, which may be lighted. The presence of sodium imparts a yellow tint to the flame. If potassium be taken, the hydrogen bursts into flame of itself, because sufficient heat is evolved in the reaction for the ignition and inflammation of the hydrogen. The flame is rendered violet by the potassium. If sodium be thrown not on water, but on an acid, it will evolve more heat, and the hydrogen will then also burst into flame. These experiments must be carried on with caution, as sometimes towards the end a mass of sodium oxide (Note 8) is produced, and flies about; therefore it is best to cover the vessel in which the experiment is carried on.

⁴² This property of spongy platinum is made use of in the so-called hydrogen cigar light. It consists of a glass cylinder or beaker, inside which there is a small lead stand (which is not acted on by sulphuric acid), on which a piece of zinc is laid. This zinc is covered by a bell, which is open at the bottom and furnished with a cock at the top.

Although gaseous hydrogen does not act directly⁴³ on many substances, yet in a *nascent state* reaction often takes place. Thus, for instance, water on which sodium amalgam is acting contains hydrogen in a nascent state. The hydrogen is here evolved from a liquid, and at the first moment of its formation it must be in a condensed form.⁴⁴

Sulphuric acid is poured into the space between the bell and the sides of the outer glass cylinder, and will thus compress the gas in the bell. If the cock of the cylinder be opened the gas will escape by it, and will be replaced by the acid, which, coming into contact with the zinc, evolves hydrogen, and it will escape through the cock. If the cock be closed, then the hydrogen evolved will increase the pressure of the gas in the bell, and thus again force the acid into the space between the bell and the walls of the outer cylinder. Thus the action of the acid on the zinc may be stopped or started at will by opening or shutting the cock, and consequently a stream of hydrogen may be always turned on. Now, if a piece of spongy platinum be placed in this stream, the hydrogen will take light, because the spongy platinum becomes hot in condensing the hydrogen and inflames it. The considerable rise in temperature of the platinum depends, among other things, on the fact that the hydrogen condensed in its pores comes into contact with previously absorbed and condensed atmospheric oxygen, with which hydrogen combines with great facility in this form. In this manner the hydrogen cigar-light gives a stream of burning hydrogen when the cock is open. In order that it should work regularly it is necessary that the spongy platinum should be quite clean, and it is best enveloped in a thin sheet of platinum foil, which protects it from dust. In any case, after some time it will be necessary to clean the platinum, which may be easily done by boiling it in nitric acid, which does not dissolve the platinum, but clears it of all dirt. This imperfection has given rise to several other forms, in which an electric spark is made to pass before the orifice from which the hydrogen escapes. This is arranged in such a manner that the zinc of a galvanic element is immersed when the cock is turned, or a small coil giving a spark is put into circuit on turning the hydrogen on.

⁴³ Under conditions the same as those in which hydrogen combines with oxygen it is also capable of combining with chlorine. A mixture of hydrogen and chlorine explodes on the passage of an electric spark through it, or on contact with an incandescent substance, and also in the presence of spongy platinum; but, besides this, the action of light alone is enough to bring about the combination of hydrogen and chlorine. If a mixture of equal volumes of hydrogen and chlorine be exposed to the action of sunlight, complete combination rapidly ensues, accompanied by a report. Hydrogen does not combine directly with carbon, neither at the ordinary temperature nor by the action of heat and pressure. But if an electric current be passed through carbon electrodes at a short distance from each other (as in the electric light or voltaic arc), so as to form an electric arc in which the particles of carbon are carried from one pole to the other, then, in the intense heat to which the carbon is subjected in this case, it is capable of combining with hydrogen. A peculiar-smelling gas, called acetylene, C_2H_2 , is thus formed from carbon and hydrogen.

⁴⁴ There is another explanation for the facility of the reactions which proceed at the moment of separation. We shall afterwards learn that the molecule of hydrogen contains two atoms, H_2 , but there are elements the molecules of which only contain one atom—for instance, mercury. Therefore, every reaction of gaseous hydrogen must be accompanied by the dissolution of that bond which exists between the atoms forming a molecule. At the moment of evolution, however, it is supposed that free atoms exist, and for this reason, according to the hypothesis, act energetically. This hypothesis is not borne out by facts, and the conception of hydrogen being condensed at the moment of its evolution is more natural, and is in accordance with the fact (Note 12) that compressed hydrogen displaces palladium and silver (Brunner, Beketoff)—that is, acts as at the moment of its evolution.

In this condensed form it is capable of reacting on substances on which it does not act in a gaseous state. There is a very intimate and evident relation between the phenomena which take place in the action of spongy platinum and the phenomena of the action in a nascent state. The combination of hydrogen with aldehyde may be taken as an example. Aldehyde is a volatile liquid with an aromatic smell, boiling at 21° , soluble in water, and absorbing oxygen from the atmosphere, and in this absorption forming acetic acid—the substance which is found in ordinary vinegar. If sodium amalgam be thrown into an aqueous solution of aldehyde, the greater part of the hydrogen evolved combines with the aldehyde, forming alcohol—a substance which is also soluble in water, which forms the principle of all spirituous liquors, boils at 78° , and which contains the same amount of oxygen and carbon as aldehyde, but more hydrogen. The composition of aldehyde is C_2H_4O , and of alcohol C_2H_6O . Reactions of substitution or displacement of metals by hydrogen at the moment of its evolution are particularly numerous.⁴⁵

Metals, as we shall afterwards see, are in many cases able to replace each other; they also, and in some cases still more easily, replace and are replaced by hydrogen. We have already seen examples of this in the formation of hydrogen from water, sulphuric acid, &c. In all these cases the metals sodium, iron, or zinc displace the hydrogen which occurs in these compounds. Hydrogen may be displaced from many of its compounds by metals by exactly the same method as it is displaced

⁴⁵ When, for instance, an acid and zinc are added to a salt of silver, the silver is reduced; but this may be explained as a reaction of the zinc, and not of the hydrogen at the moment of its evolution. There are, however, examples to which this explanation is entirely inapplicable; thus, for instance, hydrogen, at the moment of its evolution, easily takes up oxygen from its compounds with nitrogen if they be in solution, and converts the nitrogen into its combination with hydrogen. Here the nitrogen and hydrogen, so to speak, meet at the moment of their evolution, and in this state combine together.

It is evident from this that the elastic gaseous state of hydrogen fixes the limit of its energy: hinders it from entering into those combinations of which it is capable. In the nascent state we have hydrogen which is not in a gaseous state, and its action is then much more energetic. This is rendered very clear from the conception of chemical energy, because the process of passing into a gas requires a certain amount of heat, and consequently absorbs a certain amount of work. If gaseous hydrogen is produced, it shows that there are already conditions sufficient for the transmission of heat to the hydrogen evolved in order to convert it into a gas. It is evident at the moment of evolution that heat, which would be latent in the gaseous hydrogen, is transmitted to its molecules, and consequently they are in a state of potential, and can hence act on many substances.

Let us here remark the circumstance, which will be clearly understood from what has been said above, that hydrogen condensed in the pores of certain metals, like palladium and platinum, acts as a reducing agent on many substances. It will afterwards be understood that substances containing much hydrogen, and easily parting with it, can also act vigorously in effecting a reduction.

from water ; so, for example, hydrochloric acid, which is formed directly by the combination of hydrogen with chlorine, gives hydrogen by the action of a great many metals, just as sulphuric acid does. Potassium and sodium also displace hydrogen from its compounds with nitrogen ; it is only from its compounds with carbon that hydrogen is not displaced by metals. Hydrogen, in its turn, is able to replace metals ; this is accomplished most easily on heating, and with those metals which do not themselves displace hydrogen. If hydrogen be passed over the compounds of many metals with oxygen at a red heat, it takes up the oxygen from the metals and displaces them just as it is itself displaced by metals. If hydrogen be passed over the compound of oxygen with copper at a red heat, then metallic copper and water are obtained— $\text{CuO} + \text{H}_2 = \text{H}_2\text{O} + \text{Cu}$. This kind of double decomposition is called *reduction* with respect to the metal, which is thus reduced to a metallic state from its combination with oxygen. But it must be recollected that all metals do not displace hydrogen from its compound with oxygen, and, conversely, hydrogen is not able to displace all metals from their compounds with oxygen ; thus it does not displace potassium, calcium, or aluminium from their compounds with oxygen. If the metals be arranged in the following series : K, Na, Ca, Al Fe, Zn, Hg Cu, Pb, Ag, Au, then the first are able to take up oxygen from water—that is, displace hydrogen—whilst the last do not act thus, but are, on the contrary, reduced by hydrogen—that is, have, as is said, a less affinity for oxygen than hydrogen, whilst potassium, sodium, calcium have more. This is also expressed by the amount of heat evolved in the act of combination with oxygen, and is shown by the fact that potassium and sodium and other similar metals evolve heat in decomposing water ; but copper, silver, and the like do not do this, because in combining with oxygen they evolve less heat than hydrogen does, and therefore it happens that when hydrogen reduces these metals heat is evolved. Thus, for example, if 16 grams of oxygen combine with copper, 38000 units of heat are evolved ; and when 16 grams of oxygen combine with hydrogen, forming water, 69000 units of heat are evolved ; whilst 23 grams of sodium, in combining with 16 grams of oxygen, evolve 100000 units of heat. This example clearly shows that chemical reactions which proceed directly and unaided evolve heat. Sodium decomposes water and hydrogen reduces copper, because they are *exothermal* reactions, or those which evolve heat ; copper does not decompose water, because such a reaction would be accompanied by an absorption (or secretion) of heat, or belongs to the class of *endothermal* reactions, in which heat is absorbed ; and such reactions do not generally proceed directly,

although they may take place with the aid of energy (electrical, thermal, &c.) borrowed from some foreign source.⁴⁶

The reduction of metals by hydrogen is taken advantage of for *determining the exact composition of water by weight*. Copper oxide is usually chosen for this purpose. It is heated to redness in hydrogen, and the quantity of water thus formed is determined, then the quantity of oxygen which occurs in it is found from the loss in weight of the copper oxide. This loss will depend on the fact that the oxygen has entered into the water. The copper oxide must be weighed immediately before and after the experiment. The difference shows the weight of the oxygen which entered into the composition of the water formed. In this manner only solids have to be weighed, which is a very great gain in the accuracy of the results obtained.⁴⁷ Dulong and Berzelius (1819) were the first to determine the composition of water by this method, and they found that water contains 88.91 of oxygen and 11.09 of hydrogen in 100 parts, or 8.008 parts of oxygen per one part of hydrogen. Dumas (1842) improved on this method,⁴⁸ and found that

⁴⁶ Several numerical data and reflections bearing on this matter are enumerated in Notes 7, 9, and 11. It must be observed that the action of iron or zinc on water, or, conversely, of hydrogen on the oxides of iron or zinc, forms a reversible reaction, which proceeds in one or the other direction, according to which is removed from the sphere of action; the hydrogen or the water act according to which is present in a predominating mass. *The influence of mass* is clearly evinced in this case. But the reaction $\text{CuO} + \text{H}_2 = \text{Cu} + \text{H}_2\text{O}$ is not reversible; the difference between the degrees of affinity is very great in this case, and, therefore, as far as is at present known, no hydrogen is evolved even in the presence of a large excess of water. It is to be further remarked, that under the conditions of the dissociation of water, copper is not oxidised by water, most probably because the oxide of copper itself is decomposable by heat.

⁴⁷ This determination may be carried on in an apparatus like that mentioned in Note 13 of Chapter I.

⁴⁸ We will proceed to describe Dumas' method and results. For this determination pure and dry copper oxide is necessary. Dumas took a sufficient quantity of copper oxide for the formation of 50 grams of water in each determination. As the oxide of copper was weighed before and after the experiment, and as the amount of oxygen contained in water was determined by the difference between these weights, it was essential that no other substance besides the oxygen forming the water should be evolved from the oxide of copper during its ignition in hydrogen. It was necessary, also, that the hydrogen should be perfectly pure, and free not only from traces of moisture, but from any other impurities which might dissolve in the water or combine with the copper and form some other compound with it. The bulb containing the oxide of copper (fig. 26), and which was heated to redness, should be quite free from air, as otherwise the oxygen in the air might, in combining with the hydrogen passing through the vessel, form water in addition to the oxygen of the oxide of copper. The water formed should be entirely absorbed in order to accurately determine the quantity of the resultant water. The hydrogen was evolved in the three-necked bottle. The sulphuric acid, for acting on the zinc, is poured through funnels into the middle neck. The hydrogen evolved in the Woulfe's bottle passes through U tubes, in which it is purified, to the bulb, where it comes into contact with the copper oxide, forms water, and reduces the oxide to metallic copper; the water formed is condensed in the second bulb, and any passing off is absorbed in the second set of U tubes. This is the general arrangement of the apparatus. The bulb

water contains 12·575 parts of hydrogen per 100 parts oxygen, that is—7·990 parts of oxygen per 1 part of hydrogen, and therefore it is usually

with the copper oxide is weighed before and after the experiment. The loss in weight, shows the quantity of oxygen which went into the composition of the water formed,

the weight of the latter being shown by the gain in weight of the absorbing apparatus. Knowing the amount of oxygen in the water formed, we also know the quantity of hydrogen contained in it, and consequently we determine the composition of water by weight. This is the essence of the determination. We will now turn to particulars. In one neck of the three-necked bottle there is placed a tube immersed in mercury. This serves as a safety-valve to prevent the pressure inside the apparatus becoming too great from the rapid evolution of hydrogen. Did the pressure rise to any considerable extent, the current of gases and vapours would be very rapid, and, as a consequence, the hydrogen would not be perfectly purified, or the water be entirely absorbed in the tubes placed for this purpose. In the third neck of the Woulfe's bottle there is a tube leading the hydrogen to the purifying apparatus, consisting of eight U tubes, destined for the purification and testing of the hydrogen. The hydrogen, evolved by zinc and sulphuric acid, is purified by passing it first through a tube full of pieces of glass moistened with a solution of lead nitrate, next through silver sulphate; the lead nitrate retains sulphuretted hydrogen, and arseniuretted hydrogen is retained by the tube with silver sulphate. Caustic potash in the next U tube retains any acid which might come over. The two following tubes are filled with lumps of dry caustic potash in order to absorb any carbonic anhydride and moisture which the hydrogen might contain. The next two tubes are, to completely dry the gas, filled with a powder of phosphoric




FIG. 26.—Apparatus employed by Dumas for determining the composition of water. Described in text.

received that *water contains eight parts by weight of oxygen per one part by weight of hydrogen*. By whatever method water be obtained, it will

anhydride, intermingled with lumps of pumice-stone. They are immersed in a freezing mixture. The small U tube contains hygroscopic substances, and is weighed before the experiment: this is in order to know whether the hydrogen passing through still retains any moisture. If it does not, then the weight of this tube will not vary during the whole experiment, but if the hydrogen evolved still retains moisture, the tube will increase in weight. The copper oxide is dropped into the bulb, which is, previous to the experiment, dried with the copper oxide during a long period of time. The air is then exhausted from it, in order to weigh the oxide of copper in a vacuum and to avoid making any correction for weighing in air. The bulb is made of infusible glass, that it may be able to withstand a lengthy (20 hours) exposure to a red heat without changing in form. The weighed bulb is only connected with the purifying apparatus after the hydrogen has already passed through for a long time, and after experiment has shown that the hydrogen passing from the purifying apparatus is pure and does not contain any air. When the bulb is connected with the purifying apparatus, its cock is opened and the hydrogen fills the bulb. The drawn-out end of the bulb is joined by an india-rubber tube with the second bulb, in which the water formed is condensed. When this connection is made, the thread binding up the india-rubber tube is untied, and then the hydrogen can pass freely through the apparatus. On passing from the condensing bulb the gas and vapour enter into an apparatus for absorbing the last traces of moisture. The first U tube contains pieces of ignited potash, the second and third tubes phosphoric anhydride or pumice-stone moistened with sulphuric acid. The last of the two is employed for determining whether all the moisture is absorbed, and is therefore weighed separately. The final tube only serves as a safety-tube for the whole apparatus, in order that the external moisture should not penetrate into it. The glass cylinder contains sulphuric acid, through which the excess of hydrogen passes; it enables the rate at which the hydrogen is evolved to be judged, and whether its amount should be decreased or increased.

When the apparatus is set up it must be seen that all its parts are hermetically tight before commencing the experiment. When the previously weighed parts are joined up together and the whole apparatus put into communication, then the bulb containing the copper oxide is heated with a spirit lamp (reduction does not take place without the aid of heat), and the reduction of the copper oxide then takes place, and water is formed, which condenses in the absorbing apparatus. When nearly all the copper oxide is reduced the lamp is removed and the apparatus allowed to cool, the current of hydrogen being kept up all the time. When cool, the drawn-out end of the bulb is fused up, and the hydrogen remaining in it is exhausted, in order that the copper may be again weighed in a vacuum. The absorbing apparatus remains full of hydrogen, and would therefore present a less weight than if it were full of air, as it was before the experiment, and, therefore, having disconnected the copper oxide bulb, a current of dry air is passed through it until the gas passing from the glass cylinder is quite free from hydrogen. The condensing bulb and the two tubes next to it are then weighed, in order to determine the quantity of water formed. Dumas repeated this experiment many times. The average result was that water contains 1253·3 parts of hydrogen per 10000 parts of oxygen. Making a correction for the amount of air contained in the sulphuric acid employed for producing the hydrogen, Dumas obtained the average figure 1251·5, between the extremes 1247·2 and 1256·2. This proves that per 1 part of hydrogen water contains 7·9904 parts of oxygen, with a possible error of not more than $\pm \frac{1}{100}$, or 0·03, in the amount of oxygen per 1 part of hydrogen.

Erdmann and Marchand, in eight determinations, found that per 10000 parts of oxygen water contains an average of 1252 parts of hydrogen, with a difference of from 1258·5 to 1248·7; hence per 1 part of hydrogen there would be 7·9952 of oxygen, with an error of at least 0·05, because, taking the figure 1258·5, the amount of oxygen per 1 part of hydrogen would be 7·944.

always present the same composition. Whether it be taken from nature and purified, or whether it be obtained from hydrogen by oxidation, or whether it be separated from any of its compounds, or obtained by some double decomposition it will in every case contain one part of hydrogen and eight parts of oxygen. This is because water is a definite chemical compound. Detonating-gas, from which it may be formed, is a simple mixture of oxygen and hydrogen, although a mixture of the same composition as water. All the properties of both constituent gases are preserved in detonating-gas. Either one or the other gas may be added to it without destroying its homogeneity. The fundamental properties of oxygen and hydrogen are not found in water, and neither of the gases can be added to it. But they may be evolved from it. In the formation of water there is an evolution of heat ; for the decomposition of water heat is required. All this is expressed by the words, *Water is a definite chemical compound of hydrogen with oxygen.* Taking the symbol of hydrogen, H, as expressing a unit quantity by weight of this substance, and by expressing 16 parts by weight of oxygen by O, we can express all the above statements by the chemical symbol of water, H_2O . As only definite chemical compounds are denoted by formulæ, having denoted the formula of a compound substance, we express by it the entire series of conceptions which are connected with the representation of a definite compound, and, at the same time, the quantitative composition of the substance by weight. Further, as we shall afterwards see, formulæ express the volume of the gases contained in a substance. Thus the formula of water shows that it contains two volumes of hydrogen and one volume of oxygen. Besides which, we shall learn that the formula expresses the density of the vapour of a compound, and on this, as we have seen, many properties of substances depend. This vapour density, as we shall learn, also determines the quantity of a substance entering into a reaction. Thus the letters H_2O tell the chemist the entire history of the substance. This is an international language, which endows chemistry with a simplicity, clearness, stability, and trustworthiness founded on the investigation of the laws of nature.

Keiser (1888), in America, by employing palladium hydride, and by introducing various new precautions for obtaining accurate results, found the composition of water to be 15.95 parts of oxygen per 2 of hydrogen.

Certain of the latest determinations of the composition of water are hardly less exact than the analysis made by Dumas, and always give less than 8, and on the average 7.98, of oxygen per 1 part of hydrogen. At present, therefore, the atomic weight of oxygen is taken as 15.96. However, this figure is not to be entirely depended on, and for ordinary accuracy it may be considered that $\text{O}=16$.

CHAPTER III

OXYGEN AND THE CHIEF ASPECTS OF ITS SALINE COMBINATIONS.

ON the earth's surface there is no other element which is so widely distributed as oxygen in its various compounds.¹ It makes up eight-ninths of the weight of water, which occupies the greater part of the earth's surface. Nearly all earthy substances and rocks consist of compounds of oxygen with metals and other elements. Thus, the greater part of sand is formed of silica, SiO_2 , which is a compound of oxygen with silicon, and contains 53 p.c. of oxygen; clay contains water, alumina (formed of aluminium and oxygen), and silica. It may be considered that earthy substances and rocks contain up to one-third of their weight of oxygen; animal and vegetable substances are also very rich in oxygen. Without counting the water present in them, plants contain up to 40, and animals up to 20 p.c. by weight of oxygen. Thus, oxygen compounds predominate on the earth's surface, and form about one-half of the whole of the solid and liquid matters of the earth's crust. Besides this, a portion yet remains free, and is contained in admixture with nitrogen in the atmosphere, forming about one-fourth of its mass, or one-fifth of its volume.

Being so widely distributed in nature, oxygen plays a very important part in it, for a number of the phenomena which take place before us are mainly dependent on it. *Animals breathe* air in order to obtain only *oxygen* from it, the oxygen entering into their respiratory organs (the lungs of human beings and animals, the gills of fishes, and the trochæ of insects); they, so to say, drink in air in order to absorb the oxygen. The oxygen of the air (or dissolved in water) passes through the membranes of the respiratory organs into the blood, is retained in it by the blood corpuscles, is transmitted by their means to all parts of the body, aids their transformations, bringing

¹ As regards the interior of the earth, it probably contains far less oxygen compounds than the surface, judging by the accumulated evidences of the earth's origin, of meteorites, of the earth's density, &c., as set forth in the fourth chapter of my work on the 'Naphtha Industry,' 1877, in speaking of the origin of naphtha.

about chemical processes in them, and chiefly extracting carbon from them in the form of carbonic anhydride, the greater part of which passes into the blood, is dissolved by it, and is thrown off by the lungs during the absorption of the oxygen. Thus, in the process of respiration carbonic anhydride (and water) is given off, and the oxygen of the air absorbed, by which means the blood is changed from a dark-red venous to a bright-red arterial blood. The cessation of this process causes death, because then all those chemical processes, and the consequent heat and work which the oxygen introduced into the system brought about, ceases. For this reason suffocation and death ensue in a vacuum, or in a gas which does not contain free oxygen (which does not support combustion). If an animal be placed in an atmosphere of free oxygen, then at first its movements are very active and a general invigoration is remarked, but a reaction soon sets in, and perhaps death may ensue. The oxygen of the air, when it enters the lungs, is diluted with four volumes of nitrogen, which is not absorbed into the system, and therefore the blood absorbs but a small quantity of oxygen from the air, whilst in an atmosphere of pure oxygen a large quantity of oxygen would be absorbed, which would produce a very rapid change of all parts of the organism, and destroy it. From what has been said, it will be understood that oxygen may be employed in respiration, at least for a limited time, when the respiratory organs suffer under certain forms of suffocation and impediment to breathing.²

The combustion of organic substances—that is, substances which make up the composition of plants and animals—proceeds in the same manner as the combustion of many inorganic substances, such as sulphur, phosphorus, iron, &c., from the combination of these substances with oxygen, as was described in the Introduction. The decomposition, rotting, and similar transformations of substances, which

² It is evident that the partial pressure (*see* Chap. II.) acts in respiration. The researches of Paul Bert showed this with particular clearness. Under a pressure of one-fifth of an atmosphere consisting of oxygen only, animals and human beings remain under the ordinary conditions of the partial pressure of oxygen, but organisms cannot support air rarefied to one-fifth, for then the partial pressure of the oxygen falls to one-twenty-fifth of an atmosphere. Even under a pressure of one-third of an atmosphere the regular life of human beings is impossible, by reason of the impossibility of respiration (of the decrease of solubility of oxygen in the blood), owing to the small partial pressure of the oxygen, and not from the mechanical effect of the decrease of pressure. Paul Bert illustrated all this by many experiments, some of which he conducted on himself. This explains, among other things, the discomfort felt in the ascent of high mountains or in balloons when the height reached exceeds eight kilometres, and at pressures below 250 mm. (Chap. II. note 23). It is evident that an artificial atmosphere has to be employed in the ascent to great heights, just as in submarine work. The cure by compressed and rarefied air which is practised in certain illnesses is based partly on the mechanical action of the change of pressure, and partly on the alteration in the partial pressure of the respired oxygen.

proceed around us, are also very often dependent on the action of the oxygen of the air, and also reduce it from a free to a combined state. The majority of the compounds of oxygen are, like water, very stable, and do not give up their oxygen under the ordinary conditions of nature. As these processes are taking place everywhere, therefore the amount of free oxygen in the atmosphere should decrease, and this decrease should proceed somewhat rapidly. This is, in fact, observed where combustion or respiration proceeds in a closed space. Animals suffocate in a closed space because in consuming the oxygen the air remains unfit for respiration. In the same manner combustion, in time, ceases in a closed space, which may be proved by a very simple experiment. An ignited substance—for instance a piece of burning sulphur—has only to be placed in a glass flask, which is then closed with a stout cork to prevent the access of the external air; combustion will proceed for a certain time, so long as the flask contains any free oxygen, but it will cease, although there still remain unburnt sulphur, when all the oxygen of the enclosed air has combined with the sulphur. From what has been said, it is evident that regularity of combustion or respiration requires a constant renewal of air—that is, that the burning substance or respiring animal should have access to a fresh supply of oxygen. This is attained in human habitations by having many windows, outlets, and ventilators, and by the current of air produced by fires and stoves. As regards the air over the entire earth's surface, its amount of oxygen hardly decreases, because in nature there is a process going on which renews the supply of free oxygen. *Plants*, or rather their leaves, during daytime³—that is, under the influence of light—*evolve free oxygen*. Thus the loss of oxygen which occurs in consequence of the respiration of animals and of combustion is made good by plants. If a leaf be placed in a bell jar containing water, and carbonic anhydride (because this gas is absorbed and oxygen evolved from it by plants) be passed into the bell, and the whole apparatus be placed in sunlight, then oxygen will accumulate in the bell jar. This experiment was first made by Priestley at the end of the last century. Thus the life of plants on the earth not only serves for the formation of food for animals, but also for keeping up a constant percentage of oxygen in the atmosphere. In the long period of the life of the earth that equilibrium has been attained between the processes ab-

³ At night, without the action of light, without the absorption of that energy which is required for the decomposition of carbonic anhydride into free oxygen and carbon, which is retained by the plants, they breathe like animals, absorbing oxygen and evolving carbonic anhydride. This process also goes on side by side with the reverse process in daytime, but then it is far feeblower than that which gives oxygen. This observation is a necessary consequence of an aggregate of data referring to the physiological processes of plants.

sorbing and envolving oxygen, by which a definite quantity of free oxygen is preserved in the entire mass of the atmosphere.⁴

Free oxygen may be obtained by one or another method from all the substances in which it occurs. Thus, for instance, the oxygen of many substances may be transferred into water, from which, as we have already seen, oxygen may be obtained.⁵ We will first consider the methods of extracting oxygen from air as being a substance everywhere distributed. The separation of oxygen from it is, however, hampered by many difficulties.

From air, which contains a *mixture* of oxygen and nitrogen, the nitrogen alone cannot be removed, because it has no inclination to combine directly or readily with any substance; and although it does combine with certain substances (boron, titanium), these substances combine simultaneously with the oxygen of the atmosphere.⁶ However,

⁴ The earth's surface is equal to about 510 million square kilometres, and the mass of the air (at a pressure of 760 mm.) on each kilometre of surface is about $10\frac{1}{2}$ thousand millions of kilograms, or about $10\frac{1}{2}$ million tons; therefore the whole weight of the atmosphere is about 5100 million million ($=51 \times 10^{14}$) tons. Consequently there are about 2×10^{15} tons of free oxygen in the earth's atmosphere. The innumerable series of processes which absorb a portion of this oxygen are compensated for by the plant processes. Counting that 100 million tons of vegetable matter, containing 40 p.c. of carbon, formed from carbonic acid, are produced (and the same process proceeds in water) per year on the 100 million square kilometres of dry land (ten tons of roots, leaves, stems, &c. per hectare, or $\frac{1}{100}$ of a square kilometre), we find that the plant life of the dry land gives about 100,000 tons of oxygen, which is an insignificant fraction of the entire mass of the oxygen of the air.

⁵ The extraction of oxygen from water may evidently be accomplished by two processes: either by the decomposition of water into its constituent parts by the action of a galvanic current (Chap. II.), or by means of the removal of the hydrogen from water. But, as we have seen and already know, hydrogen enters into direct combination with very few substances, and then only under special circumstances; whilst oxygen, as we shall soon learn, combines with nearly all substances. Only gaseous chlorine (and especially, fluorine) is capable of decomposing water, taking up the hydrogen from it, without combining with the oxygen. Chlorine is soluble in water, and if an aqueous solution of chlorine, so-called chlorine water, be poured into a flask, and this flask be inverted in a basin containing the same chlorine water, then we shall have an apparatus by means of which oxygen may be extracted from water. At the ordinary temperature, and in the dark, chlorine does not act on water, or only acts very feebly; but under the action of direct sunlight chlorine decomposes water, with the evolution of oxygen. The chlorine then combines with the hydrogen, and gives hydrochloric acid, which dissolves in the water, and therefore free oxygen only will be separated from the liquid, and it will only contain a small quantity of chlorine in admixture, which can be easily removed by passing the gas through a solution of caustic potash, which retains the chlorine.

⁶ A difference in the physical properties of both gases cannot be here taken advantage of, because they are very similar in this respect. Thus the density of oxygen is 16, and of nitrogen 14 times greater than the density of hydrogen, and therefore porous vessels cannot be here employed—the difference between the times of their passage through a porous surface would be too insignificant.

Graham, however, succeeded in enriching air in oxygen by passing it through india-

oxygen may be separated from air by causing it to combine with substances which may be easily decomposed by the action of heat, and, in

rubber. This may be done in the following way:—A common india-rubber cushion, *E* (Fig. 27), is taken, and its orifice hermetically connected with an air-pump, or, better still, a mercury aspirator (the Sprengel pump is designated by the letters *A*, *C*, *B*). When the aspirator (Chap. II. note 16) pumps out the air, which will be seen by the mercury running out in an almost uninterrupted stream, and from its standing at near the barometric height, then it may be clearly remarked that gas passes through the india-rubber. This is also seen from the fact that bubbles of gas continually pass along with the mercury. A small pressure of air may be constantly kept up in the cushion by pouring mercury into the funnel *A*, and screwing up the cock *c*, so that the stream flowing from it be small, and then a portion of the air passing through the india-rubber will be carried along with the mercury. This air may be collected in the cylinder *x*. Its composition proves to be about 42 volumes of oxygen with 57 volumes of nitrogen, and one volume of carbonic anhydride, whilst ordinary air contains only 21 volumes of oxygen in 100 volumes. A square metre of india-rubber surface (of the usual thickness) passes about 45 c.c. of such air per hour. This experiment clearly shows that india-rubber is permeable to gases. This may, by the way, be observed in common toy balloons filled with coal-gas. They fall after a day or two, not because there are holes in them, but because air penetrates into, and the gas from, their interior, through the surface of the india-rubber of which they are made. The rate of the passage of gases through india-rubber does not, as Mitchell and Graham showed, depend on their densities, and consequently its permeability is not determined by orifices. It more resembles dialysis—that is, the penetration of liquids through colloid surfaces. Equal volumes of gases penetrate through india-rubber in periods of time which are related to each other as follows:—carbonic anhydride, 100; hydrogen, 247; oxygen, 532; marsh gas, 633; carbonic oxide, 1220; nitrogen, 1358. Hence nitrogen penetrates more slowly than oxygen, and carbonic anhydride more quickly than other gases. 2·556 volumes of oxygen and




FIG. 27. Graham's apparatus for the decomposition of air by pumping it through india-rubber.

so doing, give up the oxygen absorbed—that is, by making use of reversible reactions. Thus, for instance, the oxygen of the atmosphere may be made to oxidise sulphurous anhydride, SO_2 (by passing directly over ignited spongy platinum), and to form sulphuric anhydride, or sulphur trioxide, SO_3 ; and this substance (which is a solid and volatile, and therefore easily separated from the nitrogen and sulphurous anhydride), by heating again, gives oxygen and sulphurous anhydride. Caustic soda or lime extracts (absorbs) the sulphurous anhydride from this mixture, whilst the oxygen is not absorbed, and thus it is isolated from the air. On a large scale in works, as we shall afterwards see, sulphurous anhydride is transformed into hydrate of sulphuric trioxide, or sulphuric acid, H_2SO_4 ; if this is made to fall in drops on red-hot flagstones, water, sulphurous anhydride, and oxygen are obtained. The oxygen is easily isolated from this mixture by passing the gases over lime. The extraction of oxygen from oxide of mercury (Priestley, Lavoisier), which is obtained from mercury and the oxygen of the atmosphere, is also a reversible reaction by which oxygen may be obtained from the atmosphere. So also, by passing dry air through a red-hot tube containing barium oxide, it is made to combine with the oxygen of the air. By this reaction the so-called barium peroxide, BaO_2 , is formed from the barium oxide BaO , and at a higher temperature the former evolves the absorbed oxygen, and leaves the barium oxide originally taken.⁷

13·585 volumes of carbonic anhydride penetrate in the same time as one volume of nitrogen. By multiplying these ratios by the amounts of these gases in air, we obtain figures which are in almost the same proportion as the volumes of the gases penetrating from air through india-rubber. If the process of dialysis be repeated on the air which has already passed through india-rubber, then a mixture containing 65 p.c. by volume of oxygen is obtained. It may be thought that the cause of this phenomenon is the absorption or occlusion (*see* Chap. II) of gases by india-rubber and the evolution of the gas dissolved in a vacuum; and, indeed, india-rubber does absorb gases, especially carbonic anhydride; just as metals, especially on an increase of temperature, absorb gases, as was mentioned in the last chapter. Graham called the above method of the decomposition of air *atmolysis*.

⁷ The preparation of oxygen by this method, which is due to Bunsen, is conducted in a porcelain tube, which is placed in a stove heated by charcoal, so that its ends project beyond the stove. Barium oxide (which may be obtained by igniting barium nitrate, previously dried) is placed in the tube, one end of which is connected with a pair of bellows, or a gas-holder, for keeping up a current of air through it. The air is previously passed through a solution of caustic potash, to remove all traces of carbonic anhydride, and it is very carefully dried (for the hydrate BaH_2O_2 does not give the peroxide). At a *dark-red heat* (500–600°) the oxide of barium absorbs oxygen from the air, so that the gas leaving the tube consists almost entirely of nitrogen. When the absorption ceases, the air will pass through the tube unchanged, which may be recognised from the fact that it supports combustion. The barium oxide is converted into peroxide under these circumstances, and eleven parts of barium oxide absorb about one part of oxygen by weight. When the absorption ceases, one end of the tube is closed, a cork with a gas-conducting tube is fixed

Oxygen is evolved with particular ease by a whole series of unstable oxygen compounds, of which we will proceed to take a general survey, remarking that many of these reactions, although not all, belong to the number of reversible reactions;⁸ so that in order to obtain many of these substances (for instance, potassium chlorate) rich in oxygen, recourse must be had to indirect methods (see Introduction), with which we shall become acquainted in the course of this book.

1. *The compounds of oxygen* with certain metals, and especially with the so-called noble metals—that is, mercury, silver, gold, and platinum—having been once obtained, retain their oxygen at the ordinary temperature, but part with it at a red heat. The compounds are solids, generally amorphous and infusible, and are easily decomposed by heat into the metal and oxygen. We have seen an example of this in speaking of the decomposition of mercury oxide. Priestley, in 1774, obtained pure oxygen for the first time by heating mercury oxide by means of a burning-glass, and clearly showed its difference from air. He showed its characteristic property of supporting combustion “with remarkable vigour,” and named it dephlogisticated air.

into the other end, and the heat of the stove is increased to a *bright-red heat* (800°). At this temperature the barium peroxide gives up all that oxygen which it acquired at a dark-red heat—*i.e.*, about one part by weight of oxygen is evolved from twelve parts of barium peroxide. After the evolution of the oxygen there remains the barium oxide which was originally taken, so that air may be again passed over it, and thus the preparation of oxygen from one and the same quantity of barium oxide may be repeated many times. Oxygen has been procured one hundred times from one mass of oxide by this method; all the necessary precautions being taken, as regards the temperature of the mass and the removal of moisture and carbonic acid from the air. Unless these precautions be taken, the mass of oxide soon spoils.

As oxygen may become of considerable technical use, from its capacity for giving high temperatures and intense light in the combustion of substances, its preparation directly from air by practical methods forms a problem whose solution many investigators continue to work at up to the present day. The most practical method is that of Tessié du Motoy. It is based on the fact that a mass of equal weights of manganese peroxide and caustic soda at an incipient red heat (about 350°) absorbs oxygen from air, with the separation of water, according to the equation $\text{MnO}_2 + 2\text{NaHO} + \text{O} \rightarrow \text{Na}_2\text{MnO}_4 + \text{H}_2\text{O}$. If superheated steam, at a temperature of about 450°, be then passed through the mixture, the manganese peroxide and caustic soda originally taken are regenerated, and the oxygen held by them is evolved, according to the reverse equation $\text{Na}_2\text{MnO}_4 + \text{H}_2\text{O} \rightarrow \text{MnO}_2 + 2\text{NaHO} + \text{O}$. This mode of preparing oxygen may be repeated for an infinite number of times. The oxygen in combining separates out water, and steam, acting on the resultant substance, evolves oxygen. Hence all that is required for the preparation of oxygen by this method is fuel and the alternate cutting off the supply of air and steam.

⁸ Even the decomposition of manganese peroxide is reversible, and it may be obtained from that suboxide (or its salts), which is formed in the evolution of oxygen (Chap. XI. note 6). The compounds of chromic acid containing the trioxide CrO_3 , in evolving oxygen give chromium oxide, Cr_2O_3 , but they re-form the salt of chromic acid when heated at a red heat in air with an alkali.

2. The substances called *peroxides*⁹ evolve oxygen at a greater or less heat (and also by the action of many acids). They usually contain metals combined with a large quantity of oxygen. Peroxides are the highest oxides of certain metals; those metals which form them generally give several compounds with oxygen. Those of the lowest degrees of oxidation, containing the least amount of oxygen, are generally substances which are capable of easily reacting on acids—for instance, with sulphuric acid. Such low oxides are called bases. Peroxides contain more oxygen than the bases formed by the same metals. For example, lead oxide contains 7.1 parts of oxygen in 100 parts, and is basic, but lead peroxide contains 13.3 parts of oxygen in 100 parts. *Manganese peroxide* is a similar substance, which is a solid of a dark colour, and occurs in nature. It is employed in the manufactures under the name of black oxide of manganese (in German, ‘Braunstein,’ the pyrolusite of the mineralogist). Peroxides are able to evolve oxygen at a more or less elevated temperature. They do not then part with all their oxygen, but with only a portion of it, and are converted into a lower oxide or base. Thus, for example, lead peroxide, on heating, gives oxygen and lead oxide. The decomposition of this peroxide proceeds somewhat easily on heating, even in a glass vessel, but manganese peroxide only evolves oxygen at a strong red heat, and therefore oxygen can only be obtained from it in iron, or other metallic, or clay vessels. This used to be the method for obtaining oxygen. Manganese peroxide only parts with one-third of its oxygen (according to the equation $3\text{MnO}_2 = \text{Mn}_3\text{O}_4 + \text{O}_2$), whilst two-thirds remain in the solid substance which forms the residue from the heating. Metallic peroxides are also capable of evolving oxygen on heating with sulphuric acid. They then evolve so much oxygen as is in excess of that necessary for the formation of the base, the latter reacting on the sulphuric acid forming a compound (salt) with it. Thus barium peroxide, when heated with sulphuric acid, forms oxygen and barium oxide, which gives a compound with sulphuric acid which is termed barium sulphate ($\text{BaO}_2 + \text{H}_2\text{SO}_4 = \text{BaSO}_4 + \text{H}_2\text{O} + \text{O}$). This reaction usually proceeds with greater ease than the decomposition of peroxides by heat alone. For the purposes of experiment powdered manganese peroxide is usually taken and mixed with strong sulphuric acid in a flask, and the apparatus set up as shown in Fig. 28. The gas which is evolved is

⁹ We shall afterwards see that it is only substances like barium peroxide (which give hydrogen peroxide) which should be counted as true peroxides, and that MnO_2 , PbO_2 , &c., should be distinguished from them (they do not give hydrogen peroxide with acids, but give chlorine with hydrochloric acid), and therefore it is best to call them dioxides.

passed through a Woulfe's bottle containing a solution of caustic potash, to purify it from carbonic anhydride and chlorine, which accompany the evolution of oxygen from commercial manganese peroxide, and the gas is not collected until a thin smouldering taper placed in front of the escape orifice bursts into flame, which shows that the gas coming off is oxygen. By this method of decomposition of the manganese peroxide by sul-




FIG. 28.—Preparation of oxygen from manganese peroxide and sulphuric acid. The gas evolved is passed through a Woulfe's bottle containing caustic potash.

phuric acid there is evolved, not, as in heating, one-third, but one-half of the oxygen contained in the peroxide ($\text{MnO}_2 + \text{H}_2\text{SO}_4 = \text{MnSO}_4 + \text{H}_2\text{O} + \text{O}$)—that is, from 50 grams of peroxide about $7\frac{1}{2}$ grams, or about $5\frac{1}{2}$ litres, of oxygen,¹⁰ whilst by heating only about $3\frac{1}{2}$ litres are obtained. The chemists of Lavoisier's time generally obtained oxygen by heating manganese peroxide. Now there are more convenient methods known.

3. A third source to which recourse may be had for obtaining oxygen is represented in *acids* and *salts* containing much oxygen, and which are capable, by parting with a portion or all of their oxygen, of being converted into other compounds (lower products of oxidation) which are more difficultly decomposed. These acids and salts (like peroxides) evolve oxygen either on heating alone, or when heated with some other substance. Sulphuric acid may be taken as an example of an acid which is decomposed by the action of heat alone,¹¹ for it breaks up at a red heat into water, sulphurous anhydride,

¹⁰ Scheele, in 1785, discovered the method of obtaining oxygen by treating manganese peroxide with sulphuric acid.

¹¹ All acids rich in oxygen, and especially those whose elements form lower oxides, evolve oxygen either directly at the ordinary temperature (for instance, ferric acid), or on heating (for instance, nitric, manganic, chromic, chloric, and others), or if basic lower oxides are formed from them, by heating with sulphuric acid. Thus the salts

and oxygen, as was mentioned before. Priestley, in 1772, and Scheele, somewhat later, obtained oxygen by heating nitre to a red heat. The best examples of the formation of oxygen by the heating of salts is given in *potassium chlorate*, or Berthollet's salt, called after the French chemist who discovered it. Potassium chlorate is a salt composed of the elements potassium, chlorine, and oxygen, KClO_3 . It occurs as transparent colourless plates, is soluble in water, especially in hot water, and resembles common table salt in some of its physical properties; it melts on heating, and in melting begins to decompose, evolving oxygen gas. This decomposition ends in all the oxygen being evolved from the potassium chlorate, potassium chloride being left as a residue, according to the equation $\text{KClO}_3 = \text{KCl} + \text{O}_3$.¹² This decomposition proceeds at a temperature which allows of its being conducted in a vessel made of glass. However, in decomposing, the molten potassium chlorate swells up and boils, and gradually solidifies, so the evolution of the oxygen is not regular, and the glass vessel may crack. In order to overcome this inconvenience, the potassium chlorate is crushed and mixed with a powder of a substance which is incapable of combining with the oxygen evolved, and which is a good conductor of heat. Usually it is mixed with manganese peroxide.¹³ The decomposition of the potassium chlorate is then considerably facilitated, and proceeds at a lower temperature (because the entire mass is then better heated, both externally and internally), without swelling up, and is therefore more convenient than the decomposition of the salt alone. This method for the preparation of oxygen is very convenient; it is generally employed when a small quantity of oxygen is required. Further, potassium chlorate is easily obtained pure, and it evolves much oxygen. 100 grams of the salt give as much as 39 grams, or 30 litres, of oxygen. This method is so simple and easy,¹⁴ that a course of practical chemistry

of chromic acid (for instance, potassium dichromate, $\text{K}_2\text{Cr}_2\text{O}_7$) give oxygen with sulphuric acid; first potassium sulphate, K_2SO_4 , is formed, and then the chromic acid set free gives a sulphuric acid salt of the lower oxide, Cr_2O_3 .

¹² This reaction is not reversible, and is exothermal—that is, it does not absorb heat, but, on the contrary, evolves 9713 calories per molecular weight KClO_3 , equal to 122 parts of salt (according to the determination of Thomsen, who burnt hydrogen in a calorimeter either alone or with a definite quantity of potassium chlorate mixed with oxide of iron). It does not proceed at once, but first forms perchlorate, KClO_4 (see Chlorine and Potassium). It is to be remarked that potassium chloride melts at 738° , potassium chlorate at 372° , and potassium perchlorate at 610° .

¹³ The peroxide does not evolve oxygen in this case. It may be replaced by many oxides—for instance, by oxide of iron. It is necessary to take the precaution that no combustible substances (such as bits of paper, splinters, sulphur, &c.) fall into the mixture, as they might cause an explosion.

¹⁴ The decomposition of a mixture of melted and well-crushed potassium chlorate

is often commenced by the preparation of oxygen by this method, and of hydrogen by the aid of zinc and sulphuric acid, all the more as these gases enable many interesting and striking experiments to be made.¹⁵

A solution of *bleaching powder*, which contains calcium hypochlorite, CaCl_2O_2 , evolves oxygen when gently heated with the addition of a small quantity of certain oxides—for instance, cobalt oxide, which in this case acts by contact (*see* Introduction). Of itself, a solution of bleaching powder does not evolve oxygen when heated, but it oxidises the cobalt oxide to a higher degree of oxidation; this higher oxide of cobalt in contact with the bleaching powder, decomposes into oxygen and lower oxidation products, and the resultant lower oxide of cobalt with bleaching powder again gives the higher oxide, which again gives up its oxygen, and so on.¹⁶ The calcium hypochlorite is here decomposed according to the equation $\text{CaCl}_2\text{O}_2 = \text{CaCl}_2 + \text{O}_2$. In this manner a small quantity of cobalt oxide¹⁷ is sufficient for the decomposition of an indefinitely large quantity of bleaching powder.

with powdered manganese peroxide proceeds at so low a temperature (the salt does not melt) that it may be effected in an ordinary glass flask. As the reaction is exothermal, the decomposition of potassium chlorate with the formation of oxygen may probably be accomplished, under certain conditions (for example under contact action), at very low temperatures. Substances mixed with the potassium chlorate probably act partially in this manner.

¹⁵ Many other salts evolve oxygen by heat, like potassium chlorate, but they only part with it either at a very strong heat (for instance, common nitre) or else are unsuited for use on account of their cost (for instance, potassium manganate), or evolve impure oxygen at a high temperature (for instance, zinc sulphate at a red heat gives a mixture of sulphurous anhydride and oxygen), and are not therefore used in practice.

¹⁶ Such is, at present, the only possible method of explaining the phenomenon of contact action. In many cases, as here, it is supported by observations based on facts. Thus, for instance, it is known, as regards oxygen, that often two substances rich in oxygen retain it so long as they are separate, but directly they come into contact free oxygen is evolved from both of them. Thus, an aqueous solution of hydrogen peroxide (containing twice as much oxygen as water) acts in this manner on silver oxide (containing silver and oxygen). This reaction takes place at the ordinary temperature, and the oxygen is evolved from both compounds. To this class of phenomena may be also referred the fact that a mixture of barium peroxide and potassium manganate with water and sulphuric acid evolves oxygen at the ordinary temperature. It would seem that the essence of phenomena of this kind is entirely and purely a property of contact; the distribution of the atoms is changed by contact, and if the equilibrium be unstable it is destroyed. This is especially clear for substances which change exothermally—that is, for those reactions which are accompanied by an evolution of heat. The decomposition $\text{CaCl}_2\text{O}_2 = \text{CaCl}_2 + \text{O}_2$ belongs to this class (like the decomposition of potassium chlorate).

¹⁷ Generally a solution of bleaching powder is alkaline (contains free lime), and, there-

*The properties of oxygen.*¹⁸—It is a permanent gas—that is, it cannot be liquefied by pressure at the ordinary temperature, and further, is only liquefied with difficulty (although more easily than hydrogen) at temperatures below -120° , because this is its absolute boiling point. As its critical pressure¹⁹ is about 50 atmospheres, it can be easily liquefied under pressures greater than 50 atmospheres at temperatures below -120° . Pictet obtained liquid oxygen at -140° , by employing a pressure above 100 atmospheres. According to Dewar, the density of oxygen in a critical state is 0.65 (water=1), but it, like all other substances in this state,²⁰ varies considerably in density with a change of pressure and temperature, and therefore many investigators who made their observations under high pressures give a greater density, as much as 1.1. Oxygen, like all gases, is transparent, and like the majority of gases, colourless. It has no smell or taste, which is evident from the fact of its being a component of air. The weight of one cubic centimetre in grams at 0° and 760 mm. pressure is 0.0014298 grams, and a litre weighs 1.4298 grams; it is therefore slightly denser than air. Its density in respect to air=1.1056, and in respect to hydrogen=16 (more exactly 15.96).²¹

fore, a solution of cobalt chloride is added directly to it, by which means the oxide of cobalt required for the reaction is formed.

¹⁸ It must be remarked that in all the above-cited reactions, the formation of oxygen may be prevented by the admixture of substances capable of combining with it—for example, charcoal, many carbon (organic) compounds, sulphur, phosphorus, and various lower oxidation products, &c. These substances absorb the oxygen evolved, combine with it, and a compound containing oxygen, but not free oxygen, is formed. Thus, if a mixture of potassium chlorate and charcoal be heated, no oxygen is obtained, but an explosion takes place from the rapid formation of gases resulting from the combination of the oxygen of the potassium chlorate with the charcoal.

The oxygen obtained by any of the above-described methods is rarely pure. It generally contains aqueous vapour, from which it may be freed by passing it over calcium chloride, which retains the water. Besides this, the oxygen nearly always contains traces of carbonic anhydride, and very often small traces of chlorine. The oxygen may be freed from these impurities by passing it through a solution of caustic potash. This is done in Woulfe's bottles, as was described in the last chapter. If the potassium chlorate be dry and pure, it gives almost pure oxygen. However, if the oxygen be designed for respiration in cases of sickness, it should be washed by passing it through a solution of caustic alkali and through water. The best way to obtain pure oxygen directly, is to take potassium perchlorate (KClO_4), which can be well purified and then evolves pure oxygen on heating.

¹⁹ Concerning the absolute boiling point, critical pressure, and on the critical state in general, see Chap II. Notes 29 and 34.

²⁰ Judging from what has been said in Note 34 of the last chapter, and also from the results of direct observation, it is evident that all substances in a critical state have a large coefficient of expansion, and that they are very compressible.

²¹ As water consists of 1 volume of oxygen and 2 volumes of hydrogen, and contains 16 parts by weight of oxygen per 2 parts by weight of hydrogen, it therefore already follows from this, that oxygen is 16 times denser than hydrogen. Conversely, the com-

In its chemical properties oxygen is remarkable from the fact that it very easily—and, in a chemical sense, vigorously—reacts on a number of substances, forming oxygen compounds. However, only a few substances and mixtures of substances (for example, phosphorus, copper with ammonia, decomposing organic matter, aldehyde, pyrogallol with an alkali, &c.) combine directly with oxygen at the ordinary temperature, whilst many substances easily combine with oxygen at a red heat, and often this combination presents a rapid chemical reaction accompanied by the evolution of a large quantity of heat. Every reaction which takes place rapidly, if it be accompanied by so great an evolution of heat as to produce incandescence, is termed *combustion*. Thus combustion ensues when many metals are plunged into chlorine, or oxide of sodium or barium into carbonic anhydride, or when a spark falls on gunpowder. A great many substances are combustible in oxygen, and, owing to its presence, in air also. In order to start combustion it is generally necessary²² that the combustible substance should be brought to a state of incandescence. When once started—*i.e.*, when once the incandescent portion of the substance begins to combine with oxygen—then combustion will proceed uninterruptedly until either all the combustible substance or all the oxygen is consumed. The continuation of the process does not require the aid of fresh external heat, because sufficient heat²³ is evolved to raise the temperature of the remaining parts of the combustible substance to the required

position of water by weight may be deduced from the densities of hydrogen and oxygen, and the volumetric composition of water. This kind of mutual and opposite correction is a method which strengthens the practical data of the exact sciences, whose conclusions require, above all things, the greatest possible exactitude and variety of corrections.

It must be observed that the specific heat of oxygen at constant pressure is 0.2175, consequently it is to the specific heat of hydrogen (3.409) as 1 is to 15.6. Hence, the specific heats are inversely proportional to the weights of equal volumes. This signifies that equal volumes of both gases have (nearly) equal specific heats—that is, they require an equal quantity of heat for raising their temperature by 1°. We shall afterwards consider the specific heat of different substances more fully, and we will not, therefore, linger over it at present.

Oxygen, like the majority of difficulty-liquefiable gases, is but slightly soluble in water and other liquids. At the ordinary temperature, 100 volumes of water dissolve about 3 volumes of oxygen, or more exactly, at 0° 4.1 vols., at 10° 3.3, and at 20° 3.0 (measuring the volumes at the same temperature as the water). From this it is evident that water standing in air must absorb—*i.e.*, dissolve—oxygen. This oxygen serves for the respiration of fishes. Fishes cannot exist in boiled water, because it does not contain the oxygen necessary for their respiration (*see* Chap. I.).

²² Certain substances (with which we shall afterwards become acquainted), however, inflame of themselves in air; for example, impure phosphuretted hydrogen, silicon, hydride, zinc ethyl, and pyrophorus (very finely divided iron, &c.).

²³ If so little heat is evolved that the adjacent parts are not heated to the temperature of combustion, then combustion will cease.

degree. Examples of this are familiar to all from every-day experience. Combustion proceeds in oxygen with greater rapidity, and is accompanied by a more powerful incandescence, than in ordinary air. This may be demonstrated by a number of very convincing experiments. If a piece of charcoal, attached to a wire and previously brought to red-heat, be plunged into a flask full of oxygen, it rapidly burns at a white heat—*i.e.*, it combines with the oxygen, forming a gaseous product of combustion called carbonic anhydride, or carbonic acid gas. This is the same gas that is evolved in the act of respiration, for charcoal is one of the substances which is obtained by the decomposition of all organic substances which contain it, and in the process of respiration part of the




FIG. 29.—Mode of burning sulphur, phosphorus, sodium, &c., in oxygen.

constituents of the body, so to speak, slowly burn. If a piece of burning sulphur be laid on a small cup attached to a wire and be placed in a flask full of oxygen, then the sulphur, which burns in air with a very feeble flame, burns in the oxygen with a violet flame, which, although pale, is much larger than in air. If the sulphur be exchanged for a piece of phosphorus,²⁴ then, unless the phosphorus be heated, it combines very slowly with the oxygen; but, if heated, although on only one spot, it burns with a very brilliant white flame, which is unbearable to the sight. In order to heat the phosphorus

inside the flask, the most simple way is to bring a red-hot wire into contact with it. Before the charcoal can burn, it must be brought to a state of incandescence. Sulphur also will not burn under 100°, whilst phosphorus inflames at 40°. Phosphorus which has been already lighted in air cannot so well be introduced into the flask, because it burns very rapidly and with a large flame in air. If a small lump of metallic *sodium* be put in a small cup made of lime,²⁵ melted, and inflamed,²⁶ then it burns very feebly in air. But if burning sodium be immersed in oxygen, the

²⁴ The phosphorus must be dry; it is usually kept in water, as it oxidises in air. It should be cut under water, as otherwise the freshly-cut surface oxidises. It must be dried carefully and quickly by wrapping it in blotting-paper. If damp, it splutters in burning. A small piece should be taken, as otherwise the iron spoon will melt. In this and the other experiments on combustion, water should be poured over the bottom of the vessel containing the oxygen, to prevent it from cracking. The cork closing the vessel should not fit tightly, otherwise it may fly off with the spoon and burning substance, owing to the expansion due to the heat of the combustion.

²⁵ An iron cup will melt with sodium in oxygen.

²⁶ In order to rapidly heat the lime crucible with the sodium, they are heated in the flame of a blow-pipe described in Chap. VIII.

combustion is invigorated and is accompanied by a brighter yellow flame. Metallic *magnesium*, which burns brightly in air, continues to burn with still greater vigour in oxygen, forming a white powder, which is a compound of magnesium with oxygen (magnesium oxide; *magnesia*). A strip of *iron* or steel does not burn in air, but an iron wire or steel spring may be easily burnt in oxygen. A much larger piece of iron might naturally be burnt if it only were convenient to heat it to the required degree.²⁷ The combustion of steel or iron in oxygen is not accompanied by a flame, but sparks of oxide fly in all directions from the burning portions of the iron.²⁸

In order to demonstrate by experiment the *combustion of hydrogen* in oxygen, a gas-conducting tube, bent so as to form a convenient jet, is led from the vessel evolving hydrogen. The hydrogen is first set light to in air, and then the gas-conducting tube is let down into a flask containing oxygen. The combustion in oxygen will be similar to that in air; the flame remains pale, notwithstanding the fact that its temperature rises considerably. It is instructive to remark that oxygen may burn in hydrogen, just as hydrogen in oxygen. In order to show the combustion of oxygen in hydrogen, a tube bent vertically upwards and ending in a fine orifice is attached to the stop-cock of a gas holder full of oxygen. Two wires, placed at such a distance from



FIG. 30.—Mode of burning a steel spring in oxygen.

²⁷ In order to burn a watch spring, a piece of tinder (or paper soaked in a solution of nitre, and dried) is attached to one end. The tinder is lighted, and the spring is then plunged into the oxygen. The burning tinder heats the end of the spring, the heated part burns, and in so doing heats the further portions of the spring, which thus entirely burns if enough oxygen is present.

²⁸ The sparks of rust are produced by reason of the volume of the oxide of iron being nearly twice that of the volume of the iron, and as the heat evolved is not sufficient to entirely melt the oxide or the iron, the particles must be torn off and fly about. Similar sparks are formed in the combustion of iron, in other cases also. We saw the combustion of iron filings in the Introduction. In the welding of iron small iron splinters fly off in all directions and burn in the air, as is seen from the fact that whilst flying through the air they remain red hot, and also because, on cooling, they are seen to be no longer iron, but a compound of it with oxygen. The same thing takes place when the hammer of a gun strikes against the flint. Small scales of steel are heated by the friction, and glow and burn in the air. The combustion of iron is still better seen by taking it as a very fine powder, such as is obtained by the decomposition of certain of its compounds—for instance, by heating Prussian blue, or by the reduction of its compounds with oxygen by hydrogen; when this fine powder is strewn in air, it burns by itself, even without being previously heated (it forms a pyrophorus). This obviously depends on the fact that the powder of iron presents a larger surface of contact with air than an equal weight in a compact form.

each other as to allow the passage of a constant series of sparks from a Ruhmkorff's coil, are fixed in front of the orifice of the tube. This is in order to ignite the oxygen, which may also be done by attaching tinder round the orifice, and burning it. When the wires are arranged about the orifice of the tube, and a series of sparks passes between them, then an inverted (because of the lightness of the hydrogen) jar full of hydrogen is placed over the gas-conducting tube. When the jar covers the orifice of the gas-conducting tube (and not before, as otherwise an explosion might take place) the cock of the gasometer is opened, and the oxygen flows into the hydrogen and is set light to by the sparks. The flame obtained is similar to that formed by the combustion of hydrogen in oxygen.²⁹ From this it is evident that the flame is the locality where the oxygen combines with the hydrogen, therefore a flame of burning oxygen can be obtained as well as a flame of burning hydrogen.

If, instead of hydrogen, any other combustible gas be taken—for example, ordinary coal gas—then the phenomenon of combustion will be exactly the same, only a bright flame will be obtained, and the products of combustion will be different. However, as lighting gas contains a considerable amount of free and combined hydrogen, it will also form a considerable quantity of water in its combustion.

If hydrogen be mixed with oxygen in the proportion in which they form water—*i.e.*, if two volumes of hydrogen be taken for each volume of oxygen—then the mixture will be the same as that obtained by the decomposition of water by a galvanic current—detonating gas.

We have already mentioned in the last chapter that the combination of these gases, or their explosion, may be brought about by the action of

²⁹ The experiment may be conducted without the wires, if the hydrogen be lighted in the orifice of a cylinder, and at the same time the cylinder be brought over the end of a gas-conducting tube connected with a gas holder containing oxygen. Thomsen's method may be adopted for a lecture experiment. Two glass tubes, with platinum ends, are passed through orifices, about 1-1½ centimetres apart, in a cork. One tube is connected with a gas-holder containing oxygen, and the other with a gas-holder full of hydrogen. Having turned on the gases, the hydrogen is lighted, and a common lamp glass, tapering towards the top, is placed over the cork. The hydrogen continues to burn inside the lamp glass, at the expense of the oxygen. If the current of oxygen be then little by little decreased, a point is reached when, owing to the insufficient supply of oxygen, the flame of the hydrogen increases in size, disappears for several moments, and then reappears at the tube supplying the oxygen. If the flow of oxygen be again increased, the flame reappears at the hydrogen tube. Thus the flame may be made to appear at one or the other tube at will, only the increase or decrease of the current of gas must be by degrees and not suddenly. Further, air may be taken instead of oxygen, and ordinary coal-gas instead of hydrogen, and it will then be shown how air burns in an atmosphere of coal-gas, and it can easily be proved that the lamp glass is full of a gas combustible in air, because it may be lighted at the top.

an electric spark, because the spark heats the space through which it passes, and acts consequently in a manner similar to ignition by means of contact with an incandescent or burning substance. In fact, instead of a spark a fine wire simply may be taken, and an electric current passed through it to bring it to a state of incandescence; in this case there will be no sparks, but the gases will inflame if the wire be fine enough to become red hot by the passage of the current. Cavendish made this experiment on the ignition of detonating gas, at the end of the last century, in the apparatus shown in fig. 31. Ignition by the aid of the electric spark is convenient, for the reason that it may then be brought about in a closed vessel, and hence chemists still employ this method when it is required to ignite a mixture of oxygen with a combustible gas in a closed vessel. For this purpose they now, especially since Bunsen's time,³⁰ employ an *eudiometer*.




FIG. 31. Cavendish's apparatus for exploding detonating gas. The bell jar standing in the bath is filled with a mixture of two volumes of hydrogen and one volume of oxygen, and the thick glass vessel A is then screwed into it. The air is first pumped out of this vessel, so that when the stop-cock C is opened, it becomes filled with detonating gas. The stop-cock is then re-closed, and the explosion produced by means of a spark from a Leyden jar. After the explosion has taken place the stop-cock is again opened, and the water rises into the vessel A.

It consists of a thick glass tube graduated along its length in millimetres (for indicating the height of the mercury column), and calibrated for a definite volume (weight of mercury). Two platinum wires are fused into the upper closed end of the tube, as shown in fig. 32. They must be hermetically sealed into the tube, so that there be no aperture left between them and the glass.³¹

³⁰ Now, a great many other different forms of apparatus, sometimes designed for special purposes, are employed in the laboratory for the investigation of gases. Detailed descriptions of the methods of gas analysis, and of the apparatus employed, must be looked for in works on analytical and applied chemistry.

³¹ In order to test this, the eudiometer is filled with mercury, and its open end inverted into mercury. If there be the smallest orifice at the wires, the external air will enter into the cylinder and the mercury will fall, although not rapidly if the orifice be very fine.

By the aid of the eudiometer we may not only determine the volumetric composition of water,³² and the quantitative contents of oxygen



³² The eudiometer is used for determining the composition of combustible gases. A detailed account of *gas analysis* would be out of place in this work (see Note 30), but, as an example, we will give a short description of the determination of the composition of water by the eudiometer.

Pure and dry oxygen is first introduced into the eudiometer. When the eudiometer and the gas in it acquire the temperature of the surrounding atmosphere—which is recognised by the fact of the meniscus of the mercury not altering its position during a long period of time—then the heights at which the mercury stands in the eudiometer and in the bath are observed. The difference (in millimetres) gives the height of the column of mercury in the eudiometer. It must be reduced to the height at which the mercury would stand at 0° and deducted from the atmospheric pressure, in order to find the pressure under which the oxygen is measured (see Chap. I. Note 29). The height of the mercury also shows the volume of the oxygen. The temperature of the surrounding atmosphere and the height of the barometric column must also be observed, in order to know the temperature of the oxygen and the atmospheric pressure. When the volume of the oxygen has been measured, pure and dry hydrogen is introduced into the eudiometer, and the volume of the gases in the eudiometer again measured. They are then exploded. This is done by a Leyden jar, whose outer coating is connected by a chain with one wire, so that a spark passes when the other wire, fused into the eudiometer, is touched by the terminal of the jar. Or else an electrophorus is used, or, better still, a Ruhmkorff's coil, which has the advantage of working equally well in damp or dry air, whilst a Leyden jar or electrical machine does not act in damp weather. Further, it is necessary to close the lower orifice of the eudiometer before the explosion (for this purpose the eudiometer, which is fixed in a stand, is firmly pressed down from above on to a piece of india-rubber placed at the bottom of the bath), as otherwise the mercury and gas would be thrown from the apparatus by the explosion. It must also be remarked that to ensure complete combustion the proportion between the volumes of oxygen and hydrogen must not exceed twelve volumes of hydrogen to one volume of oxygen, or fifteen volumes of oxygen to one volume of hydrogen, because no explosion will take place if one of the gases be in great excess. It is best to take a mixture of one volume of hydrogen with several volumes of oxygen. The combustion will then be complete. It is

FIG. 32.—evident that water is formed, and that the volume (or tension) is diminished, so that on opening the end of the eudiometer the mercury will rise in it.

But the tension of the aqueous vapour is now added to the tension of the gas remaining after the explosion. This must be taken into account (Chap. I. Note 1). If there remain but little gas, the water which is formed will be sufficient for its saturation with aqueous vapour. This may be learnt from the fact that drops of water are visible on the sides of the eudiometer after the mercury has risen in it. If there be none, a certain quantity of water must be introduced into the eudiometer. Then the number of millimetres expressing the pressure of the vapour corresponding with the temperature of the experiment must be subtracted from the atmospheric pressure at which the remaining gas is measured, otherwise the result will be inaccurate.

This is essentially the method of the determination of the composition of water which was made for the first time by Gay-Lussac¹ and Humboldt with sufficient accuracy. Their determinations led them to the conclusion that water consists of two volumes of hydrogen and one volume of oxygen. Every time they took a greater quantity of oxygen, the gas remaining after the explosion was oxygen. When they took an excess of hydrogen, the remaining gas was hydrogen; and when the oxygen and hydrogen were taken in

in air,³³ but also make a number of experiments explaining the phenomenon of combustion.

Thus, for example, it may be demonstrated, by the aid of the eudiometer, that for the ignition of detonating gas a *definite temperature* is required. If the temperature be below that required, combination will not take place, but if at any spot within the tube it rises to the temperature of inflammation, then combination will ensue at that spot, and evolve enough heat for the ignition of the adjacent portions of the detonating mixture. If to 1 volume of detonating gas there be added 10 volumes of oxygen, or 4 volumes of hydrogen, or 3 volumes of carbonic anhydride, then we shall not obtain an explosion by passing a spark through the diluted mixture. This depends on the fact that the temperature falls with the dilution of the detonating gas by another gas, because the heat evolved by the combination of the small quantity of hydrogen and oxygen brought to incandescence by the spark is not only transmitted to the water proceeding from the combination, but also to the foreign substance mixed with the detonating gas.³⁴ The necessity of a definite temperature for the ignition of detonating gas is also seen from the fact that pure detonating gas explodes in the presence of a red-hot iron wire, or of charcoal so feebly incandescent as to be hardly distinguishable by day light, but with a lower degree of incandescence there is not any explosion. It may also be brought about by rapid compression, when, as is known, heat is evolved.³⁵ Experiments made in the eudiometer showed that the ignition of detonating gas takes place at a temperature between 450° and 500°.³⁶

exactly the above proportion neither one nor the other remained. The composition of water was thus definitely confirmed.

³³ Concerning this application of the eudiometer, see the chapter on nitrogen.

³⁴ Thus $\frac{1}{2}$ volume of carbonic oxide, an equal volume of marsh gas, two volumes of hydrogen chloride or of ammonia, and six volumes of nitrogen or twelve volumes of air added to one volume of detonating gas, prevent its explosion.

³⁵ If the compression be brought about slowly, so that the heat evolved succeeds in passing to the surrounding space, then the combination of the oxygen and hydrogen does not take place, even when the mixture is compressed by 150 times; for the gases are not heated. If paper soaked with a solution of platinum (in aqua regia) and sal ammoniac be burnt, then the ash obtained contains very finely-divided platinum, and in this form it is best fitted for setting light to hydrogen and detonating gas. Platinum wire requires to be heated, but platinum in so finely divided a state as it occurs in this ash inflames hydrogen, even at -20°. Many other metals, such as palladium, iridium, and gold, act with a slight rise of temperature, like platinum; charcoal, like the majority of finely divided substances, inflames detonating gas at 350°, but mercury, at its boiling point, does not inflame detonating gas. All data of this kind show that the explosion of detonating gas presents one of the many cases of contact phenomena.

³⁶ From the very beginning of the diffusion of the idea of dissociation, it might have been imagined that reversible reactions of combination (the formation of H_2 and O belongs to this number) start at the same temperature as that at which dissociation begins. And so it is in many cases, but not always, as may be seen from the facts (1) that

The combination of hydrogen with oxygen is accompanied by the evolution of a very considerable amount of heat; according to the determinations of *Favre and Silberman*,³⁷ 1 part by weight of hydrogen in forming water evolves 34462 units of heat. Many of the most recent determinations are very near this figure, so that it may be taken that in the formation of 18 parts of water (H_2O) there are evolved 69 major calories, or 69000 units of heat.³⁸ *If the specific heat*

at 450–560°, when detonating gas explodes, the density of aqueous vapour not only does not vary (and it hardly varies at higher temperatures, probably because the amount of the products of dissociation is small), but there are not, as far as is yet known, any traces of dissociation; (2) that under the influence of contact the temperature at which combination takes place falls even to the ordinary temperature, when water and similar compounds naturally are not dissociated and, judging from the data communicated by D. P. Konvaloff (Introduction, Note 39) and others, it is impossible to escape the phenomena of contact; all vessels, whether of metal or glass, show the same influence as spongy platinum although to a much less degree. The phenomena of contact, judging from the mass of the data referring to it, must be especially sensitive in reactions which are powerfully exothermal, and the explosion of detonating gas is of this kind.

³⁷ The amount of heat evolved in the combustion of a known weight (for instance, 1 gram) of a given substance is determined by the rise in temperature of water, to which the whole of the heat evolved in the combustion is transmitted. A *calorimeter*, for example, that shown in fig. 33, is employed for this purpose. It consists of a thin (in order that it may absorb less heat), polished (that it should transmit a minimum of heat) metallic vessel, surrounded by down (c), or some other bad conductor of heat, and an outer metallic vessel. This is necessary in order that the least possible amount of heat should be lost from the vessels; nevertheless, there is always a certain loss, whose magnitude

is determined by preliminary experiment (by taking warm water, and determining its fall in temperature after a definite period of time) as a correction for the results of observations. The water to which the heat of the burning substance is transmitted is poured into the vessel. The stirrer *g* allows of all the layers of water being brought to an equal temperature, and the thermometer serves for the determination of the temperature of the water. The heat evolved passes, naturally, not to the water only, but to all the parts of the apparatus. The quantity of water corresponding with the whole amount of those objects (the vessels, tubes, &c.) to which the heat is transmitted is previously determined, and in this manner another most important correction is made in the calorimetric determinations. The combustion itself is carried on in the vessel *a*. The ignited substance is introduced through the tube at the top, which closes tightly. In fig. 33 the apparatus is arranged for the combustion of a gas, introduced by a tube. The oxygen required for the combustion is led into *a* by the tube *e*, and the products of combustion either remain in the vessel *a* (if liquid or solid), or escape by the tube *f* into an apparatus in which their quantity and properties can easily




FIG. 33.—Favre and Silberman's calorimeter for determining the heat evolved in combustion.

be determined. Thus the heat evolved in combustion passes to the walls of the vessel *a*, and to the gases which are formed in it, and these transmit it to the water of the calorimeter.

³⁸ This quantity of heat corresponds with the formation of liquid water at the ordinary

of aqueous vapour (0.48) remained constant from the ordinary temperature to that at which the combustion of detonating gas takes place (but

temperature from detonating gas at the same temperature. If the water be as vapour the heat evolved = 58 major calories; if as ice = 79.4 major calories. A portion of this heat is due to the fact that 1 vol. of hydrogen and $\frac{1}{2}$ vol. of oxygen give 1 vol. of aqueous vapour—that is to say, contraction ensues—and this evolves heat. This quantity of heat may be calculated, but it cannot be said how much is expended in the tearing apart of the atoms of oxygen from each other, and therefore, strictly speaking, we do not know the quantity of heat which is evolved in the combination of hydrogen with oxygen; although the number of units of heat evolved in the combustion of detonating gas is accurately known.

The construction of the calorimeter and even the method of determination vary considerably in different cases. The greatest number of calorimetric determinations were made by Berthelot and Thomsen. They are given in their works *Essai de mécanique chimique fondée sur la thermochimie*, by M. Berthelot, 1879 (2 vols.), and *thermochemische Untersuchungen*, by J. Thomsen, 1886 (4 vols.). The student must refer to works on theoretical and physical chemistry for a description of the elements and methods of *thermochemistry*, into the details of which it is impossible to enter in this work, all the more so because, as has been shown of late, both the theoretical side of this subject and its practical methods are still in an elementary state of development, and must be subjected to improvement in many aspects before thermochemical study can be of that enormous utility to chemical mechanics which was expected from it at the time of the appearance of the first researches in its province. One of the originators of thermochemistry was a member of the St. Petersburg Academy of Sciences, Hess. Since 1870 a mass of researches have appeared in this province of chemistry, especially in France and Germany, after the leading works of the French Academician, Berthelot, and the Copenhagen professor, Thomsen. Among Russians, Beketoff, Lugmin, Cheltzoff, Chroustchoff, and others are known by their thermochemical researches. The present epoch of thermochemistry, in the absence of a steadfast foundation (and the principle of maximum work cannot be counted as such), must be considered rather as a collective one, wherein the material of facts is amassed, and the first consequences arising from them are noticed. In my opinion three essential circumstances prevent the possibility of extracting any exact consequences of importance to chemical mechanics, from the amassed and already immense store of thermochemical data: (1) The majority of the determinations are conducted in weak aqueous solutions, and, the heat of solution being known, are referred to the substances in solution; yet there is much (Chap. I.) which forces one to consider that in solution water does not play the simple part of a diluting medium, but of itself acts independently in a chemical sense on the substance dissolved. (2) The other chief portion of thermochemical determinations is conducted by the ignition of substances at high temperatures, and as yet we do not know the specific heat of many substances at these temperatures. (3) Physical and mechanical changes (decrease of volume, diffusion, and others) inevitably proceed side by side with chemical changes, and for the present it is impossible, in a number of cases, to distinguish the thermal effect of the one and the other kind of change. It is evident that the one kind of change (chemical) is essentially inseparable and incomprehensible without the other (mechanical and physical); and therefore it seems to me that thermochemical data will only acquire their true meaning when the connection between the phenomena of both kinds (on the one hand chemical and atomic, and on the other hand mechanical and molecular or between entire masses) is explained more clearly and fully than is the case at present. As there is no doubt that the simple mechanical contact, or the action of heat alone, on substances sometimes causes an evident and always a latent (incipient) chemical change—that is, a different distribution or movement of the atoms in the molecules—it follows that purely chemical phenomena are inseparable from physical and mechanical phenomena. This is because the atomic relations forming the essence of the chemical relations of a substance are not observable, and at present are incomprehensible, without the molecular relations

most probably it increases), were the combustion concentrated at one point³⁹ (but it occurs as a flame), were there no loss from radiation and heat conduction, and, chiefly, *did dissociation not take place*—that is, did not a state of equilibrium between the hydrogen, oxygen, and water come about—*then it would be possible to calculate the temperature of the flame of detonating gas*. It would then be 10000° .⁴⁰ In reality it is very much lower, but it is nevertheless higher than the temperature attained in furnaces and flames, and reaches up to 2000° . The explosion of detonating gas is explained by this high temperature, because the aqueous vapour formed must occupy a volume at least 5 times greater than that occupied by the detonating gas at the ordinary temperature. Detonating gas emits a sound, not only as a consequence of the commotion which occurs from the rapid expansion of the heated vapour, but also because it is immediately followed by a cooling effect, the conversion of the vapour into water, and a rapid contraction.⁴¹

forming the essence of the physical relations, and even without the relations of the entire masses of molecules evincing themselves in purely mechanical relations, inasmuch as an individual atom is something unreal and fantastic. A mechanical change may be imagined without a physical change, and a physical without a chemical change (although such a representation would be artificial), but it is impossible to imagine a chemical change without a physical and mechanical one, for without them we should not perceive it, and through them we attain it. There was a time when the province of physics embraced the whole of chemistry and mechanics. In the present day they have been developed independently and been isolated from each other, but in the future a fresh conjunction is imminent, and is heralded by the laws of the conservation of matter and of energy.

³⁹ The flame, or locality where the combustion of gases and vapours is accomplished, is a complex phenomenon, 'an entire factory,' as Faraday says, and therefore we will consider flame in some detail in one of the following notes.

⁴⁰ If 34500 units of heat are evolved in the combustion of 1 part of hydrogen, and this heat is transmitted to the resulting 9 parts by weight of aqueous vapour, then we find that, taking the specific heat of the latter as 0.475 , each unit of heat raises the temperature of 1 part by weight of aqueous vapour 2.1° and 9 parts by weight ($2.1 \div 9$) 0.23° ; hence the 34500 units of heat raise its temperature 7935° . If detonating gas is converted into water in a closed space, then the aqueous vapour formed cannot expand, and therefore, in calculating the temperature of combustion, the specific heat at a constant volume must be taken into consideration; it is 0.36 for aqueous vapour. This figure gives a still higher temperature for the flame. In reality it is much lower, but the results given by different observers are very contradictory (from 1700° to 2400°), the discrepancies depending on the fact that flames of different sizes are cooled by radiation to a different degree, but mainly on the fact that the methods and apparatus (pyrometers) for the determination of high temperatures, although they enable relative changes of temperature to be judged, are of little use for determining their absolute magnitude. By taking the temperature of the flame of detonating gas as 2000° , I give, I think, the average of the most trustworthy determinations.

⁴¹ It is evident that not only hydrogen, but every other combustible gas, will give an explosive mixture with oxygen. For this reason coal-gas mixed with air explodes when the mixture is ignited. The pressure obtained in the explosions serves as the *motive power of gas engines*. In this case advantage is taken, not only of the pressure produced by the explosion, but also of that contraction which takes place after the explosion. On this is based the construction of several motors, of which Lenoir's was

Mixtures of hydrogen and of various other gases with oxygen are taken advantage of for obtaining high temperatures. By the aid of such high temperatures metals like platinum may be melted on a large scale, which cannot be done in furnaces heated with charcoal and fed by a current of air. The burner, shown in fig. 34, is constructed for the application of detonating gas to the purpose. It consists of two brass tubes, one fixed inside the other, as shown in the drawing. The internal central tube C C conducts oxygen, and the outside, enveloping, tube E' E' conducts hydrogen. Previous to their egress the gases do not mix together, so that there can be no explosion inside the apparatus. When this burner is in use C is connected with a gasholder containing oxygen, and E with a gas holder containing hydrogen (or sometimes coal-gas). The flow of the gases can be easily regulated by the stop-cocks O H. The flame is shortest and evolves the greatest heat when the gases burning are in the proportion of 1 volume of oxygen to 2 volumes of hydrogen. The degree of heat may be easily judged from the fact that a thin platinum wire placed in the flame easily melts. By placing the burner in the orifice of a hollow piece of lime, a crucible A B is obtained in which platinum may be easily melted, even in large quantities if the current of oxygen and hydrogen be sufficiently great (Deville). The flame of detonating gas may also be used for illuminating purposes. It is by itself very pale, but owing to its high temperature it may serve for rendering infusible objects incandescent, and at the very high temperature produced by the detonating gas the incandescent substance gives a most intense light. For this purpose lime, magnesia, or oxide of zirconium are used, as they are not fusible at the very high temperature evolved by the detonating gas. A small cylinder of lime placed in the flame of detonating gas, if regulated to the required point, gives a very brilliant white




FIG. 34. Safety burner for detonating gas, described in text.

formerly, and Otto's is now, the best known. The explosion is usually produced by coal-gas and air, but of late the vapours of combustible liquids (kerosene, benzene) are also being employed in place of gas (Chap. IX.). In Lenoir's engine a mixture of coal-gas and air is ignited by means of sparks from a Ruhmkorff's coil, but in the most recent machines the gases are ignited by the direct action of a gas jet.

light, which was at one time proposed for illuminating lighthouses. At present in the majority of cases electric light, owing to its constancy and other advantages, has replaced it for this purpose. The light produced by lime in detonating gas is called the *Drummond light* or *limelight*.

The above cases form examples of the combustion of elements in oxygen, but exactly similar phenomena are observed in the *combustion of compounds*. So, for instance, the solid, colourless, shiny substance, naphthalene, $C_{10}H_8$, burns in air with a smoky flame, whilst in oxygen it continues to burn with a very brilliant flame. Alcohol, oil, and other substances burn brilliantly in oxygen on conducting the oxygen by a tube to the flame of lamps burning these substances. A high temperature is thus evolved, which is sometimes taken advantage of in chemical practice.

In order to understand why combustion in oxygen proceeds more rapidly, and is accompanied by a more intense heat effect, than combustion in air, it must be recollected that air is oxygen diluted with nitrogen, which does not support combustion, and therefore fewer particles of oxygen flow to the surface of a substance burning in air than when burning in pure oxygen. The chief reason of the intensity of combustion in oxygen is the high temperature acquired by the substance burning in it. Let us consider as an example the combustion of sulphur in air and in oxygen. If 1 gram of sulphur burns in air or oxygen it evolves in either case 2250 units of heat—*i.e.*, evolves sufficient heat for heating 2250 grams of water $1^\circ C$. This heat is first of all transmitted to the sulphurous anhydride, SO_2 , formed by the combination of sulphur with oxygen. In its combustion 1 gram of sulphur forms 2 grams of sulphurous anhydride—*i.e.*, the sulphur combines with 1 gram of oxygen. In order that 1 gram of sulphur should have access to 1 gram of oxygen in air, it is necessary that 3.4 grams of nitrogen should simultaneously reach the sulphur, because air contains seventy-seven parts of nitrogen (by weight) per twenty-three parts of oxygen. Thus in the combustion of 1 gram of sulphur, the 2250 units of heat are transmitted to 2 grams of sulphurous oxide and to at least 3.4 grams of nitrogen. As 0.155 units of heat are required to raise 1 gram of sulphurous anhydride $1^\circ C$., therefore 2 grams require 0.31 units. So also 3.4 grams of nitrogen require 3.4×0.244 or 0.83 units of heat, and therefore in order to raise both gases $1^\circ C$. $0.31 + 0.83$ or 1.14 units of heat are required, but as the combustion of the sulphur evolves 2,250 units of heat, therefore the gases might be heated (if their specific heats remained constant) to $\frac{2250}{1.14}$ or $1974^\circ C$. That

is, the maximum possible temperature of the flame of the sulphur burning in air will be 1974° C. In the combustion of the sulphur in oxygen the heat evolved (2250 units) can only pass to the 2 grams of sulphurous anhydride, and therefore the highest possible temperature of the flame of the sulphur in oxygen will be $= \frac{2250}{0.31}$ or 7258° .

In the same manner it may be calculated that the temperature of charcoal burning in air cannot exceed 2700° , while in oxygen it may attain 10100° C. For this reason the temperature in oxygen will always be higher than in air, although (judging from what has been said respecting detonating gas) neither one nor the other temperature will nearly approach the theoretical quantities.

Among the phenomena accompanying the combustion of certain substances, the *phenomenon of flame* attracts attention. Sulphur, phosphorus, sodium, magnesium, naphthalene, &c., burn like hydrogen with a flame, whilst in the combustion of other substances no flame is observed, as, for instance, in the combustion of iron and of charcoal. The appearance of flame depends on the capacity of the combustible substance to yield gases or vapours at the temperature of combustion. At the temperature of combustion, sulphur, phosphorus, sodium, and naphthalene pass into vapour, whilst wood, alcohol, oil, &c., are decomposed into gaseous and vaporous substances. The combustion of gases and vapours forms flames, and therefore *a flame is composed of the hot and incandescent gases and vapours produced by combustion*. It may be easily proved that the flames of such non-volatile substances as wood contain volatile and combustible substances formed from them, by placing a tube in the flame and drawing air from it with an aspirator. Besides the products of combustion, combustible gases and liquids, previously in the flame as vapours, collect in the aspirator. For this experiment to succeed—*i.e.*, in order to really extract combustible gases and vapours from the flame—it is necessary that the suction tube should be placed *inside* the flame. The combustible gases and vapours can only remain unburnt inside the flame, for at the surface of the flame they come into contact with the oxygen of the air and burn.⁴² Flames are of different degrees of

⁴² Faraday proved this by a very convincing experiment on a candle flame. If one arm of a bent glass tube be placed in a candle flame above the wick in the dark portion of the flame, then the products of the partial combustion of the stearin will pass up the tube, condense in the other arm, and collect in a flask placed under it (fig. 35) as heavy white fumes which burn when lighted. If the tube be raised into the upper luminous portion of the flame, then a dense black smoke which will not inflame accumulates in the flask. Lastly, if the tube be let down until it touches the wick, then little but stearic acid condenses in the flask.

brilliancy, according to whether *solid* incandescent particles occur in the combustible gas or vapour, or not. Incandescent gases and vapours emit but little light by themselves, and therefore give a paler




FIG. 35.—Faraday's experiment for investigating the different parts of a candle flame.

flame.⁴³ If a flame does not contain solid particles it is transparent, pale, and emits but little light.⁴⁴ The flames of burning alcohol, sulphur, and hydrogen are of this kind. A pale flame may be rendered luminous by placing fine particles of solid matter in it. Thus, if a very fine platinum wire be placed in the pale flame of burning alcohol—or, better still, of hydrogen—then the flame emits a bright light. This is still better seen by sifting the powder of an incom-
bustible substance, such as fine sand, into the flame, or by placing a bunch of asbestos threads in it. Every brilliant flame always contains some

kind of solid particles, or at least some very dense vapour. The flame of sodium burning in oxygen has a brilliant yellow colour, from the presence of particles of solid sodium oxide. The flame of magnesium is brilliant from the fact that in burning it forms solid magnesia, which becomes white hot, and similarly the brilliancy of the Drummond light is due to the heat of the flame raising the solid non-volatile lime to a state of incandescence. The flames of a candle, wood, and similar substances are brilliant, because they contain particles of charcoal or soot. It is not the flame itself which is luminous, but the incandescent soot it contains. These particles of charcoal which occur in flames may be easily observed by introducing a cold object, like a knife, into the

⁴³ All transparent substances which transmit light with great ease (that is, which absorb but little light) are but little luminous when heated; so also substances which absorb but few heat rays, when heated transmit few rays of heat.

⁴⁴ There is, however, no doubt but that very heavy dense vapours or gases under pressure (according to the experiments of Frankland) are luminous when heated, because, as they become denser they approach a liquid or solid state. Thus detonating gas when exploded under pressure is brightly luminous.

flame.⁴⁵ The particles of charcoal burn at the outer surface of the flame if the supply of air be sufficient, but if the supply of air—that is, of oxygen—be insufficient for their combustion the flame smokes, because these unconsumed particles of charcoal are carried off by the current of air.⁴⁶

⁴⁵ If hydrogen gas be passed through a volatile liquid hydrocarbon—for instance, through benzene (the benzene may be poured directly into the vessel in which hydrogen is generated)—then its vapour burns with the hydrogen and gives a very bright flame, because the resultant particles of carbon (soot) are powerfully ignited. Benzene, or platinum gauze, introduced into a hydrogen flame may be employed for illuminating purposes.

⁴⁶ In *flames* the separate parts may be distinguished with more or less distinctness. That portion of the flame whither the combustible vapours or gases flow, is not luminous because its temperature is still too low for the process of combustion to take place in it. This is the space which in a candle surrounds the wick, or in a gas jet is immediately above the orifice from which the gas escapes. In a candle the combustible vapours and gases which are formed by the action of heat on the melted tallow or stearin, rise in the wick, and are heated by the high temperature of the flame. By the action of the heat, the solid or liquid substance is here, as in other cases, decomposed, forming products of dry distillation. These products occur in the central portion of the flame of a candle. The air travels to the flame from the outside, and is not able to intermix with the vapours and gases in all parts of the flame; consequently, in the outer portion of the flame the amount of oxygen flowing to it will be greater than in the interior portions of the flames. But, owing to diffusion, the oxygen, naturally together with nitrogen, flowing to the combustible substance penetrates inside the flame, when the combustion takes place in ordinary air. The combustible vapours and gases combine with this oxygen, evolve a considerable amount of heat, and bring about that state of red heat which is so necessary both for keeping up the combustion and also for the uses to which the flame is applied. Passing from the colder envelope of air to the interior of the flame, to the source of the combustible vapours (for instance, the wick), we evidently first traverse layers of high temperature, and then layers of lower and lower temperature, in which the combustion is less complete, owing to the limited supply of oxygen.

Thus, yet unburnt products of the decomposition of organic substances occur in the interior of the flame. But there is always free hydrogen in the interior of the flame, even when oxygen is introduced there, or when a mixture of hydrogen and oxygen burns, because the temperature evolved in the combustion of hydrogen or the carbon of organic matter is so high that the products of combustion are themselves partially decomposed—that is, dissociated—at this temperature. Hence, in a flame a portion of the hydrogen and of the oxygen

which might combine with the combustible substances must always occur in a free state. If a hydrocarbon burns, and we imagine that a portion of the hydrogen occurs in a free state, then a portion of the carbon must also occur in the same form in



FIG. 36.—In the candle flame the portion C contains the vapours and products of decomposition; in the bright zone A the combustion has commenced, and particles of carbon are emitted; and in the pale zone B the combustion is completed.

The combination of various substances with oxygen may not present any signs of combustion—that is, the temperature may rise but

the flame, because, other conditions being unchanged, carbon burns after hydrogen, and this is observed in reality in the combustion of various hydrocarbons. Charcoal, or the soot of a common flame, proceeds from the dissociation of organic substances contained in the flame. The majority of hydrocarbons, especially those containing much carbon—for instance, naphthalene—burn even in oxygen, with separation of soot. The hydrogen burns, but the carbon remains unburnt, or, at least, partly so. It is this free carbon which causes the brilliancy of the flame. That the interior of the flame contains a mixture which is still capable of combustion may be proved by the following experiment: A portion of the gases may be withdrawn by an aspirator from the central portion of the flame of carbonic oxide, which is combustible in air. For this purpose Deville passed water through a metallic tube having a fine lateral orifice, which is placed in the flame. As the water passes along the tube the gases of the flame enter it, they are interrupted by cylinders of water passing along the tube, and are carried off with it into an apparatus for their investigation. It appears that all portions of the flame obtained by the combustion of a mixture of carbonic oxide and oxygen contain a portion of this mixture still unburnt. The researches of Deville and Bunsen showed that in the explosion of a mixture of hydrogen and of carbonic oxide with oxygen in a closed space, complete combustion sometimes does not take place immediately. If two volumes of hydrogen and one volume of oxygen be enclosed in a closed space, then on explosion the pressure does not attain that magnitude which it would were there immediate and complete combustion. It may be calculated that in this case the pressure should attain twenty-six atmospheres. In reality, it has been shown by direct experiment that in the explosion of hydrogen and oxygen the pressure does not exceed nine and a-half atmospheres.

This may be explained by the fact that, in the explosion, the whole of the oxygen does not all at once combine with the combustible substance. The amount of a gas burnt may even be determined from the pressure produced in its combustion, knowing the heat evolved in its combustion and the specific heat of all the resultant and participating substances, and hence the temperature of combustion, and therefore also the pressure which may be evolved as a consequence of that rise of temperature which proceeds from the evolution of heat. It appears that in this case only one-third of the gases burns, the remaining two-thirds are not able to combine at the temperature evolved in the explosion. Hence, in complete combustion, they at first remain in an uncombined state, and their mutual combination only takes place after they have cooled. Hence the admixture of the products of combustion with an explosive mixture prevents the combustion of the remaining mass, which is capable of burning. The admixture of carbonic anhydride prevents carbonic oxide from burning. The presence of any other foreign gas interferes in the same manner. This shows that every portion of a flame must contain combustible, burning, and already burnt substances—i.e., oxygen, carbon, carbonic oxide, hydrogen, hydrocarbons, carbonic anhydride, and water. Consequently, *it is impossible to attain instantaneous complete combustion*, and this is one of the reasons of the phenomenon of flame. A certain space is required, in which the temperature would be unequal in different parts. In this space different quantities of the component parts are successively subjected to combustion, or are cooled under the influence of adjacent objects, and combustion only ends where the flame ends. If the combustion could be concentrated at one spot, then the temperature would be incomparably higher than it is under the actual circumstances. Hence it is not to be wondered at that smoke and soot appear in the combustion of a substance with flame. They must occur in the flame, because from what has been said above complete combustion cannot take place instantaneously, but only at a certain fall in temperature.

The preceding considerations and investigations presuppose that the specific heats of the products of combustion are known, and are equal to the specific heats at the ordinary

inconsiderably. This may either proceed from the fact that the reaction of the substance (for example, tin, mercury, lead at a high temperature, or a mixture of pyrogallol with caustic potash at the ordinary temperature) evolves but little heat, or that the heat evolved is transmitted to good conductors of heat, like metals, or that the combination with oxygen takes place so slowly that the heat evolved succeeds in passing to the surrounding objects. Combustion is only a particular, intense, and evident case of combination with oxygen. Respiration is also an act of combination with oxygen: it also serves, like combustion, for the development of heat by those chemical processes which are its consequences (the transformation of oxygen into carbonic anhydride). Lavoisier enunciated this in the clear expression, 'respiration is slow combustion.'

Reactions of slow combination of substances with oxygen are termed *oxidations*. Combination of this kind (and also combustion) often results in the formation of acid substances, and hence the name *oxygen* (*Sauerstoff*). Combustion is only rapid oxidation. Phosphorus, iron, and wine may be taken as examples of substances which slowly oxidise in air at the ordinary temperature. If such a substance be left in contact with a definite volume of air or oxygen, it little by little absorbs the oxygen, as may be seen by the decrease in volume of the gas. This slow oxidation is, as a rule, rarely accompanied by a sensible evolution of heat; but an evolution of heat really occurs, only it is not apparent to our senses, owing to the inconsiderable rise of temperature which takes place; this is owing to the slow rate of the reaction and to the transmission of the heat formed as radiant heat, &c. Thus, in the oxidation of wine and its transformation into vinegar by the usual method of its preparation, the heat evolved cannot be observed because it extends over whole weeks, but in the so-called rapid process of the manufacture of vinegar, when a large quantity of wine is comparatively rapidly oxidised, the evolution of heat is quite apparent.

Such slow processes of oxidation are always taking place in nature by the action of the atmosphere. Dead organisms and the substances obtained from them—such as bodies of animals, wood, wool, grass, &c.—

temperature. If they vary (as Berthelot and Vieille affirm), the portion of a substance which remains unburnt on explosion cannot be calculated from the pressure, and therefore the quantitative side of the subject should be considered as doubtful. But the qualitative side of the subject cannot be subject to doubt, because the dissociation of the products of combustion at high temperatures is proved clearly by the most varied experiments.

are especially subject to this action. They *rot* and *putrefy*—that is, their solid matter is transformed into gases, under the influence of moisture, and atmospheric oxygen, and often under the influence of other organisms, such as moulds, worms, micro-organisms (bacteria), and such like. These are processes of slow combustion, of slow combination with oxygen. Everyone knows that manure rots and evolves heat, that stacks of damp hay, damp flour, straw, &c., become heated and are changed in the process.⁴⁷ In all these transformations there are formed the same chief products of combustion as are contained in smoke; the carbon gives carbonic anhydride, and the hydrogen water. Hence these processes require oxygen just like combustion. This is the reason why the entire prevention of access of air hinders these transformations,⁴⁸ and an increased supply of air accelerates them. The mechanical treatment of arable lands by the plough, harrow, and other similar means has not only the object of facilitating the spread of roots in the ground, and of making the soil more permeable to water, but it also serves to facilitate the access of the air to the component parts of the soil; as a consequence of which the organic remains of soil rot—so to speak, breathe air and evolve carbonic anhydride. One acre of good garden land in summer evolves more than six tons of carbonic anhydride.

It is not only vegetable and animal substances which are subject to slow oxidation in the presence of water. The very metals are rusted under these conditions. Copper very easily absorbs oxygen in the presence of acids. Many metallic sulphides (for example, pyrites) are very easily oxidised with access of air and moisture. Thus processes of slow oxidation proceed throughout nature.

There are many elements which do not, under any circumstances, combine directly with gaseous oxygen; nevertheless their compounds with oxygen may be obtained. Platinum, gold, iridium, chlorine, and iodine are examples of such elements. In this case recourse is had to a so-called *indirect method*—i.e., the given substance is

⁴⁷ Cotton waste (it is used in factories for cleaning machines from lubricating oil) soaked in oil and lying in heaps is self-combustible, being oxidised by the air.

⁴⁸ When it is desired to preserve a supply of vegetable and animal food, the access of the oxygen of the atmosphere (and also of the germs of organisms borne in the air) is often prevented. For this reason articles of food are often kept in hermetically closed vessels, from which the air is withdrawn; vegetables are dried and soldered up while hot in tin boxes; sardines are immersed in oil, &c. The removal of water from substances is also sometimes resorted to with the same object (the drying of hay, corn, fruits), as also is saturation with substances which absorb oxygen (such as sulphurous anhydride), or which hinder the growth of organisms forming the first cause of putrefaction, as in processes of smoking, embalming, and in the keeping of fishes and other animal specimens in spirit, &c.

combined with another element, and by a method of double decomposition this element is replaced by oxygen, or a substance is taken which easily evolves oxygen, and is brought into contact with the given substance. The oxygen then acts at the moment of its evolution. If the conditions are such that the substance to be oxidised is liberated at the same moment, then oxidation proceeds with greater ease. (The explanation of this phenomenon was given in the last chapter.) It must be remarked that substances which do not directly combine with oxygen, but form compounds with it by an indirect method, often readily lose the oxygen which was absorbed by them by double decomposition or at the moment of its evolution. Such, for example, are the compounds of oxygen with chlorine, nitrogen, and platinum, which evolve oxygen on heating. They, like other substances which easily evolve oxygen on heating, may serve as a means for obtaining oxygen, or for oxidation. They, in the presence of substances which are capable of combining with oxygen, are decomposed, give up their oxygen to them, and may thus be themselves employed for indirect oxidation. In this respect *oxidising agents*, or those compounds of oxygen which are employed in chemical and technical practice for transferring oxygen to other substances, are especially remarkable. The most important among these is nitric acid or *aqua fortis*—a substance rich in oxygen, and capable of evolving it when heated, and which easily oxidises a great number of substances. Thus nearly all metals and organic substances containing carbon and hydrogen are more or less oxidised when heated with nitric acid. If strong nitric acid be taken, and a piece of burning charcoal be immersed in the acid, it continues to burn, the combustion proceeding in this case at the expense of the oxygen contained in the liquid nitric acid. Chromic acid acts like nitric acid; alcohol burns when mixed with it. Although the action is not so marked, even water may oxidise with its oxygen. Sodium is not oxidised in perfectly dry oxygen at the ordinary temperature, but it burns very easily in water and aqueous vapour. Charcoal can burn in carbonic anhydride—a product of combustion—forming carbonic oxide. Magnesium burns in the same gas, separating carbon from it. Generally, combined oxygen can pass from one compound to another.

The products of combustion or oxidation—and in general the definite compounds of oxygen—are termed *oxides*. Some oxides are not capable of combining with other oxides—or combine with only a few, and then form unstable compounds with the evolution of very little heat; others, on the contrary, enter into combination with very many other oxides, and in general have remarkable chemical energy. The oxides incapable of combining with others, or only showing this quality in a

small degree, are termed *indifferent oxides*. Such are the peroxides, of which mention has before been made.

The class of oxides capable of entering into mutual combination we will term *saline oxides*. They fall into two chief groups—at least, as regards the most extreme members. The members of one group do not combine with each other, but combine with the members of the other group. As representative of one group may be taken the oxides of the metals, magnesium, sodium, calcium, &c. Representatives of the other group are the oxides formed by the non-metals, sulphur, phosphorus, carbon. If we take, for instance, the oxide of calcium or lime, and bring it into contact with oxides of the second group, there ensues very ready combination. Thus, for instance, if we mix calcium oxide with oxide of phosphorus, they combine with great facility, with the evolution of much heat. If we pass the vapour of sulphuric anhydride, obtained by the combination of sulphurous oxide with oxygen, over pieces of lime heated to redness, then the sulphuric anhydride is absorbed by the lime, with the formation of a substance called calcium sulphate. The oxides of the first kind, which contain metals, are termed *basic oxides* or *bases*. Lime is a familiar example of this class. The oxides of the second group, which are capable of combining with the bases, are termed *anhydrides of the acids* or *acid oxides*. Sulphuric anhydride, SO_3 , may be taken as a type of the group. It is formed by the combination of sulphur with oxygen; by the addition of a fresh quantity of oxygen to the above-mentioned sulphurous anhydride, SO_2 , by passing it and oxygen over incandescent spongy platinum. Carbonic anhydride (often termed ‘carbonic acid,’ CO_2), phosphoric anhydride, sulphurous anhydride, are all acid oxides, for they can combine with such oxides as lime or calcium oxide, magnesia or magnesium oxide, MgO , soda or sodium oxide, Na_2O , &c.

If a given element form one basic oxide, it is termed the *oxide*; for example, calcium oxide, magnesium oxide, potassium oxide. Some indifferent oxides are also called ‘oxides’ if they have not the properties of peroxides, and at the same time do not show the properties of acid anhydrides—for instance, carbonic oxide, of which mention has already been made. If an element forms two basic oxides (or two indifferent oxides not having the characteristics of a peroxide) then that of the lower degree of oxidation is called a *suboxide*—that is, suboxides contain less oxygen than oxides. Thus, when copper is heated to redness in a furnace it increases in weight and absorbs oxygen, until for 63 parts of copper there is absorbed not more than 8 parts of oxygen by weight, forming a red mass, which is suboxide of copper; but if the roasting

be prolonged, and the draught of air be increased, 63 parts of copper absorb 16 parts of oxygen, and form black oxide of copper. Sometimes to distinguish between the degrees of oxidation a change of suffix is made in the oxidised element—*-ic* oxide naming the higher degree of oxidation, and *-ous* oxide the lower degree. Thus ferrous oxide and ferric oxide are the same as suboxide of iron and oxide of iron. This nomenclature is convenient in some cases, but cannot always be employed. If an element forms one anhydride only, then it is named by an adjective formed from the name of the element made to end in *-ic* and the word *anhydride*. When an element forms two anhydrides, then the suffixes *-ous* and *-ic* are used to distinguish them: *-ous* signifying less oxygen than *-ic*; for example, sulphurous and sulphuric anhydrides.⁴⁹ When several oxides are formed from the same element, the prefixes *mon*, *di*, *tri*, *tetra* are used, thus: chlorine monoxide, chlorine dioxide, chlorine trioxide, and chlorine tetroxide or chloric anhydride.

Chemical transformations of the oxides themselves are rarely accomplished, and in the few cases where they are subject to such changes a particularly important part is played by their combinations with water. The majority of, if not all, basic and acid oxides combine with water, either by a direct or an indirect method forming *hydrates*—that is, such compounds as split up into water and an oxide of the same kind only. We already know that many substances are capable of combining with water. Oxides possess this property in the highest degree. We have already seen examples of this (Chap. I.) in the combination of lime, and of sulphuric and phosphoric anhydrides, with water. Hence the results of such combination are basic and acid hydrates. Acid hydrates are called *acids*, because they have an acid

⁴⁹ It must be remarked that certain elements form oxides of all three kinds—*i.e.*, indifferent, basic, and acid; for example, manganese forms manganous oxide, manganic oxide, peroxide of manganese, red oxide of manganese, and manganic anhydride, although some of them are not known in a free state but only in combination. It is, then, always to be remarked that the basic oxide contains less oxygen than the peroxides, and the peroxides less than the acid anhydride. Thus they must be placed in the following general normal order with respect to the amount of oxygen entering into their composition—(1) basic oxides, suboxides, and oxides; (2) peroxides; (3) acid anhydrides. The majority of elements, however, do not give all three kinds of oxides, some giving only one degree of oxidation. It must further be remarked that there are oxides formed by the combination of acid anhydrides with basic oxides, or, in general, of oxides with oxides. For every oxide having a higher and a lower degree of oxidation, it might be said that the intermediate oxide was formed by the combination of the higher with the lower oxide. But this is not true in all cases—for instance, when the oxide under consideration forms a whole series of independent compounds—for oxides which are really formed by the combination of two other oxides do not give such independent compounds, but in many cases decompose into the higher and lower oxides.

taste when dissolved in water (or saliva, for then only can they act on the palate). Vinegar, for example, has an acid taste because it contains acetic acid dissolved in water. Sulphuric acid, of which we have made mention many times, because it is the acid of the greatest importance both in practical chemistry and for its technical applications, is really a hydrate formed by the combination of sulphuric anhydride with water. Besides their acid taste, dissolved acids or acid hydrates have the property of changing to red the blue colour of certain vegetable dyes. Of these dyes *litmus* is particularly remarkable and much used. It is the blue substance extracted from certain lichens, and is used for dyeing tissues blue; it gives a blue infusion with water. This infusion, on the addition of an acid, *changes from blue to red*.⁵⁰

Basic oxides, in combining with water, form hydrates, of which, however, very few are soluble in water. Those which are soluble in water have an alkaline taste like that of soap or of water in which ashes have been boiled, and are called *alkalis*. Further, alkalis have the

⁵⁰ Blotting or unsized paper, soaked in a solution of litmus, is usually employed for detecting the presence of acids. This paper is cut into strips, and is called *test paper*; when dipped into acid it immediately turns red. This is a most sensitive reaction, and may be employed for testing for the least traces of acids. If 10000 parts by weight of water be mixed with 1 part of sulphuric acid, the coloration is distinctly perceptible, and it is quite distinguishable on the addition of ten times more water. Certain precautions must, however, be taken in the preparation of such very sensitive litmus paper. Litmus is sold in lumps. Take, say, 100 grams of it; pound it, and add it to cold pure water in a flask. Shake and decant the water. Repeat this three times. This is done to wash away easily-soluble impurities, especially alkalis. Transfer the washed litmus to a flask, and pour in 600 grams of water, heat, and allow the hot infusion to remain for some hours in a warm place. Then filter, and divide the filtrate into two parts. Add a few drops of nitric acid to one portion, so that a faint red tinge is obtained, and then mix the two portions. Add spirit to the mixture, and keep it thus in a stoppered bottle (it soon spoils if left open to the air). This infusion may be employed directly; it reddens in the presence of acids, and turns blue in the presence of alkalis. If evaporated, a solid mass is obtained which is soluble in water, and may be kept unchanged for any length of time. The test paper may be prepared as follows:—Take a strong infusion of litmus, and soak blotting-paper with it; dry it, and cut it into strips, and use it as test-paper for acids. For the detection of alkalis, the paper must be soaked in a solution of litmus just reddened by a few drops of acid; if too much acid be taken, the paper will not be sensitive. Such acids as sulphuric acid colour litmus, and especially its infusion, a brick-red colour, whilst more feeble acids, such as carbonic, give a faint red-wine tinge. Test-paper of a yellow colour is also employed; it is dyed by an infusion of turmeric roots in spirit. In alkalis it turns brown, but regains its original hue in acids. Many blue and other vegetable colouring matters may be used for the detection of acids and alkalis; for example, infusions of cochineal, violets, log-wood, &c. Certain artificially-prepared substances and dyes may also be employed. Thus rosolic acid, $C_{20}H_{16}O_3$, and phenolphthaleïn, $C_{20}H_{14}O_4$, are colourless in an acid, and red in an alkaline solution. Cyanine is also colourless in the presence of acids, and gives a blue coloration with alkalis. These are very sensitive tests. Their behaviour in respect to various acids, alkalis and salts sometimes gives the means of distinguishing substances from each other.

property of restoring the blue colour to litmus which has been reddened by the action of acids. The hydrates of the oxides of sodium and potassium, NaHO and KHO , are examples of basic hydrates easily soluble in water. They are true alkalis, and are termed *caustic*, because they act very powerfully on the skin of animals and plants. Thus NaHO is called 'caustic' soda.

Thus, the saline oxides are capable of combining together and with water. Water itself is an oxide, and not an indifferent one, for it can, as we have seen, combine with basic and acid oxides; it is a representative of a whole series of saline oxides, *intermediate oxides*, capable of combining with both basic and acid oxides. There are many such oxides, which, like water, combine with basic and acid anhydrides—for instance, the oxides of aluminium and tin, &c. From this it may be concluded that all oxides might be placed, in respect to their capacity for combining with one another, in one uninterrupted series, at one extremity of which would stand those oxides which do not combine with the bases—that is, the alkalis—while at the other end would be the acid oxides, and in the interval those oxides which combine with one another and with both the acid and basic oxides. The further apart are the members of this series the more stable are the compounds they form together, the more energetically do they act on each other, the greater the quantity of heat evolved in their reaction, and the clearer is their saline chemical character.

We said above that basic and acid oxides combine together, but rarely react on each other; this depends on the fact that the majority of them are solids or gases—that is, they occur in the state least prone to chemical reaction. The gaseo-elastic state is with difficulty destroyed, because it necessitates overcoming the elasticity proper to the gaseous particles. The solid state is characterised by the immobility of its particles; whilst chemical action requires contact, and hence a displacement and mobility. If solid oxides be heated, and especially if they be melted, then reaction proceeds with great ease. But such a change of state rarely occurs in nature or in practice. In a few furnace processes only is this the case. For example, in the manufacture of glass, the oxides contained in it combine together in a molten state. But when oxides combine with water, and especially when they form hydrates soluble in water, then the mobility of their particles increases to a considerable extent, and their reaction is greatly facilitated. Reaction then takes place at the ordinary temperature—easily and rapidly; so that this kind of reaction belongs to the class of those which take place with unusual facility, and are, therefore, very often taken advantage of in practice, and also have been and are going on in nature at

every step. We will now consider the reactions of oxides in the state of hydrates, not losing sight of the fact that water is itself an oxide with definite properties, and has, therefore, no little influence on the course of those changes in which it takes part.

If we take a definite quantity of an acid, and add an infusion of litmus to it, it turns red ; the addition of an alkaline solution does not at once alter the red colour of the litmus, but on adding more and more of the alkaline solution a point is reached when the red colour changes to violet, and then the further addition of a fresh quantity of the alkaline solution changes the colour to blue. This change of the colour of the litmus is a consequence of the formation of a new compound. This reaction is termed the *saturation* or *neutralisation* of the acid by the base, or *vice versâ*. The solution in which the acid properties of the acid are saturated by the alkaline properties of the base is termed a *neutral* solution. Such a solution, although derived from the mixture of a base with an acid, does not, however, exhibit either the acid or basic reaction on litmus, yet it preserves many other signs of the acid and alkali. It is observed that in such a definite admixture of an acid with an alkali, besides the change in the colour of litmus, there is a heating effect—*i.e.*, an evolution of heat—which is alone sufficient to prove that there was chemical action. And, indeed, if the resultant violet solution be evaporated, there separates out, not the acid nor the alkali originally taken, but a substance which has neither acid nor alkaline properties, but is usually solid and crystalline, having a saline appearance ; this is a *salt* in the chemical sense of the word. Hence it is derived from the reaction of an acid on an alkali, and through a definite relation between the acid and alkali. The water here taken for solution plays no other part than merely facilitating the progress of the reaction. This is seen from the fact that the anhydrides of the acids are able to combine with basic oxides, and give the same salts as do the acids with the alkalis or hydrates. Hence, a salt is a compound of definite quantities of an acid with an alkali. In the latter reaction, water is separated out if the substance formed be the same as is produced by the combination of anhydrous oxides together.⁵¹ Examples of the formation of salts from acids and bases are easily observed, and are very often applied in

⁵¹ That water really is separated in the reaction of acid on alkaline hydrates, may be shown by taking some other intermediate hydrate—for instance, alumina—instead of water. Thus, if a solution of alumina in sulphuric acid be taken, it will have, like the acid, an acid reaction, and will therefore colour litmus red. If, on the other hand, a solution of alumina in an alkali—for instance, potash—be taken, it will have an alkaline reaction, and will turn red litmus blue. On adding the alkaline to the acid solution until neither an alkaline nor an acid reaction is produced, a salt is formed, consisting of

practice. If we take, for instance, insoluble magnesium oxide, it is easily dissolved in sulphuric acid, and on evaporation gives a saline substance, bitter, like all the salts of magnesium, and familiar to all under the name of Epsom salts, used as a purgative. If a solution of caustic soda—which is obtained, as we saw, by the action of water on sodium oxide—be poured into a flask in which charcoal has been burnt ; or if carbonic anhydride, which is produced under so many circumstances, be passed through a solution of caustic soda, then sodium carbonate or soda, Na_2CO_3 , is obtained, of which we have spoken several times, and which is prepared on a large scale and often used in manufactures. This reaction is expressed by the equation, $2\text{NaHO} + \text{CO}_2 = \text{Na}_2\text{CO}_3 + \text{H}_2\text{O}$. Thus, the various bases and acids form an innumerable number of different salts.⁵² Salts constitute an example of definite chemical compounds which, both in the history and practice of science,

sulphuric anhydride and potassium oxide. In this, as in the reaction of hydrates, an intermediate oxide is separated out—namely, alumina. Its separation will be very evident in this case, as alumina is insoluble in water, whilst its compounds with the acid and alkali, like the compound of an alkali with an acid—*i.e.*, a salt—are soluble in water, and therefore on mixing the solutions of alumina in an acid and an alkali, it is precipitated as a gelatinous hydrate.

⁵² The mutual interaction of hydrates, and their capacity of forming salts, may be taken advantage of for determining the character of such hydrates as are insoluble in water. Let us imagine that a given hydrate, whose chemical character is unknown, is insoluble in water. It is therefore impossible to test its reaction on litmus. It is then mixed with water, and an acid—for instance, sulphuric acid—is added to the mixture. If the hydrate taken be basic, reaction will take place, either directly or by the aid of heat, with the formation of a salt. In certain cases, the resultant salt is soluble in water, and this will at once show that combination has taken place between the insoluble basic hydrate and the acid, with the formation of a soluble saline substance. In those cases where the resultant salt is insoluble, still the water loses its acid reaction, and therefore it may be ascertained, by the addition of an acid, whether a given hydrate has a basic character, like the hydrates of oxide of copper, lead, &c. If the acid does not act on the given insoluble hydrate (at any temperature), then it has not a basic character, and it should be tested as to whether it has an acid character. This is done by taking an alkali, instead of the acid, and by observing whether the unknown hydrate then dissolves, or whether the alkaline reaction disappears. Thus it may be proved that hydrate of silica is acid, because it dissolves in alkalis and not in acids. If it be a case of an insoluble intermediate hydrate, then it will be observed to react on both the acid and alkali. Hydrate of alumina is an instance in question, which is soluble both in caustic potash and in sulphuric acid. But it must be remarked that intermediate oxides, in an anhydrous state, often evince great resistance to the formation of saline compounds. Thus alumina or aluminium oxide, in the anhydrous form in which it is met with in nature, and which forms a crystalline substance, is insoluble in this form both in solutions of alkalis and of acids. In order to convert it into a soluble form, it must be ground into a fine powder and fused together with certain acid compounds, which are unchanged by heat, such as acid potassium sulphate.

The *degree of affinity* or chemical *energy* proper to oxides and their hydrates is very dissimilar; some extreme members of the series have it to a great extent. When acting on each other they evolve a large quantity of heat, and when acting on intermediate hydrates they also evolve heat to a considerable degree, as we saw in the combi-

are most often cited as confirming the conception of definite chemical compounds. Indeed, all the indications of a definite chemical combination are clearly seen in the formation and properties of salts. Thus, salts are produced with a definite proportion of oxides, heat is evolved in their formation,⁵³ and the character of the oxides and many of their physical properties are hidden in salts. Thus, when gaseous carbonic anhydride combines with a base to form a solid salt, the elasticity of the gas quite disappears in its passage into the salt.⁵⁴

Judging from the above, a salt is a compound of basic and nation of lime and sulphuric anhydride with water. When extreme oxides combine they form stable salts, which are difficultly decomposed, and often show characteristic properties. The compounds of the intermediate oxides with each other, or even with basic and acid oxides, present a very different case. However much alumina we may dissolve in sulphuric acid, we cannot saturate the acid properties of the sulphuric acid, the resulting solution will always have an acid reaction. So also, whatever quantity of alumina is dissolved in an alkali, the resulting solution will always present an alkaline reaction.

⁵³ In order to give an idea of the quantity of heat evolved in the formation of salts, I append a table of data for *very dilute aqueous solutions* of acids and alkalis, according to the determinations of Berthelot and Thomsen. The figures are given in major calories—that is, in thousands of units of heat. Hence, 49 grams of sulphuric acid, H_2SO_4 , taken in a dilute aqueous solution, when mixed with such an amount of a weak solution of caustic soda, NaHO , that a neutral salt is formed (when all the hydrogen of the acid is replaced by the sodium), evolves 15800 units of heat. A star signifies the formation of an insoluble salt.

	49 parts of H_2SO_4	63 parts of HNO_3		49 parts of H_2SO_4	63 parts of HNO_3
NaHO . . .	15·8	13·7	MgO . . .	15·6	13·8
KHO . . .	15·7	13·8	FeO . . .	12·5	10·7 (?)
NH_3 . . .	14·5	12·5	ZnO . . .	11·7	9·8
CaO . . .	15·6	13·9	Fe_2O_3 . . .	5·7	5·9
BaO . . .	18·4*	13·9			

These figures cannot be considered as the heat of neutralisation, because the water here plays an important part. Thus, for instance, sulphuric acid and caustic soda in dissolving in water, evolve very much heat, and the resultant sodium sulphate very little; consequently, the heat evolved in an anhydrous state will be different from that in a hydrated state. Those acids which are not energetic in combining with the same quantity of alkalis as is required for the formation of normal salts of sulphuric or nitric acids always, however, give less heat. For example, with caustic soda: carbonic acid gives 10·2, hydrocyanic 2·9, hydrogen sulphide 3·9. And as feeble bases (for example, Fe_2O_3) also evolve less heat than those which are more powerful, so a certain general correlation between thermochemical data and the conception of the measure of affinity shows itself here, as in other cases (*see* Chap. II., Note 7), which does not, however, give any reason for judging of the measure of the affinity which binds the elements of salts by the heat of the formation of salts in dilute solutions. This is rendered especially clear from the fact that water is able to decompose many salts, and is separated in their formation.

⁵⁴ Carbonic anhydride evolves heat in dissolving in water. The solution easily disassociates and evolves carbonic anhydride, according to the law of Henry and Dalton (*see* Chap. I., p. 78). In dissolving in caustic soda, it either gives a normal salt, Na_2CO_3 , which does not evolve carbonic anhydride, or an acid salt, NaHCO_3 , which, in disso-

acid oxides, or the result of the action of hydrates of these classes on each other, with separation of water. But salts may be obtained by other methods. Let us not forget that basic oxides are formed by metals, and acid oxides often by non-metals. But metals and non-metals are capable of combining together, and a salt is frequently formed by the oxidation of such a compound. For example, iron very easily combines with sulphur, forming iron sulphide (as we saw in the Introduction); this in air, and especially moist air, absorbs oxygen, with the formation of the same salt as may be obtained by the combination of the oxides of iron and sulphur, or of the hydrates of these oxides. Hence, it cannot be said or supposed that a salt contains the principles of the oxides, or that a salt must necessarily contain two kinds of oxides in itself. The same conclusion may be arrived at by investigating the different other methods of the formation of salts — thus, for instance, many salts enter into double decomposition with the metals, in which case the acting metal replaces that which originally occurred in the salt. As we saw in the Introduction, iron, when placed in a solution of copper sulphate, separates out the copper, and forms an iron salt. Thus, the derivation of salts from oxides, is only one of the methods of their preparation, there being many others, and, therefore, it cannot be affirmed that a salt is simply the compound of two oxides. We saw, for instance, that in sulphuric acid it was possible to replace the hydrogen by zinc, and that by this means zinc sulphate was formed; so likewise the hydrogen in many other acids may be replaced by zinc, iron, potassium, sodium, and a whole series of similar metals, corresponding salts being obtained. The hydrogen in the water of the acid, in this case, is exchanged for a metal, and a salt is obtained from the hydrate. In this sense of a salt it may be said, that *a salt is an acid in which hydrogen is replaced by a metal*. Such a definition will be much more exact than that previously given, for it refers directly to elements and not to their compounds with oxygen. It shows that a salt and an acid are essentially compounds of the same series, with the difference that the latter contains hydrogen and the former a metal. Such a definition is still more exact than the first definition of salts in respect to its referring likewise to those acids which do not contain oxygen, and, as we shall afterwards learn, there is a series of such acids. Such elements as chlorine and bromine form

ciating, evolves carbonic anhydride. The same gas, when dissolved in solutions of salts, acts in one or the other manner (*see* Chap. II., Note 38). Here it is seen what a successive series of relations exists between compounds of a different order, between substances of different degrees of stability. Were solutions distinctly separated from chemical compounds, we should not be able to see those natural transitions which exist in reality.

compounds with hydrogen, in which the hydrogen may be replaced by a metal forming substances which, in their reactions and external characters, resemble the salts formed from oxides. Table salt, NaCl , is an example of this. It may be obtained by the replacement of hydrogen in hydrochloric acid, HCl , by the metal sodium, just as sulphate of sodium, Na_2SO_4 , may be obtained by the replacement of hydrogen in sulphuric acid, H_2SO_4 , by sodium. The exterior appearance of the resulting products, their neutral reaction, and even their saline taste, show their mutual resemblance; as the acid reaction, the property of saturating bases, the capacity of exchanging their hydrogen for some metal, and the acid taste, show the common properties belonging to hydrochloric and sulphuric acids.

To the fundamental properties of salts yet another must be added—namely, that they are more or less *decomposed by the action of a galvanic current*. The results of this decomposition are very different, according to whether the salt be taken in a fused or dissolved state. But the decomposition may be so represented, that the metal appears at the electro-negative pole (like hydrogen in the decomposition of water, or its mixture with sulphuric acid), and the remaining parts of the salt appear at the electro-positive pole (where the oxygen of water appears). If, for instance, an electric current acts on an aqueous solution of sodium sulphate, then the sodium appears at the negative pole, and oxygen and the anhydride of sulphuric acid at the positive pole. But in the solution itself the result is different, for sodium, as we know, decomposes water with evolution of hydrogen, forming caustic soda; consequently hydrogen will be evolved, and caustic soda appear at the negative pole: while at the positive pole the sulphuric anhydride immediately combines with water and forms sulphuric acid, and therefore oxygen will be evolved and sulphuric acid formed round this pole.⁵⁵ In other cases, when the metal separated is not able to decompose water, it will be deposited in a free state. Thus, for example, in the decomposition of copper sulphate, copper separates out at the cathode, and oxygen and sulphuric acid appear at the anode, and if a copper plate be attached to the positive pole, then the oxygen evolved will oxidise the copper, and the oxide of copper will dissolve in the sulphuric acid which is formed around this pole; hence the copper will be dissolved at the positive, and deposited at the negative, pole—

⁵⁵ This kind of decomposition may be easily observed by pouring a solution of sodium sulphate in a U-shaped tube and inserting electrodes in both branches. If the solution be coloured with an infusion of litmus, it will easily be seen that it turns blue round the electro-negative pole, owing to the formation of sodium hydroxide, and red at the electro-positive pole, from the formation of sulphuric acid.

that is, a transfer of copper from the positive to the negative pole ensues. The galvanoplastic art (electrotyping) is based on this principle.⁵⁶ Therefore the most radical and general properties of salts (including also such salts as table salt, which contains no oxygen) may be expressed by representing the salt as composed of a metal M and a haloid X —that is, by expressing the salt by MX . In common table salt the metal is sodium, and the haloid an elementary body, chlorine. In sodium sulphate, Na_2SO_4 , sodium is again the metal, but the complex group, SO_4 , is the haloid. In sulphate of copper, $CuSO_4$, the metal is copper, and the haloid the same as in the preceding salt. Such a representation of salts expresses with great simplicity the *capacity of every salt to enter into saline double decompositions with other salts*; consisting in the mutual replacement of the metals in the salts. This exchange of their metals forms the fundamental property of salts. If there be two salts with different metals and haloids, and they be in solution or fusion, or any other manner, brought into contact, then the metals of these salts will always partially or wholly exchange places. If we designate one salt by MX , and the other by NY , then we either partially or wholly obtain from them new salts, MY and NX . Thus we saw in the Introduction, that on mixing solutions of table salt, $NaCl$, and silver nitrate, $AgNO_3$, a white insoluble precipitate of silver chloride, $AgCl$, is formed, and a new salt, sodium nitrate, $NaNO_3$, is obtained in solution. If the metals of salts exchange places in reactions of double decomposition, it is clear that metals themselves, taken in a separate state, are able to act on salts, as zinc evolves hydrogen from acids, and as iron separates copper from copper sulphate. When, to what extent, and which metals displace each other, and how the metals are distributed between the haloids, all this we will discuss later on, guided by those reflections and deductions which Berthollet introduced into the science at the beginning of this century.

According to the above observations, an acid is nothing more than a salt of hydrogen. Water itself may be looked on as a salt in which

⁵⁶ In other cases the decomposition of salts by the electric current may be accompanied by much more complex results. Thus, when the metal of the salt is capable of a higher degree of oxidation, such a higher oxide may be formed at the positive pole by the oxygen which is evolved there. This takes place, for instance, in the decomposition of salts of silver and manganese by the galvanic current, peroxides of these metals being formed. If the metal separated at the negative pole acts on a salt occurring in the solution, then it may do so at this pole, and in this manner the phenomena of the action of a current on a salt are in many cases rendered remarkably complicated. But all the phenomena as yet known may be expressed by the above law—that the current decomposes salts into metals, which appear at the negative pole, and into the remaining component parts, which appear at the positive pole.

the hydrogen is combined with either oxygen or the aqueous radicle, OH; water will then be HOH, and alkalis or basic hydrates, MOH. The group OH, or the *aqueous radicle*, otherwise called *hydroxyl*, may be looked on as a haloid like the chlorine in table salt, not only because the element Cl and the group OH very often change places, and combine with one and the same element, but also because free chlorine is very similar in many respects and reactions to peroxide of hydrogen, which is the same in composition as the aqueous radicle, as we shall afterwards see. Alkalis and basic hydrates are also salts consisting of a metal and hydroxyl—for instance, caustic soda, NaOH; this is therefore termed *sodium hydroxide*. According to this view, *acid salts* are those in which a portion only of the hydrogen is replaced by a metal, and a portion of the hydrogen of the acid remains. Thus sulphuric (H_2SO_4) acid with sodium not only gives the normal salt Na_2SO_4 , but also an acid salt, NaHSO_4 . A *basic salt* is one in which the metal is combined not only with the haloids of acids, but also with the aqueous radicle of basic hydrates—for example, bismuth gives not only a normal salt of nitric acid, $\text{Bi}(\text{NO}_3)_3$, but also basic salts like $\text{Bi}(\text{OH})_2(\text{NO}_3)$. As basic and acid salts corresponding with the oxygen acids contain hydrogen and oxygen, they are therefore able to part with these as water and to give anhydro-salts, which it is evident will be equal to compounds of normal salts with anhydrides of the acids or with bases. Thus the above-mentioned acid sodium sulphate corresponds with the anhydro-salt, $\text{Na}_2\text{S}_2\text{O}_7$, equal to 2NaHSO_4 , less H_2O . The loss of water is here, and frequently in other cases, brought about by heat alone, and therefore such salts are frequently termed *pyro-salts*—for instance, the preceding is sodium pyrosulphate ($\text{Na}_2\text{S}_2\text{O}_7$), or it may be regarded as the normal salt Na_2SO_4 + sulphuric anhydride, SO_3 . *Double salts* are those which contain either two metals, $\text{KAl}(\text{SO}_4)_2$, or two haloids.⁵⁷

⁵⁷ The above-enunciated generalisation of the conception of salts as compounds of the metals (simple, or compound like ammonium, NH_4), with the haloids (simple, like chlorine, or compound, like cyanogen, CN, or the radicle of sulphuric acid, SO_4), capable of entering into double saline decomposition, which is in accordance with the general data respecting salts, was only formed little by little after a succession of most varied propositions as to the chemical structure of salts.

Salts belong to the class of substances which have long been known in practice, and therefore were studied in many respects from very far back. At first, however, no distinction was made between the conceptions of salts, acids, and bases. Glauber prepared many artificial salts during the latter half of the seventeenth century. Up to that time the majority of salts were obtained from natural sources, and that salt which we have already mentioned several times—namely, sodium sulphate—was named Glauber's salt after this chemist. Rouelle distinguished normal, acid, and basic salts, and showed their action on vegetable dyes, still he confounded many salts with acids (by the way, we ought now to call every acid salt an acid, because it contains hydrogen, which may be replaced

Inasmuch as oxygen compounds predominate in nature, it should be expected, from what has been said above, that the occurrence of salts, rather than of acids or bases, would be most frequent in nature, for the latter on meeting, especially under the medium of the all-per-

by metals—that is, it is the hydrogen of an acid). Baumé disputed Rouelle's opinion concerning the subdivision of salts, contending that normal salts only are true salts, and that basic salts are simple mixtures of normal salts with bases and acid salts with acids, considering that washing alone could remove the base or acid from them. Rouelle, in the middle of the last century, however, rendered a great service to the study of salts and the diffusion of knowledge respecting this class of compounds in his attractive lectures. He, like the majority of the chemists of that period, did not employ the balance in his researches, but satisfied himself with purely qualitative data. The first quantitative researches on salts were carried on by Wenzel about this time. He was the director of the Freiburg mines, in Saxony. Wenzel studied the double decomposition of salts, and he observed that in the double decomposition of neutral salts a neutral salt was always obtained. He proved, by a method of weighing, that this is due to the fact that the saturation of a given quantity of a base requires such relative quantities of different acids as are capable of saturating every other base. Having taken two neutral salts—for example, sodium sulphate and calcium nitrate—let us mix their solutions together. Double decomposition takes place, because the almost insoluble calcium sulphate is formed. However much we might add of each of the salts, the neutral reaction will still be preserved, consequently the neutral character of the salts is not destroyed by the interchange of metals; that is to say, that quantity of sulphuric acid which saturated the sodium is sufficient for the saturation of the calcium, and that amount of nitric acid which saturated the calcium is enough to saturate the sodium contained in combination with sulphuric acid in sodium sulphate. Wenzel was even convinced that matter does not disappear in nature, and on this principle he corrects, in his *Doctrine of Affinity*, the results of his experiments when he remarked that he obtained less than he had originally taken. Although Wenzel deduced the law of the double decomposition of salts quite correctly, he did not determine those quantities in which acids and bases act on each other. This was done quite at the end of the last century by Richter. He determined the quantities by weight of the bases which saturate acids and of the acids which saturate bases, and he obtained comparatively correct results, although his conclusions were not correct, for he states that the quantity of a base saturating a given acid varies in arithmetical progression, and the quantity of an acid saturating a given base in geometrical progression. Richter studied the deposition of metals from their salts by other metals, and observed that the neutral reaction of the solution is not destroyed by this exchange. He also determined the quantities by weight of the metals replacing one another in salts. He showed that copper displaces silver from its salts, and that zinc displaces copper and a whole series of other metals. Those quantities of metals which were capable of replacing one another were termed equivalents.

Richter's teaching found no followers, because, although he fully believed in the discoveries of Lavoisier, yet he still held to the phlogistic reasonings which rendered his expositions very obscure. The works of the Swedish savant Berzelius freed the facts discovered by Wenzel and Richter from the obscurity of former conceptions, and led to their being explained in accordance with Lavoisier's views, and in the sense of the law of multiple proportions which had already been discovered by Dalton. On applying to salts those conclusions which Berzelius arrived at by a whole series of researches of remarkable accuracy, we are obliged to acknowledge the following law of equivalents—one part by weight of hydrogen in an acid is replaced by the corresponding equivalent weight of any metal; and, therefore, when metals replace each other their weights are in the same ratio as their equivalents. Thus, for instance, one part by weight of hydrogen is replaced by 23 parts of sodium, 39 parts of potassium, 12 parts of magnesium, 20 parts

vading water, form salts. And, indeed, salts are found everywhere in nature. In animals and plants they occur, although in but small

of calcium, 28 parts of iron, 108 parts of silver, 33 parts of zinc, &c.; and therefore, if zinc replaces silver, then 33 parts of zinc will take the place of 108 parts of silver, or 33 parts of zinc will be substituted by 23 parts of sodium, &c.

The doctrine of equivalents would be precise and simple did every metal only give one oxide or one salt. It is rendered complicated from the fact that many metals form several oxides, and consequently offer different equivalents in their different degrees of oxidation. For example, there are oxides containing iron in which its equivalent is 28—this is in the salts formed by the suboxide; and there is another series of salts in which the equivalent of iron equals $18\frac{2}{3}$ —which contain less iron, and consequently more oxygen, and correspond with a higher degree of oxidation—ferric oxide. It is true that the former salts are easily formed by the direct action of metallic iron on acids, and the latter only by a further oxidation of the compound formed already; but this is not always so. In the case of copper, mercury, and tin, under different circumstances, there are formed salts which correspond with different degrees of oxidation of these metals, and many metals have two equivalents in their different salts—that is, in salts corresponding with the different degrees of oxidation. Thus it is impossible to endow every metal with one definite equivalent weight. Therefore the conception of equivalents, while playing an important part from an historical point of view, appears, with a fuller study of chemistry, to be but an incidental conception, subordinate to a higher one, with which we shall afterwards become acquainted.

The fate of the theoretical views of chemistry was for a long time bound up with the history of salts. The clearest representation of this subject dates back to Lavoisier, and was very severely developed by Berzelius. This representation is called the *binary* theory. All compounds, and especially salts, are represented as consisting of two parts. Salts are represented as a compound of a basic oxide (a base) and an acid (that is, an anhydride of an acid, then termed an acid), whilst hydrates are represented as compounds of anhydrous oxides with water. They employed such an expression not only to denote the most usual method of formation of these substances (which would be quite true), but also to express that internal distribution of the elements by which they proposed to explain all the properties of these substances. They supposed copper sulphate to contain two most intimate component parts—copper oxide and sulphuric anhydride. This is an hypothesis. It arose from the so-called *electro-chemical hypothesis*, which supposed the two component parts to be held in mutual union, because one component (the anhydride of the acid) has electro-negative properties, and the other (the base in salts) electro-positive. Both parts are attracted together, like substances having opposite electrical charges. But as the decomposition of salts in a state of fusion by an electric current always gives a metal, therefore the representation of the constitution and decomposition of salts, called the *hydrogen theory* of acids, is more probable than that considering salts as made up of a base and an anhydride of an acid. But the hydrogen theory of acids is also a binary hypothesis, and does not even contradict the electro-chemical hypothesis, but is rather a modification of it. The binary theory dates from Rouelle and Lavoisier, the electro-chemical representation was developed with great power by Berzelius, and the hydrogen theory of acids is due to Davy and Liebig.

These hypothetical representations simplified and generalised the study of a complicated subject, and gave support to arguments, but when salts were in question it was equally convenient to follow one or the other of these hypotheses. But these theories were brought to bear on all other substances, on all compound substances. Those holding the binary and electro-chemical hypotheses searched for two anti-polar component parts, and endeavoured to express the process of chemical reactions by electro-chemical and similar differences. If zinc replaces hydrogen, they concluded that it is

amount, because, as forming the last stage of chemical reaction, they are capable of only a few chemical transformations, the energy of the elements being evolved (passing into heat) both in the formation of oxides and in their mutual combinations; hence in salts there remains but little energy. Organisms are bodies in which a series of uninterrupted, varied, and active chemical transformations proceed, whilst salts, which only enter into double decompositions between each other, are incapable of such changes. But organisms always contain salts. Thus, for instance, bones contain calcium phosphate, the juice of grapes, potassium tartrate (cream of tartar), certain lichens, calcium oxalate, and the shells of mollusca, calcium carbonate, &c. As regards water and soil, portions of the earth in which the chemical processes are less active, they are full of salts. Thus the waters of the oceans, and all others (Chap. I.), abound in salts, and in the soil, in the rocks of the earth's crust, in the upheaved lavas, and in the falling meteorites the salts of silicic acid, and

more electro-positive than hydrogen, whilst they forgot that hydrogen may, under different circumstances, displace zinc—for instance, at a red heat. Chlorine and oxygen were considered as being of opposite polarity to hydrogen because they easily combine with it, whilst one and the other are capable of replacing hydrogen, and, what is very characteristic, in the replacement of hydrogen by chlorine in carbon compounds, not only does the chemical character often remain unaltered, but even the external form remains unchanged, as Laurent and Dumas demonstrated. These considerations undermine the binary theory, and especially the electro-chemical system. An explanation of known reactions then began to be sought for not in the difference of the polarity of the different substances, but in the joint influences of all the elements on the properties of the compound formed. This is the reverse of the preceding hypotheses.

This reversal was not, however, limited to the destruction of the tottering foundations of the preceding theory; it projected a new doctrine, and laid the foundation for the whole contemporary direction of our science. This doctrine may be termed the unitary theory—that is, it is such as strictly acknowledges the joint influences of the elements in a compound substance, denies the existence of separate and contrary components in them, regards copper sulphate, for instance, as a strictly definite compound of copper, sulphur, and oxygen; then seeks for compounds which are analogous in their properties, and, placing them side by side, endeavours to express the influence of each element on the united properties of its compound. In the majority of cases it arrives at systems of consideration similar to those which are obtained by the above-mentioned hypotheses but in certain special cases the conclusions of the unitary theory are in entire opposition to the binary theory and its consequences. Cases of this kind are most often met with in the consideration of compounds of a more complex nature than salts, especially organic compounds containing hydrogen. But it is not in this revolution from an artificial to a natural system, important as it is, that the chief service and strength of the unitary doctrine lies. By a simple review of the vast store of data regarding the reactions of typical substances, it succeeded from its first appearance in establishing a new and important law, it introduced a new conception into science—namely, the conception of molecules, with which we shall soon become acquainted. The deduction of the law and of the conception of molecules has been verified by facts in a number of cases, and was the cause of the majority of chemists of our times deserting the binary theory and accepting the unitary theory, which forms the basis of the present work. Laurent and Gerhardt must be looked on as the propagators of this doctrine.

especially its double salt of potassium and aluminium, predominate. Saline substances also make up the composition of those limestones which often form mountain chains and whole thicknesses of the earth's strata, these consisting of calcium carbonate, CaCO_3 .

Thus we have seen oxygen in a free state and in various compounds of different degrees of stability, from the unstable salts, like Berthollet's salt and nitre, to the most stable silicon compounds, such as exist in granite. We saw an entirely similar gradation of stability in the compounds of water and of hydrogen. In all its aspects oxygen, as an element, as a substance, remains the same in itself in the most varied chemical states, just as a substance may appear in different physical (aggregate) states. But our notion of the immense variety of the chemical states in which oxygen can occur would not be completely understood if we did not make ourselves acquainted with it in the form in which it occurs in ozone and peroxide of hydrogen. In these it is most active, its energy seems to have increased. Then the fresh aspects of chemical correlations, and the variety of the forms in which matter can appear, stand out clearly. We will therefore consider these two substances somewhat in detail.

CHAPTER IV

OZONE AND HYDROGEN PEROXIDE. DALTON'S LAW

VAN-MARUM, during the last century, observed that oxygen in a glass tube, when subjected to the action of a series of electric sparks, acquired a peculiar smell and the property of combining with mercury at the ordinary temperature. This was afterwards confirmed by a number of fresh experiments. Even in the simple revolution of an electrical machine, when electricity diffuses into the air or passes through it, the peculiar and characteristic smell proper to ozone, proceeding from the action of the electricity on the oxygen of the atmosphere, is recognised. In 1840 Prof. Schönbein, of Basle, turned his attention to this odoriferous substance, and showed that it is also formed, with the oxygen evolved at the positive pole, in the decomposition of water by the action of a galvanic current; in the oxidation of phosphorus in damp air, and also in the oxidation of a number of substances, in consequence of which it is found in the atmosphere, although it is distinguished for its instability and capacity for oxidising other substances. The characteristic smell of this substance (which is always mixed with unaltered oxygen) gave it its name, from the Greek ὀζω, 'to emit an odour.' Schönbein pointed out the characteristic properties of *ozone*, and especially its power of oxidising many substances, even silver, acting like oxygen, but with this difference—that there are a number of substances on which oxygen does not act at the ordinary temperature, whilst ozone does so very energetically. It will be enough to point out, for instance, that it oxidises silver, mercury, charcoal, and iron with great energy at the ordinary temperature. It might be thought that ozone was some new substance, simple or compound, as it was at first supposed to be; but careful observations made in this direction have long led to the conclusion that ozone is nothing but oxygen altered in its properties. This is most strikingly proved by the complete transformation of oxygen containing ozone into ordinary oxygen when it is passed through a tube heated to 250°. Further, at a low temperature pure oxygen gives ozone when electric

sparks are passed through it (Marignac and De la Rive). Hence it is proved, by a method for its preparation from oxygen and by a method of its transformation into oxygen (synthesis and analysis), that ozone is that same oxygen with which we are already acquainted, only endowed with particular properties and in a particular state. However, by whatever method it be obtained, the amount of it contained in the oxygen is inconsiderable, generally only a few fractions of a per cent., rarely 2 per cent., and only under very propitious circumstances as much as 20 per cent. The reason of this must be looked for first in the fact that *ozone in its formation from oxygen absorbs heat*. If any substance be burnt in a calorimeter at the expense of ozonised oxygen, then more heat is evolved than when it is burnt in ordinary oxygen, and Berthelot showed that this difference is very large—namely, 29600 heat units correspond with every forty-eight parts by weight of ozone. This signifies that the transformation of forty-eight parts of oxygen into ozone is accompanied by the absorption of this quantity of heat, and that the reverse process evolves this quantity of heat. Therefore the passage of ozone into oxygen should take place easily (as an exothermal reaction), like combustion; and this is proved by the fact that at 250° ozone entirely disappears, forming oxygen. Any rise of temperature may thus bring about the breaking up of ozone, and as a rise of temperature takes place in the action of an electrical discharge, therefore there are in an electric discharge the conditions both for the preparation of ozone and for its destruction. Hence it is clear that the transformation of oxygen into ozone, *as a reversible reaction*, has a limit when a state of equilibrium is arrived at between the products of the two opposite reactions, that the phenomena of this transformation accord with the phenomena of *dissociation*, and that a fall of temperature should aid the formation of a large quantity of ozone.¹ Further, it is evident, from what has been said, that the best way of preparing ozone is not by electric sparks,² which raise the

¹ This conclusion, deduced by me as far back as 1878 (*Moniteur Scientifique*) by conceiving the molecules of ozone (see later) as more complex than those of oxygen, and ozone as containing a greater quantity of heat than oxygen, has been proved experimentally by the researches of Maillert (1880), which showed that the passage of a silent discharge through a litre of oxygen at 0° may form up to 14 milligrams of ozone, and at -30° up to 60 milligrams; but best of all in the determinations of Chappuis and Haute-feuille (1880), who found that at a temperature of -25° a silent discharge converted 20 p.c. of oxygen into ozone, whilst at 20° it was impossible to obtain more than 12 p.c., and at 100° less than 2 p.c. of ozone was obtained.

² A series of electric sparks may be obtained either by an ordinary electrical machine, the electrophorous machines of Holtz and Teploff, &c., Leyden jars, Ruhmkorff coils, or similar means, when the opposite electricities are able to accumulate at the terminals of conductors, and a discharge of sufficient electrical intensity passes through the non-conductors air or oxygen.

temperature, but by the employment of a continual discharge or flow of electricity—that is, to transform the oxygen by the action of a *silent discharge*.³ For this reason all *ozonisers* (which are of most varied construction), or forms of apparatus for the preparation of ozone from oxygen (or air) by the action of electricity, now usually consist of conductors (sheets of metal—for instance, tinfoil—or a solution of sulphuric acid with chromic acid, &c.) separated by thin glass surfaces placed at short distances from each other, and between which




FIG. 37.—Siemens' apparatus for preparing ozone by means of a silent discharge.

the oxygen or air to be ozonised is introduced and subjected to the action of a silent discharge.⁴ Thus in Siemens' apparatus (fig. 37) the

⁵ A silent discharge is such a combination of opposite statical (potential) electricities as takes place (generally between large surfaces) regularly, without sparks, slowly, and quietly (as in the dispersion of electricity). The discharge is only luminous in the dark: there is no observable rise of temperature, and therefore a larger amount of ozone is formed. But, nevertheless, on continuing the passage of a silent discharge through ozone it is destroyed. For the action to be observable a large surface is necessary, and consequently a powerful source of electrical potential. For this reason the silent discharge is best produced by a Ruhmkorff coil, as the most handy means of obtaining a considerable potential of statical electricity with the employment of the comparatively feeble current of a galvanic battery.

⁴ *V. Babo's apparatus* was one of the first constructed for ozonising oxygen by means of a silent discharge (and it is still one of the best). It is composed of a number (twenty and more) of long, thin capillary glass tubes closed at one end. A platinum wire, extending along their whole length, is introduced into the other end of each tube, and this end is then fused up round the wire, the end of which protrudes outside the tube. The protruding ends of the wires are arranged alternately in two sides in such a manner that on one side there are ten closed ends and ten wires. A bunch of such tubes (forty should make a bunch of not more than 1 c.m. diameter) is placed in a glass tube, and the ends of the wires are connected into two conductors, and are fused to the ends of the surrounding tube. The discharge of a Ruhmkorff coil is passed through these ends of the wires, and the dry air or oxygen to be ozonised is passed through the tube. If oxygen be passed through, ozone is obtained in large quantities, and free from oxides of

exterior of the tube *a* and the interior of the tube *b c* are coated with tinfoil and connected with the poles of a source of electricity (with the terminals of a Ruhmkorff's coil). A silent discharge passes through the thin walls of the glass cylinders *a* and *b c* over all their surfaces, and consequently, if oxygen be passed through the apparatus by the tube *d*, fused into the side of *a*, it will be ozonised in the annular space between *a* and *b c*. The ozonised oxygen escapes by the tube *e*, and may be introduced into any other apparatus.⁵

The properties of ozone obtained by such a method⁶ distinguish it in many respects from oxygen. Ozone very rapidly decolorises indigo, litmus, and many other dyes by oxidising them. Silver is oxidised by it at the ordinary temperature, whilst oxygen is not able to oxidise silver even at high temperatures ; a bright silver plate rapidly turns

nitrogen, which are partially formed when air is acted on. It is remarked that at low temperatures ozone is formed in large quantities. As ozone is acted on by corks and india-rubber, the apparatus should be made entirely of glass. With a powerful Ruhmkorff coil and forty tubes the ozonation is so powerful that the gas, when passed through a solution of iodide of potassium, not only sets the iodine free, but even oxidises it into potassium iodate, so that in five minutes the gas-conducting tube is choked up with crystals of the insoluble iodate.

⁵ In order to connect the ozoniser with any other apparatus it is impossible to make use of india-rubber, mercury, or cements, &c., because they are themselves acted on by, and act on, ozone. All connections must, as was first proposed by Brodie, be hermetically closed by sulphuric acid, which is not acted on by ozone. Thus, a cork is passed over the vertical end of a tube, over which a wide tube passes so that the end of the first tube protrudes above the cork ; mercury is first poured over the cork (to prevent its being acted on by the sulphuric acid), and then sulphuric acid is poured over the mercury. The protruding end of the first tube is covered by the lower end of a third tube immersed in the sulphuric acid.

⁶ The above-described method is the only one which has been well investigated. The admixture of nitrogen, or even of hydrogen, and especially of silicon fluoride, appears to aid the formation and preservation of ozone. Amongst other methods for preparing ozone we may mention the following :—1. In the action of oxygen on phosphorus at the ordinary temperature a portion of the oxygen is converted into ozone. At the ordinary temperature a stick of phosphorus, partially immersed in water and partially in air in a large glass vessel, causes the air to acquire the odour of ozone. It must further be remarked that if the air be left for long in contact with the phosphorus, or without the presence of water, the ozone formed is destroyed by the phosphorus. 2. By the action of sulphuric acid on peroxide of barium. If the latter be covered with strong sulphuric acid (the acid, if diluted with only one-tenth of water, does not give ozone), then at a low temperature the oxygen evolved contains ozone, and in much greater quantities than that in which ozone is obtained by the action of electric sparks or phosphorus. 3. Ozone may also be obtained by decomposing strong sulphuric acid by potassium manganate, especially with the addition of barium peroxide. Goussier-Besanez stated (but it requires confirmation) that ozone is formed in the slow evaporation of large quantities of water. In the near proximity of salt-gardens (salterns) the atmosphere is considerably richer in ozone than in the surrounding neighbourhood. In connection with this is the fact that the air of the sea-shore is rich in ozone. Ozone is also stated to be formed in the ordinary process of the respiration of plants. This is, however, denied by many to be the case.

black (from oxidation) in ozonised oxygen. It is rapidly absorbed by mercury, forming oxide; it transforms the lower oxides into higher—for instance, sulphurous anhydride into sulphuric, nitrous oxide into nitric, arsenious anhydride (As_2O_3) into arsenic anhydride (As_2O_5) &c.⁷ But what is especially characteristic in ozone is the decomposing action it exerts on potassium iodide. Oxygen does not act on it, but ozone passed into a solution of potassium iodide *liberates iodine*, whilst the potassium is obtained as caustic potash, which remains in solution, $2\text{KI} + \text{H}_2\text{O} + \text{O} = 2\text{KHO} + \text{I}_2$. As the presence of minute traces of free iodine may be discovered by means of starch paste, with which it forms a very dark blue coloured substance, a mixture of potassium iodide with starch paste will detect the presence of very small traces of ozone.⁸ Ozone is destroyed or converted into ordinary oxygen not only by heat, but also by long keeping, especially in the presence of alkalis, peroxide of manganese, chlorine, &c.

Hence *ozone*, although it has the same *composition as oxygen*, differs

⁷ Ozone takes up the hydrogen from hydrochloric acid; the chlorine is set free, and can dissolve gold. Chromium and iodine are directly oxidised by ozone, but not by oxygen, and so also with a number of other substances. Ammonia, NH_3 , is oxidised by ozone into ammonium nitrite (and nitrate), $2\text{NH}_3 + \text{O}_3 = \text{NH}_4\text{NO}_2 + \text{H}_2\text{O}$, and therefore a drop of ammonia, on falling into the gas, gives a thick cloud of the salts formed. Ozone converts lead oxide into peroxide, and suboxide of thallium (which is colourless) into oxide (which is brown), so that this reaction is made use of for discovering the presence of ozone. Lead sulphide, PbS , is converted into sulphate, PbSO_4 , by ozone. A neutral solution of manganese sulphate gives a precipitate of manganese peroxide, and an acid solution may be oxidised into permanganic acid, HMnO_4 . With respect to the oxidising action of ozone on organic substances, it may be mentioned that with ether, $\text{C}_4\text{H}_{10}\text{O}$, ozone gives ethyl peroxide, which is capable of decomposing with explosion (according to Berthelot), and is decomposed by water into alcohol, $2\text{C}_2\text{H}_6\text{O}$, and hydrogen peroxide, H_2O_2 .

⁸ This reaction is the one usually made use of for detecting the presence of ozone. In the majority of cases paper is soaked in solutions of potassium iodide and starch. Such *ozonometrical* or iodised starch-paper when damp turns blue in the presence of ozone, and the tint obtained varies considerably, according to the length of time it is exposed and to the amount of ozone present. The amount of ozone in a given gas may even to a certain degree be judged by the shade of colour acquired by the paper, if preliminary tests be made.

Test-paper for ozone is prepared in the following manner:—One gram of neutral potassium iodide is dissolved in 100 grams of distilled water; 10 grams of starch are then shaken up in the solution, and the mixture is boiled until the starch is converted into a jelly. This jelly is then smeared over blotting-paper and left to dry. The colour of iodised starch-paper is changed not only by the action of ozone, but of many other oxidisers; for example, by the oxides of nitrogen and hydrogen peroxide. Houzeau proposed soaking common litmus-paper with a solution of potassium iodide, which in the presence of iodine would turn blue, owing to the formation of KHO. In order to find if the blue colour is not produced by an alkali (ammonia) in the gas, a portion of the paper is not soaked in the potassium iodide, but moistened with water; this portion will then also turn blue if ammonia be present. A reagent for distinguishing ozone from hydrogen peroxide with certainty is not known, and therefore these substances in very small quantities (for instance, in the atmosphere) may easily be confounded.

from it in stability, and by the fact that it oxidises a number of substances very energetically at the ordinary temperature. In this respect ozone resembles the oxygen of certain unstable compounds, or oxygen at the moment of its liberation.

In ordinary oxygen and ozone we see an example of one and the same substance, in this case an element, appearing in two states. This indicates that the properties of a substance, and even of an element, may vary without its composition varying. Very many such cases are known. Such cases of a chemical transformation which determines a difference in the properties of one and the same element are termed isomerism. The cause of isomerism evidently lies deep within the essence of the nature of a substance, and its investigation has already led to a number of results of unexpected importance and of immense scientific significance. It is easy to understand the difference between substances containing different elements or the same elements in different proportions. That a difference should exist in the latter case necessarily follows, if, as our knowledge compels us, we admit that there is a radical difference in the simple bodies or elements. But when the quality and quantity of the elements (the composition) in a substance are the same and yet its properties are different, then it becomes clear that the conceptions of the elements and of the composition of compounds, alone, are insufficient for the expression of all the diversity of the properties of the matter of nature. Something else, still more profound and internal than the composition of substances, must, judging from isomerism, determine the properties and transformation of substances.

On what is the isomerism of ozone with oxygen, and the peculiarities of ozone, dependent? In what, besides the store of energy, which in its way expresses the peculiarities of ozone, resides the causes of its difference from oxygen? These questions for long occupied the minds of investigators, and were the motive for the most varied, exact, and accurate researches, which were chiefly directed to the study of the volumetric relations exhibited by ozone. In order to acquaint the reader with the previous researches of this kind, I cite the following from a memoir by Soret, in the 'Transactions of the French Academy of Sciences' for 1866:

'Our present knowledge of the volumetric relations of ozone may be expressed at the present time in the following manner:

'1. "Ordinary oxygen in changing into ozone under the action of electricity shows a diminution in volume." This was discovered by Andrews and Tait.

'2. "In acting on ozonised oxygen with potassium iodide and other substances capable of being oxidised, we destroy the ozone, but the

volume of the gas remains unchanged." Indeed, the researches of Andrews, Soret, v. Babo, and others showed that the quantity of oxygen absorbed by the potassium iodide is equal to the original contraction of the volume of the oxygen—that is, in the absorption of the ozone the volume of the gas remains unchanged. From this it might be imagined that ozone, so to say, does not occupy any room—is indefinitely dense.

'3. "By the action of heat ozonised oxygen increases in volume, and is transformed into ordinary oxygen. This increase in volume corresponds with the quantity of oxygen which is given up to the potassium iodide in its decomposition" (the same observers).

'4. These indubitable experimental results lead to the conclusion that ozone is denser than oxygen, and that ozone in its oxidising action gives off that portion of its substance which distinguishes it by its density from ordinary oxygen.'

If we imagine (says Weltzien) that n volumes of ozone consist of n volumes of oxygen combined with m volumes of the same substance, and that ozone in oxidising gives up m volumes of oxygen and leaves n volumes of oxygen gas, then all the above facts can be explained; otherwise it must be supposed that ozone is indefinitely dense. 'In order to determine the density of ozone (we again cite Soret) recourse cannot be had to the direct determination of the weight of a given volume of the gas, because ozone cannot be obtained in a pure state. It is always mixed with a very large quantity of oxygen. It was necessary, therefore, to have recourse to such substances as would absorb ozone without absorbing oxygen and without destroying the ozone. Then the density might be deduced from the decrease of volume produced in the gas by the action of this solvent in comparison with the quantity of oxygen given up to potassium iodide. Advantage must also be taken of the determination of the increase of volume produced by the action of heat on ozone, if the volume previously occupied by the ozone before heating be known.' Soret found two such substances, turpentine and oil of cinnamon. 'Ozone disappears in the presence of turpentine. This is accompanied by the appearance of a dense vapour, which fills a vessel of small capacity (0·14 litre) to such an extent that it is impenetrable to direct sun-rays. On then leaving the vessel at rest, it is observed that the cloud of vapour settles; the clearing is first remarked at the upper portion of the vessel, and the brilliant colours of the rainbow are seen on the edge of cloud of vapour.' Oil of cinnamon—that is, the volatile or odoriferous substance of the well-known spice, cinnamon—gives under similar circumstances the same kind of vapours, but they are much less voluminous. On

measuring the gaseous volume before and after the action of both volatile oils, a considerable decrease is remarked. On applying all the necessary corrections (for the solubility of oxygen in the oily liquids named above, for the tension of their vapour, for the change of pressure, &c.) and making a series of comparative determinations, Soret obtained the following result: two volumes of ozone capable of being dissolved, when destroyed (by heating a wire to a red heat by a galvanic current) increase by one volume. Hence it is evident that in the formation of ozone three volumes of oxygen give two volumes of ozone—that is, its density (referred to hydrogen)=24.

The observations and determinations of Soret showed that ozone is heavier than oxygen, and even than carbonic anhydride (because ozonised oxygen passes from fine orifices more slowly than oxygen and than its mixtures with carbonic anhydride), although lighter than chlorine (it flows more rapidly from such orifices than chlorine), and they also indicated that *ozone is one and a half times denser than oxygen*, which may be expressed by designating a molecule of oxygen by O_2 and of ozone by O_3 ; and which likens ozone to compound substances⁹ formed by oxygen, as, for instance, CO_2 , SO_4 , OO_2 , NO_2 , &c. This explains the chief differences between ozone and oxygen, and the cause of the isomerism, and at the same time leads one to expect¹⁰ that ozone, as a gas which is denser than oxygen, would be liquefied

⁹ Ozone is, so to say, an oxide of oxygen, just as water is an oxide of hydrogen. Just as aqueous vapour is composed of two volumes of hydrogen and one volume of oxygen, which on combining condense into two volumes of aqueous vapour, so also two volumes of oxygen are combined in ozone with one volume of oxygen to give two volumes of ozone. In the action of ozone on different substances it is only that portion of its composition by which it differs from ordinary oxygen that combines with the other bodies, and therefore, under these circumstances, the volume of the ozonised oxygen does not change. There were two volumes of ozone; one-third of its weight is parted with, and there remain two volumes of oxygen.

The above observations of Soret on the property of turpentine for dissolving ozone, together with Schönbein's researches on the formation of ozone in the oxidation of turpentine and of similar volatile vegetable oils (entering into the composition of *perfumes*), also explain the action of this ethereal oil on a great many substances. It is known that turpentine oil, when mixed with many substances, promotes their oxidation. In this case it probably not only itself promotes the formation of ozone, but also dissolves ozone from the atmosphere, and thus acquires the property of oxidising many substances. It bleaches linen and cork, decolorises indigo, promotes the oxidation and hardening of boiled linseed oil, &c. These properties of turpentine oil are made use of in practice. Dirty linen and many stained materials are easily cleaned by turpentine, not only because it dissolves the grease, but also because it oxidises. The admixture of turpentine with drying (boiled) oil, oil-colours, and lacs aids their rapid drying because it attracts ozone. Various oils occurring in plants, and entering into the composition of perfumes and various scent extracts, also act as oxidisers. They act in a similar manner to oil of turpentine and oil of cinnamon. This perhaps explains the refreshing influence they have in scents and other similar preparations, and also the salubrity of the air of pine forests.

¹⁰ The densest, most complex, and heaviest particles of matter should, under equal

much more easily. This was actually shown to be the case, in 1880, by Chappuis and Hautefeuille in their researches on the *physical properties of oxygen*. Its absolute boiling point is about -106° , and consequently compressed and refrigerated ozone when rapidly expanded gives drops, is liquefied. Liquid and compressed ¹¹ ozone is blue. In dissolving in water ozone partly passes into oxygen. Ozone violently explodes when suddenly compressed and heated, changing into ordinary oxygen, and evolving, like all explosive substances,¹² that heat which distinguishes it from oxygen.

Thus, judging by what has been said above, ozone should be formed in nature not only in the many processes of oxidation which go on, but also by the condensation of atmospheric oxygen. The significance of ozone in nature has often arrested the attention of observers. There is a series of ozonometrical observations which show the different amounts of ozone in the air at different localities, at different times of the year, and under different circumstances—for instance, on the appearance of epidemics. But the observations made in this direction cannot be considered as sufficiently exact, because the methods in use for determining ozone were not quite accurate. It is however indisputable ¹³ that the amount of ozone in the atmosphere is subject to variation; that the air of dwellings contains no ozone (it disappears in oxidising organic matter); that the air of fields and forests always contains ozone, or substances (peroxide of hydrogen) which act like it; that the amount of ozone increases after storms; and that miasms, &c., are destroyed by ozonising the atmosphere. It may be imagined that the influence exerted by ozone on animal life is due to the fact that it easily oxidises organic substances, and miasms are formed of organic substances and the germs of organisms, which are easily changed and oxidised. Indeed, many miasms—for instance,

conditions, evidently be less capable of passing into a state of gaseous movement, should sooner attain a liquid state, and have a greater cohesive force.

¹¹ The blue colour proper to ozone may be seen through a tube one metre long containing oxygen 10 p.c. ozonised. The density of liquid ozone has not, as far as I am aware, been determined.

¹² All explosive bodies and mixtures (gunpowder, detonating gas, &c.) evolve heat in exploding (in giving a greater number of molecules from one molecule, and sometimes several substances from one substance, as in the explosion of *nitro-compounds*; see later)—that is, the reactions which accompany explosions are exothermal. In this manner ozone in decomposing evolves latent heat, although generally heat is absorbed in decomposition. This shows the meaning and cause of explosion.

¹³ In Paris it has been found that the further from the centre of the town the greater the amount of ozone in the air. The reason of this is evident: in a city there are many conditions for the destruction of ozone. This is why we distinguish country air as being fresh. In spring the air contains more ozone than in autumn; the air of fields more than the air of towns.

the volatile substance of decomposing organisms—are clearly destroyed or changed not only by ozone, but also by many powerfully oxidising substances, such as chlorine with water, potassium permanganate, and the like.¹⁴

Thus in ozone we see (1) the capacity of elements (and it must be all the more marked in compounds) of changing in properties without altering in composition; this is termed isomerism;¹⁵ (2) the capacity of elements for arranging themselves in molecules of different densities; this forms a special case of isomerism called *polymerism*; (3) the capacity of oxygen for appearing in a still more intense and energetic chemical state than that in which it occurs in ordinary gaseous oxygen; and (4) the formation of unstable equilibria, or chemical states, which are expressed both by the ease with which ozone acts as an oxidiser and in its capacity for decomposing with explosion.¹⁶

Hydrogen peroxide.—Many of those properties which we have seen in ozone belong also to a peculiar substance containing oxygen and hydrogen, and called hydrogen peroxide, or oxygenated water. This substance was discovered in 1818 by Thénard. When heated it is decomposed into water and oxygen, evolving as much oxygen as is contained in the water remaining after the decomposition. That portion of oxygen by which hydrogen peroxide differs from water behaves in a number of cases just like the active oxygen in ozone, which distinguishes it from ordinary oxygen. In H_2O_2 , and in O_3 , one atom of oxygen acts in a powerfully oxidising manner, and on separating out

¹⁴ The oxidising action of ozone may be taken advantage of for technical ends; for instance, for destroying colouring matters. It has even been employed for bleaching tissues and for the rapid preparation of vinegar, although these methods have not yet received wide application.

¹⁵ Isomerism in elements is termed *allotropism*.

¹⁶ A number of substances resemble ozone in one or another of these respects. Thus cyanogen, C_2N_2 , nitrogen chloride, &c., decompose with an explosion and evolution of heat. Nitrous anhydride, N_2O_5 , forms a blue liquid like ozone, and in a number of cases oxidises like ozone. Red phosphorus is to white phosphorus, in a certain sense, what oxygen is to ozone, and in other respects the reverse; this is also a case of allotropism. Thus a chemical analogy is diffused in different and most varied directions, and it is only after an acquaintance with the diverse relations of substances that an idea can be formed of the complexity of chemical changes, whilst their general system is still wanting; that is to say, there is nothing analogous to and explaining the correlation of liquid to gaseous substances. But there is reason to think that in this case also an explanation will arise with the accumulation of data, as we see from the fact that the conception of dissociation explained in the simplest manner a number of chemical relations which without it were not at all clear. It should be here observed that the transition between oxygen and ozone under the conditions of a silent discharge forms a reversible reaction which is subject to the conception of dissociation, whilst, exempt from the conditions of a silent discharge, the passage of ozone into oxygen is not reversible, and forms an instance of decomposition in the strictest sense.

it leaves H_2O or O_2 , which do not act so sharply, although they still contain oxygen.¹⁷ Both contain the oxygen in a compressed state, so to speak, and when freed from pressure by the forces (internal) of the elements in another substance, this oxygen is easily evolved, and therefore acts like oxygen at the moment of its liberation. Both substances in decomposing, with the separation of a portion of their oxygen, *evolve* heat, while an absorption of heat is usually required for decomposition.

Hydrogen peroxide is formed under many circumstances by combustion and oxidation, but in very limited quantities ; thus, for instance, it is sufficient to shake up zinc with sulphuric acid, or even with water, to remark the formation of a certain quantity of hydrogen peroxide in the water.¹⁸ From this cause, probably, a series of diverse oxidation processes are accomplished in nature, and, according to Prof. Schöne, of Moscow, hydrogen peroxide occurs in the atmosphere, although in variable and small quantities, and probably its formation is connected with ozone, with which it has much in common. The usual case of the formation of hydrogen peroxide, and the means by which it may be in-

¹⁷ It is evident that there is a want of words here for distinguishing oxygen, O , as an ultimate *element*, from oxygen, O_2 , as a *free element*. It should be called oxygen gas, did not habit and the length of the expression render it inconvenient.

¹⁸ Schönbein states that the formation of hydrogen peroxide is to be remarked in every oxidation in water or in the presence of aqueous vapour. According to Struve, hydrogen peroxide is contained in snow and in rain-water, and its formation, together with ozone and ammonium nitrate, is even probable in the processes of respiration and combustion. A solution of tin in mercury, or liquid tin amalgam, when shaken up in water containing sulphuric acid gives rise to the formation of hydrogen peroxide, whilst iron under the same circumstances does not give rise to its formation. The presence of small quantities of hydrogen peroxide in these and similar cases is recognised by many reactions. Amongst them, its action on *chromic acid* in the presence of ether is very characteristic. Hydrogen peroxide converts the chromic acid into a higher oxide, Cr_2O_7 , which is of a dark-blue colour, and dissolves in ether. This ethereal solution is to a certain degree stable, and therefore the presence of hydrogen peroxide may be recognised by mixing the liquid to be tested with ether and adding several drops of a solution of chromic acid. On shaking the mixture the ether dissolves the higher oxide of chromium which is formed, and acquires a blue colour. The formation of hydrogen peroxide in the combustion and oxidation of substances containing or evolving hydrogen must be understood in the sense of the conception, to be considered later, of molecules occupying equal volumes in a gaseous state. At the moment of its evolution a molecule H_2 combines with a molecule O_2 and gives H_2O_2 . As this substance is unstable, a large proportion of it is decomposed, a small amount only remaining unchanged. If it is obtained, water is easily formed from it ; this reaction evolves heat, and the reverse action is not very probable. Direct determinations show that the reaction $\text{H}_2\text{O}_2 = \text{H}_2\text{O} + \text{O}$ evolves 22000 heat units. From this it will be understood how easy is the decomposition of hydrogen peroxide, as well as the fact that a number of substances which are not directly oxidised by oxygen are oxidised by hydrogen peroxide and by ozone, which also evolves heat on decomposition. Such a representation of the origin of hydrogen peroxide has been developed by me since 1870. In recent times Traube has pronounced a similar opinion.

directly obtained,¹⁹ is by the double decomposition of an acid and the peroxides of certain metals, especially those of potassium, calcium, and barium.²⁰ Among these peroxides, that of barium is the most conveniently obtained, it being enough, as we saw when speaking of oxygen (Chap. III.), to heat the anhydrous oxide of barium to a red heat in a current of air or oxygen; or, better still, to heat it with potassium chlorate, and then to wash away the potassium chloride also formed.²¹ Barium peroxide gives hydrogen peroxide by the action of acids in the cold.²² The process of decomposition is very clear in this case; the hydrogen of the acid replaces the barium of the peroxide, a barium salt of the acid being formed, while the hydrogen peroxide formed by the

¹⁹ The formation of hydrogen peroxide from barium peroxide by a method of double decomposition is an instance of a number of *indirect methods of preparation*. A substance A does not combine with B, but AB is obtained from AC in its action on BD (see Introduction) when CD is formed. Water does not combine with oxygen, but as a hydrate of acids it acts on the compound of oxygen with barium oxide, because this oxide gives a salt with an acid anhydride; or, what is the same, hydrogen with oxygen does not directly form hydrogen peroxide, but when combined with a haloid (for example, chlorine), under the action of barium peroxide, BaO_2 , it leads to the formation of a salt of barium and H_2O_2 . It is to be remarked that the passage of barium oxide, BaO , into the peroxide, BaO_2 , is accompanied by the *evolution* of 121000 heat units per 16 parts of oxygen by weight combined, and the passage of H_2O into the peroxide H_2O_2 does not proceed directly, because it would be accompanied by the *absorption* of 22000 units of heat by 16 parts by weight of oxygen combined. Barium peroxide, in acting on an acid, evidently evolves less heat than the oxide, and it is this difference of heat that is absorbed in the hydrogen peroxide. Its energy is obtained from the energy evolved in the formation of the salt of barium.

²⁰ Peroxides of lead and manganese, and other analogous peroxides (see Chapter III., Note 9), do not give hydrogen peroxide under these conditions, but yield chlorine with hydrochloric acid.

²¹ The impure barium peroxide obtained in this manner may be easily purified. For this purpose it is dissolved in a dilute solution of nitric acid. There will always remain a certain quantity of an insoluble residue, from which the solution is separated by filtration. The solution will contain not only the compound of the barium peroxide, but also a compound of the barium oxide itself, a certain quantity of which always remains uncombined with oxygen. The acid compounds of the peroxide and oxide of barium are easily distinguishable by their stability. The peroxide gives an unstable compound, and the oxide a stable salt. By adding an aqueous solution of barium oxide to the resultant solution, the whole of the peroxide contained in the solution may be precipitated as a pure aqueous compound. The first portions of the precipitate will consist of impurities—for instance, oxide of iron. The barium peroxide separates out, and is collected on a filter and washed; it then forms a substance having an entirely definite composition, $\text{BaO}_2 \cdot 8\text{H}_2\text{O}$, and is very pure. Pure hydrogen peroxide should always be prepared from such purified barium peroxide.

²² In the cold, strong sulphuric acid with barium peroxide gives ozone; when diluted with a certain amount of water it gives oxygen (see Note 6), and hydrogen peroxide is only obtained by the action of very weak sulphuric acid. The acids hydrochloric, hydrofluoric, carbonic, and hydrosilicofluoric, and others, when diluted with water also give hydrogen peroxide with barium peroxide. Professor Schöne, who investigated hydrogen peroxide with great detail, showed that it is formed by the action of many of the above-mentioned acids on barium peroxide.

barium peroxide remains in solution.²³ The reaction is expressed by the equation $\text{BaO}_2 + \text{H}_2\text{SO}_4 = \text{H}_2\text{O}_2 + \text{BaSO}_4$. It is best to take a weak cold solution of sulphuric acid and to almost saturate it with barium peroxide, so that a small excess of acid remains; insoluble barium sulphate is formed. A more or less dilute aqueous solution of hydrogen peroxide is obtained. This solution may be concentrated in a vacuum over sulphuric acid. In this way the water may even be entirely evaporated from the solution of the hydrogen peroxide; only in this case it is necessary to work at a low temperature, and not to keep the peroxide for long in the rarefied atmosphere, as otherwise it decomposes.²⁴

When pure, hydrogen peroxide is a colourless liquid, without smell, and having a very unpleasant taste—such as belongs to the salts of many metals—the so-called ‘metallic’ taste. Water held in zinc vessels has this taste, which is probably due to its containing hydrogen peroxide. The tension of the vapour of hydrogen peroxide is less than that of aqueous vapour; this enables its solutions to be concentrated in a vacuum. The specific gravity of anhydrous hydrogen peroxide is 1.455. Pure hydrogen peroxide decomposes, with the evolution of oxygen, when heated even to 20° (by the action of light?). But the more dilute its aqueous solution the more stable it is. Very weak solutions may be distilled without the hydrogen peroxide decomposing. It decolorises solutions of litmus and turmeric, and acts in a similar manner on many colouring matters of organic origin (for which reason it is employed for bleaching tissues).

Many substances decompose hydrogen peroxide, forming water and oxygen, without apparently suffering any change. In this case substances in a state of fine division evince an incomparably quicker action

²³ With the majority of acids, that salt of barium which is formed remains in solution; thus, for instance, by employing hydrochloric acid, hydrogen peroxide and barium chloride remain in solution. Complicated processes would be required to obtain pure hydrogen peroxide from such a solution. It is much more convenient to take advantage of the action of carbonic anhydride on the pure hydrate of barium peroxide. For this purpose the hydrate is stirred up in water, and a rapid stream of carbonic anhydride is passed through the water. Barium carbonate, insoluble in water, is formed, and the hydrogen peroxide remains in solution, so that it may be separated from the carbonate by filtering only. On a large scale hydrofluosilicic acid is employed, because its barium salt is also insoluble in water.

²⁴ Hydrogen peroxide may be extracted from very dilute solutions by means of ether, which dissolves it, and when mixed with it the hydrogen peroxide may even be distilled. A solution of hydrogen peroxide in water may be enriched by cooling it to a low temperature, when the water crystallises out—that is, is converted into ice—whilst the hydrogen peroxide remains in solution, as it only freezes at very low temperatures. It must be observed that hydrogen peroxide, in a strong solution in a pure state, is exceedingly unstable even at the ordinary temperature, and therefore it must be preserved in vessels always kept cold, as otherwise it evolves oxygen and forms water.

than compact masses, from which it is evident that the action is here based on contact (*see* Introduction). It is enough to bring hydrogen peroxide into contact with charcoal, gold, the peroxide of manganese or lead, the alkalis, metallic silver, and platinum, to bring about the above decomposition.²⁵ Besides which, hydrogen peroxide forms water and parts with its oxygen with great ease to a number of substances which are capable of being oxidised or of combining with oxygen, and in this respect is very like ozone and other *powerful oxidisers*.²⁶ To the number of contact phenomena, which are so natural to hydrogen peroxide, as a substance which is unstable and easily decomposable with the evolution of heat, must be referred the following—that in the presence of many substances containing oxygen it evolves, not only its own oxygen, but also that of the substances which are brought into contact with it—that is, *it acts in a reducing manner*. It behaves thus with ozone, the oxides of silver, mercury, gold and platinum, and lead peroxide. The oxygen in these substances is not stable, and therefore the feeble influence of contact is enough to destroy its position.

²⁵ As the result of careful research, certain of the *catalytic* or contact phenomena have been subjected to exact explanation, which shows the participation of a substance present in the process of a reaction, whilst, however, it does not alter the series of changes proceeding from mechanical actions only. Professor Schöne, of the Petroffsky Academy, has already explained a number of reactions of hydrogen peroxide which previously were not understood. Thus, for instance, he showed that with hydrogen peroxide, alkalis give peroxides of the alkaline metals, which combine with the remaining hydrogen peroxide, forming unstable compounds which are easily decomposed, and therefore alkalis evince a decomposing (catalytic) influence on solutions of hydrogen peroxide. Only acid solutions of hydrogen peroxide, and then only dilute ones, can be preserved well.

²⁶ *Hydrogen peroxide*, as a substance containing much oxygen (namely, 16 parts to one part by weight of hydrogen), exhibits many *oxidising reactions*. Thus, it oxidises arsenic, converts lime into calcium peroxide, the oxides of zinc and copper into peroxides; it parts with its oxygen to many sulphides, converting them into sulphates, &c. So, for example, it converts black lead sulphide, PbS , into white lead sulphate, PbSO_4 , copper sulphide into copper sulphate, and so on. The restoration of old oil-paintings by hydrogen peroxide is based on this action. Oil-colours are usually admixed with white lead, and in many cases the colour of oil-paints becomes darker in process of time. This is partly due to the sulphuretted hydrogen contained in the air, which acts on white lead, forming lead sulphide, which is black. The intermixture of the black colour darkens the rest. In cleaning a picture with a solution of hydrogen peroxide, the black lead sulphide is converted into white sulphate, and the colours brighten owing to the disappearance of the black substance which previously darkened them. Hydrogen peroxide oxidises with particular energy substances containing hydrogen and capable of easily parting with it to oxidising substances. Thus it decomposes hydriodic acid, setting the iodine free and converting the hydrogen it contains into water; it also decomposes sulphuretted hydrogen in exactly the same manner, setting the sulphur free. Starch paste with potassium iodide is not, however, directly coloured by peroxide of hydrogen in the entire absence of free acids; but the addition of a small quantity of iron sulphate (green vitriol) or of lead acetate to the mixture is enough to entirely blacken the paste. This is a very sensitive reagent (test) for peroxide of hydrogen, as is also the test with chromic acid and ether (*see* Note 8).

Hydrogen peroxide, especially in a concentrated form, in contact with these substances, evolves an immense quantity of oxygen, so that an explosion takes place and an exceedingly powerful evolution of heat is observed if hydrogen peroxide in a concentrated form be made to fall in drops upon these substances in dry powder. An exactly similar decomposition takes place in dilute solutions.²⁷

Just as a whole series of metallic compounds, and especially the oxides and their hydrates, correspond with water, so also there are many substances analogous to hydrogen peroxide. Thus, for instance, calcium peroxide is related to hydrogen peroxide in exactly the same way as calcium oxide or lime is related to water. In both cases the hydrogen is replaced by a metal—namely, by calcium. But it is most important to remark that the nearest approach to the properties of hydrogen peroxide is afforded by a non-metallic element, chlorine; its action on colouring matters, its capacity for oxidising, and for evolving oxygen from many oxides, is analogous to that exhibited by hydrogen peroxide. Even the very formation of chlorine is closely analogous to the formation of peroxide of hydrogen; chlorine is obtained from manganese peroxide, MnO_2 , and hydrochloric acid, HCl , and hydrogen peroxide from barium peroxide, BaO_2 , and the same acid. The result in one case is essentially water, chlorine, and manganese chloride; and in the other case there is produced barium chloride and hydrogen peroxide. Hence water + chlorine corresponds with hydrogen peroxide, and the action of chlorine in the presence of water is analogous to the action of hydrogen peroxide. This analogy between chlorine and hydrogen peroxide is expressed in the conception of an aqueous radicle, which (Chap. III.) has been already mentioned. *This aqueous radicle* (or hydroxyl) is that which is left from water if it be imagined as deprived of half of its hydrogen. According to this method of expression, caustic soda will be a compound of sodium with the aqueous radicle, because it is formed from water with the evolution of half the hydrogen. This is expressed by the following formulæ: water, H_2O , caustic soda, NaHO ,

²⁷ To explain the phenomenon an hypothesis has been put forward by Brodie, Clausius, and Schönbein which supposes ordinary oxygen to be an electrically neutral substance, composed of, so to speak, two electrically opposite aspects of oxygen—positive and negative. It is supposed that hydrogen peroxide contains one kind of such polar oxygen, whilst in the oxides of the above-named metals the oxygen is of opposite polarity. It is supposed that in the oxides of the metals the oxygen is electro-negative, and in hydrogen peroxide electro-positive, and that on the mutual contact of these substances ordinary neutral oxygen is evolved as a consequence of the mutual attraction of the oxygens of opposite polarity. Brodie admits the polarity of oxygen in combination, but not in an uncombined state, whilst Schönbein supposes uncombined oxygen to be polar also, considering ozone as electro-negative oxygen. The supposition of the oxygen of ozone being other than that of hydrogen peroxide is contradicted by the fact that in acting on barium peroxide strong sulphuric acid forms ozone, and dilute acid forms hydrogen peroxide.

just as hydrochloric acid is HCl and sodium chloride NaCl . Hence the aqueous radicle HO is a compound radicle, just as chlorine, Cl , is a simple radicle. They give hydrogen compounds, HHO , water, and HCl , hydrochloric acid; sodium compounds, NaHO and NaCl , and a whole series of analogous compounds. Free chlorine in this sense will be ClCl , and hydrogen peroxide HOHO , which indeed expresses its composition, because it contains twice as much oxygen as water.

Thus in ozone and hydrogen peroxide we see examples of very unstable, easily decomposable (by time, spontaneously, and on contact) substances, full of the energy necessary for change,²⁸ capable of being easily reconstructed (in this case decomposing with the evolution of heat); therefore they are examples of *unstable chemical equilibria*. If a substance exists, it signifies that it already presents a certain form of equilibrium between those elements of which it is built up. But chemical, like mechanical, equilibria exhibit different degrees of stability or solidity.²⁹

²⁸ The lower oxides of nitrogen and chlorine and the higher oxides of manganese are also formed with the absorption of heat, and therefore, like hydrogen peroxide, act in a powerfully oxidising manner, and are not formed by the same methods as the majority of other oxides. It is evident that, being endowed with a richer store of energy (acquired in combination or absorption of heat), such substances, compared with others poorer in energy, will exhibit the greatest diversity of cases of chemical action with other substances.

²⁹ If the point of support of a body lies in a vertical line below the centre of gravity, the equilibrium is entirely unstable. If the centre of gravity lies below the point of support, the state of equilibrium is very stable, and a vibration may take place about this position of stable equilibrium, as in a pendulum or balance, which ends in the body passing to its position of stable equilibrium. But if, keeping to the same mechanical example, the body be supported not on a point, in the geometrical sense of the word, but on a small plane, then the state of unstable equilibrium may be preserved, unless destroyed by external influences. Thus a man stands upright supported on the plane, or several points of the surfaces of his feet, having the centre of gravity above the points of support. Vibration is then possible, but it is limited, otherwise on passing outside the limit of possible equilibrium another more stable position is attained about which vibration becomes more possible. A prism immersed in water may have several more or less stable positions of equilibrium. It is the same with the atoms in molecules. Some molecules present a state of more stable equilibrium than others. Hence from this simple comparison it will be already clear that the stability of molecules may vary considerably, that one and the same elements, taken in the same number, may give isomerides of different stability, and, lastly, that there may exist states of equilibria which are so unstable, so ephemeral, that they will only arise under particularly special conditions—such, for example, as certain hydrates mentioned in the first chapter (*see* Notes 57, 67, and others). And if in one case the instability of a given state of equilibrium is expressed by its instability with a change of temperature or physical state, then in other cases it is expressed by the ease of decomposition under the influence of contact or of the purely chemical influence of other substances. However clearly the greater or less stability of the elementary structure of substances be depicted to us in these general considerations, still at present there is no possibility of presenting them in a sufficiently concrete form to enable purely mechanical conceptions to be applied to them; that is, to subject them to mathematical analysis, and to master the subject to such an extent

Besides this, hydrogen peroxide indicates another side of the subject which is not less important, and is much clearer and more general.

Hydrogen unites with oxygen in two degrees of oxidation: water or hydrogen oxide, and oxygenated water or hydrogen peroxide; for a given quantity of hydrogen the peroxide contains twice as much oxygen as does water. This is a fresh example confirming the correctness of the law of multiple proportions, of which we have already made mention in speaking of the water of crystallisation of salts. Now we can formulate this law with entire clearness—the *law of multiple proportions*. *If two radicles A, and B (either simple or compound substances), unite together to form several compounds, A_nB_m , A_rB_t . . . , then having expressed the compositions of all these compounds in such a way that the quantity (by weight or volume) of one of the component parts will be a constant quantity A, it will be observed that in all the compounds AB_m , AB_n the quantities of the other component part, B, will always be in commensurable relation: generally in simple multiple proportion—that is, that $a : b$. . . , or m/n is to r/q as whole numbers, for instance as 2 : 3 or 3 : 4. . . .*

The analysis of water shows that in 100 parts by weight it contains 11.112 parts by weight of hydrogen and 88.888 of oxygen, and the analysis of peroxide of hydrogen shows that it contains 94.112 parts of oxygen to 5.888 parts of hydrogen. In this the analysis is expressed, as analyses generally are, in percentages; that is, it gives the amounts of the elements in a hundred parts by weight of the substance. The direct comparison of the percentage compositions of water and hydrogen peroxide does not give any simple relation. But such a relation is immediately observed if we calculate the composition of water and of hydrogen peroxide, having taken either the quantity of oxygen or the quantity of hydrogen as a constant quantity—for instance, as unity. The most simple proportions show that in water there are contained eight parts of oxygen to one part of hydrogen, and in hydrogen peroxide sixteen parts of oxygen to one part of hydrogen; or one-eighth part of hydrogen in water and one-sixteenth part of hydrogen in hydrogen peroxide to one part of oxygen. Naturally, the analysis does not give these figures with absolute exactness—it gives them within a certain degree of error—but they approximate, as the error diminishes, to that limit which is here given. The comparison of the quantities of hydrogen and oxygen in the two substances above named, taking one of the components as a constant quantity, gives an example of the application of

as to foretell the degree of stability of different chemical states of equilibrium. The commencement of elementary generalisations has been apprehended in only a few cases.

the law of multiple proportions, because water contains eight parts and hydrogen peroxide sixteen parts of oxygen to one part of hydrogen, and these figures are commensurable and are in simple proportion as 1 : 2.

An exactly similar multiple proportion is observed in the composition of all other well-investigated definite chemical compounds,³⁰ and therefore the law of multiple proportions is accepted in chemistry as the starting point from which other considerations are judged.

The law of multiple proportions was discovered at the very beginning of this century by John Dalton, of Manchester, in investigating the compounds of carbon with hydrogen. It appeared that two gaseous compounds of these substances—marsh gas, CH_4 , and olefiant gas, C_2H_4 , contain for one and the same quantity of hydrogen quantities of carbon which stand in multiple proportion; namely, marsh gas contains relatively half as much carbon as olefiant gas. Although the analysis of that time was not exact, and did not give Dalton results in complete accordance with truth, still the accuracy of this law, recognised by Dalton, was confirmed by further more accurate investigations. On establishing the law of multiple proportions, Dalton gave a hypothetical explanation for it. This explanation is based on the atomic theory of matter. In fact, the law of multiple proportions is understood with unusual ease by admitting the atomic structure of matter.

³⁰ When, for example, any element forms several oxides, they are subject to the law of multiple proportions. For a given quantity of the non-metal or metal the quantities of oxygen in the different degrees of oxidation will stand as 1 : 2, or as 1 : 3, or as 2 : 3, or as 2 : 7, and so on. Thus, for instance, copper combines with oxygen in at least two proportions, forming the oxides found in nature, and called the suboxide and the oxide of copper, Cu_2O and CuO ; the oxide contains twice as much oxygen as the suboxide. Lead also presents two degrees of oxidation, the oxide and peroxide, and in the latter there is twice as much oxygen as in the former, PbO and PbO_2 . The substance known under the name of minium, and which is somewhat widely used as a red paint, is only a mixture of the mutual compounds of these oxides, which is proved not only by the inconstancy of its composition, but also by the fact that reagents capable of extracting the oxide of lead, especially acids, do actually extract it and leave lead peroxide. When a base and an acid are capable of forming several kinds of salts, normal, acid, basic, and anhydro-, it is found that they also clearly exemplify the law of multiple proportions. This was demonstrated by Wollaston soon after the discovery of the law in question. We saw in the first chapter that salts show different degrees of combination with water of crystallisation, and that they obey the law of multiple proportions. And, more than this, the indefinite chemical compounds existing as solutions may, as we saw in the same chapter, be brought under the law of multiple proportions by the hypothesis that solutions are unstable hydrates formed according to the law of multiple proportions, but occurring in a state of dissociation. By means of this hypothesis the law of multiple proportions becomes still more general, and all the aspects of chemical compounds are subject to it. The direction of the whole contemporary state of chemistry was determined by the discoveries of Lavoisier and Dalton. By bringing indefinite compounds also under the law of multiple proportions we arrive at that unity of chemical conceptions

The essence of the atomic theory is that matter is supposed to consist of an agglomeration of small and indivisible parts—atoms—which do not fill up the whole space occupied by a substance, but stand apart from each other, as the sun, planets, and stars do not fill up the whole space of the universe, but are at a distance from each other. The form and properties of substances are determined by the position of their atoms in space and by their state of movement, while the phenomena accomplished by substances are understood as redistributions of the relative positions of atoms and changes in their movement. The atomic representation of matter arose in very ancient times,³¹ and up to recent times was at strife with the dynamical hypothesis, which considers matter as only a manifestation of forces. At the present time, however, the majority of scientific men uphold the atomic hypothesis, although the present conception of an atom is quite different from that of the ancient

which was impossible so long as definite compounds were separated from indefinite by a sharp line of demarcation.

³¹ Leucippus, Democritus, and especially Lucretius, in the classical ages, represented matter as made up of atoms—that is, of parts incapable of further division. The geometrical impossibility of such an admission, as well as the conclusions which were deduced by the ancient atomists from their fundamental propositions, prevented other philosophers from following them, and the atomic doctrine, like very many others, lived, without being ratified by fact, in the imaginations of its followers. Between the present atomic theory and the doctrine of the above-named ancient philosophers there is naturally a remote historical connection, as between the doctrine of Pythagoras and Copernicus, but they are essentially profoundly different. For us the atom is indivisible, not in the geometrical abstract sense, but only in a physical and chemical sense. It would be better to call the atoms indivisible *individuals*. The Greek atom—the Latin individual, according to both the sum and sense of the words, but historically these two words are endowed with a different meaning. The individual is mechanically and geometrically divisible, but only indivisible in a definite sense. The earth, the sun, a man or fly are individuals, although geometrically divisible. Thus the atoms of contemporary science, indivisible in a physico-chemical sense, form those units which are concerned in the investigation of the natural phenomena of matter, just as a man is an indivisible unit in the investigation of social relations, or as the stars, planets, and luminaries serve as units in astronomy. The formation of the vortex hypothesis, in which, as we shall afterwards see, atoms are entire whirls mechanically complex, although physico-chemically indivisible, already shows that the scientific men of our time in holding to the atomic theory have only borrowed the word and form from the ancient philosophers, and not the essence of their atomic doctrine. It is erroneous to imagine that the contemporary conceptions of the atomists are nothing but the repetition of the metaphysical reasonings of the ancients. As a geometrician in reasoning about curves represents them as formed of a sum total of straight lines, because such a method enables him to analyse the subject under investigation, so the scientific man applies the atomic theory as a method of analysing the phenomena of nature. Naturally there are people now, as in ancient times, and as there always will be, who apply reality to imagination, and therefore there are to be found atomists of extreme views; but it is not in their spirit that we should acknowledge the great services rendered by the atomic doctrine to all science, which, while it has been essentially independently developed, is, if it be desired to reduce all ideas to the doctrines of the ancients, a union of the ancient dynamical and atomic doctrines.

philosophers. Now, an atom is regarded rather as an isolate or unit which is indivisible by physical³² and chemical forces, whilst the atom of the ancients was mechanically and geometrically indivisible. When Dalton (1804) discovered the law of multiple proportions, he pronounced himself in favour of the atomic doctrine, because it enables this law to be very easily understood. If the divisibility of every element has a limit, namely the atom, then the atoms of elements are the extreme limits of all divisibility, and they differ from each other in their nature, and the formation of a compound from elementary matter must consist in the aggregation of several different atoms into one whole or system of atoms, now termed *particles* or *molecules*. As atoms can only combine in their entire masses, it is evident that not only the law of definite composition, but also that of multiple proportions, must apply to the combination of atoms with one another; for one atom of a substance can combine with one, two, or three atoms of another substance, or in general one, two, three atoms of one substance are able to combine with one, two, or three atoms of another; this being the essence of the law of multiple proportions. Chemical and physical data are very well explained by the aid of the atomic theory. The displacement of one element by another follows the law of equivalency. In this case one or several atoms of a given element take the place of one or several atoms of another element in its compounds. The atoms of different substances can be mixed together in the same sense as sand can be mixed with clay. They do not unite into one whole—*i.e.*, there is not a perfect blending in the one or other case, but only a juxtaposition, a homogeneous whole being formed from individual parts. This is the first and most simple form of applying the atomic theory to the explanation of chemical phenomena.³³

³² Dalton and many of his successors distinguished the atoms of elements and compounds, in which they already clearly symbolised the difference of their opinion from the representations of the ancients. Now only the individuals of the elements, indivisible by physical and chemical forces, are termed atoms, and the individuals of compounds indivisible under physical changes are termed molecules; these are divisible into atoms by chemical forces.

³³ Under the present condition of the sciences, either the atomic or the dynamical hypothesis is inevitably obliged to admit the existence of an unobservable, invisible, and insensible motion in matter, without which it is impossible to understand either light or heat, or gaseous pressure, or the entire mass of mechanical, physical, or chemical phenomena. The ancients saw vital movement in animals only, but to us the smallest particle of matter, endued with *vis viva*, or energy in some degree or other, is incomprehensible without self-existent motion. Thus motion has become a conception inseparably knit with the conception of matter, and this has prepared the ground for the revival of the dynamical hypothesis of the constitution of matter. In the atomic theory there has arisen that generalising idea by which the world of atoms is constructed, like the universe of heavenly bodies, with its suns, planets, and meteors, endued with ever-

A certain number of atoms n of an element A in combining with several atoms m of another element B give a compound A_nB_m , each molecule of which will contain the atoms of the elements A and B in this ratio, and therefore the compound will present a *definite composition*, expressed by the formula A_nB_m , where A and B are the weights of the

lasting force of motion, forming molecules as the heavenly bodies form systems, like the solar system, which molecules are only relatively indivisible in the same way as the planets of the solar system are inseparable, and stable and lasting as the solar system is lasting. Such a representation, without necessitating the absolute indivisibility of atoms, expresses all that science can require for an hypothetical representation of the constitution of matter. In closer proximity to the dynamical hypothesis of the constitution of matter is the oft-times revived *vortex hypothesis*. Descartes first endeavoured to raise it; Helmholtz and Thomson gave it a fuller and more modern form; many scientific men applied it to physics and chemistry. The idea of vortex rings serves as the starting point of this hypothesis; these are familiar to all as the rings of tobacco smoke, and may be artificially obtained by giving a sharp blow to the sides of a cardboard box having a circular orifice and filled with smoke. Phosphine, as we shall see later on, when bubbling from water always gives very perfect vortex rings in a still atmosphere. In such rings it is easy to observe a constant circular motion about their axes, and to remark the stability the rings possess in their motion of translation. This unchangeable mass, endued with a rapid internal motion, is likened to the atom. In a medium deprived of friction, such a ring, as is shown by theoretical considerations of the subject from a mechanical point of view, would be perpetual and unchangeable. The rings are capable of grouping together, and combining, being indivisible, remain indivisible. The vortex hypothesis has been established in our times, but it has not been fully developed; its application to chemical phenomena is not clear, although not impossible; it does not satisfy a doubt in respect to the nature of the space existing between the rings (just as it is not clear what exists between atoms, and between the planets), neither does it tell us what is the nature of the moving substance of the ring, and therefore for the present it only presents the germ of an hypothetical conception of the constitution of matter, consequently, I consider that it would be superfluous to speak of it in greater detail. However, the thoughts of investigators are now (and naturally will be in the future), as they were in the time of Dalton, often turned to the question of the limitation of the mechanical division of matter, and the atomists have searched for an answer in the most diverse spheres of nature. I select one of the methods tried, which does not in any way refer to chemistry, in order to show how closely all the provinces of natural science are bound together. Wollaston proposed the investigation of the *atmosphere of the heavenly bodies* as a means for confirming the existence of atoms. If the divisibility of matter be infinite, then air must extend throughout the entire space of the heavens as it extends all over the earth by its elasticity and diffusion. If the infinite divisibility of matter be admitted, it is impossible that any portion of the whole space of the universe can be entirely void of the component parts of our atmosphere. But if matter be divisible up to a certain limit only—namely, up to the atom—then there *can exist* a heavenly body void of an atmosphere; and if such a body be discovered, it would serve as an important factor for the acceptance of the validity of the atomic doctrine. The moon has long been considered as such a luminary, and this circumstance, especially from its proximity to the earth, has been cited as the best proof of the validity of the atomic doctrine. This proof is apparently (Poisson) deprived of some of its force from the possibility of the transformation of the component parts of our atmosphere into a solid or liquid state at immense heights above the earth's surface, where the temperature is exceedingly low; but a series of researches (Poulé) has shown that the temperature of the heavenly space is, comparatively, not so very low, and is attainable by experimental means, so that at the low existing pressure the liquefaction

atoms and m and n their relative number. If the same elements A and B, in addition to A_nB_m , also yield another compound A_rB_q , then by expressing the composition of the first compound by $A_{nr}B_{mq}$ (and this is the same composition as A_nB_m), and of the second compound by $A_{rn}B_{qm}$, we have the law of multiple proportions, because for a given

of gases cannot be expected. Therefore the absence of an atmosphere about the moon, if it were not subject to doubt, would be counted as a forcible proof of the atomic theory. As a proof of the absence of a lunar atmosphere, it is cited that the moon, in its independent movement between the stars, when eclipsing a star—that is, when passing between the eye and the star—does not show any signs of refraction at its edge; the image of the star does not alter its position in the heavens on approaching the moon's surface, consequently there is no atmosphere on the moon's surface capable of refracting the rays of light. Such is the conclusion by which the absence of a lunar atmosphere is acknowledged. But this conclusion is most feeble, and there are even facts in exact contradiction to it, by which the existence of a lunar atmosphere may be proved. The entire surface of the moon is covered with a number of mountains, having in the majority of cases the conical form natural to volcanoes. The volcanic character of the lunar mountains was confirmed in October 1866, when a change was observed in the form of one of them (the crater Linnea). These mountains must be on the edge of the lunar disc. Seen in profile, they screen one another and interfere with making observations on the surface of the moon, so that when looking at the edge of the lunar disc we are obliged to make our observations not on the moon's surface, but at the summits of the lunar mountains. These mountains are higher than those on our earth, and consequently at their summits the lunar atmosphere must be exceedingly rarefied even if it possess an observable density at the surface. Knowing the mass of the moon to be eighty-two times less than the mass of the earth, we are able to approximately determine that our atmosphere at the moon's surface would be about twenty-eight times lighter than it is on the earth, and consequently at the very surface of the moon the refraction of light by the lunar atmosphere must be very slight, and at the heights of the lunar mountains it must be imperceptible, and would be lost within the limits of experimental error. Therefore the absence of refraction of light at the edge of the moon's disc cannot yet plead in favour of the absence of a lunar atmosphere. There is even a series of observations obliging us to admit the existence of this atmosphere. These researches are due to Sir John Herschel. This is what he writes:—'It has often been remarked that during the eclipse of a star by the moon there occurs a peculiar optical illusion; it seems as if the star before disappearing passed over the edge of the moon and is seen through the lunar disc, sometimes for a rather long period of time. I myself have observed this phenomenon, and it has been witnessed by perfectly trustworthy observers. I ascribe it to optical illusion, but it must be admitted that the star might have been seen on the lunar disc through some deep ravine on the moon.' Geniller, in Belgium (1856), following the opinion of Cassin , Eiler, and others, gave an explanation to this phenomenon; he considers it due to the refraction of light in the valleys of the lunar mountains which occur on the edge of the lunar disc. In fact, although these valleys do not probably present the form of straight ravines, yet it may sometimes happen that the light of a star is so refracted that its image might be seen, notwithstanding the absence of a direct path for the light-rays. He then goes on to remark that the density of the lunar atmosphere must be variable in different parts, owing to the very long nights on the moon. On the dark, or non-illuminated, portion, owing to these long nights, which last thirteen of our days and nights, there must be excessive cold, and hence a denser atmosphere, while, on the contrary, at the illuminated portion the atmosphere must be much more rarefied. This variation in the temperature of the different parts of the moon's surface explains also the absence of clouds, notwithstanding the possible presence of air and aqueous vapour, on the visible portion of the moon. The

quantity of the first element, A_{rm} , there occur quantities of the second element bearing the same ratio to each other as mr is to qn ; and as m , r , q , and n are whole numbers, therefore their products are also whole numbers, and this is also expressed by the law of multiple proportions. Consequently the atomic theory is in accordance with and evokes the first laws of definite chemical compounds: the law of definite composition and the law of multiple proportions.

So, also, is the relation of the atomic theory to the third law of definite chemical compounds, the *law of reciprocal combining weights*, which is as follows:—If a certain weight of a substance C combine with a weight a of a substance A, and with a weight b of a substance B, then, also, the substances A and B will combine together in quantities a and b (or in multiples of them). This should be the case from the conception of atoms. Let A, B, and C be the weights of the atoms of the three substances, and for simplicity of reasoning let combination proceed in the quantity of one atom. It is evident that if the substance gives AC and BC, then the substances A and B will give a compound AB, or their multiple, A_nB_m .

Sulphur combines with hydrogen and with oxygen. Sulphuretted hydrogen contains thirty-two parts by weight of sulphur to two parts by weight of hydrogen, which is expressed by the formula H_2S . Sulphur dioxide, SO_2 , contains thirty-two parts of sulphur and thirty-two parts of oxygen, and therefore we conclude, from the law of combining weights, that oxygen and hydrogen will combine in the proportion of two parts of hydrogen and thirty-two parts of oxygen, or multiple numbers of them. And we have seen this to be the case. Hydrogen peroxide contains thirty-two parts of oxygen, and water sixteen parts, to two parts of hydrogen; and so it is in all other cases. This consequence of the atomic theory is in accordance with nature, with the results of analysis, and is one of the most important laws of chemistry. It is a law, because it indicates the *relation between* the weights of substances entering into chemical combination. Further it is an eminently exact law, and not an approximate one. The law of combining weights is a law of nature, and by no means an hypothesis, for let the entire theory of atoms be cast down, still the laws of multiple proportions and of combining weights will remain, inasmuch as they deal with facts. They may be guessed at from the sense of the atomic theory, and historically presence of an atmosphere round the sun and planets, judging from astronomical observations, may be considered as fully proved. On Jupiter and Mars there may be even distinguished bands of clouds. Thus the atomic doctrine, admitting a finite mechanical divisibility only, must be, as yet at least, only accepted as a means, similar to that means which a mathematician employs when he breaks up a continuous curvilinear line into a number of straight lines. There is a simplicity of representation in atoms, but there is no absolute necessity to have recourse to them. The conception of the individuality of the parts of matter exhibited in chemical elements only is necessary and trustworthy.

the law of combining weights is intimately connected with this theory ; but they are not identical, but only connected, with it. The law of combining weights is formulated with great ease, and is an immediate consequence of the atomic theory, without it, it is even difficult to understand. Data for its evolution existed previously, but it was not seen until those data were interpreted by the atomic theory. Such is the property of hypotheses. They are indispensable to science ; they bestow an order and simplicity which are difficultly attainable without their aid. The whole history of science is a proof of this. And therefore one may boldly say that it is better to hold to an hypothesis which may afterwards prove untrue than to have none at all. Hypotheses facilitate scientific work and render it uniform. The search for truth, like the plough of the husbandman, helps forward the work of the labourer, regulates it, and forces him to think of the further improvement both of the work itself and of its implements.

CHAPTER V

NITROGEN AND AIR

GASEOUS *nitrogen* forms about four-fifths (by volume) of the atmosphere ; consequently the air contains an exceedingly large mass of it. Whilst entering in so considerable a quantity into the composition of air, nitrogen does not seem to play any active part in the atmosphere, the chemical action of which is mainly dependent on the oxygen it contains. But this is not an entirely correct idea, because animal life cannot exist in pure oxygen, in which animals pass into an abnormal state and die ; and the nitrogen of the air, although slowly, forms diverse compounds, many of which play a most important part in nature, especially in the life of organisms. However, neither plants nor animals directly absorb the nitrogen of the air, but take it up from already prepared nitrogenous compounds ; further, plants are nourished by the nitrogenous substances contained in the soil and water, and animals by the nitrogenous substances contained in plants and in other animals. Atmospheric electricity is capable of aiding the passage of gaseous nitrogen into nitrogenous compounds, as we shall afterwards see, and the resultant substances are carried to the soil by rain, where they serve for the nourishment of plants. Plentiful harvests, fine crops of hay, vigorous growth of trees—other conditions being equal—are only obtained when the soil contains *ready prepared nitrogenous compounds*, consisting either of those which occur in air and water, or of the residues of the decomposition of other plants or animals (as in manure). The nitrogenous substances contained in animals have their origin in those substances which are formed in plants. Thus the nitrogen of the atmosphere is the origin of all the nitrogenous substances occurring in animals and plants, although not directly so, but after first combining with the other elements of air.

The nitrogenous compounds which enter into the composition of plants and animals are of primary importance ; no vegetable or animal cell—that is, the elementary form of organism—exists without containing a nitrogenous substance ; organic life, before all, evinces itself in

these nitrogenous substances. The germs, seeds, and those parts by which cells multiply themselves abound in nitrogenous substances; the sum total of the phenomena which are proper to organisms depend, before all, on the chemical properties of the nitrogenous substances which enter into their composition. It is enough, for instance, to point out the fact that vegetable and animal organisms, clearly distinguishable as such, are characterised by a different degree of energy in their nature, and at the same time by a difference in the amount of nitrogenous substances they contain. In plants, which compared with animals possess but little activity, being incapable of independent movement, &c., the amount of nitrogenous substances is very much less than in animals, whose tissues are almost exclusively formed of nitrogenous substances. It is remarkable that the nitrogenous parts of plants, chiefly of the lower orders, sometimes present both forms and properties which approach to those of animal organisms; for example, the zoospores of seaweeds, or those parts by means of which the latter multiply themselves. These zoospores on leaving the seaweed in many respects resemble the lower orders of animal life, having, like the latter, the property of moving. They also approach the animal kingdom in their composition, their outer coat containing nitrogenous matter. Directly the zoospore becomes covered with that non-nitrogenous or cellular coating which is proper to all the ordinary cells of plants, it loses all resemblance to an animal organism and becomes a small plant. It may be thought from this that the cause of the difference in the vital processes of animals and plants is the different amount of nitrogenous substances they contain. Those nitrogenous elements which occur in plants and animals appertain to the series of exceedingly complex and very changeable chemical compounds; their elementary composition alone shows this; besides nitrogen, they contain carbon, hydrogen, oxygen, and sulphur. Being distinguished by a very great instability under many conditions in which other compounds remain unchanged, these substances are fitted for those perpetual changes which form the first condition of vital activity. These complex and changeable nitrogenous substances of the organism are called *proteid substances*. The white of eggs is a familiar example of such a substance. They are also contained in the flesh of animals, the curdy elements of milk, the glutinous matter of wheaten flour, or so-called gluten, which forms the chief component of macaroni, &c.

Nitrogen occurs in the earth's crust, in compounds either forming the remains of plants and animals, or derived from the nitrogen of the atmosphere as a consequence of its combination with the other component parts of the air. It is not found in other forms in the earth's

crust ; so that nitrogen must be considered, in contradistinction to oxygen, as an element which is purely superficial, and does not extend to the depths of the earth.¹

Nitrogen is liberated in a free state in the decomposition of the *nitrogenous organic substances* entering into the composition of organisms—for instance, on their combustion. All organic substances burn when heated to redness with oxygen (or substances readily yielding it, such as oxide of copper) ; the oxygen combines with the carbon, sulphur, and hydrogen, and the nitrogen is evolved in a free state, because at a high temperature it does not form any stable compound, but remains free. Carbonic anhydride and water are formed from the carbon and hydrogen respectively, and therefore to obtain pure nitrogen it is necessary to remove the carbonic anhydride from the gaseous products obtained. This may be done very easily by the action of alkalis—for instance, caustic soda. The amount of nitrogen in organic substances is determined by a method founded on this.

It is also very easy to obtain *nitrogen from air*, because oxygen combines with many substances. Either phosphorus or metallic copper are usually employed for removing the oxygen from air, but, naturally, a number of other substances may also be used. If a small saucer on which a piece of phosphorus is laid be placed on a cork floating on water, and the phosphorus be lighted, and the whole be covered with a glass bell jar, then the air under the jar will be deprived of its oxygen, and nitrogen only will remain, owing to which, on cooling the water will rise to a certain extent in the bell jar. The same object (procuring nitrogen from air) is attained much more conveniently and perfectly when air is passed through a red-hot tube containing copper filings. At a red heat, metallic copper combines with oxygen and gives a black powder of copper oxide. If the layer of copper be sufficiently long and the current of air slow, all the oxygen of the air will be absorbed, and nitrogen alone will pass from the tube.²

¹ The reason why there are no other nitrogenous substances within the earth's mass beyond those which have come there with the remains of organisms, and from the air with rain-water, must be looked for in two circumstances. In the first place, in the instability of many nitrogenous compounds, which are liable to break up with the formation of gaseous nitrogen ; and in the second place in the fact that the salts of nitric acid, forming the product of the action of air on many nitrogenous and especially organic compounds, are very soluble in water, and on penetrating into the depths of the earth (with water) give up their oxygen. The result of the changes of the nitrogenous organic substances which fall into the earth is without doubt frequently, if not always, the formation of gaseous nitrogen. Thus the gas evolved from coal always contains much nitrogen (together with marsh gas, carbonic anhydride, and other gases).

² Copper (best as shavings, which present a large surface) absorbs oxygen, forming CuO, at the ordinary temperature in the presence of solutions of acids, or, better still, in

Nitrogen may also be procured from many of its *compounds with oxygen*³ and *hydrogen*,⁴ but the best fitted for this purpose is a saline mixture containing, on the one hand, a compound of nitrogen with oxygen, termed nitrous anhydride, N_2O_3 , and on the other hand, ammonia, NH_3 —that is, a compound of nitrogen with hydrogen. By heating such a mixture the oxygen of the nitrous anhydride combines with the hydrogen of the ammonia, forming water, and gaseous nitrogen is evolved, $2NH_3 + N_2O_3 = 3H_2O + N_4$. Nitrogen is procured by this method in the following manner:—A solution of caustic potash is saturated with nitrous anhydride, by which means potassium nitrite is formed. On the other hand, a solution of hydrochloric acid saturated with ammonia is prepared; a saline substance called sal-ammoniac, NH_4Cl , is thus formed in the solution. The two solutions thus prepared are mixed together and heated. Reaction takes place according to the equation $KNO_2 + NH_4Cl = KCl + 2H_2O + N_2$. This reaction proceeds in virtue of the fact that potassium nitrite and ammonium chloride are salts which, on interchanging their metals, give potassium chloride and ammonium nitrite, NH_4NO_2 , which breaks up into water and nitrogen. This reaction does not take place without the aid of heat, but it proceeds very easily at a moderate temperature. Of the resultant substances, the nitrogen only is gaseous, the potassium chloride is non-volatile, and is left behind in the vessel in which the solutions are heated. Pure nitrogen may be obtained by drying the resulting gas and passing it through a solution of sulphuric acid (to absorb a certain quantity of ammonia which is evolved in the reaction).

Nitrogen is a gaseous substance which does not much differ in physical properties from air; its density, referred to hydrogen, is approximately equal to 14—that is, it is slightly lighter than air; one litre of nitrogen weighs 1.256 grams. Nitrogen mixed with oxygen,

the presence of a solution of ammonia, when it forms a bluish-violet solution of oxide of copper in ammonia. Nitrogen is very easily procured by this method. A flask is filled with copper shavings and closed with a cork furnished with a funnel and stop-cock. A solution of ammonia is poured into the funnel, and caused to slowly drop upon the copper. If at the same time a current of air be slowly passed through the flask (from a gasholder), then all the oxygen will be absorbed from it and the nitrogen will pass from the flask. It should be washed with water to retain any ammonia that may be carried off with it.

³ The oxygen compounds of nitrogen (for example, N_2O , NO , NO_2) are decomposed at a red heat by themselves, and under the action of red-hot copper, sodium, &c., they give up their oxygen to the metals, leaving the nitrogen free. According to Meyer and Langer (1885), nitrous oxide, N_2O , decomposes below 900° , although not completely, whilst the decomposition of nitric oxide, NO , does not start at 1200° , but is complete at 1700° .

⁴ Chlorine and bromine (in excess), as well as bleaching powder (hypochlorites), take up the hydrogen from ammonia, NH_3 , leaving nitrogen. Nitrogen is best procured from ammonia by the action of a solution of sodium hypobromite on solid sal-ammoniac.

which is slightly heavier than air, forms air. It is a gas which, like oxygen and hydrogen, is difficultly liquefied, and but little soluble in water and other liquids. Its absolute boiling point⁵ is about -140° ; above this temperature it is not liquefiable by pressure, and at lower temperatures it remains a gas at a pressure of 50 atmospheres. Liquid nitrogen boils at -193° , so that it may be employed as a source of great cold. At about -203° , in vaporising under a decrease of pressure, nitrogen solidifies into a colourless snow-like mass. Nitrogen does not burn, does not support combustion, is not absorbed by any of the reagents used in gas analysis, at least at the ordinary temperature—in a word, it presents a whole series of negative chemical properties; this is expressed by saying that this element has no energy for combination. Although it is capable of forming compounds both with oxygen and hydrogen as well as with carbon, yet these compounds are only formed under particular circumstances, to which we will directly turn our attention. At a red heat nitrogen combines with boron, titanium, and silicon, forming very stable nitrogenous compounds,⁶ whose properties are entirely different from those of nitrogen with hydrogen, oxygen, and carbon. However, the combination of nitrogen with carbon, although it does not take place directly between the elements at a red heat, yet proceeds with comparative ease by heating a mixture of charcoal with an alkaline carbonate, especially potassium carbonate or barium carbonate, to redness, carbo-nitrides or cyanides of the metals being formed; for instance, $\text{K}_2\text{CO}_3 + 4\text{C} + \text{N}_2 = 2\text{KCN} + 3\text{CO}$.⁷

Nitrogen is found with oxygen in the air, but they do not readily combine. Cavendish, however, in the last century, showed that *nitrogen combines with oxygen under the influence of a series of electric sparks*. Electric sparks in passing through a moist⁸ mixture of nitrogen and oxygen—for instance, through air—cause these elements to combine,

⁵ See Chapter II. note 29.

⁶ The combination of boron with nitrogen is accompanied by the evolution of sufficient heat to raise the mass to redness; titanium combines so easily with nitrogen that it is difficult to obtain it free from that element. It is a remarkable and instructive fact that the compounds of nitrogen with these non-volatile elements are very stable, and are themselves non-volatile. Probably in this case the physical state of the substance with which the nitrogen combines, and the state in which the nitrogenous substance is obtained, evinces its influence. Thus carbon (C—12) with nitrogen gives cyanogen, C_2N_2 , which is gaseous and very unstable, and whose molecule is not large, whilst boron (B—11) forms a nitrogenous compound which is solid, non-volatile, and very stable. Its composition, BN, is essentially like that of cyanogen, but its molecular weight is probably greater.

⁷ This reaction, as far as is known, does not proceed beyond a certain limit, probably because cyanogen, CN, itself breaks up into carbon and nitrogen.

⁸ Frémy and Becquerel took dry air, and observed the formation of brown vapours of oxides of nitrogen on the passage of sparks.

forming reddish-brown fumes of oxides of nitrogen,⁹ which form with water a compound containing nitrogen, oxygen, and hydrogen—namely, nitric acid,¹⁰ NHO_3 . The presence of the latter is easily recognised, not only from its reddening litmus paper, but also from its acting as a powerful oxidiser even of mercury. Conditions similar to these occur in nature, during a thunderstorm or in other electrical discharges accomplished in the atmosphere; whence it may be understood that air and rain-water always contain traces of nitric acid.¹¹

Further observations showed that under the influence of electrical discharges,¹² silent as well as with sparks, nitrogen is able to enter into

⁹ If a mixture of one volume of nitrogen and fourteen volumes of hydrogen be burnt, then water and a considerable quantity of nitric acid are formed. It may be partly due to this that a certain quantity of nitric acid is produced in the slow oxidation of nitrogenous substances in an excess of air. This is especially facilitated by the presence of an alkali with which the nitric acid formed can combine. If a galvanic current be passed through water containing the nitrogen and oxygen of the air in solution, then the hydrogen and oxygen set free combine with the nitrogen, forming ammonia and nitric acid.

When copper is oxidised at the expense of the air at the ordinary temperature in the presence of ammonia, oxygen is absorbed, not only for combination with the copper, but also for the formation of nitric acid.

The combination of nitrogen with oxygen, even, for example, by the action of electric sparks, is not accompanied by an explosion or rapid combination, as in the action of sparks on a mixture of oxygen and hydrogen. This is explained by the fact that heat is not evolved in the combination of nitrogen with oxygen, but is absorbed—an expenditure of energy is required, there is no evolution of energy. In fact, there will not be the transmission of heat from particle to particle which occurs in the explosion of detonating gas. Each spark will aid the formation of a certain quantity of the compound of oxygen and nitrogen, but will not excite the same in the neighbouring particles. In other words, the combination of hydrogen with oxygen is an exothermal reaction, and the combination of nitrogen with oxygen an endothermal reaction.

The conditions of the explosion of detonating gas if it be *in excess* are especially conducive to the oxidation of nitrogen. If a mixture of two volumes of detonating gas and one volume of air be exploded, then one-tenth of the air is converted into nitric acid, and consequently after the explosion has taken place there remains only nine-tenths of the volume of air originally taken. If a large proportion of air be taken—for instance, four volumes of air to two volumes of detonating gas—then (the temperature of the explosion is lowered) the volume of air taken remains unchanged, and no nitric acid is formed. This gives a rule to be observed in making use of the eudiometer—namely, that to weaken the force of the explosion not less than an equal volume of air should be added to the explosive mixture. On the other hand, a large excess must not be taken, as no explosion would then ensue (see Chapter III. note 34).

¹⁰ Really nitric oxide, NO , is first formed, but with oxygen and water it gives (brown fumes) nitrous anhydride, which, as we shall afterwards learn, in the presence of water and oxygen gives nitric acid. By the action of a silent discharge through air both oxides of nitrogen and ozone are simultaneously formed, but with a feeble discharge the formation of ozone continues, whilst the oxides of nitrogen are not produced, by which fact Berthelot proves the absence of previous ozonisation of oxygen.

¹¹ The nitric acid contained in the soil, stream water (Chapter I. note 2), wells, &c., proceeds (like carbonic anhydride) from the oxidation of organic compounds which have fallen into water, soil, &c.

¹² This energetic faculty for reaction of nitrogen, which under normal conditions is inactive, leads to the idea that under the influence of an electric discharge gaseous

many reactions with hydrogen itself and with many hydrocarbons ; although these reactions cannot be effected by exposure to a red heat. Thus, for instance, a series of electric sparks passed through a mixture of nitrogen and hydrogen causes them to combine and *form ammonia*¹³ or nitrogen hydride, NH_3 , composed of one volume of nitrogen and three volumes of hydrogen. This combination is limited to the formation of 6 per cent. of ammonia, because ammonia is decomposed, although not entirely ($\frac{9.4}{10.6}$) by electric sparks. This signifies that under the action of electric sparks the reaction $\text{NH}_3 = \text{N} + 3\text{H}$ is reversible, consequently it is a dissociation, and in it a state of equilibrium is arrived at. The equilibrium may be destroyed by the addition of gaseous hydrochloric acid, HCl , because with ammonia it forms a solid saline compound, sal-ammoniac, NH_4Cl , which (being formed from a gaseous mixture of 3H , N , and HCl) fixes the ammonia. The remaining mass of nitrogen and hydrogen, under the action of the sparks, again forms ammonia, and in this manner *solid sal-ammoniac is obtained to the end by the action of a series of electric sparks on a mixture of gaseous N , H_3 , and HCl* .¹⁴ Berthelot (1876) showed that under the action of a silent discharge many non-nitrogenous organic substances (benzene, C_6H_6 , cellulose in the form of paper, resin, glucose, $\text{C}_6\text{H}_{10}\text{O}_5$, and others) absorb nitrogen and form complex nitrogenous compounds, which are capable, like albuminous substances, of evolving their nitrogen as ammonia when heated with alkalis.¹⁵

nitrogen changes in its properties ; if not permanently like oxygen (electrolysed oxygen or ozone does not react on nitrogen, according to Berthelot), it may be temporarily at the moment of the action of the discharge, just as some substances under the action of heat are durably affected (that is, when once changed remain so—for instance, mercuric oxide is decomposed, white phosphorus passes into red, &c.), whilst others are only temporarily altered (the dissociation of S_8 into S_2 or of sal-ammoniac into ammonia and hydrochloric acid). Such a proposition is favoured by the fact of nitrogen giving two kinds of spectra, with which we shall afterwards become acquainted. It may be that the molecules N_2 then give less complex molecules, N containing one atom. Probably under a silent discharge the molecules of oxygen, O_2 , are partly decomposed and the individual atoms O combine with O_2 , forming ozone, O_3 .

¹³ This reaction, discovered by Chabrié and investigated by Thenard, was only rightly understood when Deville applied the principles of dissociation to it.

¹⁴ The action of nitrogen on acetylene (Berthelot) resembles this reaction. A mixture of these gases under the influence of a silent discharge gives hydrocyanic acid, $\text{C}_2\text{H}_2 + \text{N}_2 = 2\text{CNH}$. This reaction cannot proceed beyond a certain limit because it is reversible.

¹⁵ Berthelot successfully employed electricity of even feeble potential in these experiments, which fact led him to think that in nature, where the action of electricity takes place very frequently, a part of the complex nitrogenous substances may proceed from the gaseous nitrogen of the air by this method.

As the nitrogenous substances of organisms play a very important part in them (organic life cannot exist without them), and as the nitrogenous substances introduced into the soil are capable of invigorating its crops (naturally in the presence of the other nourishing principles required by plants), therefore the question of the means of converting the atmospheric nitrogen into the nitrogenous compounds of the soil, or

By such and, it may be, other similar indirect methods does gaseous nitrogen yield its primary compounds, in which form it enters into plants, and is elaborated in them into complex albuminous substances. But, starting from a given compound of nitrogen with hydrogen or oxygen, we may, without the aid of organisms, obtain, as will afterwards be partially indicated, most diverse and complex nitrogenous substances, which cannot by any means be formed directly from gaseous nitrogen. In this we see an example not only of the difference between an element in the free state and an intrinsic element, but also of those circuitous or *indirect methods* by which substances are formed in nature. The discovery, prognostication, and, in general, study of such indirect methods of the preparation and formation of substances forms one of the existing problems of chemistry. From the fact that A does not act at all on B, it must not be concluded that a compound AB is not to be formed. The substances A and B contain atoms which occur in AB, but their state, the nature of their movement and union, may not be at all that which is required for the formation of AB, and in this substance, although it contains the same elements in mass and quality of them as in A and B, yet their chemical state may be as different as the state of the atoms of oxygen in ozone and in water. Thus free nitrogen is inactive; but in its compounds it very easily enters into changes and is distinguished by great activity. An acquaintance with the compounds of nitrogen confirms this. But, before entering on this subject, let us consider air as a mass containing free nitrogen.

Judging from what has been already stated with respect to water, oxygen, ozone, and nitrogen, it will be evident that *atmospheric air*¹⁶

into *assimilable nitrogen* capable of being absorbed by plants and of forming complex (albuminous) substances in them, forms a question of great theoretical and practical interest. The artificial (technical) conversion of the atmospheric nitrogen into nitrogenous compounds, notwithstanding repeated trials, cannot yet be considered as fulfilled in a practical, remunerative manner, although its possibility is already evident. Electricity will probably aid in solving this problem of great practical importance. When the theoretical side of the question is further advanced, then without doubt an advantageous means will be found for the manufacture of nitrogenous substances from the nitrogen of the air; and this is needed, before all, for the agriculturist, to whom nitrogenous fertilisers form an expensive item, and are more important than all other manures.

One thousand tons of farmyard manure do not generally contain more than four tons of nitrogen in the form of complex nitrogenous substances, and this amount of nitrogen is contained in twenty tons of ammonium sulphate, therefore the action evinced by the mass of manure in respect to the introduction of nitrogen may be produced by small quantities of artificial nitrogenous fertilisers. Over 160000 tons of guano are imported into Europe from South America, because guano (the excrement of sea and other birds) contains many nitrogenous compounds which are required by the agriculturist.

¹⁶ Under the name of atmospheric air the chemist and physicist understand a very air containing nitrogen and oxygen only, notwithstanding that the other component parts of air have a very important significance for the vitality of the earth's surface. That air

contains a mixture of several gases and vapours. Some of them are met with in it in nearly constant proportions, whilst others, on the contrary, are very variable in their amount. The chief component parts of air, placed in the order of their relative amounts, are the following: nitrogen, oxygen, aqueous vapour, carbonic anhydride, nitric acid, salts of ammonia, ozone, hydrogen peroxide, and complex nitrogenous substances. Besides these, air generally contains water, as spray, drops, and snow, and particles of solids, perhaps of cosmic origin in certain instances but in the majority of cases proceeding from the mechanical translation of solid particles from one locality to another by the wind. These small solid and liquid particles (having a large surface and little weight) hang in air as solid matter hangs in turbid water; they often settle on the surface of the earth, but the air is never entirely free from them, because they are never in a state of complete rest. Then, air not unfrequently contains incidental traces of various substances, as everyone knows by experience. These incidental substances sometimes belong to the order of those which act injuriously (miasmas), the germs of lower organisms—for instance, of moulds—and to the class of carriers of infectious diseases.

In the air of the diverse countries of the earth, at different longitudes and at different altitudes above its surface, on the ocean or on the dry land—in a word, in the air of most diverse localities of the earth—the oxygen and nitrogen are everywhere in a constant ratio. This is, moreover, self-evident from the fact that the air constantly diffuses (intermixes in virtue of the internal movement of the gaseous particles) and is put in a state of movement and intermixed by the wind, and therefore it is equalised in its composition over the entire surface of the

is so represented in science is based on the fact that only the two above-named components are met with in air in a constant quantity, whilst the others are variable. The solid impurities may be separated from air required for chemical or physical research by simple filtration through a long layer of cotton-wool placed in a tube. Organic impurities are removed by passing the air through a solution of potassium permanganate. The carbonic anhydride contained in air is absorbed by alkalis—best of all, soda lime, which in a dry state in porous lumps absorbs it with exceeding rapidity and completeness. Aqueous vapour is removed by passing the air over calcium chloride, strong sulphuric acid, or phosphoric anhydride. Air thus purified is accepted as containing only nitrogen and oxygen, although in reality it still contains a certain quantity of hydrogen and hydrocarbons, from which it may be purified by passing over copper oxide heated to redness. The copper oxide then oxidises the hydrogen and hydrocarbons—it burns them, forming water and carbonic anhydride, which may be removed as above described. Such purified air differs in many respects from ordinary air. Thus, for instance, it does not support plant life. When it is said that in the determination of the density of gases the weight of air is taken as unity, then it is understood to be such air, containing only nitrogen and oxygen. It is a litre of such air that weighs 1.293 grams at 0° and 760 mm. pressure at long. 45°, and 1.294 grams at St. Petersburg.

earth. In those localities where the air is subject to change, being in a more or less enclosed space, or, at least, an unventilated space, it may alter very considerably in its composition. For this reason the air of dwellings, cellars, and wells, in which there are substances absorbing oxygen, contains less of this gas, whilst the air on the surface of standing water, abounding in the lower orders of plant life evolving oxygen, holds an excess of this gas.¹⁷ The constant composition of air over the whole surface of the earth has been proved by a number of most careful researches.¹⁸

¹⁷ As a proof of the fact that certain circumstances may actually change the composition of air, it will be enough to point out that the air contained in the cavities of glaciers (of permanent mountain ice) contains only up to 10 p.c. of oxygen. This depends on the fact that at low temperatures oxygen is much more soluble in snow-water and snow than nitrogen. When shaken up with water the composition of air should change, because the water dissolves an unequal quantity of oxygen and nitrogen. We have already seen (Chapter I.) that the air boiled off from water saturated at about 0° contains about thirty-five volumes of oxygen and sixty-five volumes of nitrogen, and we have considered the reason of this. It is remarkable that the solubility of oxygen and nitrogen in water decreases so uniformly with the temperature that the proportion of oxygen and nitrogen held in an aqueous solution remains almost constant at the most varied temperatures. This explains the circumstance that the air over the sea (especially arctic) is, as certain observers have found, poorer in oxygen than on dry land—the water dissolves more oxygen than nitrogen. The difference does not, however, exceed 0·3 p.c., and sometimes does not exist.

¹⁸ The analysis of air by weight conducted by Dumas and Boussingault in Paris, and which they repeated many times between April 27 and September 22, 1841, under various conditions of weather, showed that the amount by weight of oxygen only varies between 22·89 p.c. and 23·08 p.c., the average amount being 23·07 p.c. Brunner, at Bern in Switzerland, and Bravais, at Faulhorn in the Bernese Alps, at a height of two kilometres above the level of the sea, made analyses of the air at the same season of the year as Dumas, and found that the composition of the air at these places did not exceed the limits determined for Paris. Marignac at Geneva, Lewy at Copenhagen, and Stas at Brussels, confirmed this. The analyses of air taken from different parts of the world, at the surface of the ocean and at different heights above the level of the sea, lead to the conclusion that air everywhere contains an equal amount of oxygen, or that if it does vary it does so within very inconsiderable limits.

As there is some basis (which will be mentioned shortly) for considering that the composition of the air at great altitudes is different from that at attainable heights—namely, that it is richer in nitrogen—several fragmentary observations made at Munich and in America gave reason for thinking that in the upward currents (that is in the region of minimum barometric pressure or at the centres of meteorological cyclones) the air is richer in oxygen than in the descending currents of air (in the regions of anticyclones or of barometric maxima); but more carefully conducted observations showed this proposition to be incorrect. Improved methods for the analysis of air have shown that certain slight variations in the composition of air do actually occur, but in the first place they depend on incidental local influences (on the passage of the air over mountains and large surfaces of water, regions of forest and vegetation, and the like), and in the second place are limited by quantities which are scarcely distinguishable from possible errors in the analyses.

The considerations which make one think that the atmosphere at great altitudes contains less oxygen than at the surface of the earth are based more particularly on the law of partial pressures (page 81). It obliges one to consider that the equilibrium of the oxygen in the strata of the atmosphere is not dependent on the equilibrium of the nitro-

The analysis of air is effected by converting the oxygen into a non-gaseous compound, so as to separate it from the air. The original volume of the air is first measured, and then the volume of the remaining nitrogen. The quantity of oxygen is calculated either from the difference between these volumes or by the weight of the oxygen compound formed. All the volumetric measurements have to be corrected for pressure, temperature, and moisture (Chapters I. and II.). The medium employed for converting the oxygen into a non-gaseous substance should enable its being taken up from the nitrogen to the very end without evolving any gaseous substance. So, for instance,¹⁹ a mixture of pyrogallol, $C_6H_6O_3$, and a solution of a caustic alkali absorbs oxygen with great ease at the ordinary temperature (the solution turns black), but it is unsuited for accurate analysis because it requires an aqueous solution of an alkali, and it alters the composition of the air by acting on it as a solvent.²⁰ However, for approximate determinations this simple method gives entirely satisfactory results.

The determinations in a eudiometer (Chapter III.) give much more exact results, if all the necessary corrections for changes of pressure, temperature, and moisture be taken into account. This determination is essentially carried on as follows :—A certain amount of air is introduced into the eudiometer, and its volume is determined. Then about

gen, and that the variation in the densities of both gases with the height is determined by the pressure of each gas separately. Details of the calculations and considerations here involved are contained in my work *On Barometric Levellings*, 1876, p. 48.

On the basis of the law of partial pressure and of *hypsometical* formulæ, expressing the laws of the variation of pressures at different altitudes, the conclusion may be deduced that at the upper strata of the atmosphere the proportion of the nitrogen with respect to the oxygen increases, but the increase will not exceed a fraction per cent., even at altitudes of four and a half to six miles, the greatest height within the reach of men either by climbing mountains or by means of balloons. This conclusion is confirmed by the analyses of air collected by Welsh in England during his *aëronautic* ascents. The question of the distribution of gases in the upper strata of the atmosphere is of particular importance for understanding in what state the gaseous or vaporous masses occur which are borne in space, and are one of the elementary forms of the heavenly bodies (according to Laplace's and Kant's theory). I touch on this subject in speaking of the origin of naphtha in my work *On the Naphtha Industry*, 1879.

¹⁹ The complete absorption of the oxygen may be attained by introducing moist phosphorus into a definite volume of air; this is recognised by the fact of the phosphorus becoming non-luminous in the dark. The amount of oxygen may be determined by measuring the volume of nitrogen remaining. This method, however, cannot give accurate results, owing to a portion of the air being dissolved in the water; to the combination of some nitrogen with oxygen; to the necessity of introducing and withdrawing the phosphorus, which cannot be accomplished without introducing bubbles of air; and to the numerous corrections of the volume (for moisture, temperature, and pressure), &c.

²⁰ For rapid and approximate analyses (especially technical and hygienic), such a mixture is very suitable for determining the amount of oxygen in mixtures of gases, from which the substances absorbed by alkalis have first been removed. According to certain observers, this mixture evolves a small quantity of carbonic oxide after absorbing oxygen.

an equal volume of dry hydrogen is passed into the eudiometer, and the volume again determined. The mixture is then exploded, as was described in the determination of the composition of water. The remaining volume of the gaseous mixture is again measured; it will be less than the second of the previously measured volumes. Out of three volumes which have disappeared, one appertains to the oxygen and two to the hydrogen, consequently one-third of the loss of volume indicates the amount of oxygen held in the air.²¹

The most accurate method for the analysis of air, and one which is accompanied by the least amount of error, consists in the direct weighing, as far as is possible, of the oxygen, nitrogen, water, and carbonic




FIG. 38.—Dumas and Bousingault's apparatus for the analysis of air by weight. The globe B contains 10-15 litres. The air is first pumped out of it, and it is weighed empty. The tube T connected with it is filled with copper, and is weighed empty. It is heated in a charcoal furnace. When the copper has become red-hot, the stop-cock *r* (near R) is slightly opened, and the air passes through the vessels L, containing a solution of potash; *f*, containing solutions and pieces of caustic potash, which remove the carbonic anhydride from the air, and then through *o* and *t*, containing sulphuric acid (which has been previously boiled to expel dissolved air) and pumice-stone, which removes the moisture from the air. The pure air then gives up its oxygen to the copper in T. When the air passes into T the stop-cock R of the globe B is opened, and it becomes filled with nitrogen. When the air ceases to flow in, the stop-cocks are closed, and the globe B and tube T weighed. The nitrogen is then pumped out of the tube, and it is weighed again. The increase in weight of the tube shows the amount of oxygen, and the difference of the second and third weighings of the tube, with the increase in weight of the globe, gives the weight of the nitrogen.

anhydride contained in air. For this purpose, the air is first passed through an apparatus for retaining the moisture and carbonic anhydride (which will be considered presently), and is then led through

²¹ Details of eudiometrical analysis must, as was pointed out in Chap. III. note 32, be looked for in works on analytical chemistry. The same must be remarked in reference to the other analytical methods mentioned in this work. They are only described for the sake of showing the diversity of the methods of chemical research.

a tube, which is previously weighed, and contains shavings of metallic copper. A long layer of such copper heated to redness absorbs all the oxygen from the air, and leaves pure nitrogen, whose weight must be determined. This is done by collecting it in a weighed and exhausted globe, and the amount by weight of oxygen is shown by the increase in weight of the tube with the copper after the experiment.

Air free from moisture and carbonic anhydride²² contains 23·15 parts of oxygen and 76·85 of nitrogen by weight,²³ which, taking the density of oxygen = 16 and of nitrogen = 14, gives the volumetric composition of air as 20·84 volumes of oxygen and 79·16 of nitrogen.²⁴

The possibility of the composition of air being altered by the mere action of a solvent very clearly shows that the component parts of air are in a state of mixture, in which any gases may occur; they do not in this case form a definite compound, although the composition of the atmosphere does appear constant under ordinary conditions. The fact that its composition varies under different conditions confirms the truth of this conclusion, and therefore the constancy of the composition of air must not be considered as in any way dependent on the nature of the gases entering into its composition, but only as proceeding from cosmic phenomena co-operating towards this constancy. It must be admitted, therefore, that the processes evolving oxygen, and chiefly the processes of the respiration of plants, are of equal force with those processes which absorb oxygen over the entire surface of the earth.²⁵

²² Air free from carbonic anhydride indicates after explosion the presence of a small quantity of carbonic anhydride, as De Saussure remarked, and air free from moisture, after being passed over red-hot copper oxide, seems invariably to contain a small quantity of water, as Boussingault has observed. These observations cause one to think that air always contains a certain quantity of gaseous hydrocarbons, like marsh gas, which, as we shall afterwards learn, is evolved from the earth, marshes, &c. Its amount, however, does not exceed some hundredths of a per cent.

²³ The analyses of air are accompanied by errors, and there are variations of composition attaining hundredths per cent.; therefore one must limit oneself to the first places in decimals in expressing the average normal composition of air.

²⁴ The weight of a litre of hydrogen at 0° and 760 mm. pressure is 0·08958 gram, therefore 20·8 litres of oxygen weigh 29·87 grams, and 79·2 litres of nitrogen 99·28 grams, which gives the weight of a litre of air as 1·2914, instead of 1·293. This difference corresponds with the possible errors of both the analysis of air and of the other data entering into the calculation.

²⁵ In Chapter III. note 4, an approximate calculation made for the determination of the amount of oxygen in the entire atmosphere is evidently without solid foundation—that is, it may be supposed that the composition of air varies from time to time when the relation between vegetation and the processes absorbing oxygen changes; but such a supposition may be met by an argument of the following kind: the atmosphere of the earth has not, and should not have, a definite limit, and we have already seen (Chapter IV. note 33) that there are observations confirming this, consequently our atmosphere should vary in its component parts with the entire heavenly space. If the equilibrium now existing were destroyed, it would be rectified by means of the immense mass of rarefied air

Air always contains more or less moisture²⁶ and *carbonic anhydride*, proceeding from the respiration of animals and the combustion of carbon and carboniferous compounds. The latter shows the properties.




FIG. 33.—Apparatus for the absorption and washing of gases, known as Liebig's bulbs. The gas enters *m*, presses on the absorptive liquid, and passes from *m* into *b*, *c*, *d*, and *e* consecutively, and escapes through *f*.




FIG. 40.—Geisler's potash bulbs. The gas enters at *a*, and passes through a solution of potash in the lower bulbs, where the carbonic anhydride is absorbed, and the gas escapes from *b*. The lower bulbs are arranged in a triangle, so that the apparatus can stand without support.

of an acid anhydride. In order to determine the amount of carbonic anhydride in air, substances are employed which absorb it—namely, alkalis either in solution or solid. A solution of caustic potash, KHO , is poured into light glass vessels, through which the air is passed, and the amount of carbonic anhydride is determined by the increase in weight of the vessel. But it is best to take a solid porous alkaline mass, such as soda-lime.²⁷ With a feeble current of air a layer of soda-lime 20 c.m. in length is sufficient to completely deprive the air of the carbonic anhydride it contains. A series of tubes containing calcium




FIG. 41.—Tube for the absorption of carbonic acid. A wad of cotton wool is placed in the bulb to prevent the powder of soda-lime being carried off by the gas. The tube contains soda-lime and chloride of calcium.

which occurs in the heavenly space. If, for instance, the amount of oxygen were diminished, then it would be replenished at the expense of the oxygen pervading the space of the heavens.

²⁶ The amount of moisture contained in the air is considered in greater detail by physics and meteorology, and the subject has been mentioned above, in Chapter I. note 1, where the methods of absorbing moisture from gases were pointed out.

²⁷ Soda-lime is prepared in the following manner:—Unslaked lime must be reduced to a fine powder and mixed with a slightly warmed and very strong solution of caustic soda. The mixing should be done in an iron dish, and they should be well stirred together until the lime begins to slack. When the mass becomes hot, it boils, swells up, and solidifies, forming a porous mass very rich in alkali and capable of absorbing carbonic anhydride. A lump of caustic soda or potash presents a much smaller surface for absorption, and therefore acts much less rapidly. It is necessary to place an apparatus for absorbing water after the apparatus for absorbing the carbonic anhydride, because the alkali in absorbing the latter evolves water.

chloride for absorbing the moisture²⁸ is placed before the apparatus for the absorption of the carbonic anhydride, and a measured mass of air is caused to pass through the whole apparatus by means of an aspirator. In this manner the determination of the moisture is combined with the absorption of the carbonic acid. The arrangement shown in fig. 38 is such a combination.

The amount of carbonic anhydride²⁹ in free air is incomparably more constant than the amount of moisture. The average amount of carbonic anhydride in 100 volumes of dry air is approximately $\frac{3}{1000}$ p.c.—that is, 10000 volumes of air contain about 3 volumes of carbonic anhydride, most frequently about 2.95 volumes. As the specific gravity of carbonic anhydride, referred to air = 1.52, therefore 100 parts by weight of air contain 0.015 part by weight of carbonic anhydride. This quantity varies according to the time of year (more in winter), the altitude above the level of the sea (less at high altitudes), on the proximity to forests and fields (less) or cities (greater), &c. But the variation is small and rarely exceeds limits of $2\frac{1}{2}$ to 4 ten-thousandths by volume.³⁰ As there are many natural local influences which either increase the

²⁸ It is evident that the calcium chloride employed for absorbing the water should be free from lime or other alkalis in order that it should not retain carbonic anhydride. Such calcium chloride may be prepared in the following manner. An entirely neutral solution of calcium chloride is prepared from lime and hydrochloric acid; it is then evaporated first over a water-bath and then over a sand-bath with great care. When the solution attains a certain strength a scum is formed, which solidifies on reaching the top. This scum is collected, and will be found to be free from caustic alkalis. It is necessary in any case to test it before use, as otherwise a large error may be introduced into the results, owing to the presence of free alkali (lime). It is better still to pass carbonic anhydride through the tube containing the calcium chloride for some time before the experiment, in order to saturate any free alkali that may remain from the decomposition of a portion of the calcium chloride by water, $\text{CaCl}_2 + 2\text{H}_2\text{O} = \text{CaOH}_2\text{O} + 2\text{HCl}$.

²⁹ Recourse is had to special methods when the determination regards only the carbonic anhydride of the air. For instance, it is absorbed by an alkali which does not contain carbonates (by a solution of baryta or caustic soda mixed with baryta), and then the carbonic anhydride is expelled by an excess of an acid, and its amount determined by the volume given off. During the last ten years the question as to the amount of carbonic anhydride present in the air has been submitted to many voluminous and exact researches, especially those of Reiset, Schloesing, Müntz, and Aubin, who showed that the amount of carbonic anhydride is not subject to such variations as was at first supposed on the basis of incomplete and insufficiently accurate determinations.

³⁰ It is a different case in enclosed spaces in dwellings, cellars, wells, caves, and mines, where the renewal of air is hampered. Under these circumstances large quantities of carbonic anhydride may accumulate. Even in cities, where there are many conditions for the evolution of carbonic anhydride (respiration, decomposition, combustion), its amount is greater than in free air, yet even in still weather the difference does not often exceed one ten-thousandth (that is, rarely attains 4 instead of 2.4 vols. in 10000 vols. of air). Hundreds of very careful comparative determinations made simultaneously around Paris and in the city itself, and constant daily determinations conducted at certain meteorological stations (for instance, at Montsouris, near Paris), confirm this conclusion. On high mountains and in deep valleys, as has been proved in the Pyrenees, the difference of

amount of carbonic anhydride in the air (respiration, combustion, rotting, volcanic eruptions, &c.), or diminish it (absorption by plants and water), therefore the reason of the great constancy in the amount of this gas in air must be looked for, in the first place, in the fact that the wind mixes the air of various localities together, and, in the second place, in the fact that the waters of the ocean, holding carbonic acid in solution,³¹ form an immense reservoir for regulating the supply of this gas in the atmosphere. As immediately the partial pressure of the carbonic anhydride in the air decreases, the water evolves it, and when the partial pressure increases, it absorbs it, nature consequently supplies the conditions for a natural mobile state of equilibrium in this instance, as in a number of others.³²

Beyond nitrogen, oxygen, moisture, and carbonic acid, all other substances occurring in air are found in infinitesimally small quantities by weight, and therefore the *weight of a cubic measure of air* depends, to a sensible degree, on the above-named components alone. We have already mentioned that at 0° and 760 mm. pressure the weight of a cubic litre of air is 1.293 grams,³³ the air being understood to be

the amount of carbonic anhydride is also very slight (at a height it is, however, less, as would be expected).

³¹ In the sea as well as fresh water the carbonic acid occurs in two forms, directly dissolved in the water, and combined with lime, as calcium bicarbonate (hard waters sometimes contain very much carbonic acid in this form). If the tension of the carbonic anhydride in the first form varies with the temperature, and its amount with the partial pressure, that in the form of acid salts is under the same conditions, because direct experiments have shown a similar dependence in this case, although the quantitative relations are different in the two cases.

³² In studying the phenomena of nature one inevitably arrives at the idea that the universally reigning state of mobile equilibrium forms the chief reason of that harmonious order which impresses all observers. It not unfrequently happens that we do not see the causes regulating the order and harmony; in the particular instance of carbonic anhydride it is a striking circumstance that in the first instance a search was made for an harmonious and strict uniformity, and in incidental (insufficiently accurate and fragmentary) observations conditions were even found for concluding it to be absent. When, later, the rule of this uniformity was confirmed, then the causes regulating such order were also discovered. The researches of Schloesing were of this character. Deville's idea of the dissociation of the acid carbonates of sea-water is suggested in them. In much else, also, a right understanding can only be looked for in detailed investigation.

³³ The difference of the weight of a litre of dry air (free from carbonic anhydride) at 0° and 760 mm., at different longitudes and altitudes, depends on the fact that the force of gravity varies under these conditions, and with it the pressure of the barometrical column also varies. This is treated in detail in my works *On the Elasticity of Gases* and *On Barometric Levellings*.

In reality the weight is not measured in absolute units of weight (in pressure—refer to works on mechanics and physics), but in relative units (grams, scale weights) whose mass is one and the same, and therefore the variation of the weight of the weights itself with the change of gravity must not be here taken into account, for the matter deals with weights proportional to the masses, and with a change of locality the weight of the weights varies as the weight of a given volume of air does.

dry and free from carbonic anhydride. Taking the amount of the latter as 0.03 per 100 volumes, we obtain a greater weight—namely, 1.000156 times greater (consequently at 0° and 760 mm., instead of 1.29300 grams, the weight of a litre will then be 1.29319 grams). The weight of moist air in which the tension ³⁴ of the aqueous vapour (partial pressure) = f mm., and consequently the volume of vapour (its density referred to air = 0.62) = $\frac{f}{760}$ of the whole pressure of the moist air = 760 mm.) is to the weight of an equal volume of dry air as $\frac{760-f}{760} + 0.62 \frac{f}{760}$, or as $\frac{760-0.38f}{760}$, is to 1; that is, the weight of air containing carbonic anhydride and moisture at 0° and 760 mm. pressure is not 1.2930 grams, but this weight multiplied by 1.000156 and by $1-0.38\frac{f}{760}$. At a pressure (total) of air of H millimetres, a temperature

t , and elasticity of vapour f , the weight of a litre of air will be (i.e., if at 0° and 760 mm. the weight of dry air = 1.293) equal to $1.29319 \times \frac{H-0.38f}{760}$. For instance, if $H = 730$ mm., $t = 20^\circ$, and $f = 10$ mm. (the moisture is then slightly below 60 p.c.), the weight of a litre of air = 1.1512 gram.³⁵

The presence of ammonia, a compound of nitrogen and hydrogen, in the air, is indicated by the fact that all acids exposed to the air absorb ammonia from it after a time. De Saussure observed that aluminium sulphate is converted by air into a double sulphate of ammonium and aluminium, or the so-called ammonia alum. Quantitative determinations have shown that the amount of ammonia ³⁶ contained in air varies at different periods. However, it may be accepted that 100 cubic

³⁴ The tension of the aqueous vapour in the air is determined by hygrometers and other similar methods. It may also be determined by analysis (see Chapter I. note 1).

³⁵ In determining the weight of small and heavy objects (crucibles, &c.) a correction may be introduced for the loss of weight in the air of the room, by taking the weight of a litre of air displaced as 1.2 gram, and consequently 0.0012 gram for every cubic centimetre. But if gases or, in general, large vessels are weighed, and the weighings have to be accurate, it is necessary to take into account all the data for the determination of the density of the air (t , H , and f), because sensitive balances can determine the possible variations of the weight of air, as in the case of a litre the weight of air varies in centigrams, even at a constant temperature, with variations of H and f . The following method was long ago (1859) proposed and applied by me for this purpose. A large light and closed vessel is taken, and its volume and weight in a vacuum are accurately determined, and verified from time to time. On weighing it we obtain the weight in air of a given density, and by subtracting this weight from its absolute weight and dividing by its volume we obtain the density of the air.

³⁶ Schloesing studied the equilibrium of the ammonia of the atmosphere and of the rivers, seas, &c., and he showed that its amount is interchangeable between them. The

metres of air do not contain less than 1 and not more than 5 milligrams of ammonia. It is remarkable that mountain air contains more ammonia than the air of valleys. The air in those places where animal substances undergoing change are accumulated, and especially that of stables, generally contains a much greater quantity of this gas. This is the reason of the peculiar pungent smell noticed in such places. Moreover ammonia, as we shall learn in the following chapter, combines with acids, and should therefore be found in air as such combinations, as air contains carbonic and nitric acids.

The presence of nitric acid in air is proved without doubt by the fact that rain-water contains a somewhat considerable amount of nitric acid, as we shall learn when speaking of this acid.

Further (as has been mentioned in Chapter IV.), air contains *ozone* and hydrogen peroxide.³⁷

Besides substances in a gaseous or vaporous state,³⁸ there is always found a more or less considerable quantity of substances which are not known in a state of vapour. These substances are carried in the air as *dust*. If a linen surface, moistened with an acid, be placed in perfectly pure air, then the washings are found to contain sodium, calcium, iron, and potassium.³⁹ Linen moistened with an alkali absorbs carbonic, sulphuric, phosphoric, and hydrochloric acids. Further, the presence

ratio between the amount of ammonia in a cubic metre of air and in a litre of water at $0^{\circ}=0.004$, at $10^{\circ}=0.010$, at $25^{\circ}=0.040$ to 1, and therefore in nature there is a state of equilibrium in the amount of ammonia in the atmosphere and waters.

³⁷ Whilst formed in the air, ozone and hydrogen peroxide at the same time rapidly disappear from it by oxidising those substances which are capable of being oxidised. Owing to this instability their amounts vary considerably, and, as would be expected, ozone is met with to an observable amount in pure air, whilst its amount decreases to zero in the air of cities, and especially in dwellings where there is a maximum of substances capable of oxidation and a minimum of conditions for the formation of ozone. There is a causal connection between the amount of ozone present in the air and its purity, that is, the amount of foreign residues of organic origin liable to oxidation present in the air. Where there is much of such residues the amount of ozone must be small, because when in contact with them it oxidises them and itself disappears. For this reason efforts have been made to apply ozone for purifying the air by evolving it by artificial means in the atmosphere; for instance, by passing a series of electrical sparks through the ventilating pipes leading air into a building. Air thus ozonised destroys, oxidises—that is, brings about the combustion of—the organic residues present in the air, and thus will serve for purifying it. For these reasons the air of cities contains less ozone than country air. This forms the distinguishing feature of country air. However, animal life cannot exist in air containing a comparatively large amount of ozone, just as it cannot in an atmosphere of pure oxygen.

³⁸ Amongst them we may mention iodine and alcohol, C_2H_6O , which Müntz found to be always present in air, the soil, and water, although in minute traces only.

³⁹ A portion of the atmospheric dust is of cosmic origin; this is undoubtedly proved by the fact of its containing metallic iron, as do meteorites. Nordenskiöld found iron in the dust covering snow, and Tissandier in every kind of air, although naturally in very small quantities.

of organic substances in air has been proved by a similar experiment. If a glass globe be filled with ice and placed in a room where are a number of people, then the presence of organic substances, like albuminous substances, may be proved in the water which condenses on the surface of the globe. It may be that the miasmas causing infection in marshy localities, hospitals, and in epidemic illnesses proceed from the presence of such substances in the air, as well as from the presence of germs of lower organisms borne in the air as a minute dust. Pasteur proved the presence of such germs in the air by the following experiment:—He placed gun-cotton (pyroxylin), which has the appearance of ordinary cotton, in a glass tube. Gun-cotton is soluble in a mixture of ether and alcohol, forming the so-called collodion. A current of air was passed through the tube for a long period of time, and the gun-cotton was then dissolved in a mixture of ether and alcohol. An insoluble residue was thus obtained which actually contained the germs of organisms, as was shown by microscopical observations, and by their capacity to develop into organisms (mould, &c.) under favourable conditions. The presence of these germs determines the property of air of bringing about the processes of rotting and fermentation—that is, the fundamental alteration of organic substances, which is accompanied by an entire change in their properties. The appearance of lower organisms, both vegetable and animal, is frequently to be remarked in these processes. Thus, for instance, in the process of fermentation, when, for example, wine is procured from the sweet juice of grapes, a sediment separates out which is known under the name of lees, and contains peculiar yeast organisms. Germs are required before these organisms can appear.⁴⁰ They are borne in the air, and fall into such substances from it. Finding themselves under favourable conditions, the germs develop into organisms; they are nourished at the expense of the organic substance, and during growth change and destroy it, and bring about corruption and rotting. This is why, for instance, the juice of the grape when contained in the skin of the fruit, which allows access of the air but is impenetrable to the germs, does not ferment, does not alter so long as the skin remains intact. This is also the reason why animal substances when kept from the access of air may be preserved for a great length of time. Conserves for long sea

⁴⁰ The idea of the spontaneous growth of organisms in a suitable medium, although still upheld by many, has since the work of Pasteur and his followers (and to a certain extent of his predecessors) been discarded, because it has been proved how, when, and whence (from the air, water, &c.) the germs appear; that fermentation as well as infectious diseases cannot take place without them; and mainly because it has been shown that any change accompanied by the development of the organisms introduced may be brought about at will by the introduction of the germs into a suitable medium.

voyages are preserved in this way.⁴¹ Hence it is evident that however infinitesimal the quantity the germs carried in the atmosphere may be, still they have an immense significance in nature.⁴²

Thus we see that air contains a great variety of substances. The nitrogen, which is found in it in the largest quantity, has the least influence on those processes which are accomplished by the action of air. The oxygen, which is met with in a lesser quantity than the nitrogen, on the contrary, takes a very important part in a number of reactions; it supports combustion and respiration, it brings about corruption and every process of slow oxidation. The part played by the moisture of air is known to everyone. The carbonic anhydride, which is met with in still smaller quantities, has an immense significance in nature, inasmuch as it serves for the nourishment of plants. The importance of the ammonia and nitric acid is immense, because they are the sources of the nitrogenous substances comprising an indispensable element in all living organisms. And, lastly, the infinitesimal quantity of germs evinces their significance in a number of processes. Thus it is not the quantitative but the qualitative relations of the component parts of the atmosphere which determine its importance in nature.⁴³

Air, being a mixture of various substances, may suffer considerable *changes* in consequence of incidental circumstances. It is particularly important to remark that change in the composition of air which takes place in dwellings and in various localities where human beings have to remain during a lengthy period of time. The respiration of human beings and animals alters the air.⁴⁴ A similar deterioration of air is produced by the influence of decomposing organic substances, and

⁴¹ In further confirmation of the fact that putrefaction and fermentation depend on germs carried in the air, we may cite the circumstance that poisonous substances destroying the life of organisms stop or hinder the appearance of the above processes. Air which has been heated to redness or passed through sulphuric acid no longer contains the germs of organisms, and loses the faculty of producing fermentation and putrefaction.

⁴² Their presence in the air is naturally due to the diffusion of germs into the atmosphere, and owing to their microscopical dimensions they, as it were, hang in the air in virtue of their large surfaces compared to their weight. In Paris the amount of dust hanging in the air equals from 6 (after rain) to 23 grams per 1000 c.m. of air.

⁴³ We see similar cases everywhere. For example, the predominating mass of sand and clay in the soil takes hardly any chemical part in the economy of the soil in respect to the nourishment of plants. The plants by their roots search for substances which are diffused in comparatively small quantities in the soil. If a large quantity of these nourishing substances be taken, then the plants will not develop in the soil, just as animals die in oxygen.

⁴⁴ A man in breathing burns about 10 grams of carbon per hour—that is, he produces about 880 grams, or (as 1 c.m. of carbonic anhydride weighs about 2000 grams) about $\frac{1}{2}$ c.m. of carbonic anhydride. The air coming from the lungs contains 4 p.c. of carbonic anhydride by volume. The exhaled air acts as a direct poison, owing to this gas and to other impurities.

especially of substances burning in it.⁴⁵ Hence it is necessary to have regard to the purification of the air of dwellings. The renewal of air, the replacing of respired by fresh air, is termed 'ventilation,'⁴⁶ and the

⁴⁵ For this reason candles, lamps, and gas change the composition of air almost in the same way as respiration. In the burning of 1 kilogram of stearin candles, 50 cubic metres of air are changed as by respiration—that is, 4 p.c. of carbonic acid will be formed in this volume of air. The respiration of animals and exhalations from their skins, and especially from the intestine and the excrements and the transformations taking place in them, spoil the air to a still greater extent, because they introduce other volatile substances besides carbonic anhydride into the air. At the same time that carbonic anhydride is formed the amount of oxygen in the air decreases, and consequently the relative amount of nitrogen increases, together with which there is noticed the appearance of miasmata which occur in but small quantity, but which are noticeable in passing from fresh air into space full of such adulterated air. The researches of Schmidt and Leblanc and others show that with 20·6 p.c. of oxygen (instead of 20·9 p.c.), when the diminution is due to respiration, air already becomes noticeably heavy and unfit for respiration, and that the heavy feeling experienced in such air increases with a lesser percentage of oxygen. It is difficult to remain for a few minutes in air containing 17·2 p.c. of oxygen. These observations were chiefly obtained by observations on the air of different mines, at different depths below the surface. The air of theatres and buildings full of people also proves to contain less oxygen; it was once found that at the end of a theatrical representation the air at the stalls contained 20·75 p.c. of oxygen, whilst the air at the upper part of the theatre contained only 20·36 p.c. The amount of carbonic anhydride in the air may be taken as a measure of its purity (Pettenkofer). When it reaches 1 p.c. it is very difficult for human beings to remain long in such air, and it is necessary to set up a vigorous ventilation for the removal of the adulterated air. In order to keep the air in dwellings in a uniformly good state, it is necessary to introduce at least 10 cubic metres of fresh air per hour per person. We saw that a man exhales about five-twelfths cubic metres of carbonic anhydride per day. Accurate observations have shown that air containing one-tenth p.c. of exhaled carbonic anhydride (and consequently also a corresponding amount of the other substances evolved together with it) is not yet felt as spoilt; and therefore the five-twelfth cubic metres of carbonic anhydride should be diluted with 420 cubic metres of fresh air if it be desired to keep not more than one-tenth p.c. (by volume) of carbonic anhydride in the air. Hence a man requires 420 cubic metres of air per day, or 18 cubic metres per hour. With the introduction of only 10 cubic metres of fresh air per person, the amount of carbonic anhydride may reach one-fifth p.c., and the air will not then be of the required freshness.

⁴⁶ The *ventilation* of inhabited buildings is most necessary, and is even indispensable in hospitals, schools, and similar buildings. In winter it is carried on by the so-called calorifiers or stoves heating the air before it enters. The best kind of calorifiers in this respect are those in which the fresh cold air is led through a series of channels heated by the hot gases coming from a stove. In ventilation, particularly during winter, care is taken that the incoming air shall be moist, because in winter the amount of moisture in the air is very small. Ventilation, besides introducing fresh air into a dwelling-place, must also withdraw the air already spoilt by respiration and other causes—that is, it is necessary to construct channels for the escape of the bad air, besides those for the introduction of fresh air. In ordinary dwelling-places, where not many people are congregated, the ventilation is conducted by natural means, in the heating by fires, through crevices, windows, and various orifices in walls, doors, and windows. In mines, factories, and works ventilation is of the greatest importance.

Animal vitality may still continue for a period of several minutes in air containing up to 30 p.c. of carbonic anhydride, if the remaining 70 p.c. consist of ordinary air, but respiration ceases after a certain time, and death may even ensue. The flame of a candle is extinguished in an atmosphere containing from 5 to 6 p.c. of carbonic anhydride,

removal of impurities from the air is called 'disinfection.'⁴⁷ The accumulation of all kinds of impurities in the air of dwellings and cities is the reason why the air of mountains, forests, seas, and non-marshy localities, covered with vegetation or snow, is distinguished for its freshness, and, in all respects, beneficial action.

but animal vitality can be sustained in it for a somewhat long time, although the effect of such air is exceedingly painful to even the lower animals. There are mines in which a lighted candle easily goes out from the excess of carbonic anhydride, but in which the miners have to remain for a long time. The properties of air may be considerably vitiated by the combustion of charcoal, wood, and similar substances in it, even when it contains a comparatively small amount of carbonic anhydride. This doubtless depends on the fact that certain gaseous substances are formed in the act of combustion (carbonic oxide, acetylene, hydrocyanic acid, and others) which are positively injurious to breathe. The action of charcoal fumes and smoke is based on this fact. The presence of 1 p.c. of carbonic oxide is deadly even to cold-blooded animals. The air of explosive mines, where explosions are made, is known to produce a state of insensibility resembling that produced by charcoal fumes. Deep wells and vaults not unfrequently contain similar substances, and their atmosphere often causes suffocation. The atmospheres of such places cannot be tested by lowering a lighted candle into it, as these poisonous gases would not extinguish the flame. This method only suffices to indicate the amount of carbonic anhydride. If a candle keeps alight, it signifies that there is less than 5 p.c. of this gas. In doubtful cases it is best to lower a dog or other animal into the air to be tested.

⁴⁷ Different so-called disinfectants are capable of purifying the air, and of preventing the injurious action of certain of its components by changing or destroying them. Disinfection is especially necessary in those places where a considerable amount of volatile substances are evolved into the air, and where organic substances are decomposed; for instance, in hospitals, closets, &c. The numerous disinfectants are of the most varied nature. They may be divided into the following chief categories: oxidising substances, antiseptic substances, and absorbent substances. To the oxidising substances used for disinfection belong chlorine, and various substances evolving it, because chlorine in the presence of water oxidises the majority of organic substances. Further, to this class belong the permanganates of the alkalis, as substances easily oxidising matters dissolved in water; these salts are not volatile like chlorine, and therefore act much more slowly, and in a much more limited sphere. Antiseptic substances are those which convert organic substances into such as are little prone to change, and prevent putrefaction and fermentation. They most probably kill the germs of organisms occurring in miasmata. The most important of these substances are creosote and phenol (carbolic acid), which occur in tar, and which act in preserving smoked meat. Phenol is a substance little soluble in water, volatile, oily, and having the characteristic smell of smoked objects. Its action on animals in considerable quantities is injurious, but in small quantities, used in the form of a weak solution, it prevents the change of animal matter. The smell of privies, which depends on the change of excremental matter, may be easily removed by means of chlorine or phenol. Salicylic acid, thymol, common tar, &c., are also substances having the same property. They are used in special cases, but naturally not so generally. Absorbent substances are of no less importance than the preceding two classes of disinfectants, inasmuch as they act regularly and are innocuous. They are such substances as absorb the odoriferous gases and vapours emitted during putrefaction, which are chiefly ammonia, sulphuretted hydrogen, and other volatile compounds. To this class belong charcoal, certain salts of iron, gypsum, salts of magnesia, and such like substances, as well as peat, mould, and clay. Their employment is profitable, not only for removing the odour, but also in the radical destruction of miasmata. The questions both of disinfection and ventilation appertain to the most serious problems of common life and hygiene. These questions are so vast that we are here able only to give a short outline of their nature.

CHAPTER VI

THE COMPOUNDS OF NITROGEN WITH HYDROGEN AND OXYGEN

IN the last chapter we saw that nitrogen does not immediately combine with hydrogen, but that a mixture of these gases in the presence of hydrochloric acid gas, HCl , forms ammonium chloride, NH_4Cl , on the passage of a series of electric sparks.¹ In ammonium chloride, HCl is combined with NH_3 , consequently N with H_3 forms ammonia.² Almost all the *nitrogenous substances of plants and animals* evolve ammonia when heated with an alkali. But even without the presence of an alkali the majority of nitrogenous substances, when decomposed or heated with a limited supply of air, evolve their nitrogen, if not entirely, at all events partially, in the form of ammonia. Thus, when animal substances such as skins, bones, flesh, hair, horns, &c., are heated without access of air in iron retorts—or, as it is termed, are subjected to dry distil-




FIG. 42. The dry distillation of bones on a large scale. The bones are heated in the vertical cylinders C (about 1½ metres high and 30 centimetres in diameter). The products of distillation pass through the tubes T , into the condenser B , and receiver F . When the distillation is completed the trap H is opened, and the burnt bones are loaded into trucks V . The roof M is then opened, and a fresh quantity of bones charged into the cylinders. The ammonia water is preserved, and goes to the preparation of ammoniacal salts, as described in the following drawing.

¹ The ammonia in the air, water, and soil proceeds from the decomposition of the nitrogenous substances of plants and animals, and also probably from the reduction of nitrates. Ammonia is always formed in the rusting of iron. Its formation in this case depends in all probability on the decomposition of water, and on the action of the hydrogen at the moment of its evolution on the nitric acid contained in the air (Cloez), or on the formation of ammonium nitrite, which takes place under many circumstances. The evolution of vapours of ammonia compounds is sometimes observed in the vicinity of volcanoes.

² If a silent discharge (as in the ozonisation of oxygen), or a series of electric sparks (for instance, in a eudiometer), be passed through ammonia gas, it is decomposed

lation, they decompose. A portion of the substances proceeding from the decomposition remains in the retort and forms a carbonaceous residue, whilst the other portion, in virtue of its volatility, escapes through the tube leading from the retort. The vapours given off, on cooling, form a liquid which separates into two layers; the one, which is oily, is composed of the so-called animal oils (*oleum animale*), the other, an aqueous layer, contains a solution of ammonia salts. If this solution be mixed with lime and heated, the lime takes up the elements of carbonic acid from the ammonia salts, and ammonia is evolved as a gas.³ In ancient times ammonia compounds were imported into Europe from Egypt, where they were prepared from the soot obtained in the employment of camels' dung as fuel in the locality of the temple of Jupiter Ammon (in Lybia), and therefore the salt obtained was called 'sal-ammoniacale,' from which the name of ammonia is derived. Now ammonia is exclusively obtained, on a large scale, either from the products of the dry distillation of animal or vegetable refuse, from urine, or from the ammoniacal liquors collected in the destructive distillation of coal

into nitrogen and hydrogen. This is a phenomenon of dissociation, as was explained in the preceding chapter, p. 227. Therefore, a series of sparks do not totally decompose the ammonia, but leave a certain portion undecomposed. One volume of nitrogen and three volumes of hydrogen are obtained from two volumes of ammonia. The presence of free ammonia—that is, ammonia not combined with acids—in a gas or aqueous solution may be recognised by its characteristic smell. But many ammonia salts do not possess this smell. However, on the addition of an alkali (for instance, caustic lime, potash, or soda), they evolve ammonia gas, especially when heated. The presence of ammonia may be made visible by introducing a substance moistened with strong hydrochloric acid into its neighbourhood. A white cloud, or visible white vapour, then makes its appearance. This depends on the fact that both ammonia and hydrochloric acid are volatile, and on coming into contact with each other form solid sal-ammoniac, NH_4Cl , which forms a cloud. This test is usually made by dipping a glass rod into hydrochloric acid, and holding it over the vessel from which the ammonia is evolved. With small amounts of ammonia this test is, however, untrustworthy, as the white vapour is scarcely observable. In this case it is best to take paper moistened with mercurous nitrate, HgNO_3 . This paper turns black in the presence of ammonia, owing to the formation of a black compound of ammonia with mercurous oxide. The smallest traces of ammonia, for instance, in river water, may be discovered by means of the so-called Nessler's reagent, containing a solution of mercuric chloride and potassium iodide, which forms a brown coloration or precipitate with the smallest quantities of ammonia. Here it will be useful to give the thermo-chemical data (in thousands of units of heat, according to Thomsen), or the quantities of heat evolved in the formation of ammonia and its compounds in quantities expressed by their formulæ. Thus, for instance ($\text{N} + \text{H}_3$) 26.7 indicates that 14 grams of nitrogen in combining with 3 grams of hydrogen develop sufficient heat to raise the temperature of 26.7 kilograms of water 1° . ($\text{NH}_3 + n\text{H}_2\text{O}$) 8.4 (heat of solution); ($\text{NH}_3, n\text{H}_2\text{O} + \text{HCl}, n\text{H}_2\text{O}$) 12.3; ($\text{N} + \text{H}_4 + \text{Cl}$) 90.6; ($\text{NH}_3 + \text{HCl}$) 41.9.

³ The same ammonia water is obtained, although in smaller quantities, in the dry distillation of plants and of coal, which consists of the remains of fossil plants. In all these cases the ammonia proceeds from the destruction of the complex nitrogenous substances occurring in plants and animals. The ammonia salts employed in practice are prepared by this method.

for the preparation of coal gas. This ammoniacal liquor is placed in a retort with lime and heated; the ammonia is then evolved together with steam.⁴ In practice, only a small amount of ammonia is used in a free state—that is, in an aqueous solution; the greater portion of it is converted into different salts having technical uses, especially sal-ammoniac, NH_4Cl , and ammonia sulphate, $(\text{NH}_4)_2\text{SO}_4$. They are saline substances which are formed because ammonia, NH_3 , combines with all acids, HX , forming ammonia salts, NH_4X . Sal-ammoniac, NH_4Cl , is




FIG. 43.—Method of abstracting ammonia, on a large scale, from ammonia water obtained at gas works by the dry distillation of coal, or by the fermentation of urine, &c. This water is mixed with lime and poured into the boiler C'' , and from thence into C' and C consecutively. The last boiler is heated directly over a furnace, and therefore no ammonia remains in solution after the liquid has been boiled in it. The liquid is therefore then thrown away. The ammonia vapour and steam pass from the boiler C , through the tube T , into the boiler C' , and then into C'' , so that the solution in C' becomes stronger than that in C , and still stronger in C'' . The boilers are furnished with stirrers A , A' , and A'' to prevent the lime settling. From C'' the ammonia and steam pass through the tube T'' into worm condensers surrounded with cold water, from thence into the Woulfe's bottle P , where the solution of ammonia is collected, and from whence the still uncondensed ammonia vapour is led into the flat vessel R , containing acid which retains traces of ammonia.

a compound of ammonia with hydrochloric acid. It is prepared by passing the vapours of ammonia and water, evolved, as above described, from ammoniacal liquor, into an aqueous solution of hydrochloric acid, and on evaporating the solution sal-ammoniac is obtained in the form of soluble crystals⁵ resembling common salt in appearance and pro-

⁴ The technical methods for the preparation of ammonia water, and for the extraction of ammonia from it, are to a certain extent explained in the figures accompanying the text.

⁵ Usually these crystals are sublimed by heating them in crucibles or pots, when the vapours of sal-ammoniac condense on the cold covers as a crust, in which form it comes into the market.

perties. *Ammonia* may be very easily prepared from this *sal-ammoniac*, NH_4Cl , as from any other ammoniacal salt, by heating it with lime. Calcium hydroxide, CaH_2O_2 , as an alkali takes up the acid and sets free the ammonia, forming calcium chloride, according to the equation $2\text{NH}_4\text{Cl} + \text{CaH}_2\text{O}_2 = 2\text{H}_2\text{O} + \text{CaCl}_2 + 2\text{NH}_3$. In this reaction the ammonia, as a gas, is evolved.⁶

It must be observed that all the complex nitrogenous substances of plants, animals, and soils are decomposed when heated with an excess of sulphuric acid, the whole of their nitrogen being converted into ammonium sulphate, from which it may be liberated by treatment with an excess of alkali. This reaction is so complete that it forms the basis of Kjeldahl's method for estimating the amount of nitrogen in its compounds.

Ammonia is a colourless gas, resembling those with which we are already acquainted in its outward appearance but clearly distinguishable from any other gas by its very characteristic and strong smell. It irritates the eyes, and it is positively impossible to inhale it. Animals die in it. Its density, referred to hydrogen, is 8.5; hence it is lighter than air. It belongs to the class of gases which are easily liquefied.⁷

⁶ On a small scale ammonia may be prepared in a glass flask by mixing equal parts by weight of slacked lime and finely-powdered sal-ammoniac, the neck of the flask being connected with an arrangement for drying the gas obtained. In this instance neither calcium chloride nor sulphuric acid can be used for drying the gas, because they absorb ammonia, and therefore solid caustic potash, which is capable of retaining the water, is employed. The gas conducting tube leading from the desiccating apparatus is introduced into a mercury bath, if dry gaseous ammonia be required, because water cannot be employed in collecting ammonia gas. Ammonia was first obtained in this dry state by Priestley, and its composition was investigated by Berthollet at the end of the last century. Oxide of lead mixed with sal-ammoniac (Isambert) evolves ammonia with still greater ease than lime. The cause and process of the decomposition is almost the same, $2\text{PbO} + 2\text{NH}_4\text{Cl} = \text{Pb}_2\text{OCl}_2 + \text{H}_2\text{O} + 2\text{NH}_3$. Lead oxychloride is (probably) formed.

⁷ This is evident from the fact that its absolute boiling point lies about $+130^\circ$ (Chap. II. Note 29). Consequently, it may be liquefied by pressure alone at the ordinary, and even much higher, temperatures. The latent heat of evaporation of 17 parts by weight of ammonia equals 4400 units of heat, and therefore liquid ammonia may be employed for the production of cold. Strong aqueous solutions of ammonia, which in parting with their ammonia act in a similar manner, are not unfrequently employed for this purpose. Suppose a saturated solution of ammonia to be held in a closed vessel furnished with a receiver. If the ammoniacal solution be heated, the ammonia, with a small quantity of water, will pass off from the solution, and in accumulating in the apparatus will produce a considerable pressure, and will therefore liquefy in the cooler portions of the receiver. Hence liquid ammonia will be obtained in the receiver. The heating of the vessel containing the aqueous solution of ammonia is then stopped. After having been heated it contains only water, or a solution poor in ammonia. When once it begins to cool, the ammonia vapours commence dissolving in it, the space becomes rarefied, and a rapid vaporisation of the liquefied ammonia left in the receiver takes place. In evaporating in the receiver it will cause the temperature in it to fall considerably, and will itself pass into

Faraday employed the following method for liquefying ammonia. Ammonia, when passed over dry silver chloride, AgCl , is absorbed by it to a considerable extent, especially at low temperatures.⁸ The solid

the aqueous solution. In the end, the same ammoniacal solution as was originally taken is re-obtained. Thus, in this case, on heating the vessel the pressure increases of itself, and on cooling it diminishes, so that here heat directly replaces mechanical work. This is the principle of the simplest forms of *Carré's ice-making machines*, shown in fig. 44. C is a vessel made of boiler plates into which the saturated solution of ammonia is poured; *m* is a tube conducting the ammonia vapour to the receiver A. All parts of the apparatus should be hermetically joined together, and should be able to withstand a pressure reaching ten atmospheres. The apparatus should be freed from air, which




FIG. 44.—Carré's apparatus. Described in text.

would otherwise hinder the liquefaction of the ammonia. The process is carried on as follows:—The apparatus is first so inclined that any liquid remaining in A may flow into C. The vessel C is then placed upon a stove F, and heated until the thermometer *t* indicates a temperature of 180°C . During this time the ammonia has been expelled from C, and has liquefied in A. In order to facilitate the liquefaction, the receiver A should be immersed in a tank of water R (see the left-hand drawing in fig. 44). After about half an hour, when it may be supposed that the ammonia has been expelled, the fire is removed from under C, and this is now immersed in the tank of water R. The apparatus is represented in this position in the right-hand drawing of fig. 44. Then the liquefied ammonia evaporates, and passes over into the water in C. This causes the temperature of A to fall considerably. The substance to be refrigerated is placed in a vessel G, in the cylindrical space inside the receiver A. The refrigeration is also kept on for about half an hour, and with an apparatus of ordinary dimensions (containing about two litres of ammonia solution), five kilograms of ice are produced by the consumption of one kilogram of coal. In industrial works more complicated types of Carré's machines are employed.

⁸ Below 15° (according to Isambert), the compound $\text{AgCl}\cdot 3\text{NH}_3$ is formed, and above 20° the compound $2\text{AgCl}\cdot 3\text{NH}_3$. The tension of the ammonia evolved from the latter

compound $\text{AgCl}\cdot 3\text{NH}_3$ thus obtained is introduced into a bent tube (fig. 45), whose open end *c* is then fused up. The compound is then slightly heated at *a*, and the ammonia comes off, owing to the easy dissociation of the compound. The other end of the tube is immersed




FIG. 45.—The liquefaction of ammonia in a thick bent glass tube. A compound of chloride of silver and ammonia is placed in the end *a*, and the end *c* is then sealed up.

in a freezing mixture. The pressure of the gas coming off, combined with the low temperature at one end of the tube, causes the ammonia evolved to condense into a liquid, in which form it collects at the cold end of the tube. If the heating be stopped, the silver chloride again absorbs the ammonia. In this manner, one tube may serve for repeated experiments. Ammonia

may also be liquefied by the ordinary methods—that is, by means of pumping dry ammonia gas into a refrigerated space. Liquefied ammonia is a colourless and very mobile liquid,⁹ whose specific gravity at 0° is 0.63 (E. Andr  eff). At the temperature (about -70°) given by a mixture of liquid carbonic anhydride and ether, liquid ammonia crystallises, and in this form its odour is feeble, because at so low a temperature its vapour tension is very inconsiderable. The boiling point (at a pressure of 760 mm.) of liquid ammonia is about -32° . Hence this temperature may be obtained at the ordinary pressure by the evaporation of liquefied ammonia.

Ammonia, containing, as it does, much hydrogen, is *capable of combustion*; it does not, however, burn regularly, and sometimes not at all, in the ordinary atmospheric air. In pure oxygen it burns with a greenish-yellow flame,¹⁰ forming water, whilst the nitrogen set free

substance is equal to the atmospheric pressure at 68° , whilst for $\text{AgCl}\cdot 3\text{NH}_3$ the pressures are equal at about 20° ; consequently, at higher temperatures it is greater than the atmospheric pressure, whilst at lower temperatures the ammonia, being absorbed by the silver chloride, forms this compound. Consequently, all the phenomena of dissociation are here clearly to be observed.

⁹ The liquefaction of ammonia may be accomplished without an increase of pressure, by means of refrigeration alone, in a carefully-prepared mixture of ice and calcium chloride. It may even take place in the severe frosts of a Russian winter. The application of liquid ammonia as a motive power for engines forms a problem which has to a certain extent been solved by the French engineer Tellier.

¹⁰ The combustion of ammonia in oxygen may be effected by the aid of platinum. A small quantity of an aqueous solution of ammonia, containing about 20 p.c. of ammonia, is poured into a wide-necked beaker of about one litre capacity. A gas-conducting tube about 10 mm. in diameter, and supplying oxygen, is immersed in the aqueous solution of ammonia. But before introducing the gas an incandescent platinum spiral is placed in the beaker; the ammonia in the presence of the platinum is oxidised and burns, whilst the platinum wire becomes still more incandescent. The ammonia is then heated, and the oxygen passed into the solution. The oxygen, as it bubbles off from the ammonia solution, carries off a part of the ammonia with it, and this mixture explodes on coming into contact with the incandescent platinum. This is followed by a certain cooling effect,

gives its oxygen compound—that is, oxide of nitrogen. The decomposition of ammonia into hydrogen and nitrogen not only takes place at a red heat and under the action of electric sparks, but also by means of many oxidising substances; for instance, by passing ammonia through a tube containing red-hot copper oxide. The water thus formed may be collected by substances absorbing it, and the quantity of nitrogen may be measured in a gaseous form, and thus the composition of ammonia determined. In this manner it is very easy to prove that ammonia contains 3 parts by weight of hydrogen to 14 parts by weight of nitrogen; and, by volume, 3 vols. of hydrogen and 1 vol. of nitrogen form 2 vols. of ammonia.¹¹

Ammonia is capable of combining with a number of substances, forming, like water, substances of various degrees of stability. It is more soluble than any other known gas, both in water and in many aqueous solutions. We have already seen, in the first chapter, that one volume of water, at the ordinary temperature, dissolves about 700 vols. of ammonia gas. The great solubility of ammonia enables it to be always kept ready for use in the form of an aqueous solution¹² which is commercially known as *spirits of hartshorn*. Ammonia water

owing to the combustion ceasing, but after a short interval this is, however, renewed, so that one feeble explosion follows after another. During the period of oxidation without explosion, white vapours of ammonium nitrite and red-brown vapours of oxides of nitrogen make their appearance, while during the explosion there is complete combustion, and consequently water and nitrogen are formed.

¹¹ This may be verified by their densities. Nitrogen is 14 times denser than hydrogen, and ammonia is $8\frac{1}{2}$ times. If 3 volumes of hydrogen with 1 volume of nitrogen gave 4 volumes of ammonia, then these 4 volumes would weigh 17 times more than 1 volume of hydrogen; consequently, 1 volume of ammonia would weigh $4\frac{1}{4}$ times heavier than the same volume of hydrogen. But as these 4 volumes only give 2 volumes of ammonia, therefore they weigh $8\frac{1}{2}$ times heavier than hydrogen, which we find to be actually the case.

¹² Aqueous solutions of ammonia are lighter than water, and at 15° , taking water at $4^{\circ} = 10000$, their specific gravity, as dependent on p , or the percentage amount (by weight) of ammonia, is given by the expression $s = 9992 - 42.5p + 0.21p^2$; for instance, with 10 p.c. $s = 9587$. If the temperature be $= t^{\circ}$, but not less than 10° or above 20° , then the expression $(15 - t)(1.5 + 0.14p)$ must be added to the formula for the specific gravity. Solutions containing above 24 p.c. have not been sufficiently investigated in respect to the variation of their specific gravity. It is, however, easy to obtain more concentrated solutions, and at 0° solutions approaching $\text{NH}_5 \cdot \text{H}_2\text{O}$ (48.6 p.c. NH_3) in their composition, and of sp. gr. 0.85, may be prepared. But such solutions give up the bulk of their ammonia at the ordinary temperature, so that more than 24 p.c. NH_3 is rarely contained in solution. Ammoniacal solutions containing a considerable amount of ammonia give ice-like crystals at temperatures far below 0° (for instance, an 8 p.c. solution at -14° , the strongest solutions at -48°) which seem to contain ammonia. The whole of the ammonia may be expelled from a solution by heating, even at a comparatively low temperature; therefore, in heating aqueous solutions containing ammonia a very strong solution of ammonia is obtained in the distillate. Alcohol, ether, and many other liquids are also capable of dissolving ammonia. Solutions of ammonia, when exposed to the atmosphere,

is continually evolving ammoniacal vapour, and so has the characteristic smell of ammonia itself. It is a very characteristic and important fact that ammonia has an alkaline reaction, and colours litmus paper blue, just like caustic potash or lime ; it is therefore sometimes called *caustic ammonia* (volatile alkali). Acids may be saturated by ammonia water or gas in exactly the same way as by any other alkali. In so doing, *ammonia combines directly with acids*, and this forms the most essential chemical reaction of this substance. If sulphuric, nitric, acetic, or any

give off a part of their ammonia, in accordance with the laws of the solution of gases in liquids already considered by us. But the ammoniacal solutions at the same time absorb carbonic anhydride from the air, and ammonium carbonate remains in the solution.

Solutions of ammonia are required both in the laboratory and in practice, and have therefore to be frequently prepared. For this purpose the arrangement shown in fig. 46 is employed in the laboratory. In works the same arrangement is used, only on a larger scale (with earthenware or metallic vessels). The gas is prepared in the retort, from





FIG. 46.—Apparatus for preparing solutions of ammonia.

whence it is led into the two-necked globe A, and then through a series of Woulfe's bottles, B, C, D, E. The impurities spurting over collect in A, and the gas is dissolved in B, but the solution soon becomes saturated, and a purer (washed) ammonia passes over into the following vessels, in which only a pure solution is obtained. The bent funnel tube in the retort preserves the apparatus from the possibility both of the pressure of the gas evolved in it becoming too great (when the gas escapes through it into the air), and also from the pressure incidentally falling too low (for instance, owing to a cooling effect, or from the reaction stopping). If this takes place, the air passes into the retort, otherwise the liquid from B would be drawn into A. The safety tubes in each Woulfe's bottle, open at both ends, and immersed in the liquid, serve for the same purpose. Without them, in case of an accidental stoppage in the evolution of so soluble a gas as ammonia, the solution would be sucked from one vessel to another—for instance from E into D, &c. In order to clearly see the necessity of the *safety tubes* in a gas apparatus, it must be considered that the *gaseous pressure* in the interior of the arrangement must exceed the atmospheric pressure by the height of the sum of the columns of liquid through which the gas has to pass.

other acid be brought into contact with ammonia it absorbs it, and in so doing evolves a large amount of heat and forms a compound having all the properties of a salt. Thus, for example, sulphuric acid, H_2SO_4 , in absorbing ammonia, forms (on evaporating the solution) two salts, according to the relative quantities of ammonia and acid. One salt is formed from $\text{NH}_3 + \text{H}_2\text{SO}_4$, and consequently has the composition NH_4SO_4 , and the other is formed from $2\text{NH}_3 + \text{H}_2\text{SO}_4$, and its composition is therefore $\text{N}_2\text{H}_8\text{SO}_4$. The former has an acid reaction and the latter a neutral reaction, and they are called respectively acid ammonium sulphate (ammonium hydrogen sulphate), and normal ammonium sulphate, or simply ammonium sulphate. The same takes place in the action of all other acids; but certain of them are able to form normal ammonium salts only, whilst others give both acid and normal ammonium salts. This depends on the nature of the acid and not on the ammonia, as we shall afterwards see. Ammonium salts are very similar in appearance and in many of their properties to metallic salts; for instance, sodium chloride, or table salt, resembles sal-ammoniac, or ammonium chloride, not only in its outward appearance but even in crystalline form, in its property of giving precipitates with silver salts, in its solubility in water, and in its evolving hydrochloric acid when heated with sulphuric acid—in a word, a most perfect analogy is to be remarked in an entire series of reactions. An analogy in composition is seen if sal-ammoniac, NH_4Cl , be contrasted with table salt, NaCl ; and the ammonium hydrogen sulphate, NH_4HSO_4 , with the sodium hydrogen sulphate, NaHSO_4 ; or ammonium nitrate, NH_4NO_3 , with sodium nitrate, NaNO_3 .¹³ It is seen, on comparing the above compounds, that the part which sodium takes in the sodium salts is played in ammonium salts by a group NH_4 , which is called *ammonium*. If table salt, as the product obtained by the action of caustic soda or sodium hydroxide on hydro-

¹³ The analogy between the ammonium and sodium salts might seem to be destroyed by the fact that the latter are formed from the alkali or oxide and an acid, with the separation of water, whilst the ammonium salts are directly formed from ammonia and an acid, without the separation of water; but the analogy is restored if we compare soda to ammonia water, and liken caustic soda to a compound of ammonia with water. Then the very preparation of ammonia salts from such a hydrate of ammonia will completely resemble the preparation of sodium salts from soda. We may cite as an example the action of hydrochloric acid on both substances.



Just as in soda the hydroxyl or aqueous radicle OH is replaced by chlorine, so it is in ammonia hydrate.

chloric acid, be called 'sodium chloride,' then sal-ammoniac, as the product obtained from caustic ammonia or ammonium hydroxide, is called 'ammonium chloride.'

The hypothesis that ammoniacal salts correspond with a complex metal ammonium bears the name of the *ammonium theory*. It was enunciated by the famous Swedish chemist Berzelius after the proposition made by Ampère. The analogy admitted between ammonium and metals is probable, owing to the fact that mercury is able to form an amalgam with ammonium similar to that which it forms with sodium or many other metals. The only difference between ammonium amalgam and sodium amalgam consists in the instability of the ammonium, which easily decomposes into ammonia and hydrogen.¹⁴ Ammonium amalgam may be prepared from sodium amalgam. If the latter be shaken up with a strong solution of sal-ammoniac, the mercury swells up violently and loses its mobility while preserving its metallic appearance. In so doing, the mercury dissolves ammonium—that is, the sodium in the mercury is replaced by the ammonium, and replaces it in the sal-ammoniac, forming sodium chloride, $\text{NH}_4\text{Cl} + \text{HgNa} = \text{NaCl} + \text{HgNH}_4$. Naturally, ammonium amalgam does not entirely prove the existence of ammonium itself in a separate state; but it shows the possibility of this substance existing, and, what is more important, its analogy with the metals, because only metals dissolve in mercury, forming compounds termed 'amalgams,' without altering its metallic form.¹⁵ Ammonium amalgam crystallises in cubes, three times heavier than water; it is only stable in the cold, and particularly at very low temperatures. It begins to decompose at the ordinary temperature, evolving ammonia and hydrogen in the proportion of two volumes of ammonia and one

¹⁴ Weyl, by working at considerable pressures, obtained the compound NH_5K , and then ammonium itself—by the action of sal-ammoniac on this substance—in the form of a blue liquid, but his researches require confirmation. Ammonium amalgam was originally obtained in exactly the same way as sodium amalgam (Davy); namely, a piece of sal-ammoniac was taken, and moistened with water (in order to render it a conductor of electricity). A cavity was made in it, into which mercury was poured, and it was laid on a sheet of platinum connected with the positive pole of a galvanic battery, while the negative pole was put into connection with the mercury. On passing a current the mercury increased considerably in volume, and became plastic, while preserving its metallic appearance, just as would be the case were the sal-ammoniac replaced by a lump of a sodium salt or of many other metals. In the analogous decomposition of common metallic salts, the metal contained in a given salt separates out at the negative pole, immersed in mercury, by which the metal is dissolved. A similar phenomenon is observed in the case of sal-ammoniac; the elements of ammonium, NH_4 , in this case are also collected in the mercury, and are retained by it for a certain time.

¹⁵ It would seem that hydrogen is also capable of forming an amalgam resembling the amalgam of ammonium. If an amalgam of zinc be shaken up with an aqueous solution of platinum chloride, without access of air, then a spongy mass is formed which easily decomposes, with the evolution of hydrogen.

volume of hydrogen, $\text{NH}_4 = \text{NH}_3 + \text{H}$. By the action of water, ammonium amalgam gives hydrogen and ammonia water, just as sodium amalgam gives hydrogen and sodium hydroxide; and therefore, in accordance with the ammonium theory, ammonia water must be looked on as containing ammonium hydroxide, NH_4OH ,¹⁶ just as an aqueous solution of sodium hydroxide contains NaOH . The ammonium hydroxide, like ammonium itself, is an unstable substance, which easily dissociates, and which can only exist in a free state at low temperatures.¹⁷ Ordinary solutions of ammonia must be looked on as the products of the dissociation of this hydroxide, inasmuch as $\text{NH}_4\text{OH} = \text{NH}_3 + \text{H}_2\text{O}$. The liability to a greater or less decomposition is proper, in the same degree, to substances containing NH_3 as to substances containing water.

All ammoniacal salts *decompose at a red heat* into ammonia and an acid, which, on cooling in contact with each other, re-combine together. If the acid be non-volatile, the ammoniacal salt, when heated, evolves the ammonia, leaving the non-volatile acid behind; if the acid be volatile, then, on heating, both the acid and ammonia volatilise together, and on cooling re-combine into the salt which originally served for the formation of their vapours.¹⁸

Ammonia is not only capable of combining with acids, but also with many salts, as was seen from its forming definite compounds, $\text{AgCl} \cdot 3\text{NH}_3$ and $2\text{AgCl} \cdot 3\text{NH}_3$, with silver chloride. So, also, ammonia is absorbed by the chlorine, iodine, and bromine compounds of many metals, and in so doing evolves heat. Certain of these com-

¹⁶ We saw above that the solubility of ammonia in water at low temperatures attains to the molecular ratio $\text{NH}_3 + \text{H}_2\text{O}$, in which these substances are contained in caustic ammonia, and perhaps it may be possible at exceedingly low temperatures to obtain ammonium hydroxide, NH_4HO , in a solid form. By regarding solutions as dissociated definite compounds, we should see a confirmation of this view in the property shown by ammonia of being extremely soluble in water, and in so doing of approaching to the limit NH_4HO .

¹⁷ In confirmation of the truth of this conclusion we may cite the remarkable fact that there exist, in a free state and as comparatively stable compounds, a series of alkaline hydroxides, NR_4HO , which are perfectly analogous to ammonium hydroxide, and present a striking resemblance to it and to sodium hydroxide, with the only difference that the hydrogen in NH_4HO is replaced by complex groups, $\text{R} = \text{CH}_3$, C_2H_5 , &c., for instance $\text{N}(\text{CH}_3)_4\text{HO}$.

¹⁸ The fact that ammoniacal salts are decomposed when ignited, and not simply sublimed, may be proved by a direct experiment with sal-ammoniac, NH_4Cl , which in a state of vapour is decomposed into ammonia, NH_3 , and hydrochloric acid, HCl , as will be explained in the following chapter. The readiness with which ammonium salts decompose is seen from the fact that a solution of ammonium oxalate is decomposed with the evolution of ammonia even at -1° . Dilute solutions of ammonium salts, when boiled, give aqueous vapour, having an alkaline reaction, owing to the presence of free ammonia given off from the salt.

pounds part with their ammonia even when left exposed to the air, but others only do so at a red heat; many give up their ammonia when dissolved, whilst others dissolve without decomposition, and when evaporated separate from their solutions unchanged. All these facts only indicate that ammoniacal, like aqueous, compounds dissociate with greater or lesser facility.¹⁹ Certain metallic oxides also absorb ammonia and are dissolved in ammonia water. Such are, for instance, the oxides of zinc, nickel, copper, and many others; the majority of such compounds are unstable. The property of ammonia of combining with the oxides of certain metals explains its action on certain metals.²⁰ For this reason, copper vessels are not suitable for holding liquids containing ammonia. Iron is not acted on by such liquids.

The relation of ammonia and water to salts and other substances becomes especially clear in the case when the salt is capable of combining with both ammonia and water. Take, for example, copper sulphate, CuSO_4 . As we saw in Chapter I., it gives with water blue crystals, $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$; but it also absorbs ammonia in the same molecular proportion, forming a blue substance, $\text{CuSO}_4 \cdot 5\text{NH}_3$, and therefore the ammonia combining with salts may be termed *ammonia of crystallisation*.

Such are the *reactions of combination* proper to ammonia. Let us now turn our attention to the reactions of substitution proper to this substance. If ammonia be passed through a heated tube containing metallic potassium, then hydrogen is evolved, and a compound is obtained containing ammonia in which one atom of hydrogen is replaced by an atom of potassium, NH_2K (according to the equation $\text{NH}_3 + \text{K} = \text{NH}_2\text{K} + \text{H}$). This body is termed potassamide. We shall afterwards see that iodine and chlorine are also capable of directly displacing hydrogen from ammonia, and of replacing it; we shall also see that in hydrocyanic acid, NCH , carbon has replaced hydrogen. Hence the hydrogen of ammonia may be replaced in many ways by different elements. If in so doing NH_2 remains, the resultant substances are called *amides*, if only NH *imides*, and those in which the whole of the hydrogen is displaced are termed *nitriles*. It may be imagined that the albuminous substances—that is, the complex organic

¹⁹ Isambert studied the dissociation of ammoniacal compounds, as we have seen in Note 8, and he showed that at low temperatures many salts are able to combine with a still greater amount of ammonia, which proves an entire analogy with aqueous compounds; and as in this case it is easy to isolate the definite compounds, and as the least possible tension of ammonia is greater than that of water, therefore the ammoniacal compounds present a great and peculiar interest, both as a means for explaining the nature of aqueous solutions, and as a confirmation of the conception of the formation of definite compounds in them; for these reasons we shall frequently turn to these compounds in the further exposition of this work.

²⁰ Chapter V. Note 2.


substances which we have already had occasion to mention are the amide compounds corresponding with saccharine substances. The most important point to be remarked is that in the action of different substances on ammonia it is the *hydrogen that is substituted*; the reactions proceed at the expense of the hydrogen and not of the nitrogen, which remains in the resultant compound, so to say, untouched. The same is to be observed in the action of various substances on water. In the majority of cases the reactions of water consist in the hydrogen being evolved, and in its being replaced by different elements. The same takes place, as we have seen, in acids, in which the hydrogen is easily displaced by metals. This chemical mobility of hydrogen is distinctly connected with the great lightness of the atoms of this element.

In chemical practice²¹ ammonia is often employed, not only for saturating acids, but also for accomplishing reactions of double decomposition with salts, and especially in separating insoluble basic hydroxides from soluble salts. Let MHO stand for an insoluble basic hydroxide, and HX for an acid. The salt formed by them will have a composition $MHO + XH - H_2O = MX$. If aqueous ammonia, NH_4OH , be added to a solution of this salt, then the ammonia will change

²¹ In practice, the applications of ammonia are very varied. The use of ammonia as a stimulant, in the forms of the so-called 'smelling salts' or of spirits of hartshorn, in cases of faintness, &c., is known to everyone. The volatile carbonate of ammonium, or a mixture of an ammonium salt with an alkali, is also employed for this purpose. Ammonia also produces a well-known stimulating effect when rubbed on the skin, for which reason it is sometimes employed for outward applications. Thus, for instance, the well-known volatile salve is prepared from any liquid oil shaken up with a solution of ammonia. A portion of the oil is thus transformed into a soapy substance. The solubility of greasy substances in ammonia, which proceeds from the formation both of emulsions and soaps, explains its use in extracting grease spots. It is also employed as an external application for stings from insects, and for bites from poisonous snakes, and in general in medicine. It is also remarkable that in cases of drunkenness a few drops of ammonia in water taken internally rapidly renders a person sober. A large quantity of ammonia is used in dyeing, either for the solution of certain dyes—for example, carmine—or for changing the tints of others, or else for neutralising the action of acids. It is also employed in the manufacture of artificial pearls. For this purpose the small scales of a peculiar small fish are mixed with ammonia, and the liquid so obtained is blown into small hollow glass beads, shaped like pearls.

In nature and the arts, however, the ammonium salts, not free ammonia, are most frequently employed. In this form a portion of that *nitrogen* which is necessary for the formation of albuminous substances *is supplied to plants*. Owing to this, a large quantity of ammonium sulphate is now employed as a fertilising substance. But the same part may be fulfilled by nitre, or by animal refuse, which in putrefying gives ammonia. The nitre of the soil is formed from these ammonia-giving substances, because nitrogen in combination with hydrogen is easily converted into oxygen compounds of nitrogen, as we shall afterwards see. For this reason, if an ammoniacal (hydrogen) compound be introduced into the soil in the spring, it will be converted into a nitrate (oxygen salt) in the summer.

places with the metal M and thus form the insoluble basic hydroxide, or, as it is said, give a precipitate. The mechanism of this double decomposition is as follows :—



Thus, for instance, if aqueous ammonia is added to a solution of a salt of aluminium, Al, then hydrous alumina is separated out as a colourless gelatinous precipitate.²²

In order to grasp the relation between ammonia and the oxygen compounds of nitrogen it is necessary to recognise the general *law of substitution*, applicable to all cases of substitution between elements,²³ and therefore showing what may be the cases of substitution between oxygen and hydrogen as component parts of water. The law of substitution may be deduced from mechanical principles if the molecule be conceived as a system of elementary atoms occurring in a certain chemical and mechanical equilibrium. By likening the molecule to a system of bodies in a state of motion—for instance, to the sum total of the sun, planets, and satellites, occurring in conditions of mobile equilibrium—then we should expect the action of one part, in this system, to be equal and opposite to the other, according to Newton's third law of mechanics. Hence, being given a molecule of a compound, for instance, H_2O , NH_3 , NaCl , HCl , &c., then its every two parts must in a chemical respect represent something alike in force and capacities, and therefore *every two parts into which a molecule of a compound may be divided are capable of replacing each other*. In order that the application of the law should become clear, it is evident that among com-

²² As certain basic hydrates form peculiar compounds with ammonia, in some cases it happens that the first portions of ammonia added to a solution of a salt produces a precipitate, whilst the addition of a fresh quantity of ammonia dissolves this precipitate if the ammoniacal compound of the base be soluble in water. This, for example, takes place with the copper salts.

²³ When the element chlorine, as we shall afterwards more fully learn, replaces the element hydrogen, then the reaction by which such an exchange is accomplished proceeds as a substitution, $\text{AH} + \text{Cl}_2 = \text{ACl} + \text{HCl}$, so that two substances, AH and chlorine, react on each other, and two substances, ACl and HCl, are formed; and further, two molecules react on each other, and two others are formed. The reaction proceeds very easily, but the substitution of one element, A, by another, X, does not always proceed with such ease, clearness, or simplicity. The substitution between oxygen and hydrogen is very rarely accomplished by the action of the free elements, but the substitution between these elements, one for another, forms the most common case of oxidation and reduction. In speaking of the law of substitution, I have in view the substitution of the elements one by another, and not the direct reaction of substitution. The law of substitution determines the cycle of the combinations of a given element, if a few of its compounds (for instance, the hydrogen compounds) be known.


pounds the most stable should be chosen. We will, therefore, take water as the most stable compound of hydrogen and oxygen,²⁴ in order to see the cases of substitution between hydrogen and oxygen; but for the sake of clearness we will start by taking the very stable molecule of hydrochloric acid, HCl , as one which can be divided into H and Cl only. According to the law of substitution, if these elements are able to form a molecule, and a stable one, then they are able to replace each other. And, indeed, we shall afterwards see that in a number of instances a substitution between hydrogen and chlorine conversely takes place. Given RH , then RCl is possible, because HCl exists and is stable. The molecule of water, H_2O , may be divided in two ways, because it contains 3 atoms: into H and (HO) on the one hand, and into H_2 and O on the other. Consequently, being given RH , its substitution products will be $\text{R}(\text{HO})$ according to the first form, and R_2O according to the second; being given RH_2 , its corresponding substitution products will be $\text{RH}(\text{OH})$, $\text{R}(\text{OH})_2$, RO , $(\text{RH})_2\text{O}$, &c. The group (OH) is the same hydroxyl or aqueous radicle which we have already mentioned in the third chapter as a component part of hydroxides and alkalis—for instance, $\text{Na}(\text{OH})$, $\text{Ca}(\text{OH})_2$, &c. It is evident, judging from HCl , that (OH) can be substituted by Cl , because both are replaceable by H ; and this is of common occurrence in chemistry, because metallic chlorides—for instance, NaCl and NH_4Cl —correspond with hydroxides of the alkalis $\text{Na}(\text{OH})$ or $\text{NH}_4(\text{OH})$. In hydrocarbons—for instance, C_2H_6 —the hydrogen is replaceable by chlorine and by hydroxyl. Thus common alcohol is C_2H_6 , in which one atom of H is replaced by (OH) ; that is, $\text{C}_2\text{H}_5(\text{OH})$. It is evident that the replacement of hydrogen by hydroxyl essentially forms the phenomenon of oxidation, because RH gives $\text{R}(\text{OH})$, or RHO . Hydrogen peroxide may in this sense be regarded as water in which the hydrogen is replaced by hydroxyl; $\text{H}(\text{OH})$ gives $(\text{OH})_2$ or H_2O_2 . For this reason chlorine, as we shall afterwards see, exhibits in its reactions much analogy to hydrogen peroxide, which may be termed free hydroxyl. The other form of substitution—namely, that of O in the place of H_2 —is also a common chemical phenomenon. Thus common alcohol, $\text{C}_2\text{H}_6\text{O}$, or $\text{C}_2\text{H}_5(\text{OH})$, when oxidising in the air, gives, as every one knows, acetic acid, $\text{C}_2\text{H}_4\text{O}_2$, or $\text{C}_2\text{H}_3\text{O}(\text{OH})$, in which H_2 is replaced by O .

²⁴ If hydrogen peroxide be taken as a starting point, then still higher forms of oxidation than those corresponding with water should be looked for. They should possess the properties of hydrogen peroxide, especially that of parting with their oxygen with extreme ease (even by contact). Such compounds are known. Pernitric, persulphuric, and similar acids present these properties, as we shall see in describing them.

In the further course of this work we shall have occasion to have recourse to the law of substitution for explaining many chemical phenomena and relations.

We will now apply these conceptions to ammonia or nitrogen hydride in order to see its relation to the oxygen compounds of nitrogen. It is evident that many substances may proceed from ammonia, NH_3 , or aqueous ammonia, $\text{NH}_4(\text{OH})$, from the substitution of their hydrogen by hydroxyl, or of H_2 by oxygen. And such is the case. The two extreme cases of such substitution will be as follows: (1) One atom of H in NH_3 is substituted by (OH), and $\text{NH}_2(\text{OH})$ is produced. Such a substance, still containing much hydrogen, should have many of the properties of ammonia. It is known under the name of *hydroxylamine*,²⁵ and, in fact, it is capable, like ammonia,

²⁵ The compound of hydroxylamine with hydrochloric acid has the composition NH_4ClO —that is, it is as it were oxidised sal-ammoniac. It was prepared by Lossen in 1865 by the action of tin and hydrochloric acid in the presence of water on a substance called ethyl nitrate, in which case the hydrogen liberated from the hydrochloric acid by the tin acts upon the elements of nitric acid—



Thus in this case the nitric acid is deoxidised, not directly into nitrogen, but into hydroxylamine. Hydroxylamine is also formed by passing nitric oxide, NO , into a mixture of tin and hydrochloric acid—that is, by the action of the hydrogen evolved on the nitric oxide: $\text{NO} + 3\text{H} + \text{HCl} = \text{NH}_4\text{OCl}$ —and in many other cases. According to Lossen's method, a mixture of 30 parts of ethyl nitrate, 120 parts of tin, and 40 parts of a solution of hydrochloric acid of sp. gr. 1.06 are taken. The reaction proceeds of its own accord after the lapse of a certain time. When the reaction ceases the tin is separated by means of hydrogen sulphide, the solution is evaporated, and a large amount of sal-ammoniac is thus obtained (owing to the further action of hydrogen on the hydroxylamine compound, the hydrogen taking up oxygen from it and forming water); a solution ultimately remains containing the hydroxylamine salt; this salt is dissolved in anhydrous alcohol and purified by the addition of platinum chloride, which precipitates any ammonium salt still remaining in the solution. After concentrating the alcoholic solution the hydroxylamine hydrochloride separates in crystals. This substance melts at about 150° , and in so doing decomposes into nitrogen, hydrogen chloride, water, and sal-ammoniac. A sulphuric acid compound of hydroxylamine may be obtained by mixing a solution of the above salt with sulphuric acid. This substance is also soluble in water like the hydrochloride; this shows that hydroxylamine, like ammonia itself, forms a series of salts in which one acid may be substituted for another. It might be expected that by mixing a strong solution of a hydroxylamine salt with a solution of a caustic alkali hydroxylamine itself would be liberated, just as an ammonia salt under these circumstances evolves ammonia; but the liberated hydroxylamine is immediately decomposed with the formation of nitrogen and ammonia (and probably nitrous oxide), $3\text{NH}_5\text{O} = \text{NH}_3 + 3\text{H}_2\text{O} + \text{N}_2$. Dilute solutions give the same reaction, although very slowly, but by decomposing a solution of the sulphate with barium hydroxide a certain amount of hydroxylamine is obtained in solution; this, however, cannot be separated from the solution, either by heating or evaporation, without decomposition. The addition of an acid to such a solution again gives a salt of hydroxylamine. Hydroxylamine in aqueous solu-

of giving salts with acids; for example, with hydrochloric acid, $\text{NH}_3(\text{OH})\text{Cl}$ —which is a substance corresponding with sal-ammoniac, in which one atom of hydrogen is replaced by hydroxyl. (2) The other extreme case of substitution given by ammonium hydroxide, $\text{NH}_4(\text{OH})$, is when the whole of the hydrogen of the ammonium is replaced by oxygen; and as ammonium contains 4 atoms of hydrogen, the highest oxygen compound should be $\text{NO}_2(\text{OH})$, or NHO_3 , as we find to be really the case, because NHO_3 is nitric acid, or the highest degree of the oxidation of nitrogen.²⁶ If instead of the two extreme aspects of substitution we take an intermediate one, then we obtain one of the intermediate oxygen compounds of nitrogen. For instance, $\text{N}(\text{OH})_3$ is orthonitrous acid,²⁷ with which corresponds nitrous acid, $\text{NO}(\text{OH})$, or NHO_2 , equal to $\text{N}(\text{OH})_3 - \text{H}_2\text{O}$, and nitrous anhydride $\text{N}_2\text{O}_3 = 2\text{N}(\text{OH})_3 - 3\text{H}_2\text{O}$. Thus nitrogen gives a series of oxygen

tion, like ammonia, precipitates basic hydrates, and it deoxidises the oxides of copper, silver, and other metals. Hydroxylamine is obtained, in a great number of cases, for instance, by the action of tin on dilute nitric acid, and also by the action of zinc on ethyl nitrate and dilute hydrochloric acid, &c. The relation between hydroxylamine, $\text{NH}_2(\text{OH})$, and nitrous acid, $\text{NO}(\text{OH})$, which is so clear in the sense of the law of substitutions, becomes a reality in those cases when reducing agents act on salts of nitrous acid. Thus Raschig (1888) proposed the following method for the preparation of the hydroxylamine sulphate. A mixture of strong solutions of potassium nitrite, KNO_2 , and hydroxide, KHO , in molecular proportions, is prepared and cooled. An excess of sulphurous anhydride is then passed into the mixture, and the solution boiled for a long time. A mixture of the sulphates of potassium and hydroxylamine is thus obtained: $\text{KNO}_2 + \text{KHO} + 2\text{SO}_2 + 2\text{H}_2\text{O} = \text{NH}_2(\text{OH})_2\text{H}_2\text{SO}_4 + \text{K}_2\text{SO}_4$. The salts may be separated from each other by crystallisation.

With respect to substances intermediate between NH_5 and the oxides of nitrogen, we must turn our attention to hyponitrous acid, NHO , and amidogen, which are mentioned in Note 67.

²⁶ Nitric acid corresponds with the anhydride N_2O_5 , which will afterwards be described, but which must be regarded as the highest saline oxide of nitrogen, just as Na_2O (and the hydroxide NaHO) in the case of sodium, although sodium forms a peroxide possessing the property of parting with its oxygen with the same ease as hydrogen peroxide, if not on heating, at all events in reactions—for instance, with acids. So also nitric acid has its corresponding peroxide, which may be called pernitric acid. Its composition is not well known—probably NHO_4 —so that its corresponding anhydride would be N_2O_7 . It is formed by the action of a silent discharge on a mixture of nitrogen and oxygen, so that a portion of its oxygen is in a state similar to that in ozone. The instability of this substance (obtained by Hautefeuille, Clappuis, and Berthelot), which easily splits up with the formation of nitric peroxide, and its resemblance to persulphuric acid, which we shall afterwards describe, will permit our passing over the consideration of the little that is further known concerning it.

²⁷ Phosphorus, as we shall afterwards find, gives the hydride PH_3 , corresponding with ammonia, NH_3 , and forms phosphorous acid, PH_3O_3 , which is analogous to nitrous acid, just as phosphoric acid is to nitric acid; but phosphoric (or, better, orthophosphoric) acid, PH_3O_4 , is able to lose water and give pyro- and meta-phosphoric acids. The latter is equal to the ortho-acid minus water = PHO_3 , and therefore nitric acid, NHO_3 , is really meta-nitric acid. So also nitrous acid, HNO_2 , is meta-nitrous (anhydrous) acid, and then the ortho-acid is $\text{NH}_5\text{O}_3 = \text{N}(\text{OH})_3$.

compounds, which we will proceed to describe. Only let us first show that the passage of ammonia into the oxygen compounds of nitrogen up to nitric acid, as well as the converse preparation of ammonia from nitric acid, are reactions which proceed directly and easily under many circumstances. In nature the matter is complicated by a number of influences and circumstances, but in the law the relations are presented in their simplest aspect. The bond between this simplicity of laws and this complexity of phenomena forms the essence of a scientific understanding of things.

It is easy to prove the possibility of the oxidation of ammonia into nitric acid by passing a mixture of ammonia and air over heated spongy platinum. This causes the oxidation of the ammonia, nitric acid being formed, which partially combines with the excess of ammonia.

The converse passage of nitric acid into ammonia is accomplished by the action of hydrogen at the moment of its evolution.²⁸ Thus metallic aluminium, evolving hydrogen from caustic soda, is able to completely convert nitric acid added to the mixture (really as a salt, because the alkali gives a salt with the nitric acid) into ammonia, $\text{NHO}_3 + 8\text{H} = \text{NH}_3 + 3\text{H}_2\text{O}$.

The compounds of nitrogen with oxygen present an excellent example of the law of multiple proportions, because they contain for 14 parts by weight of nitrogen 8, 16, 24, 32, and 40 parts, respectively, by weight of oxygen. The composition of these compounds is as follows:—

N_2O , nitrous oxide; hydrate NHO .

N_2O_2 , nitric oxide, NO .

N_2O_3 , nitrous anhydride; hydrate NHO_2 .

N_2O_4 , peroxide of nitrogen, NO_2 .

N_2O_5 , nitric anhydride; hydrate NHO_3 .

Of these compounds,²⁹ nitrous and nitric oxides, peroxide of nitrogen, and nitric acid, NHO_3 , are characterised as being the most stable. *The lower oxides, when coming into contact with the higher, may give the intermediate forms; for instance, NO and NO_2 form N_2O_3 , and the intermediate oxides may, in splitting up, give a higher and lower oxide.*

²⁸ The formation of ammonia is remarked in many cases of oxidation by means of nitric acid. This substance is even formed in the action of nitric acid on tin, especially if dilute acid be employed in the cold. A still more considerable amount of ammonia is obtained if, in the action of nitric acid, there are conditions directly tending to the evolution of hydrogen, which then reduces the acid to ammonia; for instance, in the action of zinc on a mixture of nitric and sulphuric acids.

²⁹ According to the determinations of Favre, Thomsen, and more especially of Berthelot, on thermochemical data, it follows that in the formation of such quantities of the oxides of nitrogen as express their formulae, if gaseous nitrogen and oxygen be taken as the

So N_2O_4 gives N_2O_3 and N_2O_5 , or, in the presence of water, their hydrates.

We have already seen that, under certain conditions, nitrogen combines with oxygen, and we know that ammonia may be oxidised. In these cases various oxidation products of nitrogen are formed, but in the presence of water and an excess of oxygen they always give nitric acid. Nitric acid, as corresponding with the highest oxide, is able, in deoxidising, to give the lower oxides, and for this reason we will begin with it.

Nitric acid, HNO_3 , is likewise known as aqua fortis. In a free state it is only met with in nature in small quantities, in the air and rain-water after storms; but even in the atmosphere nitric acid does not long remain free, but combines with ammonia, traces of which are always found in air. On falling on the soil and into running water, &c., the nitric acid everywhere comes into contact with bases (or their carbonates), which easily act on it, and therefore it is converted into the nitrates of these bases. Ammonia and other compounds of nitrogen, if oxidised in the soil, are always in the presence of bases, and therefore also give salts of nitric acid, and not the free acid itself. Hence nitric acid is always met with in the form of salts in nature. These salts are called *nitres*. This name is derived from the Latin *sal nitri*. The potassium salt KNO_3 is common nitre, and the sodium salt NaNO_3 Chili saltpetre, or cubic nitre. Nitres are formed when a nitrogenous substance is slowly oxidised in the presence of an alkali by means of the oxygen of the atmosphere. In nature there are very frequent instances of such oxidation. For this reason, certain soils and

starting points, and if the compounds formed be also gaseous, the following amounts of heat, expressed in thousands of heat units, are *absorbed* (hence a minus sign):—

N_2O	N_2O_2	N_2O_3	N_2O_4	N_2O_5
−21	−43	−22	−5	−1
−22	+21	+17	+4	

The difference is given in the lower line. For example, if N_2 , or 28 grams of nitrogen, combine with O—that is, with 16 grams of oxygen—then 21000 units of heat are absorbed, or sufficient heat is assimilated to heat 21000 grams of water through 1° . Naturally, direct observations are impossible in this case; but if charcoal, phosphorus, or similar substances, are burnt both in nitrous oxide and in oxygen, and the heat evolved is observed in both cases, then the difference (more heat will be evolved in burning in nitrous oxide) gives the figures required. If, then, N_2O_3 , by combining with O_2 , gives N_2O_5 , then, as is seen from the table, heat should be developed, namely 38000 units of heat, or $\text{NO} + \text{O} = 19000$ units of heat. The differences given in the table show that the maximum absorption of heat corresponds with nitric oxide, and that the higher oxides are formed from it with evolution of heat. If liquid nitric acid, HNO_3 , were decomposed into $\text{N} + \text{O}_3 + \text{H}$, then 41000 heat units would be required; that is, an evolution of heat takes place in its formation from the gases. It should be observed that the formation of ammonia, NH_3 , from the gases $\text{N} + \text{H}_3$ evolves 12·2 thousand heat units.

rubbish heaps—for instance, lime rubbish (in the presence of a base—lime)—contain a more or less considerable amount of nitre. One of these nitrates—the sodium nitrate—is extracted from the earth in large quantities in Chili, where it was probably formed by the oxidation of animal refuse. This kind of nitre is employed in practice for the manufacture of nitric acid and the other oxygen compounds of nitrogen. Nitric acid is obtained from *Chili saltpetre* by heating it with *sulphuric acid*. The hydrogen of the sulphuric acid replaces the sodium in the nitre. The sulphuric acid then forms either an acid salt, NaHSO_4 , or a normal salt, Na_2SO_4 , while nitric acid is formed from the nitre and is volatilised. The decomposition is expressed by the equations: (1) $\text{NaNO}_3 + \text{H}_2\text{SO}_4 = \text{HNO}_3 + \text{NaHSO}_4$, if the acid salt be formed, and (2) $2\text{NaNO}_3 + \text{H}_2\text{SO}_4 = \text{Na}_2\text{SO}_4 + 2\text{HNO}_3$, if the normal sodium sulphate is formed. With an excess of sulphuric acid, and at a moderate heat, and at the commencement of the reaction, the decomposition proceeds according to the first equation; and on further heating with a sufficient amount of nitre, according to the second, because the acid salt NaHSO_4 itself acts like an acid (its hydrogen being replaceable as in acids), according to the equation $\text{NaNO}_3 + \text{NaHSO}_4 = \text{Na}_2\text{SO}_4 + \text{HNO}_3$.

The sulphuric acid, as it is said, here displaces the nitric acid from its compound with the base. This not unfrequently gives rise to the supposition that sulphuric acid has a particularly high degree of affinity or energy as compared with nitric acid, but, as we shall afterwards see, the idea of a relative affinity in acids and in bases is, in many instances, untrustworthy; it should not be had recourse to so long as it be possible to explain a phenomenon without its introduction, inasmuch as the degree of affinity cannot be measured. The action of the sulphuric acid can be explained by the fact that the nitric acid formed is volatile. Nitric acid alone, of all the substances taking part in the reaction, is capable of being converted into vapour (at the temperature employed), and it alone volatilises; the remaining substances are not volatile, or, more strictly speaking, are very slightly volatile. If we suppose that the sulphuric acid is able to set free even only a small quantity of nitric acid from its salt, it is sufficient for explaining eventually the complete decomposition of the nitre by the sulphuric acid, because, once the nitric acid is separated, it is, on heating, converted into vapour, and passes from the sphere of action of the remaining substances; the free sulphuric acid then again sets free a fresh small quantity of nitric acid, and so on until the nitric acid is completely displaced from the nitre. It is evident that, according to this explanation, it is necessary that the sulphuric acid

should be in excess (although but small) to the end of the reaction. According to the equation expressing the reaction, it is required that there should be 98 parts of sulphuric acid to 85 parts of sodium nitrate ; but if these quantities be taken, the nitric acid is not entirely displaced by the sulphuric acid. It is necessary that an excess of the latter should be taken ; generally, 80 parts of nitre are taken to 98 parts of sulphuric acid, and therefore a portion of the sulphuric acid remains in a free state to the end of the reaction. Thus, in the reaction of sulphuric acid on nitre there is formed a non-volatile salt of sulphuric acid, which remains, together with an excess of this acid, in the distilling apparatus, and nitric acid, which is converted




FIG. 47.—Method of preparing nitric acid on a large scale. A cast-iron retort, C, is fixed into the furnace, and heated by the fire, B. The flame and products of combustion are at first led along the flue, M (in order to heat the receivers), and afterwards into L. The retort is charged with Chili saltpetre and sulphuric acid, and the cover is luted on with clay and gypsum. A clay tube, a, is fixed into the neck of the retort (in order to prevent the nitric acid from corroding the cast iron), and a bent glass tube, D, is luted on to it. This tube carries the vapours into a series of earthenware receivers, E. Nitric acid mixed with sulphuric acid collects in the first. The purest nitric acid is procured from the second, whilst that which condenses in the third receiver contains hydrochloric acid, and that in the fourth receiver contains water. Water is poured into the last receiver in order to condense the residual vapours.

into vapour, and may be condensed, because it is a liquid and volatile substance. On a small scale, this reaction may be carried on in a glass retort with a glass condenser. On a large scale, in chemical works, the process is exactly similar, only iron retorts are employed for holding the mixture of nitre and sulphuric acid, and earthenware three-necked bottles are used instead of a condenser,⁵⁰ as shown in fig. 47.

⁵⁰ It must be observed that sulphuric acid, at least when undiluted (60° Baumé), corrodes cast iron with difficulty, so that the acid may be heated in cast-iron boilers.

Nitric acid so obtained always contains water. It is extremely difficult to deprive it of all the admixed water without destroying a portion of the acid itself and partially converting it into lower oxides, because without the presence of an excess of water it is very unstable. When rapidly distilled a portion is decomposed, and there are obtained free oxygen and lower oxides of nitrogen, which, together with the water, remain in solution with the nitric acid. Therefore it is necessary to work with great care in order to obtain a pure hydrate of nitric acid, HNO_3 , and especially to mix the nitric acid obtained from nitre, as above described, with sulphuric acid, which takes up the water, and to distil it at the lowest possible temperature—that is, by placing the retort holding the mixture in a water or oil bath and carefully heating

Nevertheless, both sulphuric and nitric acids evince a certain action on cast iron, and therefore the acid obtained will contain traces of iron. In practice sodium nitrate (Chili saltpetre) is usually employed because it is cheaper, but in the laboratory it is best to take potassium nitrate, because it is purer and does not froth up so much as sodium nitrate when heated with sulphuric acid. In the action of an excess of sulphuric acid on nitre and nitric acid a portion of the latter is decomposed, forming lower oxides of nitrogen, which are dissolved in the nitric acid. A portion of the sulphuric acid itself is also carried over as spray by the vapours of the nitric acid. Hence sulphuric acid occurs as an impurity in commercial nitric acid. A certain amount of hydrochloric acid will also be found to be present in it, because sodium chloride is generally found as an impurity in nitre, and under the action of sulphuric acid it forms hydrochloric acid. Commercial acid further contains a considerable excess of water above that necessary for the formation of the hydrate, because water is first poured into the earthenware vessels employed for condensing the nitric acid in order to facilitate its cooling and condensation. Further, the acid of composition HNO_3 decomposes with great ease, with the evolution of oxides of nitrogen. Thus the commercial acid contains a great number of impurities. Generally its specific gravity is 1.33 (36° Baumé), and it contains 53 p.c. of nitric acid. The acid employed in medicine and in the laboratory contains one-third of nitric acid and two-thirds of water, and its specific gravity is 1.2. The commercial acid is often purified in the following manner:—Lead nitrate is first added to the acid because it forms non-volatile and almost insoluble (precipitated) substances with the free sulphuric and hydrochloric acids, and liberates nitric acid in so doing, according to the equations $\text{Pb}(\text{NO}_3)_2 + 2\text{HCl} = \text{PbCl}_2 + 2\text{HNO}_3$ and $\text{Pb}(\text{NO}_3)_2 + \text{H}_2\text{SO}_4 = \text{PbSO}_4 + 2\text{HNO}_3$. Potassium chromate is then added to the impure nitric acid, by which means oxygen is liberated from the chromic acid, and this oxygen, at the moment of its evolution, oxidises the lower oxides of nitrogen and converts them into nitric acid. A pure nitric acid, containing no impurities other than water, may be then obtained by distilling the acid, manipulated as above described, with care, and particularly if only the middle portions of the distillate are collected. Such acid should give no precipitate, either with a solution of barium chloride (a precipitate shows the presence of sulphuric acid) or with a solution of silver nitrate (a precipitate shows the presence of hydrochloric acid), nor should it, after being diluted with water, give a coloration with starch containing potassium iodide (a coloration shows the admixture of other oxides of nitrogen). The oxides of nitrogen may be most easily removed from impure nitric acid by heating for a certain time with a small quantity of pure charcoal. By the action of nitric acid on the charcoal carbonic anhydride is evolved, which carries off the NO , NO_2 , and other volatile substances. On redistilling, pure acid is obtained. The oxides of nitrogen occurring in solution may also be removed by passing air through the nitric acid.

it. The first portion of the nitric acid thus distilled boils at 86° , has a specific gravity at 15° of 1.526, and solidifies at -50° ; it is very unstable at higher temperatures. This is the normal hydrate, HNO_3 , which corresponds with the salts, NMO_3 , of nitric acid. When diluted with water nitric acid presents a higher boiling point, not only as compared with that of the nitric acid itself, but also with that of water; so that, if very dilute nitric acid be distilled, the first portions passing over will consist of almost pure water, until the boiling point in the vapours reaches 121° . At this temperature a compound of nitric acid with water, containing about 70 p.c. of nitric acid,⁵¹ distils over; its specific gravity at $15^{\circ} = 1.521$. If the solution contain less than 25 p.c. of water, then, the specific gravity of the solution being above 1.44, HNO_3 evaporates off and fumes in the air, forming the above hydrate, whose vapour tension is less than that of water. Such solutions form *fuming nitric acid*. On distilling it gives monohydrated acid,⁵² HNO_3 ; it is a hydrate boiling at 121° , so that it is obtained from both weak and strong solutions. Fuming nitric acid, under the action not only of organic substances, but even of heat, loses a portion

⁵¹ Dalton, Smith, Bineau, and others considered that the hydrate of constant boiling point (see Chapter I. Note 60) for nitric acid was the compound $2\text{HNO}_3, 3\text{H}_2\text{O}$, but Roscoe showed that its composition changes with a variation of the pressure and temperature under which the distillation proceeds. Thus, at a pressure of 1 atmosphere the solution of constant boiling point contains 68.6 p.c., and at one-tenth atmosphere 66.8 p.c. Judging from what has been said concerning solutions of hydrochloric acid, and from the variation of specific gravity, I think that the comparatively large decrease of the tensions of the vapours depends on the formation of a hydrate, $\text{HNO}_3, 2\text{H}_2\text{O}$ ($= 63.6$ p.c.). Such a hydrate may be expressed by $\text{N}(\text{HO})_5$, that is as $\text{NH}_4(\text{HO})$ in which all the equivalents of hydrogen are replaced by hydroxyl. The constant boiling point will then be the temperature of the decomposition of this hydrate.

Besides which, judging by the variation of the specific gravity (see my work cited in Chapter I. Note 29), at least one more hydrate, $\text{HNO}_3, 5\text{H}_2\text{O}$ (41.2 p.c. HNO_3), must be acknowledged. Starting from water ($p=0$) to this hydrate, the specific gravities of the solutions at 15° is well expressed by $s = 9992 + 57.4p + 0.16p^2$, if water = 10000 at 4° . For example, when $p=30$ p.c., $s=11860$. For more concentrated solutions, at least, the above-mentioned hydrate, $\text{HNO}_3, 2\text{H}_2\text{O}$, must be taken, up to which the specific gravity $s = 9570 + 84.18p - 0.240p^2$; but perhaps (the results of observations of the specific gravity of the solutions are not in sufficient agreement to make a decision) the hydrate $\text{HNO}_3, 3\text{H}_2\text{O}$ should be recognised, as is indicated by many nitrates (Al, Mg, Co., &c.), which crystallise with this amount of water of crystallisation. From $\text{HNO}_3, 2\text{H}_2\text{O}$ to HNO_3 the specific gravity of the solutions (at 15°) $s = 10652 + 62.08p - 0.160p^2$. The pentahydrated hydrate is recognised by Berthelot on the basis of the thermo-chemical data for solutions of nitric acid, because on approaching to this composition there is a rapid change in the amount of heat evolved by mixing nitric acid with water. This hydrate solidifies at about -19° . One would think that a more detailed study of the reactions of hydrated nitric acid would show the existence of change in the process and rapidity of reaction in approaching these hydrates.

⁵² The normal hydrate HNO_3 , corresponding with the ordinary salts, may be termed the monohydrated acid, because the anhydride N_2O_5 with water forms this normal nitric acid. In this sense the hydrate $\text{HNO}_3, 2\text{H}_2\text{O}$ is the pentahydrated acid.

of its oxygen, forming lower oxides of nitrogen, which impart a *red-brown colour* to it ;³³ the pure acid is colourless.

Nitric acid, as an *acid hydrate*, enters into reactions of double decomposition with bases, basic hydrates (alkalis), and with salts. In all these cases a salt of nitric acid is obtained. An alkali and nitric acid give water and a salt ; so, also, a basic oxide with nitric acid gives a salt and water ; for instance, $\text{KHO} + \text{HNO}_3 = \text{KNO}_3 + \text{H}_2\text{O}$, or with lime, $\text{CaO} + 2\text{HNO}_3 = \text{Ca}(\text{NO}_3)_2 + \text{H}_2\text{O}$. Many of these salts are termed nitres.³⁴ The composition of the ordinary salts of nitric acid may be expressed by the general formula $\text{M}(\text{NO}_3)_n$, where M indicates a metal replacing the hydrogen in one or several (n) equivalents of nitric acid. We shall find afterwards that the atoms M of metals are equivalent to one (K, Na, Ag) atom of hydrogen, or two (Ca, Mg, Ba), or three (Al, In), or, in general, n atoms of hydrogen. *The salts of nitric acid* are especially characterised by being all *soluble in water*.³⁵ From the property common to all these salts

³³ For technical and laboratory purposes recourse is frequently had to *red fuming nitric acid*—that is, the normal nitric acid, HNO_3 , containing lower oxides of nitrogen in solution. This acid is prepared by decomposing nitre with half its weight of strong sulphuric acid, or by distilling nitric acid with an excess of sulphuric acid. The normal nitric acid is first obtained, but it partially decomposes, and gives the lower oxidation products of nitrogen, which are dissolved by the nitric acid, to which they impart its usual pale-brown or reddish colour. This acid fumes in the air, from which it attracts moisture, forming a less volatile hydrate. If carbonic anhydride be passed through the red-brown fuming nitric acid for a long period of time, especially if with the aid of moderate heat, it expels all the lower oxides, and leaves a colourless acid free from these oxides. It is necessary, in the preparation of the red acid, that the receivers should be kept quite cool, because it is only when cold that nitric acid is able to dissolve a large proportion of the oxides of nitrogen. The strong red fuming acid has a specific gravity 1.56 at 20°, and has a suffocating smell of the oxides of nitrogen. When the red acid is mixed with water it turns green and then of a bluish colour, and with an excess of water ultimately becomes colourless. This is owing to the fact that the oxides of nitrogen in the presence of water and nitric acid are changed, and give coloured solutions.

The action of red fuming nitric acid (or a mixture with sulphuric acid) is in many cases very powerful and rapid, and it sometimes acts differently from pure nitric acid. Thus iron becomes covered with a coating of oxides, and becomes insoluble in acids ; it becomes, as is said, passive. Thus chromic acid (and potassium dichromate) gives oxide of chromium in this red acid—that is, it is deoxidised. This is owing to the presence of the lower oxides of nitrogen, which are capable of being oxidised—that is, of passing into nitric acid like the higher oxides. But, generally, the action of fuming nitric acid, both red and colourless, is powerfully oxidising.

³⁴ Hydrogen is not evolved in the action of nitric acid (especially strong) on metals, even with those metals which evolve hydrogen under the action of other acids. This is because the hydrogen at the moment of its separation reduces the nitric acid, with formation of the lower oxides of nitrogen, as we shall afterwards see.

³⁵ Certain basic salts of nitric acid, however (for example, the basic salt of bismuth), are insoluble in water, whilst, on the other hand, all the normal salts are soluble, and this forms an exceptional phenomenon among acids, because all the ordinary acids form insoluble salts with one or another base. Thus, for sulphuric acid the salts of barium,

of entering into double decompositions, and owing to the volatility of nitric acid, they, like cubic nitre, evolve nitric acid when heated with sulphuric acid. They all, like nitric acid itself, are capable of evolving oxygen when heated, and consequently of acting like oxidising substances, and therefore, for instance, deflagrate with ignited carbon, the carbon burning at the expense of the oxygen of the salt and forming gaseous products of combustion.³⁶

Nitric acid also enters into double decompositions with a number of hydrocarbons not in any way possessing alkaline characters and not reacting with other acids. Under these circumstances, the nitric acid gives water and a new substance termed a *nitro-compound*. The chemical character of the nitro-compound is the same as that of the original substance; for example, if an indifferent substance be taken, then the nitro-compound obtained from it will also be indifferent; if an acid be taken, then an acid is obtained also. Benzene, C_6H_6 , for instance, acts according to the equation $C_6H_6 + HNO_3 = H_2O + C_6H_5NO_2$. Nitrobenzene is produced. The substance taken, C_6H_6 , is a liquid hydrocarbon having a faint tarry smell, boiling at 80° , and lighter than water; by the action of nitric acid nitrobenzene is obtained, which is a substance boiling at about 210° , heavier than water, and having an almond-like odour; it is employed in large quantities for the preparation of aniline and aniline dyes.³⁷ As they contain both combustible elements (hydrogen and carbon), as

lead, &c., for hydrochloric acid the salts of silver, &c., are insoluble in water. However, the normal salts of acetic and certain other acids are all soluble.

³⁶ *Ammonium nitrate*, NH_4NO_3 , is easily obtained by adding a solution of ammonia or of ammonium carbonate to nitric acid until it becomes neutral. On evaporating this solution crystals of the salt are formed which contain no water of crystallisation. It crystallises in prisms like those formed by common nitre, and has a refreshing taste; 100 parts of water at t dissolve $54 + 0.61t$ parts by weight of the salt. It is soluble in alcohol, melts at 160° , and is decomposed at about 180° , forming water and nitrous oxide, $NH_4NO_3 = 2H_2O + N_2O$. If ammonium nitrate be mixed with sulphuric acid, and the mixture be heated at about the boiling point of water, then nitric acid is evolved, and ammonium hydrogen sulphate remains in solution; but if the mixture be heated rapidly to 160° , then nitrous oxide is evolved. In the first case the sulphuric acid takes up ammonia, and in the second place water. Ammonium nitrate is employed in practice for the artificial production of cold, because in dissolving in water it lowers the temperature very considerably. For this purpose it is best to take equal parts by weight of the salt and water. The salt must first be reduced to a powder and then rapidly stirred up in the water, when the temperature will fall from $+15^\circ$ to -10° , so that the water freezes.

Ammonium nitrate absorbs ammonia, with which it forms unstable compounds resembling compounds containing water of crystallisation. At -10° $NH_4NO_3 \cdot 2NH_3$ is formed: it is a liquid of sp. gr. 1.50, which loses all its ammonia under the influence of heat. At $+28^\circ$ $NH_4NO_3 \cdot NH_3$ is formed: it is a solid which easily parts with its ammonia when heated, especially in solution.

³⁷ The action of nitric acid on cellulose, $C_6H_{10}O_5$, is similar. This substance, which forms the outer coating of all plant cells, occurs in an almost pure state in cotton, in

well as oxygen in unstable combination with nitrogen, in the form of the radicle NO_2 of nitric acid, the nitro-compounds, when ignited or

common writing-paper, and in flax, &c.; under the action of nitric acid it forms water and nitrocellulose, which, although it has the same appearance as the cotton originally taken, differs from it entirely in properties. It explodes when struck, bursts into flame very easily under the action of sparks, and acts like gunpowder, whence its name of pyroxylin, or gun-cotton. The composition of gun-cotton is $\text{C}_6\text{H}_7\text{N}_3\text{O}_{11} = \text{C}_6\text{H}_{10}\text{O}_5 + 3\text{NHO}_5 - 3\text{H}_2\text{O}$. The proportion of the group NO_2 in nitrocellulose may be decreased by limiting the action of the nitric acid, and a compound is obtained which burns without explosion, although it is capable of bursting into flame. This substance when dissolved in a mixture of alcohol and ether is called *collodion*. The solution when poured on to any surface loses all the ether and alcohol by evaporation, and leaves an amorphous mass in the form of a transparent membrane insoluble in water. A solution of collodion is employed in medicine for covering wounds, and in wet-plate photography for giving on glass an even coat of a substance into which the various reagents employed in the process are introduced.

The property possessed by nitroglycerin (occurring in dynamite), nitrocellulose, and the other nitro-compounds, of burning with an explosion depends on the reasons in virtue of which a mixture of nitre and charcoal deflagrates and explodes; in both cases the elements of the nitric acid occurring in the compound are decomposed, the oxygen in burning unites with the carbon, and the nitrogen is set free; thus a very large volume of gaseous substances (nitrogen and oxides of carbon) is rapidly formed from the solid substances originally taken. These gases occupy an incomparably larger volume than the original substance, and therefore produce a powerful pressure and explosion. It is evident that in exploding with the development of heat (that is, in decomposing, not with the absorption of energy, as is generally the case, but with the evolution of energy) the nitro-compounds form stores of energy which are easily set free, and that consequently their elements occur in a state of particularly energetic movement, which is especially strong in the group NO_2 ; this group is common to all nitro-compounds, and all the oxygen compounds of nitrogen are unstable, easily decomposable, and (Note 29) absorb heat in their formation. On the other hand, the nitro-compounds are instructive as an example and proof of the fact that the elements and groups forming compounds are united in definite order in the molecules of a compound. A blow, concussion, or rise of temperature is necessary to bring the combustible elements C and H into the most intimate contact with NO_2 , and to distribute the elements in a new order in new compounds.

As regards the composition of the nitro-compounds, it will be seen that the hydrogen of a given substance is replaced by the complex group NO_2 of the nitric acid. The same is observed in the passage of alkalis into nitrates, so that the reactions of substitution of nitric acid—that is, the formation of salts and nitro-compounds—may be expressed in the following manner. In these cases the hydrogen is replaced by the so-called *radicle of nitric acid* NO_2 , as is evident from the following table:—

{ Caustic potash . . .	KHO.
{ Nitre	K(NO ₂)O.
{ Hydrate of lime . .	CaH ₂ O ₂ .
{ Calcium nitrate . .	Ca(NO ₂) ₂ O ₂ .
{ Glycerin	C ₃ H ₅ H ₅ O ₅ .
{ Nitroglycerin . . .	C ₃ H ₅ (NO ₂) ₅ O ₅ .
{ Phenol	C ₆ H ₅ OH.
{ Picric acid	C ₆ H ₂ (NO ₂) ₅ OH, &c.

The difference between the salts formed by nitric acid and the nitro-compounds consists in the fact that nitric acid is very easily separated from the salts of nitric acid by

even struck, decompose with an explosion, owing to the pressure of the vapours and gases formed—free nitrogen, carbonic anhydride, and aqueous vapour. In the explosion of nitro-compounds much heat is evolved, as in the combustion of gunpowder or detonating gas, and in this case the force of explosion in a closed space is great, because from a solid or liquid nitro-compound occupying a small space there proceed vapours and gases whose elasticity is great not only from the small space in which they are formed, but owing to the high temperature corresponding to the combustion of the nitro-compound.³⁸

The combustion of nitro-compounds, as well as that which nitrates bring about (in gunpowder), originates in the weakness of the bond which holds together the oxygen and nitrogen in nitric acid itself, as well as in all the oxygen compounds of nitrogen. If the vapour of nitric acid is passed through an even moderately heated glass tube, the formation of dark-brown fumes of the lower oxides of nitrogen and the separation of free oxygen may be observed— $2\text{NHO}_3 = \text{H}_2\text{O} + 2\text{NO}_2 + \text{O}$. The decomposition is complete at a white heat—that is, nitrogen is formed, $2\text{NHO}_3 = \text{H}_2\text{O} + \text{N}_2 + \text{O}_5$. Hence it is easily understood that nitric acid may part with its oxygen to a number of substances capable of being oxidised.³⁹ It is consequently an *oxidising agent*. Charcoal, as we have already seen, burns in nitric acid; phosphorus, sulphur, iodine, and the majority of metals also decompose nitric acid,

means of sulphuric acid (that is, by a method of double saline decomposition), whilst nitric acid is not displaced by sulphuric acid from true nitro-compounds: for instance, nitrobenzene, $\text{C}_6\text{H}_5\cdot\text{NO}_2$. As nitro-compounds are formed exclusively from hydrocarbons, they are described with them in organic chemistry.

The group NO_2 of nitro-compounds in many cases (like all the oxidised compounds of nitrogen) passes into the ammonia group or into the ammonia radicle NH_2 . It is evident that this requires the action of reducing substances evolving hydrogen: $\text{RNO}_2 + 6\text{H} - \text{RNH}_2 - 2\text{H}_2\text{O}$. Thus Zinin converted nitrobenzene, $\text{C}_6\text{H}_5\cdot\text{NO}_2$, into aniline, $\text{C}_6\text{H}_5\cdot\text{NH}_2$, by the action of hydrogen sulphide.

Admitting the existence of the group NO_2 , replacing hydrogen in various compounds, then nitric acid may be considered as water in which half the hydrogen is replaced by the radicle of nitric acid. In this sense nitric acid is nitro-water, $\text{NO}_2\cdot\text{OH}$, its anhydride dinitro-water, $(\text{NO}_2)_2\text{O}$, and nitrous acid nitro-hydrogen, NO_2H . In nitric acid the radicle of nitric acid is combined with hydroxyl, just as in nitrobenzene it is combined with the radicle of benzene.

It should here be remarked that the group NO_3 may be recognised in the salts of nitric acid, because the salts have the composition $\text{M}(\text{NO}_3)_n$, just as the metallic chlorides have the composition MCl_n . But the group NO_3 does not form any other compounds beyond the salts, and therefore it should be considered as hydroxyl, HO , in which H is replaced by NO_2 .

³⁸ The nitro-compounds play a very important part in mining and artillery. Detailed accounts of them must be looked for in special works. The most important and historical work in this connection is due to Berthelot, who elucidated much in connection with explosive compounds by a series of both experimental and theoretical researches.

³⁹ Nitric acid may be entirely decomposed by passing its vapour over highly incandescent copper, because the oxides of nitrogen first formed give up their oxygen to the

some on heating and others even at the ordinary temperature ; the substances taken are oxidised and the nitric acid is deoxidised, yielding compounds containing less oxygen. Only a few metals, such as gold and platinum, do not act on nitric acid, but the majority decompose it ; in so doing, an oxide of the metal is formed, which, if it has the character of a base, acts on the remaining nitric acid ; therefore, with

red-hot metallic copper, so that water and nitrogen gas alone are obtained. This forms a means for determining the composition both of nitric acid and of all the other compounds of nitrogen with oxygen, because by collecting the gaseous nitrogen formed it is




FIG. 48.—The method of decomposition of nitrous anhydride, also applicable to the other oxides of nitrogen, and to their analysis. NO_2 is generated from nitrate of lead in the retort A. Nitric acid and other less volatile products are condensed in B. The tube CC contains copper, and is heated from below. Undecomposed volatile products (if any are formed) are condensed in D, which is cooled. If the decomposition be incomplete, brown fumes make their appearance in this receiver. The gaseous nitrogen is collected in the cylinder E.

possible to calculate, from its volume, its weight and consequently its amount in a given quantity of a nitrogenous substance, and by weighing the copper before and after the decomposition it is possible to determine the amount of oxygen by the increase in




FIG. 49.—Decomposition of nitrous oxide by sodium.

at the expense of the oxidation of the hydrogen. Sodium also decomposes the oxides of nitrogen at a red heat, taking up all the oxygen. This method is sometimes used for determining the composition of the oxides of nitrogen.

weight. For nitric acid this decomposition is expressed by the equation $2\text{HNO}_3 + 5\text{Cu} = \text{H}_2\text{O} + \text{N}_2 + 5\text{CuO}$. This reaction must be preceded by the formation of copper nitrate, $\text{Cu}(\text{NO}_3)_2$, because oxide of copper forms this salt with nitric acid. This salt is very unstable, and evolves oxygen and oxides of nitrogen at a red heat. The complete decomposition of nitric acid is also accomplished by passing a mixture of hydrogen and nitric acid vapours through a red-hot tube, gaseous nitrogen being formed

metals the result of the reaction is usually not an oxide of the metal, but the corresponding salt of nitric acid, and, at the same time, one of the lower oxides of nitrogen. The resulting salts of the metals are soluble, and hence it is said that nitric acid *dissolves* nearly all metals.⁴⁰ This case is termed the solution of metals by acids, although it is not a case of simple solution, but a complex chemical change of the substances taken. When treated with this acid, those metals whose oxides do not combine with nitric acid yield the oxide itself, and not a salt; for example, tin acts in this manner on nitric acid, forming a hydrous oxide, SnH_2O_3 , which is obtained in the form of a white powder, $\text{Sn} + 4\text{HNO}_3 = \text{H}_2\text{SnO}_3 + 4\text{NO}_2 + \text{H}_2\text{O}$. Silver is able to take up still more oxygen, and to convert a large portion of nitric acid into nitrous anhydride, $4\text{Ag} + 6\text{HNO}_3 = 4\text{AgNO}_3 + \text{N}_2\text{O}_3 + 3\text{H}_2\text{O}$. Copper takes up still more oxygen from nitric acid, converting it into nitric oxide, a perfectly colourless gas; and, by the action of zinc, nitric acid is able to give up a still further quantity of nitrogen, forming nitrous oxide, $4\text{Zn} + 10\text{HNO}_3 = 4\text{Zn}(\text{NO}_3)_2 + \text{N}_2\text{O} + 5\text{H}_2\text{O}$.⁴¹ Sometimes, and especially with dilute solutions of nitric acid, the deoxidation proceeds as far as the formation of hydroxylamine and ammonia, and

⁴⁰ The application of this acid for etching copper or steel in engraving is based on this fact. The copper is covered with a coating of wax, resin, &c. (etching ground), on which nitric acid does not act, and then the ground is removed in certain parts with a needle, and the whole is washed in nitric acid. The parts covered with the ground remain untouched, whilst the uncovered portions are eaten into by the acid. Copper plates for etchings, aquatints, &c., are prepared in this manner.

⁴¹ The formation of such complex equations as the above often presents some difficulty to the beginner. It should be observed that if the reacting and resultant substances be known, it is easy to form an equation for the reaction. Thus, if we wish to form an equation expressing the reaction that nitric acid acting on zinc gives nitrous oxide, N_2O , and zinc nitrate, $\text{Zn}(\text{NO}_3)_2$, we must reason as follows:—Nitric acid contains hydrogen, whilst the salt and nitrous oxide do not; hence water is formed, and therefore it is as though anhydrous nitric acid, N_2O_5 , were acting. For its conversion into nitrous oxide it parts with four equivalents of oxygen, and hence it is able to oxidise four equivalents of zinc and to convert it into zinc oxide, ZnO . These four equivalents of zinc oxide require for their conversion into the salt four more equivalents of nitric anhydride, consequently five equivalents in all of the latter are required, or ten equivalents of nitric acid. Consequently ten equivalents of nitric acid are necessary for four equivalents of zinc in order to express the reaction in whole equivalents. It must not be forgotten, however, that there are very few such reactions which can be entirely expressed by simple equations. The majority of equations of reactions only express the chief and ultimate products of reaction, and thus none of the three preceding equations express all that in reality occurs in the action of metals on nitric acid. In no one of them is only one oxide of nitrogen formed, but always several together or consecutively—one after the other, according to the temperature and strength of the acid. And this is easily understood. The resulting oxide is itself capable of influencing metals and of being deoxidised, and in the presence of the nitric acid it may change the acid and be itself changed. The equations given must be looked on as a systematic expression of the main aspects of reactions. Further, these reactions vary considerably with different temperatures and varying strengths of acid.

sometimes it leads to the formation of ammonia itself. The formation of one or other nitrogenous substance from nitric acid is determined not only by the nature of the reacting substances, but also by the relative mass of water and nitric acid, and also by the temperature and pressure, or the sum total of the conditions of reaction; and as in a given mixture these conditions even vary (the temperature and the relative mass vary), therefore a mixture of different products of the deoxidation of nitric acid is not unfrequently formed.

Thus the action of nitric acid on metals consists in their being oxidised, whilst it is itself converted, according to the temperature, concentration in which it is taken, and the nature of the metal, &c., into either lower oxides, or even into ammonia.⁴² Many compounds are oxidised by nitric acid like metals and other elements; for instance, lower oxides are converted into higher oxides. Thus, arsenious acid is converted into arsenic acid, suboxide of iron into oxide, sulphurous acid into sulphuric acid, the sulphides of the metals, M_2S , into sulphates, M_2SO_4 , &c.; in a word, nitric acid brings about oxidation, its oxygen is taken up and transferred to many other substances. Certain substances are oxidised by strong nitric acid so rapidly and with so great an evolution of heat that they deflagrate and burst into flame. Thus turpentine, $C_{10}H_{16}$, bursts into flame when poured into fuming nitric acid. In virtue of its oxidising property, nitric acid *removes the hydrogen* from many substances. Thus it decomposes hydriodic acid, separating the iodine and forming water; and if fuming nitric acid be poured into a flask containing gaseous hydriodic acid, then a rapid reaction takes place, accompanied by flame and the separation of violet vapours of iodine and brown fumes of oxides of nitrogen.⁴³

⁴² It is observed that normal nitric acid oxidises many metals with much greater difficulty than when diluted with water; iron, copper, and tin are very easily oxidised by dilute nitric acid, but remain unaltered under the influence of monohydrated nitric acid or of the pure hydrate NHO_5 . Nitric acid diluted with a large quantity of water does not oxidise copper, but it oxidises tin; dilute nitric acid also does not oxidise either silver or mercury; but, on the addition of nitrous acid, even dilute acid acts on the above metals. This naturally depends on the smaller stability of nitrous acid, and on the fact that after the commencement of the action the nitric acid is itself converted into nitrous acid, which continues to act on the silver and mercury.

⁴³ When nitric acid acts on many organic substances it often happens that not only is hydrogen removed, but also oxygen is combined; thus, for example, nitric acid converts toluene, C_7H_8 , into benzoic acid, $C_7H_6O_2$. In certain cases, also, a portion of the carbon contained in an organic substance burns at the expense of the oxygen of the nitric acid. So, for instance, phthalic acid, $C_8H_6O_4$, is obtained from naphthalene, $C_{10}H_8$. Thus the action of nitric acid on the hydrocarbons is often most complex; there takes place (besides nitrification) the separation of carbon, the displacement of hydrogen, and the combination of oxygen. There are few organic substances which can withstand the action of nitric acid. Hence nitric acid acts in a powerfully transforming manner on a number of organic substances. It leaves a yellow stain on the skin, and in

As nitric acid is very easily decomposed with the separation of oxygen, it was for a long time supposed that it was not capable of forming the corresponding *nitric anhydride*, N_2O_5 ; but first Deville, and then Weber and others, discovered the methods of its formation. Deville obtained nitric anhydride by decomposing silver nitrate by chlorine under the influence of a moderate heat. Chlorine acts on the above salt at a temperature of 95° ($2AgNO_3 + Cl_2 = 2AgCl + N_2O_5 + O$), and when once the reaction is started it continues by itself without further heating. Brown fumes are given off, which are condensed in a tube surrounded by a freezing-mixture. A portion condenses in this tube and a portion remains in a gaseous state. The latter contains free oxygen. A crystalline mass and a liquid substance are obtained in the tube; the liquid is poured off, and a current of dry carbonic acid gas is passed through the apparatus in order to remove all traces of volatile substances (liquid oxides of nitrogen) adhering to the crystals of nitric anhydride. These form a voluminous mass of rhombic crystals (density 1.64), which sometimes are of rather large size; they melt at about 30° and distil at about 47° . In distilling, a portion of the substance is decomposed. With water these crystals give nitric acid. Nitric anhydride is also obtained by the action of phosphoric anhydride, P_2O_5 , on cold pure nitric acid (below 0°). During the very careful distillation of equal parts by weight of these two substances a portion of the acid decomposes, giving a liquid compound, $H_2O, 2N_2O_5 = N_2O_5, 2HNO_3$, whilst the greater part of the nitric acid gives the anhydride according to the equation $2HNO_3 + P_2O_5 = 2PHO_3 + N_2O_5$. On heating, and sometimes even spontaneously with explosion, nitric anhydride decomposes into nitric peroxide and oxygen, $N_2O_5 = N_2O_4 + O$.

Nitrogen peroxide, N_2O_4 , and *nitrogen dioxide*, NO_2 , express one and the same composition, but they should be distinguished like ordinary oxygen and ozone, although in this case their mutual conversion is more easily accomplished, even by vaporisation; also, O_3 loses heat in passing into O_2 , whilst N_2O_4 absorbs heat in forming NO_2 .

Nitric acid in acting on tin and on many organic substances (for example, starch) gives brown vapours, consisting of a mixture of N_2O_3 and NO_2 . A purer product is obtained by the decomposition of lead nitrate by heat, $Pb(NO_3)_2 = 2NO_2 + O + PbO$, when non-volatile lead

a large quantity causes a wound and entirely eats away the membranes of the body. The membranes of plants are eaten into with the greatest ease by strong nitric acid in just the same manner. One of the most durable blue vegetable dyes which is employed in dyeing tissues is *indigo*, yet it is easily converted into a yellow substance by the action of nitric acid, and small traces of free nitric acid may be recognised by this means.

oxide, oxygen gas, and nitrogen peroxide are formed. The latter, in a strongly cooled vessel, condenses into a brown liquid, which boils at about 22° . The purest peroxide of nitrogen, solidifying at -9° , is obtained when dry oxygen is mixed in a freezing-mixture with twice its volume of dry nitric oxide, NO , when transparent prisms of nitrogen peroxide are formed in the receiver; they melt into a colourless liquid at about -10° . When the temperature of the receiver is above -9° , the crystals melt,⁴⁴ and at 0° give a reddish-yellow liquid, like that obtained in the decomposition of lead nitrate. The vapours of nitrogen peroxide have a characteristic odour, and at the ordinary temperature are of a dark-brown colour, but at lower temperatures the colour of the vapour is much fainter. When heated, especially above 50° , the colour becomes a very dark brown, so that the vapours almost lose their transparency.

The causes of these peculiarities of nitrogen peroxide were not clearly understood until Deville and Trooste determined the density and dissociation of the vapour of this substance at different temperatures, and showed that the density varies. If the density be referred to that of hydrogen at the same temperature and pressure, then it is found to vary from 38 at the boiling point, or about 27° , to 23 at 135° , after which the density remains constant up to those high temperatures at which the oxides of nitrogen are decomposed. As, on the basis of the laws enunciated in the following chapter, the density 23 corresponds with the compound NO_2 (because the weight corresponding with this molecular formula = 46, and the density referred to hydrogen as unity is equal to half the molecular weight), therefore at temperatures above 135° the existence of nitrogen dioxide only must be recognised. It is this gas which is of a brown colour. At a lower temperature it forms nitrogen peroxide, N_2O_4 , whose molecular weight, and therefore density, is twice that of the dioxide. This substance, which is isomeric with nitrogen dioxide, as ozone is isomeric with oxygen, and has twice as great a vapour density (46 referred to hydrogen), is formed in greater quantity the lower the temperature, and crystallises at -10° . The reasons both of the variation of the colour of the gas (N_2O_4 gives colourless and transparent vapours, whilst those of NO_2 are brown and opaque) and the variation of the vapour density with the variation of

⁴⁴ According to certain investigations, if a brown liquid is formed from the melted crystals by heating above -9° , then they no longer solidify at -10° , probably because a certain amount of N_2O_5 (and oxygen) is formed, and this substance remains liquid at -30° , or it may be that the passage from 2NO_2 into N_2O_4 is not so easily accomplished as the passage from N_2O_4 into 2NO_2 .

Liquid nitrogen peroxide (that is, a mixture of NO_2 and N_2O_4) is employed in admixture with hydrocarbons as an explosive.

temperature are thus made quite clear, and as at the boiling point a density 38 was obtained, therefore at that temperature the vapours consist of a mixture of 79 parts by weight of N_2O_4 with 21 parts by weight of NO_2 .⁴⁵ It is evident that a decomposition here takes place whose peculiarity consists in the fact that the product of decomposition, NO_2 , is polymerised (*i.e.* becomes denser, combines with itself) at a lower temperature; that is, the reaction,



is a reversible reaction, and consequently the whole phenomenon represents a *dissociation* in a homogeneous gaseous medium, where the original substance, N_2O_4 , and the resultant, NO_2 , are both gases. The *measure of dissociation* will be expressed if we find the proportion of the quantity of the substance decomposed to the whole amount of the substance. At the boiling point, therefore, the measure of the decomposition of nitrogen peroxide will be $21/(79+21)=0\cdot21$, or 21 p.c.; at 135° it=1, and at 10° it=0—that is, the N_2O_4 is not then decomposable. Consequently here the limits of dissociation are -10° and 135° at the atmospheric pressure.⁴⁶ Within the limits of these temperatures the vapours of nitrogen peroxide have not a constant density, and above and below these limits definite substances exist. Thus above 135° N_2O_4 has ceased to exist and NO_2 alone remains. It is

⁴⁵ Because if x equal the amount by weight of N_2O_4 , its volume will $=x/46$, and the amount of NO_2 will $=100-x$, and consequently its volume will $=(100-x)/23$. But the mixture, having a density 38, will weigh 100, consequently its volume will $=100/38$. Hence $x/46 + (100-x)/23 = 100/38$, or $x=79\cdot0$.

⁴⁶ The phenomena and laws of dissociation, considered by us in only separate and particular instances, are discussed in detail in works on theoretical chemistry. Besides, certain points in the doctrine of chemical equilibria are still subject to some doubt owing to the recent date at which the exact study of this subject commenced. Nevertheless, in respect to nitrogen peroxide, as an historically important example of dissociation in a homogeneous gaseous medium, we will cite the results of the careful investigations (1885–1886) of E. and L. Natanson, who determined the densities under variations of temperature and pressure. The measure of dissociation, expressed as above (it may also be expressed otherwise—for example, by the ratio of the substance decomposed to that unaltered), proves to increase at all temperatures as the pressure diminishes, which would be expected for a homogeneous gaseous medium, as a decreasing pressure aids the formation of the lightest product of dissociation (that having the least density or largest volume). Thus, in Natansons' experiments the measure of dissociation at 0° increases from 10 p.c. to 30 p.c., with a decrease of pressure of from 251 to 38 mm.; at $49\cdot7^\circ$ it increases from 49 p.c. to 93 p.c., with a fall of pressure of from 498 to 27 mm., and at 100° it increases from 89\cdot2 p.c. to 99\cdot7 p.c., with a fall of pressure of from 782\cdot5 to 11\cdot7 mm. At 130° and 150° the decomposition is complete—that is, NO_2 only remains at the low pressures (less than the atmospheric) at which the Natansons made their determinations; but it is probable that at considerable pressure (of several atmospheres) molecules of N_2O_4 would still be formed, and it would be exceedingly interesting to trace the phenomena under the conditions of both very considerable pressures and of relatively large volumes.

evident that at the ordinary temperature there is a partially dissociated system or mixture of nitrogen peroxide, N_2O_4 , and nitrogen dioxide, NO_2 . In the brown liquid boiling at 22° probably a portion of the N_2O_4 has already passed into NO_2 , and it is only the colourless liquid and crystalline substance at -10° that can be considered as pure nitrogen peroxide.⁴⁷

The above explains the action of nitrogen peroxide on water at low temperatures. N_2O_4 then acts on water like a mixture of the anhydrides of nitrous and nitric acids. The first, N_2O_3 , may be looked on as water in which the two atoms of hydrogen are replaced by the radicle NO , while in the second the hydrogen is replaced by the radicle NO_2 , proper to nitric acid; and in nitrogen peroxide one atom of the hydrogen of water is replaced by NO and the other by NO_2 , as is seen from the formulæ—



In fact, nitrogen peroxide at low temperatures gives with water (ice) both nitric, HNO_3 , and nitrous, HNO_2 , acids. The latter, as we shall afterwards see, splits up into water and the anhydride, N_2O_3 . If, however, warm water act on nitrogen peroxide, only nitric acid and oxide of nitrogen are formed: $3NO_2 + H_2O = NO + 2HNO_3$.

Although NO_2 is not decomposed into N and O even at 500° , still in many cases it acts as an oxidising agent. Thus, for instance, it oxidises mercury, converting it into mercurous nitrate, $2NO_2 + Hg = HgNO_3 + NO$, it being itself deoxidised into nitric oxide, into

⁴⁷ The fact that the presence of a portion of dioxide, NO_2 , must be acknowledged in liquid nitrogen peroxide, N_2O_4 , at temperatures of from 0° to 22° , is not only of great significance for the theory which regards solutions as liquid systems of equilibrium, consisting of combined and decomposed substances, but it also shows the nature of solutions of gaseous substances, because the NO_2 must be regarded as a gas dissolved in the volatile liquid N_2O_4 .

Liquid nitrogen peroxide is said by Geuther to boil at 22° – 26° , and to have a sp. gr. at $0^\circ = 1.494$ and at $15^\circ = 1.474$. It is evident that, in the liquid as in the gaseous state, the variation of density with the temperature depends not only on physical, but also on chemical changes, as the amount of N_2O_4 decreases and the amount of NO_2 increases with the temperature, and they (as polymeric substances) should have different densities, as we find, for instance, in the hydrocarbons C_5H_{10} and $C_{10}H_{20}$.

It may not be superfluous to here mention that the measurement of the specific heat of a mixture of the vapours of N_2O_4 and NO_2 enabled Berthelot to determine that the transformation of $2NO_2$ into N_2O_4 is accompanied by the evolution of about 13000 units of heat, and as the reaction proceeds with equal facility in either direction, it will be exothermal in the one direction and endothermal in the other; and this clearly demonstrates the possibility of reactions of both aspects proceeding in either direction, although, as a rule, reactions evolving heat proceed with greater ease.

which nitrogen dioxide in many other instances passes, and from which it is easily formed.⁴⁸

Nitrous anhydride, N_2O_3 , corresponds⁴⁹ with nitrous acid, NHO_2 , and with the latter corresponds a series of salts, the nitrites—for example, the sodium salt $NaNO_2$, the potassium salt KNO_2 , the ammonium salt $(NH_4)NO_2$,⁵⁰ the silver salt $AgNO_2$,⁵¹ &c. Neither the anhydride nor the hydrate of the acid is known in a perfectly pure state. The anhydride has only been obtained as a very unstable substance, and has not yet been investigated with proper fulness; and when efforts are made to obtain the acid NHO_2 from its salts, it always gives water and the anhydride, whilst the latter, as an intermediate oxide, easily splits up into $NO + NO_2$. But the salts of nitrous acid are distinguished for their great stability. Potassium nitrate, KNO_3 , may be converted into potassium nitrite by depriving it of a portion of its oxygen; for instance, by fusing it (at a not too great heat) with metals, such as lead, $KNO_3 + Pb = KNO_2 + PbO$. The resultant salt is soluble in water, whilst the oxide of lead is insoluble. With sulphuric and other acids the solution of potassium nitrite⁵² immediately evolves a brown gas, nitrous anhydride: $2KNO_2 + H_2SO_4 = K_2SO_4 + N_2O_3 + H_2O$. The same gas (N_2O_3) is obtained by passing nitric oxide at 0° through liquid peroxide of nitrogen,⁵³ or by heating starch with nitric acid of sp.

⁴⁸ Nitric acid of sp. gr. 1.51 in dissolving nitrogen peroxide becomes brown, whilst nitric acid of sp. gr. 1.32 is coloured greenish blue, and acid of sp. gr. below 1.15 remains colourless on absorbing nitrogen peroxide.

⁴⁹ Nitrogen peroxide as a mixed substance has no corresponding independent salts.

⁵⁰ Ammonium nitrite may be easily obtained in solution by a similar method of double decomposition (for instance, of the barium salt with ammonium sulphate) to the other salts of nitrous acid, but it decomposes with great ease when evaporated, with the evolution of gaseous nitrogen, as has been already mentioned (Chap. V.). If the solution, however, be evaporated at the ordinary temperature under the receiver of an air-pump, a solid saline mass is obtained, which is easily decomposed when heated. The dry salt even decomposes with an explosion when struck, or when heated to about 70° — $NH_4NO_2 = 2H_2O + N_2$. It is also formed by the action of aqueous ammonia on a mixture of nitric oxide and oxygen, or by the action of ozone on ammonia, and in many other instances.

⁵¹ Silver nitrite, $AgNO_2$, is obtained as a very slightly soluble substance, as a precipitate, on mixing solutions of silver nitrate, $AgNO_3$, and potassium nitrite, KNO_2 . It is soluble in a large volume of water, and this is taken advantage of to free it from silver oxide, which is also present in the precipitate, owing to the fact that potassium nitrite always contains a certain amount of oxide, which with water gives the hydroxide, forming oxide of silver with silver nitrate. The solution of silver nitrite gives, by double decomposition with metallic chlorides (for instance, barium chloride), insoluble silver chloride and the nitrite of the metal taken (for instance, barium nitrite, $Ba(NO_2)_2$).

⁵² Probably potassium nitrite, KNO_2 , when strongly heated, especially with metallic oxides, evolves N and O, and gives potassium oxide, K_2O , because nitre is liable to such a decomposition, but it has, as yet, been but little investigated.

⁵³ It is evident that the reaction $N_2O_5 = NO_2 + NO$ is reversible, and that it resembles the conversion of N_2O_4 into NO_2 , but as yet this reaction has not been thoroughly

gr. 1.3. At a very low temperature it condenses into a blue liquid boiling below 0° ,⁵⁴ but then partially decomposing into $\text{NO} + \text{NO}_2$. Nitrous anhydride evinces a remarkable capacity for oxidising. Ignited bodies burn in it, nitric acid absorbs it, and then acquires the property of acting on silver and other metals, even when diluted. *Potassium iodide* is oxidised by this gas just as it is by ozone (and by peroxide of hydrogen, chromic and other acids, but not by dilute nitric acid nor by sulphuric acid), with the *separation of iodine*. This iodine may be recognised (*see* Ozone, Chap. IV.) by its turning starch blue. The smallest traces of nitrites may be easily discovered by this method. If, for example, starch and potassium iodide are added to a solution of potassium nitrite (there will be no change, there being no free nitrous acid), and then sulphuric acid be added, then the nitrous acid (or its anhydride) immediately set free evolves iodine, which communicates a blue colour to the starch. Nitric acid does not act in this manner, but in the presence of zinc the coloration takes place, which proves the formation of nitrous acid in the deoxidation of nitric acid.⁵⁵ Nitrous acid (or even a mixture of $\text{HNO}_2 + \text{NO}$) acts directly on ammonia, forming nitrogen and water, $\text{HNO}_2 + \text{NH}_3 = \text{N}_2 + 2\text{H}_2\text{O}$.⁵⁶

As nitrous anhydride easily splits up into $\text{NO}_2 + \text{NO}$, so with warm water it, like NO_2 , gives nitric acid and nitric oxide, according to the equation $3\text{N}_2\text{O}_3 + \text{H}_2\text{O} = 4\text{NO} + 2\text{HNO}_3$.

Being in a lower degree of oxidation than nitric acid, nitrous acid

studied. The brown colour of the vapours of nitrous anhydride probably depends on the presence of NO_2 .

If nitrogen peroxide be cooled to -20° , and half its weight of water be added to it drop by drop, then the peroxide is decomposed, as we have already said, into nitrous and nitric acids; the former does not then remain as a hydrate, but straightway passes into the anhydride, and, therefore, if the resultant liquid be slightly warmed vapours of nitrous anhydride, N_2O_3 , are evolved, and condense into a blue liquid, as Fritzsche showed. This method of preparing nitrous anhydride evidently gives the purest product.

⁵⁴ According to Thorpe, N_2O_3 boils at $+18^{\circ}$. According to Geuther, at $+3.5^{\circ}$, and its sp. gr. at $0^{\circ} = 1.449$.

⁵⁵ In its oxidising action nitrous anhydride gives nitric oxide, $\text{N}_2\text{O}_3 = 2\text{NO} + \text{O}$. Thus its analogy to ozone becomes still closer, because in ozone it is only one-third of the oxygen that acts in oxidising; from O_3 there is obtained O , which acts as an oxidiser, and common oxygen O_2 . In a physical aspect the affinity between N_2O_3 and O_3 is expressed by both substances being of a blue colour when in the liquid state.


⁵⁶ This reaction is taken advantage of for converting the amides, NH_2R (where R is an element or a complex group) into hydroxides, RHO . In this case $\text{NH}_2\text{R} + \text{HNO}_2$ forms $2\text{N} + \text{H}_2\text{O} + \text{RHO}$; NH_2 is replaced by HO , the radicle of ammonia by the radicle of water. This reaction is employed for transforming many nitrogenous organic substances having the properties of amides into their corresponding hydroxides. Thus aniline, $\text{C}_6\text{H}_5\text{NH}_2$, which is obtained from nitrobenzene, $\text{C}_6\text{H}_5\text{NO}_2$ (Note 37), is converted by nitrous anhydride into phenol, $\text{C}_6\text{H}_5\text{OH}$, which occurs in the creosote extracted from coal tar. Thus the H of the benzene is successively replaced by NO_2 , NH_2 , and HO —a method which is suitable for other cases also.

and its anhydride are oxidised in solutions by many oxidising substances—for example, by potassium permanganate—into nitric acid.⁵⁷

Nitric oxide, NO.—This permanent gas⁵⁸ (that is, unliquefiable by pressure without the aid of cold) may be obtained from all the above-described compounds of nitrogen with oxygen. The deoxidation of nitric acid by metals is the usual method employed for its preparation. Dilute nitric acid (sp. gr. 1.18, but not stronger, as then N_2O_3 and NO_2 are produced) is poured into a flask containing metallic copper.⁵⁹ The reaction commences at the ordinary temperature. Mercury and silver also give nitric oxide with nitric acid. In these reactions with metals one portion of the nitric acid is employed in the oxidation of the metal, whilst the other, and by far the greater, portion combines with the metallic oxide so obtained, with formation of the nitrate corresponding with the metal taken. The first action of the copper on the nitric acid is thus expressed by the equation



The second reaction consists in the formation of copper nitrate—



Nitric oxide is a colourless gas which is only slightly soluble in water ($\frac{1}{20}$ of a volume at the ordinary temperature). Reactions of double decomposition in which nitric oxide readily takes part are not known—that is to say, it is an indifferent, not a saline, oxide. Like the other oxides of nitrogen, it is decomposed into its elements at a red heat. The most characteristic property of nitric oxide consists in its capacity for directly and easily combining with oxygen (owing to the evolution of heat in the combination). With oxygen it forms nitrous anhydride

⁵⁷ The action of a solution of potassium permanganate, KMnO_4 , on nitrous acid in the presence of sulphuric acid is determined by the fact that the higher oxide of manganese, Mn_2O_7 , contained in the permanganate is converted into the lower oxide MnO , which as a base forms manganese sulphate, MnSO_4 , and the oxygen serves for the oxidation of the N_2O_3 into N_2O_5 , or its hydrate. As the solution of the permanganate is of a red colour, whilst that of manganese sulphate is almost colourless, this reaction is clearly seen, and may be employed for the recognition and determination of nitrous acid and its salts.

⁵⁸ The absolute boiling point = 93° (see Chap. II. Note 29).

⁵⁹ Kammerer proposed preparing nitric oxide, NO, by pouring a solution of sodium nitrate over copper shavings, and adding sulphuric acid drop by drop. The oxidation of ferrous salts by nitric acid also gives NO. One part of strong hydrochloric acid is taken and iron is dissolved in it (FeCl_2), and then an equal quantity of hydrochloric acid and nitre is added to the solution. On heating, nitric oxide is evolved. When nitric oxide is prepared by either of the above methods, the apparatus first becomes full of brown fumes of nitrogen peroxide, formed by the oxygen of the air and the nitric oxide, and therefore the pure gas can only be collected after it has displaced all the air in the apparatus, and when the latter becomes full of colourless gas.

and nitrogen peroxide, $2\text{NO} + \text{O} = \text{N}_2\text{O}_3$, $2\text{NO} + \text{O}_2 = 2\text{NO}_2$. If nitric oxide is mixed with oxygen and immediately shaken up with caustic potash, it is almost entirely converted into potassium nitrite, whilst after a certain time, when the formation of nitric peroxide has already commenced, a mixture of potassium nitrite and nitrate is obtained. If oxygen is passed into a bell jar filled with nitric oxide, then brown fumes of nitrous anhydride and nitric peroxide are formed, which in the presence of water give, as we already know, nitric acid and nitric oxide, so that in the presence of an excess of water and oxygen the whole of the nitric oxide is easily and directly converted into nitric acid. This reaction of the re-formation of nitric acid from nitric oxide, air, and water, $2\text{NO} + \text{H}_2\text{O} + \text{O}_3 = 2\text{HNO}_3$, is frequently made use of in practice. The experiment showing the conversion of nitric oxide into nitric acid is very striking and instructive. As the intermixture of the oxygen with the oxide of nitrogen proceeds, the nitric acid formed dissolves in water, and if an excess of oxygen has not been added the whole of the gas (nitric oxide), being converted into HNO_3 , is absorbed, and the water entirely fills the bell jar previously containing the gas.⁶⁰ It is evident that nitric oxide⁶¹ in combining with oxygen

⁶⁰ This transformation of the permanent gases nitric oxide and oxygen into liquid nitric acid in the presence of water, and with the evolution of heat, presents a most striking instance of liquefaction produced by the action of chemical forces. They perform with ease the work which physical (cooling) and mechanical (pressure) forces do with difficulty. In this the motion, which is so clearly the property of the gaseous molecules, is extinguished. In other cases of chemical action its appearance arises from latent energy—that is, in all probability, from the movement of the atoms in the molecules.

⁶¹ Nitric oxide is capable of entering into many characteristic combinations; it is absorbed by the solutions of many acids (for instance, tartaric, acetic, phosphoric, sulphuric), and also by the solutions of many salts, especially those formed by suboxide of iron (for instance, ferrous sulphate). In this case a brown compound is formed which is exceedingly unstable, like all the analogous compounds of nitric oxide. The amount of nitric oxide combined in this manner is in atomic proportion with the amount of the substance taken; thus ferrous sulphate, FeSO_4 , absorbs it in the proportion of NO to 2FeSO_4 . Ammonia is obtained by the action of a caustic alkali on the resultant compound, because the oxygen of the nitric oxide and water are transferred to the ferrous oxide, forming ferric oxide, whilst the nitrogen combines with the hydrogen of the water. According to the investigations of Gay (1885), the compound is formed with the evolution of a large quantity of heat, and is easily dissociated, like a solution of ammonia in water. This subject must be regarded as not sufficiently studied. On passing nitric oxide through nitric acid, nitrogen peroxide and nitrous anhydride are formed, whose solutions in the nitric acid are, as we have already mentioned, of various colours. It is evident that oxidising substances (for example, potassium permanganate, KMnO_4 , Note 57) are able to convert it into nitric acid. If the presence of a radicle NO_2 , composed like nitrogen peroxide, must be recognised in the compounds of nitric acid, then a radicle NO , having the composition of nitric oxide, may be admitted in the compounds of nitrous acid. The compounds in which the radicle NO is recognised are called *nitroso-compounds*. The compounds are described in Prof. Bunge's work (Kief, 1868).

has a strong tendency to give only the higher types of nitrogen compounds, which we see in nitric acid, HNO_3 or $\text{NO}_2(\text{OH})$, in nitric anhydride, N_2O_5 or $(\text{NO}_2)_2\text{O}$, and in ammonium chloride, NH_4Cl . If X stand for an atom of hydrogen, or its equivalents, chlorine, hydroxyl, &c., and if O, which is, according to the law of substitution, equivalent to H_2 , be indicated by X_2 , then the three above-named compounds of nitrogen should be considered as compounds of the type or form NX_5 . For example, in nitric acid $\text{X}_5=\text{O}_2+(\text{OH})$, where $\text{O}_2=\text{X}_4$, and $\text{OH}=\text{X}$; whilst nitric oxide is a compound of the form NX_2 . Hence this lower form, as is true of lower forms in general, strives by combination to attain to the higher forms proper to the compounds of a given element. NX_2 passes consecutively into NX_3 —namely, into N_2O_3 and NHO_2 , NX_4 (for instance NO_2) and NX_5 .

As the decomposition of nitric oxide begins at temperatures above 600° , many substances burn in it; for instance, ignited phosphorus continues to burn in nitric oxide, but sulphur and charcoal are extinguished in it. This is due to the fact that the heat evolved in the combustion of these two substances is insufficient for the entire decomposition of the nitric oxide, whilst the heat developed by burning phosphorus suffices to produce this decomposition. That this is the true explanation of the behaviour of nitric oxide in these cases is proved by the fact that charcoal when very strongly ignited will burn in the gas.⁶²

The compounds of nitrogen with oxygen which we have so far considered may all be prepared from nitric oxide, and may themselves be converted into it. Thus nitric oxide stands in intimate connection with them.⁶³ The passage of nitric oxide into the higher degrees of

⁶² A mixture of nitric oxide and hydrogen is inflammable. If a mixture of both gases be passed over spongy platinum, the nitrogen and hydrogen even combine, forming ammonia. A mixture of nitric oxide with many combustible vapours and gases is very inflammable. A very characteristic flame is obtained in burning a mixture of nitric oxide and the vapour of the combustible carbon bisulphide, CS_2 . The latter substance is very volatile, so that it is sufficient to pass the nitric oxide through a layer of the carbon bisulphide (for instance, in a Woulfe's bottle) in order that the gas escaping should contain a considerable amount of the vapours of this substance. This mixture continues to burn when set light to, and the flame emits a large quantity of the so-called ultra-violet rays, which are capable of bringing about chemical combinations and decompositions, and therefore the flame may be employed in photography in the absence of sufficient daylight (magnesium and electric light have the same property). A mixture of nitric oxide with many gases (for instance, ammonia) explodes in a eudiometer.

⁶³ The oxides of nitrogen do not proceed directly from oxygen and nitrogen by contact alone, naturally because their formation is accompanied by the absorption of a large quantity of heat, namely (*see* Note 29), about 21500 heat units are absorbed when 16 parts of oxygen and 14 parts of nitrogen combine, consequently the decomposition of nitric oxide into oxygen and nitrogen is accompanied by the evolution of this amount of heat; and therefore with nitric oxide, as with all explosive substances and mixtures, the reaction once started is able to proceed by itself. In fact, Berthelot remarked the decomposition of nitric oxide in the explosion of fulminate of mercury. This decomposition does not take


oxidation and the converse reaction is employed in practice as a means for *transferring* the oxygen of the air to substances capable of being oxidised. Having nitric oxide, it may easily be converted, with the aid of the oxygen of the atmosphere and water, into nitric acid, nitrous anhydride, and nitric peroxide, and by their means employed to oxidise other substances. In this oxidising action nitric oxide is again formed, and it may again be converted into nitric acid, and so on without end, if only there be oxygen and water. Hence the fact, which at first appears to be a paradox, that by means of a small quantity of nitric oxide in the presence of oxygen and water it is possible to oxidise an indefinitely large quantity of substances which cannot be directly oxidised either by the action of the atmospheric oxygen or by the action of nitric oxide itself. The sulphurous anhydride, SO_2 , which is obtained in the combustion of sulphur and in roasting many metallic sulphides in the air, is an example of this kind. In practice this gas is obtained by burning sulphur or iron pyrites, the latter being thereby converted into oxide of iron and sulphurous anhydride. In contact with the oxygen of the atmosphere this gas does not pass into the higher degree of oxidation sulphuric anhydride, SO_3 , and if it does form sulphuric acid with water and the oxygen of the atmosphere, $\text{SO}_2 + \text{H}_2\text{O} + \text{O} = \text{H}_2\text{SO}_4$, it does so very slowly. With nitric acid (and especially with nitrous acid, but not with nitrogen peroxide) and water, sulphurous anhydride, on the contrary, very easily forms sulphuric acid, and especially so when slightly heated (about 40°), the nitric acid (or, better still, nitrous acid) being converted into nitric oxide—



The presence of water is absolutely indispensable here, otherwise sulphuric anhydride is formed, which combines with the oxides of nitrogen (nitrous anhydride), forming a crystalline substance containing oxides of nitrogen (*chamber crystals*, which will be described in the chapter on sulphur). Water destroys this compound, forming sulphuric acid and separating the oxides of nitrogen. The water must be taken in a greater quantity than that required for the formation of the hydrate H_2SO_4 , because the latter absorbs oxides of nitrogen. With an excess of water, however, solution does not take place. If, in the above reaction, only water, sulphurous anhydride, and nitric or nitrous acid be taken in

places spontaneously; substances even burn with difficulty in nitric oxide, probably because a certain portion of the nitric oxide in decomposing gives oxygen, which combines with another portion of nitric oxide and forms nitric peroxide, a somewhat more stable compound of nitrogen and oxygen. The further combinations of nitric oxide with oxygen all proceed with the evolution of heat, and take place spontaneously by contact with air alone. From these examples it is seen how the use of thermochemical data is limited by facts.

a definite quantity, then a definite quantity of sulphuric acid and nitric oxide will be formed, according to the preceding equation ; but there the reaction ends, the excess of sulphurous anhydride, if there be any, will remain unchanged. But if we add air and water, then the nitric oxide will unite with the oxygen to form nitrogen peroxide, and the latter with water to form nitric and nitrous acids, which again give sulphuric acid from a fresh quantity of sulphurous anhydride. Nitric oxide is again formed, which is able to start the oxidation afresh if there be sufficient air. Thus it is possible with a definite quantity of nitric oxide to convert an indefinitely large quantity of sulphurous anhydride into sulphuric acid, water and oxygen only being required.⁶⁴ This may be easily demonstrated by an experiment on a small scale, if a certain quantity of nitric oxide be first introduced into a flask, and sulphurous anhydride, steam, and oxygen be then continually passed in. Thus the above-described reaction may be expressed in the following manner :



if we consider only the original substances and those finally formed. Thus a definite quantity of nitric oxide may serve for the conversion of an indefinite quantity of sulphurous anhydride, oxygen, and water into sulphuric acid. In reality, however, there is a limit to this, because a portion of the resulting oxides of nitrogen are dissolved by the sulphuric acid, so that in employing even pure oxygen the amount of free (undissolved) or active nitric oxide decreases little by little. If air, and not pure oxygen, be employed for the oxidation, as it is necessary to do in practice, then it is necessary to remove the nitrogen of the air and to introduce a fresh quantity of air. A certain quantity of nitric oxide will pass away with this nitrogen, and will in this way be lost.⁶⁵

⁶⁴ The instance of the action of a small quantity of NO in inciting a definite chemical reaction between large masses ($\text{SO}_2 + \text{O} + \text{H}_2\text{O} = \text{H}_2\text{SO}_4$) is very instructive, because the particulars relating to it have been studied, and show that intermediate forms of reaction may be discovered in the so-called contact or catalytic phenomena. The essence of the matter here is that A ($= \text{SO}_2$) reacts upon B ($= \text{O}$ and H_2O) in the presence of C, because it gives BC, a substance which forms AB with A, and again liberates C. Consequently C is a medium, a transferring substance, without which the matter does not proceed of its own accord. Many similar phenomena may be found in other departments of life. Thus the merchant is an indispensable medium between the producer and the consumer ; thus experiment is a medium between the phenomena of nature and the cognisant faculties ; thus language, forms, and laws are media which are as necessary for the consolidation of social intercourse as nitric oxide for the relations between sulphurous anhydride and oxygen and water.

⁶⁵ If the sulphurous anhydride can be prepared by roasting iron pyrites, FeS_2 , then each equivalent of pyrites (equivalent of iron 56, of sulphur 32, of pyrites 120) requires six equivalents of oxygen (that is 96 parts) for the conversion of its sulphur into sul-

The preceding series of changes serve as the basis of the *manufacture of sulphuric acid* or so called *chamber acid*. This acid is prepared on a very large scale in chemical works because it is the cheapest acid whose action can be applied in a great number of cases. It is thus used in immense quantities.

The process is carried on in a series of chambers (or in one divided by partitions as in fig. 50, which shows the beginning and end of a chamber) constructed of sheet lead. These chambers are placed one




FIG. 50.—Section of sulphuric acid chambers, the first and last chambers only being represented. The tower to the left is called the Glover's tower, and that on the right the Gay-Lussac's tower. Less than $\frac{1}{100}$ of the natural size.

after the other, and communicate with one another by tubes or special orifices so placed that the inlet tubes are in the upper portion of the chamber, and the outlet in the lower and opposite end. The current of

phuric acid (for forming $2\text{H}_2\text{SO}_4$ with water), besides $1\frac{1}{2}$ equivalents (24 parts) for converting the iron into oxide, Fe_2O_3 ; hence the combustion of the pyrites for the formation of sulphuric acid and ferric oxide requires the introduction of an equal weight of oxygen (120 parts of oxygen to 120 parts of pyrites), or five times its weight of air, whilst four parts by weight of nitrogen will remain inactive, and in the removal of the exhausted air will carry off the remaining nitric oxide. If not all, at least a large portion of the nitric oxide may be collected by passing the escaping air, still containing some oxygen, through substances which absorb oxides of nitrogen. Sulphuric acid itself may be employed for this purpose if it be taken as the hydrate H_2SO_4 , or containing only a small amount of water, because such sulphuric acid dissolves the oxides of nitrogen.

steam and gases necessary for the preparation of the sulphuric acid passes through these chambers and tubes. The acid as it is formed falls to the bottom of the chambers, or runs down their walls, and flows from one chamber to another (from the last to the first, to permit of which the partitions do not reach to the bottom of the chambers), and therefore the floor and walls of the chambers should be made of a material on which the sulphuric acid will not act. Among the ordinary metals lead is the only one suitable. The other metals, such as iron, zinc, or copper, are corroded by the acid; glass and earthenware are not acted on, but would not withstand the changes of temperature which occur in the chambers, and would be difficult to join closely; whilst wood and similar materials are destroyed by the acid.

For the formation of the sulphuric acid it is necessary to introduce sulphurous anhydride, steam, air, and nitric acid, or some oxide of nitrogen, into the chambers. The sulphurous anhydride is produced by burning sulphur or iron pyrites. This is carried on in the furnace with four hearths to the left of the drawing. Air is led into the chambers and furnace through orifices in the furnace doors. The current of air and oxygen is regulated by opening or closing these orifices to a greater or less extent. The ingoing draught in the chambers is brought about by the fact that heated gases and vapours pass into the chambers whose temperature is further raised by the reaction itself, and also by the remaining nitrogen being continually withdrawn from the outlet (above the tower *K*) by a tall chimney situated near the chambers. Nitric acid is prepared from a mixture of sulphuric acid and Chili saltpetre, in the same furnaces in which the sulphurous anhydride is evolved (or in special furnaces). Not more than 8 parts of nitre are taken to 100 parts of sulphur burnt. On leaving the furnace the vapours of nitric acid and oxides of nitrogen mixed with air and sulphurous anhydride first pass along the horizontal tubes *T* into the receiver *B B*, which is partially cooled by water flowing in on the right-hand side and running out on the left by *o*, in order to reduce the temperature of the gases entering the chamber. The gases then pass up a tower filled with coke, and shown to the left of the drawing. In this tower are placed lumps of

They may be easily expelled from this solution by heating or by dilution with water, as they are only slightly soluble in aqueous sulphuric acid. Besides which, sulphurous anhydride acts on such sulphuric acid, being oxidised at the expense of the nitrous anhydride, and forming nitric oxide from it, which again enters into the cycle of action. Therefore the sulphuric acid which has absorbed the oxides of nitrogen escaping from the chambers in the tower *K* (see fig. 50) is led back into the first chamber, where it comes into contact with sulphurous anhydride, by which means the oxides of nitrogen are reintroduced into the reaction which proceeds in the chambers. This is the use of the towers (Gay-Lussac's and Glover's) which are erected at either end of the chambers.

coke (partially distilled coal), over which trickles sulphuric acid from the reservoir *m*. This acid has absorbed in the end tower *k* the oxides of nitrogen escaping from the chamber. This end tower is also filled with coke, over which a stream of strong sulphuric acid trickles from the reservoir *m*. The acid spreads over the coke, and, owing to the large surface offered by the coke, absorbs the greater part of the oxides of nitrogen escaping from the chambers. The sulphuric acid in passing down the tower becomes saturated with the oxides of nitrogen, and flows out at *h* into a special receiver (in the drawing situated by the side of the furnaces), from which it is forced up the tubes *h'* *h'* by steam pressure into the reservoir *m*, situated above the first tower. The gases passing through this tower from the furnace on coming into contact with the sulphuric acid take up the oxides of nitrogen contained in it, and these are thus returned to the chamber and again participate in the reaction. The sulphuric acid left after their extraction flows into the chambers. Thus, on leaving the first coke tower the sulphurous anhydride, air, and vapours of nitric acid and of the oxides of nitrogen pass through the upper tube *m* into the chamber. Here they come into contact with steam introduced by lead tubes into various parts of the chamber. The reaction takes place in the presence of water, the sulphuric acid falls to the bottom of the chamber, and the same process takes place in the following chambers until the whole of the sulphurous anhydride is consumed. A somewhat greater proportion of air than is strictly necessary is passed in, in order that no sulphurous anhydride should be left unaltered for want of sufficient oxygen. The presence of an excess of oxygen is shown by the colour of the gases escaping from the last chamber (into *D*). If they be of a pale colour it indicates an insufficiency of air (and the presence of sulphurous anhydride), as otherwise peroxide of nitrogen would be formed. A very dark colour shows an excess of air, which is also disadvantageous, because it increases the inevitable loss of nitric oxide by increasing the mass of escaping gases.⁶⁶

⁶⁶ By this means as much as 2500000 kilograms of chamber acid, containing about 60 p.c. of the hydrate H_2SO_4 and about 40 per cent. of water, may be manufactured per year in one plant of 5000 cubic metres capacity (without stoppages). This process has been brought to such a degree of perfection that as much as 300 parts of the hydrate H_2SO_4 are obtained from 100 parts of sulphur, whilst the theoretical amount is not greater than 306 parts. The acid parts with its excess of water on heating. For this purpose it is heated in lead vessels. However, the acid containing about 75 per cent. of the hydrate (60° Baumé), already begins to act on the lead when heated, and therefore the further removal of water is conducted by evaporating in glass or platinum vessels, as will be described in our article on sulphuric acid. The aqueous acid (50° Baumé) obtained in the chambers is termed chamber acid. The acid concentrated to 60° Baumé is more generally employed, and sometimes the hydrate (66° Baumé) termed

Nitrous oxide, N_2O ,⁶⁷ is similar to water in its volumetric composition. Two volumes of nitrous oxide are formed from two volumes of nitrogen and one volume of oxygen, which may be shown by the common

vitriol acid is also used. In England alone more than 1000 million kilograms of chamber acid are produced by this method. The formation of sulphuric acid by the action of nitric acid was discovered by Drebbel, and the first lead chamber was erected by Roebuck, in Scotland, in the middle of the last century. The essence of the process was ably brought to light at the beginning of this century, when many improvements were introduced into practice.

⁶⁷ Hyponitrous acid, corresponding with nitrous oxide (as its anhydride), is not known in a pure state, but its salts are known. They are prepared by the reduction of nitrous (and consequently of nitric) salts by sodium amalgam. If this amalgam be added to a cold solution of an alkaline nitrite until the evolution of gas ceases, and the excess of alkali saturated with acetic acid, an insoluble yellow precipitate of silver hyponitrite, NaAgO , will be obtained on adding a solution of silver nitrate. The hyponitrite is insoluble in cold acetic acid, and decomposes when heated, with the evolution of nitrous oxide. If rapidly heated it decomposes with an explosion. It is dissolved unchanged by feeble mineral acids, whilst the stronger acids (for example, sulphuric and hydrochloric acids) decompose it, with the evolution of nitrogen, nitric and nitrous acids remaining in solution. Among the other salts of hyponitrous acid, HNO , the salts of lead, copper, and mercury are insoluble in water. This is almost all that is at present known (according to the researches of Divers) concerning this compound, which in its composition and reactions presents a certain analogy to hypochlorous acid. There is even reason to think that the composition of silver hyponitrite, AgNO , is more complex than was at first supposed. As a substance which has not been sufficiently fully investigated, hyponitrous acid must be ranked with those compounds which yet present much that is doubtful. It is evident from the very method of its formation that it belongs to the class of compounds which are intermediate between the oxygen and hydrogen compounds of nitrogen. If its composition be NHO , then perhaps it is -NH_2 , in which two equivalents of hydrogen are replaced by oxygen (see p. 258). A substance of this composition, containing the hydrogen combined with the nitrogen, should most probably be isomeric, and not identical, with the true hydrate of nitrous oxide, because in the latter the hydrogen would be in the form of hydroxyl. Among such insufficiently investigated compounds—which, however, are of great interest—we must rank *amidogen*, or *hydrazine*, N_2H_4 , which was prepared by Curtius (1887) by means of ethyl diazoacetate, or triazoacetic acid. Curtius and Jay (1889) showed that triazoacetic acid, CHN_2COOH (the formula should be tripled), when heated with water or a mineral acid gives (quantitatively) oxalic acid and amidogen (hydrazine), $\text{CHN}_2\text{COOH} + 2\text{H}_2\text{O} - \text{C}_2\text{O}_2(\text{OH})_2 + \text{N}_2\text{H}_4$ —*i.e.* (empirically), the oxygen of the water replaces the nitrogen of the azoacetic acid. The amidogen is thus obtained in the form of a salt. With acids amidogen forms very stable salts of the two types, $\text{N}_2\text{H}_4\text{HX}$, and $\text{N}_2\text{H}_4\text{H}_2\text{X}_2$, as, for example, with HCl , H_2SO_4 , &c. These salts are easily crystallised; in acid solutions they act as powerful reducing agents, evolving nitrogen; when ignited they are decomposed into ammoniacal salts, nitrogen, and hydrogen; with nitrites they evolve nitrogen. The sulphate, $\text{N}_2\text{H}_4\text{H}_2\text{SO}_4$, is sparingly soluble in cold water (3 parts in 100 of water), but is very soluble in hot water; its specific gravity is 1.378, it fuses at 251° , with decomposition. The hydrochloride, $\text{N}_2\text{H}_4\cdot 2\text{HCl}$, crystallises in octahedra, is very soluble in water, but not in alcohol; it fuses at 198° , evolving hydrogen chloride, and forming the salt $\text{N}_2\text{H}_4\text{HCl}$; when rapidly heated it decomposes with an explosion; with platinic chloride it immediately evolves nitrogen, forming platinous chloride. By the action of the alkalis the salts $\text{N}_2\text{H}_4\cdot 2\text{HX}$ give *hydrate of amidogen*, $\text{N}_2\text{H}_4\text{H}_2\text{O}$, which is a fuming liquid, boiling at 119° , almost without odour, and whose aqueous solution corrodes glass and india-rubber, has an alkaline taste and poisonous properties. The reducing capacities of the hydrate are clearly seen from the fact that it reduces the

method of the analysis of the oxides of nitrogen (by passing them over red-hot copper or sodium). In contradistinction to the other oxides of nitrogen, it is not directly oxidised by oxygen, but it may be obtained from the higher oxides of nitrogen by the action of certain deoxidising substances; thus, for example, a mixture of two volumes of nitric oxide and one volume of sulphurous anhydride if left in contact with water and spongy platinum is converted into sulphuric acid and nitrous oxide, $2\text{NO} + \text{SO}_2 + \text{H}_2\text{O} = \text{H}_2\text{SO}_4 + \text{N}_2\text{O}$. Nitric acid, also, under the action of certain metals—for instance, of zinc⁶⁸—gives nitrous oxide, although in this case mixed with nitric oxide. The usual method of preparing nitrous oxide consists in the decomposition of ammonium nitrate by the aid of heat, because in this case only water and nitrous oxide are formed, $\text{NH}_4\text{NO}_3 = 2\text{H}_2\text{O} + \text{N}_2\text{O}$ (a mixture of NH_4Cl and KNO_3 is sometimes taken). The decomposition⁶⁹ proceeds very easily in an apparatus like that used for the preparation of ammonia or oxygen—that is, in a retort or flask with a gas-conducting tube. The decomposition must, however, be carried on carefully, as otherwise nitrogen is formed from the decomposition of the nitrous oxide.⁷⁰

Nitrous oxide is not a permanent gas (absolute boiling point $+36^\circ$), it is easily liquefied by the action of cold under a high pressure; at 15° it may be liquefied by a pressure of about 40 atmospheres. This gas is usually liquefied by means of the force pump⁷¹ shown in fig. 51.

metals platinum and silver from their solutions. With mercuric oxide it explodes. It reacts directly with the aldehydes RO , forming N_2R_2 and water; for example, with benzaldehyde it gives the very stable insoluble *benzalazine* $(\text{C}_6\text{H}_5\text{CHN})_2$, of a yellow colour. Further research should explain the relation of these very interesting salts to amidogen (N_2H_4) itself, which has not yet been isolated. Amidogen must be regarded as a substance which stands to ammonia in the same relation as hydrogen peroxide stands to water. Water, $\text{H}(\text{OH})$, gives, according to the law of substitution, as was clearly to be expected, $(\text{OH})(\text{OH})$ —that is, peroxide of hydrogen is the free radicle of water (hydroxyl). So also ammonia, $\text{H}(\text{NH}_2)$, forms hydrazine, $(\text{NH}_2)(\text{NH}_2)$ —that is, the free radicle of ammonia, NH_2 , or amidogen. In the case of phosphorus a similar substance, as we shall afterwards see, has long been known under the name of liquid phosphuretted hydrogen, P_2H_4 .

⁶⁸ It is remarkable that electro-deposited copper shavings give nitrous oxide with a 10 p.c. solution of nitric acid, whilst ordinary copper gives nitric oxide. It is here evident that the physical and mechanical structure of the substance effects the course of the reaction—that is to say, it is a case of contact.

⁶⁹ This decomposition is accompanied by the evolution of about 25000 calories per molecular quantity NH_4NO_3 , and therefore takes place with ease, and sometimes with an explosion.

⁷⁰ In order to remove any nitric oxide that might be present, the gas obtained is passed through a solution of ferrous sulphate. As nitrous oxide is very soluble in cold water (at 0° 100 volumes of water dissolve 130 volumes of N_2O , at 20° , 67 volumes), it must be collected over warm water. The nitrous oxide is much more soluble than nitric oxide, which is in agreement with the fact that the nitrous oxide is much more easily liquefied than the nitric oxide.

⁷¹ Faraday obtained liquid nitrous oxide by the same method as liquid ammonia,

Nitrous oxide forms a very mobile, colourless liquid, which acts on the skin, and which is incapable in a cold state of oxidising either metallic potassium, phosphorus, or carbon; its specific gravity is slightly less than that of water (0.94). When evaporated under the receiver of an air-pump, the temperature falls to -100° , and the liquid solidifies into a snow-like mass, and partially forms transparent crystals. Both these substances are solid nitrous oxide. Mercury is immediately solidified in contact with evaporating liquid nitrous oxide.⁷³

When introduced into the respiratory organs (and consequently into the blood also) nitrous oxide produces a peculiar kind of drunkenness accompanied by spasmodic movements, and hence this gas, discovered by Priestley in 1776, received the name of 'laughing gas.' On a prolonged respiration it produces a state of insensibility (it is an anæsthetic like chloroform), and it is therefore employed in dental and surgical operations.

Nitrous oxide is easily decomposed into nitrogen and oxygen by the action of heat, or a series of electric sparks; and this explains why a number of substances which cannot burn in nitric oxide do so with great ease in nitrous oxide. In fact, when nitric oxide gives some oxygen on decomposition, this oxygen immediately unites with a fresh portion of the gas to form nitric peroxide, whilst nitrous oxide does not possess this capacity for further combination with oxygen.⁷⁴ A mixture of nitrous oxide with hydrogen explodes like detonating gas, gaseous nitrogen being formed, $\text{N}_2\text{O} + \text{H}_2 = \text{H}_2\text{O} + \text{N}_2$. The volume of the remaining nitrogen is equal to the original volume of nitrous oxide, and is equal to the volume of hydrogen entering into

pressure of 25 mm. carbonic anhydride gives a temperature as low as -115° , and nitrous oxide of -125° (Dewar). The similarity of these properties and even of the absolute boiling point ($\text{CO}_2 + 32^{\circ}$, $\text{N}_2\text{O} + 36^{\circ}$) is all the more remarkable because these gases have the same molecular weight = 44 (Chap. IV. Note 10, and Chap. VII.).

⁷³ A very characteristic experiment of simultaneous combustion and of intense cold may be conducted by means of liquid nitrous oxide; if liquid nitrous oxide be poured into a test tube containing some mercury, then the mercury will solidify, and if a piece of red-hot charcoal be thrown upon the surface of the nitrous oxide it will continue to burn very brilliantly, giving rise to a high temperature.

⁷⁴ In the following chapter we shall consider the volumetric composition of the oxides of nitrogen. It explains the difference between nitric and nitrous oxide. Nitrous oxide is formed with a diminution of volumes (contraction), nitric oxide without contraction, its volume being equal to the sum of the volumes of nitrogen and oxygen of which it is composed. By oxidation, if it could be directly accomplished, two volumes of nitrous oxide and one volume of oxygen would not give three but four volumes of nitric oxide. These facts must be taken into consideration in comparing the calorific equivalents of formation, the capacity for supporting combustion, and other properties of nitrous and nitric oxides, N_2O and NO .

combination with the oxygen : hence in this reaction equal volumes of nitrogen and hydrogen replace each other. Nitrous oxide is also very easily decomposed by red-hot metals ; and sulphur, phosphorus, and charcoal burn in it, although not so brilliantly as in oxygen. An equal quantity of a substance in burning in nitrous oxide evolves more heat than in burning in oxygen ; which most clearly shows that in the formation of nitrous oxide by the combination of nitrogen with oxygen there was not an evolution but an absorption of heat, there being no other source for the excess of heat in the combustion of substances in nitrous oxide. If a given volume of nitrous oxide be decomposed by a metal—for instance, sodium—then there remains, after cooling and total decomposition, an exactly equal volume of nitrogen to that of the nitrous oxide taken ; consequently, the oxygen is, so to say, distributed between the atoms of nitrogen without producing an increase in the volume of the nitrogen.

CHAPTER VII

MOLECULES AND ATOMS. THE LAWS OF GAY-LUSSAC AND
AVOGADRO-GERHARDT

HYDROGEN combines with oxygen in the proportion of two volumes to one. The composition by volume of nitrous oxide is exactly similar—it is composed of two volumes of nitrogen and one volume of oxygen. By decomposing ammonia by the action of an electric spark it is easy to prove that it contains one volume of nitrogen to three volumes of hydrogen. So, similarly, it is found, whenever a compound is decomposed and the volumes of the gases proceeding from it are measured, that the volumes of the gases or vapours entering into combination are in a very simple proportion one to another. With water, nitrous oxide, &c., this may be proved by direct observation, but in the majority of cases, and especially with substances which, although volatile—that is, capable of passing into a gaseous (or vaporous) state—are liquid at the ordinary temperature, such a direct method of observation presents many difficulties. But then, if the densities of the vapours and gases be known, the same simplicity in their ratio is shown by calculation. The volume of a substance is proportional to its weight and inversely proportional to its density, and therefore by dividing the amount by weight of each substance entering into the composition of a compound by its density in the gaseous or vaporous state we shall obtain factors which will be in the same proportion as the volumes of the substances entering into the composition of the compound.¹ So,

¹ If the weight be indicated by P, the density by D, and the volume by V, then

$$\frac{P}{D} = KV,$$

where K is a coefficient depending on the system of the expressions P, D, and V. If D be the weight of a cubic measure of a substance referred to the weight of the same measure of water—if, as in the metrical system (Chap. I. Note 9), the cubic measure of one part by weight of water be taken as a unit of volume—then K = 1. But whatever it be, it is cancelled in dealing with the comparison of volumes, because comparative and not absolute measures of volumes are taken. In this chapter, as throughout the book, the weight P is given in grams in dealing with absolute weights; and if comparative, as in

for example, water contains eight parts by weight of oxygen to one part by weight of hydrogen, and their densities are 16 and 1, consequently their volumes (or the above-mentioned factors) 1 and $\frac{1}{2}$, and therefore it is seen without direct experiment that water contains two volumes of hydrogen for every one volume of oxygen. So also, knowing that nitric oxide contains fourteen parts of nitrogen and sixteen parts of oxygen, and knowing that the specific gravities of both these gases are fourteen and sixteen, we find that the volumes in which nitrogen and oxygen combine for the formation of nitric oxide are in the proportion of 1:1. Consequently, nitric oxide is a combination of equal volumes of nitrogen and oxygen. We will cite another example. In the last chapter we saw that the density of NO_2 only becomes constant and equal to twenty-three (referred to hydrogen) above 135° , and therefore a method of direct observation of the volumetric composition of this substance would be very difficult at so high a temperature. But it may be easily calculated. NO_2 , as is seen from its formula and analysis, contains thirty-two parts by weight of oxygen to fourteen parts by weight of nitrogen, forming forty-six parts by weight of NO_2 , and knowing the densities of these gases we find that one volume of nitrogen with two volumes of oxygen gives two volumes of nitrogen peroxide. Therefore, knowing the amounts by weight of the substances participating in a reaction or forming a given substance, and knowing the density of the gas or vapour,² the volumetric relations of the sub-

the expression of chemical composition, then the weight of an atom is taken as unity. The density of gases, D , is also taken in reference to the density of hydrogen, and the volume V in metrical units (cubic centimetres or cubic metres, &c.), if it be a matter of absolute magnitudes of volumes, and if it be a matter of chemical transformations—that is, of relative volumes—then the volume of an atom of hydrogen, or of one part by weight of hydrogen, is taken as unity, and all volumes are expressed according to these units.

² As the volumetric relations of vapours and gases, next to the relations of substances by weight, form the most important province of chemical learning and the most important means for the attainment of chemical conclusions, and inasmuch as these volumetric relations are determined by the densities of gases and vapours, therefore the methods of determining the densities of vapours (and also of gases) form important means in chemical research. These methods are described in detail in works on physics and physical and analytical chemistry, and therefore we here only touch on the general principles of the subject.

If we know the weight p and volume v , occupied by the vapour of a given substance at a temperature t and pressure h , then its density may be directly obtained by dividing p by the weight of a volume v of hydrogen (if the density be expressed according to hydrogen, see Chap. II. Note 23) at t and h . Hence, the methods of determining the density of vapours and gases are based on the determination of p , v , t , and h . The two last data (the temperature t and pressure h) are given by the thermometer and barometer and the heights of mercury or other liquid confining the gas, and therefore do not require further explanation. It need only be remarked that: (1) In the case of easily-volatile liquids there is no difficulty in procuring a bath with a constant temperature, but that it is, nevertheless, best (especially considering the inaccuracy of thermo-

stances acting in a reaction or entering into the composition of a compound, may be also determined.

meters) to have a medium of absolutely constant temperature, and therefore to take either a bath in which some substance is melting—such as melting ice at 0° or crystals of sodium acetate, melting at $+56^{\circ}$ —or, as is more generally practised, to place the vessel containing the substance to be experimented with in the vapour of a liquid boiling at a definite temperature, and, knowing the pressure under which it is boiling, to determine the temperature of the vapour. For this purpose the boiling points of water at different pressures are given in Chap. I. Note 11, and the boiling points of certain easily procurable liquids at various pressures are given in Chap. II. Note 27. (2) With respect to temperatures above 300° (below which mercurial thermometers may be conveniently employed), they are most simply obtained constant (to give time for the weight and volume of a substance being observed in a given space, and to allow that space to attain the calculated temperature t) by means of substances boiling at a high temperature. Thus, for instance, at the ordinary atmospheric pressure the temperature t of the vapour of sulphur is about 448° , of phosphorus pentasulphide 518° , of tin chloride 606° , of cadmium 770° , of zinc 930° (according to Violle and others), or 1040° (according to Deville), &c. (3) The indications of the hydrogen thermometer must be considered as the most exact (but hydrogen diffuses through ignited platinum, and therefore nitrogen is then employed). (4) The temperature of the vapours used as the bath should in every case be several degrees higher than the boiling point of the liquid whose density is to be determined, in order that no portion should remain in a liquid state. But even in this case, as is seen from the example of nitric peroxide (Chap. VI.), the vapour density does not always remain constant with a change of t , as it should were the law of the expansion of gases and vapours absolutely exact (Chap. II. Note 26). If variations of a chemical and physical nature similar to that which we saw in nitric peroxide take place in the vapours, the main interest is centred in *constant* densities, which do not vary with t , and therefore the possible effect of t on the density must always be kept in mind in having recourse to this means of investigation. (5) Usually, for the sake of convenience of observation, the vapour density is determined at the atmospheric pressure which is read on the barometer; but in the case of substances which are volatilised with difficulty, and also of substances which decompose, or, in general, vary at temperatures near their boiling points, it is best or indispensable to conduct the determination at low pressures, whilst for substances which decompose at low pressures the observations have to be conducted under a more or less considerably increased pressure. (6) In many cases it is convenient to determine the vapour density of a substance in admixture with other gases, and consequently under the partial pressure, which may be found, knowing the volume of the mixture and that of the intermixed gas (*see* Chap. I. Note 1). This method is especially important for substances which are easily decomposable, because, judging by the phenomena of dissociation, a substance is able to remain unchanged in the atmosphere of one of its products of decomposition. Thus, Wurtz determined the density of phosphoric chloride, PCl_3 , in admixture with the vapour of phosphorous chloride, PCl_5 . (7) It is evident, from the example of nitric peroxide, that a change of pressure may alter the density and aid decomposition, and therefore identical results are sometimes attained (if the density be variable) by raising t and lowering h ; but if the density does not vary under these variable conditions (at least, not to an observable degree exceeding the limits of experimental error), then this *constant* density indicates the *gaseous* and *invariable* state of a substance. The laws hereafter laid down refer only to such vapour densities. But the majority of volatile substances show such a constant density at a certain distance from their boiling points up to the starting point of decomposition. Thus, the density of aqueous vapour does not vary for t between the ordinary temperature and 1000° (there are no trustworthy determinations beyond this) and for pressures varying from fractions of an atmosphere up to several atmospheres. If, however, the density does vary considerably with a variation of h and t ,

Such an investigation (either direct, or by calculation from the densities and composition) of every chemical reaction, resulting in the forma-

the fact may serve as a guiding string for the investigation of the chemical changes which are undergone by the substance in a state of vapour, or, at least, as an indication of a deviation from the laws of Boyle, Mariotte, and Gay-Lussac (for the expansion of gases from t). In certain cases the separation of one form of deviation from the other may be explained by special hypotheses.

With respect to the means of determining p and v , with a view to finding the vapour density, we may distinguish three chief methods: (*a*) by weight, by ascertaining the




FIG. 52. Apparatus for determining the vapour density by Dumas' method. A small quantity of the liquid whose vapour density is to be determined is placed in the glass globe, and heated in a water or oil bath to a temperature above the boiling point of the liquid. When all the liquid has been converted into vapour and has displaced all the air from the globe, the latter is sealed up and weighed. The capacity of the globe is then measured, and in this manner the volume occupied by a known weight of vapour at a known temperature is determined.




FIG. 53. Deville and Troost's apparatus for determining the vapour densities, according to Dumas' method, of substances which boil at high temperatures. A porcelain globe containing the substance whose vapour density is to be determined is heated in the vapour of mercury (350°), sulphur (410°), cadmium (850°), or zinc (1040°). The globe is sealed up in an oxyhydrogen flame.

weight of a definite volume of vapour; (*b*) by volume, by measuring the volume occupied by the vapour of a definite weight of a substance; and (*c*) by displacement. The last-mentioned is essentially volumetric, because a known weight of a substance is taken, and the volume of the air displaced by the vapour at a given t and h is determined.

The method by weight (*a*) is the most trustworthy and historically important. *Dumas' method* is typical. An ordinary spherical glass or porcelain vessel, like those shown respectively in figs. 52 and 53, is taken, and an excess of the substance to be experimented upon is introduced into it. The vessel is heated to a temperature t higher than the boiling point of the liquid; this gives a vapour which displaces the air, and fills the spherical space. When the air and vapour cease escaping from the sphere, it is fused up or closed by some means; and when cool, the weight of the vapour remaining in the sphere is determined (either by direct weighing of the vessel with the vapour and introducing the necessary corrections for the weight of the air and of the vapour itself, or the weight of the volatilised substance is determined by chemical methods), and the volume of the vapour at t and the barometric pressure h is then calculated.

tion of definite chemical compounds, shows that the volumes of the reacting substances in a gaseous or vaporous state are either equal or are in

The volumetric method, (b) originally employed by Gay-Lussac and then modified by Hofmann and others, is based on the principle that a weighed quantity of the liquid to be experimented with (placed in a small closed vessel, which is sometimes fused up before




FIG. 54.—Hofmann's apparatus for determining vapour densities. The internal tube, about one metre long, which is calibrated and graduated, is filled with mercury and inverted in a mercury bath. A small bottle (depicted in its natural size on the left) containing a weighed quantity of the liquid whose vapour density is to be determined, is introduced into the Torricellian vacuum. Steam, or the vapour of amyl alcohol, &c., is passed through the outer tube, and heats the internal tube to the temperature t , at which the volume of vapour is measured.




FIG. 55.—Victor Meyer's apparatus for determining vapour densities. The tube b is heated in the vapour of a liquid of constant boiling point. A glass tube, containing the liquid to be experimented upon, is caused to fall from d . The air displaced is collected in the cylinder e , in the trough f .

weighing, and which, if quite full of the liquid, breaks when heated in a vacuum) is introduced into a graduated cylinder heated to t , or simply into a Torricellian vacuum, as shown in fig. 54, and the number of volumes occupied by the vapour noted when the space holding it is heated to the desired temperature t .

The method of displacement (c) proposed by Victor Meyer is based on the fact that a

simple multiple proportion.³ This forms the *first law* of those discovered by Gay-Lussac. This law may be formulated as follows: *The amounts of substances entering into chemical reaction, occupy under similar physical conditions, in a gaseous or vaporous state, equal or multiple volumes.* This law not only refers to elements, but also to compounds entering into mutual chemical combination; thus, for example, one volume of ammonia gas combines with one volume of hydrogen chloride. For in the formation of sal-ammoniac, NH_4Cl , there enters into reaction 17 parts by weight of ammonia, NH_3 , which is $8\frac{1}{2}$ times denser than hydrogen, and 36.5 parts by weight of hydrogen chloride, whose vapour density is $18\frac{1}{4}$ times that of hydrogen, as has been proved by direct experiment. By dividing the weights by the respective densities we find that the volume of ammonia, NH_3 , is equal to two, and so also the volume of hydrogen chloride. Hence the volumes of the compounds which here combine together are equal to each other. By taking into consideration that the law of Gay-Lussac holds good, not only for elements, but also for compounds, it should be expressed as follows: *Substances interact with one another in commensurable volumes of their vapours.*⁴

space b is heated to a constant temperature t (by the surrounding vapours of a liquid of constant boiling point), and the air (or other gas enclosed in this space) is allowed to attain this temperature, and when it has done so a glass bulb containing a weighed quantity of the liquid to be experimented with is dropped into the space. The liquid is immediately converted into vapour, and displaces the air into the graduated cylinder c . The amount of this air is calculated from its volume, and consequently the volume at t , and, therefore, also the volume occupied by the vapour, is found. The general arrangement of the apparatus is given in fig. 55.

³ Vapours and gases, as was explained in the second chapter, are subject to the same laws, which are, however, only approximate. It is evident that for the deduction of the laws which will presently be enunciated it is only possible to take into consideration a perfect gaseous state (removed from the liquid state) and chemical invariability in which the *vapour density is constant*—that is, the volume of a given gas or vapour varies like a volume of hydrogen, air, or other gas, with the pressure and temperature.

It is necessary to make this statement in order that it may be clearly seen that the laws of gaseous volumes, presently to be described, are in the most intimate connection with the laws of the variations of volumes with pressure and temperature. And as these latter laws (Chap. II.) are not infallible but only approximately exact, the same, therefore, applies to the laws presently to be described. And as it is possible to find more exact laws (a second approximation) for the variation of v with p and t (for example, Van der Waals' formula, Chap. II. Note 33), so also a more exact expression of the relation between the composition and the density of vapours and gases is also possible. But to prevent any doubt arising at the very beginning as to the breadth and general application of the laws of volumes, it will be sufficient to mention that the density of such gases as oxygen, nitrogen, and carbonic anhydride is already known to *remain constant* (within the limits of experimental error) between the ordinary temperature and a white heat; whilst, judging from what is said in my work on the 'Tension of Gases' (vol. i. p. 9), it may be said that, as regards pressure, the density remains very constant even when the deviations from Mariotte's law are very considerable. However, in this respect the number of data is yet too small for forming an exact conclusion.


⁴ We must recollect that this law is only approximate, like Boyle and Mariotte's law,

The law of combining volumes and the law of multiple proportions were discovered independently of each other—the one in France by Gay-Lussac, the other in England by Dalton, almost simultaneously. In the language of the atomic hypothesis it may be said that atomic quantities of elements occupy equal or multiple volumes.

The first law of Gay-Lussac expresses the relation between the volumes of the component parts of a compound; let us now consider the relation existing between the volumes of the component parts and of the compounds which proceed from them. This may sometimes be determined by direct observation. Thus the volume occupied by water, formed by two volumes of hydrogen and one volume of oxygen, may be determined by the aid of the apparatus shown in fig. 56. The long glass tube is closed at the top and open at the bottom, which is immersed in a cylinder containing mercury. The closed end is furnished with wires like a eudiometer (p. 168). The tube is filled with mercury, and then a certain volume of detonating gas is introduced. This gas is obtained from the decomposition of water, and therefore in every three volumes contains two volumes of hydrogen and one volume of oxygen. The tube is surrounded by a second and wider glass tube, and the vapour of a substance boiling above 100° —that is, whose boiling point is higher than that of water—is passed through the annular space between them. Amyl alcohol, whose boiling point is 132° , may be taken for this purpose. The amyl alcohol is boiled in the vessel to the right hand and its vapour passed between the walls of the two tubes. In the case of amyl alcohol, the outer glass tube would be connected with a condenser to prevent the escape into the air of the unpleasant-smelling vapour. The detonating gas is thus heated up to a temperature of 132° . When its volume becomes constant it is measured, the height of the column of mercury in the tube above the level of the mercury in the cylinder being noted. Let this volume equal v ; it will therefore contain $\frac{1}{3} v$ of oxygen and $\frac{2}{3} v$ of hydrogen. The current of vapour is then stopped, the open end of the tube filled with mercury, and then closed, and the gas exploded; water is formed, which condenses into a liquid. The volume occupied by the vapour of the water formed has now to be determined. For this purpose the vapour of the amyl alcohol is again passed between the tubes, and the whole of the water formed is converted into vapour at the same temperature as that at which the detonating gas was measured, and the cylinder of mercury being raised until the column of mercury in the tube stands at the same height above the surface of the mercury in the cylinder as it did before

and that, therefore, exact expressions may be found for the exceptions which occur to its application.

FIG. 56.—Apparatus for demonstrating the volume occupied by the steam
formed from the explosion of detonating gas.



the explosion, it is found that the volume of the water formed is equal to two-thirds v —that is, it is equal to the volume of the hydrogen contained in the water. Consequently, the volumetric composition of water should be expressed in the following terms: Two volumes of hydrogen combine with one volume of oxygen to form two volumes of aqueous vapour. For substances which are gaseous at the ordinary temperature, this direct method of observation is sometimes very easily conducted; for instance, with ammonia, nitric, and nitrous oxides. Thus to determine the composition by volume of nitrous oxide, the above-described apparatus may be employed. Nitrous oxide is introduced into the tube, and having measured its volume a series of electric sparks are passed through the gas, and it is found that two volumes of nitrous oxide give three volumes of gases—namely, two volumes of nitrogen and one volume of oxygen. Consequently, the composition of nitrous oxide is similar to that of water: two volumes of nitrogen and one volume of oxygen give two volumes of nitrous oxide. By decomposing ammonia it is found to be composed in such a manner that two volumes give one volume of nitrogen and three volumes of hydrogen; also, two volumes of nitric oxide are formed by the union of one volume of oxygen with one volume of nitrogen. The same may naturally be proved by calculation from the vapour densities, as was described above; hence the composition by volume of vapours may be determined in the simplest manner, if their density, composition, and the densities of the component parts are known. Thus, according to Thomsen, the density of NO referred to hydrogen = 15, and it contains 14 parts of nitrogen, and 16 parts of oxygen in 30 parts; hence the volumetric composition is 1 volume of nitrogen and 1 volume of oxygen in 2 volumes of nitric oxide.

Comparisons of various results made by the aid of direct observations or calculation, an example of which has just been cited, led Gay-Lussac to the conclusion that *the volume of a compound in a gaseous or vaporous state is always in simple multiple proportion to the volume of each of the component parts of which it is formed* (and consequently to the sum of the volumes of the elements of which it is formed). This is the *second law of Gay-Lussac*, which indicates the simplicity of the volumetric relations existing for compounds, which is of the same nature as that shown by the elements entering into mutual combination. Hence not only the substances forming a given compound, but also the substances formed, exhibit a simple relation of volume when as vapour or gas.⁵

⁵ This second law of volumes may be considered as a consequence of the first law. The first law requires simple ratios between the volumes of the combining substances A

When a compound is formed from two or more components, there is or is not a contraction ; the volume of the acting substances is in this case either equal to or greater than the volume of the resultant compound. The reverse is naturally observed in the case of decompositions, when from one substance there are produced several of simpler nature. Therefore in the future we shall term *combination* a reaction in which a contraction is observed—that is, a diminution in the volume of the component bodies in a state of vapour or gas ; and we shall term *decomposition* a reaction in which an expansion is produced ; while those reactions in which the volumes in a gaseous or vaporous state remain constant (the volumes being naturally compared at the same temperature and pressure) we shall term reactions of *substitution* or of replacement or of double decomposition. Thus the transition of oxygen into ozone is a reaction of combination, the formation of nitrous oxide from oxygen and nitrogen will also be a combination, the formation of nitric oxide from the same will be a reaction of substitution, the action of oxygen on nitric oxide a combination, and so on.

The degree of contraction proceeding in the formation of chemical compounds not unfrequently leads to the possibility of distinguishing the degree of change which takes place in the chemical character of the components when combined. In those cases in which a contraction takes place, the properties of the resultant compound are very different from the properties of the substances of which it is composed. Hence ammonia bears no resemblance in its physical or chemical properties to the elements from which it is derived ; a contraction takes place in a state of vapour, and consequently approachment of parts—the distance between the atoms is diminished, and from gaseous substances there is formed a liquid substance, or at least one which is easily liquefied. For this reason nitrous oxide formed by the condensation of two permanent gases is a substance which is somewhat easily converted into a liquid ; again nitric acid, which is formed from elements which are permanent gases, is a liquid, whilst, on the contrary, nitric oxide, which is formed without contraction and is decomposed without expansion, remains a gas which is as difficult to liquefy as nitrogen and oxygen. In order to obtain a still more com-

and *B*. A substance *AB* is produced by their combination. It may, according to the law of multiple proportion, combine not only with substances *C*, *D*, &c., but also with *A* and with *B*. In this new combination the volume of *AB*, combining with the volume of *A*, should be in simple multiple proportion with the volume of *A* ; hence the volume of the compound *AB* is in simple proportion to the volume of its component parts. Therefore, only one law of volumes need be accepted. We shall afterwards see that the third law of volumes may also embrace in itself the two first laws.

plete idea of the dependence of the properties of a compound on the properties of the component substances, it is further necessary to know the quantity of heat which is developed in the formation of the compound. If this quantity be large—as, for example in the formation of water—then the amount of energy in the resultant compound will be considerably less than the energy of the elements entering into its composition ; whilst, on the contrary, if the amount of heat evolved in the formation of a compound be small, or if there even be an absorption of heat, as in the formation of nitrous oxide, then the energy of the elements is not destroyed or is only altered to a slight extent : hence, notwithstanding the contraction (compression) involved in its formation, nitrous oxide supports combustion.

The preceding laws were deduced from purely experimental and empirical data, and as such evoke further consequences, as the law of multiple proportions evoked the atomic theory and the law of equivalents (Chapter IV.). In point of view of the atomic conception of the constitution of substances, the question naturally arises as to what then are the relative volumes proper to those physically-indivisible molecules which chemically react on each other and consist of the atoms of elements. The simplest possible hypothesis in this respect would be that the volumes of the molecules of substances are equal ; or, what is the same thing, to suppose that equal volumes of vapours and gases contain an equal number of molecules. This proposition was first enunciated by the Italian savant, *Avogadro*, in 1810. It was also admitted by the French physico-mathematician, *Ampère* (1815), for the sake of simplifying all kinds of physico-mathematical conceptions respecting gases. But *Avogadro* and *Ampère's* propositions were not generally received in science until *Gerhardt* in the forties had applied them to the generalisation of chemical reactions, and had demonstrated by aid of a series of phenomena that the reactions of substances are actually accomplished with the greatest simplicity, and before all, that such reactions take place between those quantities of substances which occupy equal volumes, and until he had stated the hypothesis in an exact manner and deduced the consequences that necessarily flow from it. Following *Gerhardt*, *Clausius*, in the fifties, placed the hypothesis of the equality of the number of molecules in equal volumes of gases and vapours on the basis of the kinetic theory of gases. Since then the hypothesis of *Avogadro* and *Gerhardt* has become the basis of contemporary physical, mechanical, and chemical conceptions ; the consequences arising from it have often been subject to doubt, but in the end have been verified by the most diverse methods, and now, when all efforts to refute those consequences have proved

fruitless, the hypothesis must be considered as verified,⁶ and the *law of Avogadro-Gerhardt* must be spoken of as fundamental, and as of great importance for the comprehension of the phenomena of nature. The law may now be formulated in two aspects. In the first place, from a physical aspect: *equal volumes of gases* (or vapours) at equal temperatures and pressures *contain an equal number of molecules* or of such quantities of matter which are neither mechanically nor physically divisible—previous to chemical change. In the second place, from a chemical aspect, the same law may be expressed thus: *the quantities of substances entering into chemical reactions occupy, in a state of vapour, equal volumes*. For our purpose, the chemical aspect is the most important, and therefore, before developing the law and its consequences, we will stay to consider the chemical phenomena from which the law is deduced or by which it may be explained.

When two isolated substances interact with each other directly and easily—as, for instance, an alkali on an acid—then it is found that the reaction is accomplished between quantities which in a gaseous state (at equal temperatures and pressures) occupy equal volumes. Thus, ammonia, NH_3 , reacts directly with hydrochloric acid, HCl , forming sal-ammoniac, NH_4Cl , and in this case the NH_3 , or 17 parts by weight of ammonia, occupy the same volume as the 36.5 parts by weight of hydrochloric acid.⁷ Ethylene, C_2H_4 , combines with chlorine, Cl_2 , in only one proportion, forming ethylene dichloride, $\text{C}_2\text{H}_4\text{Cl}_2$, and this combination proceeds directly and with great facility; the reacting quantities occupying equal volumes. Chlorine reacts with hydrogen in only one proportion, forming hydrochloric acid, HCl , and in this case

⁶ It must not be forgotten that Newton's law of gravity, or of the unity of the forces causing a body to fall to the earth, and the planets to be attracted to and revolve round the sun, was first a hypothesis, but it became a trustworthy, perfect theory, and acquired the qualities of a fundamental law owing to the concord between its consequences and reality. All laws, all theories of natural phenomena, are first hypotheses. Some are rapidly established by their exact consequences, which agree with facts; others only take root by slow degrees.

⁷ This is not only seen from the above calculations, but may be proved by experiment. A glass tube, divided in the middle by a stop-cock, is taken, and one portion filled with dry hydrogen chloride (the dryness of the gases is strictly necessary, because ammonia and hydrogen chloride are both very soluble in water, and hence a small trace of water may contain a large amount of these gases in solution) and the other with dry ammonia, under the atmospheric pressure. One orifice (for instance, of that portion which contains the ammonia) is firmly closed, and the other is immersed under mercury, and the cock is then opened. Solid sal-ammoniac is formed, but if the volume of one gas be greater than that of the other, some of the first gas will remain. By immersing the tube in the mercury in order that the internal pressure shall equal the atmospheric pressure, it may easily be shown that the volume of the remaining gas is equal to the difference between the volumes of the two portions of the tube, and that the remaining gas is that whose volume was the greater.

equal volumes interact with each other. If an equality of volumes is observed in cases of combination, it should be all the more frequently encountered in cases of decomposition taking place in substances which split up into two others. Indeed, acetic acid breaks up into marsh gas, CH_4 , and carbonic anhydride, CO_2 , and in the proportions in which they are formed from acetic acid they occupy equal volumes. Also from phthalic acid, $\text{C}_8\text{H}_6\text{O}_4$, there may be obtained benzoic acid, $\text{C}_7\text{H}_6\text{O}_2$, and carbonic anhydride, CO_2 , and as all the elements of phthalic acid enter into the composition of these substances, therefore, although they cannot re-form it by their direct action on each other (the reaction is not reversible), still they form the direct products of its decomposition, and they occupy equal volumes. But benzoic acid, $\text{C}_7\text{H}_6\text{O}_2$, is also composed of benzene, C_6H_6 , and carbonic anhydride, CO_2 , which also occupy equal volumes.⁸ There is an immense number of similar examples among those organic substances to whose study Gerhardt consecrated his whole life and work, and he did not allow such facts as these to escape his attention. Still more frequently in the phenomena of substitution, when two substances act on one another, and two are produced without a change of volumes—that is, when the first definition given (p. 4) corresponds with that given on p. 301—it is found that the two substances acting on each other occupy equal volumes as well as each of the two resultant substances. Thus, in general, reactions of substitution take place between volatile acids, HX , and volatile alcohols, $\text{R}(\text{OH})$, with the formation of ethereal salts, RX , and water, $\text{H}(\text{OH})$, and the volume of the vapour of the reacting quantities, HX , $\text{R}(\text{OH})$, and RX , is the same as that for water $\text{H}(\text{OH})$, whose weight, corresponding with the formula, 18, occupies 2 volumes, if 1 part by weight of hydrogen occupy 1 volume and the density of aqueous vapour referred to hydrogen is 9. Such general examples, of which there are many,⁹ show that the reaction of equal volumes forms a chemical phenomenon of frequent occurrence, indicating the necessity of acknowledging the law of Avogadro-Gerhardt.

⁸ Let us demonstrate this by figures. From 122 grams of benzoic acid there is obtained (a) 78 grams of benzene, whose density referred to hydrogen = 39, hence the relative volume = 2, and (b) 44 grams of carbonic anhydride, whose density = 22, and hence the volume = 2. It is the same in other cases.

⁹ A large number of such generalised reactions, showing reaction by equal volumes, occur in the case of the hydrocarbon derivatives, because many of these compounds are volatile. The reactions of alkalis on acids, or anhydrides on water, &c., which are so frequent between mineral substances, present but few such examples, because many of these substances are not volatile and their vapour densities are unknown. But essentially, the same is seen in these cases also; for instance, sulphuric acid, H_2SO_4 , breaks up into the anhydride, SO_3 , and water, H_2O , which exhibit an equality

But the question arises : What is the relation of volumes if the reaction of two substances takes place in different proportions, according to the law of multiple proportions ? A definite answer can only be given in cases which have been very thoroughly studied. Thus chlorine, in acting on marsh gas, CH_4 , forms four compounds, CH_3Cl , CH_2Cl_2 , CHCl_3 , and CCl_4 , and it may be established by direct experiment that the substance CH_3Cl (methylic chloride) precedes the remainder, and that the latter proceed from it by the further direct action of chlorine. And this substance, CH_3Cl , is formed by the reaction of equal volumes of marsh gas, CH_4 , and chlorine, Cl_2 , according to the equation $\text{CH}_4 + \text{Cl}_2 = \text{CH}_3\text{Cl} + \text{HCl}$. A great number of similar cases are met with amongst organic that is, carbon—compounds. Gerhardt was led to the discovery of his law by having investigated many such reactions, and from observing that in them the reaction of equal volumes precedes all others.

But if nitrogen or hydrogen give several compounds with oxygen, the above proposed question cannot be answered with complete clearness, because the consecutive formation of one degree of combination after the other cannot be so strictly defined. It may be supposed, but neither affirmed with assurance nor confirmed by experiment, that nitrogen and oxygen first give nitric oxide, NO , and only afterwards the brown vapours N_2O_3 and NO_2 . Such a sequence in the combination of nitrogen with oxygen can only be supposed on the basis of the fact that NO forms N_2O_3 and NO_2 directly with oxygen. If it be admitted that NO (and not N_2O or NO_2) be first formed, then this instance would also confirm the law of Avogadro-Gerhardt, because nitric oxide contains equal volumes of nitrogen and oxygen. So, also, it may be admitted that, in the combination of hydrogen with oxygen, hydrogen peroxide is first formed (equal volumes of hydrogen and oxygen), which is decomposed by the heat evolved into water and oxygen, all the more as this explains the presence of traces of hydrogen peroxide (Chap. IV.) in almost all cases of the combustion or oxidation of hydrogenous substances ; for it cannot be supposed that water is first formed and then the peroxide of hydrogen, because up to now such a reaction has not been accomplished, whilst the formation of H_2O from H_2O_2 is very easily reproduced.¹⁰

of volumes. Let us take another example where three substances combine in equal volumes : carbonic anhydride, CO_2 , ammonia, NH_3 , and water, H_2O (the volumes of all are equal to 2), form acid ammonium carbonate, $(\text{NH}_4)\text{HCO}_3$.

¹⁰ This opinion as to the primary origin of hydrogen peroxide and of the formation of water by means of its decomposition, which was always held by me (in the first editions of this work), has in latter days become more generally accepted, thanks more especially to the work of Traube. Probably, it explains most simply the necessity for

Thus a whole series of phenomena show that the chemical reaction of substances actually takes place, as a rule, between equal volumes, but this does not remove the possibility of the frequent reaction of unequal volumes, although, in this case, it is often possible to discover a preceding reaction between equal volumes.¹¹

the presence of traces of water in many reactions, as, for instance, in the explosion of carbonic oxide with oxygen, and perhaps the very theory of the explosion of detonating gas and of the combustion of hydrogen gain in clearness and truth if we take into consideration the preliminary formation of hydrogen peroxide and its decomposition. We may here point out the fact that Ettingen (at Dorpat, 1888) observed the existence of currents and waves in the explosion of detonating gas by taking photographs, which showed the periods of combustion and the waves of explosion, which should be taken into consideration in the theory of this subject. As the formation of H_2O_2 from O_2 and H_2 corresponds with a less amount of heat than the formation of water from H_2 and O , it may be that the temperature of the flame of detonating gas depends on the pre-formation of hydrogen peroxide.

¹¹ The possibility of reactions between unequal volumes, notwithstanding the general application of the law of Avogadro-Gerhardt, may, in addition to what has been said above, depend on the fact that the participating substances, at the moment of reaction, undergo a preliminary modification, decomposition, isomeric (polymeric) transformation, &c. Thus, if NO_2 seems to proceed from N_2O_3 , if O_2 is formed from O_3 , and the converse, then it cannot be denied that the production of molecules containing only one atom is also possible—for instance, of oxygen—as also of higher polymeric forms—as the molecule N from N_2 , or H_3 from H_2 . In this manner it is naturally possible, by means of a series of hypotheses, to explain the cases of the formation of ammonia, NH_3 from 3 vols. of hydrogen and 1 vol. of nitrogen. But it must be observed that perhaps our information in similar instances is, as yet, far from being complete. If the existence of hydrazine or diamide N_2H_4 (Chap. VI. Note 6) be verified, then, perhaps, an amide N_2H_2 will be discovered [this substance is now stated to have been obtained] in which 2 vols. of hydrogen are combined with 2 vols. of nitrogen—that is, the reaction is accomplished between equal volumes. If it be shown that diamide gives nitrogen and ammonia ($3\text{N}_2\text{H}_4 = \text{N}_2 + 4\text{NH}_3$) under the action of sparks, heat, or the silent discharge, &c., then it will be possible to admit that it is formed before ammonia. And, perhaps, the still less stable amide N_2H_2 , which may also decompose with the formation of ammonia, is produced before the amide N_2H_4 .

I mention this to show that the fact of there being apparent exceptions to the law of reactions between equal volumes does not prove the impossibility of their being included under the law on further study of the subject. Having admitted a certain law or hypothesis, then consequences must be deduced from it, and if by their means a clearness and harmony is arrived at—and all the more, if by their means that which could not otherwise be known can be recognised—then the consequences verify the hypothesis. This was the case with the law now under discussion. The simplicity alone of the deduction of the weight proper to the atoms of the elements, or the fact alone that having admitted the law it follows, as will afterwards be shown, that the *vis viva* of the molecules of all gases is a constant quantity, is alone a sufficient reason for retaining the hypothesis if not for believing in it as a fact beyond doubt. And as by the acceptance of the law it became possible to foretell even the properties and atomic weights of elements which had not yet been discovered, and as these predictions afterwards proved to be in agreement with the actual facts, it is evident that the law of Avogadro-Gerhardt penetrates deeply into the nature of the chemical relation of substances. This being granted, it is possible at the present time to expound and deduce the truth under consideration in many ways, and in every case it, like all that is highest in science (for example, the law of the indestructibility of matter, the law of the conservation of energy,

The law of Avogadro-Gerhardt may also be easily expressed in an algebraical form. If the weight of a molecule, or of that quantity of a substance which enters into chemical reaction, and occupies in a state of vapour, according to the law, a volume equal to the molecules of other bodies, be indicated by the letters M_1, M_2, \dots or, in general, M , and if the letters D_1, D_2, \dots , or, in general, D , stand for the density or weight of a given volume of the gases or vapours of the corresponding substances under certain definite conditions of temperature and pressure, then the law requires that

$$\frac{M_1}{D_1} = \frac{M_2}{D_2} \dots \dots \dots = \frac{M}{D} = C$$

where C is a certain constant. This expression directly shows that the volumes corresponding with the weights M_1, M_2, \dots, M , are equal to a certain constant, because the volume is proportional to the weight and inversely proportional to the density. The magnitude of C is naturally conditioned by and dependent on the units taken for the expression of the weights of the molecules and the densities. The weights of the molecules (equal to the sum of the atomic weights of the elements forming a given substance) are usually expressed by taking the weight of an atom of hydrogen as unity, and hydrogen is now also chosen as the unit for the expression of the densities of gases and vapours; it is therefore only needful to find the magnitude of the constant for any one compound, as it will be the same for all others. Let us take water. Its reacting mass is expressed (conditionally) by the formula or molecule H_2O , for which $M=18$, if $H=1$, as we already know from the composition of water. Its vapour density, or D , compared to hydrogen=9, and consequently for water $C=2$, and therefore and in general for the molecules of all substance $\frac{M}{D}=2$.

Consequently, the weight of a molecule is equal to twice its vapour density expressed in relation to hydrogen, and conversely *the density of a gas is equal to half the molecular weight referred to hydrogen*.

The truth of this may be seen from an infinitely large number of and the law of gravity, &c.), proves to be not an empirical deduction from direct observation and experiment, not a direct result of analysis, but a creation, a penetration of an inquiring mind, which is guided and directed only by experiment and observation—a synthesis to which the exact sciences are capable to an equal extent with the highest forms of art. Without such a synthetical process of reasoning, science would only be a collection of the results of arduous labour, and would not be distinguished by that force with which it is really endowed when once it succeeds in attaining a synthesis, or concordance of outward form with the inner nature of things, without departing from the analysis of individual parts; in short, when it discovers by means of outward forms, which are apparent to the sense of touch, to observation, and to the mind, the internal signification of things—discovering simplicity in complexity and uniformity in diversity.

observed vapour densities by comparing them with the results obtained by calculation. As an illustration, we may point out that for ammonia, NH_3 , the weight of the molecule or quantity of the reacting substance, as well as the composition and weight corresponding with the formula, is expressed by the figures $14 + 3 = 17$. Consequently, $M = 17$. Hence, according to the law, $D = 8.5$. And this result is also obtained by experiment. The density, according to the formula and experiment, of nitrous oxide, N_2O , is 22, of nitric acid 15, and of nitric peroxide 23. In the case of nitrous anhydride, N_2O_3 , as a substance which dissociates into $\text{NO} + \text{NO}_2$, the density should vary between 38 (so long as the N_2O_3 remains unchanged), and 19 (when $\text{NO} + \text{NO}_2$ is obtained). There are no figures of constant density for H_2O_2 , NHO_3 , N_2O_4 , and many similar compounds which are either wholly or partially decomposed in passing into vapour. Salts and similar substances either have no vapour density because they do not pass into vapour (for instance, potassium nitrate, KNO_3) without decomposition, or if they pass into vapour without decomposing, their vapour density is observed with difficulty only at very high temperatures. The practical determination of the vapour density at these high temperatures (for example, for sodium chloride, ferrous chloride, stannous chloride, &c.), requires special methods which have been worked out by Sainte-Claire, Deville, Crafts, Nilson and Pettersson, Meyer, Scott, and others. Having overcome the difficulties of experiment, it is found that the law of Avogadro-Gerhardt holds good for such salts as potassium iodide, beryllium chloride, aluminium chloride, ferrous chloride, &c.—that is, the density obtained by experiment proves to be equal to half the molecular weight—naturally within the limits of experimental error or of possible deviation from the law.

Gerhardt deduced his law from a great number of examples of volatile carbon compounds. We shall become acquainted with certain of them in the following chapters; their entire study, from the complexity of the subject, and from long-established custom, forms the subject of a special branch of chemistry, termed 'organic' chemistry. With all these substances the observed and calculated densities are very similar.

When the consequences of a law are verified by a great number of observations, it should be considered as confirmed by experiment. But this does not exclude the possibility of *apparent* deviations. They may evidently be of two kinds: the fraction $\frac{M}{D}$ may be found to be either greater or less than 2—that is, the calculated density may be either greater or less than the observed density. When the difference between the results of experiment and calculation fall within the possible errors

of experiment (for example, equal to hundredths of the density), or within a possible error owing to the laws of gases having an only approximate significance (as is seen from the deviations, for instance, from the law of Boyle and Mariotte), then the fraction $\frac{M}{D}$ proves but slightly different from 2 (between 1.9 and 2.2), and such cases as these may be classed among those which ought to be expected from the nature of the subject. It is a different matter if the quotient of $\frac{M}{D}$ be several times, and in general a multiple, *greater* or less than 2. The application of the law must then be explained or it must be laid aside, because the laws of nature admit of no exceptions. We will therefore take two such cases, and first one in which *the quotient $\frac{M}{D}$ is greater than 2, or the density obtained by experiment is less than is in accordance with the law.*

It must be admitted as a consequence of the law of Avogadro-Gerhardt, that there is a decomposition in those cases where the volume of the vapour corresponding with the weight of the amount of a substance entering into reaction is greater than the volume of two parts by weight of hydrogen. Suppose the density of the vapour of water to be determined at a temperature above that at which it is decomposed, then, if not all, at all events a large portion of the water will be decomposed into hydrogen and oxygen. The density of such a mixture of gases, or of detonating gas, will be less than that of aqueous vapour; it will be equal to 6 (compared with hydrogen), because 1 volume of oxygen weighs 16, and 2 volumes of hydrogen 2; and, consequently, 3 volumes of detonating gas weigh 18, and 1 volume 6, whilst the density of aqueous vapour = 9. Hence, if the density of aqueous vapour be determined after its decomposition, the quotient $\frac{M}{D}$ would be found to be 3 and not 2. This phenomenon might be considered as a deviation from Gerhardt's law, but this would not be correct, because it may be shown by means of diffusion through porous substances, as described in Chap. II., that water is decomposed at such high temperatures. In the case of water itself there can naturally be no doubt, because its vapour density agrees with the law at all temperatures at which it has been determined.¹² But there are

¹² As the density of aqueous vapour remains constant within the limits of experimental accuracy, even at 1000°, when dissociation has certainly commenced, it must be admitted that only a very small amount of water is decomposed at these temperatures. If even 10 p.c. of water were decomposed, then the density would be 8.57 and the quotient $M/D = 2.1$, but at the high temperatures here concerned the error of experiment is not greater than the difference of this quantity. And probably at 1000° the dissocia-

many substances which decompose with great ease directly they are volatilised, and which only exist as solids or liquids, but not in a state of vapour. There are, for example, many salts of this kind, besides all definite solutions having a constant boiling point, all the compounds of ammonia—for example, all ammonium salts—&c. Their vapour densities, determined by Bineau, Deville, and others, show that they do not agree with Gerhardt's law. Thus, the vapour density of sal-ammoniac, NH_4Cl , is nearly 14 (compared with hydrogen), whilst its molecular weight is not less than 53·5, whence the vapour density should be nearly 27 according to the law. The molecule of sal-ammoniac cannot be less than NH_4Cl , because it is formed from the molecules NH_3 and HCl , and contains single atoms of nitrogen and chlorine, and therefore it cannot be divided; it, further, never enters into reactions with the molecules of other substances (for instance, potassium hydroxide or nitric acid) in quantities of less than 53·5 parts by weight, &c. The calculated density (27) is here double the observed density (about 14), hence $\frac{M}{D} = 4$ and not 2. For this

reason the vapour density of sal-ammoniac for a long time served as an argument for doubting the truth of the law. But it proved otherwise, after the matter had been fully studied. The low density depends on the decomposition of sal-ammoniac, on volatilising, into ammonia and hydrogen chloride. The observed density is not that of sal-ammoniac, but of a mixture of NH_3 and HCl , which should be nearly 14, because the density of $\text{NH}_3 = 8\cdot5$ and of $\text{HCl} = 18\cdot5$, and therefore the density of their mixture (in equal volumes) should be 13·3.¹³ The actual decomposition of the vapours of sal-ammoniac was demonstrated by Pebal and Than by the same method as the decomposition of water, by passing the vapour of sal-ammoniac through a porous substance. The experiment demonstrating the decomposition during volatilisation of sal-ammoniac may be made very easily, and is a very instructive point in the history of the law of Avogadro-Gerhardt, because without its aid it would never have been imagined that sal-ammoniac decomposed in volatilising, as this decomposition bears all the signs of simple sublimation; consequently, the knowledge of the decomposition itself was forestalled by the law. The whole force

tion is far from being equal to 10 p.c. *Therefore, the variation in the vapour density of water cannot be the means of ascertaining the amount of its dissociation.*

¹³ This explanation of the vapour density of sal-ammoniac, sulphuric acid, and similar substances which decompose in being distilled was the most natural to resort to as soon as the application of the law of Avogadro-Gerhardt to chemical relations was begun; it was, for instance, given in my work on *Specific volumes*, 1856, p. 99. The formula, $M/D = 2$, which later was applied by many other investigators, had already been applied in that work.

and visible use of the discovery of the laws of nature lies in, and is expressed by, the fact that they enable the unknown to be foretold, and the unobserved to be foreseen. The arrangement of the experiment is based on the following reasoning.¹⁴ According to the law and to experiment the density of ammonia, NH_3 , is $8\frac{1}{2}$, and of hydrochloric acid, HCl , $18\frac{1}{2}$, if the density of hydrogen = 1. Consequently, in a mixture of NH_3 and HCl , the ammonia will penetrate much more rapidly through a porous mass, or a fine orifice, than the heavier hydrochloric acid, just as in a former experiment the hydrogen penetrated more rapidly than oxygen. Therefore, if the vapour of sal-ammoniac comes into contact with a porous mass, the ammonia will pass through it in greater quantities than the hydrochloric acid, and this excess of ammonia may be discovered by means of moist red litmus paper, which should be turned blue. If the vapour of sal-ammoniac were not decomposed, it would pass through the porous mass as a whole, and the colour of the litmus paper would not be altered, because sal-ammoniac is a neutral salt. Thus, by testing with litmus the substance passing through the porous mass, it may be decided whether the sal-ammoniac is decomposed or not when passing into vapour. Sal-ammoniac volatilises at so moderate a temperature that the experiment may be conducted in a glass tube heated by means of a lamp, an asbestos plug being placed in the central portion of a glass tube.¹⁵ The asbestos forms a porous mass, which is not changed at a high temperature. A piece of dry sal-ammoniac is placed at one side of the asbestos plug, and is heated by a Bunsen's burner. The vapours formed are driven by a current of air forced from a gasometer or bag through two tubes containing pieces of moist litmus paper, one blue and one red paper in each. If the sal-ammoniac be heated, then the ammonia appears on the opposite side of the asbestos plug, and the corresponding litmus turns blue. And as an excess of hydrochloric acid remains on the side where the sal-ammoniac is heated, therefore it turns the litmus at that end red. This proves that the sal-ammoniac, when converted into vapour, splits up into ammonia and hydrochloric acid, and at the same time gives an instance of the possibility of correctly conjecturing a fact on the basis of the law of Avogadro-Gerhardt.

So also the fact of a decomposition may be proved in the other instances where $\frac{M}{D}$ proved greater than 2, and hence the apparent

¹⁴ The beginner must remember that an experiment and the mode in which it is carried out must be determined by the principle or fact which it is intended to illustrate, and not *vice versâ* as some suppose. The idea which determines the necessity of an experiment is the chief consideration.

¹⁵ It is important that the tubes, asbestos, and sal-ammoniac should be dry, as otherwise the moisture retains the ammonia and hydrogen chloride.

deviations appear in reality as an excellent proof of the general application and significance of the law of Avogadro-Gerhardt.

In those cases where the quotient $\frac{M}{D}$ proves to be *less* than 2, or the observed density *greater* than that calculated by a multiple number of times, the matter is evidently more simple, and the fact observed only indicates that the weight of the molecule is as many times greater, as that taken as the quotient obtained is less than 2. So, for instance, in the case of ethylene, whose composition is expressed by CH_2 , the density was found by experiment to be 14, and in the case of amylene, whose composition is also CH_2 , the density proved to be 35, and consequently the quotient for ethylene=1, and for amylene= $\frac{2}{5}$. If the molecular weight of ethylene be taken, not as 14, as might be imagined from its composition, but as twice as great—namely, as 28—and for amylene as five times greater—that is as 70—then the molecular composition of the first will be C_2H_4 , and of the second C_5H_{10} , and for both of them $\frac{M}{D}$ will be equal to 2. This application of the law, which at first sight may appear perfectly arbitrary, is nevertheless strictly correct, because the amount of ethylene which reacts—for example, with sulphuric and other acids—is not equal to 14, but to 28 parts by weight. Thus with H_2SO_4 , Br_2 , or HI , &c., ethylene combines in a quantity C_2H_4 , and amylene in a quantity C_5H_{10} , and not CH_2 . On the other hand, ethylene is a gas which liquefies with difficulty (absolute boiling point= $+10^\circ$), whilst amylene is a liquid boiling at 35° (absolute boiling point= $+192^\circ$), and by admitting the greater density of the molecules of amylene ($M=70$) its difference from the lighter molecules of ethylene ($M=28$) becomes clear. Thus, the smaller quotient $\frac{M}{D}$ is an indication of *polymerisation*, as the larger quotient is of decomposition. The difference between the densities of oxygen and ozone (Chap. IV.) is a case in point.

On turning to the elements, it is found in certain cases, especially with metals—for instance, mercury, zinc, and cadmium—that that weight of the atoms which must be acknowledged in their compounds (of which mention will be afterwards made) appears to be also the molecular weight. Thus, the atomic weight of mercury must be taken as=200, but the vapour density=100, and the quotient=2. Consequently, the *molecule of mercury contains one atom*, Hg. It is the same with sodium, cadmium, and zinc. This is the simplest possible molecule, which necessarily is only possible in the case of elements, as the molecule of a compound must contain at least two atoms. However, the

molecules of many of the elements prove to be complex—for instance, the weight of an atom of oxygen=16, and its density=16, so that its molecule must contain two atoms O_2 , which might already be concluded by comparing its density with that of ozone, whose molecule contains O_3 (Chap. IV.). So also, the molecule of hydrogen equals H_2 , of chlorine Cl_2 , of nitrogen N_2 , &c. If chlorine react with hydrogen, the volume remains unaltered after the formation of hydrochloric acid, $H_2 + Cl_2 = HCl + HCl$. It is a case of substitution between the one and the other, and, therefore, the volumes remain constant. There are elements whose molecules are much more complex—for instance, sulphur, S_8 —although by heating the density is reduced to a third, and S_2 is formed. Judging from the vapour density of phosphorus ($D=62$) the molecule contains four atoms P_4 . Hence, many elements, when polymerised, appear in molecules which are more complex than the simplest possible. In carbon, as we shall afterwards find, a very complex molecule must be admitted, as otherwise its nonvolatility and other properties cannot be understood. And if compounds are decomposed by a more or less powerful heat, and if polymeric substances are depolymerised (that is, the weight of the molecule diminishes) by a rise of temperature as N_2O_4 passes into NO_2 , or ozone, O_3 , into ordinary oxygen, O_2 , then we might expect to find the splitting-up of the complex molecules of elements into the simplest molecule containing a single atom only—that is to say, if O_2 be obtained from O_3 , then the formation of O might also be looked for. The likelihood of such a proposition is indicated by the vapour of iodine. Its normal density=127 (Dumas, Deville, and others), which corresponds with the molecule I_2 . At temperatures above 800° (up to which the density remains almost constant), this density distinctly decreases, as is seen from the verified results obtained by Victor Meyer, Crafts, and Troost. At the ordinary pressure and 1000° it is about 100, at 1250° about 80, at 1400° about 75, and it apparently strives to reduce itself to one-half—that is, to 63. Under a reduced pressure this splitting-up, or depolymerisation, of iodine vapour actually reaches a density¹⁶ of 66, as Crafts demonstrated by reducing the pressure to 100 mm. and raising the temperature to 1500° . From this it may be concluded that at high temperatures and low pressures the molecule I_2 gradually passes into molecule I containing one atom like mercury, and that something similar occurs with other elements at a considerable rise of temperature, which tends to bring about

¹⁶ Just as we saw (Chap. VI. Note 46) an increase of the dissociation of N_2O_4 and the formation of a large proportion of NO_2 , with a decrease of pressure. The splitting-up of I_2 into $I + I$ is a similar dissociation.

the disunion of compounds and the decomposition of complex molecules.¹⁷

Besides these cases of apparent discrepancy from the law of Avogadro-Gerhardt there is yet a third, which is the last, and one which is very instructive. In the investigation of separate substances they have to be isolated in the purest possible form, and their chemical and physical properties, and among them the vapour density, then determined. If it be normal—that is, if $D=M/2$ —it is a proof of the purity of the substance and of its freedom from all impurities. If it be abnormal—that is, if D be not equal to $M/2$ —then for those who do not believe in the law it appears as a new argument against it and nothing more; but to those who have already grasped the important significance of the law it becomes clear that there is some error in the observation, or that the density was determined under conditions in which the vapour does not follow the laws of Boyle or Gay-Lussac, or else that the substance has not been sufficiently purified, and contains impurities, &c. The law of Avogadro-Gerhardt then appears as a convincing evidence of the necessity of a fresh and more exact research. And as yet the causes of error have always been found. There are not a few examples in point in the recent history of chemistry. We will cite one instance. In the case of pyrosulphuryl chloride, $S_2O_5Cl_2$, $M=215$, and consequently D should $=107.5$, instead of which Ogier and others

¹⁷ Although at first there appeared to be a similar phenomenon in the case of chlorine, it was afterwards proved that if there is a decrease of density it is only a small one. In the case of bromine it is not much greater, and is far from being equal to that for iodine.

As we in general very often involuntarily confuse chemical processes with physical, it may be that a physical process of change in the coefficient of expansion with a change of temperature and molecular weight participates, if not wholly, at all events partially, in the matter of the decrease of the density of chlorine, bromine, and iodine. Thus, I have remarked (*Comptes Rendus*, 1876) that the coefficient of expansion of gases increases with their molecular weight, and (Chap. II. Note 26) the results of direct experiment show the coefficient of expansion of hydrobromic acid ($M=81$) to be 0.00386 instead of 0.00367 for hydrogen ($M=2$). Therefore, in the case of the vapour of iodine ($M=254$) a very large coefficient of expansion is to be expected, and from this cause alone the density would fall. As the molecule of chlorine Cl_2 is lighter ($=71$) than that of bromine ($=160$), which is lighter than that of iodine ($=254$), therefore the order in which the decomposability of the vapours of these haloids is observed corresponds with the expected rise in the coefficient of expansion. Taking the coefficient of expansion of iodine vapour as 0.004, then at 1000° its density would already be 116. Therefore it may be that the dissociation of iodine is only an apparent phenomenon. However, on the other hand, the heavy vapours of mercury ($M=200$, $D=100$) scarcely decrease in density at a temperature of 1500° ($D=98$, according to Victor Meyer); but it must not be forgotten that the molecule of mercury contains only one atom, whilst that of iodine contains two, which would signify much. Questions of this kind which are difficult to decide by experimental means (especially the accurate determination of t) must remain long without being definitely explained by reason of the difficulty, and sometimes impossibility, of separating physical from chemical changes.

obtained 53.8—that is, a density half as great; and further, Ogier (1882) demonstrated clearly that the substance is not dissociated by distillation into SO_3 and SO_2Cl_2 , or any other two products, and thus the abnormal density of $\text{S}_2\text{O}_5\text{Cl}_2$ remained unexplained until D. P. Kononoff (1885) showed that the previous investigators were working with a mixture (containing SO_3HCl), and that pyrosulphuryl chloride has a normal density of approximately 107. Had not the law of Avogadro-Gerhardt served as a guide, the impure liquid would have still passed as pure; all the more as the determination of the amount of chlorine could not aid in the discovery of the impurity. Thus, by following a true law of nature we are aided in the attainment of true deductions.

All cases which have been studied confirm the law of Avogadro-Gerhardt, and as by it a deduction is obtained, from the determination of the vapour density (a purely physical property), as to the size of the molecule or quantity of a substance entering into chemical reaction, therefore, this law links together the two provinces of learning—physics and chemistry—in the most powerful manner. Besides which, the law of Avogadro-Gerhardt places the conceptions of *molecules* and *atoms* on a firm foundation, which was previously wanting. Although since the days of Dalton it had become evident that it was necessary to admit the existence of the atom (the chemical individual indivisible by chemical or other forces) of elements, and the groups of atoms or molecules of compounds indivisible by mechanical and physical forces; still the relative magnitude of the molecule and atom was not defined with sufficient clearness. So, for instance, the atomic weight of oxygen might be taken as 8 or 16, or any multiple of these numbers, and nothing indicated a means for the acceptation of one or another of these magnitudes;¹⁸ whilst as regards the weight of the molecules of elements and compounds there was no trustworthy conception whatever.

¹⁸ And so it was in the fifties. Some took $\text{O}=8$, others $\text{O}=16$. Water in the first case would be HO and hydrogen peroxide HO_2 , and in the second case, as is now generally accepted, water H_2O and hydrogen peroxide H_2O_2 or HO . Discussion and confusion were reigning. In 1860 the chemists of the whole world met at Carlsruhe for the purpose of arriving at some agreement and uniformity of opinion. I was present at this Congress, and well remember how great was the difference of opinion, and how a conditional agreement was defended with the greatest acumen by the ranks of science, and with what warmth the followers of Gerhardt, at whose head stood the Italian professor, Canizzaro, followed up the consequences of the law of Avogadro. In the reign of scientific freedom (without which science would make no progress, and would remain petrified as in the middle ages) and with the simultaneous necessity of scientific conservatism (without which the roots of past study could give no fruit) a conditional agreement was not arrived at, and ought not to have been, but instead of it truth, in the form of the law of Avogadro-Gerhardt, received by means of the Congress a wider development, and soon afterwards conquered all minds. Then the new so-called Gerhardt atomic weights established themselves, and in the seventies they had already become generally used.

With the establishment of the law the conception of the molecule was fully defined, and from it the conception of the magnitude of the atom of elements.

The particle or chemical particle or *molecule must be considered as the quantity of a substance entering into chemical reaction with other molecules, and which in a state of vapour occupies the same volume as two parts by weight of hydrogen.*

The molecular weight (which has been indicated by M) of a substance is determined by its composition, transformations, and vapour density.

The molecule is not divisible by the mechanical and physical changes of substances, but in chemical reaction it is either altered in its properties, or quantity, or structure, or in the nature of the movement of its parts.

An agglomeration of molecules, which are alike in all chemical respects, makes up the masses of definite homogeneous substances in all states.¹⁹

Molecules consist of atoms in a certain state of distribution and movement, just as the solar system²⁰ is made up of inseparable parts (the sun, planets, satellites, comets, &c.). The greater the number of

¹⁹ A volume of gas, a drop of a liquid, or the smallest crystal, presents an agglomeration of a number of molecules, in a state of movement, continuously repeated (like the stars of the milky way), distributing themselves in order or forming their new systems. If the aggregation of all kinds of heterogeneous molecules be possible in a gaseous state, where the molecules are considerably removed from each other, then in a liquid state, where the molecules are already close together, such an aggregation becomes possible only in that aspect of mutual reaction between the molecules which appears in their chemical attraction, and especially in the faculty of heterogeneous molecules for combining together. Solutions and other so-called indefinite chemical compounds should be regarded in this light. According to the representation evolved in this work we should regard them as containing both the compounds of the heterogeneous molecules themselves and the products of their decomposition, as in peroxide of nitrogen N_2O_4 and NO_2 . And we must consider that those molecules A, which at a given moment are combined with B in AB, will in the following moment become free in order to again enter into a combined form. The instances of chemical equilibria proper to dissociated systems cannot be regarded in any other sense.

²⁰ This strengthens the fundamental idea of the unity and harmony of the type of creation which forms one of those ideas which impress themselves on man in all ages, and give rise to a hope of arriving in time, by means of a lengthy labour of discoveries, observations, experiments, laws, hypotheses, and theories, at a comprehension of the internal and invisible structure of concrete substances with the same degree of clearness and exactitude as has been attained in the visible structure of the heavenly bodies. It is not many years ago since the law of Avogadro-Gerhardt took root in science. It is within the memory of many living scientific men. It is not surprising, therefore, that as yet little progress has been made in the province of molecular mechanics; but the theory of gases alone, which is intimately connected with the conception of molecules, shows by its success that the time is approaching when our knowledge of the internal structure of matter will grow rapidly.

atoms in a molecule, the more complex is the resultant substance. The equilibrium between the dissimilar atoms may then be more or less stable, and may for this reason give more or less stable substances. Physical and mechanical transformations alter the velocity of the movement and the distances between the individual molecules, or of the atoms in the molecules, or of their sum total, but they do not alter the original equilibrium of the system ; whilst chemical changes, on the other hand, alter the molecules themselves, that is, the velocity of movement, the relative distribution, and the quality and quantity of the atoms in the molecules.

Atoms are the smallest quantities or indivisible chemical masses of the elements forming the molecules of elements and compounds.

Atoms have weight, the sum of their weights forms the weight of the molecule, and the sum of the weights of the molecules forms the weight of masses, and is the cause of gravity, and of all the phenomena which depend on the mass of a substance.

The elements are characterised, not only by their independent existence, their incapacity of being converted into each other, &c., but also by the weight of their atoms.

Chemical and physical properties depend on the weight, composition, and properties of the molecules forming a substance, and on the weight and properties of the atoms forming the molecules.

This is the substance of those conceptions of molecular mechanics which lie at the basis of all contemporary physical and chemical constructions since the establishment of the law of Avogadro-Gerhardt. The fecundity of the principles enunciated is encountered at every step in the entire sum of the particular cases forming the present store of chemical data. We will here cite a few examples of the application of the law.

As the weight of an atom must be understood as the minimum quantity of an element entering into the composition of all the molecules formed by it, therefore, in order to find the weight of an atom of oxygen, let us take the molecules of those of its compounds which have been already described, together with the molecules of certain of those carbon compounds which will be described in the following chapter :—

	Molecular Weight.	Amount of Oxygen.		Molecular Weight.	Amount of Oxygen.
H ₂ O	18	16	HNO ₃	63	48
N ₂ O	44	16	CO	28	16
NO	30	16	CO ₂	44	32
NO ₂	46	32			

The number of substances taken might be considerably increased, but the result would be the same—that is, the molecules of the compounds of oxygen would never be found to contain less than 16 parts by weight of this element, but always $n16$, where n is a whole number. The molecular weights of the above compounds are found either directly from the density of their vapour or gas, or from their reactions. Thus, the vapour density of nitric acid (as a substance which easily decomposes above its boiling point) cannot be accurately determined, but the fact of its containing one part by weight of hydrogen, and all its properties and reactions, indicate the above molecular composition and no other. In this manner it is very easy to find the atomic weight of all the elements, knowing the molecular weight and composition of their compounds. It may, for instance, be easily proved that less than $n12$ parts of carbon never enters into the molecules of carbon compounds, and therefore C must be taken as 12, and not as 6 which was the case before Gerhardt. In similar manner the atomic weights now accepted for the elements oxygen, nitrogen, carbon, chlorine, sulphur, &c., were found and indubitably established, and they are even now termed the Gerhardt atomic weights. As regards the metals, many of which do not give a single volatile compound, we shall afterwards see that there are also methods by which their atomic weights may be established, but nevertheless the law of Avogadro-Gerhardt is here also ultimately resorted to, in order to remove any doubt which may be encountered. Thus, for instance, although much that was known concerning the compounds of beryllium necessitated its atomic weight being taken as $\text{Be}=9$ —that is, the oxide as BeO and the chloride BeCl_2 —still certain analogies gave reason for considering its atomic weight to be $\text{Be}=13\cdot5$, in which case its oxide would be expressed by the composition Be_2O_3 , and the chloride BeCl_3 .²¹ It was then found that the vapour density of beryllium chloride was approximately 40, when it became quite clear that its molecular weight was 80, and as this satisfies the formula BeCl_2 but does not suit the formula BeCl_3 , it therefore became necessary to regard the atomic weight of Be as 9 and not as $13\frac{1}{2}$.

²¹ If $\text{Be}=9$, and beryllium chloride be BeCl_2 , then for every 9 parts of beryllium there are 71 parts of chlorine, and the molecular weight of $\text{BeCl}_2 = 80$; hence the vapour density should be 40 or $n40$. If $\text{Be} = 13\cdot5$, and beryllium chloride be BeCl_3 , then to 13·5 of beryllium there are 106·5 of chlorine; hence the molecular weight would be 120, and the vapour density 60 or $n60$. The composition is evidently the same in both cases, because $9 : 71 :: 13\cdot5 : 106\cdot5$. Thus, if the symbol of an element designate different atomic weights, what seem to be very different formulæ may equally well express both the percentage composition of compounds, and those properties which are required by the laws of multiple proportions and equivalents. The chemists of former days accurately expressed the composition of substances, and accurately applied Dalton's laws, by taking $\text{H}=1$, $\text{O}=8$, $\text{C}=6$, $\text{Si}=14$, &c. The Gerhardt equivalents are also satisfied by

With the establishment of a true conception of molecules and atoms, chemical formulæ became direct expressions, not only of composition,²² but also of molecular weight or *vapour density*, and consequently them, because $O=16$, $C=12$, $Si=28$, &c., are multiples of them. The choice of one or the other multiple quantity for the atomic weight is impossible without a firm and concrete conception of the molecule and atom, and this is only obtained as a consequence of the law of Avogadro-Gerhardt, and therefore the contemporary atomic weights are the results of this law.

²² In order to calculate the percentage amounts of the elements contained in a given compound from its formula, it is necessary to use a very simple proportion sum. Thus, for example, to find the percentage amount of hydrogen in hydrochloric acid we reason as follows:— HCl shows that hydrochloric acid contains 35.5 of chlorine and 1 part of hydrogen. Hence, in 36.5 parts of hydrochloric acid there is 1 part by weight of hydrogen, consequently 100 parts by weight of hydrochloric acid will contain as many more units of hydrogen as 100 is greater than 36.5; therefore, the proportion is as follows— $x : 1 :: 100 : 36.5$ or $x = \frac{100}{36.5} = 2.739$. Therefore 100 parts of hydrochloric acid con-

tain 2.739 parts of hydrogen. In general, when it is required to transfer a formula into its percentage composition, we must replace the symbols by their corresponding atomic weights and find their sum, and knowing the amount by weight of a given element in it, it is easy by proportion to find the amount of this element in 100 or any other quantity of parts by weight. If, on the contrary, it be required to find the formula from a given percentage composition, we must proceed as follows: Divide the percentage amount of each element entering into the composition of a substance by its atomic weight, and compare the figures thus obtained together—they should be in simple multiple proportion to each other. Thus, for instance, from the percentage composition of hydrogen peroxide, 5.88 of hydrogen and 94.12 of oxygen, it is easy to find its formula; it is only necessary to divide the amount of hydrogen by unity and the amount of oxygen by 16. The numbers 5.88 and 5.88 are thus obtained, which are in the ratio of 1 : 1, which means that in hydrogen dioxide there is one atom of hydrogen to one atom of oxygen.

The following is a proof of the above practical rule:—*That to find the ratio of the number of atoms from the percentage composition, it is necessary to divide the percentage amounts by the atomic weights of the corresponding substances, and to find the ratio which these numbers bear to each other.* Let us suppose that two radicles (simple or compound), whose symbols and combining weights are A and B , combine together, forming a compound composed of x atoms of A and y atoms of B . The formula of the substance will be A_xB_y . From this formula we know that our compound contains xA parts by weight of the first element, and yB of the second. In 100 parts of our compound there will be (by proportion) $\frac{100 \cdot xA}{xA + yB}$ of the first element, and $\frac{100 \cdot yB}{xA + yB}$ of the second. Let us divide these quantities, expressing the percentage amounts by the corresponding combining weights; we then obtain $\frac{100x}{xA + yB}$ for the first element and

$\frac{100y}{xA + yB}$ for the second element. And these numbers are in the ratio $x : y$ —that is, in the ratio of the number of atoms of both substances.

It may be further observed that even the very language or nomenclature of chemistry acquires a particular clearness and conciseness by means of the conception of molecules, because then the names of substances may directly indicate their composition. Thus the term 'carbon dioxide' tells more about and expresses CO_2 better than carbonic acid gas, or even carbonic anhydride. Such nomenclature is already employed by many. But expressing the composition without an indication or even hint as to the properties, would be neglecting the advantageous sides of the present nomenclature. Sulphur dioxide, SO_2 , expresses the same as barium dioxide, BaO_2 , but sulphurous anhydride indicates the acid properties of SO_2 . Probably in time one harmonious chemical language will succeed in embracing both advantages.

of a series of fundamental chemical and physical data, inasmuch as a number of the properties of substances are dependent on their vapour density, or molecular weight and composition. Therefore, the vapour density $D = \frac{M}{2}$. For instance, the formula of ethyl ether is $C_4H_{10}O$,

hence it corresponds with the molecular weight 74, and the vapour density of 37, which is the fact. Therefore, the density of vapours and gases ceased to be an empirical magnitude obtained by experiment only, and it acquired a rational meaning. It is only then needful to remember that 2 grams of hydrogen, or the molecular weight of this primary gas in grams, occupies, at 0° and 760 mm. pressure, a volume of 22.3 litres (or 22300 cubic centimetres), in order to directly reduce the weights of cubical measures of gases and vapours from their formulæ, because *the molecular weights of all other vapours at 0° and 760 mm. occupy the same volume, 22.3 litres.* Thus, for example, in the case of carbonic anhydride, CO_2 , the molecular weight $M=44$, hence 44 grams of carbonic anhydride at 0° and 760 mm. occupy a volume of 22.3 litres—consequently, a litre weighs 1.97 grams. By combining the laws of gases—Gay-Lussac's, Mariotte's, and Avogadro-Gerhardt's—we obtain²³ a general formula for gases

$$6255s(273+t)=Mp$$

where s is the weight in grams of a cubic centimetre of a vapour or gas at a temperature t and pressure p (expressed in centimetres of mercury) if the molecular weight of the gas= M . Thus, for instance, at 100° and 760 millimetres pressure (*i.e.*, at the atmospheric pressure) the weight of a cubic centimetre of the vapour of ether ($M=74$) is equal to $s=0.0024$.²⁴

As the molecules of many elements (hydrogen, oxygen, nitrogen,

²³ This formula (which is given in my work on 'The Tension of Gases,' and in a somewhat modified form in the 'Comptes Rendus,' Feb. 1876) is deduced in the following manner. According to the law of Avogadro-Gerhardt, $M=2D$ for all gases, where M is the molecular weight and D the density referred to hydrogen. But they equal the weight S_0 of a cubic centimetre of a gas in grams at 0° and 76 c.m. pressure, divided by 0.0000896, for this is the weight in grams of a cubic centimetre of hydrogen. But the weight s of a cubic centimetre of a gas at a temperature t and under a pressure p (in centimetres) is equal to $sp/76(1+at)$. Therefore, $s_0=s.76(1+at)p$; hence $D=76.S(1+at)/0.0000896p$, whence $M=152s(1+at)/0.0000896p$, which gives the above expression, because $1/a=273$. m/v , where m is the weight and v the volume of a vapour, may be taken instead of s .

²⁴ The above formula may be applied in order to ascertain directly the molecular weight for a given vapour density, as s —the weight of vapour m , divided by the volume v , and consequently by experiment, $M=6,255 m(273+t)/pv$. Therefore, instead of the formula (*see* Chap. II. Note 33), $pv=R(273+t)$, where R varies with the mass and nature of a gas, we may apply the formula $pv=6,255(m/M)(273+t)$, and taking a weight of a gas m equal to its molecular weight, $pv=6,255(273+t)$ for all gases.

chlorine, bromine, sulphur—at least at high temperatures) are of uniform composition, therefore, the formulæ of the compounds formed by them, directly indicates the composition by volume. So, for example, the formula HNO_3 directly shows that in the decomposition of nitric acid there is obtained 1 vol. of hydrogen, 1 vol. of nitrogen, and 3 vols. of oxygen.

And as a great number of mechanical, physical, and chemical properties are directly dependent on the elementary and volumetric composition, and on the vapour density; so the accepted system of atoms and molecules gives the possibility of simplifying a number of most complex relations. For instance, it may be easily demonstrated that the *vis viva* of the molecules of all vapours and gases is alike. For it is proved by mechanics that the *vis viva* of a moving mass $= \frac{1}{2} mv^2$, where m is the mass and v the velocity. For a molecule $m = M$, or the molecular weight, and the velocity of the movement of gaseous molecules $=$ a constant which we will designate by C , divided by the square root of the density of the gas $^{25} = C/D^{\frac{1}{2}}$, and as $D = M/2$, therefore, the *vis viva* of molecules $= C^2$ that is, a constant for all molecules. *Q.E.D.*²⁶ The specific heat of gases (as we shall afterwards see), and many other of their properties, are determined by their density, and consequently by their molecular weight. Gases and vapours in passing into a liquid state evolve the so-called *latent heat*, which also proves to be in connection with the molecular weight. The observed latent heats of carbon bisulphide, $\text{CS}_2 = 90$, of ether.

²⁵ Chap. I. Note 34.

²⁶ The velocity of the transmission of sound through gases and vapours closely bears on this. It $= \sqrt{Kpg/D(1+at)}$ where K is the ratio between the two specific heats (it is approximately 1.4 for gases containing 2 atoms in a molecule), p the pressure of the gas expressed by weight (that is, the pressure expressed by the height of a column of mercury multiplied by the density of mercury), g the acceleration of gravity, D the weight of a cubic measure of the gas, $a = 0.00367$, and t the temperature. Hence, if K be known, and as D can be found from the composition of a gas, we can calculate the velocity of the transmission of sound in that gas. Or if this velocity be known, we can find K . The relative velocities of sound in two gases can be determined with peculiar ease (Kundt).

If a horizontal glass tube (about 1 metre long and closed at both ends) be full of a gas, and be firmly fixed in the middle, then it is easy to bring the tube and gas into a state of vibration, by rubbing it from centre to end with a damp cloth. The vibration of the gas is easily rendered visible, if the interior of the tube be dusted with lycopodium (the yellow powder-dust or spores of the lycopodium plant is often employed in medicine), before the gas is introduced and the tube fused up. The fine lycopodium powder forms itself into figures, whose number depends on the velocity of sound in the gas. If there be 10 figures, then the velocity of sound in the gas is ten times slower than in glass. It is evident that this is an easy method of comparing the velocity of sound in gases. It has been demonstrated by experiment that the velocity of sound in oxygen is four times less than in hydrogen, and the square roots of the densities and molecular weights of hydrogen and oxygen stand in this ratio.

$C_4H_{10}O=94$, of benzene, $C_6H_6=109$, of alcohol, $C_2H_6O=200$, of chloroform, $CHCl_3=67$, &c. These figures show the amount of heat expended in converting one part by weight of the above substances into vapour. A great uniformity is observed if the measures of heat be referred to the weights of the molecules. For carbon bisulphide the formula CS_2 expresses a weight 76, hence the latent heat of evaporation referred to the molecular quantity, $CS_2=76 \times 90=6840$, for ether=9656, for benzene=8502, for alcohol=9200, for chloroform=8007, for water=9620, &c. Consequently, for molecular quantities, the latent heat varies comparatively little, from 7000 to 10000 heat units, whilst for single parts by weight it is for water ten times greater than for chloroform and many others.²⁷

We will cite yet one more example, showing the direct dependence of the properties of a substance on the molecular weight. If one molecular part by weight of the various chlorides—for instance, of sodium, calcium, barium, &c.—be dissolved in 200 molecular parts by weight of water (for instance, in 3600 grams) then it is found that the greater the molecular weight of the salt dissolved, the greater is the specific gravity of the resultant solution.²⁸ Thus :—

	Molecular weight.	Sp. gr. at 15°.		Molecular weight.	Sp. gr. at 15°.
HCl	36·5	1·0041	CaCl ₂	111	1·0236
NaCl	58·5	1·0106	NiCl ₂	130	1·0328
KCl	74·5	1·0121	ZnCl ₂	136	1·0331
BeCl ₂	80	1·0138	BaCl ₂	208	1·0489
MgCl ₂	95	1·0203			

However, all properties of substances do not depend on the molecular weight alone.²⁹ Not only chemical, but also many physical,

²⁷ If the conception of the molecular weights of substances does not give an exact law when applied to the latent heat of evaporation, it, at all events, brings to light a certain uniformity in figures, which otherwise only represent the simple result of observation. Molecular quantities of liquids appear to expend almost equal amounts of heat in their evaporation. It may be said that the latent heat of evaporation of molecular quantities is approximately constant, because the *vis viva* of the movement of the molecules is, as we saw above, a constant quantity.

²⁸ Particulars bearing on this are given in my work: "The Investigation of Aqueous Solutions by their Specific Gravity," 1887, p. 425.

²⁹ Among the most noteworthy of the applications of the conceptions arising from the law of Avogadro-Gerhardt, are those generalisations concerning dilute solutions which have been mentioned in the Chap. I. (Notes 19, 49, 50, 51). It is first necessary to mention the fundamental experiments, Traube, Pfeiffer, and more especially, De Vries. Traube showed that certain specially-prepared films (precipitated membranes) of insoluble substances (for example, those which are formed from the salts of copper and ferrocyanide of potassium) have the property of allowing the passage of water whilst retaining the substances dissolved in it, and it was therefore possible by this means to

properties are determined by the composition of the molecules, and by the properties of the elements forming them. Thus the density of solids

determine the osmotic pressure, as in the experiment described in Chap. I. Note 19. De Vries found in vegetable cells a convenient means of determining such (isotonic) solutions, which produce identical osmotic pressures. A thin slice of a coloured plant tissue—for instance, of *Tradescantia discolor*—is moistened under the microscope with the solution to be tested. If its osmotic pressure be equal, or less than that of the liquid contained in the cells, no visible change occurs; but if the liquid taken be endued with a greater osmotic pressure than the cellular sap, then the water will pass from the cell, and the coloured matter of the cell will shrink away from the envelope, and this process is easily observed under the microscope. Knowing, then, the osmotic pressure for any one substance—for instance, for sugar—with different strengths of solutions, it is possible to find the osmotic pressure of all other substances investigated, because it is shown by direct experiment that the osmotic pressure increases in proportion to the strength of the solution. Thus having fixed on any one substance—for instance, sugar—and on one of its solutions, we may see the substance of the results which have been attained.

If (as on p. 64) a one per cent. solution of sugar be taken, then according to the experiments made by Pfeiffer (1877) its osmotic pressure = 58.5 centimetres at 14°. According to the formula of sugar, $C_{12}H_{22}O_{11}$, its molecular weight $M=342$, and as the weight of a cubic centimetre of a one per cent. solution of sugar = 1.003 gram, therefore the weight of sugar in a cubic centimetre of the solution, or s in the preceding formula ($p \cdot 320 : 6255 \text{ s } (273 + t) = Mp$), is equal to 0.01003 gram, and therefore, according to this formula (as $M=342$ and $t=14$), $p=52.6$ centimetres. This shows that *if the sugar were*, instead of being in solution, *in a state of vapour*, then in following the law of Avogadro-Gerhardt *it would produce a pressure equal to the osmotic pressure*. This deduction (whose sense is at present not clear) forms the substance of Van't Hoff's doctrine (Chap. I. Note 19), when $i=1$ (Chap. I. Note 49).

Consequently, the molecular weight determines the osmotic pressure (and together with it the vapour tension and temperature of freezing, according to Note 49, Chap. I.), and therefore the molecular weight itself may be determined by the osmotic pressure as well as by the vapour density.

But so simple a relation only exists for dilute solutions of substances like sugar, which do not conduct an electric current, for which $i=1$. For salts and acids which conduct a current, this factor varies up to $i=4$ (Chap. I. Note 49). Arrhenius explains this phenomenon by supposing (partially after Hittorf and Clausius) that a portion of such substances in solutions, and especially in dilute solutions, occurs in a state of dissociation, and owing to this the number of molecules is multiplied (Chap. I. Note 45). As the conceptions of this order have been as yet but very little developed, and as in regarding solutions from this point of view, which is warmly supported by Ostwald, the water or solvent in general, which certainly plays an important part in solutions, and especially dilute ones, is entirely lost sight of, I consider it premature at present to explain the theory of Arrhenius, but think that it contains the seeds for further development and for its being merged into a fuller theory of solutions.

For the matter now under our consideration we need not see in the fact of the variability of i any hindrance to employing (*a*) the determination of the osmotic pressure, (*b*) the freezing point of a solvent (the so-called Raoult's method), and (*c*) the variation of the vapour density as means for finding the molecular weight of a substance in solution, not only in the ordinary cases when $i=1$, but even in those cases where $i>1$. These methods have already proved useful for solving the question of the molecular weight in many particular instances among the hydrocarbons, and some portion of their application to inorganic compounds will be mentioned in the further course of this work.

It may not be superfluous to remark that the osmotic pressure in the cells of organisms attains several atmospheres, and probably forms one of the causes determining the

and liquids (as will afterwards be shown) is chiefly determined by the weights of the atoms of the elements entering into their composition, inasmuch as heavy (free) elements and compounds are only met with among substances containing elements with large atomic weights, such as gold, platinum, and uranium. And these elements themselves, in a free state, are the heaviest of all elements. Substances containing such light elements as hydrogen, carbon, oxygen, and nitrogen (like many organic substances) never have a high specific gravity; in the majority of cases it scarcely exceeds that of water. The density generally decreases with the augmentation of the amount of hydrogen, as the lightest element, and a substance is often obtained lighter than water. The refractive power of substances also entirely depends on the composition and the properties of the component elements.³⁰ The history

individual functions of the cells. The further development of the questions touching on this subject should in this manner not only aid the perfecting of the theory of solutions but also the further progress of physiological science.

⁵⁰ With respect to the optical refractive power of substances, it must first be observed that the coefficient of refraction is determined by two methods: (a) either all the data are referred to one definite ray—for instance, to the Fraunhofer (sodium) line D of the solar spectrum—that is, to a ray of definite wave length, and often to that red ray (of the hydrogen spectrum) whose wave length is 656 million parts of a millimetre; (b) or Cauchy's formula is used, showing the relation between the coefficient of refraction and dispersion to the wave length $n = A + \frac{B}{\alpha^2}$, where A and B are two constants vary-

ing for every substance but constant for all rays of the spectrum, and α is the wave length of that ray whose coefficient of refraction is n . In the latter method the investigation usually concerns the magnitudes of A, which are independent of dispersion. We shall afterwards cite the data, investigated by the first method, by which Gladstone, Landolt, and others established the conception of the refraction equivalent.

The coefficient of refraction n for a given substance decreases, as has long been known, with the density of a substance D, so that the magnitude $(n-1) \div D = c$ is almost constant for a given ray (having a definite wave length) and for a given substance. This constant is called the *refractive energy*, and its product with the atomic or molecular weight of a substance the *refraction equivalent*. The coefficient of refraction of oxygen is 1.00021, of hydrogen, 1.00014, their densities (referred to water) are 0.00143 and 0.00009, and their atomic weights, O=16, H=1; hence their refraction equivalents are 3 and 1.5. Water contains H₂O, consequently the sum of the equivalents of refraction is $(2 \times 1.5) + 3 = 6$. But as the coefficient of refraction of water = 1.331, therefore its refraction equivalent = 5.958, or nearly 6. The comparison shows that, approximately, the sum of the refraction equivalents of the atoms forming compounds (or mixtures) is equal to the refraction equivalent of the compound. According to the researches of Gladstone, Landolt, Hagen, Brühl and others, the refraction equivalent of the elements are—H = 1.3, Li = 3.8, B = 4.0, C = 5.0, N = 4.1 (in its highest state of oxidation, 5.3), O = 3.0, F = 1.4, Na = 4.8, Mg = 7.0, Al = 8.4, Si = 6.8, P = 18.3, S = 16.0, Cl = 9.9, K = 8.1, Ca = 10.4, Mn = 12.2, Fe = 12.0, (in the salts of its higher oxides 20.1), Co = 10.8, Cu = 11.6, Zn = 10.2, As = 15.4, Bi = 15.3, Ag = 15.7, Cd = 13.6, I = 24.5, Pt = 26.0, Hg = 20.2, Pb = 24.8, &c. The refraction equivalents of many elements could only be calculated from the solutions of their compounds. The composition of a solution being known it is possible to calculate the refraction equivalent of one of its component parts, those for all its other components being known. The results are founded on the acceptance of a law which cannot be strictly applied. Nevertheless the conception of the refraction equivalents gives an easy means for directly,

of chemistry presents a striking example in point—Newton foresaw from the high refractive index of the diamond that it would contain a combustible substance since so many combustible oils have a high refractive power.

As regards purely chemical relations, especially the understanding of reactions and the structure of substances, the fecundity of the law of Avogadro-Gerhardt is evinced at every step of the contemporary path of chemistry. Starting from the laws and conceptions of Lavoisier the chemistry of our time is entirely founded on the laws of Dalton and Avogadro-Gerhardt, on the doctrine of Berthollet respecting the equilibria brought about in chemical actions, and on the conceptions of dissociation introduced into the science by Saint-Claire Deville.

although only approximately, obtaining the coefficient of refraction from the chemical composition of a substance. For instance, the composition of carbon bisulphide, $\text{CS}_2=76$, and from its density, 1.27, we find its coefficient of refraction to be 1.618 (because the refraction equivalent $=5+2\times 16=37$), which is very near the actual figure. It is evident that in the above representation compounds are looked on as simple mixtures of atoms, and the physical properties of a compound as referable to the properties present in the elementary atoms forming it. If this representation of the presence of simple atoms in compounds did not exist, then the effort to combine by a few figures a whole mass of data relating to the coefficient of refraction of different substances would hardly arise.

CHAPTER VIII

CARBON AND THE HYDROCARBONS

It is necessary to clearly distinguish between the two closely-allied terms, charcoal and carbon. Charcoal is well known to everybody, although it is no easy matter to obtain it in a chemically pure state. Pure charcoal is a simple, insoluble, infusible, combustible substance produced by heating organic matter, and has the familiar aspect of a black mass, devoid of any crystalline structure, and completely insoluble. Charcoal is a substance possessing a certain combination of physical and chemical properties. This substance, whilst in a state of ignition, combines directly with oxygen; in organic substances it is found in combination with hydrogen, oxygen, nitrogen, and sulphur. But in all these combinations there is no real charcoal, as in the same sense there is no ice in steam. What is found in such combinations is termed 'carbon'—that is, an element common to charcoal, to those substances which can be formed by it, and also to those substances from which it can be obtained. Carbon may take the form of charcoal, but appears also as diamond and as graphite. It is true that no other element has such a limitation in its terminology. Oxygen was always called 'oxygen,' whether it was in a free gaseous state, or oxygen in the form of ozone, or oxygen in water, or in nitric acid or in carbonic anhydride. But here there is a certain confusion. In water it is evident that there is no oxygen in a gaseous form, such as can be obtained in a free state, no oxygen in the form of ozone, but a substance which is capable of producing both oxygen, ozone, and water. As an element oxygen possesses a known chemical individuality, and an influence on the properties of those combinations into which it enters. Hydrogen gas is a substance which reacts with difficulty, but hydrogen as an element represents in its combinations an easily displaceable component part. Carbon may be considered as an atom of carbon matter, and charcoal as a collection of such atoms forming a whole substance, as molecules in the mass of the substance. The accepted atomic weight of carbon is 12, because that is the least

quantity of carbon which enters into combination in molecules of its compounds; but the weight of the molecules of charcoal is probably very great. This weight remains unknown, because charcoal is capable of but few direct reactions, and those only at a high temperature (when the weight of its molecules probably changes, as when ozone changes into oxygen), when it does not turn into vapour. Carbon exists in nature, both in a free and combined state, in most varied forms and aspects. Carbon in a free state is found in at least three different forms, as charcoal, graphite, and the diamond. In a combined state it enters into the composition of what are called organic substances—a multitude of substances which are found in all plants and animals. It exists as carbonic anhydride both in air and in water, and in the soil and crust of the earth as salts of carbonic acid and as organic remains.

The variety of the substances of which the structure of plants and animals is built up is familiar to all. Wax, oil, turpentine, and tar, cotton and albumin, the tissue of plants and the muscular fibre of animals, vinegar and starch, are all vegetable and animal matters, and all carbon compounds.¹ The sphere of carbon compounds is so vast

¹ Wood is the non-vital part of ligneous plants; the vital part of ordinary trees is situated between the bark and the lignin. Every year a layer of lignin is deposited on this part by the juices which are absorbed by the roots and worked up by the leaves; for this reason the age of trees may be determined by the number of lignin layers deposited. The following year the juices travel over a new layer, and in this way the layer already deposited serves only as a support for the vital parts of the tree. A living tree may be regarded as an agglomeration of many plants living on one support. The woody matter consists principally of fibrous tissue on to which the lignin or so-called incrusting matter has been deposited. The tissue has the composition $C_6H_{10}O_5$, the substance deposited on it contains more carbon and hydrogen and less oxygen. This matter is saturated with moisture when the wood is in a fresh state. Fresh birch wood contains about 31 p.c. of water, lime wood 47 p.c., oak 35 p.c., pine and fir about 37 p.c. When dried in the air the wood loses a considerable quantity of water and not more than 19 p.c. remains. By artificial means this loss of water may be increased. If water be driven into the pores of wood it becomes heavier than water, as the lignin of which it is composed has a density of about 1.6. One cubic centimetre of birch wood does not weigh more than 0.901 grams, fir 0.894, lime tree 0.817, poplar 0.765 when in a fresh state; when in a dry state birch weighs 0.622, pine 0.550, fir 0.355, lime 0.430, guaiacum 1.342, ebony 1.226. It is not out of place to remark here that on one deciatin (2.7 acres) of woodland the yearly growth averages an amount of 3000 kilograms, or 180 poods of wood, but rarely reaches as much as 5000. The average chemical composition of wood dried in air may be expressed as follows:—Hygroscopic water 15 p.c., carbon 42 p.c., hydrogen 5 p.c., oxygen and nitrogen 37 p.c., ash 1 p.c. Wood parts with its hygroscopic water at 150°, and decomposes at about 300°, giving a brown, brittle, so-called red charcoal; above 350° black charcoal is produced. From the above-mentioned average composition of wood it is evident that the hydrogen may be accepted as being in about the quantity to combine with the oxygen, as the hydrogen contained in the wood requires for its combustion about forty parts by weight of oxygen. Therefore all that burns of the wood is the carbon which it contains, 100 parts of wood only giving out as much heat as forty parts of charcoal. Charcoal gives out much more useful heat than wood because the water contained in the wood, or formed by the combination of its oxygen and hydrogen, has to be

that it forms a separate branch of chemistry, which treats of the compounds of carbon, part of which are met with in plants and animals.

evaporated during its combustion. The above-mentioned composition of wood shows that it would be far more profitable to use charcoal for heating purposes than wood, if it were possible to obtain it in such quantities as correspond with its percentage ratio—that is, forty parts per 100 parts of wood. Generally, however, the quantity produced is far less, not more than 30 p.c., because part of the carbon is given off as gas, tar, &c. If wood has to be transported great distances, or if it is necessary to obtain a very high temperature by burning it, then even as little as 25 p.c. of charcoal from 100 parts of wood may be advantageous. Charcoal (wood) develops on burning 8000 heat units, whilst wood dried in air does not develop more than 2800 units of heat; therefore seven parts of charcoal give as much heat as twenty parts of wood; but twenty parts of wood are only capable of yielding five parts of charcoal. This datum may be used for comparing the heating power of wood and charcoal. As regards the temperature of combustion, it is far higher with charcoal than with wood, because twenty parts of burning wood give, besides the carbonic anhydride which is also formed with charcoal, eleven parts of water, the evaporation of which requires a considerable amount of heat.

The composition of the growing parts of plants, the leaves, young branches, shoots, &c., differs from the composition of the wood in that these vital parts contain a considerable quantity of sap which contains much nitrogenous matter (in the wood itself there is very little), mineral salts, and a large amount of water. Taking, for example, the composition of clover and pasture hay in the green and dry state. In 100 parts of green clover there is about 80 p.c. of water and 20 p.c. of dry matter, in which there are about 3.5 parts of nitrogenous matter, about 9.5 parts of soluble and about 5 parts of insoluble non-nitrogenous matter, and about 2 p.c. of ash. In dry clover or clover-hay there is about 15 p.c. of water, 13 p.c. of nitrogenous matter, and 7 p.c. of ash. This composition of grassy substances shows that they are capable of forming the same sort of charcoal as wood itself. It also shows the difference of nutritive properties existing between wood and the substances mentioned. These latter serve as food for animals, because they contain those substances which are capable of being dissolved (entering into the blood) and forming the body of animals; such substances are proteids, starch, &c. Let us remark here that with a good harvest an acre of land gives in the form of grass as much organic substance as it yields in the form of wood.

One hundred parts of dry wood are capable of giving, by means of dry distillation, besides 25 p.c. of charcoal and 10 p.c. or more of tar, 40 p.c. of watery liquid, containing acetic acid and wood spirit, and about 25 p.c. of gases, which may be used for heating or lighting purposes, because they do not differ from ordinary illuminating gas, which can indeed be obtained from wood. As wood-charcoal and tar are costly products, in some cases the dry distillation of wood is carried on principally for producing them. For this purpose those kinds of woods are particularly advantageous which contain resinous substances, especially coniferous trees, such as fir, pine, &c.; birch, oak, and ash give much less tar, but on the other hand they yield more watery liquid. The latter is used for the manufacture of wood spirit, CH_4O , and acetic acid, $\text{C}_2\text{H}_4\text{O}_2$. In such cases the dry distillation is carried on in stills. Stills are nothing more than horizontal or vertical cylindrical retorts, made of boiler plate, heated with fuel and having apertures at the top and sometimes also at the bottom for the exit of the light and heavy products of distillation. The dry distillation of wood in stoves is carried on in two ways, either by burning a portion of the wood inside the stove in order to submit the remainder to dry distillation by means of the heat obtained in this manner, or by placing the wood in a stove the thin sides of which are surrounded with a flue leading from the fuel, placed in a space below.

The first means does not give such a large amount of liquid products of the dry distillation as the latter. In the latter process there is generally an outlet below for

This branch of chemistry is known under the name of organic chemistry—that is, the chemistry of carbon compounds, or, more strictly, of the hydrocarbons and their derivatives.

If any one of these organic compounds be strongly heated without access of air—or, better still, in a vacuum—it decomposes with more or less facility. When organic substances are heated in air, it is well known that they burn; but if the supply of air be insufficient, or the temperature be too low for combustion, and if the first volatile products of transformation of the organic matter are subjected to condensation (for example, if the door of a stove be opened), an imperfect combustion takes place, and smoke, with charcoal or soot, is formed.²

emptying out the charcoal at the close of the operation. For the dry distillation of 100 parts of wood from forty to twenty parts of fuel are used.

There are many steps between the method of burning wood in stacks (Note 4), and that of burning it in an enclosed space—namely, those in which the burning of the char-




FIG. 57.—Apparatus for the dry distillation of wood. The retort *a* containing the wood is heated by the flues *c e*. The steam and volatile products of distillation pass along the tube *g* through the condenser *m*, where they are condensed. The form, distribution, and dimensions of the apparatus vary.

coal is accompanied by a certain production of tar. This is effected by means of trenches dug in the earth and having sloping bottoms, by which contrivance the tar separated by the charring of the wood flows into special receivers. This process is much used in the north of Russia.

In the north of Russia wood is so plentiful and cheap that this locality is admirably fitted to become the centre of a general trade in the products of the dry distillation of wood. Coal (Note 6), sea-weed, turf, animal substances (Chap. VI.), &c., are also submitted to the process of dry distillation.

² The result of imperfect combustion is not only the loss of a part of the fuel and the production of smoke, which in some respects is inconvenient and injurious to health, but also a low flame temperature, which means that a less amount of heat is transmitted to the object heated. Imperfect combustion is not only always accompanied by the formation of soot or unburnt particles of charcoal, but also by that of carbonic oxide, CO, in the

The nature of the phenomenon, and the products arising from it, are the same as those produced by heating alone, as that part which is in a state of combustion serves to heat the remainder of the fuel. The decomposition which takes place on heating a compound composed of carbon, hydrogen, and oxygen is as follows :—A part of the hydrogen is separated in a gaseous state, another part in combination with oxygen, and a third part separates in combination with carbon, and sometimes in combination with carbon and oxygen in the form of gaseous or volatile products, or, as they are also called, the products of dry distillation. If the vapours of these products are passed through a highly-heated tube, then they are changed again in a similar manner, and finally resolve themselves into hydrogen and charcoal. All these various products of decomposition contain a smaller amount of carbon than the primary organic matter ; part of the carbon separates in combination with hydrogen and oxygen, but part of it remains in a free state, forming charcoal.³ It remains in that space where the decomposition takes

smoke (Chapter IX.) which burns, emitting much heat. In works and factories where large quantities of fuel are consumed, many appliances are adopted to ensure perfect combustion, and to combat against such a ruinous practice as the imperfect combustion of fuel. The most effective and radical means consists in employing the combustible gases (regenerative and water gases), because by their aid perfect combustion can be easily realised without a loss of heat-producing power and the highest temperature can be reached. When solid fuel is used (such as coal, wood, and turf), imperfect combustion is most liable to occur when the furnace doors are opened for the introduction of fresh fuel. The step furnace may often prove a remedy for this defect. In the ordinary furnace fresh fuel is placed on the burning fuel, and the products of dry distillation of the fresh fuel have to burn at the expense of the oxygen remaining uncombined with the burnt fuel. Imperfect combustion is observed in this case also from the fact that the dry distillation and evaporation of the water of the fresh fuel lying on the top of that burnt, lowers the temperature of the flame, because part of the heat becomes latent. On this account a large amount of smoke (imperfect combustion) is observed when a fresh quantity of fuel is introduced into the furnace. This may be obviated by constructing the furnace (or managing the stoking) in such a way that the products of distillation pass through the red-hot charcoal remaining from the burnt fuel. It is only necessary in order to ensure this to allow a sufficient quantity of air for perfect combustion. All this may be easily attained by the use of step fire-bars. The fuel is shovelled into a funnel and falls on to the fire-bars, which are disposed in the form of a staircase. In burning charcoal is below, and therefore the flame formed by the fresh fuel is heated by the contact of the red-hot burning charcoal. An air supply through the fire grate, and its equal distribution on the fire-bars (otherwise the air will blow through the empty space and lower the temperature), a proper proportion between the supply of air and the chimney draught, and a perfect admixture of air with the flame (without an undue excess of air), are the means by which we can strive against the imperfect combustion of such kinds of fuel as wood, peat, and ordinary (smoky) coal. Coke, steam coal, anthracite, burn without smoke, because they do not contain hydrogenous substances which furnish the products of dry distillation, but imperfect combustion may occur with them also; then the smoke contains carbonic oxide.

³ The various kinds of coal used in practice and found in nature are the products of the transmutation of the remains of organic matter. There is no organic substance which contains in itself sufficient oxygen not only to combine with hydrogen in order to

place in the shape of a black, infusible, non-volatile charcoal familiar to all. The earthy matter and all non-volatile substances (ash) forming a part of the organic matter, remain behind with the charcoal. The tar-like substances, which require a high temperature in order to decompose them, also remain mixed with charcoal. If a volatile organic substance, such as a gaseous compound containing oxygen and hydrogen, be taken, the carbon separates on passing the vapour through a

form water, but also to unite with the carbon to form carbonic anhydride. The greater part of vegetable tissue consists of the cellulose, $C_6H_{10}O_5$; from its composition it is evident that the oxygen is insufficient to transform the hydrogen into water and the carbon into carbonic anhydride, because for this purpose it would require 17 equivalents and it only contains 5. This reasoning also refers to all the remaining organic substances. Under the action of air, organic substances are capable of oxidising to such an extent that all the carbon and all the hydrogen they contain will be transformed into carbonic anhydride and water. The refuse of plants and animals are subjected to such a change whether they slowly decompose and putrefy, or rapidly burn, with direct access to air. But if the supply of air be limited, then, in virtue of the above-stated reasoning, there can be no complete transformation into water and carbonic anhydride, and therefore, if organic matter decomposes under these conditions, charcoal must remain, as it is a non-volatile substance. All organic substances are unstable, they do not resist heat, and in time easily change at ordinary temperatures, particularly if water be present. Therefore it is easy to understand that charcoal may be obtained in many cases through the transformation of substances entering into the composition of organisms, but that it is never found in a pure state.

The transformation of organic matter is not, however, so simple as would appear from the preceding statements; that is to say, water and carbonic anhydride are not the only products separated from organic substances. Carbon, hydrogen, and oxygen are capable of giving a multitude of compounds; some of these are volatile compounds, gaseous, soluble in water—they are carried off from organic matter, undergoing change without access of air. Others, on the contrary, are non-volatile, rich in carbon, constant under the influence of heat and other agents. The latter remain in admixture with charcoal where the decomposition takes place; such, for example, are tarry substances. The quantity of those bodies which are found mixed with the charcoal is very varied, and depends on the energy and duration of the decomposing influence. For instance, when wood is first acted on by heat, the moisture separates; it then turns brown, but still contains a large amount of oxygen and hydrogen. If the action be further continued the quantity of these latter elements diminishes, and the proportion of carbon in the residue increases, although a part of it is carried off in the shape of the volatile products of decomposition. The greater the heat, the less the quantity of charcoal obtained, and the less the amount of hydrogen and oxygen contained in the remaining charcoal. The annexed table shows, according to the data of Violette, those changes to which wood is subjected at various temperatures when submitted to dry distillation by means of superheated steam:—

Temperature	Residue from 100 parts of alder wood	In 100 parts of the residual charcoal			
		C	H	O and N	Ash
150°	100·0	47·5	6·1	46·3	0·1
350°	29·7	76·6	4·1	18·4	0·6
1032°	18·7	81·9	2·3	14·1	1·6
1500°	17·3	95·0	0·7	3·8	1·7

tube heated to a high temperature. Organic substances, when burning with an insufficient supply of air, give off soot—that is, charcoal—proceeding from carbon compounds in a state of vapour, the hydrogen of which has, by combustion, been converted into water; so, for instance, turpentine, naphthalene, and other hydrocarbons which are with difficulty decomposed by heat, easily yield carbon in the form of soot during combustion. Chlorine and other substances, which, like oxygen, are capable of taking up hydrogen, and also substances which are capable of taking up water, can also separate carbon from (or char) most organic substances.

When organic substances are burning in an insufficient supply of air, they both separate and leave charcoal. Part of it remains behind as a residue, as, for instance, after burning wood in a stove some remains in the form of charcoal. Wood charcoal is prepared in large quantities in a similar manner—that is, by the partial combustion of wood.⁴ In nature a like process of carbonisation of vegetable refuse takes place in its transformation under water, as shown by the marshy vegetation which forms peat.⁵ In this manner, doubtless, the enormous masses

⁴ The object of producing charcoal from wood has been explained in Footnote 1. *Wood charcoal* is obtained in so-called stacks by partially burning the wood, or by means of dry distillation—that is, by heating wood in an enclosed space (in retorts, Note 1)—without the access of air. It is principally manufactured for metallurgical processes, especially for smelting and forging iron—that is, for use in smithies. The preparation of charcoal in stacks has one advantage, and that is that it may be done on any spot in the forest. But in this way all the products of dry distillation are lost. For charcoal burning, a pile or stack is generally built, in which the logs are closely placed, either horizontally, vertically, or inclined, forming a stack of from six to fifty feet in diameter and even larger. Under the stack there are several horizontal air passages, and an opening in the middle to let out the smoke. The surface of the stack is covered with sods to a considerable thickness, especially the upper part, in order to hinder the free passage of air and to concentrate the heat inside. When the stack is kindled, the pile begins to settle down by degrees, and it is then necessary to look after the turf casing and keep it in repair. As the combustion spreads throughout the whole pile, the temperature rises and real dry distillation commences. It is then necessary to stop the air holes, in order as much as possible to prevent unnecessary combustion. The nature of the process is, that part of the fuel burns and develops the heat required for subjecting the remainder to dry distillation. The charring of the stack lasts about a fortnight, and is brought to a termination by scattering earth over the incandescent charcoal to stop the combustion. The charring is stopped when the products of dry distillation, which are emitted, no longer burn with a brilliant flame, but the pale blue flame of carbonic oxide appears. Dry wood in stacks yields about one-fourth of its weight of charcoal.

⁵ When dead vegetable matter undergoes transformation in air, in the presence of moisture, there remains a substance much richer in carbon—namely, humus, black earth or mould. 100 parts of humus in a dry state contain about 70 p.c. of carbon. The roots, leaves, and stems of plants which wither and fall off form a soil rich in humus. The non-vital vegetable substances (ligneous tissue) first form brown matter (ulmic compounds), and then black matter (humic substances), which are both insoluble in water; after this a brown acid is produced, which is soluble in water (apocrenic acid),

of coal were formed,⁶ which, following the example set by England, are now utilised everywhere as the principal material for heating steam

and lastly a colourless acid also soluble in water (crenic acid). Alkali dissolves a part of the original brown and black substances, forming solutions of a brown tint (humic and humic acids), which sometimes communicate their colour to springs and rivers. The composition of the humus in the soil is generally in connection with its fertility; firstly, because putrefying plants develop carbonic anhydride and ammonia, and yield the saline substances which are necessary to vegetation; secondly, because humus is capable of attracting the moisture of the air and of absorbing water (twice its weight) and in this way keeps the soil in a damp condition, which is indispensable for nourishment; thirdly, humus renders the soil porous, and, fourthly, renders it more capable of absorbing the heat of the sun's rays. On this account black earth is often most remarkable for its fertility. One object of manuring is to increase the quantity of humus in the soil, and any easily changeable vegetable or any animal matter (composts) may be used. The boundless tracts of black earth soil in Russia are capable of bestowing countless wealth on the country.

The origin and extent of black earth soil is treated in detail in Professor Dokouchaeff's works.

If those substances which produce humus undergo decomposition under water, less carbonic anhydride is formed, a quantity of marsh gas, CH_4 , is evolved, and the solid residue forms an acid humus, found in great quantities in marshy places, and called *peat*. Peat especially abounds in the lowlands of Holland, North Germany, Ireland, and Bavaria. In Russia it is likewise found in large quantities, especially in the North-west districts. The old hard forms of peat resemble in composition and properties brown coal: the newest formations, as yet unhardened by pressure, form very porous masses which retain traces of the vegetable matter from which they have been formed. Dried (and sometimes pressed) peat is used as fuel. The composition of peat varies considerably with the locality in which it is found. When dried in air it does not contain less than 15 p.c. of water and 8 p.c. of ash; the remainder consists of 45 p.c. of carbon, 4 p.c. of hydrogen, 1 p.c. of nitrogen, and 28 p.c. of oxygen. Its heating power is about equivalent to that of wood. The brown earthy varieties of coal were probably formed from peat. In other cases they have a marked woody structure, and are then known as lignites. The composition of the brown sorts of coal resembles in a marked degree that of peat—namely, in a dried state brown coal contains on an average 60 p.c. of carbon, 5 p.c. of hydrogen, 26 p.c. of oxygen and nitrogen, and 9 p.c. of ash. In Russia brown coal is met with in many districts near Moscow, in the governments of Toula and Tver and the neighbourhood; it is very generally used as fuel, particularly when found in thick seams. The brown coals generally burn with a flame like wood and peat, and are akin to them in heating power, which is two or three times less than that of the best coal.

⁶ Grass and wood, the vegetation of primæval seas and similar refuse of all geological periods, must have been, in many cases, subjected to the same changes they now undergo—that is, under water they formed peat and lignites. Such substances, preserved for a long time underground, subjected to the action of water, compressed by the new strata formed above them, transformed by the separation of their more volatile component parts (peat and lignites, even in a finished state, still continue to evolve nitrogen, carbonic anhydride, and marsh gases), form *coal*. Coal is a dense homogeneous mass, dark brown or black, with an oily or glassy lustre, or, more rarely, dull, without any evident vegetable structure; this distinguishes it in appearance from the majority of lignites. The density of coal (not counting the admixture of pyrites, &c.) varies from 1.25 (dry bituminous coal) to 1.6 (anthracite, flameless), and even reaches 1.9 in the very dense variety of coal found in the Olonetzky government (termed thungite), which, according to the investigations of Professor Inostrantzeff, may be regarded as the extreme member of the various forms of coal.

In order to explain the formation of coal from vegetable matter, Caigniard de la Tour

boilers, and in general for all purposes of heating and burning.⁷ Russia

enclosed pieces of dried wood in a tube and heated them to the boiling point of mercury, when the wood was changed into a semi-liquid black mass from which a substance exceedingly like coal separated. In this manner some kinds of wood formed coal, which, on being heated, left caking coke, others non-caking; precisely as we find with the natural varieties of coal. Violette repeated these experiments with wood dried at 150°, and showed that when wood is decomposed in this way a gas, a watery liquid, and a residue are formed. The latter, at a temperature of 200°, has the properties of wood charcoal incompletely burnt; at 300° and higher a homogeneous mass like coal is formed, which at 340° is dense and without cavities. At 400° the residue resembles anthracite. In nature probably the decomposition was effected by heat alone in rare cases; more generally it was effected by means of water and heat, but in either case the result ought to be almost the same.

The average composition of coal compiled from many analyses, disregarding the ash, is as follows: 84 parts of carbon, 5 parts of hydrogen, 1 part of nitrogen, 8 parts of oxygen, 2 of sulphur. The medium quantity of ash is 5 p.c., but there are coals which contain a large quantity, and naturally they are not so advantageous for use as fuel. As regards the amount of water, coal in this respect is much more profitable than lignite or peat, as it does not usually contain more than 10 p.c. of water. The *anthracites* form a remarkable variety of coals, and are indeed sometimes placed in a separate category; they do not give any volatile products, or but a very small amount, as they contain but little hydrogen compared to oxygen. In the average composition of coal we saw that for 5 parts of hydrogen there were 8 parts of oxygen; therefore 4 parts by weight of the hydrogen are capable of forming hydrocarbons, because 1 part of hydrogen is necessary in order to form water with the 8 parts of oxygen. These 4 parts by weight of hydrogen can convert 48 parts of carbon into the form of benzene or similar volatile products, because 1 part of hydrogen by weight in these substances combines with 12 parts of carbon. The anthracites differ essentially from this; neglecting the ash, their average composition is as follows: 94 parts of carbon, 3 of hydrogen, and 3 of oxygen and nitrogen. According to the analyses of A. A. Voskresensky, the Grousheffsky anthracite (Don district) contains: C=93·8, H=1·7, ash=1·5. Therefore the anthracites contain but little hydrogen capable of combining with the carbon to form hydrocarbons, which burn with a flame. Anthracites are the most ancient forms of coal. The newest and least transformed, which resemble some of the brown varieties, are the dry coals (Grüner's first group). They burn with a flame like wood, and leave a coke having the appearance of lumps of coal, half their component parts being absorbed by the flame (they contain much hydrogen and oxygen). The remaining varieties of coal (2nd group, gas coal; 3rd, smithy coal; 4th, coking; and 5th, anthracite, according to Grüner) in all respects form connecting links between the dry coals and the anthracites. These coals burn with a very smoky flame, and on being heated leave *coke*, which bears the same relation to coal as charcoal does to wood. The quantity and quality of coke varies considerably with the different sorts of coal from which it is formed. In practice coals are most often distinguished by the properties and quantity of the coke which they give. In this particular the so-called bituminous coals are especially valuable, as even small coal (baked) of this kind gives by dry distillation large spongy masses of coke. If large pieces of these kinds of coal are subjected to dry distillation, they, as it were, melt, flow together, and form caking masses of coke. The best coking coals give 65 p.c. of dense caking coke. Such coal is very valuable for metallurgical purposes (*see* Note 8). Besides coke, the dry distillation of coal produces gas (*see* further, illuminating gas), coal-tar (which gives benzene, carbolic acid, naphthalene, tar for artificial asphalt, &c.), and also a watery alkaline liquid (with wood and lignites the liquid is acid from acetic acid) which contains ammonium carbonate (*see* Note 6).

⁷ In England in 1850 the output of coal was already 48 million tons, and in latter years (1884-1888) it rose to about 160 millions. Besides this the other countries con-

possesses many very rich coalfields, amongst which the Don district is most worthy of remark.⁸

During the imperfect combustion of volatile substances containing carbon and hydrogen, the hydrogen and part of the carbon first burn, and the remainder of the carbon forms soot. If oil of turpentine,

tribute 230 millions—Russia about $3\frac{1}{2}$ millions, the United States of America come next to England with an output of 75 million tons, then Germany 60 millions; France produces but little (20 millions), and takes about 5 million tons from England. Besides household purposes, coal is chiefly used as fuel for steam-engines. As every horse-power (≈ 75 kilogrammetres per second) of a steam-engine expends on the average more than 25 kilograms in 24 hours, or in a year (counting stoppages) not less than 5 tons per horse-power, and there are not less than 40 million horse-power at work in the world, the consumption of coal for motive-power is at least equal to half the whole production. For this reason coal serves as a standard for industrial development. About 15 p.c. of coal is used for the manufacture of cast iron, wrought iron, steel, and articles made of them.

⁸ The principal workable coal beds of Russia are: The Don basin (115 million poods per annum, 62 poods = 1 ton), the Polish basin (Dombrovo and others 110 million poods per annum), the Toula and Riazan beds of the Moscow basin (up to 25 million poods), the Ural basin (10 million poods), the Caucasian (Kliboul, near Kutais), the Khirjhis steppes, the smithy coal basin (Gov. of Tomsk), the Sahaline, &c. The Polish and Moscow basins do not give any coking coals. The presence of every variety of coal (from the dry coal near Lisichanena on the Donetz to the anthracites of the entire south-east basin), the great abundance of excellent metallurgical coal (coking, *see* Note 6) in the western part of the basin, its vast extent (as much as 25,000 sq. versts), the proximity of the seams to the surface (the shafts are now from 20 to 100 fathoms deep, and in England and Belgium as deep as 500 fathoms), the fertility of the soil (black earth), the proximity of the sea (about 100 versts from the Sea of Azoff) and of the rivers Donetz, Don, and Dnieper, the most abundant seams of excellent iron ore (Korsan Mogila, Krivoy rog, Soulin, &c., &c.), copper ore, mercury ore (near Nikitooka, in the Bakhmouth district of the Ekaterinoslav Gov.), and other ores, the richest probably in the whole world, the beds of rock-salt (near the stations of the Stoupka and Brianzovka), the excellent clay of all kinds (china, fire-clay), gypsum, slate, sandstone, and other *wealth of the Don coal basin*, give complete assurance of the fact that with the growth of industrial activity in Russia this bountiful land of the Cossacks and New Russia will become the centre of the most extensive productive enterprise, not only for the requirements of Russia alone, but of the whole world, because in no other place can be found such a concentration of favourable conditions. The growth of enterprise and knowledge, together with the extinction of the forests, which compels Russia to foster the production of coal, will help to bring about this desired result. The forest wealth of North Russia and the naphtha treasures of Caucasus can only contribute to its advancement, and have not the power to check that influence which the Don coal basin should have on the industrial state of Russia. England with a whole fleet of merchant vessels exports annually about 25 million tons of coal, the price of which is higher than on the Donetz (where a pood of worked coal costs less than 5 copecks on the average), where anthracites and semi-anthracites (like Cardiff or steam coal, which burns without smoke) and coking and metallurgical coals are able both in quantity and quality to satisfy the most fastidious requirements of the industry already existing and rapidly increasing everywhere. In 1850 the world's consumption and production of coal was only 5000 million poods, and now the quantity has risen to 25000 million poods. The coal mines of England and Belgium are approaching to a state of exhaustion, whilst in those of the Don basin, only at a depth of 100 fathoms 1200000 million poods of coal lies waiting to be worked.

or naphthalene or other hydrocarbons, be burned in the open air, soot is formed in large quantities, because these substances contain a large amount of carbon. Tar, pitch, and similar substances for this reason burn with a smoky flame. Thus, soot is finely-divided charcoal, separated during the imperfect combustion of the vapours and gases of carbonaceous substances rich in carbon. Specially-prepared soot (lampblack) is very largely used as a black paint, and a large quantity goes for the manufacture of printers' ink. The quantity of organic matter remaining undecomposed in the charcoal depends on the temperature to which it has been submitted. Charcoal, prepared at the lowest temperature, still contains a considerable quantity of hydrogen and oxygen—even as much as 4 p.c. of hydrogen and 20 p.c. of oxygen. Such charcoal still preserves the structure of the substance from which it was obtained. Ordinary charcoal, for instance, in which the layers of the tree are yet visible, is of this kind. On submitting it to further heating, a fresh quantity of hydrogen with carbon and oxygen (in the form of gases or volatile matter) may be separated, and the purest charcoal will be obtained on submitting it to the greatest heat.⁹ If it be required to prepare pure charcoal from soot, it is necessary first to wash it with alcohol and ether, in order to get rid of the soluble tarry products, and then submit it to a powerful heat to drive off the impurities containing hydrogen and oxygen. Charcoal, however, when completely purified does not change in appearance. Everybody knows that charcoal is a black amorphous substance, without any signs whatever of crystallisation (probably a colloid). Its porosity,¹⁰ bad conducting power for heat, capability of absorbing the

⁹ As it is difficult to separate from the charcoal the admixture of ash—that is, the earthy matter contained in the vegetable substance used for producing charcoal—in order to obtain it in its purest condition, it is necessary to use such organic substances as do not contain any ash, for example, completely refined or purified crystallised sugar, crystallised tartaric acid, &c.

¹⁰ The cavities in charcoal are the passages through which those volatile products formed at the same time as the charcoal have passed. The degree of porosity of charcoal varies considerably, and has a technical significance, in different kinds of charcoal. The most porous charcoal is very light; a cubic metre of wood charcoal weighs about 200 kilograms. Many of the properties of charcoal which depend exclusively on its porosity are shared by many other porous substances, and vary with the density of the charcoal and depend on the way it was prepared. The power which charcoal has of absorbing gases, liquids, and many substances in solution, has reference to this. The densest kind of charcoal is formed by the action of great heat on sugar. The lustrous gray dense charcoal formed in gas retorts is also of this character. This dense charcoal collects on the internal walls of the retorts subjected to great heat, and is produced by the vapours and gases separated from the heated coal in the retorts. In virtue of its density, such charcoal becomes a good conductor of the galvanic current and approaches graphite. It is principally used in galvanic batteries. Coke, or the charcoal remaining from the imperfect combustion of coal and tarry substances, is also but

luminous rays (due to its blackness and opacity), and many other qualities are familiar from everyday experience.¹¹ The specific gravity of charcoal varies from 1·4 to 1·9, and that it floats on water is due to the air contained in its pores. If charcoal be reduced to a powder and moistened with spirit, it immediately sinks in water. It is *infusible* in the furnace and even at the temperature of the oxyhydrogen flame. In the heat generated by means of a strong galvanic current, charcoal only softens, but does not completely melt, and on cooling it is found to have undergone a complete change both in properties and appearance, and is more or less transformed into graphite. The physical stability

slightly porous, brilliant, does not soil or mark paper, is dense, almost devoid of the faculty of retaining liquids and solids, and does not absorb gases. The light sorts of charcoal produced from charred wood, on the other hand, show this absorptive power in a most marked degree. This property is particularly developed in that very fine and friable charcoal prepared by heating animal substances, such as hides and bones. *The absorptive power of charcoal* with reference to gases, is similar to the condensation of gases in spongy platinum. Here evidently there is a phenomenon of the adherence of gases to a solid, precisely as liquids have the property of adhering to various solids. One volume of charcoal will absorb the following volumes of gases (charcoal is capable of absorbing an immense amount of chlorine, almost equal its own weight):—

Saussure Boxwood Charcoal.	Fayre Cocoanut Charcoal.	Heat emitted per gram of gas.
NH ₃ 90	172 vols.	494 units.
CO ₂ 35	97 "	158 "
N ₂ O 40	99 "	169 "
HCl 85	165 "	274 "

The quantity of gas absorbed by the charcoal increases with the pressure, and is approximately proportional to it. The quantity of heat given out by the absorption nearly approaches that set free on dissolving, or passing into a liquid condition.

Charcoal absorbs not only gases, but a number of other substances. For instance, alcohol, which contains disagreeably smelling fusel oil, on being mixed with charcoal or filtered through it, loses the bulk of the fusel oil. The practice of filtering substances through charcoal in order to get rid of foreign matters is often applied in chemical and manufacturing processes. Oils, spirits, various extracts, and vegetable and other solutions containing an admixture of colouring or odorous matters, and also water, are filtered through charcoal in order to purify them. The bleaching power of charcoal may be tested by using various coloured solutions—such as aniline dyes, litmus, &c. Charcoal, which has absorbed one substance to saturation, is still capable of absorbing certain other substances. The more porous charcoal is, the greater its surface, and this is the reason why animal charcoal, produced in a very finely-divided state, especially by heating bones, makes the best sort for the purposes of absorption. Bone charcoal is used in large quantities in sugar works for filtering syrups, and all saccharine solutions, in order to purify them, not only from colouring and odorous matter, but also from lime, which is mixed with the syrups in order to render them less unstable during boiling. The absorption of lime by animal charcoal depends, in all probability, in a great degree on the mineral component parts of bone charcoal.

¹¹ Charcoal is a very bad conductor of heat, and therefore forms an excellent insulator or packing to prevent the transmission of heat. A charcoal lining is often used in crucibles for heating many substances, as it does not melt and resists a far greater heat than many other substances.

of charcoal is, without doubt, allied to its chemical stability. It is evidently a substance devoid of energy, as charcoal is insoluble in all known liquids, and *at an ordinary temperature does not combine with anything*; it is an inactive substance, like nitrogen.¹² But these properties of charcoal change with a rise of temperature; thus, in contradistinction from nitrogen, charcoal, at a high temperature, combines directly with oxygen. This is well known, as charcoal burns in air. Indeed, not only does oxygen *combine with charcoal at a red heat*, but sulphur, hydrogen, and also iron and some other metals do so at a very high temperature—that is, when the molecules of the charcoal have reached a state of great instability—whilst at ordinary temperatures neither oxygen, sulphur, nor metals act on charcoal in any way. When burning in oxygen, charcoal forms carbonic anhydride, CO_2 , whilst in the vapours of sulphur carbon bisulphide, CS_2 , is formed, and wrought iron, when acted on by carbon, becomes cast iron. At the great heat obtained by passing the galvanic current through carbon electrodes, the charcoal combines with hydrogen, forming acetylene, C_2H_2 . Charcoal does not combine directly with nitrogen, but in the presence of metals and alkaline oxides, nitrogen is absorbed, forming a metallic cyanide, as, for instance, potassium cyanide, KCN . From these few direct combinations which charcoal is capable of entering into, may be derived those numerous carbonaceous compounds which enter into the composition of plants and animals, and which are obtained artificially. Certain substances containing oxygen give up a part of it to carbon at a relatively low temperature. For instance, nitric acid when boiled with charcoal gives carbonic anhydride and nitric peroxide. Sulphuric acid is reduced to sulphurous anhydride when heated with carbon. When heated to redness charcoal absorbs oxygen from a large number of the oxides. Even such oxides as those of sodium and potassium, when heated to redness, yield their oxygen to charcoal, although they do not part with it to hydrogen. Only a few of the oxides, like silica (oxide of silicon), and lime (calcium oxide), resist the reducing action of charcoal. Charcoal is capable of changing its physical condition without undergoing any alteration in its essential chemical properties—that is, it passes into *isomeric* or

¹² The unalterability of charcoal under the action of atmospheric influences, which produce changes in the majority of stony and metallic substances, is often made use of in practice. For example, charcoal is frequently strewn in boundary ditches. The surface of wood is often charred to render it durable in those places where the soil is damp, and wood itself would soon rot. The chambers (or in some works towers) through which acids pass (for example, sulphuric and hydrochloric) in order to bring them into contact with gases or liquids, are filled with charcoal or coke, because, at ordinary temperatures, it resists the action of even the most energetic acids.

allotropic forms. The two particular forms in which carbon appears are the *diamond* and *graphite*. The identity of the composition of these with charcoal is proved by burning an equal quantity of all three separately in oxygen (at a great heat), when each gives the same quantity of carbonic anhydride—namely, 12 parts of charcoal, diamond, or graphite in a pure state, yield on burning 44 parts by weight of carbonic anhydride. The physical properties present a marked contrast; the densest sorts of charcoal have a density of only 1.9, whilst the density of graphite is about 2.3, and that of the diamond 3.5. A great many other properties depend on the density, for instance, combustibility. The lighter charcoal is, the more easily it burns; graphite burns with considerable difficulty even in oxygen, and the diamond burns only in oxygen and at a very high temperature. On burning, charcoal, the diamond, and graphite develop different quantities of heat. One part by weight of wood charcoal converted by burning into carbonic anhydride develops 8080 heat units; dense charcoal separated in gas retorts develops 8050 heat units; natural graphite, 7800 heat units; and the diamond, 7770. The greater the density the less the heat evolved by the combustion of the carbon.¹³

By means of intense heat charcoal may be transformed into graphite. If a charcoal rod 4mm. in diameter and 5mm. long be enclosed in an exhausted receiver and the current from 600 Bunseu's elements, placed in parallel series of 100, be passed through it, the charcoal becomes strongly incandescent, partially volatilises, and is deposited in the form of graphite. If sugar be placed in a charcoal crucible and a powerful galvanic current passed through it, it is baked into a mass similar to graphite. If charcoal be mixed with wrought iron and heated, cast iron is formed, which absorbs as much as five per cent. of charcoal. If molten cast iron be suddenly chilled, the carbon remains in combination with the iron, forming so called white cast iron; but if the cooling proceeds slowly the greater part of the carbon separates in the form of graphite, and if such cast iron (so called grey cast iron) be dissolved in acid, the carbon remains in the form of graphite. Graphite is met with in nature, sometimes in the form of large compact masses, sometimes it permeates rocky formations like the schists or slates, and in fact is met with in those places which, in all

¹³ When subjected to pressure, charcoal loses heat, hence the densest form stands to the less dense as a solid to a liquid, or as a compound to an element. From this the conclusion might be drawn, that the molecules of graphite are more complex than those of charcoal, and those of the diamond still more so. The specific heat shows the same thing, because, as we shall see on further exposition, the complexity of a molecule leads to a diminution of the specific heat. At ordinary temperatures, the specific heat of charcoal is 0.24, graphite 0.20, the diamond 0.147.

probability, were submitted to the action of subterranean heat ¹⁴ The graphite in cast iron, and sometimes also natural graphite, occasionally appears in a crystalline form in the shape of six-sided plates, but more often it occurs as a compact amorphous mass having the characteristic properties of the familiar black-lead pencil.¹⁵

The diamond is a crystalline and transparent form of carbon. It crystallises in octahedra, dodecahedra, cubes, and other forms of the regular system.¹⁶ The efforts which have been made to produce diamonds artificially, although they have not been absolutely fruitless, have not as yet led to the production of large-sized crystals, because those means by which crystals are generally formed are inapplicable to carbon. Indeed, carbon in all its forms being insoluble and infusible does not pass into a liquid condition by means of which crystalli-

¹⁴ There are places where anthracite gradually changes into graphite, as the strata sink. I myself had the opportunity of observing this gradual transformation in the valley of Aosta, near Mont Blanc, not far from Courmayeur, near the warm mineral waters.

¹⁵ Pencils are made of graphite worked up into a homogeneous mass by disintegrating, powdering, and cleansing it from earthy impurities; the best kinds are made of completely homogeneous graphite sawn up into the requisite sticks. Graphite is found in many places. In Russia the so-called Aliberoffsky graphite is particularly renowned; it is found in the Altai mountains near the Chinese frontier; in many places in Finland and likewise on the banks of the Little Tungouska, Sidoroff also found a considerable quantity of graphite.

Graphite, like most forms of charcoal, still contains a certain quantity of hydrogen, oxygen, and ash, so that in its natural state it does not contain more than 98 p.c. of carbon.

In practice graphite is purified simply by washing it when in a finely-ground state, by which means the bulk of the earthy matter may be separated. The following process, proposed by Brodie, consists in mixing the powdered graphite with $\frac{1}{14}$ part of its weight of potassium chlorate. The mixture is then heated with twice its weight of strong sulphuric acid until no more odoriferous gases are emitted; on cooling, the mixture is thrown into water and washed; the graphite is then dried and heated to a red heat; after this it considerably shrinks in volume, and turns into a very fine powder, which is then washed. When mixed with clay, graphite is used for making crucibles and pots for melting metals. By acting on graphite several times with a mixture of potassium chlorate and nitric acid heated up to 60°, Brodie transformed it into a yellow insoluble acid substance which he called graphitic acid, $C_{11}H_4O_5$. The diamond remains unchanged when subjected to this treatment, whilst amorphous charcoal completely oxidises. Availing himself of this possibility of distinguishing graphite from the diamond or amorphous charcoal, Berthelot showed that when compounds of carbon and hydrogen are decomposed by heat, amorphous charcoal is mainly formed, whilst when compounds of carbon with chlorine, sulphur, and boron are decomposed, graphite is principally deposited.

¹⁶ Diamonds are sometimes found in the shape of small balls, and in that case it is impossible to cut them, because directly the surface is ground or broken they fall into minute pieces. Sometimes minute diamond crystals form a dense mass like sugar, and this is generally reduced to diamond powder and used for grinding. Some known varieties of the diamond are almost opaque and of a black colour. Such diamonds are as hard as the ordinary ones, and are used for polishing diamonds and other precious stones, and also for rock boring and tunnelling.

sation could take place. Diamonds have several times been successfully produced in the shape of minute microscopic crystals having the appearance of a black powder, but when viewed under the microscope they appeared transparent, and possessed that hardness which is the peculiar characteristic of the diamond. This diamond powder is deposited on the negative electrode, when a weak galvanic current is passed through liquid chloride of carbon.¹⁷

Judging from the fact that carbon forms a number of gaseous (carbonic oxide, carbonic anhydride, methane, ethylene, acetylene, &c.) and volatile (such are, for instance, many hydrocarbons and their most simple derivatives) substances, and also because the atomic weight of carbon, $C=12$, approaches that of nitrogen, $N=14$, and that of oxygen, $O=16$, and the compounds CO (carbonic oxide) and N_2C_2 (cyanogen) are gases, it must be argued that if carbon formed the molecule C_2 like N_2 and O_2 , it would be a gas. And as through polymerism, or the mutual combination of molecules (as O_2 passes into O_3 or NO_2 into N_2O_4) the temperatures of ebullition and fusion rise (which is particularly clearly proved with the hydrocarbons of the C_nH_{2n} series), it ought to be considered *that the molecules of charcoal, graphite, and the diamond are very complex*, seeing that they are not soluble, not volatile, and not fusible. The aptitude which the atoms of carbon show for combining together and forming complex molecules appears in all carbon compounds. Among the volatile compounds of carbon many are well known, the molecules of which contain $C_5 \dots C_{10} \dots C_{20} \dots C_{30}$, &c., in general C_n , where n may be very large, and in none of the other elements is this faculty of complexity so developed as in carbon.¹⁸ Up

¹⁷ Hannay, in 1880, obtained diamonds by heating a mixture of heavy liquid hydrocarbons (paraffin oils) with magnesium in a thick iron tube. This investigation was, however, not repeated. Diamonds are found in a particular dense rock, known by the name of itacolumbite, and are dug out of the *débris* produced by the destruction of the itacolumbite by water. When the *débris* is washed the diamonds remain behind; they are principally found in Brazil, in the provinces of Rio and Bahia, and at the Cape of Good Hope. The *débris* gives the black or amorphous diamond, carbonado, and the ordinary colourless or yellow translucent diamond. As the diamond possesses a very marked cleavage, the first operation consists in splitting it, and then roughly and finely polishing it with diamond powder. It is very remarkable that Professors P. A. Latchinoff and Eroféeff found (1887) diamond powder in a meteoric stone which fell in the government of Penza, in the district of Krasnoslobodsk, near the settlement of Novo Urei (Sept. 10, 1886). Up to that time charcoal and graphite (a special variety, cliftonite) had been found in meteorites and the diamond only conjectured to be therein. The Novo Urei meteorite was composed of siliceous matter and metallic iron (with nickel), like many other meteorites.

¹⁸ The existence of a molecule S_8 is known, and it must be held that this accounts for the formation of hydrogen persulphide H_2S_5 . Phosphorus appears in the molecule P_4 and gives P_4H_2 . When expounding the data on specific heat we shall have occasion to return to the question of the complexity of the carbon molecule.

to the present time there are no grounds for determining the degree of polymerism of the charcoal, graphite, or diamond molecules, and it can only be supposed that they contain C_n , where n is a large quantity. Therefore charcoal and those complex non-volatile organic substances which represent the gradual transitions to charcoal¹⁹ and which form the principal masses of the organisms, contain a store or accumulation of internal power in the form of the energy binding the atoms into complex molecules. When charcoal or complex compounds of carbon burn, the energy of the carbon and oxygen is turned into heat, and this fact is taken advantage of at every turn for the generation of heat from fuel.²⁰

No other two elements are capable of combining together in such variety as carbon and hydrogen. The hydrocarbons of the C_nH_{2m} series in many cases widely differ from each other, although they have some properties in common. All hydrocarbons, whether gaseous, liquid, or solid, are combustible substances sparingly soluble or insoluble in water. The liquefied gaseous hydrocarbons, also those which are liquid at ordinary temperatures, and those solid hydrocarbons which have been liquefied by fusion, have the appearance and property of oily liquids, more or less viscid or fluid.²¹ The solid hydrocarbons

¹⁹ The hydrocarbons, poor in hydrogen (far from the limit) and containing many atoms of carbon, like chrysene and carbopetrocene, &c., $C_nH_{2(n-m)}$ are solids, and less fusible as n and m increase. They present a marked approach to the properties of the diamond. And in proportion to the diminution of the water in the carbohydrates $C_nH_{2m}O_m$ —for example, in the humic compounds (Note 5)—the transition of complex organic substances to charcoal is very evident. That residue resembling charcoal and graphite which is obtained by the separation (by means of copper sulphate and sodium chloride) of iron from white cast-iron containing carbon, chemically combined with the iron, also seems, especially after the researches of G. A. Zaboudsky, to be a complex substance containing $C_{12}H_6O_5$. The endeavours which have been directed towards determining the measure of complexity of the molecules of charcoal, graphite, and the diamond will probably at some period lead to the solution of this problem, and will most likely prove that the various forms of charcoal, graphite, and the diamond contain molecules of different and very considerable complexity. The constancy of the grouping of benzene, C_6H_6 , and the wide diffusion and facility of formation of the carbohydrates, containing C_6 (for example, cellulose, $C_6H_{10}O_5$, glucose, $C_6H_{12}O_6$), give reason for thinking that the group C_6 is the first and simplest of those possible to free carbon, and it may be hoped that some time or other it may be possible to get charcoal in this group. Perhaps in the diamond there may be found such a relation between the atoms as in the benzene group, and in charcoal such as in the carbohydrates.

²⁰ When charcoal burns, the complex molecule C_n is resolved into the simple molecules nCO_2 , and therefore part of the heat—probably no small amount—is expended in the destruction of the complex molecule C_n . Perhaps by burning the most complex substances, which are the poorest as regards hydrogen, it may be possible to form an idea of the work required to split up C_n into separate atoms.

²¹ The viscosity, or the degree of mobility, of liquids is determined by their internal friction. It is estimated by passing the liquids through narrow (capillary) tubes, the mobile liquids passing through with greater facility and speed than the viscid ones. The

more or less resemble wax in their properties, although ordinary oils and wax generally contain oxygen in addition to carbon and hydrogen, but in relatively small proportion. There are also a few hydrocarbons which have the appearance of tar—as, for instance, metacinnamene and gutta-percha. Those liquid hydrocarbons which boil at a high temperature are like oils, and those which have a low boiling point resemble ether, whilst the gaseous hydrocarbons in many of their properties are akin to hydrogen. All this tends to show that, in hydrocarbons physically considered, the properties of solid non-volatile charcoal are strongly modified and hidden, whilst those of the hydrogen predominate. All hydrocarbons are neutral substances (neither basic nor acid), but under certain conditions they enter into peculiar reactions. It has been seen in those hydrogen compounds which have been already considered (water, nitric acid, ammonia) that the hydrogen in almost all cases enters into reaction, being displaced by metals. The hydrogen of the hydrocarbons, it may be said, has no metallic character—that is to say, it is not directly ²² displaced by metals, even by such as sodium and

viscosity varies with the temperature and nature of the liquids, and, in the case of solutions, changes with the amount of the substance dissolved, but is not proportional to it. So that, for example, with alcohol at 20° the viscosity will be 69, and for a 50 p.c. solution 100, the viscosity of water being taken as 100. The volume of the liquid which passes through by experiment (Poiseuille) and theory (Stokes) is proportional to the time, the pressure, and the fourth power of the diameter of the (capillary) tube, and inversely proportional to the length of the tube; this renders it possible to form comparative estimates of the coefficients of internal friction and viscosity.

As the complexity of the molecules of hydrocarbons and their derivatives increases by the addition of carbon (or CH_2), so does the degree of viscosity also rise. The extensive series of investigations referring to this subject still await the necessary generalisation. That connection which (already partly observed) ought to exist between the viscosity and the other physical and chemical properties, forces us to conclude that the magnitude of internal friction plays an important part in molecular mechanics. In investigating organic compounds and solutions, similar researches ought to stand foremost. Many observations have already been made, but not much has yet been done with them; the bare facts and some mechanical data exist, but their relation to molecular mechanics has not been cleared up in the requisite degree. It has already been seen from existing data that the viscosity at the temperature of the absolute boiling point becomes as small as in gases.

²² In a number of hydrocarbons and their derivatives such a substitution of metals for the hydrogen may be arrived at by indirect means. The property shown by acetylene, C_2H_2 , and its analogues of forming metallic derivatives is in this respect particularly characteristic. Judging from the fact that carbon is an acid element (that is, gives an acid anhydride with oxygen), but comparatively slightly acid (because carbonic acid is not at all an energetic acid; compounds of chlorine and carbon, even CCl_4 , are not decomposed by water as is the case with phosphorus chloride, and even silicic chloride or boric chloride, although they correspond with acids of but little energy), one might expect to find in the hydrogen of hydrocarbons this faculty for being substituted by metals. The metallic compounds which correspond with hydrocarbons are known under the name of organo-metallic compounds. Such, for instance, is zinc ethyl, $\text{Zn}(\text{C}_2\text{H}_5)_2$, which corresponds with ethyl hydride or ethane, C_2H_6 , where two atoms of hydrogen have been exchanged for one of zinc.

potassium. On the application of more or less heat, all hydrocarbons decompose,²³ forming charcoal and hydrogen. The majority of hydrocarbons do not combine with the oxygen of the air or oxidise at ordinary temperatures, but under the action of nitric acid and many other oxidising substances most of them are subject to oxidation, in which either a portion of the hydrogen and carbon is separated, or the oxygen enters into combination, or else the elements of hydrogen peroxide enter into combination with the hydrocarbon.²⁴ When heated in air, hydrocarbons burn, and, according to the amount of carbon they contain, their combustion is attended with a separation of soot—that is, finely-divided charcoal—which imparts great brilliancy to the flame, and on this account many of them are used for the purposes of illumination—as, for instance, kerosene, coal gas, oil of turpentine. As hydrocarbons contain reducing elements (that is, those capable of combining with oxygen) they often act as reducing agents—as, for instance, when heated with oxide of copper, they burn, forming carbonic anhydride and water, and leave metallic copper. According to Gerhardt, all hydrocarbons contain an even number of hydrogen atoms. Therefore, the general formula for all hydrocarbons is C_nH_{2m} where n and m are whole numbers. This fact is known as *the law of even numbers*. Hence, the simplest possible hydrocarbons ought to be: CH_2 , CH_4 , CH_6 . . . C_2H_2 , C_2H_4 , C_2H_6 , C_2H_8 . . . but all of them are not in existence, as they are subject to certain limitations.

Some of the hydrocarbons are capable of combination, whilst others do not show that power. Those which contain less hydrogen belong to the former category, and those which, for a given quantity of carbon, contain the maximum amount of hydrogen belong to the latter. The composition of those last mentioned is expressed by the general formula C_nH_{2n} . These so-called *saturated hydrocarbons* are incapable of combination.²⁵ Judging from this, the hydrocarbons CH_6 , C_2H_8 ,

²³ Gaseous and volatile hydrocarbons decompose, when passed through a heated tube. When hydrocarbons are decomposed by heating, the primary products are generally other more stable hydrocarbons, among which are acetylene, C_2H_2 , benzene, C_6H_6 , naphthalene, $C_{10}H_8$, &c.

²⁴ Wagner (1888) showed that when unsaturated hydrocarbons are shaken with a weak (1 p.c.) solution of potassium permanganate, $KMnO_4$, at ordinary temperatures, they form glycols—for example, C_2H_4 yields $C_2H_6O_2$.

²⁵ My article on this subject appeared in the journal of the St. Petersburg Academy of Sciences in 1861. Up to that time, although many additive combinations with hydrocarbons and their derivatives were known, they had not been generalised, and were even continually quoted as cases of substitution. Thus the combination of ethylene, C_2H_4 , with chlorine, Cl_2 , was often regarded as a formation of the products of the substitution of C_2H_5Cl and HCl , which it was supposed were held together as the water of crystallisation is in salts. Even earlier than this (1857, *Journal of the Petroffsky Academy*) I considered similar cases as true compounds. In general, according to the law of limits,

C_3H_{10} , &c. . . do not exist. Those containing the maximum amount of hydrogen will be represented by CH_4 ($n=1$, $2n+2=4$), C_2H_6 ($n=2$), C_3H_8 ($n=3$), C_4H_{10} , &c. This may be termed *the law of limits*. Placing this in juxtaposition with the law of even numbers, it is easy to perceive that the possible hydrocarbons can be ranged in series, the terms of which may be expressed by the general formulæ C_nH_{2n+2} , C_nH_{2n} , C_nH_{2n-2} , &c. . . Those hydrocarbons which belong to any one of the series expressible by a general formula are said to be *homologous* with one another. Thus, the hydrocarbons CH_4 , C_2H_6 , C_3H_8 , C_4H_{10} , &c. . . are members of the limiting (saturated) homologous series C_nH_{2n+2} . That is, the difference between the members of the series is CH_2 .²⁶ Not only the composition, but also the properties, of the members of a series tend to classification in one group. For instance, the members of the series C_nH_{2n+2} are not capable of forming additive compounds, whilst those of the series C_nH_{2n} are capable of combining with chlorine, sulphuric anhydride, &c.; and the members of the C_nH_{2n-6} group, belonging to the coal tar series, are acted on by nitric acid, and have other properties in common. The physical properties of the members of a given homologous series vary in such a manner, the boiling point generally rises and the internal friction increases as n increases²⁷—that is, with an increase in the atomic weight; the specific gravity also successively changes as n becomes greater.²⁸

an unsaturated hydrocarbon, or its derivative, on combining with xX_2 , gives a substance which is saturated or else approaching the limit. The investigations of Frankland with many organo-metallic compounds clearly showed the limit in the case of metallic compounds, which we shall constantly refer to later on.

²⁶ The conception of homology has been applied by Gerhardt to all organic compounds in his classical work, 'Traité de Chimie Organique,' finished in 1855 (4 vols.), where he divided all organic compounds into *fatty* and *aromatic*, which is in principle still adhered to at the present time, although the latter are more often called benzene derivatives, on account of the fact that Kekulé, in his beautiful investigations on the structure of aromatic compounds, showed the link which unites them all with the 'nucleus' benzene, C_6H_6 .

²⁷ This is always true for hydrocarbons, but for derivatives of the lower homologues it is sometimes different; for instance, in the series of saturated alcohols $C_nH_{2n+1}(OH)$, when $n=0$, we obtain water, $H(OH)$, which boils at 100° , and whose specific gravity at $15^\circ=0.9992$; when $n=1$, wood spirit $CH_3(OH)$, which boils at 66° , and at 15° has a specific gravity = 0.7964 ; when $n=2$, ordinary alcohol $C_2H_5(OH)$, boiling at 78° , specific gravity at $15^\circ=0.7936$, and with further increase of CH_2 the specific gravity increases. For the glycols $C_nH_{2n}(OH)_2$ the phenomenon of a similar kind is still more striking; at first the temperature of the boiling point and the density increase, and then for higher (more complex) members of the series diminish. The reason for this phenomenon, it is evident, must be sought for in the influence and properties of water, and that strong affinity which, acting between hydrogen and oxygen, determines many of the exceptional properties of water (Chap. I.).

²⁸ As, for example, in the saturated series of hydrocarbons C_nH_{2n+2} , the lowest member ($n=0$) must be taken as hydrogen H_2 , a gas which (*t.c.* below -190°) is liquefied with great difficulty, and when in a liquid state has doubtless a very small

Many of the hydrocarbons which are met with in nature are the products of organisms, and do not belong to the mineral kingdom. A still greater number are produced artificially. These are formed by what is termed the combination of residues. For instance, if a mixture of the vapours of hydrogen sulphide and carbon bisulphide be passed through a tube in which copper is heated, this latter absorbs the sulphur from both the compounds, and the liberated carbon and hydrogen combine to form a hydrocarbon, methane. If a mixture of bromobenzene, C_6H_5Br , and ethyl bromide, C_2H_5Br , be heated with metallic sodium, the sodium combines with the bromine of both compounds, forming sodium bromide. From the first combination the group C_6H_5 remains, and from the second C_2H_5 . Having an odd number of hydrogen atoms, they in virtue of the law of even numbers cannot exist alone, therefore they combine together forming the compound $C_6H_5.C_2H_5$ or C_8H_{10} (ethylbenzene). Hydrocarbons are also produced by the breaking up of more complex organic or hydrocarbon compounds, especially by heating—that is, by dry distillation. For instance, gum-benzoin contains an acid called benzoic acid, $C_7H_6O_2$, the vapours of which, when passed through a heated tube, split up into carbonic anhydride, CO_2 , and benzene, C_6H_6 . Carbon and hydrogen only unite directly in one degree of combination—namely, to form acetylene, having the composition C_2H_2 , which, as compared with other hydrocarbons, exhibits a very great constancy at a high temperature.²⁹

density. Where $n=1, 2, 3$, the hydrocarbons CH_4 , C_2H_6 , C_3H_8 are gases, more and more readily liquefiable. The temperature of the absolute boiling point for $CH_4 = -100^\circ$, and for ethane C_2H_6 , and in the higher members it rises. The hydrocarbon C_4H_{10} , already liquefies about 0° . C_5H_{12} boils at from $+9^\circ$ (Livoff) to 37° , C_6H_{14} from 58° to 78° , &c. The specific gravities in a liquid state at 15° are :—

C_5H_{12}	C_6H_{14}	C_7H_{16}	$C_{10}H_{22}$	$C_{16}H_{34}$
0.63	0.66	0.70	0.75	0.85

²⁹ If, at the ordinary temperature (assuming therefore that the water formed will be in a liquid state), a gram molecule (26 grams) of acetylene, C_2H_2 , be burnt, 310 thousand calories will be emitted (Thomsen), and as 12 grams of charcoal produce 97 thousand calories, and 2 grams of hydrogen 69 thousand calories, therefore, if the hydrogen and carbon of the acetylene were burnt there would be only $2 \times 97 + 69$, or 263 thousand calories produced. It is evident, then, that acetylene in its formation absorbs $310 - 263$, or 47 thousand calories—that is, the reaction of charcoal and hydrogen is endothermal and the product is in this respect a substance resembling nitrous oxide, hydrogen peroxide, &c. Such reasoning is, however, open to certain defects of one kind or another, especially when a reaction, which can really only take place at a high temperature, is supposed to be effected at ordinary temperatures or *vice versa*. Calculations cannot be made for high temperatures, on account of insufficient evidence as to specific heat.

For considerations referring to the combustion of carbon compounds, we will first enumerate the quantity of heat separated by the combustion of definite chemical carbon compounds, and then a few figures touching the kinds of fuel applied in a practical way.

There is one known substance among the saturated hydrocarbons composed of 1 atom of carbon and 4 atoms of hydrogen; this is a com-

I. For molecular quantities of combustion, the following amounts of heat are given out (when gaseous hydrocarbon and liquid water are formed), according to the data of Thomsen: (1) for gaseous C_nH_{2n+2} : $52.8 + 158.8n$ thousand calories; (2) for C_nH_{2n} : $17.7 + 158.1n$ thousand calories; (3) according to Stohmann (1888) for liquid saturated alcohols, $C_nH_{2n+2}O$: $11.8 + 156.3n$, and as the latent heat of evaporation = about $8.2 + 0.6n$, in a gaseous state, $20.0 + 156.9n$; (4) for monobasic saturated liquid acids, $C_nH_{2n}O_2$: $95.3 + 154.3n$, and as their latent heat of evaporation is about $5.0 + 1.2n$, in a gaseous form, about $90 + 155n$; (5) for solid saturated bibasic acids, $C_nH_{2n-2}O_4$: $253.8 + 152.6n$, if they are expressed as $C_nH_{2n}C_2H_2O_4$, then $51.4 + 152.6n$; (6) for benzene and its liquid homologues (still according to Stohmann) C_nH_{2n-6} : $158.6 + 156.3n$, and in a gaseous form about $155 + 157n$; (7) for the gaseous homologues of acetylene, C_nH_{2n-2} , (according to Thomsen), $5 + 157n$. It is evident from the preceding figures that the group CH_2 , or the substitution of CH_2 for H, on burning gives out from 152 to 159 thousand calories. This is less than that given out by $C + H_2$, which is $97 + 69$ or 166 thousand; the reason of this difference (it would be still greater if charcoal were gaseous) is the amount of heat separated during the formation of CH_2 . The heat of combustion of the following solids (determined by Stohmann) is expressed, not in terms of the molecular weight of the substance, but per unit of weight: $C_6H_{10}O_5$, cellulose, 4146; starch, 4123; dextrose, $C_6H_{12}O_6$, 3692; cane sugar, $C_{12}H_{22}O_{11}$, 3866; naphthalene, $C_{10}H_8$, 9621; urea, CN_2H_4O , 2465; white of eggs, 5579; dry rye bread, 4421; wheaten bread, 4802; tallow, 9365; butter, 9192; linseed oil, 9323.

II. The number of units of heat given out during the complete combustion and cooling of the following ordinary kinds of fuel in their usual state of dryness and purity are:—(1) for wood charcoal, anthracite, semi-anthracite, tarry coal and coke, from 7200 to 8200; (2) for dry, long flaming coals, and the best brown coals, from 6200 to 6800; (3) for perfectly dry wood, 3500; hardly dry, 2500; (4) perfectly dry peat, best kind, 4500; compressed and dried, 3000; (5) petroleum refuse and similar liquid hydrocarbons, about 11000; (6) illuminating gas of the ordinary composition (about 45 vols. H_2 , 40 vols. CH_4 , 5 vols. CO , and 5 vols. N_2), about 12000; (7) generator gas (*see next Chap.*), containing 2 vols. carbonic anhydride, 30 vols. carbonic oxide, and 68 vols. nitrogen for one part by weight of the whole carbon burnt, 5300, and for one part by weight of the gas, 910, units of heat; and (8) water gas (*see next Chap.*) containing 4 vols. carbonic anhydride, 8 vols. N_2 , 24 vols. carbonic oxide, and 46 vols. H_2 , for one part by weight of the carbon consumed in the generator 10900, and for one part by weight of the gas, 3600, units of heat. In these figures, as in all calorimetric observations, the water produced by the combustion of the fuel is supposed to be liquid. As regards the temperature reached by the fuel, it is important to remark that for solid fuel it is indispensable to admit (to ensure complete combustion) twice the amount of air required, but liquid, pulverised fuel, and especially gaseous fuel, does not require an excess of air; therefore, a kilogram of charcoal, giving 8000 units of heat, requires about 24 kilograms of air (3 kilograms of air per 1000 calories) and a kilogram of generator gas requires only 0.77 kilogram of air (0.85 kilo. of air per 1000 calories), 1 kilogram of water gas about 4.5 of air (1.25 kilos. of air per 1000 calories).

III. As one of the most important and extensive applications of combustible matter is the formation of steam and conversion of it into work, we will take as an example the calculation for a boiler burning *per hour* (=3600 seconds) 100 kilograms of anthracite, giving out 8000 units of heat, and containing 90 p.c. C, 3 p.c. H, 3 p.c. O, and 4 p.c. of ash and nitrogen. For the combustion of 100 kilos. of such coal, giving 800 thousand units of heat, about 2400 kilos. (counting double the amount) of air will be required, therefore in the smoke there will be 2500 kilos., and as the specific heat of the products of combustion is about 0.25, so, taking the temperature of the smoke passing from underneath the boiler, $t = 200^\circ$ (higher than the temperature of the air), the smoke will carry off 125 thousand units of heat, and 187.5 units of heat per second will be communi-

pound containing the highest percentage of hydrogen (CH_4 contains 25 per cent. of hydrogen), and at the same time it is the only hydrocarbon whose molecule contains a single atom of carbon. This saturated hydrocarbon, CH_4 , is called *marsh-gas* or *methane*. If vegetable or animal refuse suffers decomposition in a space where the air has not free access, or no access at all, then the decomposition is accompanied with the formation of marsh gas, and this either at an ordinary temperature, or at a comparatively much higher one. On this account *plants*, when decomposing under water in *marshes*, give out this gas. It is well known that if the mud in bogs be stirred up, the act is accompanied with the evolution of a large quantity of gas bubbles; these may, although slowly, also separate of their own accord. The gas which is evolved consists principally of marsh-gas.³⁰ If wood, coal, or many other vegetable or animal substances are decomposed by the *action of heat* without access of air—that is, are subjected to dry distillation—they, in addition to many other gaseous products of decomposition (carbonic anhydride, hydrogen, and various other substances), evolve a great deal of methane. Generally, the gas which is used for lighting purposes is obtained by this means, and, therefore, always contains marsh gas, mixed with hydrogen and other vapours and gases, although it is subsequently purified from many of them.³¹ As the

cated to the boiler, and to the surrounding air. Subtracting 27.5 units of heat for radiation, we have 160 units of heat per second communicated to the water. If the pressure in the boiler be 5 atmospheres, $t=152^\circ$ (page 54), and the temperature of the feed water 12° , then (the heat of warming and evaporation of 640 units of heat, see page 53) 0.25 kilo. of steam at 150° per second (900 kilos. per hour) will be produced. If this steam does its work without waste of any kind, and be condensed in the condenser at 50° , then, according to the second law of the mechanical theory of heat, not more in any case than $160(150-50)/(150+273)$ or 37.8 units of heat, will be converted into work, which (according to the first law of the mechanical theory of heat) will equal 424×37.8 or 15927 kilogrammetres of work per second, or 212 horse-power (one horse power = 75 kilogrammetres per second).

But as at least 35 p.c. (in the best machines) is lost in inevitable loss of heat and through friction, only about 140 horse-power can be obtained with the above-mentioned quantity of fuel in a steam-engine of excellent construction. Generally, 1 kilo. of coal per horse-power per hour is consumed in the best steam-engines (with expansion and condensation). Only in gas engines at present does the work of the fuel approach the theoretical limit.

³⁰ It is easy to collect the gas which is evolved in marshy places if a glass bottle be inverted in the water and a funnel put into it (in water); if the mud of the bottom be now agitated, the bubbles which rise may be easily caught in the funnel.

³¹ Illuminating gas is generally prepared by heating gas coal (see Note 6) in oval cylindrical horizontal cast-iron or clay retorts. Several such retorts *BB* (fig. 58) are disposed in the furnace *A*, and heated together. When the retorts are heated to a red heat, lumps of coal are thrown into them, and they are then closed with a closely-fitting cover. The illustration shows the furnace, with five retorts. Coke (see Note 1, dry distillation) remains in the retorts, and the volatile products in the form of vapours and gases travel along the pipes *d*, rising from each retort. These pipes branch above the stove, and are hermetically sealed into the receiver *f* (hydraulic main) placed above




FIG. 58. General view of gas works. *B*, retorts; *f*, hydraulic main; *H* and *I*, tar well; *i*, condensers; *L*, purifiers; *P*, gasholder.

decomposition of the organic matter, which forms coal, is still going on underground, the evolution of large quantities of marsh gas frequently

the furnace. Those products of the dry distillation which most easily pass from the gaseous into the liquid and solid states collect in the hydraulic main. From the hydraulic main the vapours and gases travel along the pipe *g* and the series of vertical pipes *j* (which are sometimes cooled by water trickling over the surface), where the vapours and gases cool from the contact of the colder surface, and a fresh quantity of vapour condenses. The condensed liquids pass from the pipes *g* and *j* and into the troughs *H*. These troughs always contain liquid at a constant level (the excess flowing away), so that the gas cannot escape, and thus forms, as it is termed, a hydraulic joint. In the state in which it leaves the condensers, the gas consists principally of the following vapours and gases: (1) vapour of water, (2) ammonium carbonate, (3) liquid hydrocarbons, (4) hydrogen sulphide, H_2S , (5) carbonic anhydride, CO_2 , (6) carbonic oxide, CO , (7) sulphurous anhydride, SO_2 , but a great part of the illuminating gas consists of (8) hydrogen, (9) marsh gas, (10) olefiant gas, C_2H_4 , and other gaseous hydrocarbons. The hydrocarbons (3, 9, and 10), the hydrogen, and carbonic oxide are capable of combustion, and are useful component parts, but the carbonic anhydride, the hydrogen sulphide, and sulphurous anhydride, as well as the vapours of ammonium carbonate, form an injurious admixture, because they do not burn (CO_2 , SO_2) and lower the temperature and brilliancy of the flame, or else, although they are capable of burning, they give out during combustion sulphurous anhydride (for example, H_2S , CS_2 , and others), which has a disagreeable smell, is injurious when inhaled, and spoils many surrounding objects. In order to separate the injurious products, the gas is washed with water, a cylinder (not shown in the illustration) filled with coke continually moistened with water serving for this purpose. The water coming into contact with the gas dissolves the ammonium carbonate; hydrogen sulphide, carbonic anhydride, and sulphurous anhydride, being only partly soluble in water, have to be got rid of by a special means. For this purpose the gas is passed through moist lime or another alkaline liquid, as the above-mentioned gases have acid properties and are therefore retained by the alkali. In the case of lime, calcium carbonate, sulphite and sulphide, all solid substances, are formed. It is necessary to renew the purifying material, as its absorbing power ceases. A mixture of lime and sulphate of iron, FeSO_4 , acts still better, because the latter, with lime, $\text{Ca}(\text{HO})_2$, forms ferrous hydroxide, $\text{Fe}(\text{HO})_2$, and gypsum, CaSO_4 . The suboxide (partly turning into oxide) of iron absorbs H_2S , forming FeS and H_2O , and the gypsum retains the remainder of the ammonia, the excess of lime absorbing carbonic anhydride and sulphuric anhydride. [In English works a native hydrated ferric hydroxide is used for removing hydrogen sulphide.] This purification of the gas takes place in the apparatus *L*, where the gas passes through netting *m*, covered with sawdust mixed with lime and sulphate of iron. It is necessary to remark that in the manufacture of gas it is indispensable to draw off the vapours from the retorts, so that they should not remain there long (otherwise the hydrocarbons would in a considerable degree be resolved into charcoal and hydrogen), and also to avoid a great pressure of gas in the apparatus, otherwise a quantity of gas would escape at all cracks such as must inevitably exist in such a complicated arrangement. For this purpose there are special pumps (exhausters) so regulated that they only pump off the quantity of gas formed (the pump is not shown in the illustration). The purified gas passes through the pipe *n* into the gasometer (gasholder) *P*, a dome made of iron plate. The edges of the dome dip into water poured into a ring-shaped channel *g*, in which the sides of the dome rise and fall. The gas is collected in this holder, and distributed to its destination by pipes communicating with the pipe *o*, issuing from the dome. The pressure of the dome on the gas enables it, on issuing from a long pipe, to penetrate through the small aperture of the burner. 100 kilograms of coal give about 20 to 30 cubic metres of gas, having a density from four to nine times greater than that of hydrogen. A cubic metre (1000 litres) of hydrogen weighs about 87 grams; therefore 100 kilograms of coal give about 18 kilograms of gas, or about one-sixth of its weight. Illuminating gas is

occurs in coal-mines.⁵² When mixed with air it forms an explosive mixture, which forms one of the great dangers of coal mining, as subterranean work has always to be carried on by lamp-light. This danger is, however, overcome by the use of Humphry Davy's safety

generally lighter than marsh gas, as it contains a considerable amount of hydrogen, and is only heavier than marsh gas when it contains much of the heavier hydrocarbons. Thus olefiant gas, C_2H_4 , is fourteen times, and the vapours of benzene thirty-nine times, heavier than hydrogen, and illuminating gas sometimes contains 15 p.c. of its volume of them. The brilliancy of the flame of the gas increases with the quantity of olefiant gas and similar heavy hydrocarbons, as it then contains more carbon for a given volume and a greater number of carbon particles are separated. Gas usually contains from 35 to 60 p.c. of its volume of marsh gas, from 30 to 50 p.c. of hydrogen, from 3 to 5 p.c. of carbonic oxide, from 2 to 10 p.c. heavy hydrocarbons, and from 3 to 10 p.c. of nitrogen. Wood gives almost the same sort of gas as coal, and almost the same quantity, but the wood gas contains a great deal of carbonic anhydride, and the vapours of water and tarry liquids, but on the other hand there is almost complete absence of sulphur compounds. Tar, oils, naphtha, and such like materials furnish a large quantity of good illuminating gas. An ordinary burner of 8 to 12 candle power burns 5 to 6 cubic feet of coal gas per hour, but only 1 cubic foot of naphtha gas. One pood (36 lbs. Eng.) of naphtha gives 500 cubic feet of gas—that is, one kilogram of naphtha produces about one cubic metre of gas. The formation of combustible gas by heating coal was discovered in the beginning of the last century, but only put into practice towards the end by Le-Bon in France and Murdoch in England. In England, Murdoch, together with the renowned Watt, built the first gas works in 1805.

It is worthy of remark that 1 candle-power per hour entails a consumption of not less than 7 grams of coal gas, or 1½ grams of naphtha gas, whilst lamps consume but 4 grams of kerosene per candle-power, and ordinary-sized candles burn 6–9 grams of stearin, wax, or paraffin, or 13 grams of tallow per hour. In practice illuminating gas is not only used for lighting (electricity and kerosene are cheaper in Russia), but also as the motive-power for gas engines (*see* p. 172), which consume about half a cubic metre per horse-power per hour; gas is also used in laboratories for heating purposes. When it is necessary to concentrate the heat, either the ordinary blowpipe (fig. 59) is applied, placing the end in the flame and blowing through the mouthpiece; or, in other forms, gas is passed through the blowpipe; when a large, hot, smokeless flame is required for heating crucibles or glass-blowing, a foot-blower is used. High temperatures, which are often required for laboratory and manufacturing purposes, are most easily attained by the use of gaseous fuel (illuminating gas, generator gas, and water gas, which will be treated of in the following chapter) because complete combustion may be effected without an excess of air. It is evident that for obtaining high temperatures means must be taken to diminish the loss of heat by radiation.

⁵² The gas which is set free in coal mines contains a good deal of nitrogen, some carbonic anhydride, and a large quantity of marsh gas. The best means of avoiding an explosion consists in efficient ventilation. It is best to light coal mines with electric lamps.



FIG. 59.—Blowpipe. Air is blown in at the trumpet-shaped mouthpiece, and escapes in fine stream from the platinum jet placed at the extremity of the side tube.

lamp.³³ Sir Humphry Davy observed that on introducing a piece of wire gauze into a flame, it absorbs so much heat that combustion does not proceed beyond it (the unburnt gases which pass through it may be kindled on the other side). In accordance with this, the flame of the Davy lamp is surrounded with a thick glass (as shown in the drawing), and has no communication whatever with the explosive mixture except through a wire gauze which prevents it igniting the mixture of the marsh-gas issuing from the coal with air. In some places, particularly in those districts where petroleum is found—as, for instance, near Baku, where a temple of the Indian fire-worshippers was built, and in Pennsylvania, and other places—marsh-gas in abundance issues from the earth, and it is used, like coal gas, for the purposes of lighting and warming.³⁴ Fairly pure marsh gas³⁵ may be obtained by heating a mixture of an acetate with an alkali. Acetic acid, $C_2H_4O_2$, on being heated is decomposed into marsh gas and carbonic anhydride, $C_2H_4O_2 = CH_4 + CO_2$.

An alkali—for instance, $NaHO$ —gives with acetic acid a salt, $C_2H_3NaO_2$, and on decomposition with excess of alkali, this retains carbonic anhydride, and forms a carbonate, Na_2CO_3 , and marsh gas is formed.



Marsh gas is difficult to liquefy; it is almost insoluble in water, and is without taste or smell. The most important point in connection with its chemical reactions is that it does not combine directly with





FIG. 60.—Davy safety-lamp.

³³ The Davy lamp is used for lighting coal and other mines where combustible gas is found. The wick of the lamp is enclosed in a thick glass cylinder, which is firmly held in a metallic holder. Over this a metallic cylinder and the wire gauze are placed. The products of combustion pass through the gauze, and the air enters through the space between the cylinder and the wire gauze. To ensure greater safety the lamp cannot be opened without extinguishing the flame.

³⁴ In Pennsylvania (beyond the Alleghany mountains) many of the shafts sunk for petroleum only emitted gas, but many useful applications for it were found, and it was conducted in metallic pipes to works hundreds of miles distant, principally for metallurgical purposes.

³⁵ The purest gas is prepared by mixing the liquid substance called zinc methyl, $Zn(CH_3)_2$, with water, when the following reaction occurs:



anything, whilst the other hydrocarbons which contain less hydrogen than expressed by the formula C_nH_{2n+2} are capable of combining with hydrogen, chlorine, certain acids, &c.

Marsh gas is the only hydrocarbon which contains one atom of carbon in its molecule,³⁶ and stands, therefore, to that element in the same relation as water does to oxygen or ammonia to nitrogen. The multitude of hydrocarbons which carbon has the power of forming must be derived from this unique and simplest hydrocarbon. By arranging the molecules (and consequently equal volumes) in the following order —




it is evident that hydrogen and chlorine are univalent, oxygen and sulphur bivalent, nitrogen and phosphorus trivalent, carbon and silicon quadrivalent. And if the law of substitution gives a very simple explanation of the formation of hydrogen peroxide as a compound containing two aqueous residues (OH) (OH), then on the basis of this law all hydrocarbons ought to be derived from methane, CH_4 , as being the simplest hydrocarbon. The increase in complexity of a molecule of methane is brought about by the faculty of mutual combination which exists in the atoms of carbon, and, as a consequence of the most detailed study of the subject, much of that which might be foreseen and conjectured from the law of substitution has been actually brought about in such manner as might have been predicted. Although this subject, on account of its magnitude, appertains, as has been already stated, to the sphere of organic chemistry, yet it has been touched on here in order to show, although only in part, the best investigated example of the application of the law of substitution. According to this law, a molecule of methane, CH_4 , is capable of undergoing substitution in the four following ways:—(1) Methyl substitution, when the radicle equivalent to hydrogen CH_3 , called *methyl*, replaces the hydrogen. In CH_4 this radicle is combined with H, and therefore can replace it, as (OH) replaces H because with it it gives water; (2) methylene substitution, or the exchange between H_2 and CH_2 (this radicle is called *methylene*) is founded on a similar division of the molecule CH_4 into two equivalent parts, H_2 and CH_2 ; (3) acetylene substitution, or the exchange between CH on the one hand and H_3 on the other; and (4) carbon substitution—that is, the substitution of H_4 by an atom of carbon C, which is founded on the law of substitution similarly to the methyl substitution. These four cases of substitution render it possible to understand the principal relations of the hydrocarbons. For instance,

³⁶ Methylene, CH_2 , does not exist. When attempts are made to obtain it (for example, by removing X_2 from CH_2X_2), C_2H_4 or C_5H_6 are produced—that is to say, it undergoes polymerisation.

the *law of even numbers* is seen from the fact that in all the cases of substitution mentioned the hydrogen atoms increase or decrease by an even number ; but, as in CH_2 they are likewise even, it follows that no matter how many substitutions they produce there will always be an even number of hydrogen atoms obtained. Indeed, when H is replaced by CH_3 there is an increase of CH_2 ; when H_2 is replaced by CH_2 there is no increase of hydrogen ; in the acetylene substitution CH replaces H_2 , therefore there is an increase of C and a decrease of H_2 ; in the carbon substitution there is a decrease of H_4 . In a similar way the *law of limit* may be deduced as a corollary of the law of substitution. In fact, the largest possible quantity of hydrogen introduced corresponds with the methyl substitution, but it leads to the introduction of CH_2 ; therefore, no matter how many times this exchange may be effected with CH_4 , and, denoting the number of times by $(n-1)$, the result will always be $\text{CH}_4(n-1)(\text{CH}_2)$, or $\text{C}_n\text{H}_{2n+2}$ as the highest hydrogen compound. Unsaturated hydrocarbons, containing less hydrogen, are evidently only formed when the increase of the new molecule derived from methane proceeds from one of the other forms of substitution. When the methyl substitution alone takes place with methane, CH_4 , it is evident that the saturated hydrocarbon formed is C_2H_6 or $(\text{CH}_3)(\text{CH}_3)$.³⁷ This is called *ethane*. Directly, by means of the methylene substitution alone, *ethylene*, C_2H_4 , or $(\text{CH}_2)(\text{CH}_2)$ may be obtained from CH_4 , and by the acetylene substitution, C_2H_2 or $(\text{CH})(\text{CH})$, or *acetylene*, both the latter being unsaturated hydrocarbons. Thus we have all the possible hydrocarbons with two atoms of carbon in the molecule, C_2H_6 , ethane, C_2H_4 , ethylene, and C_2H_2 , acetylene. But with them, according to the law of substitution, the same forms of substitution may be repeated—that is, the methyl,

³⁷ Although the methods of formation and the reactions connected with hydrocarbons are not described in this work, because they are dealt with in organic chemistry, yet, in order to clearly show the mechanism of those transformations by which the carbon atoms are built up in the molecules of the carbon compounds, we here give a general example of reactions of this kind. From marsh gas, CH_4 , on the one hand, the substitution of chlorine or iodine, CH_3Cl , CH_3I , for the hydrogen may be effected, and, on the other hand, such metals as sodium may be substituted for the hydrogen, CH_3Na . Such and other similar products of substitution are exceedingly characteristic of hydrocarbons, and serve as a means of obtaining other more complex substances from given carbon compounds. If we place the two above-named products of substitution of marsh gas (metallic and haloid) in mutual contact, the metal combines with the halogen, forming a very stable compound—namely, common salt or sodium chloride and the carbon-groups which were in combination with them separate in mutual combination, as shown by the equation :



This is the most simple example of the formation of a complex hydrocarbon from these radicles. The cause of the reaction must be sought for in the property which chlorine and sodium have of entering into mutual combination.

methylene, acetylene, and even carbon substitutions (because C_2H_6 will still contain hydrogen when C replaces H_4)—and therefore further substitutions will serve as a source for the production of a set of saturated and unsaturated hydrocarbons, all containing more and more carbon in the molecule and, in the case of the acetylene substitution and carbon substitution, containing less and less hydrogen. Thus *by means of the law of substitution we can foresee* not only the limit C_nH_{2n+2} , but an unlimited number of unsaturated hydrocarbons, C_nH_{2n} , C_nH_{2n-2} $C_nH_{2(n-m)}$, where m varies from 0 to $n-1$,³⁸ and where n increases indefinitely. From these facts not only does the existence of a multitude of polymeric hydrocarbons, differing in molecular weight, become evident, but it is also seen that there is a possibility of cases of isomerism with the same molecular weight. Already in the first unsaturated series C_nH_{2n} that *polymerism* so common to hydrocarbon compounds is apparent, because all the terms of this series C_2H_4 , C_3H_6 , C_4H_8 $C_{30}H_{60}$ have one and the same composition CH_2 , but different molecular weights, as has been already explained in Chapter VII. (page 312). The differences in the vapour density, boiling points, and melting points, of the quantities entering into reactions,³⁹ and the means of preparation⁴⁰ also so clearly tally with the doctrine of polymerism, that this example will always be the clearest and most conclusive for the conception of polymerism and molecular weight. Such a case is also met with among other hydrocarbons. Thus benzene, C_6H_6 , and cinnamene, C_8H_8 , correspond with the composition of acetylene or to a compound of the composition CH .⁴¹ The first boils at 81° , the second at 144° ;

³⁸ When $m=n-1$, we have the series C_nH_2 . The lowest member is acetylene, C_2H_2 . Amongst the hydrocarbons with C_5 , there ought to be two of the formula C_5H_2 , one with the structure CH_3CCH , and the other CCH_3C . But one of these is unknown. For C_4H_2 , $CHCCCH$ is known the diacetylene of v. Baeyer, an explosive, easily destructible, gaseous substance. Nothing more is known of the series C_nH_2 .

³⁹ For instance, ethylene, C_2H_4 , combines with Br_2 , HI , H_2SO_4 , as a whole molecule, as also does amylene, C_5H_{10} , and, in general, C_nH_{2n} —that is, the reacting masses are proportional to the molecular weight or n , or to the density of the vapours (page 307).

⁴⁰ For instance, ethylene is obtained by removing the water from ethyl alcohol, $C_2H_5(OH)$, and amylene, C_5H_{10} , from amyl alcohol, $C_5H_{11}(OH)$, or in general C_nH_{2n} from $C_nH_{2n+1}(OH)$.

⁴¹ Acetylene and its polymerides have an empirical composition CH , ethylene and its homologues (and polymerides) CH_2 , ethane CH_3 , methane CH_4 . This series presents a good example of the law of multiple proportions, but such diverse proportions are met with between the number of atoms of the carbon and hydrogen in the hydrocarbons already known that the accuracy of Dalton's law might be doubted. Thus the difference in weight between the substances $C_{50}H_{62}$ and $C_{50}H_{60}$ is so slight that it is within the inevitable errors of analysis, but their reactions and properties are so distinct that they can be distinguished beyond a doubt. Without Dalton's law, chemistry could not have been brought to its present condition, but it cannot alone express all those shades which are quite clearly understood and predicted by the law of Avogadro-Gerhardt.

the specific gravity of the first is 0.899 ; that of the second, 0.925, at 0° —that is, here also the boiling point rises with the increase of molecular weight, and so also, as might be expected, does the density.

Cases of isomerism in the exact sense of the word—that is, when, with an identity of composition and of molecular weight, the properties of the substances are different—are very numerous among the hydrocarbons and their derivatives. Such cases are particularly important for the comprehension of molecular structure, and they also, like the polymerides, may be predicted from the above-mentioned conceptions, expressing the principles of the structure, of the carbon compounds⁴² based on the law of substitution. According to it, for example, it is evident that there can be no isomerism in the cases of the saturated hydrocarbons C_2H_6 and C_3H_8 , because the former is CH_4 , where methyl has taken the place of H, and as all parts of the hydrogen atoms of methane ought to be supposed to have the same relation to carbon, it is all the same which of them be subjected to the methyl substitution—the resulting product will only be ethane, CH_3CH_3 ;⁴³ and therefore the same argument applies in the case of propane, $CH_3CH_2CH_3$, where one compound only can be imagined. It

⁴² The conception of the structure of hydrocarbon compounds—that is, the expression of those unions and correlations which their atoms have in the molecules—was for a long time limited to the representation that organic substances contained complex radicles (for instance, ethyl C_2H_5 , methyl CH_3 , phenyl C_6H_5 , &c.); then about the year 1840 the phenomena of substitution and the correspondence of the products of substitution with the primary bodies (nuclei and types) were observed, but it was not until about the year 1860 and later when, on the one hand, the teaching of Gerhardt about molecules was spreading, and, on the other hand, the materials had accumulated for discussing the transformations of the simplest hydrocarbon compounds, that conjectures began to appear as to the mutual connection of the atoms of carbon in the molecules of the complex hydrocarbon compounds. Then Kekulé and A. M. Butleroff began to express the connection between the separate atoms of carbon, regarding it as a quadrivalent element. Although in their methods of expression and in some of their views they differ from each other, and also from the way in which the subject is treated in this work, yet the essence of the matter—namely, the comprehension of the causes of isomerism and of the union between the separate atoms of carbon—remains the same. In addition to this, starting from the year 1870, there appears a tendency, which from year to year increases, to discover the actual spacial distribution of the atoms in the molecules. Thanks to the endeavours of Le Bel (1874), Van't Hoff (1874), and Wislicenus (1887) in observing cases of isomerism—such as the effect of different isomerides on the direction of the rotation of the plane of polarisation of light—this tendency promises much for chemical mechanics, but the details of the still imperfect knowledge in relation to this matter must be sought for in special works devoted to organic chemistry.

⁴³ Direct experiment shows that however CH_3X is prepared (where X=for instance Cl, &c.) it is always one and the same. If, for instance, in CX_4 , X is gradually replaced by hydrogen until CH_3X is produced, or in CH_4 the hydrogen by various means is replaced by X, or else, for instance, if CH_3X be obtained by the decomposition of more complex compounds, the same product is always obtained.

This was shown in the year 1860, or there about, by many methods, and is the fundamental conception of the structure of hydrocarbon compounds. If the atoms of hydro-

is to be expected, however, that there should be two butanes, C_4H_{10} , and this is actually the case. In one methyl may be considered as replacing the hydrogen of one of the methyls, $CH_3CH_2CH_2CH_3$; and in the other CH_3 may be considered as substituted for H in CH_2 , and there it will consist of $CH_3CH \begin{smallmatrix} CH_3 \\ CH_3 \end{smallmatrix}$. It may be also regarded as methane, in which three of hydrogen are exchanged for three of methyl. On going further in the series it is evident that the number of possible isomerides will be still greater. But we have limited ourselves to the simplest examples, showing the possibility and actual existence of isomerides. C_2H_4 and CH_2CH_2 are, it is evident, identical, but there ought to be, and are, two hydrocarbons of the composition C_3H_6 , propylene and trimethylene; the first is ethylene CH_2CH_2 , in which one part of hydrogen is exchanged for methyl CH_2CHCH_3 , and trimethylene is ethane, CH_3CH_3 , only with the exchange of methylene for two hydrogen atoms from two methyl groups—that is, $\begin{smallmatrix} CH_2 \\ CH_2 \end{smallmatrix}CH_2$,⁴⁴ where the methyl introduced is united to both the atoms of carbon existing in CH_3CH_3 . It is evident that the cause of isomerism here is, on the one hand, the difference of the amount of hydrogen in union with the particular atoms of carbons, and, on the other, the different connection between the separate atoms of carbon. In the first case they may be said to be chained together (more generally to form 'an open chain'), and in the second case, to be locked up (to form a 'closed chain' or 'ring'). Here, also, it is easily understood that on increasing the quantity of carbon atoms the number of conjectured and existing isomerides will greatly increase. If, also, in addition to the substitution of one of the radicles of methane for hydrogen a further exchange of part of the hydrogen for some of the other groups of elements X, Y occurs, the quantity of possible isomerides still further increases in a considerable degree. For instance, there are even two possible isomerides for the derivatives of ethane, C_2H_6 : if two parts of the hydrogen be exchanged for X_2 , one

gen in methyl were not absolutely identical in value and position (as, for instance, in $CH_3CH_2CH_3$, or CH_3CH_2X), then there would be as many different forms of CH_5X as there were diversities in the atoms of hydrogen in CH_4 . The scope of this work does not permit of a more detailed account of this matter. It is given in works on organic chemistry.

⁴⁴ The union of carbon atoms in closed chains or rings was first suggested by Kekulé as an explanation of the structure and isomerism of the derivatives of benzene, C_6H_6 , forming aromatic compounds (Note 26). It is now incontestable, although the question of isomerism between the benzene derivatives cannot be considered as finally solved, that this closed connection exists, and gives a peculiar character to these compounds.

will have the ethylene structure, $\text{CH}_2\text{XCH}_2\text{X}$, and the other an ethylidene structure, CH_3CHX_2 ; such are, for instance, ethylene chloride, $\text{CH}_2\text{ClCH}_2\text{Cl}$, and ethylidene chloride, CH_3CHCl_2 . And as in the place of the first part of hydrogen not only metals may be substituted, but Cl, Br, I, (OH) the water radicle, (NH_2) the ammonia radicle, (NO_2) the radicle of nitric acid, &c., so also in exchange for two parts of hydrogen O, NH, S, &c., may be substituted, whence it will be understood that the quantity of isomerides is sometimes very great. It is impossible here to describe how the isomerides are distinguished from each other, in what reactions they occur, how and when one changes into another, &c.; for this, taken together with the description of the hydrocarbons already known, and their derivatives, forms a most extended and most thoroughly investigated branch of chemistry, called *organic chemistry*. Enriched with a mass of closely-observed phenomena and strictly-deduced generalisations, this branch of chemistry has been treated separately for the reason that in it the hydrocarbon groups are subjected to transformations which are not met with in such quantity in dealing with any of the other elements or their hydrogen compounds. It was important for us to show that notwithstanding the great variety of the hydrocarbons and their products,⁴⁵ they are all of them governed by the law of substitution, and referring our readers for detailed information to works on organic chemistry, we will limit ourselves to a short exposition of the properties of the two simplest unsaturated hydrocarbons: ethylene, CH_2CH_2 , and acetylene, CHCH , and a short acquaintance with petroleum as the natural source of a mass of hydrocarbons. *Ethylene, or olefiant gas*, C_2H_4 , is

⁴⁵ The following are the most generally known of the oxygenised but non-nitrogenous hydrocarbon derivatives. (1) The alcohols. These are hydrocarbons in which hydrogen is exchanged for *hydroxyl* (OH). The simplest of these is methyl-alcohol, $\text{CH}_3(\text{OH})$, or wood spirit obtained by the dry distillation of wood. The common spirits of wine or ethyl alcohol, $\text{C}_2\text{H}_5(\text{OH})$, and glycol, $\text{C}_2\text{H}_4(\text{OH})_2$, correspond with ethane. Normal propyl alcohol, $\text{CH}_3\text{CH}_2\text{CH}_2(\text{OH})$, and isopropyl alcohol, $\text{CH}_3\text{CH}(\text{OH})\text{CH}_3$, propylene-glycol, $\text{C}_3\text{H}_6(\text{OH})_2$, and glycerol, $\text{C}_3\text{H}_5(\text{OH})_3$ (which, with stearic and other acids, forms fatty substances), correspond with propane, C_3H_8 . All alcohols are capable of forming water and ethereal salts with acids, just as alkalis form ordinary salts. (2) Aldehydes are alcohols minus hydrogen; for instance, acetaldehyde, $\text{C}_2\text{H}_4\text{O}$, corresponds with ethyl alcohol. (3) It is simplest to regard organic acids as hydrocarbons in which hydrogen has been exchanged for carboxyl (CO_2H), as will be explained in the following chapter. There are a number of intermediate compounds; for example, the aldehyde-alcohols, alcohol-acids (or hydroxy-acids), &c. Thus the hydroxy-acids are hydrocarbons in which some of the hydrogen has been replaced by *hydroxyl*, and some by *carboxyl*; for instance, lactic acid corresponds with C_2H_5 , and has the constitution $\text{C}_2\text{H}_4(\text{OH})(\text{CO}_2\text{H})$. If to these products we add the haloid salts (where H is replaced by Cl, Br, I), the nitro-compounds containing NO_2 instead of H, the amides, cyanides, ketones, and other compounds, it will be readily seen what an immense number of organic compounds there are and what a variety of properties these substances have; this we see also from the composition of plants and animals.

the lowest known member of the unsaturated hydrocarbon series of the composition C_nH_{2n} . As in composition it is equal to two molecules of marsh gas deprived of two molecules of hydrogen, it is evident that it might be, and actually can, together with hydrogen, be produced, although but in small quantities, by heating marsh gas. On being heated, however, olefiant gas is decomposed into charcoal and marsh gas: $C_2H_4 = CH_4 + C$; and therefore in those cases where marsh gas is produced by heating, olefiant gas, hydrogen, and charcoal will also be formed, although only in small quantities. The lower the temperature at which complex organic substances are heated, the greater the quantity of olefiant gas found in the gases given off; at a white heat it is entirely decomposed into charcoal and marsh gas. If coal, wood, and more particularly petroleum, tars and fatty substances are subjected to dry distillation, they give off illuminating gas, which contains more or less olefiant gas.

Olefiant gas, almost free from other gases,⁴⁶ may be obtained from ordinary alcohol (if possible, free from water), if it be mixed with five parts of strong sulphuric acid and the mixture heated to slightly above 100° . Under these conditions, the sulphuric acid removes the elements of water from the alcohol, $C_2H_5(OH)$, and gives olefiant gas, $C_2H_6O = H_2O + C_2H_4$. The greater molecular weight of olefiant gas compared with marsh gas points out that it may be comparatively easily converted into a liquid by means of pressure or great cold; this may be effected, for example, by the evaporation of liquid nitrous oxide. Its absolute boiling-point is $+10^\circ$, it boils at -103° (1 atmosphere), liquefies at 0° , at a pressure of 43 atmospheres, and solidifies at -160° . Ethylene is colourless, has a slight ethereal smell, is slightly soluble in water, and somewhat more soluble in alcohol and in ether (in five volumes of spirit and six volumes of ether).⁴⁷

Like other unsaturated hydrocarbons, olefiant gas readily enters

⁴⁶ Ethylene bromide, $C_2H_4Br_2$, when gently heated in alcoholic solution with finely divided zinc, yields pure ethylene, the zinc merely taking up the bromine (Sabañeyff).

⁴⁷ Ethylene decomposes somewhat easily under the influence of the electric spark, or a high temperature. In this case the volume of the gas formed may remain the same when olefiant gas is decomposed into carbon and marsh gas, or may increase to double its volume when hydrogen and carbon are formed, $C_2H_4 = CH_4 + C = 2C + 2H_2$. A mixture of olefiant gas and oxygen is highly explosive; two volumes of this gas require six volumes of oxygen for its perfect combustion. The eight volumes thus taken then resolve themselves into a mixture of eight volumes of the products of combustion, water and carbonic anhydride, $C_2H_4 + 3O_2 = 2CO_2 + 2H_2O$. On cooling, after the explosion, diminution of volume occurs because the water becomes liquid. For two volumes of the olefiant gas taken, the diminution will be equal to four volumes, and the same for marsh gas. The quantity of carbonic anhydride formed by both gases is not the same. Two volumes of marsh gas give only two volumes of carbonic anhydride, and two volumes of ethylene give four volumes of carbonic anhydride ($2CO_2$).

into combination with certain substances, such as chlorine, bromine, iodine, fuming sulphuric acid, or sulphuric anhydride. If olefiant gas be sealed up with a small quantity of sulphuric acid in a glass vessel, and be subjected to continued shaking (as, for instance, by suspending it from a moving part of a machine), the prolonged contact and repeated mixing causes the olefiant gas, little by little, to combine with the sulphuric acid, forming $C_2H_4H_2SO_4$. If, after this absorption, the sulphuric acid be diluted with water and distilled, alcohol separates, which is produced in this case by the olefiant gas combining with the elements of water, $C_2H_4 + H_2O = C_2H_6O$. In this reaction (Berthelot) we see an excellent example of the fact that if a given substance, like olefiant gas, is produced by the decomposition of another, then in the reverse way this substance, entering into combination, is capable of forming the original substance—in our example, alcohol. Therefore the reaction, $CH_3CH_2(OH) = H(OH) + CH_2CH_2$, ought to be classed as a reversible reaction. In combination with various molecules, X_2 , ethylene gives saturated compounds, $C_2H_4X_2$ —that is, either CH_2XCH_2X , or CH_3CHX_2 , which correspond with ethane, CH_3CH_3 , or C_2H_6 .⁴⁸

Acetylene, $C_2H_2 = CHCH$, is a gas; it was first prepared by Berthelot (1857). It has a very pungent smell, is characterised by its great constancy under the action of heat, and is the only product of the direct combination of carbon with hydrogen. This combination takes place under the action of great heat, such as is produced by a very strong electric current between carbon points. A brilliant arc (voltaic) is then formed between the carbon electrodes, which contains particles of carbon passing from one pole to the other. If the carbons be surrounded with an atmosphere of hydrogen, the carbon in part combines with the hydrogen, forming C_2H_2 . Acetylene may be formed from olefiant gas if two atoms of hydrogen be taken from it. This may be effected in the following way: the olefiant gas is first made to combine with bromine, giving $C_2H_4Br_2$; from this the hydrobromic acid is taken by means of an alcoholic solution of caustic potash, leaving the volatile product C_2H_3Br ; and from this yet another part of hydrobromic acid is withdrawn by passing it through anhydrous alcohol in which metallic sodium has been dissolved, or by heating it with a strong alcoholic solution of caustic potash. Under these cir-

⁴⁸ The homologues of ethylene, C_nH_{2n} , are also capable of direct combination with halogens, &c., but with various degrees of facility. The composition of these homologues can be expressed thus: $(CH_3)_x(CH_2)_y(CH)_zC_r$, where the sum of $x+z$ is always an even number, and the sum of $x+z+r$ is equal to half the sum of $3x+z$, whence $z+2r=x$; by this means the possible isomerides are determined. For example, for butylenes, C_4H_8 , $(CH_3)_2(CH)_2$, $(CH_3)_2(CH_2)C$, $(CH_2)(CH_2)_2CH$, and $(CH_2)_4$ are possible.

circumstances (Berthelot, Sawitsch, Miasnikoff) the alkali takes up the hydrobromic acid from $C_nH_{2n-1}Br$, forming C_nH_{2n-2} .

Acetylene is also produced in all those cases where organic substances are decomposed by the action of a high temperature for example, by dry distillation. On this account a certain quantity is always found in coal gas, and gives to it, at all events in part, its peculiar smell, but the quantity of acetylene in coal gas is very small. If the vapour of alcohol be passed through a heated tube a certain quantity of acetylene is formed. It is also produced by the imperfect combustion of olefiant and marsh gas for example, if the flame of coal gas has not free access to air.⁴⁹ The inner part of every flame contains gases in imperfect combustion, and in them some amount of acetylene.

Acetylene, being further removed than ethylene from the limit C_nH_{2n+2} of hydrocarbon compounds, has a still greater faculty of combination than is shown by olefiant gas, and therefore can be more readily separated from any mixture containing it. Actually, acetylene not only combines with one and two molecules of I_2 , HI , H_2SO_4 , Cl_2 , Br_2 , &c. . . . (many other unsaturated hydrocarbons combine with them) but also with cuprous chloride, $CuCl$, forming a red precipitate. If a gaseous mixture containing acetylene be passed through a solution of cuprous chloride (or $AgNO_3$) and ammonia water, the other gases do not combine, but the acetylene gives a red precipitate (or gray with silver), which on being struck with a hammer decomposes with an explosion. This red precipitate gives off acetylene under the action of acids. In this manner pure acetylene may be produced. Acetylene and its homologues also readily react with corrosive sublimate, $HgCl_2$ (Koucheroff, Favorsky). Acetylene burns with a very brilliant flame, which is accounted for by the comparatively large amount of carbon it contains.⁵⁰

The formation and existence in nature of large masses of petroleum or a mixture of liquid hydrocarbons, principally of the series C_nH_{2n+2} and C_nH_{2n} is in most respects remarkable.⁵¹ In some mountainous dis-

⁴⁹ This is easily accomplished with those gas lamps which are used in laboratories and mentioned in the Introduction, page 11. In these lamps the gas is first mixed with air in a long tube, above which it is kindled. But if it be lighted inside the pipe it does not fully burn, but forms acetylene, on account of the cooling effect of the walls of the metallic tube; this is observed by the smell, and may be shown by passing the issuing gas (by aid of an aspirator) into an ammoniacal solution of cuprous chloride.

⁵⁰ Amongst the homologues of acetylene, C_nH_{2n-2} , the lowest is C_3H_4 ; allylene, CH_3CCH , and allene, CH_2CCH_2 , are known, but the closed structure, $CH_2(CH)_2$, is unknown.

⁵¹ The saturated hydrocarbons predominate in American petroleum, especially in its more volatile parts; in Baku naphtha the hydrocarbons of the composition C_nH_{2n} form

tricts—as, for instance, by the slopes of the Caucasian chain, on inclines in a parallel direction to the chain—an oily liquid issues from the earth together with salt water and hot gases (methane and others); it has a tarry smell, dark brown colour, and is lighter than water. This liquid is called naphtha or rock oil (petroleum), and is obtained in large quantities by making wells and deep bore-holes in those places where traces of naphtha are observed, the naphtha being sometimes thrown up from the wells in fountains of considerable height.⁵² The evolution of naphtha is always accompanied by salt water and marsh gas. Naphtha has from ancient times been worked in Russia in the Apsheron peninsula near Baku, and is also now worked in Burmah (India), in Galicia near the Carpathians, and in America, especially in Pennsylvania and Canada. Naphtha does not consist of one definite hydrocarbon, but of a mixture of many, and its density, external appearance, and other qualities vary with the amount of the different hydrocarbons of which it is composed. The light kinds of naphtha have a specific gravity about 0.8 and the heavy kinds up to 0.98. The former are very mobile liquids, and are more volatile; the latter contain less of the volatile hydrocarbons and are less mobile. When the light kinds of naphtha are distilled the boiling point in the vapours constantly changes, beginning at 0° and going up to above 350°. That which passes over first is a very mobile, colourless ethereal liquid, from which the hydrocarbons whose boiling points start from 0° may be extracted—namely, the hydrocarbons C_4H_{10} , C_5H_{12} (which boils at 30°), C_6H_{14} (boils at 62°), C_7H_{16} (boils about 90°), &c. Those fractions of the distillate of naphtha which boil

the main part (Lisenko, Markovinkoff, Beilstein), but doubtless (Mendeléeff) it also contains saturated ones, C_nH_{2n+2} . The structure of the naphtha hydrocarbons is only known for the lower homologues, but doubtless the distinction between the hydrocarbons of the Pennsylvanian and Baku naphthas, boiling at the same temperature (after the requisite refining by repeated, methodical distillation, which can be very conveniently done by means of steam, passing the steam through the dense mass—that is, by means of rectification), depends not only on the predomination of saturated hydrocarbons in the former, and naphthenes, C_nH_{2n} , in the latter, but also on the diversity of composition and structure of the corresponding portions of the distillation. The products of the Baku naphtha are richer in carbon (therefore, in a suitably constructed lamp they ought to give a brighter light), they are of greater specific gravity, and have greater internal friction (and are therefore more suitable for lubricating machinery) than the American products collected at the same temperature.

⁵² The formation of naphtha fountains (which burst forth after the higher clay strata covering the layers of sand impregnated with naphtha have been bored through) is without doubt caused by the pressure or tension of the combustible hydrocarbon gases which accompany the naphtha, and are soluble in it under pressure. Sometimes these naphtha fountains reach a height of 100 metres—for instance, the fountain of 1887, near Baku. Naphtha fountains generally act periodically, and their force diminishes with the lapse of time, which might be expected, because the gases which cause the fountains find an outlet, and the naphtha issuing from the bore-hole carries away the sand which was partially choking it up.

above 130° , and contain hydrocarbons with C_9 , C_{10} , C_{11} , &c., enter into the composition of the oily substance, universally used for lighting, called kerosene or photogen or photonaphthalene and other names. The specific gravity of kerosene is from 0.78 to 0.84, and it smells like naphtha. Those products of the distillation of naphtha which pass off below 130° and have a specific gravity below 0.75, enter into the composition of light petroleum (benzoline, ligroin, petroleum spirit, &c.); which is used as a solvent for india-rubber, for taking out grease spots, &c. Those portions of naphtha (which can only be distilled without change by means of superheated steam, otherwise they are largely decomposed) which boil above 275° to 300° and have a specific gravity higher than 0.85, form an excellent oil,⁵³ safe as regards inflammability (which is very important as diminishing the risks of fire), and may be used in lamps as an effective substitute for kerosene.⁵⁴ Those portions of naphtha which pass over at a still higher temperature and have a higher specific gravity than 0.9, which are found in abundance (about 30 p.c.) in the Baku naphtha, make excellent lubricating or machine oils. Naphtha

⁵³ This is a so-called intermediate (between kerosene and lubricating oils) oil or pyronapht. Lamps are already being manufactured for burning it, but still require improvement. Above all, however, it requires a more extended market, and at present is likely to want it owing to the following two reasons: (1) The products of the American petroleum, which are the most widely spread and almost universally consumed, contain but little of this intermediate oil, and what there is is partly introduced into the kerosene and partly into the lubricating oils; (2) the Baku naphtha, which is capable of yielding a great deal (up to 30 p.c.) of intermediate oil, is produced in enormous quantities, about 165 million poods (1887), but has no regular markets abroad, and for the consumption in Russia (about 20 million poods of kerosene per annum) and for the limited export (20 millions poods per annum) into Western Europe (by the Trans-Caucasian Railway) those volatile and more dangerous parts of the naphtha which enter into the composition of the American petroleum are sufficient, because Baku naphtha yields about 20 p.c. of such kerosene. For this reason pyronapht is not manufactured in sufficient quantities, and the whole world is consuming the unsafe kerosene. When a pipe line has been laid from Baku to the Black Sea (in America there are many which carry the raw naphtha to the sea-shore, where it is made into kerosene and other products) then the whole mass of the Baku naphtha will furnish safe illuminating oils, which, without doubt, will find an immense application. A mixture of the intermediate oil with kerosene or Baku oil (specific gravity 0.84 to 0.85) may be considered (on removing the benzoline) to be the best illuminating oil, because it is safe (flashing point from 40° to 60°), cheaper (Baku naphtha gives as much as 60 p.c. of Baku oil), and burns perfectly well in lamps, differing but little from those made for burning American kerosene (unsafe, flashing point 20° to 25° to 30°).

⁵⁴ The substitution of Baku pyronapht, or intermediate oil, or Baku oil (*see* Note 53), would not only be a great advantage as regards safety from fire, but would also be highly economical. A ton (62 poods) of American crude petroleum costs there at the coast considerably more than 24s. (12 roubles), and yields two-thirds of a ton of kerosene suitable for ordinary lamps. A ton of raw naphtha in Baku costs less than 4s. (1 rouble 80 copecks), and with a pipe line to the shore of the Black Sea would not cost more than 8 roubles, or 16s. And a ton of Baku naphtha will also yield as much as two-thirds of a ton of kerosene, Baku oil, and pyronapht suitable for illuminating purposes.

has many important applications, and the naphtha industry is now of great commercial importance, especially as naphtha and its refuse may be used as fuel.⁵⁵ Whether naphtha was formed from organic matter is very doubtful, as it is found in the most ancient Silurian strata which correspond with epochs of the earth's existence when there was little organic matter; it could not penetrate from the higher to the lower strata (more ancient) as it floats on water (and water penetrates through all strata). It therefore tends to rise to the surface of the earth, and it is always found in highlands parallel to the direction of the mountains.⁵⁶ It is much more probable that its formation should be attributed to the action of water, penetrating through the crevices formed on the mountain slopes to the heart of the earth, on that kernel of heated metallic matter which must be accepted as existing in the interior of the earth. And as meteoric iron often contains carbon (like cast iron), so, accepting the existence of such carburetted iron at unattainable depths in the interior of the earth, it may be sup-

⁵⁵ Naphtha has been applied to heating purposes on a large scale in Russia only, not only on account of the low cost of naphtha and of the refuse from the preparation of kerosene, but also because the products of all the Baku naphtha do not find an outlet for universal consumption. Naphtha itself and its various residues form excellent fuel, burning without smoke and giving a high temperature (steel and iron may be easily melted in the flame). A hundred poods of good coal (for instance, Don coal) used as fuel for heating boilers are equivalent to 36 cubic feet (about 250 poods) of dry wood, while only 70 poods of naphtha will be required; and, moreover, there is no need for stoking, as the liquid can be readily and evenly supplied in the required quantity. The economical and other questions dealing with American and Baku petroleum have been discussed more in detail in some separate works of mine (D. Mendeléeff): (1) 'The Naphtha Industry of Pennsylvania and the Caucasus,' 1870; (2) 'Where to Build Naphtha Works,' 1880; (3) 'On the Naphtha Question,' 1883; (4) 'The Baku Naphtha Question,' 1886.


⁵⁶ As during the process of the dry distillation of wood, seaweed, and similar vegetable *débris*, and also when fats are decomposed by the action of heat (in closed vessels), hydrocarbons similar to those of naphtha are formed, it was natural that this should have been turned to account to explain the formation of the latter. But the hypothesis of the formation of naphtha from vegetable *débris* inevitably assumes coal to be the chief element of decomposition, and naphtha is met with in Pennsylvania and Canada, in the Silurian and Devonian strata, which do not contain coal, and correspond to an epoch not abounding in organic matter. Coal was formed from the vegetable *débris* of the Carboniferous, Jurassic, and other recent strata. but, judging from the composition and structure, it was subjected to the same decomposition as peat; neither could liquid hydrocarbons have been formed to such an extent as we see in naphtha. If we ascribe the derivation of naphtha to the decomposition of fat (adipose, animal fat), we encounter three almost insuperable difficulties: (1) Animal remains would furnish a great deal of nitrogenous matter, whilst there is but very little in naphtha; (2) the enormous quantity of naphtha already discovered as compared with the insignificant amount of fat in the animal carcass; (3) the sources of naphtha always running parallel to mountain chains is completely inexplicable. Being struck with this last-mentioned circumstance in Pennsylvania, and finding that the sources in the Caucasus surround the whole Caucasian range (Baku, Tiflis, Gouria, Kouban, Tainan, Groznoe, Dagestan), I developed in 1876 the hypothesis of the mineral origin of naphtha expounded further on.

posed that naphtha was produced by the action of water penetrating through the crevices of the strata during the upheaval of mountain chains,⁵⁷ because water with iron carbide ought to give iron oxide and hydrocarbons.⁵⁸ Direct experiment proves that the so-called *spiegeleisen* (manganiferous iron, rich in chemically-combined carbon) when treated with acids gives liquid hydrocarbons,⁵⁹ which in

⁵⁷ During the upheaval of mountain ranges crevasses would be formed at the peaks with openings upwards, and at the foot of the mountains with openings downwards. These cracks in course of time fill up, but the younger the mountains (the Alleghany mountains are, without doubt, more recent; they were formed during the tertiary epoch) the fresher the cracks; through them water must gain access deep into the recesses of the earth to an extent that could not occur on the level (on plains). The situation of naphtha at the foot of mountain chains is the principal argument in my hypothesis.

Another fundamental reason is the consideration of the mean density of the earth. Cavendish, Airy, Cornu, and many others who have investigated the subject by various methods, found that, taking water = 1, the mean density of the earth is nearly 5.5. As at the surface water and all rocks (sand, clay, limestone, granite, &c.) have a density less than 3, it is evident (as solid substances are but slightly compressible even under the greatest pressure) that inside the earth there are substances of a greater density — namely, not less than 7 or 8. What conclusion can then be arrived at? Something heavy contained in the bosom of the earth must be scattered not only on its surface, but in the whole solar system, because everything tends to show that the sun and planets proceed from the same material, and, according to the hypothesis of Laplace and Kant, it is most probable, and even ought to be held, that the earth and planets are but fragments of the solar atmosphere which have had time to cool considerably and become masses semi-liquid inside and solid outside, forming planets and satellites. The sun, amongst other heavy elements, contains a great deal of iron, as shown by spectrum analysis. There is also much of it in an oxidised condition on the surface of the earth. Meteoric stones, carried as fragments of the planets in the solar system and sometimes falling upon the earth, consisting of siliceous rocks similar to terrestrial ones, often contain either dense masses of iron (for example, the Pallosovo iron preserved in the St. Petersburg Academy of Sciences) or granular masses (for instance, the Okhansk meteorite of 1886). For this reason it is possible that the interior of the earth contains much iron in a metallic state. This might be expected from the hypothesis of Laplace, for the iron must have been compressed into a liquid at that period when the other component parts of the earth were still strongly heated, and oxides of iron could not yet be formed. The iron was covered with slags (mixtures of silicates, like glass fused together with rocky matter), which did not allow it to burn at the expense of the oxygen of the atmosphere and water, just at that time when the temperature of the earth was very high. Carbon was in the same state; its oxides were also capable of dissociation (Deville); it is also but slightly volatile, and has an affinity for iron, and iron carbide is found in meteoric stones. On this account the supposition of the existence of iron carbides in the interior of the earth was drawn by me from many indications, some of which are confirmed by the fact that granular pieces of iron have been found in some basalts (ancient lava) as well as in meteoric stones.

⁵⁸ The following is the typical equation for this formation :



⁵⁹ Cloez investigated the hydrocarbons formed when cast-iron is dissolved in hydrochloric acid, and found C_nH_{2n} and others. I treated crystalline manganiferous cast-iron with the same acid, and obtained a liquid mixture of hydrocarbons exactly similar to natural naphtha in taste, smell, and reaction. The occurrence of iron with carbon during the formation of the earth is all the more probable because those elements predominate in nature which have small atomic weights, and among them the most widely-diffused, the most difficultly-fusible, and therefore the most easily-condensed (Chap. XV.) are

composition, appearance, and properties are completely identical with naphtha.⁶⁰

carbon and iron. They passed into the liquid state when all compounds were at a temperature of dissociation.

⁶⁰ Probably naphtha was produced during the upheaval of all mountain chains, but only in some cases were the conditions favourable to its being preserved underground. The water penetrating below formed there a mixture of naphtha and watery vapours, and this mixture issued through fissures to the cold parts of the earth's crust. The naphtha vapours, on condensing, formed naphtha, which, if there were no obstacles, appeared on the surface of land and water. Here part of it soaked through formations (perhaps the bituminous slates, schists, domites, &c., were thus formed), another part was carried away on the water, became oxidised, evaporated, and was driven to the shores (the Caucasian naphtha probably in this way, during the existence of the Aralo-Caspian sea, was carried as far as the Sisran banks of the Volga, where many strata are impregnated with naphtha and products of its oxidation resembling asphalt and pitch); a great part of it was burnt in one way or another—that is, gives carbonic anhydride and water. If the mixture of vapours, water, and naphtha formed inside the earth had no free outlet to the surface, it nevertheless would find its way through fissures to the superior and colder strata, and there become condensed. Some of the formations (clays) which do not absorb naphtha were only washed away by the warm water, and formed mud, which we also now observe issuing from the earth in the form of mud volcanoes. All the suburbs of Baku and the whole of the Caucasus in the neighbourhood of the naphtha districts are full of such volcanoes, still from time to time in a state of eruption. In old naphtha beds (such as the Pennsylvanian) even these blow-holes are closed, and the mud volcanoes have had time to be washed away. The naphtha and the gaseous hydrocarbons formed with it under the pressure of the overlying earth and water impregnated the layers of sand, which are capable of absorbing a great quantity of such liquid, and if above this there were strata impermeable to naphtha (dense, clayey damp strata) the naphtha would accumulate in them. It is thus preserved from remote geological periods up to the present day, compressed and dissolved under the pressure of the gases which burst out in places forming naphtha fountains. If this be granted, it may be thought that in the comparatively new (geologically speaking) mountain chains, such as the Caucasian, naphtha is even now being formed. Such a supposition may explain the remarkable fact that, in Pennsylvania, localities where naphtha had been rapidly worked for five years have become exhausted, and it becomes necessary to constantly have recourse to sinking new wells in fresh places. Thus, from the year 1859, the workings were gradually transferred along a line running parallel to the Alleghany mountains for a distance of more than 200 miles, whilst in Baku the industry dates from time immemorial (the Persians worked near the village of Ballaghama) and up to the present time keeps to one and the same place. The amounts of the Pennsylvanian and Baku annual outputs are at present equal—namely, about 150 million poods ($2\frac{1}{2}$ million tons). It may be that the Baku beds, as being of more recent geological formation, are not so exhausted by nature as those of Pennsylvania, and perhaps in the neighbourhood of Baku naphtha is still being formed, which is partially indicated by the continued activity of the mud volcanoes. As many varieties of naphtha contain in solution solid, slightly volatile hydrocarbons like paraffin and mineral wax, the production of ozocerite, or mountain wax, is accounted for in conjunction with the formation of naphtha. Ozocerite is found in Galicia, also in the neighbourhood of Novorossisk, in the Caucasus, and on the islands of the Caspian Sea (particularly in the Chileken and Holy Islands); it is met with in large masses, and is used for the production of paraffin and *ceresene*, for the manufacture of candles, and similar purposes.

As the naphtha treasures of the Caucasus are hardly broached (near Baku and near Kouban and Novorossisk), and as naphtha finds manifold uses, the subject presents most interesting features to chemists and geologists, and is worthy of the close attention of practical men.

CHAPTER IX

COMPOUNDS OF CARBON WITH OXYGEN AND NITROGEN

CARBONIC anhydride (or carbonic acid or carbon dioxide, CO_2) was the first of all gases distinguished from atmospheric air. Paracelsus and Van Helmont, in the sixteenth century, knew that on heating limestone a particular gas separated, which is also formed during the alcoholic fermentation of saccharine solutions (for instance, in the manufacture of wine); they knew that it was identical with the gas which is produced by the combustion of charcoal, and that in some cases it is found in nature. In course of time it was found that this gas is absorbed by alkali and saturates it, forming a salt which, under




FIG. 61.—Dumas and Stas' apparatus for determining the composition of carbonic anhydride. Carbon, graphite, or a diamond is placed in the tube E in the furnace, and heated in a stream of oxygen displaced from the bottle by water flowing from A. The oxygen is purified from carbonic anhydride and water in the tubes B C D. Carbonic anhydride, together with a certain amount of carbon monoxide, is formed in E. The latter is converted into carbonic acid by passing the products of combustion through a tube F, containing cupric oxide heated in a furnace. The cupric oxide oxidises this CO into CO_2 , forming metallic copper. The potash bulbs H and tubes I, J, K retain the carbonic anhydride. Thus, knowing the weight of carbon taken and the weight of the resultant carbonic anhydride (by weighing H, I, J, K before and after the experiment), the composition of carbonic anhydride and the equivalent of carbon may be determined.

the action of acid, again yields this same gas. Priestley found that this gas exists in air, and Lavoisier determined its formation during respiration, combustion, putrefaction, and during the reduction of metals by charcoal; he determined its composition, and showed that it only contains oxygen and carbon. Berzelius, Dumas with Stas, and Roscoe, determined its composition, showing that it contains twelve


parts of carbon to thirty-two of oxygen. The composition by volume of this gas is determined from the fact that during the combustion of charcoal in oxygen, the volume remains unchanged; that is to say, *carbonic anhydride occupies the same volume as the oxygen which it contains*—that is, the atoms of the carbon are, so to speak, squeezed in between the atoms of the oxygen. O_2 occupies two volumes and is a molecule of ordinary oxygen; CO_2 likewise occupies two volumes, and expresses the composition and molecular weight of the gas. Carbonic anhydride exists *in nature*, both in a free state and in the most varied compounds. In a free state it is always contained (Chap V.) in the air, and in solution is in all kinds of water. It is evolved from volcanoes, from mountain fissures, and in some caves. The well known Dog grotto, near Agnano on the bay of Baia, near Naples, is the best known example of such an evolution. Similar sources of carbonic anhydride are also found in other places. In France, for instance, there is a well-known poisonous fountain in Auvergne. It is a round hole, surrounded with luxurious vegetation and constantly evolving carbonic anhydride. In the woods surrounding the Lacher See, near the Rhine, in the neighbourhood of extinct volcanoes, there is a depression constantly filled with this same gas. The insects which fly to this place perish, animals being unable to breathe this gas. The birds chasing the insects also die, and this is turned to profit by the local peasantry. Many mineral springs carry into the air enormous quantities of this gas. Vichy in France, Sprüdel in Germany, and Narzan in Russia (in Kislovodsk near Piatigorsk) are known for their carbonated gaseous waters. Much of this gas is also evolved in mines, cellars, diggings, and wells. For this reason sometimes people descending into such places are suffocated and die. The evolution of carbonic anhydride in the earth is accounted for by the slow oxidation of organic matter underground. The combustion, putrefaction, and fermentation of organic substances give rise to the formation of carbonic anhydride. It is also introduced into the atmosphere during the respiration of animals at all times and during the respiration of plants in darkness and also during their growth. Very simple experiments prove the formation of carbonic anhydride under these circumstances; thus, for example, if the air expelled from the lungs be passed through a glass tube into a transparent solution of lime (or baryta) in water a white precipitate will soon be formed which contains an insoluble compound of lime and carbonic anhydride. If a funnel be held over a substance in a state of combustion—for instance, over a lighted candle or brazier—and the air be collected from it by means of an aspirator, the presence of a large amount of carbonic

anhydride in this air may be detected by its action on lime water. By allowing the seeds of plants to grow under a bell jar, or in a closed vessel, the formation of carbonic anhydride may be similarly confirmed. By forcing an animal, for instance a mouse, to remain under a bell jar, the quantity of carbonic acid which it evolves may be exactly determined, and it will be found to be many grams per day for a mouse. Such experiments on the respiration of animals have been also made with great exactitude with large animals, such as men, bulls, sheep, &c. By means of enormous hermetically-closed bell receivers and the analysis of the gases evolved during respiration it was found that a man expels about 900 grams (more than two pounds) of carbonic anhydride per diem, and absorbs during this time 700 grams of oxygen.¹ It must be remarked that the carbonic anhy-

¹ The quantity of carbonic acid gas exhaled by a man during the twenty-four hours is not evenly distributed; during the night more oxygen is taken in than during the day (by night, in twelve hours, about 450 grams), and more carbonic anhydride is separated by day than during night-time and repose; thus, of the 900 grams separated during the twenty-four hours about 375 are given out during the night and 525 by day. This depends on the separation of carbonic anhydride during any kind of work performed by the man. During the day-time his activity in many respects is comparatively greater than by night. Every movement is the result of some change of matter, because force cannot be produced by itself (in accordance with the law of the conservation of energy). Proportionally to the amount of carbon consumed an amount of force is stored up in the organism and is consumed in the various movements performed by animals. This is proved by the fact that during work-time, in twelve hours, a man exhales 900 grams of carbonic anhydride instead of 525, absorbing the same amount of oxygen as before. In a working day a man exhales by night almost the same amount of carbonic anhydride as in a day of rest, so that during a total twenty-four hours' work a man exhales about 1300 grams of carbonic anhydride and absorbs about 950 grams of oxygen. Therefore in work the change of matter increases. The carbon expended on the work is obtained from the food; on this account the food of animals ought certainly to contain carbonaceous substances capable of dissolving under the action of the digestive fluids, and of passing into the blood, or, in other words, capable of being digested. Such food for man and all other animals is formed of vegetable matter, or of parts of other animals. The latter in every case obtain their carbonaceous matter from plants, in which it is formed by the separation of the carbon from the carbonic anhydride taken up during the day by the respiration of the plants. The green parts of plants during the day absorb the carbonic anhydride of the air, and find it ample notwithstanding the small proportion of it in the air, and give out oxygen. The volume of the oxygen exhaled is almost equal to the volume of the carbonic anhydride absorbed; that is to say, nearly all the oxygen entering into the plant in the form of carbonic anhydride is separated in a free state, whilst the carbon from the carbonic anhydride remains in the plant. At the same time, the plant absorbs moisture by its leaves and roots. By a process, which is unknown to us, this absorbed moisture and carbon remaining from the carbonic acid enter into the composition of the plants in the form of so-called carbohydrates, composing the greater part of the vegetable tissues, starch and cellulose of the composition $C_6H_{10}O_5$ being representatives of them. We may represent their composition as a compound of carbon remaining from carbonic acid and water, $6C + 5H_2O$. In this way a *circulation* of the carbon goes on in nature by means of vegetable and animal organisms, in which changes the principal item is the carbonic anhydride of the air.

dride of the air constitutes the fundamental food of plants (Chaps. III., V., and VIII.). Carbonic anhydride, in a state of combination with most varied substances, is perhaps even more widely diffused in nature than in a free state. Some of these substances are very stable, and form a large portion of the earth's crust. In this state carbonic anhydride enters into the composition of limestones. Limestones, calcium carbonate CaCO_3 , were formed as precipitates in the seas existing previously on the earth; this is proved by their stratified structure and the number of remains of sea animals which they frequently contain. It may be concluded, judging from the enormous quantity of these limestones, that the amount of carbon in the form of carbonic anhydride in the atmosphere was in former periods much greater than at present. Chalk, lithographic stone, limestone, marls (a mixture of limestone and clay), and many other rocks are examples of such sedimentary formations. Carbonates with various other bases—such as, for instance, magnesia, ferrous oxide, zinc oxide, &c.—are often found in nature. The shells of molluscs have also the composition CaCO_3 , and many limestones were exclusively formed from the shells of minute organisms.

For the preparation of carbonic anhydride in laboratories and often in manufactories, various kinds of calcium carbonate are used, being treated with some acid; it is, however, most usual to employ the so-called muriatic acid—that is, an aqueous solution of hydrochloric acid, HCl —because, in the first place, the substance formed, calcium chloride, CaCl_2 , is soluble in water and does not hinder the further action of the acid on the calcium carbonate, and secondly because, as we shall see further on, muriatic acid is a common product of chemical works and one of the cheapest. For calcium carbonate, either limestone, chalk, or marble is used.²



² Other acids may be used instead of hydrochloric; for instance, acetic, or even sulphuric, although this latter is not suitable, because it forms as a product insoluble calcium sulphate (gypsum) surrounding the untouched calcium carbonate, and thus preventing a further evolution of gas. But if porous limestone—for instance, chalk—be treated with sulphuric acid diluted with an equal volume of water, the latter is absorbed, and, acting on the mass of the salt, the evolution of carbonic anhydride continues evenly for a long time. Instead of calcium carbonate, other carbonates may of course be used; for instance, washing-soda Na_2CO_3 , which is often chosen when it is required to produce a rapid stream of carbonic anhydride (for example, for liquefying it). But natural crystalline magnesium carbonate and similar salts are with difficulty decomposed by hydrochloric and sulphuric acids. When for manufacturing purposes—for instance, in precipitating lime in sugar-works—a large quantity of carbonic acid gas is required; generally charcoal is burnt, and the products of combustion, rich in carbonic anhydride, are pumped into the liquid containing the lime, and the carbonic anhydride is thus

The nature of the reaction in this case is the same as in the decomposition of nitre by sulphuric acid ; only in the latter case a hydrate is formed, but in the former an anhydride of the acid, because the hydrate, carbonic acid, H_2CO_3 , is unstable and, as soon as it separates, decomposes into water and its own anhydride. It is evident from the explanation of the cause of the action of sulphuric acid on nitre that not every acid can be employed for obtaining carbonic anhydride ; namely, those will not set it free which chemically are but slightly energetic, or those which are insoluble in water, or are themselves as volatile as carbonic anhydride.³ But as almost all the known acids are characterised by their great solubility in water and are less volatile than carbonic anhydride, the latter is evolved by the action of most acids on its salts, and this reaction takes place at ordinary temperatures, provided the acid be soluble in water and that the calcium salt formed is also soluble in water.⁴

For the preparation of carbonic anhydride in laboratories marble is generally used. It is placed in a Woulfe's bottle and treated with hydrochloric acid in an apparatus similar to the one used for the production of hydrogen. The gas evolved carries away through the tube part of the volatile hydrochloric acid, and it is therefore necessary to wash the gas by passing it through another Woulfe's bottle containing water. If

absorbed. Another method is also practised, which consists in using the carbonic anhydride separated during fermentation, or that evolved from lime-kilns. During the fermentation of sweet-wort, grape-juice, and other similar saccharine solutions, the glucose $\text{C}_6\text{H}_{12}\text{O}_6$ changes under the influence of the yeast organism, forming alcohol ($2\text{C}_2\text{H}_5\text{O}$) and carbonic anhydride (2CO_2), which separates in the form of gas ; if the fermentation proceeds in closed bottles sparkling wine is obtained. When carbonic acid gas is prepared for saturating water and other beverages it is necessary to use it in a pure state. Whilst in the state in which it is evolved from ordinary limestones by the aid of acids it contains, besides a certain quantity of acid, the organic matters of the limestone ; in order to diminish the quantity of these substances the densest kinds of dolomites are used, which contain less organic matter, and the gas formed is passed through various washing apparatus, and then through a solution of potassium permanganate, which absorbs organic matter and does not take up carbonic anhydride.

³ Hypochlorous acid, HClO , and its anhydride, Cl_2O , do not displace carbonic acid, and hydrogen sulphide has the same relation to carbonic acid as nitric acid to hydrochloric--an excess of either one displaces the other.

⁴ Thus, in preparing the ordinary effervescing powders, sodium bicarbonate (or acid carbonate of soda) is used, and mixed with powdered citric or tartaric acid. In a dry state these powders do not evolve carbonic anhydride, but when mixed with water the evolution takes place briskly, which is due to the substance passing into solution. The salts of carbonic acid may be recognised from the fact that they evolve carbonic acid with a hissing noise when treated with acids. If vinegar, which contains acetic acid, be poured upon limestone, marble, malachite (contains copper carbonate), &c., carbonic anhydride is evolved with a hissing noise. It is necessary to remark that without the presence of water neither hydrochloric acid, nor even sulphuric acid nor acetic acid, acts on limestone. We shall refer to this hereafter.

it be necessary to obtain dry carbonic anhydride, it must be passed through chloride of calcium.⁵

Carbonic anhydride may also be prepared by heating many of the salts of carbonic acid ; for instance, by heating magnesium carbonate, MgCO_3 (in dolomite), the separation is easily effected, particularly in the presence of the vapours of water. The acid salts of carbonic acid (see further on) readily give much carbonic anhydride when heated. Carbonic anhydride, together with water, is produced during the combustion of all organic compounds in a stream of oxygen or by heating them with substances which readily part with oxygen to them—for instance, with copper oxide, potassium chlorate (readily causing an explosion), &c.




FIG. 62.—Apparatus for the combustion of organic substances by igniting them with oxide of copper.

The method of estimating the amount of carbon in organic compounds is founded on this property. For this purpose a glass tube, closed at one end, is filled with a mixture of the organic substance (about 0.2 grams) and copper oxide. The open end of the tube is fitted with a

⁵ The direct observations made (1876) by Messrs. Bogouski and Kayander lead to the conclusion that the quantity of carbonic anhydride evolved by the action of acids on marble (as homogeneous as possible) is directly proportional to the time of action, the extent of surface, and the degree of concentration of the acid, and inversely proportional to the molecular weight of the acid. If the surface of a piece of Carrara marble be equal to one decimetre, the time of action one minute, and one cubic decimetre or litre contains one gram of hydrochloric acid, then about 0.02 gram of carbonic anhydride will be evolved. If the litre contains n grams of hydrochloric acid, then by experiment the amount will be $n \times 0.02$ of carbonic anhydride. Therefore, if the litre contains 36.5 ($=\text{HCl}$) grams, about 0.73 grams of carbonic anhydride (about half a litre) would be evolved per minute. If nitric acid or hydrobromic acid be used instead of hydrochloric, then, with a combining proportion of the acid, the same quantity of carbonic anhydride will be evolved ; thus, if the litre contains 63 ($=\text{HNO}_3$) grams of nitric acid, or 81 ($=\text{HBr}$) grams of hydrobromic acid, the quantity of carbonic anhydride evolved will still be 0.73 gram.

cork and tube containing calcium chloride, for absorbing the water formed by the oxidation of the substance. This tube is hermetically connected (by a caoutchouc tube) with potash bulbs or other weighing apparatus (Chap. V.) containing alkali destined to absorb the carbonic anhydride. The increase in weight of this apparatus shows the amount of carbonic anhydride formed during the combustion of the given substance, and the quantity of carbon may be determined from this, because three parts of carbon give eleven parts of carbonic anhydride.

Carbonic anhydride is colourless, has a slight smell and a feeble acid taste; its density in a gaseous state is twenty-two times greater than that of hydrogen, because its molecular weight is forty-four.⁶ It is an example of those gaseous substances which have been long ago transformed into all the three states. In order to obtain liquid carbonic anhydride, the gas must be submitted to a pressure of thirty-six atmospheres at 0°.⁷ Its absolute boiling point = +32°.⁸ Liquid carbonic anhydride is colourless, does not mix with water, but is soluble in alcohol, ether, and oils; at 0° its specific gravity is 0.83. When poured into a tube, which is then sealed up, liquid carbonic anhydride is easily preserved, because a thick tube easily resists the pressure which the liquid entails at an ordinary temperature—namely, about fifty atmospheres. The boiling point of this liquid lies at -80° that is to say, the pressure of carbonic acid gas at that temperature does not exceed that of the atmosphere. At the ordinary temperature the liquid remains as such for some time under ordinary pressure, on account of its requiring a considerable amount of heat for its evaporation. If the evaporation takes place rapidly, especially if the liquid issues in a stream, such a decrease of temperature occurs that

⁶ As carbonic anhydride is one and a half times heavier than air, it diffuses with difficulty, and therefore does not easily mix with air, but sinks in it. This may be shown in various ways; for instance, it may be carefully poured from one vessel into another containing air. If a lighted taper be plunged into the vessel containing carbonic anhydride it is extinguished, and then, after pouring the gas into the other cylinder, it will burn in the former and be extinguished in the latter. If a certain quantity of carbonic anhydride be poured into a vessel containing air, and soap-bubbles be introduced, they will only sink as far as the line where the atmosphere of carbonic anhydride commences, as this latter is heavier than the soap-bubbles filled with air. Naturally, after a certain lapse of time, the carbonic anhydride will be diffused throughout the vessel, and form a uniform mixture with the air, just as salt in water.

⁷ This liquefaction was first observed by Faraday, who sealed up in a tube a mixture of a carbonate and sulphuric acid. Afterwards this method was very considerably improved by Thilorner and Natterer, whose apparatus is described on page 289. It is, however, necessary to remark here that in working with liquid carbonic anhydride it is indispensable to have good liqetifying apparatus, constant cooling, and in particular a rapid preparation of large masses of pure carbonic anhydride.

⁸ Carbonic anhydride, having the same molecular weight as nitrous oxide, very much resembles it when in a liquid state.

a part of the carbonic anhydride is transformed into a solid snowy mass. Water, mercury, and many other liquids freeze on coming into contact with snowlike carbonic anhydride.⁹ In this form carbonic anhydride may be preserved for a long time in the open air, because it requires still more heat to turn it into a gas than when in a liquid state. Solid carbonic anhydride, notwithstanding its very low temperature, can be safely placed on the hand, because it constantly evolves gas which prevents its coming into actual contact with the skin; but if a piece be squeezed between the fingers, it produces a severe frost bite similar to a burn. If the snowlike solid be mixed with ether a semi-liquid mass is obtained, which may be used for artificial refrigeration. This mixture may be used for liquefying many other gases—such as chlorine, nitrous oxide, hydrogen sulphide, and others. The evaporation of such a mixture proceeds with far greater rapidity under the receiver of an air-pump, and consequently the refrigeration is more intense. By this means many gases may be liquefied which resist other methods—namely, olefiant gas, hydrochloric acid gas, and others. Liquid carbonic anhydride in this case congeals in the tube into a glassy transparent mass. Pictet availed himself of this method for liquefying many permanent gases (see Chap. II.).

The capacity which carbonic anhydride has of being liquefied stands in connection with its *solubility in considerable quantity in water*, alcohol, and other liquids. Its solubility in water has been already spoken of in the first chapter. Carbonic anhydride is still more soluble in alcohol than in water, namely at 0° one volume of alcohol dissolves 4.3 volumes of this gas, and at 20° 2.9 volumes.

Aqueous solutions of carbonic anhydride, under a pressure of several atmospheres, are now prepared artificially, because water saturated with this gas is a good means of promoting digestion and quenching thirst. For this purpose the carbonic anhydride is pumped by means of a force pump into a closed vessel containing the liquid, and then bottled off, taking special means to ensure rapid and air-tight corking. Various effervescing drinks and artificially effervescing wines are thus prepared. The presence of carbonic anhydride has an important

⁹ When a fine stream of liquid carbonic anhydride is discharged into a closed metallic vessel, about one-third of its mass solidifies and the remainder evaporates. In employing solid carbonic anhydride for making experiments at low temperatures, it is best to use it mixed with ether, otherwise there will be few points of contact. If a stream of air be blown through a mixture of liquid carbonic anhydride and ether, the evaporation proceeds rapidly, and great cold is obtained. At present in some special manufactories (and for making artificial mineral waters) carbonic anhydride is liquefied on the large scale, poured into wrought-iron cylinders provided with screwed taps, and in this manner it can be transported and safely preserved for a long time.

significance in nature, because by this means water acquires the property of destroying and dissolving many substances which are not acted on by pure water; for instance, calcium phosphates and carbonates are soluble in water containing carbonic acid. If the water in the interior of the earth is saturated with carbonic acid under pressure, the quantity of calcium carbonate in solution may reach three grams per litre, and on issuing at the surface, as the carbonic anhydride escapes, the calcium carbonate will be deposited.¹³ Water charged with carbonic anhydride brings about the destruction of many rocky formations by removing the lime, alkali, &c., from them. This process has been going on and continues on an enormous scale. Rocky formations contain silica and the oxides of various metals, amongst others oxides of aluminium, calcium, and sodium. Water charged with carbonic acid dissolves both the latter, transforming them into carbonates. The waters of the ocean ought, as the evolution of the carbonic anhydride proceeds, to precipitate salts of lime; these are actually found everywhere on the surface of the ground in those places which previously formed the bed of the ocean.

The presence of carbonic anhydride in solution in water is essential to the nourishment and growth of water plants. Although carbonic anhydride is soluble in water, yet no definite hydrate is formed;¹⁴ nevertheless an idea of the composition of this hydrate may be

¹³ If such water trickles through crevices and enters a cavern, the evaporation will be slow, and therefore in those places from whence the water drips growth of calcium carbonate will be formed, just like the stalactes formed on the roof grottoes in winter time. Similar conical and conical-tower growths form the so-called stalactites or pendants hanging from above and stalagmites formed on the bottom of caverns. Sometimes these two kinds meet together, forming entire columns filling the cave. Many of these caverns are remarkable for their picturesque aspect; for instance, the cave of Atrypae, in the Grecian Archipelago. This same cave also forms sparry masses of calcium carbonate in those places where the springs come to the surface of the earth. It is therefore very evident that a calcareous solution is sometimes capable of penetrating plants and filling the whole of their mass with calcium carbonate. This is one of the means of petrified plants. Calcium phosphate in solution in water containing carbonic acid plays an important part in nourishing plants, because all plants contain both lime and phosphoric acid.

¹⁴ The crystallhydrate $\text{CO}_2 \cdot \text{H}_2\text{O}$ of Winkler (Chapter I. Note 67), is the first place, is only formed under special conditions; in the second place, it still requires confirmation; and in the third place, it does not correspond with that hydrate H_2CO_3 which should occur, judging from the composition of the salts.

It is easy to demonstrate the acid properties of carbonic anhydride by taking a long tube, closed at one end, and filling it with this gas; a test-tube is then filled with a solution of an alkali (for instance, sodium hydroxide), which is then poured into the long tube and the open end is corked. The solution is then well shaken in the tube, and the corked end plunged into water. If the cork be now withdrawn, under water the water will fill the tube. The vacuum obtained by the absorption of the carbonic anhydride by an alkali is so complete that even an electric discharge will not pass through it. This method is often applied to produce a vacuum.

formed from the composition of the salts of carbonic acid, because a hydrate is nothing but a salt in which the metal is replaced by hydrogen. As carbonic anhydride forms salts of the composition K_2CO_3 , Na_2CO_3 , $HNaCO_3$, &c., therefore carbonic acid ought to have the composition H_2CO_3 —that is, it ought to be formed from $CO_2 + H_2O$. Whenever this substance is formed, it decomposes into its component parts—that is, into water and carbonic anhydride. *The acid properties* of carbonic anhydride are demonstrated by its being directly absorbed by alkaline solutions and forming salts with them. In distinction from nitric, HNO_3 , and similar monobasic acids which with univalent metals (exchanging one atom for one atom of hydrogen) give salts such as those of potassium, sodium, and silver containing only one atom of the metal ($NaNO_3$, $AgNO_3$), and with bivalent ¹² metals (such as calcium, barium, lead) salts containing two acid groups—for example $Ca(NO_3)_2$, $Pb(NO_3)_2$ —carbonic acid, H_2CO_3 , is *bibasic*, that is, contains two atoms of hydrogen in the hydrate or two atoms of univalent metals in their salts: for example Na_2CO_3 is washing soda, a normal salt; $NaHCO_3$ is the bicarbonate or an acid salt. Therefore, if M' be a univalent metal, its carbonates in general are the normal carbonate M'_2CO_3 and the acid carbonate $M'HCO_3$; or if M'' be a bivalent metal (replacing H_2) its normal carbonate will be $M''CO_3$; these metals do not usually form acid salts, as we shall see further on. The bibasic character of carbonic acid is akin to that of sulphuric acid, H_2SO_4 ,¹³ but the latter, in distinction

¹² The reasons for distinguishing the uni-, bi-, tri-, and quadri-valent metals will be examined hereafter on passing from the univalent metals (Na, K, Li) to the divalent (Mg, Ca, Ba).

¹³ Up to the year 1840, or thereabout, acids were not distinguished by their basicity. Graham, while studying phosphoric acid, H_3PO_4 , and Liebig, while studying many organic acids, distinguished mono-, bi-, and tri-basic acids. Gerhardt and Laurent generalised these relations, showing that this distinction extends over many reactions (for instance, to the faculty of bibasic acids of forming acid salts with alkalis, KHO or $NaHO$, or with alcohols RHO , &c.); but now, from the determination of a hard-and-fast conception as to atoms and molecules, *the basicity of an acid is determined by the number of hydrogen atoms contained in a molecule of the acid which can be exchanged for metals*. If carbonic acid forms acid salts, $NaHCO_3$, and normal salts, Na_2CO_3 , it is evident that the hydrate is H_2CO_3 , a bibasic acid. Otherwise it is at present impossible to account for the composition of these salts. But when $C=6$ and $O=8$ were taken, then the formula CO_2 expressed the composition, but not the molecular weight, of carbonic anhydride; and the composition of the normal salt would be $Na_2C_2O_6$ or $NaCO_3$, therefore carbonic acid might have been considered as a monobasic acid. Then the acid salt would have been represented by $NaCO_3.HCO_3$. Such questions were the cause of much argument and difference of opinion among chemists about forty years ago. At present there cannot be two opinions on the subject if the law of Avogadro-Gerhardt and its sequences be strictly adhered to. Let us, however, remark here that the monobasic acids $R(OH)$ were for a long time considered to be incapable of being decomposed into water and anhydride, and this property was ascribed to the bibasic acids $R(OH)_2$ as containing the elements necessary for the separation of the molecule of water H_2O . This H_2SO_4 or $SO_2(OH)_2$, H_2CO_3 ,

from the former, is an example of the energetic or strong acids (such as nitric or hydrochloric), whilst in carbonic acid we observe but feeble development of the acid properties; hence carbonic acid must be considered a *weak acid*. This conception must, however, be taken as only comparative, as up to this time there is no definitely established rule for measuring the energy¹⁴ of acids. The feeble acid properties of carbonic

or $\text{CO}(\text{OH})_2$, and other bibasic acids decompose into the anhydride, RO , and water, H_2O . But as nitrous, HNO_2 , iodic, HIO_3 , hypochlorous, HClO , and other monobasic acids easily give their anhydrides N_2O_5 , I_2O_5 , Cl_2O , &c., that method of distinguishing the basicity of acids, although it fairly well satisfies the requirements of organic chemistry, must not be considered correct. It may also be remarked that up to the present time not one of the bibasic acids has been found to have the faculty of being distilled without being decomposed into anhydride and water (even H_2SO_4 , on being evaporated and distilled, gives $\text{SO}_3 + \text{H}_2\text{O}$), and the decomposition of acids into water and anhydride proceeds particularly easily in dealing with feebly energetic acids, such as carbonic, nitrous, boric, and hypochlorous. Let us add that carbonic acid, as a hydrate corresponding to marsh gas, $\text{C}(\text{HO})_4 = \text{CO}_2 + 2\text{H}_2\text{O}$, ought to be tetrabasic. But in general it does not form such salts. Basic salts, however, such as $\text{CuCO}_3 \cdot \text{CuO}$, may be regarded in this sense, because CCu_2O_4 corresponds with CH_4O_4 , as Cu corresponds with H_2 . Amongst the ethereal salts (alcoholic derivatives) of carbonic acid corresponding cases are, however, observed; for instance, ethylic orthocarbonate, $\text{C}(\text{C}_2\text{H}_5\text{O})_4$ (obtained by the action of chloropicrin, $\text{C}(\text{NO}_2)_3\text{Cl}$, on sodium ethoxide, $\text{C}_2\text{H}_5\text{ONa}$; boiling point, 158° ; specific gravity, 0.92). The name *orthocarbonic acid* for CH_4O_4 is taken from *orthophosphoric acid*, PH_5O_4 , which corresponds with PH_3 (see Chapter on Phosphorus).

¹⁴ Long ago endeavours were made to find a *measure of affinity* of acids and bases, because some of the acids, such as sulphuric or nitric, form comparatively stable salts, decomposed with difficulty by heat and water, whilst others, like carbonic and hypochlorous acids, do not combine with feeble bases, and with many form salts which are easily decomposed. The same may be said with regard to bases, among which those of potassium, K_2O , sodium, Na_2O , and barium, BaO , may serve as examples of the most powerful, because they combine with the most feeble acids and form a mass of salts of great stability, whilst as examples of the feeblest bases alumina, Al_2O_3 , or bismuth oxide, Bi_2O_3 , may be taken, because they form salts easily decomposed by heat and water if the acid be volatile. Such a division of acids and bases into the feeblest and most powerful is justified by all evidence concerning them, and is quoted in this work. But in recent years the teaching of this subject has acquired quite a new tone, which, in my opinion, cannot be accepted without certain reservations and remarks, although it comprises many interesting features. The fact is that Thomsen, Ostwald, and others proposed to express the measure of affinity of acids to bases by figures drawn from data of the measure of displacement of acids in aqueous solutions, judging (1) from the amount of heat developed by mixing a solution of the salt with a solution of another acid (the avidity of acids, according to Thomsen); (2) from the change of the volumes accompanying such a mutual action of solutions (Ostwald); (3) from the change of the index of refraction of solutions (Ostwald), &c. Besides this there are many other methods which allow us to form an opinion about the distribution of bases among various acids in aqueous solutions. Some of these methods will be described hereafter. It ought, however, to be remarked that in making investigations in aqueous solutions the affinity to water is generally left out of sight. If a base N , combining with acids X and Y in presence of them both, divides in such a way that one-third of it combines with X and two-thirds with Y , a conclusion is formed that the affinity, or power of forming salts, of the acid Y is twice as great as that of X . But the presence of the water is not taken into account. If the acid X has an affinity for water and for N it will be distributed between them; and if X has a greater affinity for water than Y , then less of X will combine with N than of Y . If, in addition to this, the acid X is

acid may, however, be judged from the *accumulation* of many indications. With such energetic alkalis as soda and potash, carbonic acid forms

capable of forming an acid salt NX_2 , and Y is not, the conclusion of the relative strength of X and Y will be still more erroneous, because the X set free will form such a salt on the addition of Y to NX . We shall see in Chapter X. that when sulphuric and nitric acids in weak aqueous solution act on sodium they are distributed exactly in this way: namely, one-third of it combines with the sulphuric and two-thirds with the nitric acid; but, in my opinion, this does not show that sulphuric acid, compared with nitric acid, possesses but half the degree of affinity for bases similar to soda, and only demonstrates the greater affinity of sulphuric acid for water compared with that of nitric acid. In this way the methods of studying the distribution in aqueous solutions probably only shows the difference of the relation of the acid to a base and to water. In general, it is impossible to hope to be able to determine the direct relative degree of affinity of acids for bases by studying aqueous solutions without taking into account the relation of the acids, bases, and salts to water, and by regarding the water as a passive medium, because the water itself forms saline and all other compounds with substances. This refers more especially to those weak solutions by means of which investigations of this kind are most often conducted, because the weak solutions contain a large mass of water, and its influence is then great even when there is but little affinity, in accordance with the law of the action of masses, and from the fact that water itself is a saline oxide.

In deference to these considerations, although the teaching of the distribution of salt-forming elements in *aqueous solutions* is an object of great and independent interest, it can hardly serve to determine the measure of affinity between bases and acids. Similar considerations ought to be kept in view when determining the energy of acids by means of the *electrical conductivity of their weak solutions*. This method, proposed by Arrhenius (1884), and applied on an extensive scale by Ostwald (who developed it in great detail in his *Lehrbuch d. allgemeinen Chemie*, v. ii., 1887), is founded on the fact that the relation of the so-called molecular electrical-conductivity of weak solutions of various acids (I) coincides with the relation in which the same acids stand according to the distribution, (II) found by one of the above-mentioned methods, and with the relation deduced for them from observations upon the velocity of reaction, (III) for instance, according to the rate of the splitting up of an ethereal salt (into alcohol and acid), or from the rate of the so-called inversion of sugar—that is, its transformation into glucose—as is seen by comparing the annexed figures, in which the energy of hydrochloric acid is taken as equal to 100:—

	I.	II.	III.
Hydrochloric acid, HCl . .	100	100	100
Hydrobromic acid, HBr . .	101	98	105
Nitric acid, HNO_3 . . .	100	100	96
Sulphuric acid, H_2SO_4 . .	65	49	74
Formic acid, CH_2O_2 . . .	2	4	1
Acetic acid, $C_2H_4O_2$. . .	1	2	1
Oxalic acid, $C_2H_2O_4$. . .	20	24	18
Phosphoric acid, PH_3O_4 . .	7	—	6

The coincidence of these figures, obtained by so many various methods, presents a most important and most instructive relation between phenomena of a different kind, but in my opinion it does not permit us to assert that the degree of affinity existing between bases and various acids is determined by all these various methods, because the influence of the water must be taken into consideration. On this account, until the theory of solution is more thoroughly worked out, this subject (which now ought to be treated of in special treatises on chemical mechanics) must be treated with great caution. But now we may hope to decide this question by exact methods, which we shall partially touch on when speaking about the velocity of reaction.

There is no means of determining the degree of energy of carbonic acid by any one of the above-mentioned methods.

normal salts, soluble in water, but having an alkaline reaction and in many cases acting themselves as alkalis.¹⁵ The acid salts of these alkalis, NaHCO_3 and KHCO_3 , have a neutral reaction on litmus, although they, like acids, contain hydrogen, which may be exchanged for metals. The acid salts of such acids—as, for instance, of sulphuric acid, NaHSO_4 —have a clearly-defined acid reaction, and therefore carbonic acid is unable to saturate the powerful basic properties of such alkalis as potash or soda. Carbonic acid does not even combine at all with feeble bases, such as alumina, Al_2O_3 , and therefore if a strong solution of sodium carbonate, Na_2CO_3 , be added to a strong solution of aluminium sulphate $\text{Al}_2(\text{SO}_4)_3$, then (according to double saline decompositions) aluminium carbonate, $\text{Al}_2(\text{CO}_3)_3$, ought to be formed, but the carbonic acid separates as this salt splits up in the presence of water into aluminium hydroxide and carbonic anhydride: $\text{Al}_2(\text{CO}_3)_3 + 3\text{H}_2\text{O} = \text{Al}_2(\text{OH})_6 + 3\text{CO}_2$. Therefore feeble bases are unable to retain carbonic acid even at ordinary temperatures. For this reason in the case of bases of medium energy, although they form carbonates, these are comparatively easily decomposed by heating, as is shown by the decomposition of copper carbonate, CuCO_3 (see Introduction), and even calcium carbonate, CaCO_3 . Only the normal (but not the acid) salts of such powerful bases as potassium or sodium are capable of standing a red heat without decomposition. But the acid salts, for instance NaHCO_3 , decompose even on heating their solutions ($2\text{NaHCO}_3 = \text{Na}_2\text{CO}_3 + \text{H}_2\text{O} + \text{CO}_2$), evolving carbonic anhydride. The amount of heat given out by the combination of carbonic acid with bases also shows its feeble acid properties, because it is considerably less than with energetic acids. Thus if a weak solution of forty grams of sodium hydroxide be saturated (until the formation of a normal salt) with sulphuric or nitric acid or another powerful acid, from thirteen to fifteen thousand calories are given out, but with carbonic acid only about ten thousand calories.¹⁶ The majority of carbonates are insoluble in water, and

¹⁵ Thus, for instance, in the washing of fabrics the caustic alkalis, such as sodium hydroxide, in weak solutions, act in removing the fatty matter just in the same way as carbonate solutions; for instance, a solution of soda crystals, Na_2CO_3 . Soap, acts in the same way, being composed of feeble acids, either fatty or resinous, combined with alkali. On this account all such substances are applied to manufacturing purposes, and used equally well in practice for bleaching and washing fabrics. Soda crystals or soap are preferred to caustic alkali, because an excess of the latter may have a destructive effect on the fabrics. It may be supposed that in aqueous solutions with soap or with soda crystals part of the base will form caustic alkali: that is to say, the water will compete with the weak acids, and the alkali will be distributed between them and the water.

¹⁶ Although carbonic acid is reckoned among the feeble acids, yet there are evidently many others still feebler—for instance, hydrogen sulphide, prussic acid, hypochlorous acid, many organic acids, &c. Bases like alumina, or such feeble acids as silica, when in combination with alkalis are decomposed in aqueous solutions by carbonic acid,

therefore such solutions as sodium, potassium, or ammonium carbonates form in solutions of most other salts MX or $M'X_2$, insoluble precipitates of carbonates of the given metals M (univalent metal replacing H) or M' (bivalent metal replacing H_2)—that is, M_2CO_3 or $M'CO_3$. Thus a solution of barium chloride gives with sodium carbonate a precipitate of barium carbonate, $BaCO_3$. For this reason in nature the waters issuing from rocky formations very often contain carbonates; for example, calcium, ferrous or magnesium carbonates, &c.

Carbonic anhydride—which, like water, is formed with the development of a large amount of heat—is very stable. For this reason very few substances are capable of depriving it of its oxygen. However, magnesium, potassium and like metals, on being heated, burn in it, separating carbon and forming oxides. If a mixture of carbonic anhydride and hydrogen be passed through a heated tube, the formation of water and carbonic oxide will be observed; $CO_2 + H_2 = CO + H_2O$.

but on fusion—that is, without the presence of water—they displace it, which clearly shows in phenomena of this kind how much depends upon the conditions of reaction and the properties of the substances formed. These relations, which at first sight appear complex, may be best understood if we represent that two salts, MX and NY , in general always give, more or less, two other salts, MY and NX , and examine the properties of the derived substances. Thus, in solution, sodium silicate, Na_2SiO_5 , with carbonic anhydride will to some extent form sodium carbonate and silica, SiO_2 ; but the latter, being colloid, separates, and the remaining mass of sodium silicate is again decomposed by carbonic anhydride, so that the matter terminates with the complete separation of the silica and the formation of sodium carbonate. In a fused state the case is different; sodium carbonate will react with silica to form carbonic anhydride and sodium silicate, but the carbonic anhydride will be separated as a gas, and therefore in the residue the former reaction will again take place, and the matter will end with the complete separation of carbonic anhydride and the formation of sodium silicate. If nothing is separated from the sphere of the reaction distribution takes place. Therefore, although carbonic anhydride is a feeble acid, still not for this reason, but only in virtue of its gaseous form, do all soluble acids displace it in saline solutions. The small amount of energy of carbonic anhydride was brought forward to account for its being separated from salts by other acids. This is, however, not correct. Such a separation only depends on the properties of the gas and its compounds. Thus acetic acid displaces carbonic anhydride from all carbonates, but under certain conditions the latter is capable of displacing acetic acid. Thus if carbonic anhydride be passed through an alcoholic solution of potassium acetate the acetic acid is set free and the potassium carbonate separates, being insoluble in alcohol. Just the reverse decomposition takes place in water. From this it is evident that the properties of the compounds formed and of the reacting substances have just as much influence on the course of double decompositions as the measure of affinity. Notwithstanding its feeble acid properties, carbonic acid decomposes certain salts in solution, as shown, for instance, in the investigations of Sechenoff on the solution of carbonic anhydride in saline solutions (Chap. I. Note 38). Still the relative energy of acids and bases plays a part in all these cases, which we shall discuss further on when touching on questions of distribution and of velocity of reaction. The principles of that kind of conception of chemical mutual action such as ought now to be accepted were sought for by Berthollet at the commencement of the present century, and sometimes bear the name of 'Berthollet's laws,' to which we will turn our attention in the following chapter.

But only a portion of the carbonic acid gas undergoes this change, and therefore the result will be a mixture of carbonic anhydride, carbonic oxide, hydrogen, and water, which does not change under the action of heat.¹⁷ Although, like water, carbonic anhydride is exceedingly stable, still on being heated it partially decomposes into carbonic oxide and oxygen. Deville showed that such is the case if carbonic anhydride be passed through a long heated tube containing pieces of porcelain and heated to 1300° . If the products of decomposition—namely, the carbonic oxide and oxygen—be suddenly cooled, they can be collected separately, although they partly reunite together. A similar decomposition of carbonic anhydride into carbonic oxide and oxygen takes place on passing a series of electric sparks through it (for instance, in the eudiometer). With this an increase of volume occurs, because two volumes of CO_2 give two volumes of CO and one volume of O. The decomposition reaches a certain limit (less than one-third) and does not proceed further, so that the result is a mixture of carbonic anhydride, carbonic oxide, and oxygen, which is not altered in composition by the continued action of the sparks. This is readily understood, as it is a reversible reaction. If the carbonic anhydride be removed, then the mixture explodes when a spark is passed and forms carbonic anhydride. If from an identical mixture the oxygen (and not the carbonic anhydride) be removed, and a series of sparks again be passed, the decomposition is renewed,

¹⁷ Hydrogen and carbon are near akin to oxygen as regards affinity, but it ought to be considered that the affinity of hydrogen is slightly greater than that of carbon, because during the combustion of hydrocarbons the hydrogen burns first. Some idea of this similarity of affinity may be formed by the quantity of heat evolved. Gaseous hydrogen, H_2 , on combining with an atom of oxygen, O 16, develops 69000 heat-units if the water formed be condensed to a liquid state. If the water remains in the form of a gas (steam) the latent heat of evaporation must be subtracted, and then 58000 calories will be developed. Charcoal taken in the solid form on combining with O_2 -32 develops about 97000 calories, forming gaseous CO_2 . If the charcoal were gaseous like the hydrogen, and only contained C_2 in its molecule, much more heat would be developed, and judging by other substances, whose molecules on passing from the solid to the gaseous state absorb about 10000 to 15000 calories, it must be held that gaseous carbon on forming gaseous carbonic anhydride would develop not less than 110,000 calories—that is, approximately twice as much as is developed in the formation of water. And as in a molecule of carbonic anhydride there is twice as much oxygen as in a molecule of water, the oxygen develops approximately the same quantity of heat on combining with hydrogen and carbon. That is to say, that here we find the same close affinity (*see* Chap. II. Note 7) determined by the quantity of heat as between hydrogen, zinc, and iron. For this reason here also, as in relation to hydrogen and iron, we ought to expect an evident distribution of oxygen between hydrogen and carbon, if they are both in excess compared with the amount of oxygen; but if there be an excess of carbon it will decompose water, whilst an excess of hydrogen will decompose carbonic anhydride. If similar relations of mutual action are made clear in isolated cases, still the full theory of the subject is wanting in the present condition of chemical knowledge.

and terminates with the complete decomposition of the carbonic anhydride. Phosphorus is used in order to attain the complete absorption of the oxygen. In these examples we see that a known mixture of changeable substances is capable of arriving at a state of stable equilibrium, destroyed, however, by the removal of one of the substances composing the mixture. This represents one of the instances of the influence of mass. And as on rapid cooling the combustible carbonic oxide does not succeed in combining with the oxygen, with which it totally combines if slowly cooled, forming carbonic anhydride, here, as in all chemical phenomena, the action of time is apparent—that is, the existence of a definite velocity of reaction.

Although carbonic anhydride is decomposed on heating, yielding oxygen, it is, nevertheless, like water, an unchangeable substance at ordinary temperatures. The decomposition of carbonic anhydride, as effected by plants, is on this account all the more remarkable ; in this case the whole of the oxygen of the carbonic anhydride is separated in the free state. The mechanism of this decomposition is that the heat and light absorbed by the plants are expended in the decomposition of the carbonic anhydride. This accounts for the enormous influence of temperature and light on the growth of plants. But it is at present not clearly understood how this takes place, or by what separate intermediate reactions the whole process of decomposition of carbonic anhydride in plants into oxygen and the carbohydrates (Chapter VIII.) remaining in them, takes place. It is known that sulphurous anhydride (in many ways resembling carbonic anhydride) under the action of light (and also of heat) forms sulphur and sulphuric anhydride, SO_3 , and in the presence of water sulphuric acid. But no similar decomposition has been directly obtained with carbonic anhydride, indeed it forms the highest degree of oxidation of carbon ; perhaps for that reason the oxygen separates. On the other hand, it is known that plants always form and contain *organic acids*, and these must be regarded as derivatives of carbonic acid, as is seen by all their reactions, which we will shortly treat of. For this reason it might be thought that the carbonic acid absorbed by the plants first forms organic acids in them, and that these latter in their final transformation form all the other complex organic substances of the plants. Many organic acids are found in plants in considerable quantity ; for instance, tartaric acid, $\text{C}_4\text{H}_6\text{O}_6$, found in grape-juice and in the acid juice of many plants ; malic acid, $\text{C}_4\text{H}_6\text{O}_5$, not only found in unripe apples but in still greater quantities in mountain ash berries ; citric acid, $\text{C}_6\text{H}_8\text{O}_7$, found in the acid juice of lemons, in gooseberries, cranberries, &c. ; oxalic acid, $\text{C}_2\text{H}_2\text{O}_4$, found in wood-sorrel and

many other plants. Sometimes these acids exist in a free state in the plants, and sometimes in the form of salts; for instance, tartaric acid is met with in grapes as the salt known as cream of tartar, but in the impure state called argol, or tartar, $C_4H_5KO_6$. In sorrel we find the so-called salts of sorrel, or acid potassium oxalate, C_2HKO_4 . There is a very clear connection between carbonic anhydride and the above-mentioned organic acids—namely, they all, under one condition or another, yield carbonic anhydride, and can all be formed by means of it from substances destitute of acid properties. The following examples afford the best demonstration of this fact: if acetic acid, $C_2H_4O_2$, the acid of vinegar, be passed in the form of vapour through a heated tube, it splits up into carbonic anhydride and marsh gas $=CO_2 + CH_4$. But it can also be obtained conversely from those components into which it decomposes. If one equivalent of hydrogen in marsh gas be replaced (by indirect means) by sodium, and the compound CH_3Na is obtained, this directly absorbs carbonic anhydride, forming a salt of acetic acid, $CH_3Na + CO_2 = C_2H_3NaO_2$; from this acetic acid itself may be easily obtained in a similar way to that by which nitric acid may be obtained from nitre. Therefore acetic acid decomposes into marsh gas and carbonic anhydride, and conversely is obtainable from them. The hydrogen of marsh gas does not, like that in acids, show the property of being directly replaced by metals; the gas itself does not show any acid character whatever, but on combining with the elements of carbonic anhydride it acquires the properties of an acid. The investigation of all other organic acids shows similarly that their acid character depends on their containing the elements of carbonic anhydride. For this reason there is no organic acid containing less oxygen in its molecule than there is in carbonic anhydride; every organic acid contains in its molecule at least two atoms of oxygen. In order to express the relation between carbonic acid, H_2CO_3 , and organic acids, and in order to understand the reason of the acidity of these latter, it is simplest to turn to that law of substitution which shows (Chapter VI.) the relation between the hydrogen and oxygen compounds of nitrogen, and permits us (Chapter VIII.) to regard all hydrocarbons as derived from methane. The facts of the matter are as follows: if we have a given organic compound, A, which has not the properties of an acid, but as the derivative of a hydrocarbon contains hydrogen combined with carbon, then ACO_2 will be a monobasic organic acid, A_2CO_2 a bibasic, A_3CO_2 a tribasic, and so on—that is, each molecule, CO_2 , transforms one atom of hydrogen into that state in which it may be replaced by metals, as in acids. This already furnishes proof that in organic acids it is necessary to recognise the group HCO_2 , or carboxyl.

If the addition of CO_2 raises the basicity the removal of CO_2 lowers it. Thus from the bibasic oxalic acid, $\text{C}_2\text{H}_2\text{O}_4$, or phthalic acid, $\text{C}_8\text{H}_6\text{O}_4$, by eliminating CO_2 (easily effected experimentally) we obtain the monobasic formic acid, CH_2O_2 , or benzoic acid, $\text{C}_7\text{H}_6\text{O}_2$, respectively. The nature of carboxyl is directly explained by the law of substitution. Judging from what has been stated in Chapters V. and VIII. concerning this law, it should already be evident that CO_2 is CH_4 , with the exchange of H_1 for O_2 , and the hydrate of carbonic acid, H_2CO_3 , is $\text{CO}(\text{OH})_2$, that is, methane, where two parts of hydrogen are replaced by two parts of the water radicle (OH , hydroxyl), and the other two by oxygen. Therefore the group $\text{CO}(\text{OH})$, or carboxyl, HCO_2 , is a part of carbonic acid, and is equivalent to (OH) , and therefore also to H . That is, it is a univalent residue of carbonic acid capable of replacing one atom of hydrogen. Carbonic acid itself is a bibasic acid, both hydrogen atoms in it being replaceable by metals, therefore carboxyl, which contains one of the hydrogen atoms of carbonic acid, represents a group in which the hydrogen is exchangeable with metals. And therefore if 1, 2 . . . n atoms of non-metallic hydrogen are exchanged 1, 2 . . . n times for carboxyl we ought to obtain 1, 2 . . . n -basic acids. *Organic acids are the products of the carboxyl substitution of hydrocarbons.*¹⁸ If in the saturated hydrocarbons, $\text{C}_n\text{H}_{2n+2}$, one part of hydrogen is replaced by carboxyl the monobasic saturated (or fatty) acids, $\text{C}_n\text{H}_{2n+1}(\text{CO}_2\text{H})$, will be obtained, as, for instance, formic,

¹⁸ If CO_2 is the anhydride of a bibasic acid, and carboxyl corresponds with it, replacing the hydrogen of hydrocarbons, and giving them the character of comparatively feeble acids, then SO_3 is the anhydride of an energetic bibasic acid, and *sulphoxyl*, $\text{SO}_2(\text{OH})$, corresponds with it, being capable of replacing the hydrogen of hydrocarbons, and forming comparatively energetic *sulphur oxyacids (sulphonic acids)*; for instance, $\text{C}_6\text{H}_5(\text{COOH})$, benzoic acid, and $\text{C}_6\text{H}_5(\text{SO}_2\text{OH})$, benzenesulphonic acid, are derived from C_6H_6 . As the exchange of H for methyl, CH_3 , is equivalent to the addition of CH_2 , the exchange of carboxyl, COOH , is equivalent to the addition of CO_2 ; so the exchange of H for sulphoxyl is equivalent to the addition of SO_3 . The latter proceeds directly, for instance: $\text{C}_6\text{H}_6 + \text{SO}_3 = \text{C}_6\text{H}_5(\text{SO}_2\text{OH})$.

In Chapter VIII. we saw that the structure of hydrocarbons might and ought to be represented by the presence of CH_3 , CH_2 , CH , and C -radicles of methane, starting from methane itself; therefore the atoms of hydrogen are retained by separate atoms of carbon, which refers also to OH , COOH , and other radicles. Although with one atom of carbon, H_4 , H_5 , and H_2 , or several, CH_3 , Cl , &c., may be retained, yet not more than one of hydroxyl may be retained, and therefore there is no alcohol $\text{CH}_2(\text{OH})_2$ or $\text{C}_3\text{H}_1(\text{OH})_4$. The carboxyl, as well as the sulphoxyl, substitution of hydrogen in hydrocarbons, leads to the formation of acids, because the derivative acids H_2CO_3 and H_2SO_4 are bibasic. Nitric acid, being monobasic, is unable to form a similar radicle. Its radicle, NO_3 , does not contain hydrogen, and does not produce acidity, but has the same relation to the acid $\text{NO}_2(\text{OH})$ as carboxyl to carbonic acid.

As, according to the determinations of Thomsen, the heat of combustion of the vapours of acids RCO_2 is known where R is a hydrocarbon, and the heat of combustion of the hydrocarbons R themselves, it may be seen that the formation of acids, RCO_2 , from $\text{R} + \text{CO}_2$ is always accompanied by a *small* absorption or development of heat. We give

HCO_2H , acetic acid, $\text{CH}_3\text{CO}_2\text{H}$, . . . stearic acid, $\text{C}_{17}\text{H}_{35}$, CO_2H , &c. The double substitution will give bibasic acids, $\text{C}_n\text{H}_{2n}(\text{CO}_2\text{H})(\text{CO}_2\text{H})$; for instance, oxalic $n=0$, malonic $n=1$, succinic acid $n=2$, &c. To benzene, C_6H_6 , correspond benzoic acid, $\text{C}_6\text{H}_5(\text{CO}_2\text{H})$, phthalic acid (and its isomerides), $\text{C}_6\text{H}_4(\text{CO}_2\text{H})_2$, up to melitic acid, $\text{C}_6(\text{CO}_2\text{H})_6$, in all of which the basicity is equal to the number of carboxyl groups. As many isomerides exist in hydrocarbons, it is readily understood not only that such can exist also in organic acids, but that their number and structure may be foreseen. As in hydrocarbons the hydrogen may be replaced by chlorine, hydroxyl, &c., evidently the same is possible with organic acids. And, therefore, the number and transformations of such compounds are exceedingly great. This complex and most interesting branch of chemistry is treated separately in organic chemistry.

Carbonic Oxide.—This gas is formed whenever the combustion of organic substances takes place in the presence of a large excess of incandescent charcoal; the air first burns the carbon into carbonic anhydride, but this in penetrating through the red-hot charcoal is transformed into carbonic oxide, $\text{CO}_2 + \text{C} = 2\text{CO}$. By this reaction carbonic oxide is prepared by passing carbonic anhydride through charcoal at a red heat. It may be separated from the excess of carbonic anhydride by passing it through a solution of alkali, which does not absorb carbonic oxide. This reduction of carbonic anhydride explains why carbonic oxide is formed in ordinary clear fires, where the incoming air passes over a large surface of heated coal. A blue flame is then observed burning above the coal; this is the burning carbonic oxide. When charcoal is burnt in stacks, or when a thick layer of coal is burning in a brazier, and under many similar circumstances, carbonic oxide is also formed. In metallurgical processes, for instance, when iron is smelted from the ore, very often the same process of conversion of carbonic anhydride into carbonic oxide occurs, especially if the combustion of the coal be effected in high, so-called blast, furnaces and ovens, where the air enters from the lower part and is compelled to pass through a thick layer of coal. In this way, also, combustion with flame may be

the heats of combustion in thousands of calories, referring to the molecular weights of the burning substances:—

R=	H_2	CH_4	C_2H_6	C_6H_6
	68.4	212	370	777
$\text{RCO}_2=$	69.4	225	387	766

Thus H_2 corresponds with formic acid, CH_2O_2 ; benzene, C_6H_6 , with benzoic acid, $\text{C}_7\text{H}_6\text{O}_2$. The data for the latter are taken from Stohmann, and refer to the solid condition. For formic acid Stohmann gives the heat of combustion as 59000 calories in a liquid state, but in a state of vapour, 64.6 thousand units, which is much less than according to Thomsen.

obtained from those kinds of fuel which under ordinary conditions burn without flame : for instance, anthracite, coke, charcoal. Heating by means of a gas-producer—that is, an apparatus producing carbonic oxide from fuel—is carried on in the same manner.¹⁹ In transforming one part of charcoal into carbonic oxide 2420 heat units are given out, and on burning to carbonic anhydride 8080 heat units. It is evident that on transforming the charcoal first into carbonic oxide we obtain a gas which in burning is capable of giving out 5660 heat units for one part of charcoal. This preparatory transformation of fuel into carbonic oxide, or producer gas containing a mixture of carbonic oxide (about $\frac{1}{3}$ by volume) and nitrogen ($\frac{2}{3}$ volume), in many cases presents most important advantages, as it is easy to completely burn gaseous fuel without an excess of air, which would lower the temperature.²⁰ In stoves where solid fuel is burnt it is impossible to effect the complete combustion of the various kinds of fuel without admitting an excess of air. Gaseous fuel, such as carbonic oxide,

¹⁹ In gas-producers all carbonaceous fuels are transformed into inflammable gas. In those which (on account of their slight density and large amount of water, or incombustible admixtures which absorb heat) are not as capable of giving a high temperature




FIG. 63.—Gas-producer for the formation of carbon monoxide for heating purposes.

in ordinary furnaces—for instance, fir cones, peat, the lower kinds of coal, &c.—the same gas is obtained as with the best kinds of coal, because the water condenses on cooling, and the ashes and earthy matter remain in the gas-producer. The construction of a gas-producer is seen from the accompanying drawing. The fuel lies on the fire-bars O, the air enters through them and the ash-hole (drawn by the draught of the chimney of the stove where the gas burns, or else forced by a blowing apparatus), the quantity of air being exactly regulated by means of valves. The gases formed are then led by the tube V, provided with a valve, into the gas main, U. The addition of fuel ought to proceed in such a way as to avoid the separation of carbonic anhydride; hence the space A is kept filled with the combustile and covered with a lid.

²⁰ An excess of air lowers the temperature of combustion, because it becomes heated itself, as explained in Chapter III. In ordinary furnaces the excess of air is three or four times

greater than the quantity required for perfect combustion. In the best furnaces (with fire-bars, regulated air supply, and corresponding chimney draught) it is necessary to introduce twice as much air as is necessary, otherwise the smoke contains much carbonic oxide.

is easily completely mixed with air and burnt without excess of it. If, in addition to this, the air and gas required for the combustion be previously heated by means of the heat which would otherwise be uselessly carried off in the products of combustion (smoke)²¹ it is easy to reach a high temperature, so high (about 1800°) that platinum may be melted. Such an arrangement is known as a *regenerative furnace*.²² By means of this process not only may there be obtained the high temperatures indispensable in many industries (for instance, glass-working, steel-melting, &c.), but also great advantage²³ as regards the quantity of fuel, because the transmission of heat to the object to be heated, conditions being equal, is determined by the difference of temperatures.

The transformation of carbonic anhydride, by means of charcoal,

²¹ If in manufactories it is necessary, for instance, to maintain the temperature in a furnace at 1000°, the flame passes out at this or a higher temperature, and therefore much fuel is lost in the smoke. For the draught of the chimney a temperature of 100° to 150° is sufficient, and therefore the remaining heat ought to be utilised. For this purpose the flues are carried under boilers or other heating apparatus. The preparatory heating of the air is the best means of utilisation, as by this means the highest temperature is attained and the quickest heating and greatest economy are effected.

²² Regenerative furnaces were introduced by the Brothers Siemens about the year 1860 in many industries, and mark a most important progress in the use of fuel, especially in obtaining high temperatures. The principle is as follows: The products of combustion from the furnace are led into a chamber, I, and heat up the bricks in it, and then pass into the outlet flue; when the bricks are at a red heat the products of combustion are passed (by altering the valves) into another adjoining chamber, II, and air requisite for the combustion of the generator gases is passed through I. In passing round about the incandescent bricks the air is heated, and the bricks cool—that is, the heat of the smoke is returned into the furnace. The air is then passed through II, and the smoke through I. The regenerative burners for illuminating gas are founded on this same principle, the products of combustion heat the incoming air and gas, the temperature is higher, the light brighter, and an economy of gas is effected in lighting. Absolute perfection in these appliances has of course not yet been attained; amelioration is still further possible, but dissociation imposes a limit because at a certain high temperature combinations do not ensue, possible temperatures being limited by reverse reactions. Here, as in a number of other cases, the ultimate conception of the subject ought to be limited to the sphere of general external and visible advantages.

²³ At first sight it appears absurd, useless, and paradoxical to lose nearly one-third of the heat which fuel develops by turning it into gas. Actually the advantage is enormous, especially for producing high temperatures, as is already seen from the fact that fuel rich in oxygen (for instance, wood) when damp is unable, with any kind of hearth whatever, to give the temperature required for glass-melting or steel-casting, whilst in the gas-producer they furnish exactly the same gas as the driest and most carbonaceous fuel. In order to understand the principle which is here involved, it is sufficient to turn one's attention to the fact that the only heat employed with advantage is that which is concentrated in the shape of products of combustion having a high temperature. A large amount of heat, but having a low temperature, in many cases is of no use whatever. We are unable here to enter into all the details of the complicated matter of the application of fuel, and further particulars must be sought for in special technical treatises. The following footnotes, however, contain certain fundamental figures for calculations concerning combustion.


into carbonic oxide ($C + CO_2 = CO + CO$), is considered a reversible reaction, because at a high temperature the carbonic oxide splits up into carbon and carbonic anhydride, as Sainte-Claire Deville showed by using the method of the 'cold and hot tube.' Inside a tube heated in a furnace another thin metallic (silvered copper) tube is fitted, through which a constant stream of cold water flows. The carbonic oxide coming into contact with the heated walls of the exterior tube forms charcoal, and its minute particles settle in the form of lampblack on (the lower part) of the cold tube, and, since they are cooled, they do not act further on the oxygen or carbonic anhydride formed.²⁴ A series of electric sparks also decomposes carbonic oxide into carbonic anhydride and carbon, and if the carbonic anhydride be removed by alkali complete decomposition may be obtained (Deville). Aqueous vapour, which is so similar to carbonic anhydride in many respects, acts, at a high temperature, on charcoal in an exactly similar way, $C + H_2O = H_2 + CO$. From 2 volumes of carbonic anhydride with charcoal 4 volumes of carbonic oxide (2 molecules) are obtained, and precisely the same from 2 volumes of water vapour with charcoal

²⁴ The first product of combustion of charcoal is always carbonic anhydride, and not carbonic oxide. This is seen from the fact that with a shallow layer of charcoal (less than a decimetre if the charcoal be closely packed) carbonic oxide is not formed at all. It is not even produced with a deep layer of charcoal if the temperature is not above 500° , and the current of air or oxygen is very slow. With a rapid current of air the charcoal becomes red hot, and the temperature rises, and then carbonic oxide appears (Lang 1888). Naumann and Pistor determined that the reaction of carbonic anhydride with carbon commences at about 550° , and that between water and carbon at about 500° . At the latter temperature carbonic anhydride is formed, and only with a rise of temperature is carbonic oxide formed (Lang) from the action of the carbonic anhydride on the carbon, and from the reaction $CO_2 + H_2 = CO + H_2O$. Rathke (1881) showed that at no temperature whatever is the reaction as expressed by the equation $CO_2 + C = 2CO$ complete; a part of the carbonic anhydride remains, and Lang determined that at about 1000° not less than 3 p.c. of the carbonic anhydride remains untransformed into carbonic oxide, even after the action has been continued for several hours. The endothermal reactions, $C + 2H_2O = CO_2 + 2H_2$, and $CO + H_2O = CO_2 + H_2$, are just as incomplete. This is made clear if we note that on the one hand the above-mentioned reactions are all reversible, and therefore bounded by a limit; and, on the other hand, that at about 500° oxygen begins to combine with hydrogen and carbon, and also that the lower limits of dissociation of water, carbonic anhydride, and carbonic oxide lie near one another between 500° and 1200° . For water and carbonic oxide the lower limit of the commencement of dissociation is unknown, but judging from the accumulated data (according to Le Chatelier, 1888) that of carbonic anhydride may be taken as about 1050° . Even at about 200° half the carbonic anhydride dissociates if the pressure be small, about 0.001 atmosphere. At the atmospheric pressure, not more than 0.05 of the carbonic anhydride decomposes. The influence of pressure is here evident, for the reason that the splitting up of carbonic anhydride into carbonic oxide and oxygen is accompanied by an increase in volume (as in the case of the dissociation of nitric peroxide. See Chapter VI. Note 46). As in stoves and lamps, and also with explosive substances, the temperature is not higher than 2000° to 2500° , it is evident that although the partial pressure of carbonic anhydride is small, still its dissociation cannot be considerable, and probably does not exceed 5 p.c.

4 volumes of a gas consisting of hydrogen and carbonic oxide ($\text{H}_2 + \text{CO}$) is formed. This mixture of combustible gases is called *water gas*.²⁵ But aqueous vapour (and only when strongly superheated, otherwise it cools the charcoal) only acts on charcoal to form a large amount of carbonic oxide at a very high temperature (when carbonic anhydride dissociates); it begins to react at about 500° , forming carbonic anhydride, according to the equation $\text{C} + 2\text{H}_2\text{O} = \text{CO}_2 + 2\text{H}_2$. Besides this, carbonic oxide on splitting up forms carbonic anhydride, and therefore water gas always contains a mixture²⁶ in which hydrogen pre-

²⁵ A molecular weight of this gas, or 2 volumes CO (28 grams), on combustion (forming CO_2) gives out 68,000 heat units (Thomsen 67960 calories). A molecular weight of hydrogen, H_2 (or 2 volumes), develops on burning into *liquid* water 69000 heat units (according to Thomsen 68300), but if it forms aqueous vapour 58000 heat units. Charcoal, resolving itself by combustion into the molecular quantity of CO_2 (2 volumes), develops 97000 heat units. From the data furnished by these exothermal reactions it follows: (1) that the oxidation of solid charcoal into carbonic oxide develops 29000 heat units; (2) that the reaction $\text{C} + \text{CO}_2 = 2\text{CO}$ absorbs 39000 heat units; (3) $\text{C} + \text{H}_2\text{O} = \text{H}_2 + \text{CO}$ absorbs (if the water be in a state of vapour) 29000 calories, but if the water be liquid 40000 calories (almost as much as $\text{C} + \text{CO}_2$); (4) $\text{C} + \text{H}_2\text{O} = \text{CO}_2 + 2\text{H}_2$ absorbs (if the water be in a state of vapour) 19000 heat units; (5) the reaction $\text{CO} + \text{H}_2\text{O} = \text{CO}_2 + \text{H}_2$ develops 10000 heat units if the water be in the state of vapour.

Therefore it follows that 2 volumes of CO or H_2 burning into CO_2 or H_2O develop almost the same amount of heat, just as also the heat effects corresponding with the equations



are nearly equal.

²⁶ *Water gas*, obtained from steam at a white heat, contains about 50 p.c. of hydrogen, about 40 p.c. of carbonic oxide, about 5 p.c. of carbonic anhydride, the remainder being nitrogen from the charcoal and air. Compared with producer gas, which contains much nitrogen, this is a gas much richer in combustible matter, and therefore capable of giving high temperatures, and is for this reason of the greatest utility. If carbonic anhydride could be as readily obtained in as pure a state as water, there would be no difference in the heating powers of producer gas and water gas. As regards the utilisation of the heat of the charcoal there is no difference, because on burning carbonic oxide gives out almost as much heat as hydrogen—even more if the smoke has a temperature above 100° , and the water remains as vapour (Note 25). But water gas stands higher than producer gas as regards the concentration of the fuel in its transformation into gas, and therefore in places where a particularly high temperature is required (for instance, for lighting by means of incandescent lime or magnesia, or for steel melting, &c.), and for distributing through pipes at great distances, water gas is at present held in high estimation, but when (in ordinary furnaces, re-heating, glass-melting, and other furnaces) a very high temperature is not required, and there is no need to convey the gas in pipes, producer gas is generally preferred on account of the simplicity of its preparation, especially as for water gas such a high temperature is required that the plant soon becomes damaged.

Water gas is prepared (there are very many systems, but the American patent of T. Lowe, of Norristown, Pennsylvania, is much used) in a cylindrical generator, into which heated air is introduced, in order, by partial combustion of the coke, to heat the remainder, &c., to a white heat. The products of combustion containing carbonic oxide are utilised in a contrivance for superheating steam, which is then passed over the white hot coke. Water gas, or a mixture of hydrogen and carbonic oxide, is thus obtained. The practical

dominates, the volume of carbonic oxide being comparatively less, whilst the amount of carbonic anhydride increases as the temperature of the reaction decreases (generally it is more than 3 per cent.).

Metals, like iron and zinc, which at a red heat are capable of decomposing water with the formation of hydrogen, also decompose carbonic anhydride with the formation of carbonic oxide; so both the ordinary products of complete combustion, water and carbonic anhydride, are very similar in their reactions—and hydrogen may be compared with carbonic oxide. The metallic oxides of the above-mentioned metals, when reduced by charcoal, also give carbonic oxide. Priestley obtained it by heating charcoal with zinc oxide. It must be held that here carbonic anhydride is first produced, but that, combining with carbon, it forms carbonic oxide. As free carbonic anhydride may be transformed into carbonic oxide, so, in the same way precisely, may that carbonic acid which is in a state of combination; therefore, if magnesium or barium carbonates (MgCO_3 or BaCO_3) be heated to a red heat with charcoal, or iron or zinc, carbonic oxide will be produced—for instance, it is obtained by heating an intimate mixture of 9 parts of chalk and 1 part of charcoal in a clay retort.

Many organic substances²⁷ on being heated, or under the action of different agents, yield carbonic oxide; amongst these are many organic or carboxylic acids. The simplest are formic and oxalic acids. Formic acid, CH_2O_2 , on being heated to 200° , easily decomposes into carbonic oxide and water, $\text{CH}_2\text{O}_2 = \text{CO} + \text{H}_2\text{O}$. This reaction may be effected

side of the question resolves itself into utilising all the heat given out by the charcoal, and contained in the incandescent gas, for heating up the air, for the formation and super-heating of the steam.

Water gas is sometimes called '*the fuel of the future*,' because it is applicable to all purposes, develops a high temperature, and is therefore available, not only for domestic and industrial uses, but also for gas-motors (page 172) and for lighting. For the latter purpose platinum, lime, magnesia, zirconia, and similar substances (as in the Drummond light, Chapter III.), are rendered incandescent in the flame, or else the gas is *carburised*—that is, mixed with the vapours of volatile hydrocarbons (generally benzene or naphtha, naphthalene, or simply naphtha gas), which communicate to the pale flame of carbonic oxide and hydrogen a great brilliancy, owing to the high temperature developed by the combustion of the non-luminous gases. As water gas, possessing these properties, may be prepared at central works and conveyed in pipes to the consumers, may be produced from any kind of fuel, and ought to be much cheaper than ordinary gas, it may actually be considered that in course of time (when practice will have determined the cheapest and best way to prepare it) it will not only supplant ordinary gas but will with advantage everywhere replace the ordinary forms of fuel, which in many respects are inconvenient. At present its consumption spreads principally for lighting purposes, and for use in gas-engines instead of ordinary illuminating gas.

²⁷ The so-called yellow prussiate, $\text{K}_4\text{FeC}_6\text{N}_6$, on being heated with ten parts of strong sulphuric acid forms a considerable quantity of very pure carbonic oxide completely free from carbonic anhydride.

by mixing formic acid with glycerin, because in a separate state it volatilises much earlier, and therefore cannot be heated up to the required temperature. The salts of formic acid, on being heated with sulphuric acid, yield carbonic oxide. Usually, however, carbonic oxide is prepared in laboratories, not from formic but from oxalic acid, $C_2H_2O_4$, the more so as formic acid is itself prepared from oxalic acid. The latter acid is easily obtained by the action of nitric acid on starch, sugar, &c.; it is also found in nature. Oxalic acid is easily decomposed by heat; its crystals first lose water, then partly volatilise, but the greater part is decomposed. The decomposition is of the following nature: it splits up into water, carbonic oxide, and carbonic anhydride,²⁸ $C_2H_2O_4 = H_2O + CO_2 + CO$. This decomposition is generally practically effected by mixing oxalic acid with strong sulphuric acid, because the latter favours the decomposition by taking up the water. On heating a mixture of oxalic and sulphuric acids a mixture of carbonic oxide and carbonic anhydride is evolved. This mixture is passed through a solution of an alkali in order to absorb the carbonic anhydride, whilst the carbonic oxide passes on. Oxalic acid in admixture with glycerin, on being heated first to 100° and then to 140° , decomposes in a similar manner.

In its physical *properties* carbonic oxide resembles nitrogen; this is explained by the equality of their molecular weights. The absence of colour and smell, the low temperature of the absolute boiling point, -140° (nitrogen -146°), the faculty of solidifying at -200° (nitrogen, -202°), the boiling point of -190° (nitrogen, -203°), and the slight solubility (page 78), of carbonic oxide are almost the same as in those of nitrogen. The chemical properties of both gases are, however, very different, and in these carbonic oxide resembles hydrogen. Carbonic oxide burns with a blue flame, giving 2 volumes of carbonic anhydride from 2 volumes of carbonic oxide, just as 2 volumes of hydrogen give 2 volumes of aqueous vapour. It explodes with oxygen, in the eudiometer, like hydrogen.²⁹ When

²⁸ The decomposition of formic and oxalic acids, with the formation of carbonic oxide, considering these acids as carboxyl derivatives, may be explained as follows:—The first is $H(COOH)$, and the second $(COOH)_2$, or H_2 , in which one or both parts of hydrogen are exchanged for carboxyl; therefore they are equal to $H_2 + CO_2$ and $H_2 + 2CO_2$; but H_2 reacts with CO_2 , as has been stated above, forming CO and H_2O . From this it is also evident that oxalic acid on losing CO_2 forms formic acid, and also that the latter may proceed from $CO + H_2O$, as we shall see further on.

²⁹ It is remarkable that, according to the investigations of Dixon, perfectly dry carbonic oxide does not explode with oxygen when a spark of low intensity is used, but an explosion takes place if there is the slightest admixture of moisture. L. Meyer, however, showed that sparks of an electric discharge of considerable intensity produce an explosion. I think that this may be explained by the fact that water with

breathed it acts as a strong poison, because it is absorbed by the blood ;³⁰ this explains the action of charcoal fumes, the products of the incomplete combustion of charcoal and other carbonaceous fuels. Owing to its faculty of combining with oxygen, carbonic oxide acts as a powerful reducing agent, taking up the oxygen from many compounds at a red heat, and being itself transformed into carbonic anhydride. The reducing action of carbonic oxide, however, is (like that of hydrogen, Chapter II.) naturally confined to those oxides which easily part with their oxygen—as, for instance, copper oxide—whilst the oxides of magnesium or potassium are not reduced. Metallic iron itself is capable of reducing carbonic anhydride into carbonic oxide, just as it liberates the hydrogen from water. Copper, which does not decompose water, does not decompose carbonic oxide. If a platinum wire heated to 300°, or spongy platinum at the ordinary temperature, be plunged into a mixture of carbonic oxide and oxygen, or of hydrogen and oxygen, the mixture explodes. These reactions remind one exceedingly of those which are peculiar to hydrogen. The following important distinction, however, exists between them, namely : the molecule of hydrogen is composed of H_2 , a group of elements divisible into two like parts, whilst, as the molecule of carbonic oxide, CO , contains unlike atoms of carbon and oxygen, in none of its reactions of combination can it give two molecules of matter containing its elements. This is particularly noticeable in the action of chlorine on hydrogen and on carbonic oxide respectively ; with the former chlorine forms hydrogen chloride, and with the latter it produces the so-called carbonyl chloride, $COCl_2$; that is to say, the molecule of hydrogen, H_2 , under the action of chlorine divides, forming two molecules of hydrochloric acid, whilst the molecule of carbonic oxide entirely enters into the molecule of carbonyl chloride. This characterises the so-called *diatomic* or *bivalent* reactions of radicles or *residues*. H is a monatomic residue or radicle, like K , Cl , and others, whilst carbonic oxide, CO , is an indivisible (without decomposition) bivalent radicle, equivalent to H_2 and not to H , and therefore combining with X_2 and

carbonic oxide gives carbonic anhydride and hydrogen, but hydrogen with oxygen gives hydrogen peroxide (Chapter VII. p. 305), which with carbonic oxide forms carbonic anhydride and water. The water, therefore, is renewed, and again serves the same purpose. But it may be that here it is necessary to acknowledge a simple contact influence.

³⁰ Carbonic oxide is a very quick poison, because it is absorbed by the blood in the same way as oxygen. In addition to this, the spectrum of the absorption of the blood changes so that by the help of blood it is easy to detect the slightest traces of carbonic oxide in the air. M. A. Kapoustin found that linseed oil (and therefore oil paints) are capable of giving off carbonic oxide while drying (absorbing oxygen).

interchangeable with H_2 . This distinction is evident from the annexed comparison :

H^{\cdot} , hydrogen.	CO, carbonic oxide.
HCl , hydrochloric acid.	$COCl_2$, carbonyl chloride.
HKO , potash.	$CO(KO)_2$, potassium carbonate.
HNH_2 , ammonia.	$CO(NH_2)_2$, urea.
HCH_3 , methane.	$CO(CH_3)_2$, acetone.
HHO , water.	$CO(HO)_2$, carbonic acid.

Such monatomic (univalent) residues, X, like H, Cl, Na, NO_2 , NH_4 , CH_3 , CO_2H (carboxyl), OH, and others, in accordance with the law of substitution, combine together, forming compounds, XX' ; with oxygen, or in general with diatomic (bivalent) residues, Y—for instance, with O, CO, CH_2 , S, Ca, &c.—compounds $XX'Y$; but diatomic residues, Y, sometimes capable of existing separately, combine together, YY' and with X_2 or XX' , as we see from the transition of CO into CO_2 and $COCl_2$. This combining faculty of carbonic oxide appears in many of its reactions. Thus it is very easily absorbed by cuprous chloride, CuCl, dissolved in fuming hydrochloric acid, forming a crystalline compound, $COCu_2Cl_2 \cdot 2H_2O$, decomposable by water; it combines directly with potassium (at 90°), forming $(KCO)_n$ ³¹ with platinum dichloride, $PtCl_2$, with chlorine, Cl_2 , &c.

But the compounds of carbonic oxide with the alkalis are still more remarkable—for instance, with potassium or barium hydroxides, &c.—although it is not directly absorbed by them, as it has no acid properties. Berthelot (1861) showed that potash in the presence of water is capable of absorbing carbonic oxide, but the absorption takes place slowly, little by little, and it is only after being heated for many hours that the whole of the carbonic oxide is absorbed by the potash. The salt, $CHKO_2$, is obtained by this absorption; it corresponds with an acid found in nature, namely, the simplest organic—carboxylic acid, *formic acid*, CH_2O_2 . It can be extracted from the potassium salt by means of distillation with dilute sulphuric acid, just as nitric acid is prepared from sodium nitrate. The same acid is found in ants, in nettles (when the points of the nettles enter

³¹ The molecule of metallic potassium (Scott, 1887), like that of mercury, contains one atom, and it is probably in virtue of this that the molecules CO and K combine together. But as in the majority of cases potassium acts as a univalent radicle, the polymeride $K_2C_2O_2$ is formed, and probably $K_{10}C_{10}O_{10}$, because products containing C_{10} are formed by the action of hydrochloric acid. The black mass formed by the combination of carbonic oxide with potassium explodes with great ease, and oxidises in the air. Although Brodie and Lerch have greatly extended our knowledge of this compound, much still remains unexplained.

the skin they break, and the corrosive formic acid enters into the body); it is obtained during the action of oxidising agents on many organic substances; it is formed from oxalic acid, and under many conditions splits up into carbonic oxide and water. In the formation of formic acid from carbonic oxide we observe an example of the synthesis of organic compounds, such as are now very numerous, and are treated of in detail in organic chemistry.

Formic acid, $\text{H}(\text{CHO}_2)$, carbonic acid, $\text{HO}(\text{CHO}_2)$, and oxalic acid $(\text{CHO}_2)_2$, are the simple organic or carboxylic acids, $\text{R}(\text{CHO}_2)$ corresponding with HH and HOH . Proceeding from carbonic oxide, CO , the formation of carboxylic acids is clearly seen from the fact that CO is capable of combining with X_2 , that is, forming COX_2 . If, for instance, one X is an aqueous residue, OH (hydroxyl), and the other X hydrogen, then the simplest organic acid—formic acid, $\text{H}(\text{COOH})$ —is obtained. As all hydrocarbons (Chapter VIII.) correspond with the simplest, CH_4 , so all organic acids may be considered to proceed from formic acid.

In a similar way it is easy to explain the relation to other compounds of carbon of those compounds which contain nitrogen. By way of an example we will examine one class of such nitrogenous compounds. There are ammonium salts, $\text{R}(\text{CNH}_4\text{O}_2)$ corresponding with every carboxylic acid, $\text{R}(\text{CHO}_2)$, which salts contain the elements of water; this, with the assistance of substances taking up the water, may be separated with formation of a special class of nitrogenous organic, or, as they are termed, *cyanogen compounds*, RCN ,³² because the group or monovalent residue, or radicle, CN , is called *cyanogen*. From this the connection of the most varied organic compounds is apparent, and it is not only expressed in relation to their composition but by a multitude of reactions. It is most important to turn our attention to the two following circumstances: (1) We have already noticed the various mutual transformations of the simplest organic acids, clearly explained by the existence of carboxyl in their composition. In a similar way, in many reactions, the various cyanogen compounds undergo mutual transformation, especially hydrocyanic acid, $\text{H}(\text{CN})$, corresponding with formic acid, $\text{H}(\text{CHO}_2)$; cyanic acid, $\text{OH}(\text{CN})$, corresponding to carbonic acid, $\text{OH}(\text{CHO}_2)$; and cyanogen, $(\text{CN})_2$, corresponding with oxalic acid, $(\text{CHO}_2)_2$. The mutual transitions of cyanogen compounds into one another were known much earlier than the doctrine of carboxylic acids, and therefore Gay-Lussac acknowledged *cyanogen*,

³² The connection of the immense series of cyanogen compounds with the rest of the hydrocarbons by means of carboxyl was enunciated by me, about the year 1860, at the first Annual Meeting of the Russian Naturalists.

CN, as the radicle of cyanic acid or hydrocyanic acid, HCN, forming salts, for instance of mercury, which latter on being heated, as Gay-Lussac showed, gives cyanogen itself, $(\text{CN})_2$. (2) As the ammonium salt of a carboxylic acid, $\text{R}(\text{CNH}_4\text{O}_2)$, contains the elements of two molecules of water, and molecular quantities are those which act in reactions; then, previously to forming a cyanogen compound, or *nitrile*, by parting with two molecules water, an ammonium salt ought to form an *amide* by losing one molecule of water: $\text{R}(\text{CO}_2\text{NH}_4) - \text{H}_2\text{O} = \text{R}(\text{CNH}_2\text{O})$. Amides are therefore compounds containing the univalent amide residue, NH_2 , of ammonia, or a compound, COX_2 , in which one $\text{X}=\text{R}$ and the other $=\text{NH}_2$. Such are, for instance, formamide, or the amide of formic acid, $(\text{CO})\text{H}(\text{NH}_2)$, or $\text{H}(\text{CONH}_2)$. The amides compose a most numerous series of nitrogen compounds, and are obtained in many ways; ³³ they are met with in plants and animals, and, as has already been shown, by parting with water they form nitriles or cyanogen compounds, so that they serve as transitional terms between $\text{R}(\text{CO}_2\text{NH}_4)$ and RCN . The varieties, reactions, and properties of the amides and nitriles of organic acids, and therefore also of cyanogen compounds, are, as carbon compounds, examined in greater detail in organic chemistry, and here we will only dwell on the simplest of them; and, in order to clearly explain the derived ammonia compounds, we will first dwell on the ammonium salts and amides of carbonic acids.

As carbonic acid is bibasic, its ammonium salts ought to have the following composition: *acid carbonate of ammonium*, $\text{H}(\text{NH}_4)\text{CO}_3$, and the *normal carbonate*, $(\text{NH}_4)_2\text{CO}_3$; they represent compounds of one or two molecules of ammonia with carbonic acid. The acid salt appears in the form of a non-odoriferous and (when tested with litmus) neutral substance, soluble at the ordinary temperature in six parts of water, insoluble in alcohol, and obtainable in a crystalline form either without water of crystallisation or with various proportions of it. If an aqueous solution of ammonia be saturated with carbonic anhydride, and then evaporated over sulphuric acid in the bell jar of an air-pump, crystals of this salt are separated. Solutions of all other ammonium carbonates, when evaporated under the air-pump, yield crystals of this salt. A solution of this salt, even at the ordinary temperature, gives off carbonic anhydride, as do all the acid salts of carbonic acid (for

³³ Thus, for instance, *oxamide*, or the amide of oxalic acid, $(\text{CNH}_2\text{O})_2$, is obtained in the form of an insoluble precipitate on adding a solution of ammonia to an alcoholic solution of ethyl oxalate $(\text{CO}_2\text{C}_2\text{H}_5)_2$, which is formed by the action of oxalic acid on alcohol: $(\text{CHO}_2)_2 + 2(\text{C}_2\text{H}_5)\text{OH} = 2\text{HOH} + (\text{CO}_2\text{C}_2\text{H}_5)_2$. As the nearest derivatives of ammonia, the amides with alkalis yield ammonia and form the salt of the acid. The nitriles do not, however, give similar reactions so readily.

instance, NaHCO_3), and at 38° the separation of carbonic anhydride takes place with great rapidity. For this reason the formation of the acid salt in the solution, and the evaporation, must be conducted at a low temperature, and *with an excess of carbonic acid*, as the product of dissociation of this salt. On losing carbonic anhydride and water, the acid salt is converted into the normal salt, $2(\text{NH}_4)\text{HCO}_3 = \text{H}_2\text{O} + \text{CO}_2 + (\text{NH}_4)_2\text{CO}_3$; the latter, however, decomposes in solution, and therefore can only be obtained in crystals, $(\text{NH}_4)_2\text{CO}_3 \cdot \text{H}_2\text{O}$, at low temperatures, and from solutions containing *an excess of ammonia* as the product of dissociation of this salt: $(\text{NH}_4)_2\text{CO}_3 = \text{NH}_3 + (\text{NH}_4)\text{HCO}_3$. But the normal salt,³⁴ according to the general type, is capable of decomposing *with separation of water*, and forming *ammonium carbamate*, $\text{NH}_4\text{O}(\text{CONH}_2) = (\text{NH}_4)_2\text{CO}_3 - \text{H}_2\text{O}$; this still further complicates the history of the carbonates of ammonium. It is evident that, in reality, on changing the quantity of water, ammonia, and carbonic acid, various intermediate salts will be formed containing mixtures or combinations of those mentioned above, or, in other words, various states of equilibrium of reactions reverse to one another will be produced. Thus the ordinary commercial *carbonate of ammonia*, obtained by distillation of a mixture of chalk and sulphate of ammonia (Chapter VI.), or sal-ammoniac, $2\text{NH}_4\text{Cl} + \text{CaCO}_3 = \text{CaCl}_2 + (\text{NH}_4)_2\text{CO}_3$, does not remain as a normal salt, but, through loss of part of the ammonia, partly contains the acid salt, and, through loss of water, contains some carbamate, and most frequently presents the composition $\text{NH}_4\text{O}(\text{CONH}_2) + 2\text{OH}(\text{CO}_2\text{NH}_4) = 4\text{NH}_3 + 3\text{CO}_2 + 2\text{H}_2\text{O}$. Indeed, this salt, from having under various conditions parted with ammonia, carbonic anhydride, and water, does not present a constant composition, and ought rather to be regarded as a mixture of acid salt and amide salt. The latter must be recognised as entering into the composition of the ordinary carbonate of ammonia, because it contains less water than is required for the normal or acid salt;³⁵ but on being dissolved in water this salt gives a mixture of acid and normal salts. Ammonium carbamate itself, whose composition (and formation) is equal to $2\text{NH}_3 + \text{CO}_2$, when dissolved in water, does not entirely precipitate a calcium salt, for instance CaCl_2 , which produces a normal salt, $(\text{NH}_4)_2\text{CO}_3 + \text{CaCl}_2 = 2\text{NH}_4\text{Cl} + \text{CaCO}_3$, probably because a calcium carbamate is produced which is soluble in water.

³⁴ The acid salt $(\text{NH}_4)\text{HCO}_3$ on losing water ought to form the *carboxylic acid*, $(\text{NH}_2)\text{HCO}_2$, or, better, $\text{OH}(\text{CNH}_2\text{O})$, as we wrote it before; but it is not formed, which is accounted for by the instability of the acid salt itself. Carbonic anhydride is given off and ammonia is produced, which gives a carboxylic ammonium salt.

³⁵ In the normal salt, $2\text{NH}_3 + \text{CO}_2 + \text{H}_2\text{O}$, in the acid salt, $\text{NH}_3 + \text{CO}_2 + \text{H}_2\text{O}$, but in the commercial salt to 3CO_2 only $2\text{H}_2\text{O}$.

This ammonium carbamate is one of the most remarkable of the ammonium carbonates, because it is the simplest in its composition, and is easily and immediately formed by mixing two volumes of *dry* ammonia with one volume of dry carbonic anhydride, $2\text{NH}_3 + \text{CO}_2 = \text{NH}_4\text{O}(\text{CONH}_2)$; it is a solid substance, smells strongly of ammonia, attracts moisture from the air, and entirely decomposes at 60° . The fact of this decomposition may be judged³⁶ by the density of its vapour, which $=13$ ($\text{H}=1$); this exactly corresponds with the density of a mixture of 2 volumes of ammonia and 1 volume of carbonic anhydride. It is easily understood that such a combination will take place with any ammonium carbonate under the action of salts which take up the water—for instance, sodium or potassium carbonate.³⁷ As ammonia and carbonic anhydride in an anhydrous state only form one compound, $\text{CO}_2 2\text{NH}_3$,³⁸ ammonium carbamate, as has been already stated, may be regarded as COX_2 , where X has been replaced by the residues NH_2 and NH_4O (that is, HO in which H is replaced by NH_1), and therefore is still capable of losing water and forming the symmetrical amide $\text{CO}(\text{NH}_2)_2$. This must be termed carbamide. It is identical with urea, $\text{CN}_2\text{H}_4\text{O}$, which, contained in the urine (about 2 per cent. in human urine), is for the higher animals (especially the carnivorous) the ordinary product of excretion³⁹ of the nitrogenous substances found in the organism. If ammonium carbamate be heated to 140° (in a sealed tube, Bazaroff), or if carbonyl chloride, COCl_2 , be treated with ammonia (Natanson), urea will be obtained, which

³⁶ Naumann determined the following densities of the vapour of ammonium carbamate (in millimetres of mercury):—

-10°	0°	$+10^\circ$	20°	30°	40°	50°	60°
5	12	30	62	124	248	470	770

Horstmann and Isambert studied the densities corresponding with excess of NH_3 or CO_2 , and found, as might have been expected, that with such excess the mass of the salt formed (in a solid state) increases and the decomposition (transition into vapour) decreases.

³⁷ Calcium chloride enters into double decomposition with ammonium carbamate. Acids (for instance sulphuric) take up ammonia, and set free carbonic anhydride; alkalis (for instance, potash) take up carbonic anhydride and set free ammonia, and therefore, for removing water here only sodium or potassium carbonate may be taken.

³⁸ It must be imagined that the reaction takes place at first between equal volumes (Chapter VII.); but then carbamic acid, $\text{HO}(\text{CNH}_2\text{O})$, is produced, which, as an acid, immediately combines with the ammonia, forming $\text{NH}_4\text{O}(\text{CNH}_2\text{O})$.

³⁹ Urea is undoubtedly a product of the oxidation of complex nitrogenous matters (albumin) of the animal body. It is found in the blood. It is absorbed from the blood by the kidneys. A man excretes about 30 grams of urea per day. As a derivative of carbonic anhydride, into which it is readily converted, urea is in a sense a product of oxidation.

shows its direct connection with carbonic acid—that is, the presence of carbonic acid and ammonia in it. From this it will be understood how urea during the putrefaction of urine is converted into ammonium carbonate, $\text{CN}_2\text{H}_4\text{O} + \text{H}_2\text{O} = \text{CO}_2 + 2\text{NH}_3$.

Thus urea, both by its origin and reactions, is an amide of carbonic acid. Representing as it does ammonia (two molecules) in which the hydrogen (two atoms) is replaced by the bivalent radicle of carbonic acid, urea retains the property of ammonia of entering into combination, with acids (for instance, with nitric acid, $\text{CN}_2\text{H}_4\text{O}, \text{HNO}_3$), with bases (for instance, with mercury oxide), and with salts (for instance, sodium chloride, ammonium chloride), but it has no alkaline properties. It is soluble in water without change, but at a red heat loses ammonia and forms *cyanic acid*, CNHO , and its polymeride, *cyanuric acid*, $\text{C}_3\text{N}_3\text{H}_3\text{O}_3$. The first is a nitrile of carbonic acid—that is to say, is a cyanogen compound. This conformity is evident from the fact that the acid ammonium carbonate, $\text{OH}(\text{CNH}_4\text{O}_2)$, on parting with $2\text{H}_2\text{O}$, ought to form cyanic acid, CNOH . There is a relation of direct polymerisation between cyanuric acid (a solid, crystalline, and very stable substance) and cyanic acid (a liquid, very unstable substance, easily changeable in several ways). Both have the same composition, and they pass one into another at different temperatures. If crystals of cyanuric acid be heated to a temperature, t° , then the vapour tension, p , in millimetres of mercury (Troost and Hautefeuille) will be :

$t.$	160°	170°	200°	250°	300°	350°.
$p.$	56,	68,	130,	220,	430,	1200.

The vapour contains cyanic acid, and, if it be rapidly cooled, it condenses into a mobile volatile liquid (specific gravity at $0^\circ = 1.14$). If the liquid cyanic acid be gradually heated, it passes into a new amorphous polymeride (cyamelide), which, on being heated, like cyanuric acid, forms vapours of cyanic acid. If these fumes are heated above 150° , they directly pass into cyanuric acid. Thus, at a temperature of 350° , the pressure does not rise above 1200 mm. on the addition of vapours of cyanic acid, because the whole excess is transformed into cyanuric acid. Therefore, the above-mentioned figures give the tension of dissociation of cyanuric acid, or the greatest pressure which the vapours of HOCN are able to attain at a given temperature, whilst at a greater pressure, or by the introduction of a large mass of matter into the given volume, the whole of the excess is converted into cyanuric acid. The properties of cyanic acid which we have described were principally observed by Wöhler, and clearly show the *faculty of polymerism of cyanogen compounds*. This is observed in many other

cyanogen derivatives, and is regarded as the consequence of the above-mentioned explanation of their nature. All cyanogen compounds are ammonium salts, $R(CNH_4O_2)$, deprived of water, $2H_2O$; therefore their molecules ought to show the faculty of combining with two molecules of water or with other molecules in exchange for it (for instance, with H_2S , or HCl , or $2H_2$, &c.), and are therefore capable of combining together. The combination of molecules of the same kind to form more complex ones is nothing else but polymerisation.⁴⁰

Besides being a substance very apt to form polymerides, cyanic acid presents many other features of interest, expounded in greater detail in organic chemistry. First of all, the transition of ammonium cyanate into urea ought to be considered. The reason is that the salts of cyanic acid, which are easily split up, by the action of acids and even of water, into ammonia and carbonic anhydride, are produced by the oxidation of saline metals, as we shall see further on. Potassium cyanate, $KCNO$, for instance, is most often obtained in this way. Solutions of cyanates, by the addition of sulphuric acid, yield cyanic acid, which, however, immediately decomposes: $CNHO + H_2O = CO_2 + NH_3$. A solution of ammonium cyanate, $CN(NH_4)O$, behaves in the same manner, but only in the cold. On being heated it completely changes, because it is transformed into urea. The composition of both substances is identical, CN_2H_4O , but the structure or disposition and the connection between the elements is different: in the ammonium cyanate one atom of nitrogen exists in the form of cyanogen, CN —that is, united with carbon—and the other as ammonium, NH_4 , but, as cyanic acid contains the hydroxyl radicle of carbonic acid, $OH(CN)$, the ammonium in this salt is united with oxygen; whilst in urea both the nitrogen atoms are symmetrically and uniformly disposed as regards the radicle CO of carbonic acid: $CO(NH_2)_2$. For this reason, urea is much more stable than ammonium cyanate, and therefore the latter, on being slightly heated in solution, is converted into

⁴⁰ Just as the aldehydes (for instance, C_2H_4O , page 145) are alcohols (for instance, C_2H_6O) which have lost hydrogen.

The aldehydes are also capable of entering into combination with many substances, and of polymerising, forming slightly-volatile polymerides, which depolymerise on heating. Although there are also many similar phenomena (for instance, the transformation of yellow into red phosphorus, the transition of cinnamene into metacinnamene, &c.) of polymerisation, in no other case are they so clearly and simply expressed as in cyanic acid. The details relating to this must be sought for in treatises on organic and theoretical chemistry. If we touch on certain sides of this question it is principally with the view of showing the phenomenon of polymerisation by typical examples (this phenomenon being met with more frequently than was formerly imagined, see Silica), and also to show the faculty which cyanogen derivatives have of forming the most varied compounds.

urea. This remarkable isomeric transformation was discovered by Wöhler in 1828. It had an important historical signification, because at that time such an easy formation outside the organism of those substances which are met with in it was quite unexpected, it being at that time supposed that the vital force of the organism produced substances which could not be formed outside it. But in addition to the abolition of this presupposition, the easy transition of NH_4OCN into $\text{CO}(\text{NH}_2)_2$ is the best example of the transition of one state of atomic equilibrium into another more stable one. Every carboxyl acid, RCOOH , has its corresponding amide, RCONH_2 ,⁴¹ and nitrile, as is the case with carbonic acid. In this way, formamide, HCONH_2 , and *hydrocyanic acid*, HCN , as a nitrile, correspond with formic acid, HCOOH , and therefore ammonium formate, HCOONH_4 , and formamide, under the action of heat and substances which take up water (phosphoric anhydride), form hydrocyanic acid, HCN , whilst, under many conditions (for instance, on combining with hydrochloric acid in presence of water), this hydrocyanic acid forms formic acid and ammonia. Although containing hydrogen in the presence of two acid-forming elements—namely, carbon and nitrogen⁴²—hydrocyanic acid does not give an acid reaction with litmus (cyanic acid has very marked acid properties), *but forms salts, MCN*, and therefore presents the properties of a feeble acid, and for this reason is called an *acid*. The small amount of energy which it has is shown by the fact that the cyanides of the alkali metals—for instance, potassium cyanide ($\text{KHO} + \text{HCN} = \text{H}_2\text{O} + \text{KCN}$) in solution—have a strongly

⁴¹ The majority of the amides corresponding with acids, being represented by the composition RNH_2 , very easily undergo the inverse change; they combine with water, even when simply boiled with it, and still more so under the action of alkalis and acids. Ammonia is evolved by the action of alkalis on amides, naturally in virtue of the water combining with the amide, in addition to which there is formed a salt of the acid, which had served to form the amide according to the equation: $\text{RNH}_2 + \text{KHO} = \text{RKO} + \text{NH}_3$. The same thing takes place under the action of acids, only, naturally, an ammonium salt of the given acid is formed, and the acid, previously in the condition of an amide, separates in the free state: $\text{RNH}_2 + \text{HCl} + \text{H}_2\text{O} = \text{RHO} + \text{NH}_4\text{Cl}$. Thus the amides, in the majority of cases, easily pass back into ammonium salts in the presence of water, alkalis, and acids; but they differ in a marked way from them. None of the ammonium salts are distillable, nor volatilise without change; in most cases ammonia salts, on being heated, lose water and form amides; many amides volatilise without change, and sometimes are crystalline volatile substances easily distilled. Such are, for instance, the amides of acetic, benzoic, formic, and a large number of other organic acids. Judging from the preceding facts, amides may be regarded as acids RHO , in which the hydroxyl HO is replaced by the ammonia radicle (amidogen) NH_2 .

⁴² If ammonia and methane (marsh gas) do not show any acid properties, that is in all probability due to the presence of a large amount of hydrogen in both; but in hydrocyanic acid one atom of hydrogen is under the influence of two acid-forming elements. Acetylene, C_2H_2 , which contains but little hydrogen, presents acid properties in certain respects, because its hydrogen is easily replaced by metals.

alkaline reaction.⁴⁵ If ammonia be passed over charcoal at a red heat, especially in the presence of an alkali, or if gaseous nitrogen be passed through a mixture of charcoal and an alkali (especially potash, KHO), and also if a mixture of nitrogenous organic substances and alkali be heated to a red heat, in all these cases the alkali metal combines with the carbon and nitrogen, forming a metallic cyanide, MCN—for example, KCN. Potassium cyanide is much used in the arts, and is obtained, as above stated, under many circumstances—as, for instance, in iron smelting, especially with the assistance of wood charcoal, the ash of which contains much potash. The nitrogen of the air, the alkali of the ash, and the charcoal are brought into contact at a high temperature during iron smelting, and therefore, under these conditions, a considerable quantity of potassium cyanide is formed. In practice it is not usual to prepare potassium cyanide directly, but a peculiar compound of it containing potassium, iron, and cyanogen. This compound is potassium ferrocyanide, and is also known as *yellow prussiate of potash*, because with ferric salts it forms a blue colour—Prussian blue. This saline substance, having the composition $K_4FeC_6N_6 + 3H_2O$, is prepared on the large scale in cast-iron pots (the iron of which enters into the salt), by heating with alkali leather cuttings, horn filings and shavings, and similar animal matter, composed of complex organic substances containing carbon and nitrogen; the alkali which is added is composed of potashes containing potassium; thus all the necessary elements for producing the yellow prussiate are brought into contact at a high temperature, and the above-mentioned substance is formed. The name of cyanogen (*κύανος*) is derived from the property which the yellow prussiate possesses of forming, with a solution of a ferric salt, FeX_3 , the familiar pigment Prussian blue. The yellow prussiate is generally used as the source of the other cyanogen compounds (because it is manufactured on a large scale), and we will therefore describe the method of forming the cyanogen compounds derived from it.

If yellow prussiate be mixed with two parts of water and three-

⁴⁵ Solutions of cyanides—for instance, of those of potassium or barium—are decomposed by carbonic acid. Even the carbonic anhydride of the air acts in a similar way, and for this reason these solutions do not keep, because, in the first place, free hydrocyanic acid itself decomposes and polymerises, and, in the second place, with alkaline liquids it forms ammonia and formic acid. Hydrocyanic acid does not liberate carbonic anhydride from solutions of sodium or potassium carbonates. But a mixture of solutions of potassium carbonate and hydrocyanic acid yields carbonic anhydride on the addition of oxides similar to zinc oxide, mercuric oxide, &c. This is due to the great inclination which the cyanides evince to form double salts. For instance, $ZnK_2(CN)_4$ is formed, which is a kind of soluble double salt.

quarter part of sulphuric acid, and the mixture be heated, it decomposes, volatile hydrocyanic acid separating. This was obtained for the first time by Scheele in 1782, but it was only known to him in solution. In 1809 Ittner prepared anhydrous prussic acid, and in 1815 Gay-Lussac finally settled its properties and showed that it contains only hydrogen, carbon, and nitrogen, CNH . If the distillate be redistilled (a weak solution of HCN), and the first part be collected, the anhydrous acid may be prepared from this stronger solution. In order to do this, pieces of calcium chloride are added to the concentrated solution, and the anhydrous acid floats as a separate layer, because it is not soluble in an aqueous solution of calcium chloride. If this layer be then distilled over a new portion of calcium chloride at the lowest temperature possible, the prussic acid may be obtained completely free from water. It is, however, necessary to use the greatest caution in work of this kind, because prussic acid, besides being extremely poisonous, is exceedingly volatile.⁴⁴

Anhydrous prussic acid is a very mobile and volatile liquid; its specific gravity is 0.697 at 18° ; at lower temperatures, especially when mixed with a small quantity of water, it easily congeals; it boils at 26° , and therefore very easily evaporates, and at ordinary temperatures may be regarded as a gas. On this account the greatest caution is necessary in dealing with it, as an insignificant amount, when inhaled or brought into contact with the skin, causes death. It is soluble in all proportions in water, alcohol, and ether; weak aqueous solutions are used in medicine.⁴⁵


⁴⁴ The mixture of the vapours of water and hydrocyanic acid, evolved on heating yellow prussiate with sulphuric acid, may be directly passed through vessels or tubes filled with calcium chloride. These tubes must be cooled, because, in the first place, hydrocyanic acid easily changes on being heated, and, in the second place, the calcium chloride, when warm, would absorb less water. The mixture of hydrocyanic acid and aqueous vapour on passing over a long layer of calcium chloride gives up water, and hydrocyanic acid alone remains in the vapour. It ought to be cooled as carefully as possible in order to bring it into a liquid condition. The method which Gay-Lussac employed for obtaining pure hydrocyanic acid consisted in the action of hydrochloric acid gas on mercuric cyanide. The latter may be obtained in a pure state if a solution of yellow prussiate be boiled with a solution of mercuric nitrate, then filtered and crystallised by cooling; the mercuric cyanide is then obtained in the form of colourless crystals $\text{Hg}(\text{CN})_2$.

If a strong solution of hydrochloric acid be poured upon these crystals, and the mixture of vapours evolved, consisting of aqueous vapour, hydrochloric acid, and hydrocyanic acid, be passed through a tube containing, first marble (for absorbing the hydrochloric acid), and then lumps of calcium chloride, on cooling, the hydrocyanic acid will be condensed. In order to obtain the hydrocyanic acid in an anhydrous form, the decomposition of heated mercury cyanide by hydrogen sulphide may be made use of. Here the sulphur and cyanogen change places, and hydrocyanic acid and mercury sulphide are formed: $\text{Hg}(\text{CN})_2 + \text{H}_2\text{S} = 2\text{HCN} + \text{HgS}$.

⁴⁵ A weak (up to 2 p.c.) aqueous solution of hydrocyanic acid is obtained by the dis-

The salts MCN —for instance, potassium, sodium, ammonium—as well as the salts $\text{M}(\text{CN})_2$ —for instance, barium, calcium, mercury—are soluble in water, but the salts of manganese, zinc, lead, and many others are insoluble in water. They form double salts with potassium cyanide and similar metallic cyanides, an example of which we will consider in a further description of the yellow prussiate. Not only are some of the double salts remarkable for their constancy and comparative stability, but so also are the soluble salt HgC_2N_2 , the insoluble silver cyanide AgCN , and even potassium cyanide in the absence of water. This salt,⁴⁶ when fused, acts as a reducing agent with its elements, K and C, and oxidises when fused with lead oxide, forming potassium cyanate, KOCN , which establishes the connection between HCN and OHCN —that is, between the nitriles of formic and carbonic acids—which connection is the same as between the acids themselves, because formic acid, on oxidation, yields carbonic acid. The relation which exists between hydrocyanic acid, metallic cyanides, and the salts of cyanic acid, as well as between all the above-mentioned compounds, may be expressed by granting the existence of a radicle in them containing carbon and nitrogen—cyanogen, CN . In this sense, prussic acid is hydrocyanic acid, and cyanic acid a cyanogen hydroxide, in exactly the same way as for chlorine we have hydrochloric acid, HCl , and hypochlorous acid, ClOH . Free cyanogen ought to be represented as prussic acid in which the hydrogen has been replaced by cyanogen, $(\text{CN})_2$ or CNCN . This composition, judging from what has been

tillation of certain vegetable substances. The so-called laurel water in particular enjoys considerable notoriety from its containing hydrocyanic acid. It is obtained by the steeping and distillation of laurel leaves. A similar kind of water is formed by the infusion and distillation of bitter almonds. It is well known that bitter almonds are poisonous, and have a peculiar characteristic taste. This bitter taste is due to the presence of a certain substance called amygdalin, which can be extracted by alcohol. This amygdalin decomposes in an infusion of bruised almonds, forming the so-called bitter almond oil, glucose, and hydrocyanic acid:



If after this the infusion of bitter almonds be distilled with water, the hydrocyanic acid and the volatile bitter almond oil are carried over with the aqueous vapour. The latter is insoluble in water, or only sparingly soluble, while the hydrocyanic acid remains as an aqueous solution. Bitter almond water is similar to laurel water, and is used, like the former, in medicine, naturally only in small quantities, because a considerable amount has poisonous effects. Perfectly pure anhydrous hydrocyanic acid keeps without change, just like the weak solutions, but the strong solutions only keep in the presence of other acids; but in the presence of many admixtures these solutions easily give a brown polymeric substance, which is also formed from a solution of potassium cyanide.

⁴⁶ This salt will be described under potassium, as it is one of those which are often used.

already stated, exactly expresses that of the nitrile of oxalic acid, and, as a matter of fact, oxalate of ammonia and the amide corresponding with it (oxamide), on being heated with phosphoric anhydride, which takes up the water, yield *cyanogen*. This substance is also produced by simply heating some of the metallic cyanides. Mercuric cyanide is particularly adapted for this purpose, because it is easily obtained in a pure state and is very stable in a separate form. If mercuric cyanide be heated, it decomposes, in like manner to mercury oxide, into metallic mercury and cyanogen: $\text{HgC}_2\text{N}_2 = \text{Hg} + \text{C}_2\text{N}_2$.⁴⁷ When cyanogen is formed, part of it always polymerises into a dark brown insoluble substance called *paracyanogen*, capable of forming cyanogen when heated to redness.⁴⁸ Cyanogen is an odorous, colourless, poisonous gas, easily condensed by cooling into a colourless liquid, insoluble in water and having a specific gravity of 0.86. It boils at about -21° , and therefore cyanogen may be easily condensed into a liquid by a strong freezing mixture. At -35° liquid cyanogen solidifies. This gas is soluble in water and in alcohol to a considerable extent—namely, 1 volume of water absorbs as much as $4\frac{1}{2}$ volumes, and alcohol 23 volumes. Cyanogen resists the action of heat without decomposing, but, under the action of the electric spark, the carbon is separated, leaving a

⁴⁷ For the preparation it is necessary to take completely dry mercuric cyanide, because when heated in the presence of moisture it gives ammonia, carbonic anhydride, and hydrocyanic acid. Instead of mercuric cyanide, a mixture of perfectly dry yellow prussiate and mercuric chloride may be used, then double decomposition and the formation of mercuric cyanide take place in the retort. Silver cyanide also disengages cyanogen on being heated.

⁴⁸ *Paracyanogen* is a brown substance having the composition of cyanogen, formed during the preparation of cyanogen by all methods, and remaining as a residue. Silver cyanide, on being slightly heated, fuses, and on being further heated evolves a gas; in the residue a considerable quantity of paracyanogen is formed. Here it is remarkable that exactly half the cyanogen becomes gaseous, and the other half is transformed into paracyanogen. Metallic silver will be found in the residue with the paracyanogen; it may be extracted with mercury or nitric acid, which does not act on paracyanogen. If paracyanogen be heated in a vacuum, it decomposes, forming cyanogen; but here the pressure p for a given temperature t exceeds the determined magnitude, so that the phenomenon presents all the external appearance of a physical transformation into vapour; but, nevertheless, it is a complete change in the nature of the substance, but limited by the *pressure of dissociation*, as we saw before in the transformation of cyanuric acid into hydrocyanic, and as ought to be expected from the fundamental principles of dissociation. Troost and Hautefeuille (1868) found that for paracyanogen

$t = 530^\circ$	581°	600°	635°
$p = 90$	143	296	1089 mm.

However, already at 550° part of the cyanogen decomposes into carbon and nitrogen. The reverse transition of cyanogen into paracyanogen commences at 350° , and at 600° proceeds rapidly. And if the transition of the first kind is likened to evaporation, then the reverse transition, or polymerisation, presents a likeness to the transition of vapours into the solid state.

volume of nitrogen equal to the volume of the gas taken. As it contains carbon it burns, and the colour of the flame is reddish-violet, which is due to the presence of nitrogen, all compounds of which impart more or less of this reddish-violet hue to the flame. During the combustion of cyanogen, carbonic anhydride and nitrogen are formed. This also takes place in the eudiometer with oxygen and during the action of cyanogen on many oxides at a red heat.

The relation of cyanogen to the metallic cyanides is seen not only from the fact that it is formed from mercuric cyanide, but also by its forming cyanide of sodium or potassium on being heated with sodium or potassium, the sodium or potassium taking fire in the cyanogen. On heating a mixture of hydrogen and cyanogen to 500° (Berthelot),⁴⁹ or under the action of the silent discharge (Boilleau), hydrocyanic acid is formed, so that the reciprocity of the transitions does not leave any doubt in the matter that all the nitriles of the organic acids contain cyanogen, just as all the organic acids contain carboxyl, and in it the elements of carbonic anhydride. Besides the amides,⁵⁰ the nitriles (or cyanogen compounds, RCN), and nitro-compounds (containing the radicle of nitric acid, RNO_2), there are a great number of other substances containing, at the same time, carbon and nitrogen, particulars of which must be sought for in special works on organic chemistry.

⁴⁹ Cyanogen (like chlorine) is absorbed by a solution of sodium hydroxide, sodium cyanide and cyanate being produced: $\text{C}_2\text{N}_2 + 2\text{NaHO} = \text{NaCN} + \text{CNNaO} + \text{H}_2\text{O}$. However, the latter salt easily decomposes, just as also part of the cyanogen liberated by heat from its compounds is subjected to a more complex transformation.

⁵⁰ If, in general, compounds containing the radicle NH_2 are called amides, some of the *amines* ought to be ranked with them; that is, the hydrocarbons, C_nH_{2m} , in which the hydrogen is replaced by NH_2 ; for instance, methylamine, CH_3NH_2 , aniline, $\text{C}_6\text{H}_5\text{NH}_2$, &c. In general the amines represent ammonia in which part or all of the hydrogen is replaced by hydrocarbon radicles—such as, for instance, trimethylamine $\text{N}(\text{CH}_3)_3$. They, like ammonia, combine with acids and form crystalline salts. Related substances are sometimes met with in nature, and bear the general name of *alkaloids*; such are, for instance, quinine in cinchona bark, nicotine in tobacco, &c.

CHAPTER X

SODIUM CHLORIDE—BERTHOLLET'S LAWS—HYDROCHLORIC ACID

IN the preceding chapters we have become acquainted with the most important properties of the four elements, hydrogen, oxygen, nitrogen, and carbon. They are sometimes termed the *organogens*, because they enter into the composition of organic substances. Their mutual combinations may serve as types for all other chemical compounds—that is, they present the same atomic relations (types, forms, or grades of combinations) as those in which the other elements also combine together.

Hydrogen,	HH ,	or, in general,	HR .
Water,	H_2O ,	„ „	H_2R .
Ammonia,	H_3N ,	„ „	H_3R .
Marsh gas,	H_4C ,	„ „	H_4R .

One, two, three, and four atoms of hydrogen enter into these molecules for one atom of another element. No compounds of one atom of oxygen with three or four atoms of hydrogen are known; hence the atom of oxygen is without certain properties which are found in the atoms of carbon and nitrogen.

The faculty of an element to form a compound of definite composition with hydrogen (or an element analogous to it) gives the possibility of foretelling the composition of many other of its compounds. Thus, if we know that an element, M , combines with hydrogen, forming HM , and not forming H_2M , H_3M , H_nM_m , then we must conclude, on the basis of the law of substitution, that this element will give compounds M_2O , M_3N , MHO , MH_3C , &c. Chlorine is an example of this kind. If we know that another element, R , like oxygen, gives with hydrogen a molecule, H_2R , then we may expect that it will form compounds like hydrogen peroxide, or the metallic oxides, or carbonic anhydride, or carbonic oxide, and others. Sulphur is an instance of this kind. Hence the elements may be classified according to their resemblance to hydrogen, oxygen, nitrogen, and carbon, and in conformity with this analogy it is possible to foretell, if not the properties (for example,

the acidity or basicity), at all events, the composition¹ of their compounds. This forms the substance of *the conception of the valency or*

¹ But it is impossible to foretell all the compounds formed by an element from its atomicity or valency, because the atomicity of the elements is variable, and furthermore this variability is not identical for different elements. In CO_2 , COX_2 , CH_4 , and the multitude of carbon compounds corresponding with them, the C is quadrivalent, but in CO either the carbon must be taken as bivalent or the atomicity of oxygen be accounted as variable. And carbon, nevertheless, is an example of an element which preserves its atomicity to a greater degree than most of the other elements. Nitrogen in NH_3 , $\text{NH}_4(\text{OH})$, N_2O_5 , and even in CNH , must be considered as trivalent, but in NH_4Cl , $\text{NO}_2(\text{OH})$, and in all their corresponding compounds it is necessarily pentavalent. In N_2O , if the atomicity of oxygen = 2, nitrogen has an uneven atomicity (1, 3, 5), whilst in NO it is bivalent. If sulphur be bivalent, like oxygen, in many of its compounds (for example, H_2S , SCl_2 , KNS , &c.), then it could not be foreseen from this that it would form SO_2 , SO_3 , SCl_4 , SOCl_2 , and a series of similar compounds in which its atomicity must be acknowledged as greater than 2. Thus in SO_2 , sulphurous anhydride, there are a multitude of points in common with CO_2 , and if carbon be quadrivalent then the S in SO_2 is quadrivalent. Therefore the principle of the atomicity (valency) of the elements cannot be established as the basis for the study of the elements, although it gives an easy possibility for grasping many analogies. Although a definite atomicity cannot be considered as a radical property of atoms and elements, it may, however, be made use of with great advantage in investigating the compounds of such elements as carbon, because carbon in all its usual compounds, and especially in the saturated compounds and those approaching them, acts as a quadrivalent element. I consider the four following as the chief obstacles to acknowledging the atomicity of the elements as a primary conception for the consideration of the properties of the elements: 1. Such univalent elements as H, Cl, &c., appear in a free state as molecules H_2 , Cl_2 , &c., and are consequently like the univalent radicles CH_3 , OH , CO_2H , &c., which, as might be expected, appear as C_2H_6 , O_2H_2 , $\text{C}_2\text{O}_4\text{H}_2$ (ethane, hydrogen peroxide, oxalic acid), whilst on the other hand, potassium and sodium (perhaps also iodine at a high temperature) contain only one atom, K, Na, in the molecule in a free state. Hence it follows that *free affinities* may exist. And then nothing obliges us not to admit free affinities in all unsaturated compounds; for example, it may be said that in C_2H_4 each atom of carbon is bound to the other by one affinity, two other affinities holding the hydrogen, and that the fourth affinity of each carbon atom is free. If such instances of free affinities be admitted, then all the possible advantages to be gained by the application of the doctrine of atomicity (valency) are lost. 2. There are instances—for example, Na_2H —where univalent elements are gathered together in molecules which are more complex than R_2 , and form molecules, R_3 , R_4 , &c.; which may again be either taken as evidence of the existence of free affinities, or else necessitates such primary univalent elements as sodium and hydrogen being considered as variable in their atomicity. 3. The periodic system of the elements, with which we shall afterwards become acquainted, shows that there is a law or rule for the variation of the forms of oxygen and hydrogen compounds; chlorine is univalent with respect to hydrogen, and septavalent with respect to oxygen; sulphur is bivalent to hydrogen, and sexavalent to oxygen; phosphorus is trivalent to hydrogen and pentavalent in respect to oxygen—the sum is in every case equal to 8. Only carbon and its analogues (for example, silicon) are quadrivalent to both hydrogen and oxygen. Hence the property of the elements to change their atomicity lies in the essence of their nature, and consequently atomicity cannot be considered as a fundamental property. 4. Crystallohydrates (for instance, $\text{NaCl} \cdot 2\text{H}_2\text{O}$, or $\text{NaBr} \cdot 2\text{H}_2\text{O}$), double salts (for instance, $\text{PtCl}_4 \cdot 2\text{KCl}$, H_2SiF_6 , &c.), and similar complex compounds (and, according to Chap. I., solutions also) demonstrate the capacity not only of the elements themselves, but also of their saturated and limiting compounds, of entering into further combination. Therefore the admission of a definite limited atomicity of the elements includes in itself an admission of limitation which is not in accordance with the nature of chemical reactions.

atomicity of the elements. Hydrogen is taken as the representative of the univalent elements, giving compounds, RH , R(OH) , R_2O , RCl , R_3N , R_4C , &c. Oxygen, in that form in which it gives water, is the representative of the bivalent elements, forming RH_2 , RO , RCl_2 , RHCl , R(OH)Cl , R(OH)_2 , R_2C , RCN , &c. Nitrogen in ammonia is the representative of the trivalent elements, giving compounds RH_3 , R_2O_3 , R(OH)_3 , RCl_3 , RN , RHC , &c. In carbon is expressed the properties of the quadrivalent elements, RH_4 , RO_2 , RO(OH)_2 , R(OH)_4 , RHN , RCl_4 , RHC_3 , &c. We meet with these *forms of combination* or aspects of union of atoms in all other elements, some being analogous to hydrogen, others to oxygen, and others to nitrogen or to carbon. But besides these quantitative analogies or resemblances, which are foretold by the law of substitution (Chapter VI.), there exist among the elements qualitative analogies and relations which are not exhausted in the compounds of the elements which have been considered, but are most distinctly expressed in the formation of bases, acids, and salts of different types and properties. Therefore, for a complete study of the nature of the elements and their compounds it is especially important to become acquainted with the salts as substances of a peculiar character, corresponding with acids and bases. Common table salt, or sodium chloride, NaCl , may in every respect be taken as a type of salts in general, and therefore we will pass to the consideration of this substance, of hydrochloric acid, and of the base sodium hydroxide, of the non-metal chlorine, and the metal sodium, which correspond with it.

Sodium chloride, NaCl , or the familiar table salt, occurs in the primary formations of the earth's crust,² from which it is washed away by the atmospheric waters, and is held in small quantities in all waters flowing through these formations, and is in this manner collected in the oceans and seas. The immense mass of salt in the oceans has been accumulated by this process from the remote ages of the earth's crea-

² The primary formations are those which do not bear any distinct traces of having been deposited from water (have not a stratified formation, contain no remains of animal or vegetable life), occur under the sedimentary formations of the earth, and are everywhere uniform in composition and structure, which is generally distinctly crystalline. If the origin of the earth were of a molten nature, the first primary formations are those which formed the first solid crust of the earth. But even with this hypothesis of the earth's origin, it is necessary to admit that the first aqueous deposits must have re-formed the crust of the earth, and therefore under the head of the primary formations must be understood the most ancient of the products of decomposition (mostly by atmospheric, aqueous, and organic agency, &c.), from which all the rocks and substances of the earth's surface have arisen. In speaking of the origin of one or another substance, we can only, on the basis of facts, descend to the primary formation, of which granite, gneiss, and trachyte may be taken as examples.

tion, because the water has evaporated from them while the salt has remained in solution. The salt of sea water serves as the source not only for its direct extraction, but also for the formation of other masses of workable salt, such as rock salt and of saline springs and lakes.

The extraction of salt *from sea water* is carried on in several ways. In southern climes, especially on the shores of the Atlantic Ocean, the Mediterranean and Black Seas, the summer heats are taken advantage of. A convenient, low-lying sea shore is chosen, and a whole series of basins, communicating with each other, are constructed along it. The upper of these basins are filled with sea water by pumping, or else advantage is taken of high tides. These basins are sometimes separated from the sea by natural sand-banks (limans) or by artificial means, and in April the water already begins to evaporate considerably. As the solution becomes more concentrated, it is run into the succeeding basins, and the upper ones are supplied with a fresh quantity of sea water, or else an arrangement is made enabling the salt water to flow by degrees through the series of basins. It is evident that the bed of the basins should be, as far as possible, impervious to water, and for this purpose they are made of beaten clay. The crystals of table salt begin to separate out when the concentration attains 28 p.c. of salt (which corresponds to 28° of Baumé's hydrometer). It is raked off, and employed for all those purposes to which table salt is applicable. In the majority of cases only the first half of the sodium chloride which can be separated from the sea water is extracted, because the second half has a bitter taste, from the presence of magnesium salts which separate out together with the table salt. But in certain localities—as, for instance, in the estuary of the Rhone, on the island of Camarga³—the evaporation is carried on to the very end, in order to obtain those magnesium and potassium salts which separate out at the end of the evaporation of sea water. Various salts are separated from sea water in its evaporation. In the water of oceans (Chapter I.) there is held so large an amount of sodium chloride that on evaporation this salt, notwithstanding its great solubility in water, soon reaches saturation and separates out. From 100 parts of sea water there separates out, by natural and artificial evaporation, about one part of tolerably pure table salt at the very commencement of the operation; the total amount held in solution

³ The extraction of the potassium salts (or so-called summer salts) was carried on at the Isle of Camarga about 1870, when I had occasion to visit that spot. If I mistake not, this industry is now no longer carried on, because the deposits of Stassfurt provide a much cheaper salt, owing to the evaporation and separation of the salt being there carried on by natural means and only requiring a treatment and refining, which is also necessary in addition for the 'summer salt' obtained from sea water.

being about $2\frac{1}{2}$ p.c. The remaining portion of the table salt separates out, intermixed with the bitter salts of magnesium which form the chief admixture with table salt in sea water. These salts of magnesium, owing to their degree of solubility and the small amount in which they are present (less than 1 p.c.), only separate out, in the first crystallisations, in traces with the table salt; whilst, in the succeeding crystallisations, they are deposited together with the table salt. Gypsum, or calcium sulphate, $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$, owing to its sparing solubility, separates together with or even before the table salt. When about half of the table salt has separated, then, on further evaporation, the sea water gives a mixture of table salt and magnesium sulphate, and, on still further evaporation, the chlorides of potassium and magnesium begin to separate in a state of combination, forming the double salt $\text{KMgCl}_3 \cdot 6\text{H}_2\text{O}$, which occurs in nature as *carrollite*. This is a crystallo-hydrated compound of KCl and MgCl_2 .⁴ After the separation of this salt from sea water, there remains a mother liquor, containing a large amount of magnesium chloride in admixture with various other salts.⁵ The extraction of sea salt is usually carried on for the purpose of procuring table salt, and therefore directly it begins to separate mixed with a considerable proportion⁶ of magnesium salts (when it acquires a bitter taste) the remaining liquor is run back into the sea.

The same process which is employed for artificially obtaining salt in a crystalline form from sea water has been repeatedly accomplished during the geological evolution of the earth on a gigantic scale; upheavals of the earth have cut off portions of the sea from the remainder (as the Dead Sea was formerly a part of the Mediterranean, and the Sea

⁴ The double salt, $\text{KCl} \cdot \text{MgCl}_2$, is only formed from solutions containing an excess of magnesium chloride, because water decomposes this double salt, extracting the more soluble magnesium chloride from it.

⁵ Owing to the fundamental property of salts of interchanging their metals, it cannot be said that sea water contains this or that salt, but only that it contains certain amounts of certain metals M (univalent like Na and K , and bivalent like Mg and Ca), and haloids X (univalent like Cl , Br , and bivalent like SO_4 , CO_3), which are disposed in every possible kind of grouping; for instance, K as KCl , KBr , K_2SO_4 , Mg as MgCl_2 , MgBr_2 , MgSO_4 , and so on for all the other metals. In evaporation different salts separate out consecutively only because they reach saturation. A proof of this may be seen in the fact that a solution of a mixture of sodium chloride and magnesium sulphate (both of which salts are obtained from sea water, as was mentioned above), when evaporated, separates out crystals of these salts, but when refrigerated (if the solution be sufficiently saturated) the salt $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ is first deposited because it is the first to arrive at saturation at low temperatures. Consequently, this solution contains MgCl_2 and Na_2SO_4 , besides MgSO_4 and NaCl . So it is with sea water.

⁶ The salt extracted from water is piled up in heaps and left under the action of rain water, which purifies the salt, owing to its becoming saturated with table-salt and then no longer dissolving it, but washing out the impurities.

of Aral of the Caspian), and their water has evaporated and formed (if the mass of the inflowing fresh water were less than that of the mass evaporated) deposits of *rock salt*. It is always accompanied by gypsum, because the latter is separated from sea water before the sodium chloride. For this reason rock salt may always be looked for in those localities where there are deposits of gypsum. But inasmuch as the gypsum may remain on the spot where it has been deposited (as it is a sparingly soluble salt), whilst the rock salt (as one which is very soluble) may be washed away by rain or fresh running water, it may sometimes happen that although gypsum is found still there may be no salt; but, on the other hand, where there is rock salt there will always be gypsum. As the geological changes of the earth's surface are still proceeding to the present day, so in the midst of the dry land salt lakes are met with, which are sometimes scattered over vast districts formerly covered by seas now dried up. Such is the origin of many of the salt lakes about the lower portions of the Volga and in the Kirghiz steppes, where at a geological epoch preceding the present the Aralo-Caspian Sea extended. Such are the Baskunchaksky (in the Government of Astrakhan, 112 square kilometres superficial area), the Eltousky (140 versts from the left bank of the Volga, and 200 square kilometres in superficial area), and upwards of 700 other salt lakes lying about the lower portions of the Volga. In those in which the inflow of fresh water is less than that yearly evaporated, and in which the concentration of the solution has reached saturation, the *self-deposited* salt is found already deposited on their beds, or is being yearly deposited during the summer months. Certain limans, or sea-side lakes, of the Azoff Sea are essentially of the same character—as, for instance, those in the neighbourhood of Henichesk and Berdiansk. The saline soils of certain Central Asian steppes, which suffer from a want of atmospheric fresh water, are of the same origin. Their salt originally proceeded from the salt of seas which previously covered these localities, and has not yet been washed away by fresh water. The main result of the above described process of nature is the formation of masses of rock salt, which are, however, being gradually washed away by the subsoil waters flowing in their neighbourhood, and afterwards rising to the surface in certain places as *saline springs*, which indicate the presence of masses of deposited rock salt in the depths of the earth. If the subsoil water flows along a strata of salt for a sufficient length of time it becomes saturated; but in flowing in its further course along an impervious strata (clay) it becomes diluted by the fresh water leaking through the upper soil, and therefore the greater the distance of source of a saline spring from the deposit of rock salt, the poorer will it be in

salt. A perfectly-saturated brine, however, may be procured from the depths of the earth by means of bore holes. The deposits of rock salt themselves, which are sometimes hidden at great depths below the earth's strata, may be arrived at by the guidance of bore-holes and the arrangement of the strata of the district. Deposits of rock salt, about 35 metres thick and 20 metres below the surface, were discovered in this manner in the neighbourhood of Briauścieffky and Dekonoffky, in the Bakhmut district of the Government of Ekaterinoslav. Large quantities of most excellent rock salt are now (since 1880) won from these deposits, whose presence was indicated by the neighbouring salt springs (near Slaviansk and Bakhmut), and bore-holes which had been sunk at these localities for procuring strong (saturated) brines. But the Stassfurt deposits of rock salt, near Magdeburg in Germany, are distinguished as being the first discovered in this manner, and for their many remarkable peculiarities.⁷ The considerable distribution of saline springs in this and the neighbouring districts suggested the presence of deposits of rock salt in the near vicinity. Deep bore-holes sunk in this locality in fact did give a richer brine—even quite saturated with salt. On sinking to a still greater depth, the deposits of salt were themselves in the end arrived at. But the first salt which was met with was a bitter salt unfit for consumption, and which was, therefore, called refuse salt (*abraumsalz*). On sinking still deeper through fresh bands of earth, vast beds of real rock salt were struck. In this instance, the presence of these upper strata containing salts of potassium, magnesium, and sodium, is an excellent proof of the formation of rock salt from sea water. It is a self-evident fact that not only a case of evaporation to the end—for instance, to the separation of carnallite—but also the conservation of such soluble salts as those which separate out from sea water after the sodium chloride, forms a very exceptional phenomenon, which is not repeated in all deposits of rock salt. The Stassfurt deposits, therefore, are of particular interest, not only from a scientific point of view, but also because they form a rich source of potassium salts which have many practical uses. In Western

⁷ When the German savants pointed out the exact locality of the Stassfurt salt-beds and their depth below the surface on the basis of information collected from various quarters respecting bore-holes and the direction of the strata, and when the borings, conducted by the Government, struck out a salt-bed which was bitter and unfit for use, then there was a great outcry against science, and the doubtful result even caused the cessation of the further work of deepening the shafts. It required a great effort to persuade the Government to continue the work. Now, when the pure salt encountered below forms one of the important riches of Germany, and when those 'refuse salts' have proved to be most precious (as a source of potassium and magnesium), we should see in the utilisation of the Stassfurt deposits one of the conquests of science for the common welfare.

Europe, deposits of rock salt have long been known at Wieliczka, near Cracow, and at Cardona in Spain. In Russia the following deposits are known : (*a*) the vast masses of rock salt (3 square kilometres area and up to 140 metres thick) lying directly on the surface of the earth at Iletzky Zastchit, on the left bank of the river Ural, in the Government of Orenburg ; (*b*) the Chingaksky deposit, 90 versts from the river Volga, in the Enotaeffsky district of the Government of Astrakhan ; (*c*) the Kulepinsky (and other) deposits (whose thickness attains 150 metres), on the Araks, in the Government of Erivan in the Caucasus ; (*d*) the Katchiezmansky deposit in the province of Kars ; and (*e*) the Krasnovodsky deposit in the Trans-Caspian province.

A saturated brine, formed by the continued contact of subsoil water with rock salt, is extracted by means of bore-holes, as, for instance, in the Governments of Perm, Kharkoff, and Ekaterinoslav. Sometimes, as at Wergtesgaden in Austria (at Salzkammerhutte), spring water is run on underground beds of rock salt containing much clay.

If a saline spring or the salt water pumped from bore-holes contains but little salt, then the first concentration of the natural solution is not carried on by the costly consumption of fuel, but by the cheaper method of evaporation by means of the wind. For this purpose the so-called graduators are constructed : they consist of long and lofty sheds, which are sometimes several versts long, and generally extend in a direction at right angles to that of the usual course of the wind in the district. These sheds are open at the sides, and are filled with brushwood as shown in fig. 64. Troughs, *A B, C D*, into which the salt water is pumped, run along the top. On flowing from these troughs, through the openings, *a*, the water spreads over the brushwood and distributes itself in a thin layer over it, so that it presents a very large surface for evaporation, in consequence of which it rapidly becomes concentrated in warm or windy weather. After trickling over the brushwood, the solution collects in a reservoir under the graduator, from whence it is usually pumped up by the pumps *P P'*, and again run a second and third time through the graduator, until the solution reaches a degree of concentration at which it becomes profitable to extract the salt by direct heating. Generally the evaporation in the graduator is not carried beyond a concentration of 15 to 20 parts of salt in 100 parts of solution. Strong natural solutions of salt, and also the graduated solutions, are evaporated in large shallow metallic vessels, which are either heated by the direct action of the flame from below or from above. These vessels are made of boiler plate, and are called salt pans. Various means are employed for accelerating the evapora-

tion and for economising fuel, which are mainly based on an artificial draught to carry off the steam as it is formed, and on subjecting the saline solution to a preliminary heating by the waste heat of the steam and furnace gases. Furthermore, the first portions of the salt which




FIG. 64.—Graduator for the evaporation of the water of saline springs.

crystallise out in the salt pans always contain gypsum, owing to the water of saline springs always containing this substance. It is only the portions of the salt which separate later that are distinguished by their great purity. The salt is ladled out as it is deposited, and left to drain on inclined tables and then dried, and in this manner the so-called bay salt is obtained. Since it has become possible to discover the saline deposits themselves, the extraction of table salt from the water of saline springs by evaporation, which was before in general use, has begun to be rejected, and is only able to hold its ground in cases where fuel is cheap.

In order to understand the full importance of the extraction of salt, it will be enough to mention that on the average 20 lbs. of table

salt are consumed per head of population, directly in food or for cattle. In those countries where common salt is employed in technical processes, and especially in England, almost an equal quantity is consumed in the production of substances containing chlorine and sodium, and especially in the manufacture of washing soda, &c., and of chlorine compounds (bleaching powder and hydrochloric acid).

Although certain lumps of rock salt and crystals of bay salt sometimes consist of almost pure sodium chloride, still the ordinary commercial salt contains various impurities, the most common of which are magnesium salts. If the salt be pure, its solution gives no precipitate with sodium carbonate, Na_2CO_3 , showing the absence of magnesium salts, because magnesium carbonate, MgCO_3 , is insoluble in water. Rock salt, which is ground for use, further generally contains a large admixture of clay and other insoluble impurities.⁸ For common use the bulk of the salt obtained is quite suitable without further purification; but some salts are purified by solution and crystallisation of the solution after standing, in which case the evaporation is not carried on to the end, and the impurities remain in the *mother liquor* or in the sediment. When perfectly pure salt is required for chemical purposes it is best to proceed as follows: a saturated solution of table salt is prepared, and hydrochloric acid gas is passed through it; this precipitates the sodium chloride (which is not soluble in a strong solution of hydrochloric acid), while the impurities remain in solution. By repeating the operation and fusing the salt (when adhering hydrochloric acid is volatilised) a pure salt is obtained, which is again crystallised from its solution by evaporation.⁹

Pure sodium chloride, in the form of well-formed crystals (slowly formed at the bottom of the liquid) or in compact masses (in which form rock salt is sometimes met with), is a colourless and transparent substance resembling, but more brittle and less hard than, glass.¹⁰ Common

⁸ The fracture of rock salt generally shows the presence of interlayers of impurities, which are sometimes very small in weight, but visible owing to their refraction. In the excellently laid out salt mines of Briansk, belonging to Mr. Letunoffsky, I counted (1888), if my memory does not deceive me, on an average ten interlayers per metre of thickness, between which the salt was in general very pure, and in places quite transparent. If this be the case, then there would be 350 interlayers for the whole thickness (about 35 metres) of the bed. They probably correspond with the yearly deposition of the salt. In this case the deposition would have extended over more than 300 years. This should be observable at the present day in lakes where the salt is saturated and in course of deposition.

⁹ I have personally convinced myself that by this method not only the sulphates, but also the potassium salts are entirely removed.

¹⁰ According to the determinations of Klodt, the Briansk rock salt withstands a pressure of 340 kilograms per square centimetre, whilst glass withstands 1700 kilos.

salt always crystallises in the cubic system, most frequently in *cubes*, and more rarely in octahedra. Large transparent cubes of common salt, having edges up to 10 centimetres long, are sometimes found in masses of rock salt.¹¹ By rapid evaporation common salt is deposited from its solutions in the form of very small crystals, but with slow evaporation the crystals attain a considerable size. When evaporated in open spaces the salt often separates out on the surface¹² as cubes, which grow on to each other in the form of pyramidal square funnels. In still weather, these clusters are able to support themselves on the surface of the water for a long time, and sometimes go on increasing to a considerable degree, but they sink directly the water penetrates inside them. Salt fuses into a colourless liquid (sp. gr. 1.602, according to Quincke) at about 774° (Carnelley), and if pure it solidifies into a non-crystalline mass, and if impure into an opaque mass whose surface is not smooth. In fusing, sodium chloride commences to volatilise (its

In this respect salt is twice as secure as bricks, and therefore immense masses may be extracted from underground workings with perfect safety, without having recourse to brickwork supports, but only taking advantage of the properties of the salt itself.

¹¹ To obtain well-formed crystals, a saturated solution is mixed with ferric chloride, and several small crystals of sodium chloride are placed at the bottom, and the solution is allowed to slowly evaporate in a closed vessel. Octahedral crystals are obtained in the presence of borax, urea, &c., in the solution. Very fine crystals are formed in a mass of gelatinous silica.

¹² If a solution of sodium chloride be slowly heated from above, where the evaporation is accomplished, then the upper layer will become saturated before the lower and cooler layers, and therefore crystallisation will then begin on the surface, and the crystals first formed will be held up, having also dried from above, on the surface until they become quite soaked. Being heavier than the solution the crystals are partially immersed under it, and the following crystallisation, also proceeding on the surface, will only form crystals along the side of the original crystals. The funnels are formed in this manner. It will be borne on the surface like a boat (if there be no waves), because it will grow more from the upper edges. We can thus understand this, at first sight, strange funnel form of crystallisation of salt. In explanation why the crystallisation under the above conditions begins at the surface and not at the lower layers, it must be mentioned that the specific gravity of a crystal of sodium chloride = 2.16, and that of a solution saturated at 25° contains 26.7 p.c. of salt and has a specific gravity at 25.4° of 1.2004; at 15° a solution contains 26.5 p.c. of salt and has a sp. gr. 1.203 at 15.4°. Hence a solution saturated at a higher temperature is specifically lighter, notwithstanding the greater amount of salt it contains. *Surface crystallisation* cannot take place with many substances, because their solubility increases more rapidly with the temperature than their specific gravity decreases. In this case the saturated solution will always be in the lower layers, where also the crystallisation will take place. Besides which, it may be added that, as a consequence of the properties of water and solutions, when they are heated from above (for instance, by the sun's rays) the warmer layers being the lightest remain above, whilst when heated from below they rise to the top. For this reason the water at great depths below the surface is always cold, as has long been known. These circumstances, as well as those observed by Soret (Chapter I. Note 19), explain the great differences of density, temperature, and in the amount of salts held in the oceans at different latitudes (in polar and tropical climes) and at various depths.

weight decreases), and at a white heat it volatilises with great ease and entirely; but at the ordinary temperature it may, like all ordinary salts, be considered as non-volatile, although as yet no exact experiments have been made in this respect.

A saturated¹³ solution of table salt (containing 26·4 per cent.) has at the ordinary temperature a specific gravity of about 1·2. The specific gravity of the crystals is 2·16. The salt which separates out at the ordinary and higher temperatures contains no water of crystallisation;¹⁴ but if the crystals are formed at a low temperature, especially from a saturated solution cooled to -12° , then they present a prismatic form, and contain two equivalents of water, $\text{NaCl}, 2\text{H}_2\text{O}$. At the ordinary temperature, these crystals split up into sodium chloride and its solution.¹⁵ Unsaturated solutions of table salt when cooled below 0° give¹⁶ crystals of ice, but when the solution has a

¹³ By combining the results of Poggiale, Müller, and Karsten (they are evidently more accurate than those of Gay-Lussac and others), I found that a saturated solution at t° , from 0° to 108° , contains $35\cdot7 + 0\cdot024t + 0\cdot0002t^2$ grams of salt per 100 grams of water. This formula gives a solubility at $0^{\circ} = 35\cdot7$ grams ($\approx 26\cdot3$ p.c.), whilst according to Karsten it is 36·09, Poggiale 35·5, and Müller 35·6 grams. The somewhat large diversity in the data respecting so common a substance as sodium chloride shows the necessity of fresh and most exact determinations.

¹⁴ Perfectly pure *fused* salt is not hygroscopic, according to Karsten, whilst the crystallised salt, even when quite pure, attracts as much as 0·6 p.c. of water from moist air, according to Stas. In the Briansk mines, where the temperature throughout the whole year is about $+10^{\circ}$, it may be observed, as Baron Klodt informed me, that in the summer during damp weather the walls become moist, while in winter they are dry. This is in accordance with the fact that the vapour tension of solutions has a definite magnitude, which is less than that of water.

If the salt contain impurities—such as magnesium sulphate, &c.—it is more hygroscopic. If it contain any magnesium chloride it partially effloresces in a damp atmosphere. The crystallised and not perfectly pure salt decrepitates when heated, owing to its containing water. The pure salt, and also the transparent rock salt, or that which has been once fused, does not decrepitate. Fused sodium chloride gives a feeble alkaline reaction with litmus, as has been shown by many observers, which is due to the formation of sodium oxide (probably by the action of the oxygen of the atmosphere). According to A. Stcherbakoff very sensitive litmus (washed in alcohol and neutralised with oxalic acid) shows an alkaline reaction with even the crystallised salt.

It may be observed that rock salt sometimes contains cavities filled with a colourless liquid. Certain kinds of rock salt emit an odour like that of hydrocarbons. These phenomena have as yet received very little attention.

¹⁵ By cooling a solution of table salt saturated at the ordinary temperature to -15° I first obtained well-formed tabular (six-sided) crystals, which on arriving at the ordinary temperature disintegrated (with the separation of anhydrous sodium chloride), and then prismatic needles up to 20 mm. long were formed from the same solution. I have not yet investigated what is the reason of the difference in crystalline form. It is known (Mitscherlich) that $\text{NaI}, 2\text{H}_2\text{O}$ also crystallises in plates or prisms. Sodium bromide also crystallises with $2\text{H}_2\text{O}$ at the ordinary temperature.

¹⁶ Notwithstanding the great simplicity (p. 91) of the observations on the formation of ice from solution, still even for sodium chloride they cannot yet be considered as sufficiently homogeneous. According to Blagden and Raoult the temperature of the formation

composition $\text{NaCl}, 10\text{H}_2\text{O}$ it solidifies completely at a temperature of -23° . A solution of table salt saturated at its boiling point boils at about 109° , and contains about 42 parts of salt per 100 parts of water.

Of all its physical properties the specific gravity of solutions of sodium chloride is the one which has been the most fully investigated. A comparison of the results of Kremers, Gerlach, Schmidt, Marignac, Thomsen, Nicol, and Bender proves¹⁷ that the specific gravity (in vacuum, taking water at 4° as 10000) at 15° in relation to p , or the percentage amount of the salt in solution, is expressed by the equation $S_{15} = 9991.6 + 71.17p + 0.2140p^2$. For instance, for a solution $200\text{H}_2\text{O} + \text{NaCl}$, in which case $p = 1.6$, $S_{15} = 10106$. It is seen from the curve that the addition of water to the solution produces a contraction,¹⁸ and that the addition of salt (or the differential $\frac{ds}{dp}$) causes, at 15° , a change of specific gravity which is expressed by the straight line $71.17 + 0.428p$. At 0° and 100° (when the specific

of ice from a solution containing c grams of salt per 100 grams of water = $-0.6c$ to $c = 10$, according to Rosetti = $-0.649c$ to $c = 8.7$, according to De Coppet (to $c = 10$) = $-0.762c + 0.0084c^2$, and according to Guthrie a much lower figure. By taking Rosetti's figure and applying the rule given on p. 91 (Chapter I. Note 49) we obtain—

$$i = 0.649 \times \frac{58.5}{18.5} = 2.05.$$

The data for strong solutions are not less contradictory. Thus with 20 p.c. of salt, ice is formed at -14.4° according to Karsten, -17° according to Guthrie, -17.6° according to De Coppet. Riidorff says that for strong solutions the temperature of the formation of ice descends in proportion to the contents of the compound, $\text{NaCl}, 2\text{H}_2\text{O}$ (per 100 grams of water) by 0.342° per 1 gram of salt, and De Coppet shows that there is no proportionality, in a strict sense, for either a percentage of NaCl or of $\text{NaCl}, 2\text{H}_2\text{O}$. The data respecting the vapour tension and boiling point of solutions of sodium chloride are as untrustworthy as the preceding.

¹⁷ A collection of observations on the specific gravity of solutions of sodium chloride and all other aqueous solutions which have been more or less investigated up to the present time is given in my work cited in Chapter I. Note 50.

Solutions of common salt have also been frequently investigated as regards rate of *diffusion* (p. 62), but as yet there are no complete data in this respect. It may be mentioned that Graham and De Vries demonstrated that diffusion in gelatinous masses (for instance, gelatin jelly or gelatinous silica) proceeds in the same manner as in water, which may probably lead to a convenient and accurate method for the investigation of the phenomena of diffusion. N. Umoff (Odessa, 1888) investigated the diffusion of common salt by means of glass globules of definite density. Having poured water into a cylinder over a layer of a solution of sodium chloride, he observed during a period of several months the position (height) of the globules, which floated up higher and higher as the salt permeated upwards. Umoff found that at a constant temperature the distances of the globules (that is, the length of a column limited by layers of definite concentration) remain constant; that at a given moment of time the concentration, q , of different layers situated at a depth z is expressed by the equation $B - Kz - \log. (A - q)$, where A , B , and K are constants; that at a given moment the velocity of the different layers is proportional to their depth, &c. The information respecting diffusion is considerably extended by these researches, but still this subject, from its importance for the theory of solutions and of liquids in general, yet awaits a perfectly-detailed investigation.

¹⁸ If S_0 be the specific gravity of water, and S the specific gravity of a solution containing

gravity of water is 9998.7 and 9585) this augmentation is expressed if 75.4 and 65.7 be substituted for 71.17, and 0.31 and 0.72 for 0.428. In this manner the specific gravity¹⁹ at

	0°	15°	30°	100°
$p = 5$	10372	10353	10307	9922
10	10768	10728	10669	10278
15	11164	11107	11043	10652
20	11568	11501	11429	11043

when water at 0° = 10000.²⁰

p p.c. of salt, then by mixing, for instance, equal weights of water and the solution, we shall obtain a solution containing $\frac{1}{2}p$ of the salt, and if it be formed without contraction, then its specific gravity x will be determined by the equation $\frac{2}{x} = \frac{1}{S_0} + \frac{1}{S}$, because the volume is equal to the weight divided by the density. In reality, the specific gravity always comes out greater than that calculated on the supposition of an absence of contraction, as may be shown by substituting S by its parabolic expression, $S = S_0 + Ap + Bp^2$, and x by $S_0 + A\frac{1}{2}p + B\frac{1}{4}p^2$. By this means it may be easily shown that the contraction, c , in the formation of 100 grams of solution, is not in so simple a relation to the composition of the solution as G. T. Gerlach (1888) takes it, on the supposition that $c = Ap(100 - p)$, where A is a constant for all solutions of a given substance. The magnitude of c is evidently determined by the equation $p.B + (100 - p)S_0 = 100/S + c$, where B is the specific gravity of the substance dissolved, on the supposition of its being in a liquid state. If for sodium chloride at 15° with $p = 10$ and $p = 20$, the mean observed specific gravities be taken as 10726 and 11501, then (as $S_0 = 9991.6$) $A = 2851 \times 10^{-10}$, and $B = 17476$, and therefore for $p = 5$, the calculated specific gravity will be 10377, and the observed is 10353, with a probable error of not more than ± 2 : hence the difference greatly exceeds the possible error. A similar unadaptability of the above-mentioned supposition is evinced in the investigation of all other solutions. The hypothesis under consideration resembles in this respect the hypothesis of Michéland Crafts or Grosjean, which are examined in my work on the specific gravities of solutions. In a first rough approximation solutions may be regarded as mechanical aggregates, and then a general law of their formation may be looked for, but a detailed study of the subject necessitates the search for chemical reactions in them, and such a representation of the nature of solutions leads to the conclusions enunciated in the first chapter and more fully developed in my above-mentioned work. This naturally does not exclude the desire to find laws to which solutions may be subjected, but under the inevitable condition of the consideration of their chemical composition. Such are, for example, the deductions of Van't Hoff, who does not, however, touch on the specific gravity of solutions. With respect to the sp. gr. of weak solutions of metallic chlorides, it may, for instance, be supposed that, having a composition $\text{RCl}_n + 200\text{OH}_2$, they would all have a specific gravity at 15° $4c$, approaching to $9951 + 2.585M$, where M is the molecular weight of the metallic chloride dissolved. For instance, for SrCl_2 , $M = 158$, and the formula gives $S = 10361$, and experiment 10364; for LiCl , $M = 42.5$, and $S = 10061$, and experiment 10060. But similar rules, without the existence of a complete theory of solutions, can only serve as material for the construction of a theory, and too great an importance should not be attached to them.

¹⁹ Generally the specific gravity is observed by weighing in air, dividing the weight in grams by the volume in cubic centimetres, found from the weight of water displaced, divided by its density at the temperature under which the experiment is carried on. If we call this specific gravity S_1 , then as a cubic centimetre of air under the usual conditions weighs about 0.0012 gram, the sp. gr. in a vacuum $S = S_1 - 0.0012 (S_1 - 1)$, if the density of water = 1.

²⁰ If the sp. gr. S_2 be found directly by dividing the weight of a solution by the

It should be remarked that Baumé's hydrometer is graduated by taking a 10 per cent. solution of sodium chloride as 10° on the scale, and therefore it gives approximately the percentage amount of the salt in a solution. Table salt is somewhat soluble in alcohol,²¹ but it is insoluble in ether and in oils.

Table salt gives very few compounds²² (double salts), and these are very readily decomposed; it is also decomposed with great difficulty and its dissociation is unknown.²³ But it is easily decomposed, both when fused and in solution, by the action of a galvanic current. If the dry salt be fused in a crucible and an electric current be passed through it by immersing carbon or platinum electrodes in it (the positive electrode is made of carbon and the negative of platinum or mercury), it is *decomposed into two substances*: a malodorous gas called chlorine appears at the positive pole and metallic sodium at the negative pole, which shows that table salt consists of these two elements. Both of them act on water at the moment of their evolution; the sodium, as we already know, evolves hydrogen from water and forms caustic soda, and the chlorine evolves oxygen from water and forms hydrochloric acid, and therefore on passing a current through a solution of table salt metallic sodium will not be formed—but oxygen, chlorine, and hydrochloric acid will appear at the positive pole, and hydrogen and caustic soda at the negative pole. The presence of hydrochloric acid is easily recognised by its acid properties, and the presence of caustic soda by its alkaline

weight of water at the same temperature and in the same volume, then the true sp. gr. *S* referred to water at 4° is found by multiplying S_2 by the sp. gr. of water at the temperature of observation. All the necessary corrections for the specific gravity of liquids are considered in my two works, *On the Compounds of Alcohol with Water*, 1865, and *The Investigation of Aqueous Solutions by their Specific Gravity*, 1887.

It may not be superfluous to remark that the data respecting the sp. gr. for solutions of sodium chloride near saturation do not sufficiently agree, and there is reason for thinking that in strong solutions containing more sodium chloride than in $\text{NaCl} \cdot 10\text{H}_2\text{O}$ ($p = 24.53$) a different curve should be adopted.

²¹ According to Schiff 100 grams of alcohol, containing p p.c. by weight of $\text{C}_2\text{H}_6\text{O}$, dissolves at 15° —

$p = 10$	20	40	60	80
25	22.6	18.2	5.9	1.2 grams NaCl.

²² Amongst the double salts formed by sodium chloride that obtained by Ditte (1870) by the evaporation of the solution remaining after heating sodium iodate with hydrochloric acid until chlorine ceases to be liberated, is a remarkable one. Its composition is $\text{NaIO}_3 \cdot \text{NaCl} \cdot 4\text{H}_2\text{O}$. Rammelsberg obtained a similar (perhaps the same) salt in well-formed crystals by the direct reaction of both salts.

²³ But it already gives sodium in the flame of a Bunsen's burner (see Spectrum Analysis), doubtless under the reducing action of the elements carbon and hydrogen. In the presence of an excess of hydrochloric acid in the flame (when the sodium would give sodium chloride), there is no sodium formed in the flame and the salt does not communicate its usual coloration.

reaction. Thus table salt, like other salts, is decomposed by the action of an electric current into a metal and a haloid, and presents a composition of great simplicity in comparison with the composition of many salts containing oxygen, which fact supports the hydrogen theory of acids discussed in Chapter III. Naturally, like all other salts, it may be formed from the corresponding base and acid with the separation of water. In fact if we mix caustic soda (alkali) with hydrochloric acid (acid) then table salt is formed, $\text{NaHO} + \text{HCl} = \text{NaCl} + \text{H}_2\text{O}$.

With respect to the double decompositions of sodium chloride it should be observed that they are most varied, and serve as the means for obtaining nearly all the other compounds of sodium and chlorine.


The double decompositions of sodium chloride, as an example of the double decompositions of salts, are almost exclusively based on the possibility of the metal sodium being exchanged for hydrogen and other metals. But neither hydrogen nor any other metal is able to directly displace the sodium from table salt. This would result in the separation of metallic sodium, which itself displaces hydrogen and the majority of other metals from their compounds, and is not, as far as is known, ever separated by them. The replacement, then, of the sodium in sodium chloride by hydrogen and different other metals is accomplished by the transference of the sodium into some other sodium compound. If hydrogen or another metal, M, were combined with an element X, then the double decomposition $\text{NaCl} + \text{MX} = \text{NaX} + \text{MCl}$ takes place. Such double decompositions proceed under particular conditions, sometimes completely and sometimes only partially, as we shall endeavour to explain. In order to acquaint ourselves with the double decompositions of sodium chloride, we will follow the methods actually employed in practice to procure compounds of sodium and chlorine from table salt. For this purpose we will first describe the treatment of sodium chloride by sulphuric acid for the preparation of hydrochloric acid and sodium sulphate. We will then describe the substances obtained from hydrochloric acid and sulphate of sodium. Chlorine itself, and nearly all the other compounds of this element, may be procured from hydrochloric acid, whilst sodium carbonate, caustic soda, metallic sodium itself and all its compounds may be obtained from sodium sulphate.

Even in the laboratory of animal organisms table salt is subjected to similar changes, furnishing the sodium, alkali, and hydrochloric acid, which take part in the processes of animal life.


Its necessity as a constituent in the food of both human beings and animals becomes evident when we consider that both hydrochloric acid and salts of sodium are found in the substances which are separated out from the blood into the stomach and intestines. So, for example,

sodium salts are found in the blood and in the bile elaborated in the liver, and acting on the food in the alimentary canal, whilst hydrochloric acid is found in the acid juices of the stomach. Chlorides of the metals are always found in considerable quantities in the urine, and if they are excreted they must be replenished in the organism; and for the replenishment of the loss substances containing chlorine compounds must be taken in food. Not only do animals consume those amounts of sodium chloride which are found in drinking water or in plants or other animals, but experience has shown that many wild animals travel long distances in search of salt springs, and that domestic animals, which in their natural condition do not require table salt, willingly take it, and that the functions of their organisms become much more regular from doing so.

The action of sulphuric acid on sodium chloride.—If sulphuric acid be poured over table salt, then even at the ordinary temperature, as Glauber observed, an odorous gas, hydrochloric acid, is evolved. The reaction which takes place consists in the sodium of the table salt and the hydrogen of the sulphuric acid changing places.



At the ordinary temperature this reaction is not complete, but soon ceases. If the mixture be heated, the decomposition proceeds until, if there be sufficient table salt present, all the sulphuric acid taken is converted into acid sodium sulphate. If there be an excess of acid it will remain unaltered. If 2 molecules of sodium chloride (117 parts) be taken per molecule of sulphuric acid (98 parts), then on heating the mixture to a moderate temperature only one-half (58·5) of the table salt will suffer change. Complete decomposition, after which neither hydrogen nor chlorine is left in the residual salt, proceeds (when 117 parts of table salt are taken per 98 parts of sulphuric acid) *at a red heat only*. Then—



This double decomposition is the result of the action of the acid salt, NaHSO_4 , first formed on sodium chloride, because the acid salt, as it contains hydrogen, itself acts like an acid, $\text{NaCl} + \text{NaHSO}_4 = \text{HCl} + \text{Na}_2\text{SO}_4$. By adding this equation to the first we obtain the second, which expresses the ultimate reaction. Then all the hydrogen of the sulphuric acid and chlorine of the salt are evolved as gaseous

hydrochloric acid, and the residue will be entirely free from them. Hence in the above reaction, non-volatile or sparingly-volatile table salt and sparingly-volatile sulphuric acid are taken, and as the result of their reaction, after the hydrogen and sodium have exchanged places, there is obtained non-volatile sodium sulphate and gaseous hydrochloric acid. The fact of the latter being a gaseous substance forms the main reason for the reaction proceeding to the very end. The mechanism of this kind of double decomposition, and the cause of the course of the reaction, are exactly the same as those we saw in the decomposition of nitre (Chapter VI.) by the action of sulphuric acid. The sulphuric acid in each displaces the other, volatile, acid.

Not only in these two, but in every instance, if a volatile acid can be formed through the substitution for a metal of the hydrogen of sulphuric acid, then this volatile acid will be formed. From this it may be concluded that the volatility of the acid should be considered as the cause of the progress of the reaction ; and, indeed, if the acid be soluble but not volatile, or if the reaction takes place in an enclosed space where the resulting acid cannot volatilise, or at the ordinary temperature when it does not pass into an elastic state of vapour—then the decomposition does not proceed to the end, but only up to a certain limit. In this respect the explanations given at the beginning of this century by the French chemist Berthollet in his work ‘*Essai de Statique Chimique*,’ are very important. *The doctrine of Berthollet* starts from the supposition that the chemical reaction of substances is accomplished in consequence not only of the measure of affinity between the different parts, but also under the influence of the relative masses of the reacting substances and of those physical conditions under which the reaction takes place. Two substances containing the elements MX and NY, being brought into mutual contact, form by double decomposition the compounds MY and NX, but the formation of these two new compounds will not proceed to the end unless one of the resulting substances is removed from the sphere of action. But it can only be removed if it possesses different physical properties from those of the other substances which are present together with it. Either it will be a gas while the others are liquid or solid, or it will be an insoluble solid while the others are liquid or soluble. The relative amounts of the resultant substance depend, if nothing be separated out from their mutual contact, only on the relative quantities of the substances MX and NY, and upon the measure of attraction existing between the elements M, N, X, and Y ; but however great their mass may be, and however considerable the attraction, still in any case, if nothing be separated out from the sphere of action, the decomposition will cease, a state of equilibrium will be

established, and instead of two there will remain four substances in the mass : namely, a portion of the original bodies MX and NY, and a certain quantity of the newly-formed substances MY and NX, if it be admitted that neither MN nor XY, nor any other substances, are produced, which may for the present²⁴ be admitted in the case of the double decomposition of salts, for which M and N are metals and X and Y haloids. As the ordinary double decomposition consists exclusively in the exchange of metals, the above simplification is applicable in this case. The sum total of the existing data concerning the double decomposition of salts leads to the conclusion that from salts MX + NY there always proceeds a certain quantity of NX and MY, as it should be according to Berthollet's doctrine. A portion of the historical data concerning this subject will be afterwards mentioned, and we will now proceed to point out the observations made by Spring (1888), which show that *even in a solid state* salts are subject to a similar interchange of metals if under a condition of sufficiently close contact (which requires time, a finely-divided state, and intimate mixture). Spring took two non-hygroscopic salts, potassium nitrate, KNO_3 , and well-dried sodium acetate, $\text{C}_2\text{H}_3\text{NaO}_2$, and left a mixture of their powders for several months in a desiccator. An interchange of metals took place, as was seen from the fact that the resultant mass vigorously attracted the moisture of the air owing to the formation of sodium nitrate, NaNO_3 , and potassium acetate, $\text{C}_2\text{H}_3\text{KO}_2$, both of which are highly hygroscopic.^{24b}

When Berthollet enunciated his doctrine the present views of atoms and molecules had yet to be developed, but it is now necessary to submit the examination of the matter to these conceptions, and we will therefore consider the reaction of salts, taking M and N, X and Y as

²⁴ If MX and NY represent the molecules of two salts, and if there be *no third substance* present (such as water in a solution), the formation of XY would also be possible ; for instance, cyanogen, iodine, &c., are capable of combining with simple haloids, and with the complex groups which play the part of haloids in salts. Besides which the salts MX and NY or MY with NX may form double salts. If the number of molecules be unequal, or if the valency of the elements contained be different, as in $\text{NaCl} + \text{H}_2\text{SO}_4$, where Cl is a univalent haloid and SO_2 is bivalent, then the matter may be complicated by the formation of other compounds besides MY and NX, and when a solvent participates in the action, and especially if in a large proportion, then the phenomena must evidently become still more complex ; and this is actually the case in reality. Therefore in placing before the reader a certain portion of the existing store of matter concerning the phenomena of double saline decompositions I cannot consider the theory of the subject as complete, and have therefore limited myself to a few data, the completion of which must be looked for, without losing sight of what has been said above, in more detailed works on the subject of theoretical chemistry.

^{24b} When the mixture of potassium nitrate and sodium acetate was heated by Spring to 100° it was completely fused into one mass, although potassium nitrate fuses at about 340° , and sodium nitrate at about 320° .

equivalent to each other—that is, as capable of replacing each other ‘in toto,’ as Na or K, $\frac{1}{2}$ Ca or $\frac{1}{2}$ Mg (bivalent elements), replace hydrogen.

And as, according to Berthollet's doctrine, when mMX of one salt comes into contact with nNY of another salt a certain quantity xMY and xNX is formed, therefore there remains $m-x$ of the salt MX , and $n-x$ of the salt NY . If m be greater than n , and the mass of M and N and X and Y be equivalent, then the maximum interchange could lead to $x=n$, whilst from the salts taken there would ensue $nMY + nNX + (m-n)MX$ —that is, a portion of one of the salts taken would remain unchanged only because the reaction could only proceed between nMX and nNY . If x were actually equal to n or 0, the mass of the salt MX would not have any influence on the *modus operandi* of the reaction, which is essentially according to the teaching of Bergman, who supposed double reactions to be independent of the mass but determined by affinity only. If M had more affinity to X than to Y, and N more affinity to Y than to X, then, according to Bergman, there would be no decomposition whatever, and x would equal 0. If the affinity of M to Y and of N to X were greater than in the original grouping, then the affinities of M for X and of N for Y would act, and, according to Bergman's doctrine, complete interchange would take place—i.e., x would equal n . According to Berthollet's teaching, a distribution of M and N between X and Y will take place in every case, not only in proportion to the measure of affinity, but also in proportion to the mass, so that with a small affinity and a large mass the same action can be produced as with a large affinity and a small mass. Therefore, (1) x will always be less than n and their ratio $\frac{x}{n}$ less than unity—that is, the decomposition will be expressed by the equation, $mMX + nNY = (m-x)MX + (n-x)NY + xMY + xNX$; (2) by increasing the mass m we increase the decomposition—that is, the measure of x and the ratio $\frac{x}{(n-x)}$ —until with an infinitely large quantity m the fraction $\frac{x}{n}$ will equal 1 and the fraction $\frac{x}{(n-x)}$ be infinite, and the decomposition will be complete, however small the affinities MY and NX may be; and (3) (if $m=n$) by taking $MX + NY$ or $MY + NX$ we arrive at one and the same system in both cases: $(n-x)MX + (n-x)NY + x'MY + xNX$. These direct consequences of Berthollet's teaching are verified in reality. Thus, for example, a mixture of the solutions of sodium nitrate and potassium chloride in all cases has the same sum of properties as a mixture composed of the solutions of potassium nitrate and sodium chloride, naturally under the condition of the mixed solutions being of

identical composition. But this similarity of properties may either proceed from the fact that one system of salts passes into the other (as Bergman professed), in conformity with the predominating affinities (for instance, from $\text{KCl} + \text{NaNO}_3$ there proceeds $\text{KNO}_3 + \text{NaCl}$, if it be admitted that the affinity of the elements of the latter system be greater than in the former); or, on the other hand, because both systems by the interchange of a portion of their elements give one and the same state of equilibrium, as according to Berthollet's teaching. Experiment proves the latter. But before citing the most historically important experiments verifying Berthollet's doctrine, we must stop to consider the conception of *the mass* of the reacting substances. Berthollet by mass understood the direct relative quantity of substances; but now it is impossible to understand this term otherwise than as the number of molecules, for they act as chemical units, and in the special case of double saline decompositions it is better to take the number of equivalents. Thus in the reaction $\text{NaCl} + \text{H}_2\text{SO}_4$, the salt is taken in one equivalent and the H_2SO_4 in two. If $2\text{NaCl} + \text{H}_2\text{SO}_4$ act, then the number of equivalents are equal, and so on. The *influence of mass* on the measure of decomposition $\frac{x}{n}$ forms the root of Berthollet's doctrine, and therefore we will first of all turn our attention to the establishment of this conception with regard to the double decomposition of salts.

About 1840 H. Rose showed that water decomposes metallic sulphides like calcium sulphide, CaS , forming hydrogen sulphide, H_2S , notwithstanding the fact that the affinity of hydrogen sulphide, as an acid, for lime, CaH_2O_2 , as a base, causes them to react on each other, forming calcium sulphide and water, $\text{CaS} + 2\text{H}_2\text{O}$. Furthermore, Rose showed that the greater the amount of water acting on the calcium sulphide, the more complete is the decomposition. The results of this reaction are evident from the fact that the hydrogen sulphide formed may be expelled from the solution by heating, and that the resulting lime is sparingly soluble in water. Rose clearly saw from this that such feeble agents, in a chemical sense, as carbonic anhydride and water, by acting in a mass and for long periods of time in nature on the durable rocks, which resist the action of the most powerful acids, are able to bring about chemical change—to extract, for example, from rocks the bases, lime, soda, potash. The influence of the mass of water on antimonious chloride, bismuth nitrate, &c., is essentially of the same character. These substances give up to the water a mass of acid which is greater according as the mass of the water acting on them is greater.²⁵

²⁵ Historically the influence of the mass of water was the first well-observed phenomenon in support of Berthollet's teaching, and it should not now be forgotten. In double

Barium sulphate, BaSO_4 , which is insoluble in water, when fused with sodium carbonate, Na_2CO_3 , gives, but not completely, barium carbonate, BaCO_3 (also insoluble), and sodium sulphate, Na_2SO_4 . If a solution of sodium carbonate acts on precipitated barium sulphate, then the same decomposition is also accomplished (Dulong, Rose), but it is restricted by a limit and requires time. A mixture of sodium carbonate and sulphate is obtained in the solution and a mixture of barium carbonate and sulphate in the precipitate. If the solution be decanted off and a fresh solution of sodium carbonate be poured over the precipitate, then a fresh portion of the barium sulphate passes into barium carbonate, and so by increasing the mass of sodium carbonate it is possible to entirely convert the barium sulphate into barium carbonate. If a definite quantity of sodium sulphate be added to the solution of sodium carbonate, then the sodium carbonate will have no action whatever on the barium sulphate, because then an equilibrated system, determined by the reverse action of the sodium sulphate on the barium carbonate and by the presence of the sodium carbonate and sulphate in the solution, is at once arrived at. On the other hand, if the mass of the sodium sulphate in the solution be great, then the barium carbonate is reconverted into sulphate until a definite state of equilibrium is attained between the reverse reactions, producing the barium carbonate by the aid of the sodium carbonate or the barium sulphate by the aid of the sodium sulphate.

Another most important conception of Berthollet's teaching consists in the existence of *a limit of exchange decomposition, or in the attainment of a state of equilibrium*. In this respect the determinations of Malaguti (1857) are historically the most important. He took a mixture of the solutions of equivalent quantities of two salts MX and NY , and judged the amount of the resulting exchange from the composition of the precipitate produced by the addition of alcohol. When, for example, zinc sulphate and sodium chloride (ZnSO_4 and 2NaCl) were taken, then there were produced by exchange sodium sulphate and zinc chloride. A mixture of zinc sulphate and sodium sulphate was precipitated by an excess of alcohol, and it appeared from the composition of the precipitate that 72 per cent. of the salts taken had been decomposed. When, however, a mixture of solutions of

decompositions taking place in dilute solutions where the mass of water is large, its influence, notwithstanding the weakness of affinities, must be great, according to the very spirit of Berthollet's doctrine.

As explaining the action of the mass of water, the experiments of Pattison Muir (1879) are very instructive. These experiments demonstrate that bismuth chloride is decomposed the more the greater the relative quantity of water, and the less the mass of hydrochloric acid forming one of the products of the reaction.

sodium sulphate and zinc chloride were taken, the precipitate presented the same composition as before—that is, about 28 per cent. of the salts taken had been subjected to decomposition. In a similar experiment with a mixture of sodium chloride and magnesium sulphate, $2\text{NaCl} + \text{MgSO}_4$, about half of the metals were subjected to decomposition, which may be expressed by the equation $4\text{NaCl} + 2\text{MgSO}_4 = 2\text{NaCl} + \text{MgSO}_4 + \text{Na}_2\text{SO}_4 + \text{MgCl}_2 = 2\text{Na}_2\text{SO}_4 + 2\text{MgCl}_2$. A no less clear limit expressed itself in other of Malaguti's researches when he investigated the above-mentioned reversible reactions of the insoluble salts of barium. When, for example, barium carbonate and sodium sulphate ($\text{BaCO}_3 + \text{Na}_2\text{SO}_4$) were taken, then about 72 per cent. of the salts were decomposed, that is, were converted into barium sulphate and sodium carbonate. But when the two latter salts were taken, then about 19 per cent. of the salts passed into barium carbonate and sodium sulphate. Probably the end of the reaction was not reached in either case, because this would require a great time and a difficultly attainable uniformity of conditions.

Gladstone (1855) took advantage of the colour of solutions of different ferric salts for determining the measure of exchange between metals. Thus a solution of ferric thiocyanate has an exceedingly intense red colour, and by making a comparison between the colour of the resulting solutions and the colour of solutions of known strength it was possible to judge to a certain degree the quantity of the thiocyanate formed. This colorimetric method of determination has an important significance as being the first in which a method was applied for determining the composition of a solution without the removal of any of its component parts. When Gladstone took equivalent quantities of ferric nitrate and potassium thiocyanate $\text{Fe}(\text{NO}_3)_3 + 3\text{KCNS}$ —then only 13 per cent. of the salts were subjected to decomposition. On increasing the mass of the latter salt the quantity of ferric thiocyanate formed increased, but even when more than 300 equivalents of potassium thiocyanate were taken a portion of the iron still remained as nitrate. It is evident that the affinity acting between Fe and NO_3 and between K and CNS on the one hand is greater than the affinities acting between Fe and CNS, together with the affinity of K for NO_3 , on the other hand. The investigation of the variation of the fluorescence of quinine sulphate, as well as the variation of the rotation of the plane of polarisation of nicotine, gave in the hands of Gladstone many proofs of the entire applicability of Berthollet's doctrine, and in particular demonstrated the influence of mass which forms the chief distinctive feature of the, in his time, but little appreciated teaching of Berthollet.

At the beginning of the year 1860, the doctrine of the limit of reaction and of the influence of mass on the process of chemical transformations received a very important support in the researches of Berthelot and P. de Saint-Gilles on the formation of the ethereal salts RX from the alcohols ROH and acids HX , when water is also formed. This conversion is essentially very similar to the formation of salts, but differs in that it proceeds slowly at the ordinary temperature, extending over whole years and is not complete—that is, it has a distinct limit determined by a reverse reaction; thus an ethereal salt RX with water gives an alcohol ROH and an acid HX —up to that limit generally corresponding with two thirds of the alcohol taken, if the action proceed between molecular quantities of alcohol and acid. Thus common alcohol, C_2H_5OH , with acetic acid, $HC_2H_3O_2$, gives the following system rapidly when heated, or slowly at the ordinary temperature, $ROH + HX + 2RX + 2H_2O$, whether we start from $3RHO + 3HX$ or from $3RX + 3H_2O$. The process and completion of the reaction in the above-described instance are very easily observed, because the quantity of free acid is easily determined from the amount of alkali requisite for its saturation, as neither alcohol nor ethereal salt acts on litmus and other reagents for acids. Under the influence of an increased mass of alcohol the reaction proceeds further. If two molecules of alcohol, RHO , be taken for every one molecule of acetic acid, HX , then instead of 66 p.c., 85 p.c. of the acid passes into ethereal salt, and with fifty molecules of RHO nearly all the acid is etherised. The researches of Menshutkin in their details touched on many essential aspects of the same subject, such as the influences of the composition of the alcohol and acid on the limit and rate of exchange—but these, as well as other details, must be looked for in special treatises on organic and theoretical chemistry. In any case the study of etherification supplied chemical mechanics with clear and valuable data, which directly confirm the two fundamental propositions of Berthollet: the influence of mass, and the limit of reaction—that is, the equilibrium between opposite reactions. The study of numerous instances of dissociation which we have already touched on, and which we shall yet meet with on several occasions, gave the same results. With respect to double saline decompositions, it is necessary to further mention the researches of Wiedemann on the decomposing action of the mass of water on the ferric salts, which could be judged of by measuring the magnetism of the solutions, because the ferric oxide (soluble colloid) set free by the water is less magnetic than the ferric salts.

A very important epoch in the history of Berthollet's doctrine was attained when, in 1867, the Norwegian chemists, Guldberg and Waage,

submitted it to an algebraical formula. They called the active mass the number of molecules occurring in a given volume, and allowed, as follows from the spirit of Berthollet's teaching, that the action between the substances was equal to the product of the masses of the reacting substances. Hence if the salts MX and NY be taken in equivalent quantities ($m=1$ and $n=1$) and the salts MY and NX are not added to the mixture but proceed from it, then if k represent the coefficient of the ratio of the action of MX on NY and if k' represent the same coefficient for the pair MY and NX, then we shall have at the moment when the decomposition equals x a measure of action for the first pair : $k(1-x)(1-x)$ and for the second pair $k'xx$, and a state of equilibrium or limit will be reached when $k(1-x)^2=k'x^2$, whence the ratio $k/k'=[x/(1-x)]^2$. Therefore in the case of the action of alcohol on an acid, when $x=\frac{2}{3}$ the magnitude, $k/k'=4$, that is, the reaction of alcohol on the acid is four times greater than that of the ethereal salt on water. If the ratio k/k' be known, then *the influence of mass may be easily determined* from it. Thus if instead of one molecule of alcohol two be taken, then the equation will be $k(2-x)(1-x)=k'xx$, whence $x=0.85$ or 85 p.c., which is close to the result of experiment. If 300 molecules of alcohol be taken, then x proves to be approximately 100 p.c., which is also found to be the case by experiment.²⁶

But it is impossible to subject the formation of salts to any process directly analogous to that which is so conveniently effected in etherification. Many efforts have, however, been made to solve the problem of the measure of reaction in this case also. Thus, for example, Khichinsky (1866), Petrieff (1885), and many others investigated the distribution of metals and haloid groups in the case of one metal and several haloids taken in excess, as acids ; or conversely with an excess of bases, the distribution of these bases with relation to an acid ; in cases where a portion of the substances forms a precipitate and a portion occurs in solution. But such complex cases, although they in general confirm Berthollet's teaching (for instance, a solution of silver nitrate gives a portion of silver oxide with lead oxide, and a solution of nitrate of lead precipitates a portion of lead oxide under the action of silver oxide, as Petrieff demonstrated), still, owing to the complexity of the phenomena (for instance, the formation of basic and double salts), they cannot give

²⁶ From the above it follows that an excess of acid should influence the reaction like an excess of alcohol. If two molecules of acetic acid be taken to one molecule of alcohol, then it is indeed shown by experiment that 84 p.c. of alcohol is etherified. If with a large preponderance of acid or of alcohol certain discrepancies are observed, then their cause must be looked for in the incomplete resemblance of the conditions and outside influences.

simple results. But much more instructive and complete are researches similar to those made by Pattison Muir (1876), who took the simple case of the precipitation of calcium carbonate, CaCO_3 , by the mixture of solutions of calcium chloride and sodium or potassium carbonate, and found in this case that not only was the rate of action (for example, in the case of $\text{CaCl}_2 + \text{Na}_2\text{CO}_3$, 75 per cent. of CaCO_3 was precipitated in five minutes, 85 per cent. in thirty minutes, and 94 in two days) determined by the temperature, relative mass, and amount of water (the mass of water decreases the rate and limit), but that the limit of decomposition was also dependent on these influences. However, even in researches of this kind the conditions of reaction are complicated by the non-uniformity of the media, inasmuch as a portion of the substance is obtained or remains in the precipitate, so that the system is heterogeneous. The investigation of double saline decompositions offers many difficulties, which cannot be considered as yet entirely overcome. Many efforts have, however, long since been made. In virtue of their historical interest, I will cite two of these efforts, which are due to Thomsen (1869) and Ostwald (1876).

Thomsen applied a thermo-chemical method to exceedingly dilute solutions without taking the water into further consideration. He took solutions containing $100\text{H}_2\text{O}$ per NaHO , and sulphuric acid containing $\frac{1}{2}\text{H}_2\text{SO}_4 + 100\text{H}_2\text{O}$. If these solutions be mixed in such proportions that atomic proportions of acid and alkali would act, then for forty grams of caustic soda (which answers to its equivalent) there should be employed 49 grams of sulphuric acid, and then +15689 heat units would be evolved. If the normal sodium sulphate so formed be mixed with n equivalents of sulphuric acid, then a certain amount of heat is absorbed, namely a quantity equal to $\frac{n \cdot 1650}{(n+0.8)}$ heat units. An equivalent of caustic soda, in combining with an equivalent of nitric acid, evolves +13617 units of heat, and the augmentation of the amount of nitric acid entails an absorption of heat for each equivalent equal to -27 units; so also in combining with hydrochloric acids +13740 heat units are absorbed, and for each equivalent of hydrochloric acid beyond this amount there are absorbed 32 heat units. Thus sulphuric acid evolves a somewhat greater quantity of heat than nitric and hydrochloric acids; the difference being approximately equal to 2000 heat units per equivalent of caustic soda. From this it might be concluded that nitric acid or hydrochloric acid would not act on sodium sulphate. In reality, Thomsen found this not to be the case. Nitric and hydrochloric acids decompose sodium sulphate to a much more considerable extent than sulphuric acid decomposes sodium

chloride or sodium nitrate. The following are the data from which Thomsen deduced this conclusion. He mixed any one of these three neutral salts with an acid which is not contained in it ; for instance, he mixed a solution of sodium sulphate with a solution of nitric acid and determined the number of heat units then absorbed. An absorption of heat ensued because a normal salt was taken in the first instance, and the mixture of all the above normal salts with acid produced an absorption of heat. The amount of heat absorbed enabled him to obtain an insight into the process taking place in this intermixture, for sulphuric acid added to sodium sulphate absorbs a considerable quantity of heat, whilst hydrochloric and nitric acids absorb a very small amount of heat in this case. By mixing an equivalent of sodium sulphate with various numbers of equivalents of nitric acid Thomsen observed that the amount of heat absorbed increases more and more as the amount of nitric acid was increased ; thus when HNO_3 was taken per $\frac{1}{2}\text{Na}_2\text{SO}_4$, 1752 heat units were absorbed per equivalent of soda contained in the sodium sulphate. When twice as much nitric acid was taken 2026 heat units, and when three times as much 2050 heat units were absorbed. Had the double decomposition been complete in this case when one equivalent of nitric acid was taken, then the heat evolved would be determined by the sum of $13617 - 15689 - 1650/1.8$, or would equal -2989 heat units, if it be admitted that sulphuric acid when mixed with NaNO_3 absorbs as much heat as when mixed with $\frac{1}{2}\text{Na}_2\text{SO}_4$. But as in reality only 1752 heat units were absorbed instead of 2989 units, therefore a displacement of only about two-thirds of the sulphuric acid had taken place—that is, the ratio $k : k'$ for the reaction $\frac{1}{2}\text{Na}_2\text{SO}_4 + \text{HNO}_3$ and $\text{NaNO}_3 + \frac{1}{2}\text{H}_2\text{SO}_4$ is equal, as for ethereal salts, to 4. By taking this figure and admitting the above supposition, Thomsen found that for all mixtures of sodium with nitric acid, and of sodium nitrate with sulphuric acid, the amounts of heat followed Guldberg and Waage's law ; that is, the limit of decomposition reached was greater the greater the mass of acid added. The relation of hydrochloric to sulphuric acid gave the same results. Thus on mixing $\frac{1}{2}\text{Na}_2\text{SO}_4$ with HCl , the thermal result of experiment was -1682 , and by calculation -1690 ; when mixed with 2HCl the experimental result was -1878 and by calculation -1870 , with 4HCl the result of experiment was -1896 and by calculation -1917 . When $\text{NaCl} + \frac{1}{2}\text{H}_2\text{SO}_4$ was taken, then experiment showed an evolution of $+244$ heat units, whilst from calculation it should have been $+257$ heat units ; on doubling the quantity of acid experiment gave $+336$ and calculation $+292$. The slight differences between the results obtained by experiment and calculation are due to the unavoidable errors of calorimetric determi-

nations. Therefore the researches of Thomsen fully confirm the hypotheses of Guldberg and Waage and the doctrine of Berthollet.²⁷

²⁷ Thomsen concludes his investigation with the words: (a) 'When equivalent quantities of NaHO , HNO_3 (or HCl) and $\frac{1}{2}\text{H}_2\text{SO}_4$ react on one another in an aqueous solution, then two-thirds of the soda combines with the nitric and one-third with the sulphuric acid; (b) this subdivision repeats itself, whether the soda be taken combine 1 with nitric or with sulphuric acid; (c) and therefore nitric acid has double the tendency to combine with the base that sulphuric acid has, and therefore in the wet way it is a stronger acid than the latter.'

'It is therefore necessary,' Thomsen afterwards remarks, 'to have an expression indicating the tendency of an acid for the saturation of bases. This idea cannot be expressed by the word *affinity*, because by this term is most often understood that force which it is necessary to overcome in order to decompose a substance into its component parts. This force should therefore be measured by the amount of work or heat employed for the decomposition of the substance. The above-mentioned phenomenon is of an entirely different nature,' and Thomsen introduces the term *avidity*, by which he designates the tendency of acids for neutralisation. 'Therefore the avidity of nitric acid with respect to soda is twice as great as the avidity of sulphuric acid. An exactly similar result is obtained with hydrochloric acid, so that its avidity with respect to soda is also double the avidity of sulphuric acid. Experiments conducted with other acids showed that not one of the acids investigated had so great an avidity as nitric acid; some had a greater avidity than sulphuric acid, others less, and in some instances the avidity 0.' The reader will naturally clearly see that the path chosen by Thomsen deserves being worked out, because his results concern important questions of chemistry, but great faith cannot be placed in the deductions as yet arrived at by Thomsen, because great complexity of relations is to be seen in the very method of his investigation. It is especially important to turn attention to the fact that all the reactions investigated are reactions of double decomposition. In them A and B do not combine with C and distribute themselves according to their affinity or avidity for combination, but reversible reactions are induced. MX and NY give MY and NX , and conversely; therefore, the affinity or avidity for combination is not here directly determined, but only the difference or relation of the affinities or avidities. The affinity of nitric acid not only for the water of constitution, but also for that serving for solution, is much less than that of sulphuric acid. This is seen from thermal data. The reaction $\text{N}_2\text{O}_5 + \text{H}_2\text{O}$ gives +3600 heat units, and the solution of the resultant hydrate, 2HNO_3 , in a large excess of water evolves +14986 heat units. The formation of $\text{SO}_3 + \text{H}_2\text{O}$ evolves +21308 heat units, and the solution of H_2SO_4 in an excess of water 17860—that is, sulphuric acid gives more heat in both cases. The interchange between Na_2SO_4 and 2HNO_3 is not only accomplished at the expense of the production of NaNO_3 , but also at the expense of the formation of H_2SO_4 , hence the affinity of sulphuric acid for water plays its part in the phenomena of displacement. Therefore in determinations like those made by Thomsen the water does not form a medium which is present without participating in the process, but surely plays its own part. No less essential is the circumstance that sodium sulphate is able to combine with an excess of sulphuric acid to form the acid salt, whilst the salts of nitric and hydrochloric acids do not have this property. But with that method of interpretation of Guldberg and Waage's deduction which is given in the text, the adaptability of their formula to the phenomena observed by Thomsen may be expected, notwithstanding these incidental actions, although the idea of the relative tendencies of acids for combining with alkalis cannot be deduced from the coincidence of the results of experiment with those of calculation. If sodium oxide (Na_2O) were brought into contact with sulphuric anhydride and nitric anhydride (SO_3 and N_2O_5) the distribution would probably be different, and even if stronger solutions than those employed by Thomsen were taken perhaps the result would be different, more especially judging from what is said in the following note. (Compare also Chapter IX. Note 14.)

Whilst retaining essentially the methods of Thomsen, Ostwald determined the variation of the sp. gr. (and afterwards of volume) proceeding in the same dilute solutions, on the saturation of acids by bases, and in the decomposition of the salts of one acid by the other, and arrived at conclusions of just the same nature as Thomsen did. Ostwald's method will be clearly understood from an example. A solution of caustic soda, containing an almost molecular (40 grams) weight per litre, had a specific gravity of 1.04051. The specific gravities of solutions of equal volume and equivalent composition of sulphuric and nitric acids were 1.02970 and 1.03084 respectively. On mixing the solutions of NaHO and H_2SO_4 there was formed a solution of Na_2SO_4 of sp. gr. 1.02959; hence there ensued a decrease of specific gravity which we will term Q , equal to $1.04051 + 1.02970 - 2(1.02959) = 0.01103$. So also the specific gravity after mixture of the solutions of NaHO and HNO_3 was 1.02633, and therefore $Q = 0.01869$. When one volume of the solution of nitric acid was added to two volumes of the solution of sodium sulphate, a solution of sp. gr. 1.02781 was obtained, and therefore the resultant decrease of sp. gr.

$$Q_1 = 2(1.02959) + 1.03084 - 3(1.02781) = 0.00659.$$

Had there been no chemical reaction between the salts, then according to Ostwald's reasoning the specific gravity of the solutions would not have changed, and if the nitric acid had displaced the sulphuric acid Q_2 would be $= 0.01869 - 0.01103 = 0.00766$. It is evident that a portion of the sulphuric acid was displaced by the nitric acid. But the measure of displacement is not equal to the ratio between Q_1 and Q_2 , because a decrease of sp. gr. also occurs on mixing the solution of sodium sulphate with sulphuric acid, whilst the mixing of the solutions of sodium nitrate and nitric acid only produces a slight variation of sp. gr. which falls within the limits of error of experiment. Ostwald deduces from similar data the same conclusions as Thomsen, and thus re-confirms the formula deduced by Guldberg and Waage, and the teaching of Berthollet.²⁸

²⁸ The participation of water is seen still more clearly in the methods adopted by Ostwald than in those of Thomsen, because in the saturation of solutions of acids by alkalis (which Kremers, Reinhold, and others had previously studied) there is observed not a contraction, as might have been expected from the quantity of heat which is then evolved, but an expansion, of volume (a decrease of specific gravity, if we calculate as Ostwald did in his first investigations). Thus by mixing 1180 grams of a solution of sulphuric acid of the composition $\text{SO}_3 + 100\text{H}_2\text{O}$, occupying a volume of 1815 c.c., with a corresponding quantity of a solution $2(\text{NaHO} + 5\text{H}_2\text{O})$, whose volume = 1793 c.c., we obtain not 3608 but 3633 c.c., an expansion of 25 c.c. per gram molecule of the resulting salt, Na_2SO_4 . It is the same in other cases. Nitric and hydrochloric acids give a still greater expansion than sulphuric acid, and potassium hydroxide than sodium hydroxide.

The majority of the above-mentioned researches were carried on in aqueous solutions, and as water is itself a saline compound, and is able to combine with salts and enter into double decomposition with them, such reactions taking place in solutions in reality present very complex cases. In this sense the reaction between alcohols and acids is much more simple, and therefore its significance in confirmation of Berthollet's doctrine is of particular importance. The only cases which can be compared with these reactions from their simplicity are those exchange decompositions investigated by G. G. Gustavson, and which take place between CCl_4 and RBr_n on the one hand and CBr_4 and RCl_n on the other. This case is convenient for investigation in the sense that the RCl_n and RBr_n taken belong (like BCl_3 , SiCl_4 , TiCl_4 , POCl_3 , and SnCl_4) to the number of substances which are decomposed by water, whilst CCl_4 and CBr_4 are not decomposed by water; and therefore, by heating, for instance, a mixture $\text{CCl}_4 + \text{SiBr}_4$ it is possible to arrive at a conclusion as to the amount of interchange by treating the product with water, which decomposes the SiBr_4 left unchanged and the SiCl_4 formed by the exchange, and therefore by determining the composition of the product acted on by the water it is possible to form a conclusion as to the amount of decomposition.

whilst a solution of ammonia gives a contraction. The relation to water must be considered as the cause of these phenomena. When sodium hydroxide and sulphuric acid dissolve in water they develop heat and give a vigorous contraction; the water is separated from such solutions with great difficulty. After mutual saturation they form the salt Na_2SO_4 , which retains the water but feebly and evolves but little heat with it, which, in a word, has little affinity for water. The water in the saturation of sulphuric acid by soda is, so to say, displaced from a stable combination and passes into an unstable combination; hence an expansion (decrease of sp. gr.) takes place. It is not the reaction of the acid on the alkali, but the reaction of water, that produces the phenomenon by which Ostwald desires to measure the degree of salt formation. The water, which escaped attention, itself has affinity, and influences those phenomena which are being investigated. Furthermore, in the given instance its influence is very great because its mass is large. When it is not present, or only present in small quantities, the affinity of the base to the acid leads to contraction, and not expansion. Na_2O has a sp. gr. 2.8, hence its volume = 22; the sp. gr. of SO_5 is 1.9 and volume 41, hence the sum of their volumes is 63, and for Na_2SO_4 the sp. gr. is 2.65 and volume 53.6, consequently a contraction of 10 c.c. per gram molecule of salt. The volume of H_2SO_4 = 53.3, that of 2NaHO = 37.4; there is produced $2\text{H}_2\text{O}$, volume = 36 + Na_2SO_4 , volume = 53.6. There react 90.7 c.c., and on saturation there results 89.6 c.c.; consequently contraction again ensues, although less, and although this reaction is one of substitution and not of combination. Consequently the phenomena studied by Ostwald hardly depend on the measure of the reaction of the salts, but more on the relation of the substances dissolved to water. In substitutions, for instance, $2\text{NaNO}_3 + \text{H}_2\text{SO}_4 - 2\text{HNO}_3 - \text{Na}_2\text{SO}_4$, the volumes vary but slightly; in the above example they are $2(38.8) + 53.3$ and $2(41.2) + 53.6$; hence 131 volumes act, and 136 volumes are produced. It may be thought, therefore, on the basis of what has been said, that on taking water into consideration the phenomena studied by Thomsen and Ostwald prove to be much more complex than they at first appear, and that this method can scarcely lead to a right judgment as to the distribution of acids between bases.

The mixture was always formed with equivalent quantities—for instance, $4\text{BCl}_3 + 3\text{CBr}_4$. It appeared that there was no exchange whatever on simple intermixture, but that it proceeds, and then slowly, when the mixture is heated (for example with the above-cited mixture at 123° 4.06 per cent. of Cl was replaced by Br after 1.4 days' heating, and 6.83 per cent. after 28 days, and 10.12 per cent. when heated at 150° for 60 days) A limit was always reached which corresponded with the complementary system; for example, in the given instance to the system $4\text{BBr}_3 + 3\text{CCl}_4$. So in this last 89.97 per cent. of bromine in the BBr_3 was replaced by chlorine; that is, there was obtained 89.97 molecules of BCl_3 and there remained 10.02 molecules of BBr_3 , and therefore the same state of equilibrium was reached as that given by the system $4\text{BCl}_3 + 3\text{CBr}_4$. Both systems gave one and the same state of equilibrium at the limit, as follows from Berthollet's doctrine.^{28b}

^{28b} G. G. Gustavson's researches, which were conducted in the laboratory of the St. Petersburg University in 1871-72, are among the first in which the measure of the affinity of the elements for haloids appears with perfect clearness in the limit of substitution and in the rate of reaction. The researches conducted by A. L. Potilitzin (of which mention will be made in Chapter XI. Note 66) in the same laboratory touch on another aspect of the same problem which has not yet made much progress, notwithstanding its importance and the fact that the theoretical side of the subject (thanks especially to Guldberg and Van't Hoff) has since been rapidly pushed forward. It would be very important if the researches of Gustavson touched on the influence of mass, and were more fully supplied with data concerning velocities and temperatures, because of the great significance which the instance considered has for the understanding of double saline decompositions in the 'absence of water.'

Furthermore, Gustavson showed that the greater the atomic weight of the element (B, Si, Ti, As, Sn) combined *with chlorine* the greater the amount of chlorine replaced by bromine by the action of CBr_4 , and consequently the less the amount of bromine replaced by chlorine by the action of CCl_4 on bromine compounds. For instance, for chlorine compounds the percentage of substitution (at the limit) is—

BCl_3	SiCl_4	TiCl_4	AsCl_3	SnCl_4
10.1	12.5	43.6	71.8	77.5

It should be observed, however, that Thorpe, on the basis of his experiments, denies the universality of this. I may mention one conclusion which it appears to me may be drawn from the above cited figures of Gustavson, if they further verify themselves even within narrow limits. If CBr_4 be heated with RCl_4 , then an exchange of the bromine by chlorine takes place. But what would be the result if it were mixed with CCl_4 ? Judging by the magnitude of the atomic weights, B = 11, C = 12, Si = 28, about 11 p.c. of the chlorine would be replaced by bromine. But what does this signify? I think that this shows the existence of a movement of the atoms in the molecule. The mixture of CCl_4 and CBr_4 does not remain in a state of static equilibrium; not only are the molecules contained in it in a state of movement but also the atoms in the molecules, and the above figures show the measure of their translation under these conditions. The bromine in the CBr_4 is, *within the limit*, substituted by the chlorine of the CCl_4 in a quantity of about 11 out of 100; that is, a portion of the atoms of bromine previously to this moment in combination with one atom of carbon pass over to the other atom of carbon, and the chlorine passes over from this second atom of carbon to replace it. Therefore, also, in the homogeneous mass CCl_4 all the atoms of Cl do not remain constantly combined with the same atoms of

Thus we now find ample confirmation from various quarters for the following rules of Berthollet, on referring them to double saline decompositions: 1. From two salts MX and NY containing different haloids and metals there result from their reaction two others, MY and NX, but such a substitution will not proceed to the end unless one product passes from the sphere of action. 2. This reaction is limited by the existence of an equilibrium between MX, NY, MY, and NX, because a reverse reaction is quite as possible as the direct reaction. 3. This limit is determined by both the measure of the active affinities and by the relative masses of the substances measured by the number of the reacting molecules. 4. Other conditions being constant, the chemical action is proportional to the product of the chemical masses in action.²⁹

Thus if the salts MX and NY after reaction partly formed salts MY and NX, then a state of equilibrium is reached and the reaction ceases; but if one of the resultant compounds, in virtue of its physical properties, passes from the sphere of action of the remaining substances, then the reaction will continue. This exit from the sphere of action depends on the physical properties of the substance and on the conditions under which the reaction takes place. Thus, for instance, the salt NX may, in the case of reaction between solutions, separate as a precipitate, as an insoluble substance, while the other three substances remain in solution, or it may pass into vapour, and in this manner also pass away from the sphere of action of the remaining substances. Let us now suppose that it passes away in some form or other from the sphere of action of the remaining substances—for instance, that it is transformed into a precipitate or vapour—then a fresh reaction will set in and a

carbon, and *there is an exchange of atoms between different molecules in a homogeneous medium also.* This hypothesis may, in my opinion, explain certain phenomena of dissociation, but in mentioning it I do not consider it possible to linger on it. I will only observe that a similar hypothesis suggested itself to me in my researches on solutions, and that Pfaunder essentially enunciated a similar hypothesis, and in recent times a like view is beginning to diffuse itself with respect to the electrolysis of saline solutions.

²⁹ Berthollet's doctrine can hardly be in any way undermined when it is shown that there are cases in which there is no decomposition between salts, because in principle the affinity may be so small that a large mass would still give no observable displacements. The fundamental condition of the adaptability of Berthollet's doctrine, as well as Deville's doctrine, of dissociation lies in the reversibility of reactions. As there are practically unversible reactions (for instance, $\text{CCl}_4 + 2\text{H}_2\text{O} \rightarrow \text{CO}_2 + 4\text{HCl}$), and as non-volatile substances do exist, so whilst accepting the doctrine of reversible reactions and retaining the doctrines of the evaporation of liquids, it is possible to admit the existence of non-volatile substances, and in just the same way of reaction without any visible conformity to Berthollet's doctrine. This doctrine evidently approaches nearer than the opposite doctrine of Bergman to the solution of the complex problems of chemical mechanics, for the successful resolution of which at the present time the richest fruits are to be expected from the working out of data concerning dissociation, the influence of mass, and the equilibrium and velocity of reactions.

reformation of the salt NX . If it be removed, then, although the quantity of the elements N and X in the mass will be diminished, still, according to Berthollet's law, a certain amount of NX should be again formed. When this substance is again formed, then, owing to its physical properties, it will again pass away; hence the reaction, in consequence of the physical properties of the resultant substance, is able to proceed to completion notwithstanding the possible weakness of the attraction existing between the elements entering into the composition of the resultant substance NX . Naturally, if the resultant substance is also formed of elements having a considerable degree of affinity, then the complete decomposition is considerably facilitated.

Such a representation of the *modus operandi* of chemical transformations is applicable with great clearness to a number of reactions studied in chemistry, and, what is especially important, the application of this aspect of Berthollet's teaching does not in any way require the determination of the measure of affinity acting between the substances present. For instance, the action of ammonia on solutions of salts; the displacement, by its means, of basic hydrates soluble in water; the separation of volatile nitric acid by the aid of non-volatile sulphuric acid, as well as the decomposition of table salt by means of sulphuric acid, when gaseous hydrochloric acid is formed—may be taken as examples of reactions which proceed to the end, inasmuch as one of the resultant substances is entirely removed from the sphere of action, but they in no way indicate the measure of affinity.³⁰

³⁰ Common salt not only enters into double decomposition with acids but also *with every salt*. However, as clearly follows from Berthollet's doctrine, this form of decomposition will only in a few cases render it possible for new metallic chlorides to be obtained, because the decomposition will not be carried on to the end unless the metallic chloride formed separates from the mass of the active substances. Thus, for example, if a solution of common salt be mixed with a solution of magnesium sulphate, double decomposition ensues, but not completely, because all the substances remain in the solution. In this case the decomposition may result in the formation of sodium sulphate and magnesium chloride, substances which are soluble in water; nothing is disengaged, and therefore the decomposition $2NaCl + MgSO_4 = MgCl_2 + Na_2SO_4$ cannot proceed to the end. However, the sodium sulphate formed in this manner may be separated by freezing the mixture. Sulphate of sodium is sparingly soluble in the cold, and therefore if a sufficiently strong solution of common salt and magnesium sulphate be taken, the resulting sodium sulphate will separate out in the cold as crystals containing water of crystallisation. The complete separation of the sodium sulphate will naturally not take place, owing to a portion of the salt remaining in the solution in the cold. Nevertheless, this kind of decomposition is made use of for the preparation of sodium sulphate from the residues left after the evaporation of sea-water, which contain a mixture of magnesium sulphate and common salt. Such a mixture is encountered at Stassfurt in a natural form. The separation is sometimes carried on by means of artificial cooling by refrigerating machines. It might be said that this form of double decomposition is only accomplished with a change of temperature; but this would not be true, as may be concluded from other analogous cases. Thus, for instance, a solution of copper sulphate is of a blue

As a proof that double decompositions like the above are actually accomplished in the sense of Berthollet's doctrine, the fact may be cited that table salt may be entirely decomposed by nitric acid, and nitre may be completely decomposed by hydrochloric acid, just as they are decomposed by sulphuric acid; but this only takes place when, in the first instance, an excess of nitric acid is taken, and in the second instance with an excess of hydrochloric acid for a given quantity of the sodium salt, and if the resultant acid passes off. If sodium chloride be put into a porcelain evaporating basin, nitric acid be added to it, and the mixture be heated, then both hydrochloric and nitric acids are expelled by the heat. Thus the nitric acid partially acts on the sodium chloride, but on heating, as both acids are volatile, they are both converted into vapour; and therefore the residue will contain a mixture of a certain quantity of the sodium chloride taken and of the sodium nitrate formed. If a fresh quantity of nitric acid be then added, reaction will again set in, a certain portion of hydrochloric acid is again evolved, and on heating is expelled together with nitric acid. If this be repeated several times, it is possible to expel all the hydrochloric acid, and to obtain sodium nitrate only in the residue. If, on the contrary, we take sodium nitrate and add hydrochloric acid to it in an aqueous solution, then reaction again sets in, a certain quantity of the hydrochloric acid displaces a portion of the nitric acid, and on heating the excess of hydrochloric acid passes away with the nitric acid formed. On repeating this process, it is possible to displace the nitric acid with an excess of hydrochloric acid, just as it was possible to displace the hydrochloric acid by an excess of nitric acid. The influence of the mass of the substance in action and the influence of volatility is here very distinctly

colour, while a solution of copper chloride is green. If we mix both salts together the green tint is distinctly visible, so that by this means the presence of the copper chloride in the solution of copper sulphate is clearly seen. If now we add a solution of common salt to a solution of copper sulphate a green coloration is obtained, which indicates the formation of copper chloride. In this instance it is not separated, but it is immediately formed on the addition of common salt, as it should be according to Berthollet's doctrine.

The complete formation of a metallic chloride from common salt can only occur, judging from the above, when it separates from the sphere of action. The salts of silver are instances in question, because the silver chloride is insoluble in water; and therefore if we add a solution of sodium chloride to a solution of a silver salt, then silver chloride and the sodium salt of that acid which was in the silver salt are formed. The amount of silver chloride formed immediately separates from the solution, because it is insoluble in water, and the reaction in consequence is further directed to the end—that is, either the whole quantity of the silver is separated or all the chlorine passes into silver chloride. This method is made use of for separating silver from its solutions, and also for determining the quantity of chlorine. It must not, however, be forgotten that silver chloride is slightly soluble in water and still more so in a solution of sodium chloride, and that, therefore, a certain trace of silver escapes precipitation.

seen. Hence it may be affirmed that sulphuric acid does not displace hydrochloric acid because of an especially high degree of affinity, but that this reaction is only carried on to the end because the sulphuric acid is not volatile whilst the hydrochloric acid which is formed is volatile.

The preparation of hydrochloric acid in the laboratory and on a large scale is based upon these data. In the first instance, an excess of sulphuric acid is employed in order that the reaction may proceed easily and at a low temperature, whilst on a large scale, when it is necessary to economise every material, equivalent quantities are taken in order to obtain the normal salt Na_2SO_4 and not the acid salt (p. 422), which would require twice as much acid. It may be remarked that dry hydrochloric acid is a gas which is very soluble in water. It is most frequently used in practice in this state of solution under the name of *muratic acid*.³¹




FIG. 65.—Section of a salt cake furnace. B, pan in which the sodium chloride and sulphuric acid are first mixed and heated. C, muffle for the ultimate decomposition.

In chemical works the decomposition of sodium chloride by means of sulphuric acid is carried on on a very large scale, chiefly with a view to the preparation of normal sodium sulphate, the hydrochloric acid being a bye-product. The furnace employed is termed a *salt cake furnace*. It is represented in fig. 65, and consists of the following two parts : the

³¹ The apparatus shown in fig. 46 (p. 250) is generally employed for the preparation of small quantities of hydrochloric acid. Common salt is placed in the retort ; the salt is generally previously fused, as it otherwise froths and boils over the apparatus. When the

pan B and the roaster C, or enclosed space built up of large bricks *a* and enveloped on all sides by the smoke and flames from the fire grate, F. The ultimate decomposition of the salt by the sulphuric acid is accomplished in the roaster. The hydrochloric acid gas evolved in this reaction escapes through the tube O as will presently be described. But the first decomposition of sodium chloride by sulphuric acid does not require so high a temperature as the ultimate decomposition, and is therefore carried on in the front and cooler portion, B, whose bottom is heated by gas flues. When the reaction in this portion ceases and the evolution of hydrochloric acid stops, then the mass, which contains about half of the sodium chloride yet undecomposed and the sulphuric acid in the form of acid sodium sulphate, is removed from B and thrown into the roaster C, where the action is completed. Normal sodium sulphate, which we shall afterwards describe, remains in the roaster. It is employed both directly in the manufacture of glass, and in the preparation of other sodium compounds for instance, in the preparation of soda ash, as will afterwards be described. For the present we will only turn our attention to the hydrochloric acid evolved in B and C. In chemical works, where sulphuric acid of 60° Baumé (22 p. c. of water) is employed, 117 parts of sodium chloride are taken to about 125 parts of sulphuric acid.

The hydrochloric acid gas evolved is subjected to condensation by dissolving it in water.³² If the apparatus in which the decomposition apparatus is placed in order sulphuric acid mixed with water is poured down the thistle funnel into the retort. About one and a half times the weight of the salt of strong sulphuric acid is usually taken, and it is diluted with a small quantity of water (half) if it be desired to retard the action, as in using strong sulphuric acid the action immediately begins with great vigour. The mixture, at first without the aid of heat and then at a moderate temperature (in a water-bath), evolves hydrochloric acid. Commercial hydrochloric acid contains many impurities; it is usually purified by distillation, the middle portions being collected. It is purified from arsenic by adding FeCl_2 , distilling, and casting aside the first third of the distillate. If free hydrochloric acid gas be required, it is passed through a vessel containing strong sulphuric acid to dry it, and it is collected over a mercury bath.

Phosphoric anhydride absorbs hydrogen chloride (Bailey and Fowler, 1888; $2\text{P}_2\text{O}_5 + 3\text{HCl} = \text{POCl}_3 + 3\text{HPO}_3$) at the ordinary temperature, and therefore the gas cannot be dried by this substance.

³² As at works which treat common salt in order to obtain sodium sulphate, the hydrochloric acid is sometimes held in no value, they would readily allow it to escape into smoke and into the atmosphere, which would greatly injure the air of the neighbourhood and destroy all vegetation, and therefore in all countries there are laws forbidding the works to proceed in this manner, and requiring the absorption of the hydrochloric acid by water at the works themselves, and not permitting the solution to be run into rivers and streams, whose waters it would spoil. It may be remarked that the absorption of hydrochloric acid presents no particular difficulties (the absorption of sulphurous acid is much more difficult), because hydrochloric acid has a great affinity for water and gives a hydrate which boils above 100°. Hence, even steam and hot water, as well as weaker solutions, can be used for absorbing the acid. However, Warder (1888) showed that weak

is accomplished were hermetically closed, and only presented one outlet, then the escape of the hydrochloric acid would only proceed through the escape pipe intended for this purpose. But as it is impossible to construct a perfectly hermetically closed furnace, it is necessary to increase the draught by artificial means, or to oblige the hydrochloric acid gas to pass through those arrangements in which it is condensed. This is done by connecting the ends of the tubes through which the hydrochloric acid gas escapes from the furnace with high chimneys, where the strong draught proceeding from the combustion of the fuel carries off the hydrochloric acid and air which is mixed with it. This causes a current of hydrochloric acid gas to pass through the absorbing apparatus in a definite direction. Here it encounters a current of water flowing in the opposite direction, by which it is absorbed. It is not customary to cause the acid to pass through the water, but only to bring it into contact with the surface of the water. The absorption apparatus consists of large earthenware vessels having four orifices, two above and two lateral ones in the wide central portion of each vessel. The upper orifices serve for connecting the vessels together, and the hydrochloric acid gas escaping from the furnace passes through these tubes. The water for absorbing the acid enters at the upper, and flows out from the lower, vessel, and passes through the lateral orifices in the vessels. The water flows from the chimney towards the furnace, and it is therefore evident that the outflowing water will be the most saturated with acid, of which it actually contains about 20 per cent. The absorption in these vessels is not complete. The ultimate absorption of the hydrochloric acid is carried on in the so-called *coke towers*. These are high chimneys, like that shown in fig. 66. They are frequently divided into two portions, or consist of two adjacent chimneys. A lattice work of bricks, C, is laid on the bottom of these towers, on which coke is piled up to the top of the tower. Water, distributing itself over the coke, trickles down to the bottom of the tower, and in so doing absorbs the hydrochloric acid gas rising upwards.

It will be readily understood that hydrochloric acid may be

solutions of composition $\text{H}_2\text{O} + n\text{HCl}$ when boiled (the residue will be almost $\text{HCl}, 8\text{H}_2\text{O}$) evolve (not water but) a solution of the composition $\text{H}_2\text{O} + 44.5n\text{HCl}$; for example, on distilling $\text{HCl}, 10\text{H}_2\text{O}$, $\text{HCl}, 23\text{H}_2\text{O}$ is first obtained in the distillate. As the strength of the residue becomes greater, so also does that of the distillate, and therefore in order to completely absorb hydrochloric acid it is necessary in the end to have recourse to water.

As in Russia the manufacture of sodium sulphate from sodium chloride has not yet been sufficiently developed, and as hydrochloric acid is required for many technical purposes (for instance, for the preparation of zinc chloride, which is employed for soaking railway sleepers), therefore the salt is often treated mainly for the manufacture of hydrochloric acid.

obtained from all other metallic chlorides.³³ It is

³³ Thus the metallic chlorides, which are decomposed to a greater or less degree by water, correspond with feeble bases. Such are, for example, MgCl_2 , AlCl_3 , SbCl_3 , BiCl_3 . The decomposition of magnesium chloride (and also carnallite) by sulphuric acid proceeds at the ordinary temperature and *may be employed as a convenient method for the production of hydrochloric acid*. The vapour of common salt in the presence of steam and silica (which is capable of combining with sodium oxide) gives hydrochloric acid and sodium silicate. Hydrochloric acid is also produced in many reactions of decomposition of carbon compounds containing chlorine and hydrogen; for instance, when the vapour of ethyl chloride is passed through a red-hot tube, it gives olefiant gas and hydrochloric acid. It is also produced by the ignition of certain metallic chlorides in a stream of hydrogen, especially of those metals which are easily reduced and difficultly oxidised—for instance, silver chloride. Lead chloride, when heated to redness in a stream of steam, gives hydrochloric acid and lead oxide. In general $2\text{MCl}_n + n\text{H}_2\text{O}$ frequently gives $\text{M}_2\text{O}_n + 2n\text{HCl}$, and $\text{MCl}_n + \text{H}_n$ sometimes $\text{M} + n\text{HCl}$, although both these reactions also proceed in the opposite direction, that is, $\text{M}_2\text{O}_n + n2\text{HCl}$ frequently forms $2\text{MCl}_n + n\text{H}_2\text{O}$ and sometimes $\text{M} + n\text{HCl} = \text{MCl}_n + \text{H}_n$, where M is a metal. The multitude of the cases of formation of hydrochloric acid are understood from the fact that it is a substance which is comparatively very stable, resembling water in this respect, and even most probably more stable than water, because, at a high temperature and even under the action of light, chlorine decom-




FIG. 66.—Coke tower.

frequently formed in other reactions, many of which we shall meet with in the further course of this work. It is, for instance, formed by the action of water on sulphur chloride, phosphorus chloride, antimony chloride, &c.

Hydrochloric acid is a colourless gas having a pungent suffocating odour and an acid taste. This gas fumes in air and attracts moisture, because it forms vapour containing a compound of hydrochloric acid and water. Hydrochloric acid is liquefied by cold, and under a pressure of 40 atmospheres into a colourless liquid of sp. gr. 0.908 at 0°, ³⁴ boiling point -35° and absolute boiling point +52. We have already seen (Chap. I.) that hydrochloric acid combines very energetically *with water*, and in so doing evolves a considerable amount of heat. The solution saturated in the cold attains a density 1.23. On heating such a solution containing about 45 parts of acid per 100 parts, the hydrochloric acid gas is expelled with only a slight admixture of aqueous vapour. But it is impossible to entirely separate the whole of the hydrochloric acid from the water by this means, as could be done in the case of an ammoniacal solution. The temperature required for the evolution of the gas rises and reaches 110°-111°, and after this remains constant—that is, a solution having a constant boiling point is obtained (p. 98), which, however, does not (Roscoe and Dittmar) present a constant composition under different pressures, because the hydrate is decomposed in distillation, as is seen from the determinations of its vapour density (Bineau). Judging from the facts (1) that with decrease of the pressure under which the distillation proceeds the solution of constant boiling point approaches to a composition of 25 p.c. of hydrochloric acid, ³⁵ (2) that by passing a stream of dry air through a solution of hydrochloric acid there is obtained in the residue a solution which also approaches to 25 p.c. of acid, more nearly as the temperature falls, ³⁶ (3) that many of the properties of solutions of hydrochloric acid vary distinctly according as they contain more or less than 25 p.c. of hydrochloric acid (for instance, antimonious sulphide gives hydrogen sulphide with a stronger acid, but is not acted on by a weaker solution, also a stronger solution fumes in the air, &c.), and (4) that the composition $\text{HCl}, 6\text{H}_2\text{O}$ corresponds with 25.26 p.c.

poses water, with the formation of hydrochloric acid. The combination of chlorine and hydrogen also proceeds by their direct action, as we shall afterwards describe.

³⁴ According to Ansdell (1880) the sp. gr. of liquid hydrochloric acid at 0° = 0.908, at 11.67° = 0.854, at 22.7° = 0.808, at 33° = 0.748. Hence it is seen that the expansion of this liquid is greater than that of gases (Chapter II. Note 34).

³⁵ According to Roscoe and Dittmar at a pressure of three atmospheres the solution of constant boiling point contains 18 p.c. of hydrogen chloride, and at a pressure of one-tenth atmosphere 23 p.c. The percentage is intermediate at medium pressures.

³⁶ At 0° 25 p.c., at 100° 20.7 p.c.; Roscoe and Dittmar.

HCl—judging from all these data, and also from the loss of tension which occurs in the combination of hydrochloric acid with water, it may be said that they form a *definite hydrate* of the composition $\text{HCl}, 6\text{H}_2\text{O}$. The conclusions to be drawn from the densities of solutions of hydrochloric acid also point to the same fact, as will presently be explained. Besides this hydrate there exists also a crystallo-hydrate $\text{HCl}, 2\text{H}_2\text{O}$,³⁷ which is formed by the absorption of hydrochloric acid by a saturated solution at a temperature of -23° . It crystallises and melts at -18° .³⁸

³⁷ This crystallo-hydrate (obtained by Pierre and Puchot, and investigated by Roozeboom) is analogous to $\text{NaCl}, 2\text{H}_2\text{O}$. The crystals $\text{HCl}, 2\text{H}_2\text{O}$ at -22° have a specific gravity 1.46, the vapour tension (dissociation) of the solution having a composition $\text{HCl}, 2\text{H}_2\text{O}$ at $-24^\circ=760$, at $-19^\circ=1010$, at $-18^\circ=1057$, at $-17^\circ=1112$ mm. of mercury. In a solid state the crystallo-hydrate at -17.7° has the same tension, whilst at lower temperatures it is much less: at -24° about 150, at -19° about 580 mm., at -17.2° about 10 atmospheres; at -13° about 150 atmospheres. A mixture of fuming hydrochloric acid with snow reduces the temperature to -38° .

³⁸ According to Roscoe at 0° a *hundred* grams of water at a pressure p (in millimetres of mercury) dissolves—

	$p = 100$	200	300	500	700	1000
Grams HCl	65.7	70.7	73.8	78.2	81.7	85.6

At a pressure of 760 millimetres and temperature t , a *hundred* grams of water dissolves

	$t = 0$	8°	16°	24°	40°	60°
Grams HCl	82.5	78.3	74.2	70.0	63.3	56.1

Roozeboom (1886) showed that at t° solutions containing c grams of hydrogen chloride per 100 grams of water may (with the variation of the pressure p) be formed together with the crystallo-hydrate $\text{HCl}, 2\text{H}_2\text{O}$:

$t =$	-28.8°	-21°	-19°	-18°	$+17.7^\circ$
$c =$	84.2	86.8	92.6	98.4	101.4
$p =$	—	334	580	900	1073 mm.

The last composition answers to the melted crystallo-hydrate $\text{HCl}, 2\text{H}_2\text{O}$, which splits up at temperatures above -17.7° , and at a constant atmospheric pressure when there are no crystals—

$t =$	-24°	-21°	-18°	-10°	0
$c =$	101.2	98.3	95.7	89.8	84.2

From these data it is seen that the hydrate $\text{HCl}, 2\text{H}_2\text{O}$ can exist in a liquid state, which is not the case for the hydrates of carbonic and sulphurous anhydrides, chlorine, &c.

According to Marignac, the specific heat c of a solution $\text{HCl} + m\text{H}_2\text{O}$ (at about 30° , taking the specific heat of water = 1) is given by the expression—

$$C(36.5 + m18) = 18m - 28.39 + 140/m - 268/m^2$$

if m be not less than 6.25. For example, for $\text{HCl} + 25\text{H}_2\text{O}$ $C = 0.877$.

According to Thomsen's data, the amount of heat Q , expressed in thousands of calories, evolved in the solution of 36.5 grams of gaseous hydrochloric acid in $m\text{H}_2\text{O}$ or 18*m* grams of water—

$m =$	2	4	10	50	400
$Q =$	11.4	14.3	16.2	17.1	17.3

In these quantities the latent heat of liquefaction is included, which, judging by analogy (page 321), must be taken as 5–9 thousand calories per molecular quantity of hydrogen chloride.

The researches of Scheffer (1888) on the rate of diffusion (in water) of solutions of

The mean (from the observations of Ure, Kremers, Kolbe, Berthelot, Marignac, and Kohlrausch) specific gravities at 15°, taking water at its maximum density (4°) as 10000, for solutions containing p per cent. of hydrogen chloride, are given in the following table in the columns under the symbol s . Their possible error is not less than ± 2 , and is scarcely greater than ± 10 .

p	s	S	p	s	S
5	10242	10240	25	11266	11263
10	10490	10492	30	11522	11522
15	10744	10746	35	11773	11770
20	11001	11003	40	11997	12005

Under the letter S in the third column is given the specific gravity calculated according to the formula $S = 9991.6 + 49.43p + 0.0571p^2$, until $p = 25.26$, which answers to the hydrate $\text{HCl}, 6\text{H}_2\text{O}$ mentioned above. Above this percentage $S = 9785.1 + 65.10p - 0.240p^2$. A comparison of the results obtained by experiment and calculation (s with S) shows that the curve is in perfect harmony with the mean result of observation. The necessity of two curves is already indicated by the fact that the rise of specific gravity with an increase of percentage (or the differential $\frac{ds}{dp}$) reaches a maximum at about 25 p.c.³⁹ Thus between 0 and 10 p.c. the mean difference of s , corresponding with 1 p.c. = 49.8, between 20 and 30 p.c. = 52.1, and between 30 and 40 p.c. = 47.5, judging from the results of experiment. The intermediate solution, $\text{HCl}, 6\text{H}_2\text{O}$, is further distinguished by the fact that the variation of the specific gravity with the variation of temperature is a constant quantity, so that the specific gravity of this solution is equal to 11352.7 ($1 - 0.000447t$), where 0.000447 is the modulus of expansion of the solution.⁴⁰ In the case of more dilute solutions, as with

hydrochloric acid show that the coefficient of diffusion k decreases with the amount of water n , if the composition of the solution is $\text{HCl}, n\text{H}_2\text{O}$ at 0°:—

$n =$	5	6.9	9.8	14	27.1	129.5
$k =$	2.31	2.08	1.86	1.67	1.52	1.39

It also appears that strong solutions diffuse more rapidly into dilute solutions than into water.

³⁹ If it be admitted that the maximum of the differential corresponds with $\text{HCl}, 6\text{H}_2\text{O}$, then it might be thought that the specific gravity is expressed by a parabola of the third order; but such an admission does not give expressions in accordance with reality, either in this or especially in those cases (solutions of alcohol and sulphuric acid) where the data for the specific gravities are established with great accuracy, as is more fully considered in my work mentioned on page 65.

⁴⁰ As in water, the modulus of expansion (or the quantity k in the expression $S_t = S_0 - kS_0t$, or $V_t = 1/(1 - kt)$, and if the variation of the specific gravity be non-

water, the specific gravity at 1° (or the differential $\frac{ds}{dt}$) rises with a rise of temperature, for the difference between $S_0 - S_{15}$ and $S_{15} - S_{30}$ (i.e. the difference between the specific gravities at 0° , 15° , and 30°) varies as follows :⁴¹

$p =$	0	5	10	15	20
$S_0 - S_{15} =$	7.1	23	38	52	64
$S_{15} - S_{30} =$	33.9	42	50	59	67

Whilst for solutions which contain a greater proportion of hydrogen chloride than $\text{HCl}, 6\text{H}_2\text{O}$, these coefficients *decrease* with a rise of temperature : for instance, for 30 p.c. of hydrogen chloride $S_0 - S_{15} = 88$ and $S_{15} - S_{30} = 87$ (according to Marignac's data). In the case of $\text{HCl}, 6\text{H}_2\text{O}$ these differences are constant, and equal 76.

Thus the formation of two definite hydrates, $\text{HCl}, 2\text{H}_2\text{O}$ and $\text{HCl}, 6\text{H}_2\text{O}$, between hydrochloric acid and water may be accepted upon the basis of many facts. But both of them, inasmuch as they occur in a liquid state, dissociate with great facility into hydrogen chloride and water, and are completely decomposed when distilled.

All solutions of hydrochloric acid present the properties of an energetic acid. They not only transform blue vegetable colouring-matter into red, and disengage carbonic acid gas from carbonates, &c., but they also entirely saturate bases, even such energetic ones as pot-

uniform, then the modulus of expansion must be taken as $-ds/dtS_0$) attains a magnitude 0.000447 at about 48° , it might be thought that at 48° all solutions of hydrochloric acid would have the same modulus of expansion, but in reality this is not the case. At low and the ordinary temperatures the modulus of expansion of aqueous solutions is greater than that of water, and the greater it is the greater the amount of the substance dissolved (for this reason the temperature of maximum density, when the modulus = 0, is lowered by solution). But for water the modulus of expansion ($-ds/dtS_0$) rises rapidly with the temperature, whilst for solutions the increase is much slower (or even falls, as for sulphuric acid or fuming hydrochloric acid), and therefore at a certain temperature t the modulus of solutions becomes equal to that of water. This temperature may be termed the 'characteristic temperature.' For solutions of sodium chloride it is about 58° , for lithium chloride 30° , for potassium nitrate about 80° , for weak solutions of sulphuric acid about 68° . In order to illustrate this by an example I will insert the magnitudes of denomination of expansion (multiplied by 10000) of solutions of sodium chloride :—

	0°	20°	50°	60°	80°	100°
Water	-065	2.07	3.64	5.11	6.25	7.09
10 p.c. NaCl . .	2.3	3.4	4.3	5.0	5.7	6.3
20 p.c.	3.6	4.0	4.5	5.0	5.4	5.8

⁴¹ The figures cited above may serve for the direct determination of the variation of the specific gravity of solutions of hydrochloric acid with the temperature, because we may take $S_t = S_0 - t(A - Bt)$. Thus, knowing that at 15° the specific gravity of a 10 p.c. solution of hydrochloric acid = 10492, we find that at t° it = $10530 - t(2.13 + 0.027t)$. Whence also may be found the modulus of expansion (Note 40).

ash, lime, &c. In a dry state, however, hydrochloric acid does not alter vegetable dyes, and does not accomplish many double decompositions which easily take place in the presence of water. This is explained by the fact that the gaso-elastic state of the hydrochloric acid prevents its entering into reaction. However, incandescent iron, zinc, sodium, &c., act on gaseous hydrochloric acid, displacing the hydrogen and leaving half a volume of hydrogen against one volume of hydrochloric acid gas; this reaction may serve for determining the composition of hydrochloric acid. Combined with water the hydrochloric acid gas is deprived of its elasticity, and loses a considerable amount of heat in its passage into a liquid and combined state. It then acts as an acid which much resembles nitric acid⁴² in its energy and in many of its reactions; however, the latter contains oxygen, which is disengaged with great ease, and so very frequently acts as an oxidiser, which hydrochloric is not capable of doing. The majority of metals (even those which do not displace the H from H_2SO_4 but which, like copper, decompose it to the limit of SO_2) displace the hydrogen from hydrochloric acid. Thus hydrogen is disengaged by the action of zinc, and even of copper and tin. Only a few metals withstand its action; for example, gold and platinum. Lead is only acted on feebly in compact masses, because the lead chloride formed is insoluble and prevents the further action of the acid on the metal. The same is to be remarked with respect to the feeble action of hydrochloric acid on mercury and silver, because the compounds of these metals, AgCl and HgCl , are insoluble in water. Metallic chlorides are not only formed by the action of hydrochloric acid on the metals, but also by many other methods; for instance, by the action of hydrochloric acid on the carbonates, oxides, and hydroxides, and also by the action of chlorine on metals and certain of their compounds. Metallic chlorides have a composition MCl ; for example, NaCl , KCl , AgCl , HgCl , if the metal replaces hydrogen equivalent for equivalent, or, as it is said, if it be monatomic or univalent. In the case of bivalent metals, they have a composition MCl_2 ; for example, CaCl_2 , CuCl_2 , PbCl_2 , HgCl_2 , FeCl_2 , MnCl_2 . The composition of the haloid salts of other metals presents a further variation; for example, AlCl_3 , Fe_2Cl_6 , PtCl_4 , &c. Many metals, as will have been remarked in the preceding examples, give several degrees of combination with chlorine, as with hydrogen. In their composition the metallic chlorides differ

⁴² Thus, for instance, with feeble bases they evolve in dilute solutions (Chapter III. Note 53) almost equal amounts of heat; their relation to sulphuric acid is quite identical. They both form fuming solutions as well as hydrates; they both form solutions of constant boiling point; in the solutions of both (with $\text{HCl}, 6\text{H}_2\text{O}$ and with $\text{NH}_3, 5\text{H}_2\text{O}$) the direction of the differential ds/dp varies, &c.

from the corresponding oxides in that the O is replaced by Cl_2 , as should follow from the law of substitution, because oxygen gives OH_2 and is consequently bivalent, whilst chlorine forms HCl , and is therefore univalent. So, for instance, ferrous oxide, FeO , corresponds with ferrous chloride, FeCl_2 , and the oxide Fe_2O_3 with ferric chloride, which is also seen from the origin of these compounds, because FeCl_2 is obtained by the action of hydrochloric acid on ferrous oxide or carbonate and FeCl_3 by its action on ferric oxide. The action of hydrochloric acid, like that of every acid, on basic oxides, MO , and in general on M_nO_m , consists in a double decomposition, water, $m\text{H}_2\text{O}$, and a metallic chloride, M_nCl_{2m} , being formed. Hydrochloric acid, HCl , acts in the same manner on the hydroxides of the bases $\text{M}_n(\text{OH})_{2m} + 2m\text{HCl} = 2m\text{H}_2\text{O} + \text{M}_n\text{Cl}_{2m}$, and on carbonates, for instance, $\text{Na}_2\text{CO}_3 + 2\text{HCl} = 2\text{NaCl} + \text{H}_2\text{O} + \text{CO}_2$. In a word, all the typical properties of acids are shown by hydrochloric acid, and all the typical properties of salts in the metallic chlorides derived from it. Acids and salts composed like HCl and M_nCl_{2m} without any oxygen bear the name of *haloid* salts; for instance, HCl is a haloid acid, NaCl a haloid salt, chlorine a halogen. Certain higher degrees of combination of chlorine with the metals disengage chlorine when heated to redness; for instance, the salt CuCl_2 is converted into CuCl . The capacity of hydrochloric acid to give, by its action on bases, MO , a metallic chloride, MCl_2 , and water, is limited at high temperatures by the reverse reaction $\text{MCl}_2 + \text{H}_2\text{O} = \text{MO} + 2\text{HCl}$, and the more pronounced are the basic properties of MO the feebler is the reverse reaction, while for feebler bases such as Al_2O_3 , MgO , &c., this reverse reaction proceeds with ease. In this manner Deville obtained crystals of the amorphous oxides Fe_2O_3 , SnO_2 , &c., by passing a slow current of hydrogen chloride over them at a red heat; Fe_2Cl_6 and SnCl_4 were momentarily formed, but were again decomposed by the water liberated and the liberated oxides were separated as crystals. Metallic chlorides corresponding with the peroxides either do not exist, or are easily decomposed with the disengagement of chlorine. Thus there is no compound BaCl_4 corresponding with the oxide BaO_2 . Metallic chlorides having the general aspect of salts, like their representative sodium chloride, are, as a rule, easily fusible, more so than the oxides (for instance, CaO is infusible whilst CaCl_2 is easily fused), and many other salts. Under the action of heat many are more stable than the oxides, many are even converted into vapour; thus corrosive sublimate, HgCl_2 , is particularly volatile, whilst the oxide HgO decomposes at a red heat. Silver chloride, AgCl , is fusible and is decomposed with difficulty, whilst Ag_2O is easily decomposed. The majority of the metallic chlorides are soluble in

water, but silver chloride, cuprous chloride, mercurous chloride, and lead chloride are sparingly soluble in water, and are therefore easily obtained as precipitates when a solution of the salts of these metals is mixed with a solution of any chloride or even with hydrochloric acid. The metal contained in a haloid salt may often be replaced by another metal, or even by hydrogen, just as is the case with a metal in an oxide. Thus copper displaces mercury from a solution of mercuric chloride, $\text{HgCl}_2 + \text{Cu} = \text{CuCl}_2 + \text{Hg}$; thus hydrogen at a red heat displaces silver from silver chloride, $2\text{AgCl} + \text{H}_2 = \text{Ag}_2 + 2\text{HCl}$. These, and a whole series of similar reactions, form the typical methods of double saline decompositions. The measure of decomposition and the conditions under which one or the other side of reactions of double saline decompositions proceeds (for instance, whether a metal and an acid give hydrogen and a salt or the reverse) are determined by the properties of the compounds which are in action, and which are able to be formed at the temperature, &c., as was shown when speaking of sodium chloride, and as will be frequently found hereafter.

If hydrochloric acid enters into double decomposition with basic oxides and their hydrates, this is only due to its acid properties; and for the same reason it rarely enters into double decomposition with acids and acid anhydrides. Sometimes, however, it combines with the latter, as, for instance, with the anhydride of sulphuric acid, forming the compound SO_3HCl ; and in other cases it acts on acids, giving up its hydrogen to their oxygen and forming chlorine, as will be seen in the following chapter.

Hydrochloric acid, as may already be concluded from the composition of its molecule, belongs to the monobasic acids, and does not, therefore, give true acid salts (like HNaSO_4 or HNaCO_3); nevertheless many metallic chlorides, formed from powerful bases, are capable of *combining with hydrochloric acid*, just as they combine with water, or with ammonia, and as they give double salts. Compounds have long been known of hydrochloric acid with auric, platinic, and antimonious chlorides, and other similar metallic chlorides corresponding with very feeble bases. But Berthelot, Engel, and others have shown that the capacity of HCl for combining with M_nCl_m is much more frequently encountered than was before supposed. Thus, for instance, dry hydrochloric acid when passed into a solution of zinc chloride (containing an excess of the salt) gives in the cold (0°) a compound $\text{HCl}, \text{ZnCl}_2, 2\text{H}_2\text{O}$, and at the ordinary temperature $\text{HCl}, 2\text{ZnCl}_2, 2\text{H}_2\text{O}$, just as it is able at low temperatures to form the crystallo-hydrate $\text{ZnCl}_2, 3\text{H}_2\text{O}$ (Engel, 1886). Similar compounds are obtained with CdCl_2 , CuCl_2 , HgCl_2 , Fe_2Cl_6 , &c. (Berthelot, Ditte, Cheltzoff, Lachinoff,

and others). These compounds with hydrochloric acid are generally more soluble in water than the metallic chlorides themselves, so that whilst hydrochloric acid decreases the solubility of MCl_m , corresponding with energetic bases (for instance, sodium or barium chlorides), it increases the solubility of the metallic chlorides corresponding with feeble bases (cadmium chloride, ferric chloride, &c.). Silver chloride, which is insoluble in water, is soluble in hydrochloric acid. Hydrochloric acid also combines with certain unsaturated hydrocarbons (for instance with turpentine, $C_{10}H_{16}2HCl$) and their derivatives. *Sal-ammoniac*, or ammonia hydrochloride, $NH_4Cl = NH_3, HCl$, also belongs to this class of compounds.⁴³ If dry hydrogen chloride be mixed with dry ammonia, a solid compound formed from equal volumes of each is immediately formed. The same compound is formed on mixing solutions of the two gases. It is also produced by the action of hydrochloric acid on ammonium carbonate. *Sal-ammoniac* is usually prepared by the last method in practice.⁴⁴ The specific gravity of *sal-ammoniac* is 1.55. We have already seen (p. 253) that *sal-ammoniac*,

⁴³ When an unsaturated hydrocarbon, or, in general, an unsaturated compound, assimilates to itself the molecules Cl_2 , HCl , SO_2 , H_2SO_4 , &c., the cause of the reaction is most simple. As nitrogen, besides the type NX_3 to which NH_3 belongs, forms compounds of the form NX_5 —for example, $NO_2(OH)$ —therefore the formation of the salts of ammonium should be understood in this sense. NH_3 gives NH_4Cl because NX_5 is capable of giving NX_3 . But as saturated compounds—for instance, HCl , H_2O , $NaCl$, &c.—are also capable of combination even between themselves, therefore it is impossible to deny the capacity of HCl also for combination. SO_2 combines with H_2O , and also with HCl and the unsaturated hydrocarbons. It is impossible to see the limit here, which it was lately wished to establish, by distinguishing atomic from molecular compounds, and regarding, for instance, PCl_5 as an atomic compound and PCl_3 as a molecular one, only because it easily splits up into molecules PCl_5 and Cl_2 .

⁴⁴ *Sal-ammoniac* is prepared from ammonium carbonate, obtained in the dry distillation of nitrogenous substances (Chapter VI.), by saturating the resultant solution with hydrochloric acid. A solution of *sal-ammoniac* is thus produced, it is evaporated, and in the residue a mass is obtained containing a mixture of various other, especially tarry, products of dry distillation. The *sal-ammoniac* is generally purified by sublimation. For this purpose iron vessels covered with semispherical metallic covers are employed, or else simply clay crucibles covered by other crucibles. The upper portion, or helmet, of the apparatus of this kind will have a lower temperature than the lower portion, which is under the direct action of the flame. The *sal-ammoniac* volatilises when heated, and settles on the cooler portion of the apparatus. It is thus purified from many impurities, and is obtained as a crystalline crust, generally several centimetres thick, in which form it is generally sold.

In order to demonstrate the very instructive formation of solid *sal-ammoniac* from the gases $NH_3 + HCl$ we may proceed as follows: A thin glass tube is filled with ammonia and closed with a cork, and placed in a thick glass cylinder into which a rapid stream of hydrogen chloride is introduced and is then closed with a cork; the inside tube is then broken by violently shaking the apparatus. The ammonium chloride is obtained in white flakes. A glass rod, or paper moistened with hydrochloric acid, also gives a distinct cloud of *sal-ammoniac* when held over the mouth of a bottle containing a strong solution of ammonia.

like all other ammonium salts, easily decomposes; for instance, by volatilisation with alkalis, and even partially when its solution is boiled. But at higher temperatures ammonia decomposes with the liberation of hydrogen, and therefore ammonia is then able to act as a reducing agent—as, for example, on metallic oxides. The other properties and reactions of sal-ammoniac, especially in solution, fully bring to mind what has been already mentioned in speaking of sodium chloride. Thus, for instance, with silver nitrate it gives a precipitate of silver chloride; with sulphuric acid it gives hydrochloric acid and ammonium sulphate, and it forms double salts with certain metallic chlorides and other salts.⁴⁵

⁴⁵ The solubility of sal-ammoniac in 100 parts of water (according to Alluard) is—

0°	10°	20°	30°	40°	60°	80°	100°	110°
28.40	32.48	37.28	41.72	46	55	64	73	77

A saturated solution boils at 115.8°. The specific gravity at 15°/4° of solutions of sal-ammoniac (water 4°—10000) $= 9991.6 + 31.26p - 0.085p^2$, where p is the amount by weight of ammonium chloride in 100 parts of solution. With the majority of salts the differential ds/dp increases, but here it decreases with the increase of p . For (unlike the sodium and potassium salts) a solution of the alkali *plus* a solution of acid occupy a greater volume than that of the resultant ammonium salt. In the solution of *solid* ammonium chloride a contraction, and not expansion, generally takes place. It may further be remarked that solutions of sal-ammoniac have an acid reaction even when prepared from the salt remaining after prolonged washing of the sublimed salt with water (A. Stcherbakoff).

CHAPTER XI

THE HALOGENS : CHLORINE, BROMINE, IODINE, AND FLUORINE

ALTHOUGH hydrochloric acid, like water, is one of the most stable substances, it is nevertheless decomposed not only by the action of a galvanic current¹ but also by a rise of temperature. Sainte-Claire Deville showed that decomposition already occurs at 1300°, because a cold tube (p. 388) covered with an amalgam of silver absorbs chlorine in a red-hot tube, and the escaping gas contains hydrogen. Meyer and Langer (1885) observed the decomposition of hydrochloric acid at 1690° in a platinum vessel; the decomposition in this instance was proved not only from the fact that hydrogen permeated through the platinum (p. 141), owing to which the volume was diminished, but also from chlorine being obtained in the residue (the hydrogen chloride was mixed with nitrogen), which liberated iodine from potassium iodide.² The usual method for the preparation of chlorine consists in the abstraction of the hydrogen by oxidising agencies.

The acid properties of hydrochloric acid were known when Lavoisier pointed out the formation of acids by the combination of water with the oxides of the non-metals, and therefore there was reason for thinking that hydrochloric acid was formed by the combination of water with the oxide of some element. Therefore when Scheele obtained chlorine by the action of hydrochloric acid on manganese peroxide he considered it as the acid contained in common salt. When it became known that chlorine gives hydrochloric acid with hydrogen, Lavoisier and Berthollet supposed it to be a compound with oxygen of an anhydride contained in hydrochloric acid. They supposed that hydrochloric acid contained water and the oxide of a particular radicle

¹ The decomposition of fused sodium chloride by an electric current has been proposed in America and Russia (N. N. Beketoff) as a means for the preparation of chlorine and sodium. A strong solution of hydrochloric acid is decomposed into equal volumes of chlorine and hydrogen by the action of an electric current.

² To obtain so high a temperature (at which the best kinds of porcelain soften) Langer and Meyer employed the dense graphitoidal carbon from gas retorts, and a strong draught. They determined the temperature by the alteration of the volume of nitrogen in the platinum vessel, for it does not permeate through platinum, and is not altered by heat.

and that chlorine was a higher degree of oxidation of this radicle *murias* (from the Latin name of hydrochloric acid, *acidum muriaticum*). It was only in 1811 that Gay-Lussac and Thenard in France and Davy in England arrived at the conclusion that the substance obtained by Scheele does not contain oxygen, nor under any conditions give water with hydrogen, and that there is no water in hydrochloric acid gas, and therefore concluded that chlorine is an elementary substance. They named it 'chlorine' from the Greek word *χλωρός*, signifying a green colour, because of the peculiar colour by which this gas is characterised.

An aqueous solution of hydrochloric acid is generally employed for the evolution of chlorine. The hydrogen has to be abstracted from the hydrochloric acid. This is accomplished by nearly all oxidising substances, and especially by those which are able to evolve oxygen at a red heat (besides bases, such as mercury and silver oxides, which are able to give salts with hydrogen chloride); for example, manganese peroxide, potassium chlorate, chromic acid, &c. The decomposition essentially consists in the oxygen of the oxidising substance displacing the chlorine from 2HCl , forming water, H_2O , or taking up the hydrogen and setting the chlorine free, as is sometimes said, $2\text{HCl} + \text{O}$ (disengaged by the oxidising substances) $= \text{H}_2\text{O} + \text{Cl}_2$. Even nitric acid partially produces a like reaction, but as we shall afterwards see its action is more complicated, and it is therefore not suitable for the preparation of pure chlorine. But other oxidising substances which do not give any other volatile products with hydrochloric acid may be employed for the preparation of chlorine. Among these may be mentioned: potassium chlorate, acid potassium chromate, sodium manganate, manganese peroxide, &c. Manganese peroxide is commonly employed in the laboratory, and on a large scale, for the preparation of chlorine. The chemical process which proceeds in this case may be represented as follows: an exchange takes place between 4HCl and MnO_2 , in which the manganese takes the place of the four atoms of hydrogen, or the chlorine and oxygen exchange places— that is, MnCl_4 and $2\text{H}_2\text{O}$ are produced. The chlorine compound, MnCl_4 , obtained is very unstable; it splits up into chlorine, which as a gas passes from the sphere of action, and a lower compound containing less chlorine than the substance first formed, and which remains in the apparatus in which the mixture is heated, $\text{MnCl}_4 = \text{MnCl}_2 + \text{Cl}_2$.³ The action of hydro-

³ This representation of the process of the reaction is the most natural. However, this decomposition is generally represented as if chlorine gave only one degree of combination with manganese, MnCl_2 , and therefore directly reacts in the following manner— $\text{MnO}_2 + 4\text{HCl} = \text{MnCl}_2 + 2\text{H}_2\text{O} + \text{Cl}_2$, in which case it is, as it were, supposed that

chloric acid requires a temperature of about 100° . In the laboratory the *preparation of chlorine* is carried on in flasks, heated over a water bath, by acting on manganese peroxide with hydrochloric acid or a

manganese peroxide, MnO_2 , breaks up into manganous oxide, MnO , and oxygen, both of which react with hydrochloric acid, the manganous oxide acting as a base, $\text{MnO} + 2\text{HCl} = \text{MnCl}_2 + \text{H}_2\text{O}$, and at the same time $2\text{HCl} + \text{O} = \text{H}_2\text{O} + \text{Cl}_2$. In reality a mixture of oxygen and hydrochloric acid does give chlorine at a red heat, and this may also take place at the moment of its evolution in this case.

All the oxides of manganese (Mn_2O_3 , MnO_2 , MnO , Mn_2O_7), with the exception of manganous oxide, MnO , disengage chlorine from hydrochloric acid, because manganous chloride, MnCl_2 , is the only compound of chlorine and manganese which exists as a stable compound, all the higher chlorides of manganese being unstable and evolving chlorine. The reaction between hydrochloric acid and salts containing much oxygen is explained according to the law of substitution by the double decomposition and instability of the higher chlorides; thus, for example, by taking potassium dichromate, $\text{K}_2\text{Cr}_2\text{O}_7$, a compound, $\text{K}_2\text{Cr}_2\text{Cl}_{14}$, might be formed, but it is unknown, and if it is formed it in all probability immediately decomposes into chlorine, 6Cl , potassium chloride, 2KCl , and chromium chloride, Cr_2Cl_6 . Hence we here encounter two circumstances: (1) a substitution between oxygen and chlorine, and (2) the instability of those higher chlorine compounds. Both these circumstances have a very important signification for the comprehension of the relation of such elements as chlorine and oxygen. As (according to the law of substitution) in the substitution of oxygen by chlorine, Cl_2 takes the place of O , therefore the chlorine compounds will contain in themselves more atoms than the corresponding oxygen compounds. It is not surprising, therefore, that certain of the chlorine compounds corresponding with oxygen compounds do not exist, or if they are formed are very unstable. And furthermore, an atom of chlorine is heavier than an atom of oxygen, and therefore a given element would have to retain a large mass of chlorine if in the higher oxides the oxygen were replaced by chlorine. For this reason equivalent compounds of chlorine do not exist for all oxygen compounds. Many of the former are immediately decomposed, when formed, with the evolution of chlorine. Therefore chlorine is evolved by the action of hydrochloric acid on compounds which contain much oxygen. From this it is evident that there should exist such chlorine compounds as would evolve chlorine as peroxides evolve oxygen, and indeed a large number of such compounds are known. Amongst them may be mentioned antimony pentachloride, SbCl_5 , which splits up into chlorine and antimony trichloride when heated. Cupric chloride, corresponding with copper oxide, and having a composition CuCl_2 , similar to CuO , when heated parts with half its chlorine, just as barium peroxide evolves half its oxygen. This method may even be taken advantage of for the preparation of chlorine and cuprous chloride, CuCl . The latter attracts oxygen from the atmosphere, and in so doing is converted from a colourless substance into a green compound whose composition is $\text{Cu}_2\text{Cl}_2\text{O}$. With hydrochloric acid this substance gives cupric chloride ($\text{Cu}_2\text{Cl}_2\text{O} + 2\text{HCl} = \text{H}_2\text{O} + 2\text{CuCl}_2$), which has only to be dried and heated, and it again evolves chlorine. Thus, in solution, and at the ordinary temperature, the compound CuCl_2 is constant, but when heated it splits up. On this property is founded Deacon's process for the preparation of chlorine from hydrochloric acid by the aid of air and copper salts, by passing a mixture of air and hydrochloric acid at about 440° over bricks soaked with a solution of a copper salt (a mixture of solutions of CuSO_4 and Na_2SO_4). CuCl_2 is then formed by the double decomposition of the salt of copper and the hydrochloric acid; the CuCl_2 liberates chlorine, and the CuCl forms $\text{Cu}_2\text{Cl}_2\text{O}$ with the oxygen of the air, which again gives CuCl_2 with 2HCl , and so on.

Magnesium chloride, which is obtained from sea-water, carnallite, &c., may serve not only as a means for the preparation of hydrochloric acid, but also of chlorine, because (Weldon-Pechiny's process) its basic salt (magnesium oxychloride) when heated in the air gives magnesium oxide and chlorine. Chlorine is now prepared on a large scale by this method.

mixture of common salt and sulphuric acid⁴ and washing the gas with water to remove hydrochloric acid. The action of hydrochloric acid on bleaching powder (p. 161) gives chlorine without the aid of heat: $\text{CaCl}_2\text{O}_2 + 4\text{HCl} = \text{CaCl}_2 + 2\text{H}_2\text{O} + 2\text{Cl}_2$, and is therefore also taken advantage of in the laboratory for the preparation of chlorine.⁵ Chlorine cannot be collected over mercury, because it combines with it as with many other metals, and it is soluble in water; however, it is but slightly soluble in hot water or brine. Owing to its great weight, chlorine may be directly collected in a dry vessel by introducing the gas-conducting tube into the bottom of the vessel. The chlorine will lie in a heavy layer at the bottom of the vessel, displace the air, and the extent to which it fills the vessel may be followed by its colour.⁶

⁴ The following proportions are then taken by weight: 3 parts of powdered manganese peroxide, 4 parts of salt (best fused, to prevent its frothing), and 9 parts of sulphuric acid previously mixed with 5 parts of water. It is heated in a salt bath, so as to obtain a temperature above 100° . The corks in the apparatus must be soaked in paraffin (otherwise they are corroded by the chlorine), and black india-rubber tubing must be taken, and not vulcanised (which contains sulphur, and becomes brittle under the action of the chlorine).

The reaction which proceeds may be expressed thus: $\text{MnO}_2 + 2\text{NaCl} + 2\text{H}_2\text{SO}_4 = \text{MnSO}_4 + \text{Na}_2\text{SO}_4 + 2\text{H}_2\text{O} + \text{Cl}_2$. The preparation of Cl_2 from manganese peroxide and hydrochloric acid was discovered by Scheele, and from sodium chloride by Berthollet.

⁵ The reaction of hydrochloric acid on bleaching powder is very violent if all the acid be added at once; it should be poured in drop by drop (Mermé, Kammerer). C. Winkler proposed mixing bleaching powder with one quarter of burnt and powdered gypsum, and having damped the mixture with water, to press and cut it up into cubes and dry at the ordinary temperature. These cubes can be used for the preparation of chlorine in the same apparatus as that used for the evolution of hydrogen and carbonic anhydride—the disengagement of the chlorine proceeds uniformly.

A mixture of potassium dichromate and hydrochloric acid evolves chlorine perfectly free from oxygen (V. Meyer and Langer).

⁶ Chlorine is manufactured on a *large scale* from manganese peroxide and hydrochloric acid. It is most conveniently prepared in the arrangement shown in fig. 67, which consists of a three-necked earthenware vessel whose central orifice




FIG. 67.—Clay retort for the preparation of chlorine on a large scale.

is the largest. A clay or lead funnel, furnished with a number of orifices, is placed in the central wide neck of the vessel. Roughly-ground lumps of natural manganese peroxide are placed in the funnel, which is then closed by the cover N, and luted with clay. One orifice is closed by a clay stopper, and is used for the introduction of the hydrochloric acid and withdrawal of the residues. The chlorine disengaged passes along a leaden gas-conducting tube placed in the other orifice. A row of these vessels is surrounded by a water-bath, to ensure their being uniformly heated. Manganese chloride is found in the residue. In Weldon's process lime is added to the acid solution of manganese chloride. A double decomposition takes place, resulting

in the formation of manganous hydroxide and calcium chloride. When the insoluble manganous hydroxide has settled, a further excess of milk of lime is added (to make a mixture $2\text{Mn}(\text{OH})_2 + \text{CaO} + x\text{CaCl}_2$, which is found to be the best proportion, judging from experiment), and then air is forced through the mixture. The hydroxide is then converted from a colourless to a brown substance, containing peroxide, MnO_2 , and oxide of manganese, Mn_2O_3 . This is due to the manganous oxide absorbing oxygen from the

Chlorine is a *gas* of a yellowish green colour, and has a very suffocating and characteristic odour. On lowering the temperature to -50° or increasing the pressure to six atmospheres (at 0°) chlorine condenses⁷ into a liquid which has a yellowish green colour and a density of 1.3, and boils at -34° . The density and atomic weight of chlorine is 35.5 times greater than that of hydrogen, hence the molecule contains Cl_2 .⁸ At 0° one volume of water dissolves about $1\frac{1}{2}$ volumes of chlorine, at 10° about three volumes, at 50° again $1\frac{1}{2}$ volumes.⁹ Such a solution of chlorine is termed 'chlorine water'; and is employed in a diluted form in medicine and laboratory practice. It is prepared

air. Under the action of hydrochloric acid this mixture evolves chlorine, because of all the compounds of chlorine and manganese the chloride MnCl_2 is the only one which is stable (*see* Note 3). Thus one and the same mass of manganese may be repeatedly used for the preparation of chlorine. The same result is attained in other ways. If manganoous oxide be subjected to the action of oxides of nitrogen and air (Coleman's process), then manganese nitrate is formed, which at a red heat gives oxides of nitrogen (which are again used in the process) and manganese peroxide, which is thus renewed for the fresh evolution of chlorine.

⁷ Davy and Faraday liquefied chlorine in 1823 by heating the crystallo-hydrate $\text{Cl}_2\cdot 8\text{H}_2\text{O}$ in a bent tube (like that shown in fig. 45, p. 248), in warm water, while the other end of the tube was immersed in a freezing mixture. Meselan condensed chlorine in freshly-burnt charcoal (placed in a glass tube), which when cold absorbs an equal weight of chlorine. The tube was then fused up, the bent end cooled, and the charcoal heated, by which means the chlorine was expelled from the charcoal, and the pressure increased.

⁸ Judging from Ludwig's observations (1868), and from the fact that the coefficient of expansion of gases increases with their molecular weight (Chapter II. Note 26, for hydrogen = 0.367, carbonic anhydride = 0.373, hydrogen bromide = 0.386), it might be expected that the expansion of chlorine would be greater than that of air or of the gases composing it. V. Meyer and Langer (1885) having remarked that at 1400° the density of chlorine (taking its expansion as equal to that of nitrogen) = 29, consider that the molecules of chlorine split up and partially give molecules Cl , but it might be thought that the decrease in density observed only depends on the increase of the coefficient of expansion.

⁹ Investigations on the solubility of chlorine in water (the solutions evolve all their chlorine on boiling and passing air through them) show many different peculiarities. First Gay-Lussac, and then Pelouze, determined that the solubility increases between 0° and 8° to 10° (from $1\frac{1}{2}$ to 2 vols. of chlorine per 100 vols. of water at 0° to 3 to $2\frac{3}{4}$ at 10°). In the following note we shall see that this is not due to the breaking-up of the hydrate at about 8° to 10° , but to its formation below 9° . Roscoe observed an increase in the solubility of chlorine in the presence of hydrogen—even in the dark. Berthelot determined an increase of solubility with the progress of time. Schönebein and others suppose that chlorine acts on water, forming hypochlorous and hydrochloric acids ($\text{HClO} + \text{HCl}$).

The equilibrium between chlorine, steam as a gas, between water, liquid chlorine, ice, and the solid crystallo-hydrate of chlorine is evidently very complex. Guldberg (1870) gave a theory for similar states of equilibrium, which was afterwards developed by Roozeboom (1887), but it would be inopportune here to enter into its details. It will be enough in the first place to mention, that there is now no doubt (according to the theory of heat, and the direct observations of Ramsay and Young) that the vapour tension at one and the same temperature are different for the liquid and solid states of substances; secondly, to call attention to the following note; and, thirdly, to state that, in the presence of the crystallo-hydrate, water between 0.24° and $+28.7^{\circ}$ (when the hydrate and a solution may occur simultaneously) dissolves a different amount of chlorine than it does in the absence of the crystallo-hydrate.

by passing chlorine through a series of Woulfe's bottles, or into an inverted retort filled with water. Under the action of light, chlorine water gives oxygen and hydrochloric acid. At 0° a saturated solution of chlorine yields a crystallo-hydrate, $\text{Cl}_2 \cdot 8\text{H}_2\text{O}$, which easily splits up into chlorine and water when heated, so that if it be fused up in a tube and heated to 35° two layers of liquids are formed—a lower stratum of chlorine containing a small quantity of water, and an upper stratum of water containing a small quantity of chlorine.¹⁰

Chlorine explodes *with hydrogen*, if a mixture of equal volumes be exposed to the direct action of the sun's rays¹¹ or brought into contact with spongy platinum, or a strongly-heated substance, or subjected to the action of an electric spark. The explosion in this case takes place

¹⁰ According to Faraday's data the hydrate of chlorine contains $\text{Cl}_2 \cdot 10\text{H}_2\text{O}$, but Roozeboom (1885) showed that it is poorer in water = $\text{Cl}_2 \cdot 8\text{H}_2\text{O}$. At first small, almost colourless, crystals are obtained, but they gradually form (if the temperature be below their critical point 28.7° , above which they do not exist) large yellow crystals, like those of potassium chromate. The specific gravity is 1.23. The hydrate is formed if there be more chlorine in a solution than it is able to dissolve under the dissociation pressure corresponding with a given temperature. *In the presence of the hydrate* the percentage amount of chlorine at $0^{\circ}=0.5$, $9^{\circ}=0.9$, and at $20^{\circ}=1.82$. At temperatures below 9° the solubility (determined by Gay-Lussac and Pelouzé, *see* Note 9) is dependent on the formation of the hydrate; whilst at higher temperatures under the ordinary pressure the hydrate cannot be formed, and the solubility of chlorine falls, as it does for all gases (Chapter I.). If the crystallo-hydrate is not formed, then below 9° the solubility follows the same rule ($6^{\circ} 1.07$ p.c. Cl , $9^{\circ} 0.95$ p.c.). According to Roozeboom the chlorine evolved by the hydrate presents the following tensions of dissociation at $0^{\circ}=249$ mm., at $4^{\circ}=398$, at $8^{\circ}=620$, at $10^{\circ}=797$, at $14^{\circ}=1400$ mm. In this case a portion of the crystallo-hydrate remains solid. At 9.6 the tension of dissociation is equal to the atmospheric pressure. At a higher pressure the crystallo-hydrate may form at temperatures above 9° up to 28.7° , when the vapour tension of the hydrate equals the tension of the chlorine. It is evident that the equilibrium which is established is on the one hand a case of a complex heterogeneous system, and on the other hand a case of the solution of solid and gaseous substances in water.

The crystallo-hydrate or chlorine water must be kept in the dark, or the access of light be prevented by coloured glass, otherwise oxygen is evolved and hydrochloric acid formed.

¹¹ The chemical action of light on a mixture of chlorine and hydrogen was discovered by Gay-Lussac and Draper (1809). It has been investigated by many, and especially by Draper, Bunsen, and Roscoe. Electric or magnesium light, or the light emitted by the combustion of carbon bisulphide in nitric oxide, and in general that which forms photographic images, acts in the same manner as sunlight, according to the intensity. At temperatures below -12° light no longer brings about reaction, or at all events does not give an explosion. It was long supposed that chlorine that had been subjected to the action of light was afterwards able to act on hydrogen in the dark, but it was shown that this only takes place with moist chlorine, and depends on the formation of oxides of chlorine. The presence of foreign gases, and even of excess of chlorine or of hydrogen, very much enfeebles the explosion, and therefore the experiment is conducted with a detonating mixture prepared by the action of an electric current on a strong solution (sp. gr. 1.15) of hydrochloric acid, in which case the water is not decomposed—that is, no oxygen is mixed with the chlorine.

from exactly the same reasons—*i.e.* the evolution of heat and expansion of the resultant product—as in detonating gas (Chap. III.). Diffused light acts in the same way, but slowly, whilst the direct sunlight excites an explosion.¹² The hydrochloric acid gas produced by the reaction of chlorine on hydrogen occupies (at the same temperature and pressure) a volume equal to the sum of the original volumes; that is, a reaction of substitution here takes place: $\text{H}_2 + \text{Cl}_2 = 2\text{HCl}$, the atoms of chlorine and hydrogen change places—there were two molecules and two molecules are also obtained, although different molecules were first taken and like molecules are formed. In this reaction twenty-two thousand heat units are evolved for one part by weight of hydrogen.¹³

These relations show that the affinity of chlorine for hydrogen is very great and analogous to the affinity between hydrogen and oxygen.

¹² The quantity of chlorine and hydrogen which combine is proportional to the intensity of the light—not of all the rays, but only those so termed chemical (actinic) rays which produce chemical action. Hence a mixture of chlorine and hydrogen, when exposed to the action of light in vessels of known capacity and surface, may be employed as a means for estimating the intensity of the chemical rays (as an actinometer), the influence of the heat rays being previously destroyed, which may be done by passing the rays through water. Investigations of this kind (photo-chemical) showed that chemical action is chiefly limited to the violet end of the spectrum, and that even the invisible ultra-violet rays produce this action. A colourless gas flame contains no chemically-active rays, the flame coloured green by a salt of copper evinces more chemical action than the colourless flame, but the flame brightly coloured yellow by salts of sodium has no more chemical action than that of the colourless flame.

As the chemical action of light becomes evident in plants, photography, the bleaching of tissues, and the fading of colours in the sunlight, and as a means for studying the phenomenon is given in the reaction of chlorine on hydrogen, this subject has been the most fully investigated in *photo-chemistry*. The researches of Bunsen and Roscoe in the fifties and sixties are the most complete in this respect. Their actinometer contains hydrogen and chlorine, and is enclosed by a solution of chlorine in water. The hydrochloric acid is absorbed as it forms, and therefore the variation in volume indicates the progress of the combination. As was to be expected, the action of light proved to be proportional to the time of exposure and intensity of the light, so that it was possible to conduct detailed photometrical investigations respecting the time of day and season of the year, various sources of light, its absorption, &c. This subject is considered in detail in special works, and we only stop to mention one circumstance, that a small quantity of a foreign gas decreases the action of light; for example, $\frac{1}{330}$ of hydrogen by 38 p.c., $\frac{1}{200}$ of oxygen by 10 p.c., $\frac{1}{100}$ of chlorine by 60 p.c., &c. According to the researches of Klimenko and Pekatoros (1889), the photo-chemical alteration of chlorine water is retarded by the presence of traces of metallic chlorides, and this influence varies with different metals.

As much heat is evolved in the reaction of chlorine on hydrogen, and as this reaction, being exothermal, may proceed by itself, therefore the action of light is essentially the same as that of heat—that is, it brings the chlorine and hydrogen into the condition necessary for the reaction—it, as we may say, shakes the original equilibrium; this is the work done by the luminous energy. It seems to me that the action of light on the mixed gases should be understood in this sense, as Pringsheim (1877) pointed out.

¹³ In the formation of steam (from one part by weight of hydrogen) 29000 heat units are evolved. The following are the quantities of heat (thousands of units) evolved in

Thus ¹⁴ on the one hand by passing a mixture of steam and chlorine through a red-hot tube, or by exposing water and chlorine to the sunlight, oxygen is disengaged, whilst on the other hand, as we saw above, oxygen in many cases displaces chlorine from its compound with hydrogen, and therefore the reaction $\text{H}_2\text{O} + \text{Cl}_2 = 2\text{HCl} + \text{O}$ belongs to the number of reversible reactions, and hydrogen will distribute itself between oxygen and chlorine if it comes into contact with both these elements. These relations determine many of the properties of chlorine—that is, its relation to substances containing hydrogen and its reactions in the presence of water, to which we shall turn our attention after having pointed out the relation of chlorine to other elements.

Many *metals* when brought into contact with chlorine immediately combine with it, and form those metallic chlorides which correspond with hydrogen chloride and with the oxide of the metal taken. With a large surface of metal, and if it be slightly heated, this combination may proceed rapidly with the evolution of heat and light; that is, metals are able to burn in chlorine. Thus, for example, sodium ¹⁵ burns in chlorine, thus synthesising common salt. Metals in the form of powders burn without the aid of heat, and become highly incandescent in the process; for instance, antimony, which is a metal easily converted into a powder.¹⁶ Even such metals as gold and platinum,¹⁷

the formation of various other *corresponding* compounds of oxygen and of chlorine (from Thomsen's, and, for Na_2O , Beketoff's results):

{ 2NaCl , 195;	CaCl_2 , 170;	HgCl_2 , 63;	2AgCl , 59.
{ Na_2O , 100;	CaO , 181;	HgO , 42;	Ag_2O , 6.
{ 2AsCl_3 , 148;	2PCl_3 , 210;	CCl_4 , 21;	2HCl , 44 (gas).
{ As_2O_3 , 155;	P_2O_5 , 370;	CO_2 , 97;	H_2O , 58 (gas).

With the first four elements the formation of the chlorine compound gives the most heat, and with the four following the formation of the oxygen compound evolves the greater amount of heat. The first four chlorides are true salts formed from HCl and the oxide, whilst the remainder have other properties, as is seen from the fact that they are not formed from hydrochloric acid and the oxide, but give hydrochloric acid with water. If affinity be measured by heat, then in the former the affinity for chlorine is greater than that for oxygen, whilst in the latter it is the reverse. But as the physical states of the substances are different, and as chlorine displaces oxygen as well as oxygen displaces chlorine, the affinity cannot be determined from thermo-chemical data without a number of corrections which are still subject to doubt.

¹⁴ This has been already pointed out in Chap. III. Note 5.


¹⁵ Sodium remains unaltered in perfectly dry chlorine at the ordinary temperature, and even when slightly warmed; but the combination is exceedingly violent at a red heat.

¹⁶ An instructive experiment on combustion in chlorine may be conducted as follows: leaves of Dutch metal (used for gilding instead of gold) are placed in a glass globe, and a gas-conducting tube furnished with a glass cock is placed in the cork closing it, and the air is pumped out of the globe. The gas-conducting tube is then connected with a vessel containing chlorine, and the cock opened; the chlorine rushes in, and the metallic leaves are consumed.

¹⁷ The behaviour of platinum to chlorine at a high temperature (1400°) is very

which do not combine directly with oxygen and give very unstable compounds with it, unite directly with chlorine to form metallic chlorides. Either chlorine water or aqua regia may be employed for this purpose instead of gaseous chlorine. These dissolve gold and platinum, converting them into metallic chlorides. *Aqua regia* is a mixture of 1 part of nitric acid with 2 to 3 parts of hydrochloric acid. This mixture converts into soluble chlorides not only those metals which are acted on by hydrochloric and nitric acids, but also gold and platinum, which are insoluble in either acid separately. This action of aqua regia depends on the fact that nitric acid in acting on hydrochloric acid deprives it of its hydrogen, and evolves chlorine little by little as the action proceeds. If the chlorine evolved be transferred to a metal, then a fresh quantity is formed from the remaining acids and combines with the metal.¹⁸ Thus the aqua regia acts in virtue of the chlorine which it contains and disengages.


The majority of *non-metals* also react directly on chlorine; sulphur and phosphorus burn in it, and combine with it directly when heated or even at the ordinary temperature. Only nitrogen, carbon, and oxygen do not form any direct compounds with it. The chlorine compounds formed by the non-metals—for instance, phosphorus trichloride, PCl_3 , and sulphurous chloride, &c., do not have the properties of salts, and if the metallic chlorides M_nCl_{2m} correspond with bases M_nO_m and their hydrates $\text{M}_n(\text{OH})_{2m}$, then, as we shall afterwards see more fully, the chlorides of the non-metals bear the same relation to acid anhydrides and acids:



remarkable, because platinous chloride, PtCl_2 , is then formed, whilst this substance decomposes at a much lower temperature into chlorine and platinum. Therefore, when chlorine comes into contact with platinum at such high temperatures it forms fumes of platinous chloride, and they on cooling decompose with the liberation of platinum, so that the phenomenon appears to be dependent on the volatility of platinum. Deville proved the formation of platinous chloride by inserting a cold tube inside a red-hot one (as in the experiment on carbonic oxide, p. 388). However, Meyer was able to observe the density of chlorine in a platinum vessel at 1690° , at which temperature chlorine does not exert this action on platinum, or at least only to an insignificant degree.

¹⁸ When left exposed to the air aqua regia disengages chlorine, and afterwards it no longer acts on gold. Gay-Lussac, in explaining the action of aqua regia, showed that when heated it evolves, besides chlorine, the vapours of two chloranhydrides—that of nitric acid, NO_2Cl (nitric acid, NO_2OH , in which HO is replaced by chlorine, *see* chapter on Phosphorus), and that of nitrous acid, NOCl (*ibid.*)—but these do not act on gold. The formation of aqua regia may therefore be expressed by $4\text{HNO}_3 + 8\text{HCl} = 2\text{NO}_2\text{Cl} + 2\text{NOCl} + 6\text{H}_2\text{O} + 2\text{Cl}_2$. The formation of the chlorides NO_2Cl and NOCl is explained by the fact that the nitric acid is deoxidised, gives the oxides NO and NO_2 , and they directly combine with chlorine to form the above anhydrides.


As the above-mentioned relation in composition exists between many chlorine compounds and their corresponding hydrates and as furthermore some (acid) hydrates are obtained from chlorine compounds by the action of water, for instance




whilst other chlorine compounds (basic) are formed from hydroxides and hydrochloric acid, with the liberation of water, for instance



therefore this intimate connection between the hydrates and chlorine compounds is endeavoured to be expressed by calling the latter *chloranhydrides*. In general terms, if the hydrate be basic, then,



and if the hydrate ROH be acid, then



In this manner a distinct equivalency is remarked between the compounds of chlorine and the so-called hydroxyl radicle (HO), which is also expressed in the analogy existing between chlorine, Cl_2 , and hydrogen peroxide, $(\text{HO})_2$.

As regards the chloranhydrides corresponding with acids and non-metals, they bear but little resemblance to metallic salts. They are nearly all volatile, and have a powerful suffocating smell which irritates the eyes and respiratory organs. They react on water like many anhydrides of the acids, with the evolution of heat and liberation of hydrochloric acid, forming acid hydrates. For this reason they cannot usually be obtained from hydrates—that is, acids—by the action of hydrochloric acid, as then water would be formed together with them, and water decomposes them, converting them into hydrates. There are many intermediate chlorine compounds between true saline metallic chlorides like sodium chloride and true acid chloranhydrides, just as there are all kinds of transitions between bases and acids; feeble bases not unfrequently present feeble acid properties. These relations will become gradually clearer as we become acquainted with elements of different character, and for the sake of greater clearness we will not enter into an intimate acquaintance with the saline character of acid chloranhydrides, and will only remark that compounds of this type are

not only obtained from chlorine and non-metals, but also from many lower oxides, by the aid of chlorine. Thus, for example, CO, NO, NO₂, SO₂, and other lower oxides which are capable of combining with oxygen may also assimilate to themselves a corresponding quantity of chlorine. Thus COCl₂, NOCl, NO₂Cl, SO₂Cl₂, &c., are obtained. They correspond with the hydrates CO(OH)₂, NO(OH), NO₂(OH), SO₂(OH)₂, &c., and to the anhydrides CO₂, N₂O₃, N₂O₅, SO₃, &c. In this we should evidently see two sides of the matter: (1) chlorine combines with that with which oxygen is able to combine, because it is in many respects equally if not more energetic than oxygen and replaces it in the proportion Cl² : O or (Cl : OH); (2) that highest limit of possible combination which is proper to a given element or grouping of elements is very easily and often attained by combination with chlorine. If phosphorus gives PCl₃ and PCl₅, it is evident that PCl₅ is the higher form of combination compared with PCl₃. To the form PCl₅ or in general PX₅, correspond PH₄I, PO(OH)₃, POCl₃, &c. If chlorine does not always directly give compounds of the highest possible forms for a given element, then generally the lower forms combine with it in order to reach or approach the limit. This is particularly clear in hydrocarbons, where we see the limit C_nH_{2n+2} very distinctly. The unsaturated hydrocarbons are sometimes able to combine with chlorine with the greatest ease and thus reach the limit. Thus ethylene, C₂H₄, combines with Cl₂ forming the so-called Dutch liquid or ethylene chloride, C₂H₄Cl₂, because it then reaches the limit C_nX_{2n+2}. In all like cases the combined chlorine is able by reactions of substitution to give a hydroxide and a whole series of other derivatives. Thus a hydroxide called glycol, C₂H₄(OH)₂, is obtained from C₂H₄Cl₂.

In this way chlorine whilst entering with great ease into combination with simple gases, in a number of cases converts lower forms of combination into higher. Very often chlorine *in the presence of water* acts directly *as an oxidising agent*. A substance A combines with chlorine and gives, for example, ACl₂, and this in turn a hydroxide A(OH)₂, which on losing water forms AO. Hence the chlorine oxidised the substance A. This frequently happens in the simultaneous action of water and chlorine: $A + H_2O + Cl_2 = 2HCl + AO$. Examples of this oxidising action of chlorine may frequently be observed both in chemical practice and technical processes. Thus chlorine, for instance, in the presence of water oxidises sulphur and metallic sulphides. In this case the sulphur is converted into sulphuric acid, and the chlorine into hydrochloric acid or a metallic chloride if a metallic sulphide be taken. A mixture of carbonic oxide and chlorine passed into water gives carbonic anhydride

and hydrochloric acid. Sulphurous anhydride is oxidised by chlorine in the presence of water into sulphuric acid, just as it is by the action of nitric acid: $\text{SO}_2 + 2\text{H}_2\text{O} + \text{Cl}_2 = \text{H}_2\text{SO}_4 + 2\text{HCl}$. The oxidising action of chlorine in the presence of water is taken advantage of in practice for the rapid bleaching of tissues and fibres. The colouring matter of the fibres is altered by oxidation and converted into a colourless substance, but the chlorine afterwards acts on the tissue itself. Bleaching by means of chlorine therefore requires a certain amount of technical skill in order that the chlorine should not act on the fibres themselves, but that its action should be limited to the colouring matter only. The fibre for making writing paper, for instance, is bleached in this manner. The property of chlorine of bleaching was discovered by Berthollet, and forms an important acquisition to the arts, because it has in the majority of cases replaced that which before was the universal method of bleaching, namely, exposure to the sun of the fabrics damped with water, which is still employed for linens, &c. Time and great trouble, and therefore money also, have been considerably saved by this change.¹⁹

The power of chlorine for combination is intimately connected with its capacity for substitution, because, according to the law of substitution, if chlorine combines with hydrogen, then it also replaces hydrogen, and furthermore the combination and substitution are accomplished in the same quantities. Therefore *the atom of chlorine which combines with the atom of hydrogen is also able to replace the atom of hydrogen*. We mention this property of chlorine not only because it illustrates the adaptation of the law of substitution in clear and historically important examples, but more especially because reactions of this kind explain those *indirect methods* of the formation of many substances which we have often mentioned and to which recourse is had in many cases in chemistry. Thus chlorine does not act on carbon,²⁰ oxygen, or nitrogen, but nevertheless its compounds with these elements may be obtained by the indirect method of the substitution of hydrogen by chlorine.

As chlorine easily combines with hydrogen and does not act on

¹⁹ The oxidising property of chlorine shows itself when it destroys the majority of organic tissues, and proves fatal to organisms. This property of chlorine is taken advantage of in quarantine stations. But the simple fumigation by chlorine must be carried on with great care in dwelling places, because chlorine disengaged into the atmosphere renders it harmful to the health by attacking the respiratory organs and the tissues of the lungs.

²⁰ A certain propensity of carbon to attract chlorine must be seen in the immense absorption of chlorine by charcoal (Note 7), but, as far as is at present known (no one has tried, if I do not mistake, to have recourse to the aid of light), no combination then takes place between the chlorine and carbon.

carbon, it decomposes hydrocarbons (and many of their derivatives) at a high temperature, depriving them of their hydrogen and liberating the carbon, as, for example, is clearly seen when a lighted candle is placed in a vessel containing chlorine. The flame becomes smaller but continues for a certain time, a large amount of soot is obtained, and hydrochloric acid is formed. In this case the gaseous and incandescent substances of the flame are decomposed by the chlorine, the hydrogen combines with it, and the carbon is disengaged as soot.²¹ This action of chlorine on hydrocarbons, &c., proceeds otherwise at lower temperatures, as we will proceed to consider.


A very important epoch in the history of chemistry was formed by the discovery of Dumas and Laurent that chlorine is able to displace and *replace hydrogen*. This discovery is important from the fact that chlorine proved to be an element which combines with great ease simultaneously with both the hydrogen and the element with which the hydrogen was combined. This clearly proved that there is no opposite polarity between elements forming stable compounds. Chlorine does not combine with hydrogen because it has opposite properties, as Dumas and Laurent stated previously, accounting hydrogen to be electro-positive and chlorine electro-negative; this is not the reason of their combining together, because the same chlorine which combines with hydrogen is also able to replace it without altering many of the properties of the resultant substance. This substitution of hydrogen by chlorine is termed *metalepsis*. The mechanism of this substitution is very constant. If we take a hydrogen compound, preferably a hydrocarbon, and if chlorine act directly on it, then there is produced on the one hand hydrochloric acid and on the other hand a compound containing chlorine in the place of the hydrogen—so that the chlorine divides itself into two equal portions, one portion is evolved as hydrochloric acid, and the other portion takes the place of the hydrogen thus liberated. *Hence this metalepsis is always accompanied by the formation of hydrochloric acid.*²² The scheme of the process is as follows:



²¹ The same takes place under the action of oxygen, with the difference that it burns the carbon, which chlorine is not able to do. If chlorine and oxygen compete together at a high temperature, the oxygen will unite with the carbon, and the chlorine with the hydrogen; if pure hydrogen be taken with a sufficient quantity of chlorine, it will all combine with the chlorine without forming any water with the oxygen.

²² This division of chlorine into two portions may at the same time be taken as a clear confirmation of the conception of molecules. According to Avogadro-Gerhardt's law, the molecule of chlorine (p. 303) contains two atoms of this substance; one atom replaces the hydrogen, and the other combines with it.

Or, in general terms—



The conditions under which metalepsis takes place are also very constant. In the dark chlorine does not usually act on hydrogen compounds, but the action commences under the influence of light. The direct action of the sun's rays is particularly propitious to metalepsis. It is also remarkable that the presence of traces of certain substances²³ promotes the action (especially of iodine, aluminium chloride, antimony chloride, &c.). A trace of iodine added to the substance subjected to metalepsis often produces the same effect as sunlight.²⁴

If marsh gas be mixed with chlorine and the mixture ignited, then the hydrogen is entirely taken up from the marsh gas and hydrochloric acid and carbon formed, but there is no metalepsis.²⁵ But if a mixture of equal volumes of chlorine and marsh gas be exposed to the action of diffused light, then the greenish yellow mixture gradually becomes colourless, and hydrochloric acid and the first product of metalepsis, namely, methyl chloride, are formed :



²³ Such carriers or media for the transference of chlorine and the halogens in general were long known to exist in iodine and antimonious chloride, and have been most fully studied by Gustavson and Friedel, of the Petroffsky Academy—the former with respect to aluminium bromide, and the latter with respect to aluminium chloride. Gustavson showed that if a trace of metallic aluminium be dissolved in bromine (it floats on bromine, and when combination takes place much heat and light are evolved), the latter becomes endowed with the property of entering into metalepsis, which it is not able to do of its own accord. When pure, for instance, it acts very slowly on benzene, C_6H_6 , but in the presence of a trace of aluminium bromide the reaction proceeds violently and easily, so that each drop of the hydrocarbon gives a mass of hydrobromic acid, and of the product of metalepsis. Gustavson showed that the *modus operandi* of this instructive reaction is based on the property of aluminium bromide to enter into combination with hydrocarbons and their derivatives. The details of this and all researches concerning the metalepsis of the hydrocarbons must be looked for in works on organic chemistry.

²⁴ As small admixtures of iodine, aluminium bromide, &c., aid the metalepsis of large quantities of a substance, just as nitric oxide aids the reaction of sulphurous anhydride on oxygen and water, so the matter is essentially the same in both cases. Effects of this kind (which should also be explained by a chemical reaction proceeding at the surfaces) only differ from true contact phenomena in that the latter are produced by solid bodies and are accomplished at their surfaces, whilst in the former all is in solution. Probably the action of iodine is founded on the formation of iodine chloride, which reacts more easily than chlorine.

²⁵ Metalepsis belongs to the number of delicate reactions—if it may be so expressed—as compared with the energetic reaction of combustion. Many cases of substitution are of this kind. Reactions of metalepsis are accompanied by the evolution of heat, but in a less quantity than that evolved in the formation of the resulting quantity of the halogen acids. Thus the reaction $\text{C}_2\text{H}_6 + \text{Cl}_2 = \text{C}_2\text{H}_5\text{Cl} + \text{HCl}$, judging from the data given by

The volume of the mixture remains unaltered. The methyl chloride which is formed is a gas. If it be separated from the hydrochloric acid (it is soluble in acetic acid, in which hydrochloric is but sparingly soluble) and be again mixed with chlorine then it may be subjected to a further metalepsical substitution—the second atom of hydrogen may be substituted by chlorine, and a liquid substance CH_2Cl_2 , called methylene chloride, will be obtained. In the same manner the substitution may be carried on still further, and CHCl_3 , or chloroform, and, lastly, carbon tetrachloride, CCl_4 , will be produced. Of these substances the best known is chloroform, owing to its being formed in many cases from organic substances (by the action of bleaching powder) and to its being used in medicine as an anæsthetic; chloroform boils at 62° and carbon tetrachloride at 78° . They are both colourless odoriferous liquids, heavier than water. The progressive substitution of hydrogen by chlorine is thus evident, and it can be clearly seen that the double decompositions are accomplished between molecular quantities of the substance—that is, between equal volumes in a gaseous state. Chloroform may be obtained directly from marsh gas, but this, judging from the above, will be the third product of the metalepsis of marsh gas. Between it and marsh gas there are two more intermediate products, and the first of them is produced in the action of one molecule of marsh gas on one molecule of chlorine.

Carbon tetrachloride, which is obtained by the metalepsis of marsh gas, is not obtained directly from chlorine and carbon, but it may be obtained from certain compounds of carbon—for instance, from carbon bisulphide—if its vapour mixed with chlorine be passed through a red-hot tube. Both the sulphur and carbon then combine with the chlorine. It is evident that by ultimate metalepsis a corresponding carbon chloride may be obtained from any hydrocarbon—indeed, the number of chlorides of carbon already known is very large.

As a rule, the fundamental chemical characters of hydrocarbons are not changed by metalepsis; that is, if a neutral substance be taken, then the product of metalepsis is also a neutral substance, or if an acid be taken the product of metalepsis also has acid properties. Even the crystalline form not unfrequently remains unaltered after metalepsis. The metalepsis of acetic acid, $\text{CH}_3\cdot\text{COOH}$, is historically the most important. It contains three of the atoms of the hydrogen of marsh gas, the fourth being replaced by carboxyl, and therefore by the action of chlorine it gives three products of metalepsis (according to the mass of the chlorine and conditions under which the reaction takes place),

Thomsen, evolves about 20000 heat units, whilst the formation of hydrochloric acid evolves 22000 units.

mono-, di-, and tri-chloroacetic acids— $\text{CH}_2\text{Cl}\cdot\text{COOH}$, $\text{CHCl}_2\cdot\text{COOH}$, and $\text{CCl}_3\cdot\text{COOH}$; they are all, like acetic acid, monobasic. Without entering into the further description of cases of like reaction (they must be looked for in organic chemistry), it is necessary to turn special attention first to the fact that in this manner *by an indirect method*, carbon compounds (for instance, CCl_4 , C_2Cl_4 , C_6Cl_6 , &c.) are formed, which cannot be obtained directly from the elements, and secondly, that the resulting products of metalepsis, in containing an element which so easily acts on metals as chlorine, give the possibility of attaining a further complexity of molecules for which the original hydrocarbon is often in no way capable. Thus on treating with an alkali (or first with a salt and then with an alkali, or with a basic oxide and water, &c.) the chlorine forms a salt with its metal, and the hydroxyl radicle takes the place of the chlorine—for example, $\text{CH}_3\cdot\text{OH}$ is obtained from CH_3Cl . By the action of metallic derivatives of hydrocarbons—for instance, CH_3Na —the chlorine also gives a salt, and the hydrocarbon radicle—for instance, CH_3 —takes the place of the chlorine. Thus, or in a similar manner, $\text{CH}_3\cdot\text{CH}_3$ or C_2H_6 is obtained from CH_3Cl or $\text{C}_6\text{H}_5\cdot\text{CH}_3$ from $\text{C}_6\text{H}_5\text{Cl}$. The products of metalepsis also often react on ammonia, forming hydrochloric acid (and thence NH_4Cl) and an amide; that is, the product of metalepsis with the ammonia radicle NH_2 in the place of chlorine. Thus by means of metalepsical substitution a method is found in chemistry for an artificial and general means of the formation of complex carbon compounds from more simple compounds which are often totally incapable of direct reaction. Besides which, this key opened the doors of that secret edifice of the structure of complex organic compounds into which man had up to then feared to enter, supposing it to be the dwelling of the spirits of organisms under the influence of whose magical force that was united which by other means could not be brought together.²⁶

²⁶ With the predominance of the representation of compound radicles (this doctrine dates from Lavoisier and Gay-Lussac) in organic chemistry, it was a very important moment in its history when it became possible to gain an insight into the structure of the radicles themselves. It was clear, for instance, that ethyl, C_2H_5 , or the radicle of common alcohol, $\text{C}_2\text{H}_5\cdot\text{OH}$, passes, without changing, into a number of ethyl derivatives, but its relation to the still simpler hydrocarbons was not clear, and occupied the attention of science in the 'forties' and 'fifties.' Having obtained ethyl hydride, $\text{C}_2\text{H}_5\text{H} - \text{C}_2\text{H}_6$, it was looked on as containing the same ethyl, just as methyl hydride, $\text{CH}_4 = \text{CH}_3\text{H}$, was considered as existing in methane. Having obtained free methyl, $\text{CH}_3\text{CH}_3 = \text{C}_2\text{H}_6$, from it, it was considered as a derivative of methyl alcohol, CH_3OH , and as only isomeric with ethyl hydride. By means of the products of metalepsis it was proved that this is not a case of isomerism but of strict identity, and it therefore became clear that ethyl is methylated methyl, $\text{C}_2\text{H}_5 - \text{CH}_2\text{CH}_3$. In its time a still greater impetus was given by the study of the reactions of monochloroacetic acid, $\text{CH}_2\text{Cl}\cdot\text{COOH}$, or $\text{CO}(\text{CH}_2\text{Cl})(\text{OH})$. It appeared that metalepsical chlorine, like the chlorine of chloranhydrides—for instance

It is not only hydrocarbons which are subjected to metalepsis. Certain other hydrogen compounds, under the action of chlorine, also give corresponding chlorine derivatives in exactly the same manner; for instance, ammonia, caustic potash, caustic lime, and a whole series of *alkaline* substances.²⁷ In fact, just as the hydrogen in marsh gas can be replaced by chlorine and form methyl chloride, so the hydrogen in caustic potash, KHO, ammonia, NH₃, and calcium hydroxide, CaH₂O₂ or Ca(OH)₂, may be replaced by chlorine and give potassium hypochlorite, KClO, calcium hypochlorite, CaCl₂O₂, and the so-called chloride of nitrogen, NCl₃. Not only is the correlation in composition the same as in the substitution in marsh gas, but the whole mechanism of the reaction is the same. Here, also, two atoms of chlorine act: one takes the place of the hydrogen whilst the other is evolved as hydrochloric acid, only in the former case the hydrochloric acid evolved remained free, and in the latter, in presence of alkaline substances, the hydrochloric acid formed reacts on them. Thus, in the action of chlorine on caustic potash, the hydrochloric acid formed acts on another quantity of caustic potash and gives potassium chloride and water, and, therefore, not only $\text{KHO} + \text{Cl}_2 = \text{HCl} + \text{KClO}$, but also $\text{KHO} + \text{HCl} = \text{H}_2\text{O} + \text{KCl}$, and therefore the result of both simultaneous phases will be $2\text{KHO} + \text{Cl}_2 = \text{H}_2\text{O} + \text{KCl} + \text{KClO}$. We will here enter into certain special cases.

The action of chlorine on ammonia may either result in the entire breaking up of the ammonia with the evolution of gaseous nitrogen, or in a product of metalepsis (as with CH₄ and H₂O). With an excess of chlorine and the aid of heat the ammonia is decomposed, with the disengagement of free nitrogen.²⁸ This reaction is evidently accom-

of methyl chloride, CH₃Cl, or ethyl chloride, C₂H₅Cl—is capable of substitution; for instance, glycollic acid, CH₂(OH)(CO₂H), or CO(CH₂·OH)(OH), was obtained from it, and it appeared that the OH in the group CH₂(OH) reacted like that in alcohols, and it became clear, therefore, that it was necessary to examine the radicles themselves by analysing them from the point of view of the bonds connecting the constituent atoms. Whence arose the present doctrine of the structure of the carbon compounds. (*See Chapter VIII. Note 42.*)

²⁷ By embracing many instances of the action of chlorine under metalepsis we not only explain the indirect formation of CCl₄, NCl₅, and Cl₂O by one method, but we also arrive at the fact that the reactions of the metalepsis of the hydrocarbons lose that exclusiveness which was often ascribed to them. Also by subjecting the chemical representations to the law of substitution we may foretell metalepsis as a particular case of a general law.

²⁸ This may be taken advantage of in the preparation of nitrogen. If a large excess of chlorine water be poured into a beaker, and a small quantity of a solution of ammonia be added, then, after shaking, nitrogen is evolved. If chlorine act on a dilute solution of ammonia, then the volume of nitrogen does not correspond with the volume of the chlorine taken, because ammonium hypochlorite is formed. If ammonia gas be passed through a fine orifice into a vessel containing chlorine, then the reaction of the formation

panied by the formation of sal-ammoniac, $8\text{NH}_3 + 3\text{Cl}_2 = 6\text{NH}_4\text{Cl} + \text{N}_2$. But if the ammonium salt be in excess, then the reaction proceeds with the replacement of the hydrogen in the ammonia by chlorine. The essence of the matter is that $\text{NH}_3 + 3\text{Cl}_2$ forms $\text{NCl}_3 + 3\text{HCl}$.²⁹ The resulting product of metalepsis, or *chloride of nitrogen*, NCl_3 , discovered by Dulong, is a liquid having the property of decomposing with excessive ease not only when heated, but even under the action of mechanical influences, as by a blow or the contact of certain solid substances. The explosion which accompanies the decomposition is due to the fact that the liquid chloride of nitrogen gives gaseous products, nitrogen and chlorine; a large volume of gas is evolved instantaneously and causes the explosion. It is even dangerous to prepare this substance in any considerable quantity. Whenever an ammoniacal substance comes into contact with chlorine great care must be taken, because it might be a case of the formation of such products and a very dangerous explosion. The liquid product of the metalepsis of ammonia may be most safely prepared in the form of small drops by the action of a galvanic current on a slightly warm solution of sal-ammoniac; chlorine is then evolved at the positive pole, and this chlorine, acting on the ammonia, gradually forms the product of metalepsis, which floats on the surface of the liquid (because it is borne up by the gas), and if a layer of turpentine be poured on to it these small drops, on

of nitrogen is accompanied by the emission of light and the appearance of a cloud of sal-ammoniac. In all these instances there must be an excess of chlorine.

²⁹ The hydrochloric acid formed combines with ammonia, and therefore the result is $4\text{NH}_3 + 3\text{Cl}_2 = \text{NCl}_3 + 3\text{NH}_4\text{Cl}$. Consequently, more ammonia enters into the reaction, but the metalepsical aspect of the reaction in reality only takes place with an excess of ammonia in the form of the salt. If bubbles of chlorine be passed through a fine tube into a vessel containing ammonia gas, then each bubble gives rise to an explosion. If, however, chlorine be passed into a solution of ammonia, then the reaction first directs itself towards the formation of nitrogen, because chloride of nitrogen acts on ammonia like chlorine. But when sal-ammoniac begins to form, then the reaction directs itself towards the formation of chloride of nitrogen. The first action of chlorine on a solution of sal-ammoniac always consists in the formation of chloride of nitrogen, which reacts on ammonia thus: $\text{NCl}_3 + 4\text{NH}_3 = \text{N}_2 + 3\text{NH}_4\text{Cl}$. Therefore, so long as the liquid is alkaline from the presence of ammonia the chief product will be nitrogen. The reaction $\text{NH}_4\text{Cl} + 3\text{Cl}_2 = \text{NCl}_3 + 4\text{HCl}$ is reversible; with a dilute solution it proceeds in the above-described direction (perhaps owing to the affinity of the hydrochloric acid for the excess of water), but with a strong solution of hydrochloric acid it takes the opposite direction (probably in virtue of the affinity of hydrochloric acid for ammonia). Therefore there must exist a very interesting case of equilibrium between ammonia, hydrochloric acid, chlorine, water, and chloride of nitrogen which has not yet been investigated. The reaction $\text{NCl}_3 + 4\text{HCl} = \text{NH}_4\text{Cl} + 3\text{Cl}_2$ enabled Deville and Hautefeuille to determine the composition of chloride of nitrogen. When slowly decomposed by water, chloride of nitrogen gives, like a chloranhydride, nitrous acid or its anhydride $2\text{NCl}_3 + 3\text{H}_2\text{O} = \text{N}_2\text{O}_5 + 6\text{HCl}$. From these observations it is evident that chloride of nitrogen presents great chemical interest, which is strengthened by its analogy with trichloride of phosphorus.

coming into contact with the turpentine, give feeble explosions, which are in no way dangerous, owing to the small mass of the substance formed. The drops of chloride of nitrogen may, with great precaution, be collected for investigation in the following manner. The neck of a funnel is immersed in a basin containing mercury, and, first, a saturated solution of common salt is poured into the funnel, and above it a solution of sal-ammoniac in 9 parts of water. Chlorine is then slowly passed through the solutions, when drops of chloride of nitrogen fall into the salt water. It is a yellow oily liquid of sp. gr. 1.65, which boils at 71° , and breaks up into $N + Cl_3$ at 97° . The contact of phosphorus, turpentine, india-rubber, &c., causes an explosion, which is sometimes so violent that a small drop will pierce through a thick board. The exceeding facility of the decomposability of chloride of nitrogen is connected with the fact that it is formed with an absorption of heat, which it evolves when decomposed, to the amount of about 38000 heat units for NCl_3 , as Deville and Hautefeuille determined.

Chlorine, when absorbed by a solution of caustic soda (and also of other alkalis) at the ordinary temperature causes the replacement of the hydrogen in the caustic soda by the chlorine, with the formation of sodium chloride by the hydrochloric acid formed, so that the reaction may be represented in two phases, as was described above. In this manner, sodium hypochlorite, $NaClO$, and sodium chloride are simultaneously formed: $2NaHO + Cl_2 = NaCl + NaClO + H_2O$. The resultant solution is termed 'eau de Javelle.' An exactly similar reaction takes place when chlorine is passed over dry hydrate of lime at the ordinary temperature: $2Ca(HO)_2 + 2Cl_2 = CaCl_2O_2 + CaCl_2 + 2H_2O$. A mixture of the product of metalepsis and calcium chloride is obtained. This mixture is employed in practice on a large scale, and is termed 'bleaching powder,' owing to its acting, especially when mixed with acids, as a bleaching agent on tissues, so that it resembles chlorine in this respect, but is preferable to chlorine, because the destructive action of the chlorine may be moderated in this case, and because it is much more convenient to deal with a solid substance than with gaseous chlorine. Bleaching powder is also called *chloride of lime*, because this substance is obtained from chlorine and hydrate of lime, and contains³⁰ both

³⁰ Quicklime, CaO (or calcium carbonate, $CaCO_3$), does not absorb chlorine when cold, but at a red heat, in a current of chlorine, it forms calcium chloride, with the evolution of oxygen. This reaction corresponds with the decomposing action of chlorine on methane, ammonia, and water. Slaked lime (calcium hydroxide, CaH_2O_2) also, when dry, does not absorb chlorine at 100° . The absorption proceeds at the ordinary temperature (below 40°). The dry mass thus obtained contains not less than three equivalents of calcium hydroxide to four equivalents of chlorine, so that its composition is $[Ca(HO)_2]_3Cl_4$. In all probability a simple absorption of chlorine by the lime at first takes place in this case, as may be seen from the fact that even carbonic anhydride, when

these substances. It may be prepared in the laboratory by passing a stream of chlorine through a cold mixture of water and lime (milk of lime). The mixture must be kept cold, as otherwise $3\text{Ca}(\text{ClO})_2$ passes into $2\text{CaCl}_2 + \text{Ca}(\text{ClO}_3)_2$. In the manufacture of bleaching powder in large quantities at chemical works, the purest possible slaked lime is




FIG. 68.—Apparatus for the manufacture of bleaching powder (at small works) by the action of chlorine, which is generated in the vessels C, on lime, which is charged into M.

taken and laid in a thin layer in large flat chambers, M (whose walls are made of Yorkshire flags or tarred wood, on which chlorine has no action), and into which chlorine gas is introduced by lead tubes. The distribution of the plant is shown in the annexed drawing (fig. 68).

acting on the dry mass obtained as above, disengages all the chlorine from it, forming only calcium carbonate. But if the bleaching-powder be obtained by a wet method, or if it be dissolved in water (it is very soluble), and carbonic anhydride be passed into it, then chlorine is no longer disengaged, but chlorine oxide, Cl_2O , and only half of the chlorine is converted into this oxide while the other half remains in the liquid as calcium chloride. From this it may be supposed that calcium chloride is formed by the action of water on bleaching powder, and this is proved to be the case by the fact that small quantities of water extract much calcium chloride from bleaching-powder. If a large quantity of water act on bleaching-powder there remains an excess of calcium hydroxide, a portion of which is not subjected to change. The action of the water may be expressed by the following formulæ: From the dry mass $\text{Ca}_5(\text{HO})_6\text{Cl}_1$ there is formed lime, $\text{Ca}(\text{HO})_2$, calcium chloride, CaCl_2 , and a saline substance, $\text{Ca}(\text{ClO})_2$. $\text{Ca}_5\text{H}_6\text{O}_6\text{Cl}_1 = \text{CaH}_2\text{O}_2 + \text{CaCl}_2\text{O}_2 + \text{CaCl}_2 + 2\text{H}_2\text{O}$. The resulting substances are not equally soluble; water first extracts the calcium chloride, which is the most soluble, then the compound $\text{Ca}(\text{ClO})_2$, and calcium hydroxide is ultimately left. A mixture of calcium chloride and hypochlorite passes into solution. On evaporation there remains $\text{Ca}_2\text{O}_2\text{Cl}_3 \cdot 3\text{H}_2\text{O}$. The dry bleaching-powder does not absorb more chlorine, but the solution is able to absorb it in considerable quantity. If the liquid be boiled, a considerable amount of chlorine monoxide is evolved. After this calcium chloride alone remains in solution, and the decomposition may be expressed as follows: $\text{CaCl}_2 + \text{CaCl}_2\text{O}_2 + 2\text{Cl}_2 = 2\text{CaCl}_2 + 2\text{Cl}_2\text{O}$. Chlorine monoxide may be prepared in this manner.

It is sometimes said that bleaching-powder contains a substance, $\text{Ca}(\text{OH})_2\text{Cl}_2$, like calcium peroxide, CaO_2 , in which one atom of oxygen is replaced by $(\text{OH})_2$, and the other by Cl_2 ; but, judging from what has been said above, this can only be admitted in the dry mass, and not in solutions.

After being kept for some time, bleaching-powder sometimes decomposes, with the evolution of oxygen (page 161); the same takes place when it is heated.

The products of the metalepsis of alkaline hydrates, NaClO and $\text{Ca}(\text{ClO})_2$, which are held in solutions of 'Javelle salt,' and bleaching powder (they are not obtained free from metallic chlorides), must be counted as salts, because their metals are liable to substitution. But the hydrate HClO corresponding with these salts, or *hypochlorous acid*, is not obtained in a free or pure state, for two reasons: in the first place, because this hydrate, as a very feeble acid, splits up (like H_2CO_3 or HNO_3) into water and the anhydride, or *chlorine monoxide*, $\text{Cl}_2\text{O} = 2\text{HClO} - \text{H}_2\text{O}$; and, in the second place, because, in a number of instances, it evolves oxygen with great facility, forming hydrochloric acid: $\text{HClO} = \text{HCl} + \text{O}$. Both hypochlorous acid and chlorine monoxide may be regarded as the product of the metalepsis of water, because HOH corresponds with ClOH and ClOCl . Hence, in many instances, bleaching salts (a mixture of hypochlorites and chlorides) break up, with the evolution of (1) *chlorine*, under the action of an excess of a powerful acid, capable of evolving hydrochloric acid from sodium or calcium chlorides, and which is most simple under the action of hydrochloric acid itself, because (p. 456) $\text{NaCl} + \text{NaClO} + 3\text{HCl} = 2\text{NaCl} + \text{HCl} + \text{Cl}_2 + \text{H}_2\text{O}$; (2) *oxygen*, as we saw in Chapter III. (p. 161)—the bleaching properties and, in general, *oxidising action* of bleaching salts is based on this evolution of oxygen (or chlorine); oxygen is also disengaged on heating the dry salts—for instance, $\text{NaCl} + \text{NaClO} = 2\text{NaCl} + \text{O}$; (3) and, lastly, *chlorine monoxide*, which contains both chlorine and oxygen. Thus, if a little sulphuric, nitric, or similar acid (in order that hydrochloric acid should not yet be produced) be added to a solution of a bleaching salt (which has an alkaline reaction, owing either to an excess of alkali or to the feeble acid properties of HClO), then the hypochlorous acid set free gives water and chlorine monoxide. If carbonic anhydride (or boracic or a similar very feeble acid) act on the solution of a bleaching salt, then hydrochloric acid is not evolved from the sodium or calcium chlorides, but the hypochlorous acid is displaced and gives chlorine monoxide,⁵¹ because hypochlorous acid is one of the most feeble acids (p. 371). An excellent method for the preparation of chlorine monoxide is based on these feeble acid properties of hypochlorous acid. Zinc oxide and mercury oxide, under

⁵¹ For this reason it is necessary that in the formation of bleaching powder the chlorine should be free from hydrochloric acid, and even the lime from calcium chloride. An excess of chlorine, in acting on a solution of bleaching-powder, may also give chlorine monoxide, because calcium carbonate also gives chlorine monoxide under the action of chlorine. This reaction may be brought about by treating freshly-precipitated calcium carbonate with a stream of chlorine in water: $2\text{Cl}_2 + \text{CaCO}_3 = \text{CO}_2 + \text{CaCl}_2 + \text{Cl}_2\text{O}$. From this we may conclude that, although carbonic anhydride displaces hypochlorous anhydride, it may be itself displaced by an excess of the latter.

the action of chlorine in the presence of water, do not give a salt of hypochlorous acid, but form a chloride and hypochlorous acid, which fact shows the incapacity of this acid to combine with the given bases. Therefore, if such oxides as those of zinc or mercury be shaken up in water, and chlorine be passed through the turbid liquid,³² a reaction occurs which may be expressed in the following manner : $2\text{HgO} + 2\text{Cl}_2 = \text{Hg}_2\text{OCl}_2 + \text{Cl}_2\text{O}$. In this case, a compound of mercury oxide with mercury chloride, or the so-called mercury oxychloride, is obtained : $\text{Hg}_2\text{OCl}_2 = \text{HgO} + \text{HgCl}_2$. This is insoluble in water, and is not affected by hypochlorous anhydride, so that the solution will contain hypochlorous acid only, but the greater part of it splits up into the anhydride and water.

A solution of hypochlorous anhydride is also obtained by the action of chlorine on many salts ; for example, in the action of chlorine on a solution of sodium sulphate the following reaction takes place : $\text{Na}_2\text{SO}_4 + \text{H}_2\text{O} + \text{Cl}_2 = \text{NaCl} + \text{HClO} + \text{NaHSO}_4$. Hence here the hypochlorous acid is formed, together with HCl, at the expense of the reaction of chlorine on water, for $\text{Cl}_2 + \text{H}_2\text{O} = \text{HCl} + \text{HClO}$. If the crystallo-hydrate of chlorine be mixed with mercury oxide, then the hydrochloric acid formed in the reaction gives mercury chloride, and hypochlorous acid remains in solution. A dilute solution of hypochlorous acid or chlorine monoxide may be concentrated by distillation, and if a substance which takes up water (without destroying the acid)—for instance, calcium nitrate—be added to the stronger solution then the anhydride of hypochlorous acid—*i.e.* chlorine monoxide—is disengaged.

In the bleaching salts and hypochlorous salts which correspond with chlorine monoxide and contain the two elements oxygen and chlorine, which both act in an oxidising manner, we see a characteristic example of a compound of elements which, in the majority of cases, act chemically in an analogous manner. Chlorine monoxide, as prepared from an aqueous solution by the abstraction of water or by the action of dry chlorine on cold mercury oxide, is, at the ordinary temperature, a gas or vapour which condenses into a red liquid boiling at $+20^\circ$ and giving a vapour whose density (43 referred to hydrogen) shows that

³² Dry red mercury oxide acts on chlorine, forming dry hypochlorous anhydride (chlorine monoxide) (Balard); when mixed with water, red mercury oxide acts feebly on chlorine, and when freshly precipitated it evolves oxygen and chlorine. An oxide of mercury which easily and abundantly evolves chlorine monoxide under the action of chlorine in the presence of water may be prepared as follows: the oxide of mercury, precipitated from a mercuric salt by an alkali, is heated to 300° and cooled (Pelouze). If a salt, MClO , be added to a solution of mercuric salt, HgX_2 , then mercuric oxide is liberated, because the hypochlorite is decomposed.

2 vols. of chlorine and 1 vol. of oxygen give 2 vols. of chlorine monoxide. In an anhydrous form the gas or liquid easily explodes, splitting up into chlorine and oxygen. This explosiveness is determined by the fact that heat is *evolved* in the decomposition to the amount of about 15000 heat units for Cl_2O .³³ The explosion may even take place accidentally, and also in the presence of many oxidisable substances (for instance, sulphur, organic compounds, &c.), but the solution, although unstable and showing strong oxidising properties, does not give any explosion.³⁴

Hypochlorous acid, its salts, and chlorine monoxide serve as a transition between hydrochloric acid, chlorides, and chlorine, and a whole series of compounds containing the same elements combined with a still greater quantity of oxygen. The higher oxides of chlorine, even in their origin, are closely connected with hypochlorous acid and its salts :

Cl_2 , NaCl , HCl , hydrochloric acid.

Cl_2O , NaClO , HClO , hypochlorous acid.

Cl_2O_3 , NaClO_2 , HClO_2 , chlorous acid.³⁵

Cl_2O_5 , NaClO_3 , HClO_3 , chloric acid.

Cl_2O_7 , NaClO_4 , HClO_4 , perchloric acid.

When heated, solutions of hypochlorites undergo a remarkable change. Themselves so unstable, they, without the addition of any-

³³ All explosive substances are of this kind—ozone, hydrogen peroxide, chloride of nitrogen, nitro-compounds; &c. Hence they cannot be formed directly from the elements or their simplest compounds, but, on the contrary, decompose into them. In a liquid state chlorine monoxide even explodes on contact with powdery substances, or when rapidly agitated—for instance, if a file be rasped over the vessel in which it is.

³⁴ A solution of chlorine monoxide, or hypochlorous acid, does not explode, owing to the presence of the mass of water. In dissolving, chlorine monoxide evolves about 9000 heat units, so that its store of heat becomes less.

The capacity of hypochlorous acid for entering into combination with the unsaturated hydrocarbons (Carius and others) is very often taken advantage of in organic chemistry. Thus its solution absorbs ethylene, forming the chlorhydrin $\text{C}_2\text{H}_4\text{Cl}\cdot\text{OH}$.

The oxidising action of hypochlorous acid and its salts is not only applied to bleaching but also to many reactions of oxidation. Thus it converts the lower oxides of manganese into the peroxide.

³⁵ *Chlorous acid*, HClO_2 (judging from the data given by Millon, Brandau, and others) in many respects resembles hypochlorous acid HClO , whilst they both differ from chloric and perchloric acids in their degree of stability, which is expressed, for instance, in their bleaching properties; the two higher acids do not bleach, but both the lower ones do so (oxidise at the ordinary temperature). On the other hand, chlorous acid is analogous to nitrous acid, HNO_2 . The anhydride of chlorous acid, Cl_2O_3 , is not known in a pure state, but it probably occurs in admixture with chlorine dioxide, ClO_2 , which is obtained by the action of nitric and sulphuric acids on a mixture of potassium chlorate with such reducing substances as nitric oxide, arsenious oxide, sugar, &c. All that is at present known is that pure chlorine dioxide ClO_2 (see Notes 39–43) is gradually converted into a mixture of hypochlorous and chlorous acids under the action of water (and alkalis)

thing, yield two fresh salts which are both much more stable ; one contains more oxygen than MClO , the other contains none at all.



Part of the salt—namely, two-thirds of it—parts with its oxygen in order to oxidise the remaining third.³⁶ From an intermediate substance, RX , there proceed two extremes, R and RX_3 , just as from nitrous anhydride there proceed nitric oxide and nitric anhydride (or nitric acid) : $3\text{N}_2\text{O}_3 = \text{N}_2\text{O}_5 + 4\text{NO}$. The resulting salt MClO_3 corresponds with *chloric acid* and potassium chlorate, KClO_3 . It is evident that a similar salt is obtained directly by the action of chlorine on an alkali if its solution be heated, because RCLO will be first formed, and then RCLO_3 ; for example, $6\text{KHO} + 3\text{Cl}_2 = \text{KClO}_3 + 5\text{KCl} + 3\text{H}_2\text{O}$. Chlorates are formed thus : for instance, *potassium chlorate*, which is

that is, it acts like nitric peroxide, NO_2 (giving HNO_5 and HNO_3), or as a mixed anhydride, $2\text{ClO}_2 + \text{H}_2\text{O} = \text{HClO}_5 + \text{HClO}_3$. The silver salt, AgClO_3 , is sparingly soluble in water. The investigations of Garzarolli-Thurnluckh and others seem to show that the anhydride Cl_2O_5 does not exist.

³⁶ Hydrochloric acid, which forms an example of compounds of this kind, is a saturated substance which does not combine directly with oxygen, but in which, nevertheless, a considerable quantity of oxygen may be inserted between the elements forming it. The same may be observed in a number of other cases. Thus, for instance, oxygen may be added or inserted between the elements, sometimes in considerable quantities, in the saturated hydrocarbons ; for instance, in C_5H_8 , three atoms of oxygen produce an alcohol, glycerin or glycerol $\text{C}_5\text{H}_5(\text{OH})_3$. We shall meet with similar examples hereafter. This is explained generally by regarding oxygen as a bivalent element—that is, as capable of combining with two different elements, such as chlorine, hydrogen, &c. On the basis of this view, it may be inserted between each pair of combined elements ; the oxygen will then be combined with one of the elements by one of its affinities and with the other element by its other affinity. This view does not, however, express the entire substance of the matter, even when applied to the compounds of chlorine. Hypochlorous acid, HOCl —that is, hydrochloric acid in which one atom of oxygen is inserted—is, as we have already seen, a substance of small stability ; it would therefore be expected that on the addition of a fresh quantity of oxygen a still less stable substance would be obtained, because, according to the above view, the chlorine and hydrogen, which form such a stable compound together, are then still further removed from each other. But it appears that chloric and perchloric acid, HClO_3 and HClO_4 , are much more stable substances. Furthermore, the addition of oxygen has also its limit, it can only be added to a certain extent. If the above representation were true and not formal, then a limit to the combination of oxygen could not be looked for, and the more it entered into one uninterrupted chain the more stable would be the resultant compound. But not more than four atoms of oxygen can be added to hydrogen sulphide, nor to hydrochloric acid, nor to hydrogen phosphide. This peculiarity must lie in the properties of oxygen itself ; four atoms of oxygen seem to have the power of forming a kind of radicle which retains two or several atoms of different other substances—for example, chlorine and hydrogen, hydrogen and sulphur, sodium and manganese, phosphorus and metals, &c., forming comparatively stable compounds, NaClO_4 , Na_2SO_4 , NaMnO_4 , Na_3PO_4 , &c. See Chapter X. Note 1.

easily separated from potassium chloride, because it is sparingly soluble in cold water.³⁷

If dilute sulphuric acid be added to a solution of potassium chlorate, then *chloric acid* is liberated; but it cannot be separated by distillation, as it is decomposed in the process. To obtain the free acid sulphuric acid must be added to a solution of barium chlorate.³⁸ The sulphuric acid gives a precipitate of barium sulphate with the barium, and free chloric acid remains in solution. The solution may be evaporated under the receiver of an air-pump. This solution is colourless, has no smell, and acts as a powerful acid (it saturates sodium hydroxide, decomposes sodium carbonate, gives hydrogen with zinc, &c.); when

³⁷ If chlorine be passed through a *cold* solution of potash, then a bleaching compound, potassium chloride and hypochlorite, $\text{HCl} + \text{KClO}$, is formed, but if it be passed through a *hot* solution potassium chlorate is formed. As this is sparingly soluble in water, it chokes the gas-conducting tube, which should therefore be widened out at the end.

Potassium chlorate is usually prepared on a large scale from calcium chlorate, which is prepared by passing chlorine (as long as it is absorbed) into water containing lime, the mixture being kept warm. A mixture of calcium chlorate and chloride is thus formed in the solution. Potassium chloride is then added to the warm solution, and on cooling a precipitation of potassium chlorate is formed as a substance which is sparingly soluble in cold water, especially in the presence of other salts. The double decomposition taking place is $\text{Ca}(\text{ClO}_3)_2 + 2\text{KCl} = \text{CaCl}_2 + 2\text{KClO}_3$. On a small scale in the laboratory potassium chlorate is best prepared from a strong solution of bleaching powder by passing chlorine through it and then adding potassium chloride.

Potassium chlorate crystallises easily in large colourless tabular crystals. Its solubility in 100 parts of water at $0^\circ = 3$ parts, $20^\circ = 8$ parts, $40^\circ = 14$ parts, $60^\circ = 25$ parts, $80^\circ = 40$ parts. For comparison we will cite the following figures showing the solubility of potassium chloride and perchlorate in 100 parts of water: potassium chloride at $0^\circ = 28$ parts, $20^\circ = 35$ parts, $40^\circ = 40$ parts, $100^\circ = 57$ parts; potassium perchlorate at 0° about 1 part, 20° about $1\frac{1}{2}$ parts, 100° about 18 parts. When heated potassium chlorate melts (the melting point has been given as from 335° – 376° ; according to the latest determination by Carnelley, 359) and decomposes with the evolution of oxygen, potassium perchlorate being at first formed, as will afterwards be described. A mixture of potassium chlorate and nitric and hydrochloric acids brings about oxidation and chlorination in solutions. It deflagrates when thrown upon incandescent carbon, and when mixed with sulphur ($\frac{1}{3}$ by weight) it sets light to it, even when struck, in which case an explosion takes place. The same occurs with many metallic sulphides and organic substances. Such mixtures are inflamed by a drop of sulphuric acid. All these effects are due to the large amount of oxygen contained in potassium chlorate, and to the ease with which it is evolved. A mixture of two parts of potassium chlorate, one part of sugar, and one part of yellow prussiate of potash acts like gunpowder, but it burns very rapidly, and therefore bursts the guns, and also it has a very strong oxidising action on their metal. The sodium salt, NaClO_3 , is much more soluble than the potassium salt, and it is therefore more difficult to free it from sodium chloride, &c. The barium salt is also more soluble than the potassium salt; $0^\circ = 24$ parts, $20^\circ = 37$ parts, $80^\circ = 98$ parts of salt per 100 of water.

³⁸ Barium chlorate, $\text{Ba}(\text{ClO}_3)_2 \cdot \text{H}_2\text{O}$, is prepared in the following way: impure chloric acid is first prepared and saturated with baryta, and the barium salt purified by crystallisation. The impure free chloric acid is obtained by converting the potassium in potassium chlorate into an insoluble salt. This is done by adding tartaric or hydrofluosilicic acid to a solution of potassium chlorate, because potassium tartrate and potassium silicofluoride are very sparingly soluble in water. Chloric acid is easily soluble in water.

heated above 40° , however, it decomposes, forming chlorine, oxygen, and perchloric acid: $4\text{HClO}_3 = 2\text{HClO}_4 + \text{H}_2\text{O} + \text{Cl}_2 + \text{O}_3$. When considerably concentrated the acid acts as an exceedingly energetic oxidiser, so that organic substances, when brought into contact with it, burst into flame. Iodine, sulphurous acid, and similar substances liable to oxidation form higher oxidation products and reduce the chloric acid to hydrochloric acid. Hydrochloric acid gas gives chlorine with chloric acid in the same manner as it acts on the lower acids: $\text{HClO}_3 + 5\text{HCl} = 3\text{H}_2\text{O} + 3\text{Cl}_2$.

By cautiously acting on potassium chlorate with sulphuric acid, the *dioxide (chloric peroxide)*, ClO_2 ,³⁹ is obtained (Davy, Millon). This gas is easily liquefied in a freezing mixture, and the liquid boils at $+10^\circ$. The vapour density (about 35 if $\text{H}=1$) shows that the molecule of this substance is ClO_2 .⁴⁰ In a gaseous or liquid state it very easily explodes (for instance, at 60° , or by contact with organic compounds or finely divided substances, &c.), forming Cl_2 and O , and it therefore in many instances⁴¹ acts as an oxidising agent, although (like nitric peroxide) it may be itself further oxidised.⁴² In dissolving in water or alkalis chloric peroxide gives chlorous and hypochlorous acids $2\text{ClO}_2 + 2\text{KHO} = \text{KClO}_3 + \text{KClO}_2 + \text{H}_2\text{O}$ —and therefore, like nitric peroxide, the dioxide may be regarded as an intermediate oxide between the (unknown) anhydrides of chlorous and chloric acids: $4\text{ClO}_2 = \text{Cl}_2\text{O}_3 + \text{Cl}_2\text{O}_5$.⁴³

³⁹ 100 grams of sulphuric acid are cooled in a mixture of ice and salt, and 15 grams of powdered potassium chlorate are gradually added to the acid, which is then carefully distilled at 20° to 40° , the vapour given off being condensed in a freezing mixture. Potassium perchlorate is then formed: $3\text{KClO}_3 + 2\text{H}_2\text{SO}_4 = 2\text{KHSO}_4 + \text{KClO}_4 + 2\text{ClO}_2 + \text{H}_2\text{O}$. The reaction may result in an explosion. Calvert and Davies obtained chloric peroxide without the least danger by heating a mixture of oxalic acid and potassium chlorate in a test tube in a water-bath. In this case $2\text{KClO}_3 + 3\text{C}_2\text{H}_2\text{O}_4 \cdot 2\text{H}_2\text{O} = 2\text{C}_2\text{HKO}_4 + 2\text{CO}_2 + 2\text{ClO}_2 + 8\text{H}_2\text{O}$. The reaction is still further facilitated by the addition of a small quantity of sulphuric acid.

⁴⁰ By analogy with nitric peroxide it would be expected that at low temperatures a doubling of the molecule into Cl_2O_4 would take place, as the reactions in which it acts as the mixed anhydride of HClO_2 and HClO_3 point out.

⁴¹ Owing to the formation of this chlorine dioxide, a mixture of potassium chlorate and sugar is inflamed by a drop of sulphuric acid. This property was formerly made use of for making matches, and is now sometimes employed for setting fire to explosive charges by means of an arrangement in which the acid is caused to fall on the mixture at the moment required. An interesting experiment on the combustion of phosphorus under water may be conducted with chlorine dioxide. Pieces of phosphorus and of potassium chlorate are placed under water, and sulphuric acid is poured into them (through a long funnel); the phosphorus then burns at the expense of the chlorine dioxide.

⁴² Potassium permanganate oxidises chlorine dioxide into chloric acid (Fürst).

⁴³ The *euchlorine* obtained by Davy by gently heating potassium chlorate with hydrochloric acid is (Pebal) a mixture of chlorine dioxide and free chlorine. The liquid and gaseous chlorine oxide (Note 35), which Millon considered to be Cl_2O_5 , probably contains a mixture of ClO_2 (vapour density 35), Cl_2O_5 (whose vapour density should be 59), and chlorine (vapour density 35.5), because its vapour density was determined to be about 40.

As the salts of chloric acid, HClO_3 , are produced by the oxidation of the salts of hypochlorous acid, so, in a similar manner, the salts of perchloric acid, HClO_4 , are produced by the oxidation of the salts of chloric acid, HClO_3 . But this is the highest form of the oxidation of HCl . *Perchloric acid*, HClO_4 , is the most stable of all the acids of chlorine. When fused potassium chlorate begins to swell up and solidify, after having parted with one-third of its oxygen; then potassium chloride and potassium perchlorate are formed, $2\text{KClO}_3 = \text{KClO}_4 + \text{KCl} + \text{O}_2$.

The formation of this salt is clearly remarked in the preparation of oxygen from potassium chlorate, owing to the fact that the potassium perchlorate fuses with greater difficulty than the chlorate, and therefore appears in the molten salt as solid grains. (Under the action of certain acids—for instance, sulphuric and nitric—potassium chlorate also gives potassium perchlorate.) It may be easily purified, because it is but sparingly soluble in water, although all the other salts of perchloric acid are very soluble and even effloresce in the air. It is a remarkable fact that the perchlorates, although they contain more oxygen than the chlorates, are decomposed with greater difficulty, and, even when thrown on ignited charcoal, give a much feebler deflagration than the chlorates. Sulphuric acid (at a temperature not below 100°) evolves volatile and, to a certain extent, stable perchloric acid from potassium perchlorate. Neither sulphuric nor any other acid will further decompose perchloric acid as it decomposes chloric acid. Of all the acids of chlorine, perchloric acid alone can be distilled.⁴⁴ The pure hydrate HClO_4 ⁴⁵ is a colourless and exceedingly caustic substance

⁴⁴ If a solution of chloric acid, HClO_3 , be first concentrated over sulphuric acid under the receiver of an air-pump and afterwards distilled, then chlorine and oxygen are evolved and perchloric acid formed: $4\text{HClO}_3 = 2\text{HClO}_4 + \text{Cl}_2 + 3\text{O} + \text{H}_2\text{O}$. Roscoe accordingly directly decomposed a solution of potassium chlorate by hydrofluosilicic acid, decanted it from the precipitate of potassium silicofluoride, K_2SiF_6 , concentrated the solution of chloric acid, and then distilled it, perchloric acid being then obtained (see following footnote). That chloric acid is capable of passing into perchloric acid is also seen from the fact that potassium permanganate is decolorised, although slowly, by the action of a solution of chloric acid. On decomposing a solution of potassium chlorate by the action of an electric current, potassium perchlorate is obtained at the positive electrode (where the oxygen is evolved). Perchloric acid is also formed by the action of an electric current on solutions of chlorine and chlorine monoxide. Perchloric acid was obtained by Count Stadion and afterwards by Serullas, and was studied by Roscoe and others.

⁴⁵ Perchloric acid, which is obtained in a free state by the action of sulphuric acid on its salts, may be separated from a solution very easily by distillation, because it is volatile, although it is partially decomposed by distillation. The solution obtained after distillation may be concentrated by evaporation in open vessels. In the distillation the solution reaches a temperature of 200° , and then a very constant liquid hydrate of the composition $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$ is obtained in the distillate. If this hydrate be mixed with sulphuric acid, it begins to decompose at 100° , but, nevertheless, a portion of the acid passes over into the receiver without decomposing, forming a crystalline hydrate $\text{HClO}_4 \cdot \text{H}_2\text{O}$ which melts at 50° . On carefully heating this hydrate it breaks up into perchloric acid, which

which fumes in the air and has a sp. gr. 1.78 at 15° (sometimes, after being kept for some time, it decomposes with a violent explosion). It explodes violently when brought into contact with charcoal, paper, wood, and other organic substances. If a small quantity of water be added to this hydrate, and if it be subjected to cold, then a crystalline hydrate, $\text{ClHO}_4 \cdot \text{H}_2\text{O}$, separates out. It is much more stable, but the liquid hydrate $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$ is still more so. The acid dissolves in water in all proportions, and its solutions are distinguished for their stability.⁴⁶ When ignited both the acid and its salts are decomposed, with the evolution of oxygen.⁴⁷

distils over below 100°, and into the liquid hydrate $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$. The acid HClO_4 may also be obtained by adding one-fourth part of strong sulphuric acid to potassium chlorate, and carefully distilling and subjecting the crystals of the hydrate $\text{HClO}_4 \cdot \text{H}_2\text{O}$ obtained in the distillate to a fresh distillation. A liquid of the composition HClO_4 then passes over. Perchloric acid, HClO_4 , when taken separately, does not distil, and is decomposed in distillation until the more stable hydrate $\text{HClO}_4 \cdot \text{H}_2\text{O}$ is formed; this is decomposed in distillation into HClO_4 and $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$, which latter hydrate distils without alteration. This forms an excellent example of the influence of water on stability, and of the property of chlorine to give compounds of the type ClX_7 , of which all the above hydrates, $\text{ClO}_5(\text{OH})$, $\text{ClO}_4(\text{OH})_5$, and $\text{ClO}(\text{OH})_5$, are members. Probably further research will lead to the discovery of a hydrate $\text{Cl}(\text{OH})_7$.

⁴⁶ According to Roscoe the sp. gr. of perchloric acid = 1.782 and of the hydrate $\text{HClO}_4 \cdot \text{H}_2\text{O}$ in a liquid state (50°) 1.811; hence a considerable contraction takes place in the combination of HClO_4 with H_2O .

⁴⁷ The decomposition of salts analogous to potassium chlorate has been more fully studied in recent years by Potilitzin and P. Frankland. Professor Potilitzin, by decomposing, for example, lithium chlorate LiClO_3 , found (from the quantity of lithium chloride and oxygen) that at first the decomposition of the fused salt (368°) is accomplished according to the equation, $3\text{LiClO}_3 = 2\text{LiCl} + \text{LiClO}_4 + 5\text{O}_2$, and that towards the end the remaining salt is decomposed thus: $5\text{LiClO}_3 = 4\text{LiCl} + \text{LiClO}_4 + 10\text{O}_2$. The phenomena observed by Potilitzin obliged him to admit that lithium perchlorate is capable of decomposing simultaneously with lithium chlorate, with the formation of the latter salt and oxygen; and this was confirmed by direct experiment, which showed that lithium chlorate is always formed in the decomposition of the perchlorate. Potilitzin turned particular attention to the fact that the decomposition of potassium chlorate and of salts analogous to it, although exothermal (Chapter III. Note 12), not only does not proceed by itself, but requires time and a rise of temperature in order to attain completion, which again shows that chemical equilibria are not expressed by the heat effects of reactions only.

P. Frankland and J. Dingwall (1887) showed that at 448° (in the vapour of sulphur) a mixture of potassium chlorate and pounded glass is decomposed almost in accordance with the equation $2\text{KClO}_3 = \text{KClO}_4 + \text{KCl} + \text{O}_2$, whilst the salt by itself evolves about half as much oxygen, in accordance with the equation, $8\text{KClO}_3 = 5\text{KClO}_4 + 3\text{KCl} + 2\text{O}_2$. The decomposition of potassium perchlorate in admixture with manganese peroxide proceeds to completion, $\text{KClO}_4 = \text{KCl} + 2\text{O}_2$. But in decomposing by itself the salt at first gives potassium chlorate, approximately according to the equation $7\text{KClO}_4 = 2\text{KClO}_3 + 5\text{KCl} + 11\text{O}_2$. Thus there is now no doubt that when potassium chlorate is heated, the perchlorate is formed, and that this salt, in decomposing also with the evolution of oxygen, gives the former salt.

I may further remark that the decomposition of potassium chlorate as a reaction evolving heat from this very reason easily lends itself to the contact action of manganese peroxide and other similar admixtures; for such very feeble influences as those of contact may evince themselves, as is observed either in those cases (for instance, detonating gas,

On comparing chlorine as an element not only with nitrogen and carbon but with all the other non-metallic elements (chlorine has so little analogy with the metals that a comparison would be superfluous), we find in it the following fundamental properties of *the halogens* or salt-producers. With metals chlorine gives salts (such as sodium chloride, &c.); with hydrogen a very energetic and monobasic (containing one H in its molecule) acid HCl, and the same chlorine is able by metalepsis to replace the hydrogen; with oxygen it forms oxides of an acid character. These properties of chlorine are possessed by three other elements, bromine, iodine, and fluorine. They are members of one natural family. Each representative has its peculiarities, its individual properties, and points of distinction in combination and in the free state—otherwise they would not be independent elements; but the repetition in all of them of the same chief signs of the family enables one to foretell from one element the properties of another, and thus abbreviates an acquaintance with all the differences of their elementary properties and a systemisation of the elements themselves.

In order to have a guiding thread in forming comparisons between the elements, attention must be turned to those of their properties and signs in which they differ most from each other, because it is only under this condition that the comparison ceases to be artificial. And the atomic weights of the elements must be counted as their most elementary property; it being a quantity which is most undoubtedly established, and which acts in all the manifestations of the element. The halogens are endowed with atomic weights—

$$F = 19, \quad Cl = 35.5, \quad Br = 80, \quad I = 127.$$

All the properties, physical and chemical, of the elements and their corresponding compounds must evidently be in a certain dependence on this fundamental point, if the grouping in one family be natural. And we find in reality that, for instance, the properties of bromine, whose atomic weight is almost the mean between those of iodine and chlorine, occupy a mean position between those of these two elements. The second measurable property of the elements is their equivalence or their capacity for forming *compounds of definite forms*. Thus carbon

hydrogen peroxide, &c.), when the reaction is accompanied by the evolution of heat, or when (for instance, $H_2 + I_2$, &c.) little heat is absorbed or evolved. In these cases it is evident that the existing equilibrium is not very stable, and that a feeble alteration in it proceeding at the surfaces of contact may suffice to cause its destruction. In order to conceive the *modus operandi* of contact phenomena, it is enough to imagine, for instance, that at the borders of contact the movement of the atoms in the molecules changes from a circular to an elliptical path. Momentary and transitory compounds may be formed, but their formation cannot alter the explanation of the phenomena.

or nitrogen in this respect differs widely from the halogens. Although the form ClO_2 corresponds with NO_2 and CO_2 , yet the latter is the highest oxide of carbon, whilst that of nitrogen is N_2O_5 , and for chlorine, if there was an anhydride of perchloric acid, its composition would be Cl_2O_7 , which is quite different from that of carbon. In respect to the forms of their compounds the halogens, like all elements of one family or group, are perfectly analogous to each other, as is seen from their hydrogen compounds :



It is the same with their oxygen compounds. Only fluorine does not give any oxygen compounds. The iodine and bromine compounds corresponding with HClO_3 and HClO_4 are HBrO_3 and HBrO_4 , HIO_3 and HIO_4 . On comparing the properties of these acids we can even foresee the fact that fluorine will not form any oxygen compound. In fact, iodine is easily oxidised—for instance, by nitric acid—whilst chlorine is not directly oxidised. The oxygen acids of iodine are comparatively more stable than the acids of chlorine; and, generally speaking, the affinity of iodine for oxygen is much greater than that of chlorine. Here also bromine occupies an intermediate position. In fluorine we may expect a still smaller affinity for oxygen than in chlorine—and up to now it has not been combined with oxygen. If any oxygen compound of fluorine be obtained, it will be exceedingly unstable. The relation of these elements to hydrogen is the reverse of the above. Fluorine has so great an affinity for hydrogen that it decomposes water at the ordinary temperature; whilst iodine has so little affinity for hydrogen that hydriodic acid, HI , is formed with difficulty, is easily decomposed, and acts as a reducing agent in a number of cases.

From the form of their compounds the halogens are *univalent elements* with respect to hydrogen and septivalent with respect to oxygen, if N be trivalent to hydrogen (it gives NH_3) and quinquivalent to oxygen (it gives N_2O_5), and if C be quadrivalent to both H and O as it forms CH_4 and CO_2 .

As not only their oxygen compounds, but also their hydrogen compounds, have acid properties, the halogens are *elements* of an exclusively *acid character*. Such metals as sodium, potassium, barium only give basic oxides. In the case of nitrogen, although it forms acid oxides, still in ammonia we find that capacity to give an alkali with hydrogen which indicates a less distinctly acid character than in the halogens. In no other elements are the acid characters so strongly developed as in the halogens.

In describing certain peculiarities characterising the halogens, we shall at every step encounter a confirmation of the above-mentioned general relations.

As *fluorine* decomposes water with the evolution of oxygen (which forms ozone if the temperature be not high), $F_2 + H_2O = 2HF + O$, therefore for a long time all efforts to obtain it in free state by means of methods similar to those for the preparation of chlorine proved fruitless. Thus by the action of hydrofluoric acid on manganese peroxide, or by decomposing a solution of hydrofluoric acid by an electric current, either oxygen or a mixture of oxygen and fluorine were obtained instead of fluorine. Probably a certain quantity of fluorine⁴⁸ was set free by the action of oxygen or an electric current on incandescent and fused calcium fluoride, but it then, at the high temperature, acted even on platinum, and was therefore absorbed, leaving only oxygen. When chlorine acted on silver fluoride, AgF , in a vessel of natural fluor spar, CaF_2 , fluorine was also liberated; but it was mixed with chlorine, and it was impossible to study the properties of the resultant gas. Brauner also obtained fluorine by igniting cerium fluoride, $2CeF_4 = 2CeF_3 + F_2$; but this, like all preceding efforts, only showed fluorine to be a gas which decomposes water, and is capable of acting in a number of instances like chlorine, but gave no possibility of testing its properties. It was evident that it was necessary to avoid as far as possible the presence of water and a rise of temperature; this Moissan succeeded in doing in 1886. He decomposed anhydrous hydrofluoric acid, liquefied at a temperature of -23° and contained in a U-shaped tube (to which a small quantity of potassium fluoride had been added to make it a better conductor), by the action of a powerful electric current (twenty Bunsen's elements in series). Hydrogen was then evolved at the negative pole, and fluorine appeared at the positive pole (of iridium platinum) as a colourless gas which decomposed water with the formation of ozone and hydrofluoric acid, and combined directly with silicon (forming silicon fluoride, SiF_4), boron (forming BF_3), sulphur, &c. But

⁴⁸ It is most likely that in this experiment of Fremy's, which corresponds with the action of oxygen on calcium chloride, fluorine was set free, but that a converse reaction also proceeded, $CaO + F_2 = CaF_2 + O$ —that is, the calcium distributed itself between the oxygen and fluorine. MnF_2 , which is capable of splitting up into MnF and F_2 , is without doubt formed by the action of a strong solution of hydrofluoric acid on manganese peroxide, but under the action of water the fluorine gives hydrofluoric acid, and probably this is aided by the affinity of the manganese fluoride and hydrofluoric acid. In all the efforts (Davy, Knox, Louget, Fremy, Gore, and others) made to decompose fluorides (those of lead, silver, calcium, and others) by chlorine, there were doubtless also cases of distribution, a portion of the metal combined with chlorine and a portion of the fluorine was evolved; but it is improbable that there were pure results. Probably Fremy obtained fluorine, but it was not pure.

the action of fluorine on metals at the ordinary temperature is comparatively feeble, because the metallic fluoride formed coats the remaining mass of the metals; it is, however, completely absorbed by iron. Hydrocarbons (for instance, naphtha), alcohol, &c., immediately absorb fluorine, with the formation of hydrofluoric acid. Fluorine when mixed with hydrogen easily explodes violently, forming hydrofluoric acid.⁴⁹

Among the compounds of fluorine calcium fluoride, CaF_2 , is rather widely spread in nature as fluor spar,⁵⁰ whilst *cryolite*, or aluminium sodium fluoride, Na_3AlF_6 , is found more rarely (in large masses in Greenland). Cryolite, like fluor spar, is also insoluble in water, and gives hydrofluoric acid with sulphuric acid. Small quantities of fluorine have also in a number of cases been found in the bodies of animals, in the blood, urine, and bones. If fluorides occur in the bodies of animals, they must have been introduced by food, and must occur in plants and water. And in reality river, and especially sea, water always contains a certain, although small, quantity of fluorine compounds.

⁴⁹ According to Moissan, fluorine is disengaged by the action of an electric current on fused hydrogen potassium fluoride, KHF_2 . The present state of chemical knowledge is such that the notion of an element with its properties is much more general than the notion of that element in the free state. It is profitable and agreeable to learn that even fluorine in the free state has not succeeded in eluding experiment and research, that the efforts to isolate it have been crowned with success, but the sum total of the general chemical data concerning fluorine as an element gain but little by this result. The gain will be augmented, however, if it be now possible to subject fluorine to a comparative study in relation to oxygen and chlorine. There is particular interest in the phenomena of the distribution of fluorine and oxygen, or fluorine and chlorine, competing under different conditions and relations.

⁵⁰ It is called spar because it very frequently occurs as crystals of a clearly laminar structure, and is therefore easily split up into pieces bounded by planes. It is called fluor spar because when used as a flux it renders ores fusible, owing to its reacting with silica, $\text{SiO}_2 + 2\text{CaF}_2 = 2\text{CaO} + \text{SiF}_4$; the silicon fluoride escapes as a gas and the lime combines with a further quantity of silica, and gives a vitreous slag. Fluor spar occurs in mineral veins and rocks, sometimes in considerable quantities. It always crystallises in the cubic system, sometimes in very large semitransparent cubic crystals, which are colourless or of different colours. It is insoluble in water. It melts under the action of heat, and crystallises on cooling. The sp. gr. is 3.1. When steam is passed over incandescent fluor spar, lime and hydrofluoric acid are formed: $\text{CaF}_2 + \text{H}_2\text{O} = \text{CaO} + 2\text{HF}$. A double decomposition is also easily produced by fusing fluor spar with sodium or potassium hydroxides, or potash, or even with their carbonates; the fluorine then passes over to the potassium or sodium, and the oxygen to the calcium. In solutions—for example, $\text{Ca}(\text{NO}_3)_2 + 2\text{KF} = \text{CaF}_2$ (precipitate) + 2KNO_3 (in solution)—the formation of calcium fluoride takes place, owing to its very sparing solubility. 26000 parts of water dissolve one part of fluor spar. Fluorine in the form of calcium fluoride also enters into the composition of certain minerals: but in general the amount of fluorine in minerals is inconsiderable. Apatite is a mineral whose chief mass consists of calcium phosphate. Apatites sometimes contain no fluorine whatever, but only chlorine; whilst in other instances a certain amount of fluorine enters into their composition, in which case the atomic proportion of chlorine is proportionately diminished.

Hydrofluoric acid, HF, cannot be obtained from fluor spar in glass retorts, because glass is acted on by and destroys the hydrofluoric acid. It is prepared in lead vessels, and when it is required pure, in platinum vessels, because lead in reality also acts on hydrofluoric acid, only very feebly at the surface, and when once a coating of fluoride and sulphate of lead is formed there is no further action. Powdered fluor spar and sulphuric acid evolve hydrofluoric acid (which fumes in the air) even at the ordinary temperature, $\text{CaF}_2 + \text{H}_2\text{SO}_4 = \text{CaSO}_4 + 2\text{HF}$. At 130° fluor spar is completely decomposed by sulphuric acid. The acid is then evolved as vapour, which may be condensed by a freezing mixture into an anhydrous acid. The condensation is aided by pouring water into the receiver of the condenser, as the acid is easily soluble in cold water.

In the liquid anhydrous form hydrofluoric acid boils at $+19^\circ$, and its sp. gr. at $12.8^\circ = 0.9849$.⁵¹ It dissolves in water with the evolution of a considerable amount of heat, and gives a solution of constant boiling point which distils over at 120° ; hence the acid is able to combine with water. The specific gravity of the compound is 1.15, and its composition $\text{HF}, 2\text{H}_2\text{O}$.⁵² With an excess of water a dilute solution first distils over. The aqueous solution and the acid itself must be kept in platinum vessels, but the dilute acid may be conveniently preserved in vessels made of various organic materials, such as gutta-percha, or even in glass vessels having an interior coating of paraffin. Hydrofluoric acid does not act on hydrocarbons and many other substances, but it acts in a highly corrosive manner on metals, glass, porcelain, and the majority of rock substances.⁵³ It also corrodes the skin,

⁵¹ According to Gore, hydrofluoric acid remains liquid when cooled to -34° . Fremy obtained anhydrous hydrofluoric acid by decomposing lead fluoride at a red heat, by hydrogen, or by heating the double salt HKF_2 , which easily crystallises (in cubes) from a solution of hydrofluoric acid, half of which has been saturated with potassium hydroxide, or carbonate.

⁵² This composition corresponds with the crystallo-hydrate $\text{HCl}, 2\text{H}_2\text{O}$. All the properties of hydrofluoric acid call to mind those of hydrochloric acid, and therefore the comparative ease with which hydrofluoric acid is liquefied (it boils at $+19^\circ$, hydrochloric acid at -35°), must be explained by a polymerisation taking place at low temperatures, as will be afterwards explained, H_2F_2 , being formed, and therefore in a liquid state it differs from hydrochloric acid, for which a phenomenon of a similar kind has not yet been observed.

⁵³ The corrosive action of hydrofluoric acid on glass and similar siliceous compounds is based upon the fact that it acts on silica, SiO_2 , as we shall consider more fully in describing that compound, forming gaseous silicon fluoride, $\text{SiO}_2 + 4\text{HF} = \text{SiF}_4 + 2\text{H}_2\text{O}$. Silica, on the other hand, forms the binding (acid) element of glass and of the mass of mineral substances forming the salts of silica. When it is removed the bond is destroyed. This is made use of in practice, and the laboratory, for etching designs and scales, &c., on glass. In *engraving on glass* the surface is covered with a varnish composed of four parts of wax and one part of turpentine. This varnish is not acted on by

and is distinguished by its poisonous properties, so that in working with the acid a strong draught must be kept up, to prevent the possibility of the fumes being inhaled. The non-metals do not act on hydrofluoric acid, but all metals—with the exception of mercury, silver, gold, and platinum, and, to a certain degree, lead—decompose it with the evolution of gaseous hydrogen. With bases it directly gives metallic fluorides, and behaves in many respects like hydrochloric acid. There are, however, several distinct individual differences, which are furthermore much greater than those between hydrochloric, hydrobromic, and hydriodic acids. Thus the silver compounds of the latter are insoluble in water, whilst silver fluoride is moderately soluble. Calcium fluoride, on the contrary, is insoluble in water, whilst calcium chloride, bromide, and iodide are not only soluble, but attract water with great energy, owing to which gases are frequently dried by passing them over calcium chloride. Neither hydrochloric, nor hydrobromic, nor hydriodic acid acts on sand and glass, whilst hydrofluoric acid corrodes them, forming gaseous silicon fluoride. The other halogen acids only form normal salts, KCl , NaCl , with Na or K , whilst hydrofluoric acid gives acid salts, for instance HKF_2 (and by dissolving KF in liquid HF , $\text{KHF}_2 \cdot 2\text{HF}$ is obtained). This latter property is in close connection with the fact that at the ordinary temperature the vapour density of hydrofluoric acid is nearly 20, which corresponds with a formula H_2F_2 , as Mallet (1881) showed; but a depolymerisation occurs with a rise of temperature, and the density approaches 10, which answers to the formula HF .⁵⁴

The analogy between chlorine and the other two halogens, bromine

hydrofluoric acid, and it is soft enough to allow designs being drawn upon it whose lines lay bare the glass. The drawing is made with a steel point, and the glass is afterwards laid in a lead trough in which a mixture of fluor spar and sulphuric acid is placed. The sulphuric acid must be taken in considerable excess, as otherwise transparent lines are obtained (owing to the formation of hydrofluosilicic acid). After being exposed for some time, the varnish is removed (melted), and the design drawn by the steel point is found reproduced in dull lines. The drawing may be also made by the direct application of a mixture of a silicofluoride and sulphuric acid, which forms hydrofluoric acid. In the laboratory a solution of hydrofluoric acid or its fumes is employed for decomposing siliceous substances which are insoluble in ordinary acids, or else they are fused with the salts KHF_2 or NH_4F .

⁵⁴ Mallet (1881) determined the density at 30° and 100° , previous to which Gore (1869) had determined the vapour density at 100° , whilst Thorpe and Hambly (1888) made fourteen determinations between 26° and 88° , and showed that within this limit of temperature the density gradually diminishes, just like the vapour of acetic acid. The capacity of HF to polymerise into H_2F_2 is probably connected with the property of many fluorides of forming acids with HF —for example, KHF_2 and H_2SiF_6 . We saw above that HCl has the same property (forming, for instance, H_2PtCl_6 , &c., p. 450), and hence this property of hydrofluoric acid does not stand isolated from the properties of the other halogens.

and iodine, is much more perfect. Not only have their hydrates or halogen acids much in common, but they themselves resemble chlorine in many respects,⁵⁵ and even the properties of the corresponding metallic compounds of bromine and iodine are very much alike. Thus the chlorides, bromides, and iodides of sodium and potassium crystallise in the cubic system, and are soluble in water; the chlorides of calcium, aluminium, magnesium, and barium are soluble in water, like the bromides and iodides of these metals. The iodides and bromides of silver and lead are sparingly soluble in water, like the chlorides of these metals. Besides which even the oxygen compounds of bromine and iodine present a very strong analogy to the corresponding compounds of chlorine. A hypobromous acid is known corresponding with hypochlorous acid. The salts of this acid have the same bleaching property

⁵⁵ For instance, the experiment with Dutch metal foil (Note 16) may be made with bromine just as well as with chlorine. A very instructive experiment on the direct combination of the halogens with metals may be made by throwing a small piece (a shaving) of aluminium into a vessel containing liquid bromine; the aluminium, being lighter, floats on the bromine, and after a certain time reaction sets in accompanied by the evolution of heat, light, and fumes of bromine. The incandescent piece of metal moves rapidly over the surface of the bromine in which the resultant aluminium bromide is dissolved. It was in this manner that Gustavson prepared that mixture of bromine and aluminium bromide which reacts by metalepsis with the greatest ease in those cases when bromine by itself is not able to bring about metalepsis, or else only acts very slowly, as, for instance, with benzene, C_6H_6 . When drops of this hydrocarbon are added to bromine containing aluminium bromide, they immediately give a mass of hydrobromic acid and of the product of metalepsis. Gustavson showed that the cause of this facility of reaction must be looked for in the capacity of aluminium bromide to form an unstable compound with the products of reaction which are formed. For the sake of comparison we will proceed to cite several thermochemical data (Thomsen) for analogous actions of (1) chlorine, (2) bromine, and (3) iodine, with respect to metals; the halogen being expressed by the symbol X, and the sign plus connecting the reacting substances. All the figures are given in thousands of calories, and refer to molecular quantities in grams and to the ordinary temperature:—

	1	2	3
$K_2 + X_2$	211	191	160
$Na_2 + X_2$	195	172	138
$Ag_2 + X_2$	59	45	28
$Hg_2 + X_2$	83	68	48
$Hg + X_2$	63	51	34
$Ca + X_2$	170	141	—
$Ba + X_2$	195	170	—
$Zn + X_2$	97	76	49
$Pb + X_2$	83	64	40
$Al + X_3$	161	120	70

We may remark that the latent heat of vaporisation of the molecular weight Br_2 is about 7.2, and of iodine 6.0 thousand heat units, whilst the latent heat of fusion of Br_2 is about 0.3, and of I_2 about 3.0 thousand heat units. From this it is evident that the difference between the amounts of heat evolved does not depend on the difference in physical state. For instance, the vapour of iodine in combining with Zn to form ZnI_2 would give $48 + 8 + 3$, or about sixty thousand heat units, or $1\frac{1}{2}$ times less than $Zn + Cl_2$.

as the salts of hypochlorous acid. The higher oxygen acids of iodine, bromine, and chlorine are closely analogous to each other. Iodine was discovered in 1811 by Courtois in kelp, and was soon investigated by Clement, Gay-Lussac, and Davy. Bromine was discovered in 1826 by Balard in the mother liquor of sea water.

Bromine and iodine, like chlorine, occur in sea water in combination with metals. However, the amount of bromides, and especially of iodides, in sea water is so small that their presence can only be discovered by means of sensitive reactions.⁵⁶ In the extraction of salt from sea water the bromides remain in the mother liquor, and can be obtained therefrom; this method is, however, rarely employed on a large scale, as other and richer sources are known for the extraction of this substance. Iodine and bromine also occur combined with silver, in admixture with silver chloride, as a rare ore which is mainly found in America. Certain mineral waters (those of Kreuznach and Schönebeck) contain metallic bromides and iodides, always in admixture with an excess of sodium chloride. Those upper strata of the Stassfurt rock salt (Chapter X.) which are a source of potassium salts also contain metallic bromides,⁵⁷ which collect in the mother liquors left after the crystallisation of the potassium salts; and this now forms the chief source (together with certain American springs) of the bromine in common use. Bromine may be easily liberated from a mixture of bromides and chlorides, owing to the fact that chlorine displaces bromine from its compounds with sodium, magnesium, calcium, &c. A colourless solution of bromides and chlorides turns an orange colour after the passage of chlorine, owing to the disengagement of bromine.⁵⁸ Bromine may be extracted on a large scale by a similar method, but it

⁵⁶ One litre of sea water contains about 20 grams of chlorine, and about 0.07 grams of bromine. The Dead Sea contains about ten times as much.

⁵⁷ But there is no iodine in Stassfurt carnallite.

⁵⁸ The chlorine must not, however, be in large excess, as otherwise the bromine would contain chlorine. Commercial bromine not unfrequently contains chlorine, as bromine chloride; this is more soluble in water than bromine, which may thus be freed from it. To obtain pure bromine the commercial bromine is washed with water, dried by sulphuric acid, and distilled, the portion coming over at 58° being collected; the greater part is then converted into potassium bromide and dissolved, and the remainder is added to the solution in order to separate iodine, which is removed by shaking with carbon bisulphide. By heating the potassium bromide thus obtained with manganese peroxide and sulphuric acid, bromine is obtained quite free from iodine, which, however, is not present in certain kinds of commercial bromine (the Stassfurt, for instance). By treatment with potash, the bromine is then converted into a mixture of potassium bromide and bromate, and the mixture (which is in the proportion given in the equation) is distilled with sulphuric acid, bromine being then evolved: $5\text{KBr} + \text{KBrO}_3 + 6\text{H}_2\text{SO}_4 = 6\text{KHSO}_4 + 3\text{H}_2\text{O} + 3\text{Br}_2$. After dissolving the bromine in a strong solution of calcium bromide and precipitating with an excess of water, it loses all the chlorine it contained, because chlorine forms calcium chloride with CaBr_2 .

is simpler to add a small quantity of manganese peroxide and sulphuric acid to the mother liquid direct. This sets free a portion of the chlorine, and this chlorine liberates the bromine. Bromine is a *dark brown liquid*, giving brown fumes, and having a poisonous suffocating smell, from whence its name (from the Greek $\beta\rho\omega\mu\omicron\varsigma$, signifying evil smelling). The vapour density of bromine shows that its molecule is Br_2 . In the cold bromine freezes into brown-grey scales like iodine. The melting point of pure bromine is -7.05° .⁵⁹ The density of liquid bromine at 0° is 3.187, and at 15° about 3.0. The boiling point of bromine is about 58.7° ; it is generally purified by distillation. Bromine, like chlorine, is soluble in water; 1 part of bromine at 5° requires 27 parts of water, and at 15° 29 parts of water. The aqueous solution of bromine is of an orange colour, and when cooled to -2° yields crystals containing 10 molecules of water to 1 molecule of bromine.⁶⁰ Alcohol dissolves a

⁵⁹ There has long existed a difference of opinion as to the melting point of pure bromine. By some (Regnault, Pierre) it was given as between -7° and -8° , and by others (Balard, Liebig, Quincke, Baumhauer) as between -20° and -25° . There is now no doubt, thanks more especially to the researches of Ramsay and Young (1885), that pure bromine melts at about -7° . This figure is not only established by direct experiment (Van der Plaats confirmed it) but also by means of the determination of the vapour tensions. For solid bromine the vapour tension p , in mm. at t was found to be—

$p =$	20	25	30	35	40	45 mm.
$t =$	-16.6°	-14°	-12°	-10°	-8.5°	-7°

For liquid bromine—

$p =$	50	100	200	400	600	760 mm.
$t =$	-5.0°	$+8.2^\circ$	28.4°	40.4°	51.9°	58.7°

These curves intersect at -7.05 . Besides which, in comparing the vapour tension of many liquids (for example, those given in Chapter II. Note 27), Ramsay and Young observed that the ratio of the absolute temperatures ($t+273$) corresponding with equal tension *varies* for every pair of substances in rectilinear proportion in dependence upon t , and, therefore, for the above pressure p , Ramsay and Young determined the ratio of $t+273$ for water and bromine, and found that the straight lines expressing these ratios for liquid and solid bromine intersect also at 7.05 ; thus, for example, for solid bromine—

$p =$	20	25	30	35	40	45
$273+t =$	256.4	259	261	263	264.6	266
$273+t' =$	295.3	299	302.1	304.8	307.2	309.3
$c =$	1.152	1.154	1.157	1.159	1.161	1.163

where t' indicates the temperature of water corresponding with a vapour tension p , and where c is the ratio of $273+t'$ to $273+t$. The magnitude of c is evidently expressed with great accuracy by the straight line $c = 1.1703 + 0.0011t$. In exactly the same way we find the ratio for liquid bromine and water to be $c_1 = 1.1585 - 0.00057t$. The intersection of these straight lines in fact corresponds with -7.06° , which again confirms the melting point given above for bromine. In this manner it is possible with the existing store of data to accurately establish and *verify* the melting point of substances. Ramsay and Young established the thermal constants of iodine by exactly the same method.

⁶⁰ The observations made by Paterno and Nasini (by Raoult's method, Chapter I. Note 49) on the temperature of the formation of ice (-1.115° , with 1.391 grams of bromine

greater quantity of bromine, and ether a still greater amount. But after a certain time products of the action of the bromine on these organic substances are formed in the solutions. Aqueous solutions of the bromides also absorb a large amount of bromine.

With respect to *iodine*, it is almost exclusively extracted from the mother liquors after the crystallisation of natural sodium nitrate (Chili saltpetre) and the ashes of the sea-weed cast upon the shores of France, Great Britain, and Spain, sometimes in considerable quantities, by the high tides. The majority of these sea-weeds are of the genera *Fucus*, *Laminaria*, &c. The fused ashes of these sea-weeds are called 'kelp' in Scotland and 'varec' in Normandy. A somewhat considerable quantity of iodine is contained in these sea-weeds. After being burnt (or subjected to dry distillation) an ash is left which chiefly contains salts of potassium, sodium, and calcium. The metals occur in the sea-weed as salts of organic acids. On being burnt these organic salts are decomposed, forming carbonates of potassium and sodium. Hence, sodium carbonate is found in the ash of sea plants. The ash is dissolved in hot water, and on evaporation sodium carbonate and other salts separate, but a portion of the substances remains in solution. These mother liquors left after the separation of the sodium carbonate contain chlorine, bromine, and iodine in combination with metals, the chlorine and iodine being in excess of the bromine. 13000 kilos. of kelp give about 1000 kilos. of sodium carbonate and 15 kilos. of iodine.

The liberation of the iodine from the mother liquor is accomplished with comparative ease, because chlorine disengages iodine from potassium iodide and its other combinations with the metals. Not only chlorine, but also sulphuric acid, liberates iodine from sodium iodide. Sulphuric acid, in acting on an iodide, sets hydriodic acid free, but the latter easily decomposes, especially in the presence of substances capable of evolving oxygen, such as chromic acid, nitrous acid, and even ferric salts.⁶¹ Owing to its sparing solubility in water, the iodine liberated

in 100 grams of water) in an aqueous solution of bromine, showed that bromine is contained in solutions as the molecule Br_2 . Similar experiments conducted on iodine show that the molecule in different solvents is of different complexity.

B. Roozeboom investigated the hydrate of bromine as completely as the hydrate of chlorine (Notes 9, 10). The temperature of the complete decomposition of the hydrate is $+6.2^\circ$; the density of $\text{Br}_2 \cdot 10\text{H}_2\text{O} = 1.49$.

⁶¹ In general, $2\text{HI} + \text{O} = \text{I}_2 + \text{H}_2\text{O}$, if the oxygen proceed from a substance from which it is easily evolved. For this reason compounds corresponding with the higher stages of oxidation or chlorination frequently give a lower stage when treated with hydriodic acid. Ferric oxide, Fe_2O_3 , is a higher oxide, and ferrous oxide, FeO , a lower oxide; the former corresponds with FeX_3 , and the latter with FeX_2 , and this passage from the higher to the lower takes place under the action of hydriodic acid. Thus hydrogen peroxide and ozone (Chapter IV.) are able to liberate iodine from hydriodic acid. Compounds of copper oxide, CuO or CuX_2 , give compounds of the suboxide Cu_2O , or CuX . Even sulphuric acid,

separates as a precipitate. To obtain pure iodine it is enough to distil it, and neglect the first and last portions of the distillate, the middle portion only being collected. Iodine passes directly from a state of vapour into a crystalline form, and settles on the cool portions of the apparatus in tabular crystals, having a black grey colour and metallic lustre.⁶²

The specific gravity of the crystals of iodine is 4.95. It melts at 114° and boils at 184° . Its vapour is formed at a much lower temperature, and is of a violet colour, from whence iodine receives its name. The smell of iodine calls to mind the characteristic smell of hypochlorous acid; it has a sharp sour taste. It destroys the skin and organs of the body, and is therefore frequently employed for cauterising and as an irritant for the skin. In small quantities it turns the skin brown, but the coloration disappears after a certain time, partly owing to the volatility of the iodine. Water dissolves only $\frac{1}{5000}$ part of iodine. A brown solution is thus obtained, which bleaches, but much more feebly than bromine and chlorine. Water which contains salts, and especially iodides, in solution dissolves iodine in considerable quantities, and the resultant solution is of a dark brown colour. Pure alcohol dissolves a small amount of iodine, and in so doing acquires a brown colour, but the solubility of iodine is considerably increased by the presence of a small quantity of an iodine compound—for instance, ethyl iodide—in the alcohol.⁶³ Ether dissolves a larger amount of iodine than alcohol; but

which corresponds to the higher stage SO_5 , is able to act thus, forming the lower oxide SO_2 . The liberation of iodine from hydriodic acid proceeds with still greater ease under the action of substances capable of disengaging oxygen. In practice, many methods are employed for liberating iodine from acid liquids containing, for example, sulphuric acid and hydriodic acid. The higher oxides of nitrogen are most commonly used; they then pass into nitric oxide. Iodine may even be disengaged from hydriodic acid by the action of iodic acid, &c. But there is a limit in these reactions of the oxidation of hydriodic acid because, under certain conditions, especially in dilute solutions, the iodine set free is itself able to act as an oxidising agent—that is, it evinces in itself the character of chlorine, and of the halogens in general, to which we shall again have occasion to refer.

⁶² For the ultimate purification of iodine, Stas dissolves it in a strong solution of potassium iodide, and precipitates it by the addition of water (*see* Note 58).

⁶³ The solubility of iodine in solutions containing oxides, and compounds of iodine in general, may serve, on the one hand, as an indication that solution is called forth by analogy (p. 70), and, on the other hand, as an indirect proof of that view as to solutions which was cited in Chapter I., because in many instances unstable highly-iodised compounds, resembling crystallo-hydrates, have been obtained from such solutions. Thus iodide of tetramethylammonium $\text{N}(\text{CH}_3)_4\text{I}$, combines with I_2 and I_4 . Even a solution of iodine in a saturated solution of potassium iodide presents traces of the formation of a definite compound KI_5 . Thus, an alcoholic solution of KI_5 does not give up iodine to carbon bisulphide, although this solvent takes up iodine from an alcoholic solution of iodine itself (Girault, Jørgensen, and others). The instability of these compounds resembles the instability of many crystallo-hydrates, for instance of $\text{HCl} \cdot 2\text{H}_2\text{O}$.

iodine is particularly soluble in liquid hydrocarbons, in carbon bisulphide, and in chloroform. A small quantity of iodine dissolved in carbon bisulphide tints it rose-colour, but in a somewhat larger amount it gives a violet colour. Chloroform (quite free from alcohol) is also tinted rose colour by a small amount of iodine. This gives an easy means for detecting the presence of free iodine in small quantities. The coloration which free iodine gives with *starch* may, also, as has already been frequently mentioned, serve for the detection of iodine.

If we compare the four elements, fluorine, chlorine, bromine, and iodine, we see in them an example of analogous substances which arrange themselves by their physical properties in the same order as they stand in respect to their atomic and molecular weights. If the weight of the molecule be large, the substance has a higher specific gravity, a higher melting and boiling point, and a whole series of properties depending on this difference in its fundamental properties. A large atomic weight should determine a larger affinity between the molecules, and consequently a greater difficulty in their division and a greater attraction between them. We meet a very evident example in question in polymeric compounds; for instance, in the hydrocarbons expressed by the formula, C_nH_{2n} : C_2H_4 , C_3H_6 are gases, those having a greater molecular weight—for instance, C_5H_{10} , C_7H_{14} , &c.—are liquids, and those of a still greater molecular weight are solids. The same relation is found in the above-named four elements. Chlorine in a free state boils at about -35° , bromine boils at 60° , and iodine only above 180° . According to Avogadro-Gerhardt's law, the vapour densities of these elements in a gaseous state are proportional to their atomic weights, and here, at all events approximately, the densities in a liquid (solid) state are also almost in the ratio of their atomic weights. Dividing the atomic weight of chlorine (35.5) by its sp. gr. in a liquid state (1.3), we obtain a volume = 27, for bromine ($80/3.1$) 26, as also for iodine ($127/4.9$) 26.⁶⁴

The metallic bromides and iodides are in the majority of cases and

⁶⁴ The equality of the atomic volumes of the halogens themselves is all the more remarkable because in all the halogen compounds the volume augments with the substitution of fluorine by chlorine, bromine, and iodine. Thus, for example, the volume of sodium fluoride (obtained by dividing the weight expressed by its formula by its specific gravity) is about 15, of sodium chloride 27, of sodium bromide 32, and of sodium iodide 41. The volume of silicon chloroform, $SiHCl_3$, and of the corresponding bromine and iodine compounds, are 82, 108, and 122 respectively. So in solutions, for example $NaCl + 200H_2O$ has a sp. gr. (at $15^\circ 4'$) of 1.0106, consequently the volume of the solution $3658.5/1.0106 = 3620$, hence the volume of sodium chloride in solution = $3620 - 3603$ (this is the vol. of $200 H_2O$) = 17. So also in similar solutions, $NaBr = 26$ and $NaI = 35$.

respects analogous to the corresponding chlorides,⁶⁵ but chlorine displaces the bromine and iodine from them, and bromine liberates iodine from iodides, which is taken advantage of in the preparation of these halogens. However, the researches of Potilitzin showed that a *reverse* displacement of chlorine by bromine may occur both in solutions of and in ignited metallic chlorides in an atmosphere of bromine vapour—that is, a distribution of the metal (according to Berthollet's doctrine) takes place between the halogens, although, however, the larger portion still unites with the chlorine, which shows its greater affinity for metals as compared with that of bromine and iodine.⁶⁶ The latter, however,

⁶⁵ But the density (and even volume, Note 64) of a bromine compound is always greater than that of a chlorine compound, whilst that of an iodine compound is still greater. The order is the same in many other respects. For example, an iodine compound has a higher boiling point than a bromine compound, &c.

⁶⁶ A. L. Potilitzin showed that in heating various metallic chlorides in a closed tube, with an equivalent quantity of bromine, a distribution of the metal between the halogens always occurs, and that the amounts of chlorine replaced by the bromine in the ultimate product are proportional to the atomic weights of the metals taken and inversely proportional to their equivalency. Thus, if $\text{NaCl} + \text{Br}$ be taken, then out of 100 parts of chlorine, 5.54 are replaced by the bromine, whilst if $\text{AgCl} + \text{Br}$ be taken, the 27.28 parts are replaced. These figures are in the ratio 1 : 4.9, but the atomic weights $\text{Na} : \text{Ag} = 1 : 4.7$. In general terms, if a chloride MCl_n be taken, then it gives with $n\text{Br}$ a percentage substitution $= 4\text{M} / n^2$, where M is the atomic weight of the metal. This law was deduced from observations on the chlorides of Li, K, Na, Ag ($n=1$), Ca, Sr, Ba, Co, Ni, Hg, Pb ($n=2$), Bi ($n=3$), Sn ($n=4$), and Fe_2 ($n=6$).

In these determinations of Potilitzin we see not only a brilliant confirmation of Berthollet's doctrine, but also the first effort (there have been no similar determinations since 1879) to directly determine the affinities of elements by means of displacement. The chief object of these researches consisted in proving whether a displacement occurs in those cases where heat is absorbed, and in this instance it should be absorbed, because the formation of all metallic bromides is attended with the evolution of less heat than that of the chlorides, as is seen by the figures given in Note 55. Among the results of other researches made by Potilitzin in the same direction, it is necessary to turn attention to the following.

If the mass of the bromine be increased, then the amount of chlorine displaced also increases. For example, if masses of bromine of 1 and 4 equivalents act on a molecule of sodium chloride, then the percentages of the chlorine displaced will be 6.08 p.c. and 12.46 p.c.; in the action of 1, 4, 9, 16, 25, and 100 molecules of bromine on a molecule of barium chloride, there will be displaced 7.8, 17.6, 23.5, 31.0, 35.0, and 45.0 p.c. of chlorine. If an equivalent quantity of hydrochloric acid act on metallic bromides in closed tubes, and in the absence of water at a temperature of 360° , then the percentages of the substitution of the bromine by the chlorine in the double decomposition taking place between univalent metals are inversely proportional to their atomic weights. For example, $\text{NaBr} + \text{HCl}$ gives at the limit 21 p.c. of displacement, KCl 12 p.c. and AgCl 14½ p.c. Essentially the same takes place in an aqueous solution, although the phenomena is complicated by the participation of the water. The reactions proceed of themselves in one or the other direction at the ordinary temperature but at different *rates*. In the action of a dilute solution (1 equivalent per 5 litres) of sodium chloride on silver bromide at the ordinary temperature, 2.07 p.c. of bromine is replaced in six and a half days, with potassium chloride 1.5 p.c. With an excess of the chloride the magnitude of the substitution increases; with four equivalents it is 4.95 p.c. in nine days. In the action of 9 grams of sodium chloride on 1.1 grams of silver bromide, 9.69 p.c. of bromine is replaced in thirteen days.

sometimes behave with respect to metallic oxides in exactly the same manner as chlorine. Gay-Lussac, by igniting potassium carbonate in iodine vapour, obtained (as with chlorine) an evolution of oxygen and carbonic anhydride, $K_2CO_3 + I_2 = 2KI + CO_2 + O$, only the reactions between the halogens and oxygen are more easily reversible with bromine and iodine than with chlorine. Thus, at a red heat oxygen displaces iodine from barium iodide (besides which the reaction is here complicated by iodine being more easily oxidised than chlorine). Aluminium iodide burns in a current of oxygen (Deville and Troost), and a similar, although not so highly developed, relation exists for aluminium chloride, and shows that the halogens have a distinctly smaller affinity for metals which only form feeble bases. This refers to a still greater extent to non-metals, which form acids and evolve much more heat with oxygen than the halogens. But in all these instances the affinity (and amount of heat evolved) of iodine and bromine is less than that of chlorine, probably because the atomic weights are greater, whilst the properties of the atoms of all the halogens are analogous. The smaller store of energy in iodine and bromine is seen still more clearly in the relation of the halogens to hydrogen. In a gaseous state they all enter, with more or less ease, into direct combination with gaseous hydrogen—for example, in the presence of spongy platinum, forming halogen acids, HX but the latter are far from being equally stable; hydrogen chloride is the most stable, hydrogen iodide the least so, and hydrogen bromide occupies an intermediate position. A very strong heat is required to only partially decompose hydrogen chloride,

These conversions also proceed with the absorption of heat. The reverse reactions evolving heat proceed incomparably more rapidly, but also to a certain limit; for example, in the reaction $AgCl + RBr$ the following percentages of silver bromide are formed in different times:

hours	2	3	22	96	120
K	79.82	87.4	88.22	—	94.21
Na	83.63	90.74	91.70	95.49	—

Consequently, the conversions which are accompanied by this evolution of heat proceed with very much greater rapidity than the reverse conversions. If the rates at the commencement of the first reactions be placed side by side with the amounts of heat evolved by them, then a perfect conformity is seen to exist between the data. In the reaction between $AgCl$ and KBr 3.5 thousand heat units are evolved, and the rate of this reaction in the first two hours is expressed by the formation of 79.8 p.c. of bromide of silver; if $NaBr$ act on $AgCl$, then 4.3 thousand heat units are evolved, and the rate during the first two hours is 83.2 p.c. This conformity between the rate of reaction and the thermal figures is also remarked for other compounds. This shows that the thermal figures are not equivalent to the entire work of affinity, but are only proportional to the first rates of reactions. This explains why it is possible upon their basis to foresee the direction of the dominating reaction in a complex medium, but impossible to foretell in what direction the reaction will proceed.

whilst hydrogen iodide is decomposed by light at even the ordinary temperature, and very easily by a red heat. And therefore the reaction $I_2 + H_2 = HI + HI$ is very easily reversible, and consequently has a limit, and hydrogen iodide easily dissociates.⁶⁷ Judging by the direct measurement of the heat evolved, the conversion of $2HCl$ into $H_2 + Cl_2$ requires the expenditure of 44000 heat units (because the formation of HCl evolves 22000 heat units). The decomposition of $2HBr$ into $H_2 + Br_2$ requires, if the bromine is obtained in a gaseous state, a consumption of only about 24000 units, and in the decomposition of $2HI$ into $H_2 + I_2$ as vapour about 3000 heat units are evolved,⁶⁸ which, without doubt, stands in causal connection with the great

⁶⁷ The dissociation of hydriodic acid has been studied in detail by Hautefeuille and Lemoine, from whose researches we will extract the following information. The decomposition of hydriodic acid is distinct, but proceeds slowly at 180° ; the rate and limit of decomposition increases with a rise of temperature. The reverse action is the same—that is, $I_2 + H_2$ forms $2HI$, not only under the influence of spongy platinum (Corenwinder), which also accelerates the decomposition of hydriodic acid, but it also proceeds by itself, although slowly. The limit of the reverse reaction remains the same with or without spongy platinum. An increase of pressure has a very powerful accelerative effect on the rate of the reaction of the formation of hydriodic acid, and therefore spongy platinum by condensing gases has the same effect as increase of pressure. At the atmospheric pressure the decomposition of hydriodic acid reaches the below-mentioned limit at 250° in several months, and at 440° in several hours. The limit at 250° is about 18 p.c. of decomposition—that is, out of 100 parts of hydrogen previously combined in hydriodic acid, about 10 p.c. may be disengaged at this temperature (this hydrogen may be easily measured, and the measure of dissociation determined), but not more; the limit at 440° is about 26 p.c. If the pressure under which $2HI$ passes into $H_2 + I_2$ be $4\frac{1}{2}$ atmospheres, then the limit is 24 p.c.; under a pressure of $\frac{1}{2}$ atmosphere the limit is 29 p.c. The small influence of pressure on the dissociation of hydriodic acid (compared with N_2O_2 , Chap. VI. Note 46) is due to the fact that the reaction $2HI = I_2 + H_2$ is not accompanied by a change of volume, and probably the existing differences are determined by deviations from Boyle-Mariotte's law. In order to show the influence of time, we will cite the following figures referring to 350° : 1. Reaction $H_2 + I_2$, 3 hours, 88 p.c. of hydrogen remained free; 8 hours, 69 p.c.; 34 hours, 48 p.c.; 76 hours, 29 p.c.; and 327 hours, 18.5 p.c. of hydrogen remained in a free state. 2. The reverse decomposition of $2HI$, 9 hours, 3 p.c. of hydrogen set free, and after 250 hours 18.6 p.c. of hydrogen became free—that is, the limit was reached. The addition of extraneous hydrogen diminishes the limit of the reaction of decomposition, or increases the formation of hydriodic acid from iodine and hydrogen, as would be expected from Berthollet's doctrine (Chap. X.). Thus at 440° 26 p.c. of hydriodic acid is decomposed if there be no admixture of hydrogen, while if H_2 be added, then at the limit half as small a mass of HI is decomposed. Therefore, if an infinite mass of hydrogen be taken there will be no decomposition of the hydriodic acid. Light aids the decomposition of hydriodic acid very powerfully. At the ordinary temperature 80 p.c. is decomposed under the influence of light, whilst under the influence of heat alone this limit corresponds with a very high temperature. The distinct action of light, spongy platinum, and of imperfect cleanliness in glass (especially of sodium sulphate, which destroys hydriodic acid), not only render the investigations difficult, but also show that in reactions like $2HI = I_2 + H_2$, which are accompanied by slight heat effects, all foreign and feeble influences may deeply affect the process of the phenomenon (Note 47).

⁶⁸ The thermal determinations of Thomsen (at 18°) gave in thousands of calories, $Cl + H = +22$, $HCl + Aq$ (that is, a large amount of water dissolves HCl) = $+17.3$, and

stability of hydrogen chloride, the easy decomposability of hydrogen iodide, and the intermediate properties of hydrogen bromide. From this it would be expected that chlorine is capable of decomposing water with the evolution of oxygen, whilst iodine has not the energy to produce this disengagement,⁶⁹ although it is able to liberate the oxygen from the oxides of potassium and sodium, as the affinity of these metals for the halogens is very considerable. For this reason oxygen, especially in compounds from which it can be evolved (for instance, ClHO , CrO_3 , &c.), easily decomposes hydrogen iodide. A mixture of hydrogen iodide and oxygen burns in the presence of an ignited substance, forming water and iodine. Drops of nitric acid in an atmosphere of hydrogen iodide produce the disengagement of violet fumes of iodine and brown fumes of nitric peroxide. In the presence of alkalis and an excess of water, however, iodine is able to produce oxidation like chlorine—that is, it decomposes water; the action is here aided by the affinity of hydrogen iodide for the alkali and water, just as sulphuric acid helps zinc to decompose water. But the relative instability of hydriodic acid is best seen in comparing the acids in a gaseous state. If the halogen acids be dissolved in water, they evolve so much heat that they approach much nearer to each other in properties. This is seen from thermochemical data, because in the formation of HX in solution (in a large excess of water) from the *gaseous* elements there is *evolved* for HCl 39000, for HBr 22000,

therefore $\text{H} + \text{Cl} + \text{Aq} = +39\cdot3$. In taking molecules, all these figures must be doubled. $\text{Br} + \text{H} = +8\cdot4$; $\text{HBr} + \text{Aq} = 19\cdot9$; $\text{H} + \text{Br} + \text{Aq} = +28\cdot3$. According to Berthelot $7\cdot2$ go to the vaporisation of Br_2 , hence $\text{Br}_2 + \text{H}_2 = 16\cdot8 + 7\cdot2 = +24$, if Br_2 be taken as vapour for comparison with Cl_2 . $\text{H} + \text{I} = -6\cdot0$, $\text{HI} + \text{Aq} = 19\cdot2$; $\text{H} + \text{I} + \text{Aq} = +13\cdot2$, and, according to Berthelot, the heat of fusion of $\text{I}_2 = 3\cdot0$, and of vaporisation $6\cdot0$ thousand heat units, and therefore $\text{I}_2 + \text{H}_2 = -2(6\cdot0) + 3 + 6 = -3\cdot0$, if the iodine be taken as vapour. Berthelot, on the basis of his determinations, gives, however, $+0\cdot8$ thousand heat units. Similar contradictory results are often met with in thermochemistry with the imperfection of the existing methods, and depend on the necessity of obtaining the fundamental figures by an indirect method. Thus Thomsen decomposed a dilute solution of potassium iodide by gaseous chlorine; the reaction gave $+26\cdot2$, whence, having first determined the heat effects of the reactions $\text{KHO} + \text{HCl}$, $\text{KHO} + \text{HI}$ and $\text{Cl} + \text{H}$ in aqueous solutions, it was possible to find $\text{H} + \text{I} + \text{Aq}$; then, knowing $\text{HI} + \text{Aq}$, to find $\text{I} + \text{H}$. It is evident that the unavoidable errors may multiply themselves.

⁶⁹ One would think, however, that on the basis of Berthollet's doctrine, and the observations of Potilitzin (Note 66), a certain trace of slow decomposition of water by iodine may exist. In this sense the observations of Dossios and Weith on the fact that the solubility of iodine in water increases after lapse of several months, will be comprehensible. Hydriodic acid is then formed, and it increases the solubility. If the iodine be extracted from such a solution by carbon bisulphide, then, as the authors showed, after the action of nitrous anhydride, iodine may be again found in the solution by means of starch. One can easily imagine that a number of like reactions, requiring much time and taking place in small quantities, have up to now eluded the attention of investigators who even still doubt the universal application of Berthollet's doctrine, or only see the thermochemical side of reactions, or else neglect to pay attention to the element of time and the influence of mass.

and for HI 18000 heat units.⁷⁰ But this is especially evident from the fact that solutions of hydrogen bromide and iodide in water have many points in common with solutions of hydrogen chloride, both in their capacity to form hydrates, fuming solutions of constant boiling point, and in their capacity to form haloid salts, &c., by reacting on bases.

In consequence of what has been said above, it follows that *hydrobromic and hydriodic acids*, being substances which are but slightly stable, cannot be evolved in a gaseous state under many of those conditions under which hydrochloric acid is formed. Thus if sulphuric acid in solution acts on sodium iodide, all the same phenomena take place as with sodium chloride (a portion of the sodium iodide gives hydriodic acid, and all remains in solution), but if sodium iodide be mixed with strong sulphuric acid, then its oxygen decomposes the hydriodic acid set free with liberation of iodine, $\text{H}_2\text{SO}_4 + 2\text{HI} = 2\text{H}_2\text{O} + \text{SO}_2 + \text{I}_2$. This reaction proceeds in the reverse direction in the presence of a *mass* of water (2000 parts of water per 1 part of SO_2), in which not only the affinity of hydriodic acid for water evinces itself, but also the direct participation of water in the direction of chemical reactions accomplished through its medium.⁷¹ Therefore, having a halogen salt, it is easy to obtain gaseous hydrochloric acid (by the action of sulphuric acid), but neither hydrobromic nor hydriodic acid can be so obtained free (as gases).⁷² Other methods are requisite for their preparation ; but above all there must be conditions for the removal of oxygen, which is so easily able to destroy these acids. Therefore hydrogen sulphide, phosphorus, &c., which themselves easily take up oxygen, are introduced as means for the conversion of bromine and iodine into hydrobromic and hydriodic acids in the presence of water. For example, in the action of phosphorus the essence of the matter is that the oxygen of the water goes to the phosphorus, and the reaction of the remainders leads to the formation of hydrobromic or hydriodic acid ; but the matter is complicated by the reversibility of the reaction, the affinity for water, and other circumstances which are understood by following Berthollet's doctrine. Chlorine (also bromine) directly decomposes hydrogen sulphide, forming hydrochloric acid and liberating sulphur, both in a gaseous form and in solutions, whilst iodine only decomposes hydrogen sulphide in weak

⁷⁰ On the basis of the data in Note 68.

⁷¹ A number of like cases confirm what has been said in Notes 26 and 28 of Chapter X.

⁷² This is prevented by the reducibility of sulphuric acid. If volatile acids be taken they pass over, together with the hydrobromic and hydriodic acids, when distilled ; whilst many non-volatile acids which are not reduced by hydrobromic and hydriodic acids only act feebly (like phosphoric acid), or do not act at all (like boric acid).

solutions when its affinity for hydrogen is aided by the affinity of hydrogen iodide for water. In a gaseous state iodine does not act on hydrogen sulphide,⁷³ whilst sulphur is able to decompose gaseous hydriodic acid, forming hydrogen sulphide, and a compound of sulphur and iodine with which water forms hydriodic acid.⁷⁴

If hydrogen sulphide be passed through water containing iodine, the reaction $\text{H}_2\text{S} + \text{I}_2 = 2\text{HI} + \text{S}$ proceeds so long as the solution be dilute; or with a greater mass of iodine, so long as a solution of iodine in hydriodic acid having a composition of nearly $2\text{HI} + 4\text{I}_2 + 9\text{H}_2\text{O}$ (according to Bincau) be not formed. Hydrogen sulphide then no longer acts on such a solution, whatever be the mass of the free iodine. Therefore, only weak solutions of hydriodic acid can be obtained by passing hydrogen sulphide into water with iodine.^{74b}

To obtain⁷⁵ gaseous hydrobromic and hydriodic acids it is most

⁷³ This is in agreement with the thermochemical data, because if all the substances be taken in the gaseous state (for sulphur the heat of fusion is 0.3, and the heat of vaporisation 2.3) we have $\text{H}_2 + \text{S} = 4.7$; $\text{H}_2 + \text{Cl}_2 = 44$; $\text{H}_2 + \text{Br}_2 = 24$, and $\text{H}_2 + \text{I}_2 = -3000$ heat units; hence the formation of H_2S gives less heat than that of HCl and HBr , but more than that of HI . In dilute solutions $\text{H}_2 + \text{S} + \text{Aq} = 9.3$, and consequently less than the formation of all the halogen acids, as H_2S evolves but little heat with water, and therefore in dilute solutions chlorine, bromine, and iodine decompose hydrogen sulphide.

⁷⁴ Here there are three elements, hydrogen, sulphur, and iodine, each pair of which is able to form a compound, HI , H_2S , and SI , besides which the latter may unite in various proportions. The complexity of chemical mechanics is seen in such examples as these. It is evident that only the study of the simplest cases can give the key to the more complex problems, and, on the other hand, it is evident from the examples cited in the last pages that, without penetrating into the conditions of chemical equilibria, it would be impossible to explain chemical phenomena. By following the footsteps of Berthollet the possibility of unravelling the problem will be reached; but the work in this direction has only been begun during the last ten years, and much remains to be done by first collecting experimental material, for which occasions present themselves at every step. The new chemistry will without doubt place these problems to the fore. In speaking of the halogens I wished to turn the reader's attention to problems of this kind, and to the methods by which we may expect to arrive at their solution. However, owing to the limited space of this book, I am not able to touch on all the existing problems of this nature.

^{74b} The same essentially takes place when sulphurous anhydride, in a dilute solution, gives hydriodic acid and sulphuric acid with iodine. On concentration a reverse reaction proceeds. The equilibrated systems and the part played by water are everywhere distinctly seen.

⁷⁵ Methods of formation and preparation are nothing else but particular cases of chemical reaction. If the knowledge of chemical mechanics were more exact and complete than it is now it would be possible to foretell all cases of preparation *with every detail* (of the quantity of water, temperature, pressure, masses, &c.). The study of practical methods of preparation is therefore one of the paths for the study of chemical mechanics. The reaction of iodine on phosphorus and water is a case like that mentioned in Note 74, and the matter is here further complicated by the possibility of the formation of the compound PH_3 with HI , as well as the production of PI_3 , PI_5 , and the affinity of hydriodic acid and the acids of phosphorus for water. The theoretical interest of

convenient to take advantage of the reactions between phosphorus, the halogens, and water, when the latter is present in small quantity (otherwise the halogen acids formed are dissolved by the water), and the halogen is gradually added to the phosphorus moistened with water. Thus if red phosphorus be placed in a flask and moistened with water, and bromine be added drop by drop (from a closed funnel with a glass tap), hydrobromic acid is abundantly and uniformly disengaged.⁷⁶ Hydrogen iodide is prepared by adding 1 part of common (yellow) dry phosphorus to 10 parts of dry iodine in a glass flask. On revolving the flask, reaction (light and heat are evolved) proceeds quietly between them, and when the mass of the iodide of phosphorus which is formed has cooled, water is added drop by drop (from a funnel with a tap) and hydrogen iodide is evolved even without the aid of heat. These methods of preparation will be at once understood when it is remembered (p. 462) that phosphorus chloride gives hydrogen chloride with water. It is exactly the same here—the oxygen of the water passes over to the phosphorus, and the hydrogen to the iodine; for example, $\text{PI}_3 + 3\text{H}_2\text{O} = \text{PH}_3\text{O}_3 + 3\text{HI}$.⁷⁷

In a gaseous form hydrobromic and hydriodic acids are closely

equilibria in all their complexity is naturally very great, but it falls in the background before the primary interests of discovering practical methods for the isolation of substances, and the means of employing them for the requirements of man. It is only after the satisfaction of these requirements that interests of the other order arise, which themselves reflect the interests of the primary nature. For these reasons, whilst considering it opportune to point out the theoretical interests of chemical equilibria, the chief attention of the reader is directed in this work to the primary chemical interests.

⁷⁶ Hydrobromic acid is obtained by the action of bromine on paraffin heated to 180° . Gustavson proposed preparing it by the action of bromine (it is best if it be added in drops together with traces of aluminium bromide) on anthracene (a solid hydrocarbon from coal tar). Balard prepared it by passing bromine vapour over moist pieces of common phosphorus. The liquid tribromide of phosphorus, directly obtained from phosphorus and bromine, also gives hydrobromic acid when treated with water. Bromide of potassium or sodium, when treated with sulphuric acid in the presence of a piece of phosphorus, also gives hydrobromic acid, but hydriodic acid is decomposed by this method. In order to free hydrobromic acid from bromine vapour it is passed over moist phosphorus and dried either by phosphoric anhydride or calcium bromide (calcium chloride cannot be used, as hydrochloric acid would be formed). Neither hydrobromic nor hydriodic acids can be collected over mercury, on which they act, but they may be directly collected in a dry vessel by letting the gas-conducting tube pass down to the bottom of the vessel, both gases being much heavier than air.

⁷⁷ But, generally, more phosphorus is taken than is required for the formation of PI_3 , because, otherwise, a portion of the iodine is distilled over. If less than one-tenth part of iodine be taken, then much phosphonium iodide, PH_4I is formed. This proportion was established by Gay-Lussac and Kolbe. Hydriodic acid is also prepared in many other ways. Bannoff dissolves two parts of iodine in one part of a previously-prepared strong (sp. gr., 1.67) solution of hydriodic acid, and pours it on to red phosphorus in a retort. Personne takes a mixture of fifteen parts of water, ten of iodine, and one of red phosphorus, which, when heated, disengages hydriodic acid mixed with iodine vapour, which is removed by passing it over moist phosphorus (Note 76). It must be remembered,

analogous to hydrochloric acid ; they are liquefied by pressure and cold, they fume in the air, form solutions and hydrates of constant boiling point, and react on metals, oxides and salts, &c.⁷⁸ Only the relatively easy decomposability of hydrobromic acid, and especially of hydriodic acid, clearly distinguish these acids from hydrochloric acid. For this reason, hydriodic acid acts in a number of cases as a deoxidiser or reducer, and frequently even serves as a means for the transmission of hydrogen. Thus Berthelot, Baeyer, Wreden, and others, by heating unsaturated hydrocarbons in a solution of hydriodic acid, obtained their compounds with hydrogen nearer to the limit C_nH_{2n+2} or even the saturated compounds. For example, benzene, C_6H_6 , when heated in a closed tube with a strong solution of hydriodic acid, gives hexylene, C_6H_{12} . The easy decomposability of hydriodic acid accounts for the fact that iodine does not act by metalepsis on hydrocarbons, for the hydrogen iodide liberated with the product of metalepsis, RI , formed, gives iodine and the hydrogen compound, RH , back again. And therefore, to obtain the products of iodine substitution, either iodic acid, HIO_3 (Kekulé), or mercury oxide, HgO (Weselsky), is added, as they immediately react on the hydrogen iodide, thus : $HIO_3 + 5HI = 3H_2O + 3I_2$, or, $HgO + 2HI = HgI_2 + H_2O$. From these considerations it will be readily understood that iodine acts like chlorine (or bromine) on ammonia and sodium hydroxide, for in this case the hydriodic acid produced forms NH_4I and NaI . Thus with tincture of iodine, or even the solid element, a solution of ammonia immediately forms a highly-explosive

however, that reverse reaction (Oppenheim) may take place between the hydriodic acid and phosphorus, in which the compounds PH_4I and PI_3 are formed.

It should be observed that the reaction between phosphorus and iodine and water must be carried on in the above proportions and with caution, as they may react with explosion. With red phosphorus the reaction proceeds quietly, but nevertheless requires care.

L. Meyer showed that with an excess of iodine the reaction proceeds without the formation of bye-products (PH_4I), according to the equation $P + 5I + 4H_2O = PH_5OI + 5HI$. For this purpose 100 grams of iodine and 10 grams of water are placed in a retort, and a paste of 5 grams of red phosphorus and 10 grams of water is added little by little (at first with great care). The hydriodic acid may be obtained free from iodine by directing the neck of the retort upwards and causing the gas to pass through a shallow layer of water.

⁷⁸ The specific gravities of their solutions, as deduced by me (in my work, cited Note 20, Chapter X.) on the basis of Topsøe and Berthelot's determinations for $15^\circ/4^\circ$ are as follows:—

	10	20	30	40	50	60 p.c.
HBr	1·071	1·157	1·258	1·374	1·505	1·650
HI	1·075	1·164	1·267	1·399	1·567	1·769

Hydrobromic acid forms two hydrates, $HBr \cdot 2H_2O$ and $HBr \cdot H_2O$, which have been studied by Roozeboom with as much completeness as the hydrate of hydrochloric acid (Chapter X. Note 37).

With metallic silver, solutions of hydriodic acid give hydrogen with great ease, forming silver iodide. Mercury, lead, and other metals act in a like manner.

solid black product of metalepsis, generally known as *iodide of nitrogen*, although it probably contains hydrogen, $3\text{NH}_3 + 2\text{I}_2 = 2\text{NH}_4\text{I} + \text{NHI}_2$. However, the composition of the product is variable, and with an excess of water NI_3 seems to be formed. Iodide of nitrogen is no less explosive than nitrogen chloride. In the action of iodine on sodium hydroxide no bleaching compound is formed (whilst bromine gives one), but a direct reaction is always accomplished with the formation of an iodate $6\text{NaHO} + 3\text{I}_2 = 5\text{NaI} + 3\text{H}_2\text{O} + \text{NaIO}_3$ (Gay-Lussac). Solutions of other alkalis, and even a mixture of water and oxide of mercury, act in the same manner. This direct formation of *iodic acid*, $\text{HIO}_3 = \text{IO}_2(\text{OH})$, shows the propensity of iodine to give compounds of the type IX_5 . Indeed, the propensity of iodine to form compounds of a higher type clearly evinces itself in many ways. But it is most important to turn attention to the fact that iodic acid is easily and directly formed by the action of oxidising substances on iodine. Thus, for instance, strong nitric acid directly converts iodine into iodic acid, whilst it has no oxidising action on chlorine.⁷⁹ This shows a greater affinity in iodine for oxygen than in chlorine, and this conclusion is confirmed by the fact that iodine displaces chlorine from its oxygen acids,⁸⁰ and that in the presence of water chlorine oxidises iodine.⁸¹ Even ozone or a silent discharge passed through a mixture of oxygen and iodine vapour is able to directly oxidise iodine⁸² into iodic acid. It is disengaged from solu-

⁷⁹ The oxidation of iodine by strong nitric acid was discovered by Connell; Millon showed that it is accomplished, although more slowly, by the action of the hydrates of nitric acid up to $\text{HNO}_5 \cdot 2\text{H}_2\text{O}$, but that the solution $\text{HNO}_5 \cdot 2\text{H}_2\text{O}$, and weaker solutions, do not oxidise, but simply dissolve, iodine. The participation of water in reactions is seen in this instance. It is also seen, for example, in the fact that dry ammonia combines directly with iodine—for instance, at 0° forming the compound $\text{I}_2 \cdot 4\text{NH}_3$ —whilst iodine of nitrogen is only formed under the action of water.

⁸⁰ Bromine also displaces chlorine—for instance, from chloric acid, directly forming bromic acid. If a solution of potassium chlorate be taken (75 parts per 400 parts of water), and iodine be added to it (80 parts), and then a small quantity of nitric acid, chlorine is disengaged on boiling, and potassium iodate is formed in the solution. In this instance the nitric acid first evolves a certain portion of the chloric acid, and the latter, with the iodine, evolves chlorine. The iodic acid thus formed acts on a further quantity of the potassium chlorate, sets a portion of the chloric acid free, and in this manner the action is kept up. Potilitzin (1887) remarked, however, that not only do bromine and iodine displace the chlorine from chloric acid and potassium chlorate, but also chlorine displaces bromine from sodium bromate, and, furthermore, the reaction does not proceed as a direct substitution of the halogens, but is accompanied by the formation of free acids; for example, $5\text{NaClO}_3 + 3\text{Br}_2 + 3\text{H}_2\text{O} = 5\text{NaBr} + 5\text{HClO}_3 + \text{HBrO}_3$.

⁸¹ If iodine be stirred up in water, and chlorine passed through it, then the iodine is dissolved; the liquid becomes colourless, and contains, according to the mass of water and chlorine, either the compounds IHCl_2 , or ICl_5 , or HIO_5 . If there be a small amount of water, then the iodic acid may separate out directly in crystals, but a complete conversion (Bornemann) only occurs when not less than ten parts of water are taken to one part of iodine— $\text{ICl} + 3\text{H}_2\text{O} + 2\text{Cl}_2 = \text{HIO}_5 + 5\text{HCl}$.

⁸² Schönebein and Ogier proved this. Ogier found that at 45° ozone immediately


tions as a hydrate, HIO_3 , which loses water at 170° , and gives an anhydride, I_2O_5 . Both these substances are crystalline (sp. gr. I_2O_5 5.037, HIO_3 4.869 at 0°), colourless, soluble in water,⁸³ decompose at a red heat into iodine and oxygen, are in many cases powerfully oxidising—for instance, they oxidise sulphurous anhydride, hydrogen sulphide, carbonic oxide, &c.—form chloride of iodine and water with hydrochloric acid, and with bases form salts, not only normal MIO_3 , but also acid, for example, KIO_3HIO_3 , $\text{KIO}_3\cdot 2\text{HIO}_3$. With hydriodic acid iodic acid immediately reacts, disengaging iodine, $\text{HIO}_3 + 5\text{HI} = 3\text{H}_2\text{O} + 3\text{I}_2$.

As with chlorine, so with iodine, a *periodic acid*, HIO_4 , is formed. This acid is produced, as its salts, by the action of chlorine on alkaline solutions of iodates, and also by the action of iodine on chloric acid.⁸⁴


oxidises iodine vapour, first forming the oxide I_2O_5 , which is decomposed by water or on heating into iodic anhydride and iodine. Iodic acid is formed at the positive poles (Riche) when a solution of hydriodic acid is decomposed by a galvanic current. It is also formed in the combustion of hydrogen mixed with a small quantity of hydriodic acid (Salet).

⁸⁵ Kämmerer showed that a solution of sp. gr. 2.127 at 14° , containing $2\text{HIO}_3, 9\text{H}_2\text{O}$, entirely solidified in the cold. On comparing solutions $\text{HI} + m\text{H}_2\text{O}$ with $\text{HIO}_3 + m\text{H}_2\text{O}$, we find that the specific gravity increases but the volume decreases (it is the same in their passage to solutions $\text{HIO}_3 + m\text{H}_2\text{O}$), whilst in the passage of solutions $\text{HCl} + m\text{H}_2\text{O}$ to $\text{HClO}_3 + m\text{H}_2\text{O}$ the specific gravity augments, and so does the volume, which is remarked also in certain other cases (for example, H_3PO_3 and H_3PO_4). Observations on the specific volume of solution of iodic and periodic acids were made by Thomsen at $17^\circ/17^\circ$. He expresses for $\text{HIO}_3 + m\text{H}_2\text{O}$ by $18m + 39.1 - 13.1m/(m + 18)$, and for $\text{H}_5\text{IO}_6 + m\text{H}_2\text{O}$ by $18m + 23.8$, which shows the absence of contraction in mixing these acids with water (see Mendeléeff, *Investigation of Aqueous Solutions*, p. 368).

⁸⁴ If sodium iodate be mixed with a solution of sodium hydroxide, heated, and chlorine be passed through the solution, then a sparingly soluble salt separates out, which corresponds with periodic acid, and has the composition $\text{Na}_4\text{I}_2\text{O}_9, 3\text{H}_2\text{O}$.



This compound is sparingly soluble in water, but easily dissolves in a very dilute solution of nitric acid. If silver nitrate be added to this solution a precipitate is formed which contains the corresponding compound of silver, $\text{Ag}_4\text{I}_2\text{O}_9, 3\text{H}_2\text{O}$. If this sparingly soluble silver compound be dissolved in hot nitric acid, then, on evaporating, orange crystals of a salt having the composition AgIO_4 separate. This salt is formed from the preceding by the nitric acid taking up silver oxide. $\text{Ag}_4\text{I}_2\text{O}_9 + 2\text{HNO}_3 = 2\text{AgNO}_3 + 2\text{AgIO}_4 + \text{H}_2\text{O}$ is decomposed by water, with the re-formation of the preceding salt, while iodic acid remains in solution—



The structure of the first of these salts, $\text{Na}_4\text{I}_2\text{O}_9, 3\text{H}_2\text{O}$, presents itself in a simpler form if the water of crystallisation is regarded as an integral portion of the salt; the formula is then divided in two, and takes the form of $\text{IO}(\text{OH})_5(\text{ONa})_2$ —that is, it answers to the type IOX_5 , or IX_7 (like AgIO_4) which is $\text{IO}_5(\text{OAg})$. The composition of all the salts of periodic acids are expressed by this type IX_7 . Kimmins (1889) classes all the salts of periodic acid into four types—the meta-salts of HIO_4 (salts of Ag, Cu, Pb), the meso-salts of H_5IO_6 (Pb, Ag_2 , H, Cd, H), the para-salts of H_5IO_6 (Na_2H_5 , Na_7H_2), and the di-salts of $\text{H}_4\text{I}_2\text{O}_9$ (K_4 , Ag_4 , Ni_2). The three first are direct compounds of the type IX_7 , namely, $\text{IO}_5(\text{OH})$, $\text{IO}_5(\text{OH})_5$, and $\text{IO}(\text{OH})_5$, and the latter are types of diperiodic

It crystallises from solutions as a hydrate containing $2\text{H}_2\text{O}$ (corresponding with $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$), but as there are salts containing up to 5 atoms of metals, this water must be counted as water of constitution. Therefore $\text{IO}(\text{OH})_5 = \text{HIO}_4 \cdot 2\text{H}_2\text{O}$ corresponds with the higher form of halogen compounds, IX_7 .⁸⁵ In decomposing (at 200°) or acting as an oxidiser, periodic acid first gives iodic acid, but it may also be ultimately decomposed, with the formation of hydriodic acid.

Thus both bromine and iodine present a great analogy to chlorine in their behaviour with various substances, but nevertheless a series of qualitative distinctions characterise each element. The formation of a compound between chlorine and iodine must be classed among these distinctions.⁸⁶ These elements combine directly together with the evolution of heat, and form *iodine monochloride*, ICl , or *iodine trichloride*, ICl_3 .⁸⁷ As water reacts on these substances, forming iodic

salts, which correspond with the type of the meso-salts, as pyrophosphoric salts correspond with orthophosphoric salts—*i.e.* $2\text{H}_2\text{IO}_5 - \text{H}_2\text{O} = \text{H}_4\text{I}_2\text{O}_9$.

⁸⁵ Periodic acid, discovered by Magnus and Ammermüller, and whose salts were afterwards studied by Langlois, Rammelsberg, and many others, presents an example of hydrates in which it is evident that there is not that distinction between the water of hydration and of crystallisation which was at first considered to be so clear. In $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$ the water, $2\text{H}_2\text{O}$, is not displaced by bases and must be regarded as water of crystallisation, whilst in $\text{HIO}_4 \cdot 2\text{H}_2\text{O}$ it must be regarded as water of hydration. We shall afterwards see that the system of the elements obliges one to consider the halogens as substances giving a highest saline type, GX_7 , if G signify a halogen, and X oxygen ($\text{O} = \text{X}_2$), OH , and other like elements. The hydrate $\text{IO}(\text{OH})_5$ corresponding with many of the salts of periodic acid (for example, the salts of barium, strontium, mercury) does not exhaust all the possible forms. It is evident that various other pyro-, meta-, &c., forms are possible by the loss of water, as will be more fully explained in speaking of phosphoric acid, and as was pointed out in the preceding note.

⁸⁶ With respect to hydrogen, oxygen, chlorine, and other elements, bromine occupies an intermediate position between chlorine and iodine, and therefore there is no particular need for lingering over the compounds of bromine. This is the great advantage of a natural grouping of the elements.

⁸⁷ They were both obtained by Gay-Lussac and many others. Recent verified data respecting iodine monochloride, ICl , entirely confirm the numerous observations of Trapp (1854), and even confirm his statement as to the existence of two isomeric (liquid and crystalline) forms (Stortenbecker). With a small excess of iodine, iodine monochloride remains liquid, but in the presence of traces of iodine trichloride it easily crystallises. Schützenberger amplified the data concerning the action of water on the chlorides (Note 88) and Christomanos gave the fullest data regarding the trichloride.

After being kept for some time, the liquid monochloride of iodine yields red deliquescent octahedra, having the composition ICl_3 , which are therefore formed from the monochloride with the liberation of free iodine, which dissolves in the remaining quantity of the monochloride. This substance, however, judging by certain observations, is impure iodine trichloride. If 1 part of iodine be stirred up in 20 parts of water, and chlorine be passed through the liquid, then all the iodine is dissolved, and a colourless liquid is ultimately obtained which contains a certain proportion of chlorine, because this compound gives a metallic chloride and iodate with alkalis without evolving any free iodine: $\text{ICl}_3 + 6\text{KHO} = 5\text{KCl} + \text{KIO}_3 + 3\text{H}_2\text{O}$. The existence of a pentachloride ICl_5 is, however, denied, because this substance has not been obtained in a free state.

acid and iodine, they have to be prepared from dry iodine and chlorine.⁸⁸ Both substances are formed in a number of reactions ; for example, by the action of aqua regia on iodine, of chlorine on hydriodic acid, of hydrochloric acid on periodic acid, of iodine on potassium chlorate (with the aid of heat, &c.). Trapp obtained iodine monochloride, in beautiful red crystals, by passing a rapid current of chlorine into molten iodine. The monochloride then distils over and solidifies ; it melts at 27°. By passing chlorine over the crystals of the monochloride, it is easy to obtain iodine trichloride in orange crystals, which melt at 34° and volatilise at 47°, but in so doing decompose (into Cl_2 and ICl). The chemical properties of these chlorides entirely correspond with the properties of chlorine and iodine, which would be expected, because, in this instance, a combination by similitude took place as in the formation of solutions or alloys. Thus, for instance, the unsaturated hydrocarbons (for example, C_2H_4), which are capable of directly combining with chlorine and iodine, also directly combine with iodine monochloride.

Stortenbeker (1888) investigated the equilibrium of the system containing the molecules I_2 , ICl , ICl_3 , and Cl_2 , in the same way that Roozeboom (Chapter X. Note 38) examined the equilibrium of the molecules HCl , $\text{HCl}\cdot 2\text{H}_2\text{O}$, and H_2O . He found that iodine monochloride appears in two states, one (the ordinary) is stable and melts at 27·2°, whilst the other is obtained by rapid cooling, and melts at 13·9°, and easily passes into the first form. Iodine trichloride melts at 101° only in a closed tube under a pressure of 16 atmospheres.

⁸⁸ By the action of water on iodine monochloride and trichloride a compound IHCl_2 is obtained, which does not seem to be altered by water. Besides this compound, iodine and iodic acid are always formed, $10\text{ICl} + 3\text{H}_2\text{O} = \text{HIO}_3 + 5\text{IHCl}_2 + 2\text{I}_2$; and in this respect iodine trichloride may be regarded as a mixture $\text{ICl} + \text{ICl}_3 = 2\text{ICl}_3$, but $\text{ICl}_3 + 3\text{H}_2\text{O} = \text{HIO}_3 + 5\text{HCl}$; hence iodic acid, iodine, the compound IHCl_2 , and hydrochloric acid are also formed by the action of water.

CHAPTER XII

S O D I U M

WHEN common salt is submitted to the action of sulphuric acid, as we saw in Chapter X., hydrochloric acid is disengaged, and a neutral salt, sodium sulphate, Na_2SO_4 , is formed if the mixture be strongly heated at the end of the reaction. This salt¹ forms a colourless saline mass consisting of fine crystals, soluble in water. It is the product of many other double decompositions, sometimes produced on a large scale ; for instance, it is formed when ammonium sulphate is heated with common salt, in which case the sal-ammoniac is volatilised, also when sulphuric acid acts on sodium nitrate, &c. A similar decomposition also takes place when, for instance, a mixture of lead sulphate and common salt is heated ; this mixture easily fuses, and if the temperature be further raised heavy vapours of lead chloride appear. When the disengagement of these vapours ceases, the remaining mass, on being treated with water, yields a solution of sodium sulphate mixed with a solution of undecomposed common salt. A considerable quantity, however, of the lead sulphate remains unchanged during this reaction, $\text{PbSO}_4 + 2\text{NaCl} = \text{PbCl}_2 + \text{Na}_2\text{SO}_4$, the vapours will contain lead chloride, and the residue will contain the mixture of the three remaining salts. Here the decomposition is produced by the lead salt as with sulphuric acid. The cause and nature of the reaction are just the same as were pointed out when considering Berthollet's doctrine. And here it may evidently be shown that the double decomposition is not determined by any other means than the removal of the substance formed from the sphere of the action of the remaining substances. This is seen

¹ Whilst describing in some detail the properties of sodium chloride, hydrochloric acid, and sodium sulphate, I wish to impart a conception, by separate examples, of the properties of saline substances, but the dimensions of this treatise and its purpose and aim do not permit the possibility of entering into particulars concerning every salt, acid, or other substance. The fundamental object of this work—an account of the characteristics of the elements and an acquaintance with the forces acting between atoms—has nothing to gain from the multiplication of the number of as yet ungeneralised properties and relations.

from the fact that sodium sulphate, on being dissolved in water and mixed with a solution of any lead salt (and even with a solution of lead chloride, although this latter is but sparingly soluble in water), immediately gives a white precipitate of lead sulphate. In this case the lead takes up the elements of sulphuric acid from the sodium sulphate in the solutions. On heating, the reverse phenomenon is observed. The contrary reaction in the solution is founded on the insolubility of the lead sulphate, and the phenomenon which takes place on heating is founded on the volatility of the lead chloride. Let us cite other examples of double decompositions in solutions giving sodium sulphate. Silver sulphate, Ag_2SO_4 , when treated with common salt, gives silver chloride, because it is insoluble in water, $\text{Ag}_2\text{SO}_4 + 2\text{NaCl} = \text{Na}_2\text{SO}_4 + 2\text{AgCl}$. Sodium carbonate, mixed in solution with sulphates of iron, copper, manganese, magnesium, &c., gives in solution sodium sulphate, and in the precipitate a carbonate of the corresponding metal, because these salts of carbonic acid are insoluble in water; for instance, $\text{MgSO}_4 + \text{Na}_2\text{CO}_3 = \text{Na}_2\text{SO}_4 + \text{MgCO}_3$. In precisely the same way sodium hydroxide acts on solutions of the majority of the salts of sulphuric acid containing metals, the hydroxides of which are insoluble in water—for instance, $\text{CuSO}_4 + 2\text{NaHO} = \text{Cu}(\text{HO})_2 + \text{Na}_2\text{SO}_4$. Sulphates of magnesium, aluminum, iron, &c., on being mixed in solution with common salt, ought to form chlorides of magnesium, aluminum, &c., and sodium sulphate, as the above-mentioned chlorides are more soluble in water than sodium sulphate. On cooling the mixture of such (concentrated) solutions sodium sulphate is deposited. This is made use of for preparing it on the large scale in works where sea water is treated. In a similar way sodium sulphate is prepared by the aid of the magnesium sulphate which is found in large quantities in Stassfurt in the seams of common salt. In this case, on cooling, the reaction $2\text{NaCl} + \text{MgSO}_4 = \text{MgCl}_2 + \text{Na}_2\text{SO}_4$ takes place.

Thus where sulphates and salts of sodium are in contact, it may always be expected that sodium sulphate will be formed and separated if the conditions are favourable; for this reason it is not surprising to often find sodium sulphate in the native state. Some of the springs and salt lakes in the steppes beyond the Volga, and in the Caucasus, contain a considerable quantity of sodium sulphate, and yield it by simple evaporation of the solutions. Beds of this salt are also met with; thus at a depth of only 5 feet, about 38 versts to the east of Tiflis, at the foot of the range of the 'Wolf's mane' (Votchia griva) mountains, a deep stratum of very pure Glauber's salt, $\text{NaSO}_4 \cdot 10\text{H}_2\text{O}$, has been found.² A layer two metres thick of the

² Anhydrous (heated) sodium sulphate, Na_2SO_4 , in trade is known as 'sulphate' or

same salt lies at the bottom of several lakes (an area of about 10 square kilometres) in the Kouban district near Batalpaschinsk, and here its working has been commenced (1887). In Spain, near Arangoulz and Madrid, mineral sodium sulphate has likewise been found, and is already being worked.

The methods of obtaining salts by means of double decomposition from others already prepared are so general, that in describing a given salt there is no necessity to enumerate the cases hitherto observed of its being formed through various double decompositions.³ The possibility of this occurrence ought to be foreseen according to Berthollet's doctrine from the properties of the salt in question. On this account it is important to know the properties of salts; all the more so because up to the present time those very properties (solubility, formation of crystallo-hydrates, volatility, &c.) which may be made use of for separating them from other salts have not been generalised.⁴ These properties as yet remain subjects for investigation, and are rarely to be foreseen.

Sodium sulphate very easily parts with water, and may be obtained in an anhydrous state if it be carefully heated until the weight remains constant; but if heated further, it partly loses the elements of sulphuric anhydride. It fuses at 861° (red heat), and volatilises in a small proportion when very strongly heated, in which case it naturally decomposes. At 0° in 100 parts of water, 5 parts of the anhydrous salt dissolve, at 10° 9 parts, at 20° 19.4, at 30° 40, and at 34° 55 parts, the same being the case in the presence of an excess of crystals of $\text{Na}_2\text{SO}_4, 10\text{H}_2\text{O}$.⁵ At 34° the latter fuses, and the solubility decreases

salt-cake, in mineralogy *thenardite*. Crystalline decahydrated salt is termed in mineralogy *mirabilite*. On fusing it, the monohydrate $\text{Na}_2\text{SO}_4\text{H}_2\text{O}$ is obtained, together with a supersaturated solution.

³ The salts may be obtained not only by methods of substitution of various kinds, but also by many other combinations. Thus sodium sulphate may be formed from sodium oxide, and sulphuric anhydride by oxidising sodium sulphide, Na_2S , sodium sulphite, Na_2SO_3 , &c. When sodium chloride is heated in a mixture of the vapours of water, air, and sulphuric anhydride, sodium sulphate is formed.

⁴ Many observations have been made, but little general information has been extracted from particular cases. In addition to which, the properties of a given salt are changed by the presence of other salts. This takes place not only in virtue of mutual decomposition or formation of double salts capable of separate existence, but is determined by the influence which some salts exert on others, or by forces similar to those which act during decomposition. Here, nothing has been generalised to that extent which would render it possible to foretell uninvestigated examples. Let us state one of these numerous cases: 100 parts of water at 20° dissolve 34 parts of potassium nitrate, but on the addition of sodium nitrate the solubility of potassium nitrate increases to 48 parts in 100 of water (Carnelley and Thomson). In general, in all cases of which there are accurate observations, it appears that the presence of foreign salts changes the property of any given salt.

⁵ The information concerning solubility (Chapter I. p. 72) is given according to the determinations of Gay-Lussac, Lovell, and Mulder.

at higher temperatures.⁶ A concentrated solution at 34° has a composition nearly approaching to $\text{Na}_2\text{SO}_4 + 14\text{H}_2\text{O}$, and the decahydrated salt, when mixed with 100 parts of water, contains 78.9 of the anhydrous salt, from whence it is seen that the decahydrated salt cannot fuse without decomposing,⁷ similarly to hydrate of chlorine, $\text{Cl}_2 \cdot 8\text{H}_2\text{O}$, or sulphurous acid, $\text{SO}_2 \cdot 7\text{H}_2\text{O}$. Not only the fused decahydrated salt, but also the concentrated solution at 34° (not all at once, but gradually), yields the monohydrated salt $\text{Na}_2\text{SO}_4 \cdot \text{H}_2\text{O}$. The heptahydrated salt, $\text{Na}_2\text{SO}_4 \cdot 7\text{H}_2\text{O}$, also splits up, even at low temperatures, with the formation of this monohydrated salt, and therefore from 35° the solubility can be given only for the latter, and it is as follows for 100 parts of water: at 40° 48.8, at 50° 46.7, at 80° 43.7, at 100° 42.5 parts of the anhydrous salt. If the decahydrated salt be fused, and the solution be allowed to cool in the presence of the monohydrated salt, then at 30° 50.4 parts of anhydrous salt are retained in the solution, and at 20° 52.8 parts. Hence, with respect to the anhydrous and monohydrated salts, the solubility is one and the same, and falls with

⁶ In Chapter I. Note 24, we have already seen that with many other sulphates the solubility also decreases after a certain temperature. Gypsum, $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$, lime, and many other compounds present such a phenomenon, not as yet, however, thoroughly investigated. The observation of Tilden and Shenstone (1884) is most instructive, and shows that on raising the temperature (in closed vessels) above 140° the solubility of sodium sulphate again begins to increase. At 100° , 100 parts of water dissolve about 43 parts of anhydrous salt, at 140° 42 parts, at 160° 43 parts, at 180° 44 parts, at 230° 46 parts. It is evident that the phenomenon of saturation, determined by the presence of an excess of the dissolved substance, is very complex, and, therefore, for the theory of solutions considered as liquid indefinite chemical compounds, many useful results can hardly be given; more especially as the physico-mechanical side of the transition of the solid into the liquid condition (or the reverse) is up to the present time less clearly understood in theory than the transition of a liquid into vapour.

⁷ As has been referred to in Chapter I. Note 56.

The example of sodium sulphate is historically very important for the theory of solutions. Notwithstanding the mass of investigations which have been made, it is still insufficiently studied, especially from the point of the vapour tension of solutions and crystallo-hydrates, so that those processes cannot be applied to it which Guldberg, Roozeboom, Van't Hoff, and others applied to solutions and crystallo-hydrates. It would also be most important to investigate the influence of pressure on the various phenomena corresponding with the combinations of water and sodium sulphate, because when crystals are separated—for instance, in the decahydrated salt—an increase of volume takes place, as can be seen from the following data:—the sp. gr. of the anhydrous salt is 2.66, that of the decahydrated salt = 1.46, but the sp. gr. of solutions at 15° $d_{15} = 9992 + 90.2p + 0.35p^2$ if p represents the percentage of anhydrous salt in the solution, and if the sp. gr. of water at $4^\circ = 10000$. Hence, for solutions containing 20% of anhydrous salt, the sp. gr. = 1.1936; therefore the volume of 100 grams of this solution = 83.8 c.c., and the volume of anhydrous salt contained in it is equal to 20.2.66, or = 7.5 c.c., and the volume of water = 80.1 c.c. Therefore, the solution, on decomposing into anhydrous salt and water, increases in volume (from 83.8 to 87.6); but in the same way 83.8 c.c. of 20 p.c. solution are formed from $(45.4 \cdot 1.46) = 31.1$ c.c. of the decahydrated salt, and 54.6 c.c. of water—that is to say, that during the formation of a solution from 85.7 c.c., 83.8 c.c. are formed.

the temperature, whilst with respect to decahydrated salt, the solubility rises with the temperature. So that if in the presence of a solution of sodium sulphate there be only crystals of that heptahydrated salt (p. 59) $\text{Na}_2\text{SO}_4 \cdot 7\text{H}_2\text{O}$ which is formed from saturated solutions, then saturation sets in when the solution has the following composition per 100 parts of salt: at 0° 19.6, at 10° 30.5, at 20° 44.7, and at 25° 52.9 parts of anhydrous salt. Above 27° the heptahydrated salt, like the decahydrated salt at 34° , splits up into the monohydrated salt and a saturated solution. Thus sodium sulphate has three curves of solubility: one for $\text{Na}_2\text{SO}_4 \cdot 7\text{H}_2\text{O}$ (from 0° to 26°), one for $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ (from 0° to 34°), and one for $\text{Na}_2\text{SO}_4 \cdot \text{H}_2\text{O}$ (a descending curve beginning at 26°), because there are three of these crystallo-hydrates, whilst the solubility can only be referred to a definite state of a substance which is present (or separated) in excess.⁸

Thus solutions of sodium sulphate give crystallo-hydrates of three kinds on cooling the saturated solution: the unstable equilibrium of the heptahydrated salt at temperatures below 26° , the decahydrated salt forms under ordinary conditions at temperatures below 34° , and the monohydrated salt at temperatures above 34° . Both the latter crystallo-hydrates present a stable state of equilibrium, and the heptahydrated salt decomposes into them, probably according to the equation $3\text{Na}_2\text{SO}_4 \cdot 7\text{H}_2\text{O} = 2\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O} + \text{Na}_2\text{SO}_4 \cdot \text{H}_2\text{O}$. The ordinary decahydrated salt is called *Glauber's salt*. All forms of these crystallo-hydrates entirely lose their water, and give the anhydrous salt when dried over sulphuric acid.⁹

Sodium sulphate, Na_2SO_4 , enters into only a few reactions of combination with other salts, and chiefly with salts of the same acid, forming double sulphates. Thus, for example, if a solution of sodium

⁸ From this example it is evident that the phenomena of saturation are not able to contribute much towards the understanding of solutions themselves. The solution remains the same, but from the contact of a solid it becomes either saturated or supersaturated, because crystallisation is determined by the attraction to a solid, as the phenomenon of supersaturation clearly demonstrates.

⁹ According to the demonstrations of Pickering (1886), the molecular weight in grams (that is, 142 grams) of anhydrous sodium sulphate, on being dissolved in a large mass of water, at 0° absorbs (therefore the — sign) —1100 heat units, at 10° —700, at 15° —275, at 20° (gives out) +25°, at 25° +300 calories. For the decahydrated salt $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$, 5° —4225, 10° —4000, 15° —3570, 20° —3160, 25° —2775. Hence (just as in Chapter I. Note 56) the heat of the combination $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ at 5° = +3125, 10° = +3250, 20° = +3200 and 25° = +3050.

It is evident that the decahydrated salt dissolving in water gives a decrease of temperature. Solutions in hydrochloric acid give a still greater decrease, because the water of crystallisation is here taken in a solid state—that is, like ice—and on melting absorbs heat. A mixture of 15 parts of $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ and 12 parts of strong hydrochloric acid produces sufficient cold to freeze water. During the treatment with hydrochloric acid a certain quantity of sodium chloride is formed.

sulphate be mixed with a solution of aluminium, magnesium, or ferrous sulphate, it gives crystals of a double salt when evaporated. Sulphuric acid itself forms a compound with sodium sulphate, which is exactly like these double salts. It is formed with great ease if sodium sulphate is dissolved in sulphuric acid and the solution be evaporated. On evaporation, crystals of the *acid salt* separate, $\text{Na}_2\text{SO}_4 + \text{H}_2\text{SO}_4 = 2\text{NaHSO}_4$. This separates from hot solutions, whilst the crystallhydrate $\text{NaHSO}_4, \text{H}_2\text{O}^{10}$ separates from cold solutions. The crystals, when exposed to damp air, split up into H_2SO_4 , which deliquesces, and Na_2SO_4 (Graham, Rose); alcohol also extracts sulphuric acid from the acid salt. This shows the feeble force which holds the sulphuric acid to the sodium sulphate.¹¹ Both acid sodium sulphate and all mixtures of the normal salt and sulphuric acid lose water when heated, and are converted into sodium *pyrosulphate*, $\text{Na}_2\text{S}_2\text{O}_7$, at a low red heat. This anhydrous salt, at a bright red heat, parts with the elements of sulphuric anhydride, the normal sodium sulphate remaining behind. $\text{Na}_2\text{S}_2\text{O}_7 = \text{Na}_2\text{SO}_4 + \text{SO}_3$. From this it is seen that the normal salt is able to combine with water, with other sulphates, and with sulphuric anhydride or acid, &c.^{11b}

Sodium sulphate may, by double decomposition, be converted into a sodium salt of any other acid, by means of heat and taking advantage of the volatility, or by means of solution and taking advantage of the different degree of solubility of the different salts. Thus, for instance, owing to the insolubility of barium sulphate, sodium hydroxide or caustic soda may be prepared from sodium sulphate, if barium hydroxide be added to its solution, $\text{Na}_2\text{SO}_4 + \text{Ba}(\text{HO})_2 = \text{BaSO}_4 + 2\text{NaHO}$. And by taking any salt of barium, BaX_2 , the corresponding salt of sodium

¹⁰ The very large and well-formed crystals of this salt resemble the hydrate $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$, or $\text{SO}(\text{OH})_2$. In general the replacement of hydrogen by sodium modifies many of the properties of acids less than its replacement by other metals. This most probably depends on the volumes being nearly equal.

¹¹ In solution (Berthelot) the acid salt in all probability decomposes most in the greatest mass of water. The specific gravity (according to the determinations of Marignac) of solutions at $15^\circ, 4^\circ - 9992 + 77.92 p - 0.231 p^2$ (see Note 7). From these figures, and from the specific gravities of sulphuric acid, it is evident that on mixing solutions of this acid and sodium sulphate *expansion* will always take place; for instance, $\text{H}_2\text{SO}_4 + 25\text{H}_2\text{O}$ with $\text{Na}_2\text{SO}_4 + 25\text{H}_2\text{O}$ increases from 483 volumes to 486. In addition to which, in weak solutions heat is absorbed, as shown in Chapter X. Note 27. Nevertheless, even more acid salts may be formed. For instance, on cooling a solution of 1 part of sodium sulphate in 7 parts of sulphuric acid, crystals of the composition $\text{NaHSO}_4, \text{H}_2\text{SO}_4$ are separated (Schultz, 1868). This fuses at about 100° ; the ordinary acid salt, NaHSO_4 , at 149° .

^{11b} In order to demonstrate the weakness of the bond acting in sodium hydrogen sulphate, NaHSO_4 , it is useful to remember that on decreasing the pressure this salt dissociates much more easily than at the ordinary pressure; it loses water and forms the pyrosulphate, $\text{Na}_2\text{S}_2\text{O}_7$; this reaction is utilised in chemical works.

may be obtained, $\text{Na}_2\text{SO}_4 + \text{BaX}_2 = \text{BaSO}_4 + 2\text{NaX}$. Barium sulphate thus formed, being a very sparingly-soluble salt, is obtained as a precipitate, whilst the sodium hydroxide, or salt, NaX , is obtained in solution, because *all salts of sodium are soluble*. Berthollet's doctrine permits all such cases to be foreseen.

The reactions of *decomposition* of sodium sulphate are above all noticeable by the separation of oxygen. Sodium sulphate itself is very stable, and it is only at a temperature sufficient to melt iron that it is possible to separate the elements SO_3 from it, and then only partially. However, the oxygen may be separated from sodium sulphate, as from all other sulphates, by means of many substances which are able to combine with oxygen, such as charcoal and sulphur, but hydrogen is not able to produce this action. If sodium sulphate be heated with charcoal, then carbonic oxide and anhydride are evolved, and there is produced, according to the circumstances, either the lower oxygen compound, sodium sulphite, Na_2SO_3 (for instance, in the formation of glass); or else the decomposition proceeds further and sodium sulphide, Na_2S , is formed, according to the equation $\text{Na}_2\text{SO}_4 + 2\text{C} = 2\text{CO}_2 + \text{Na}_2\text{S}$.

On the basis of this reaction the greater part of the sulphate of sodium prepared at chemical works is converted into *soda ash*—that is, *sodium carbonate*, Na_2CO_3 , which is used for many purposes. In the form of carbonates, the metallic oxides behave in many cases just as they do in the state of oxides or hydroxides, owing to the feeble acid properties of carbonic acid. However, the majority of the salts of carbonic acid are insoluble, whilst sodium carbonate is one of the few soluble salts of this acid, and therefore reacts with facility. Therefore sodium carbonate is employed for many purposes, in which it acts owing to its alkaline properties. Thus sodium carbonate, even under the action of feeble organic acids, immediately parts with its carbonic acid, and gives a sodium salt of the acid taken. Furthermore, its solutions already exhibit an alkaline reaction on litmus, and in many cases are able to act as an alkali. Thus, for instance, sodium carbonate, like the alkalis, aids the passage of certain organic substances (tar, acids) into solution, and is therefore used, like alkalis and soap (which also acts by virtue of the alkali it contains), for the removal of certain organic substances, especially in bleaching tissues in cotton and similar works. Besides which, a considerable quantity of sodium carbonate is used for the preparation of sodium hydroxide or caustic soda, which has also a very wide application. In large chemical works where sodium carbonate is manufactured it is usual to first manufacture sulphuric acid, and then by its aid to convert common salt into sodium sulphate,

and lastly to convert the sodium sulphate thus obtained into carbonate and caustic soda. Hence these works prepare alkaline substances (soda ash and caustic soda) and acid substances (sulphuric and hydrochloric acids), those two forms of chemical products which are distinguished for the greatest energy of their reactions, and which are therefore frequently applied to technical purposes. And therefore the works manufacturing soda are generally called chemical works (alkali works).

The process of the conversion of sodium sulphate into sodium carbonate consists in strongly heating a mixture of the sulphate with charcoal and calcium carbonate. The following reactions then take place: the sodium sulphate is first deoxidised by the charcoal, forming sodium sulphide and carbonic anhydride, $\text{Na}_2\text{SO}_4 + 2\text{C} = \text{Na}_2\text{S} + 2\text{CO}_2$. The sodium sulphide thus formed then enters into double decomposition with the calcium carbonate taken and gives calcium sulphide and sodium carbonate, $\text{Na}_2\text{S} + \text{CaCO}_3 = \text{Na}_2\text{CO}_3 + \text{CaS}$.

Besides which, under the action of the heat, a portion of the excess of calcium carbonate is decomposed into lime and carbonic anhydride, $\text{CaCO}_3 = \text{CaO} + \text{CO}_2$, and the carbonic anhydride with the excess of charcoal forms carbon monoxide, which towards the end of the operation shows itself by the appearance of a blue flame. Thus from a mass containing sodium sulphate we obtain a mass which includes sodium carbonate, calcium sulphide, and calcium oxide, but none of the sodium sulphide first formed, or, strictly speaking, only a small portion. The entire process, which proceeds at a high temperature, may be expressed by a combination of the three above-mentioned formulæ, if it be taken into consideration that the product contains one equivalent of calcium oxide to two equivalents of calcium sulphide.¹² The sum of the reactions may then be expressed thus: $2\text{Na}_2\text{SO}_4 + 3\text{CaCO}_3 + 9\text{C} = 2\text{Na}_2\text{CO}_3 + \text{CaO}, 2\text{CaS} + 10\text{CO}$. Indeed, the quantities in which the substances are mixed together at chemical works approaches to the proportion required by this equation. The entire process of decomposition is carried on in reverberatory furnaces, into which a mixture of 1000 parts of sodium sulphate, 1040 parts of calcium carbonate (as a

¹² Calcium sulphide, CaS , like many metallic sulphides which are soluble in water, is decomposed by water (page 426), $\text{CaS} + \text{H}_2\text{O} = \text{CaO} + \text{H}_2\text{S}$, because hydrogen sulphide is a very feeble acid. If calcium sulphide be acted on by a large mass of water, lime may be precipitated, a state of equilibrium will be entered on, when the system $\text{CaO} + 2\text{CaS}$ remains unchanged. Lime, being the product of the action of water on CaS , limits this action. Therefore, if in black ash the lime was not in excess, a part of the sulphide compounds would be in solution (actually there is but very little). In this manner in the manufacture of sodium carbonate the conditions of equilibrium which enter into double decompositions have been made use of (*see above*), and the aim is to form directly the unchangeable product $\text{CaO}, 2\text{CaS}$. This was first regarded as a special insoluble compound, but nothing points to its independent existence.

somewhat porous limestone), and 500 parts of small coal is charged from above. This mixture is first heated in the portion of the furnace which is furthest removed from the fire-grate ; it is then brought to the




FIG. 69.—Reverberatory furnace for the manufacture of sodium carbonate. F, grate. A, bridge. M, hearth for the ultimate calcination of the mixture of sodium sulphate, coal, and calcium carbonate, which is charged from above into the part of the furnace furthest removed from the fire F. P, P, doors for stirring and bringing the mass towards the grate F by means of stirrers R. At the end of the operation the semifused mass is charged into trucks C.

portion nearest to the fire-grate, when it is stirred during heating. The partially-fused mass obtained at the end of the process is cooled, and then subjected to methodical lixiviation¹³ to extract the sodium

¹⁵ *Methodical lixiviation* is the extraction, by means of water, of a soluble substance from the mass containing it. It is carried on so as not to obtain weak aqueous solutions, and in such a way that the residue shall not contain any of the soluble substance. This problem is practically of great importance in many industries. It is required to extract from the mass all that is soluble in water. This is easily effected if water be first poured




FIG. 70.—Apparatus for the methodical lixiviation of black ash, &c. Water flows into the tanks from the pipes *r, r'*, and the saturated liquid is drawn off from *c, c'*.


on the mass ; the strong solution thus obtained is then decanted, then water is again poured on, time being allowed for it to act ; then again decanted, and so on until the water does not take up anything. But then finally such weak solutions are obtained that it would be very disadvantageous to evaporate them. This is avoided by pouring

carbonate, the mixture of calcium oxide and sulphide forming the so-called 'soda waste.'¹⁴

the fresh hot water destined for the lixiviation, not on the fresh mass, but upon a mass already subjected to preparatory lixiviation by means of weak solutions. In this way the fresh water gives a weak solution. The solution which is obtained flows to those parts of the apparatus which contain the fresh, as yet unlixivated, mass, and thus in the latter parts the weak alkali formed in the other parts of the apparatus becomes saturated as far as possible with the soluble substance. Generally several intercommunicating vessels are constructed (standing at the same level) into which in turn the fresh mass is deposited which is intended for lixiviation; the water is poured in, the alkali drawn off, and the lixiviated residue cleared out. The illustration represents such an apparatus, consisting of four communicating vessels. The water poured into one of them flows through the two nearest and issues from the third. If the fresh mass be placed in one of these cases or vessels, the stream of water passing through the apparatus is directed in such a manner as to finally issue from this vessel containing the fresh unlixivated mass. The fresh water is added to the vessel containing the matter which is almost completely exhausted. The fresh water passing through this vessel is conveyed by the pipe (syphon passing from below the first case to the top of the second) communicating with the second; it finally passes (also through a syphon pipe) into the case (the third) containing the fresh stuff. The water will extract all that is soluble in the first vessel, leaving only an insoluble mass. This vessel is then destined to be emptied, and refilled with fresh matter. The level of the liquids in the various vessels will naturally be different, in consequence of the various strengths of the solutions which they contain.

¹⁴ The whole of the sulphur used in the production of the sulphuric acid employed in decomposing the common salt enters into this residue. This residue carrying off the sulphur is the great burden and expense of the soda works which use Leblanc's method. As an instructive example from a chemical point of view it is worth while describing here one of the various methods of regaining the sulphur from the soda waste.

Kynaston (1885) treats the soda waste with a solution (sp. gr. 1.21) of magnesium chloride, which disengages sulphuretted hydrogen: $\text{CaS} + \text{MgCl}_2 + 2\text{H}_2\text{O} = \text{CaCl}_2 + \text{Mg}(\text{OH})_2 + \text{H}_2\text{S}$. Sulphurous anhydride is passed through the residue in order to form the insoluble calcium sulphite: $\text{CaCl}_2 + \text{Mg}(\text{OH})_2 + \text{SO}_2 = \text{CaSO}_3 + \text{MgCl}_2 + \text{H}_2\text{O}$. The solution of magnesium chloride obtained is again used, and the washed calcium sulphite is brought into contact at a low temperature with hydrochloric acid (a weak aqueous solution) and hydrogen sulphide, the whole of the sulphur then separating:



It is necessary to turn once more to the lixiviation of the sodium carbonate from the mass formed in the furnace (*see also* Note 25). *

It must not, however, be thought that sodium carbonate alone passes into the solution; there is also a good deal of caustic soda with it, formed by the action on the carbonate of sodium of the lime remaining from the first process of the action of the charcoal, and there are also certain sodium sulphur compounds with which we shall partly become acquainted hereafter. The sodium carbonate, therefore, is not obtained in a very pure state. The solution is subjected to evaporation. The evaporation is conducted at the expense of the waste heat from the soda furnaces, together with that of the gases given off. The process in the soda furnaces is only carried on at a high temperature, and therefore the smoke and gases issuing from the furnaces are inevitably very hot. If the heat they contain was not made use of there would be a great waste of fuel; consequently in immediate proximity to the soda furnaces there is generally a series of pans or evaporating boilers, under which the gases from the furnace pass, and into these the alkali solution obtained is poured. On evaporating the solution first of all the undecomposed sodium sulphate separates, then the sodium carbonate or soda crystals. These crystals

The above-mentioned process for making soda was discovered in the year 1808 by the French doctor Leblanc, and is known as the Leblanc process. The particulars of this discovery are somewhat remarkable. Sodium carbonate, having a considerable application in industry, was for a long time prepared exclusively from the ash of marine plants (Chapter XI. page 490). Even up to the present time this process is carried on in Normandy. In France, where for a long time the manufacture of large quantities of soap (so-called Marseilles soap) and various fabrics required a large amount of soda, the quantity prepared at the coast was insufficient to meet the demand. For this reason during the wars at the beginning of the century, when the import of foreign goods into France was interdicted, the want of sodium carbonate was felt. The French Academy offered a prize for the discovery of a profitable method of preparing it from common salt. Leblanc then proposed the above-mentioned process, which is remarkable for its great simplicity.¹⁵

which separate are raked out and placed on planks, where the liquid flows off. Caustic soda remains in the residue, and also any sodium chloride which was not decomposed in the foregoing process.

Part of the sodium carbonate is crystallised in order to purify it more thoroughly. In order to do this a saturated solution is left to crystallise at a temperature below 30° in a current of air, in order to promote the separation of the vapour of water. Then the large transparent crystals (efflorescent in air) of $\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O}$ are formed which have been spoken of already (Chapter I.).

¹⁵ Among the drawbacks of the Leblanc process are the accumulation of 'soda waste,' and the impossibility at the comparatively low price of sulphur (especially in the form of pyrites) of finding a suitable employment for it (although this waste can furnish sulphur and sulphur compounds, for which purposes it is sometimes treated), and also the insufficient purity of the sodium carbonate for many purposes. The advantage of the Leblanc process, besides its simplicity and cheapness, are that almost all acids having a commercial value are obtained as bye-products; chlorine and bleaching powder are produced with the assistance of the large amount of hydrochloric acid which appears as a bye-product, and caustic soda is very easily made, and the demand for it increases every year. In those places where salt, pyrites, charcoal, and limestone (which are the materials required for soda works) are found side by side—as, for instance, in the Ural or Don districts—all conditions are favourable to the development of the manufacture of sodium carbonate on an enormous scale; and where, as in the Caucasus, sodium sulphate occurs naturally, the conditions are still more favourable. A large amount, however, of the latter salt, even from soda works, is used in making glass. The most important soda works, as regards the quantity of products obtained from them, are the English works.

As an example of the other numerous and various methods of manufacturing soda from sodium chloride, the following processes may be mentioned: Sodium chloride is decomposed by oxide of lead, PbO , forming lead chloride and sodium oxide, which, with carbonic anhydride, yields sodium carbonate (Scheele's process). In Cornu's method sodium chloride is treated with lime, and then exposed to the air, when it yields a small quantity of sodium carbonate. In E. Kopp's process sodium sulphate (125 parts) is mixed with oxide of iron (80 parts) and charcoal (55 parts), and the mixture is heated in reverberatory furnaces. Here a compound, $\text{Na}_3\text{Fe}_2\text{S}_5$, is formed, which is insoluble in water and absorbs oxygen and carbonic anhydride, and then forms sodium carbonate and ferrous sulphide; this when roasted can give sulphurous anhydride, which is indispensable for the manufacture of sulphuric acid, and ferric oxide, which is again used in the

Of all other industrial processes for manufacturing sodium carbonate the *ammonia process* is the most worthy of mention.¹⁶ In this the vapours of ammonia, and then an excess of carbonic anhydride, are directly introduced into a concentrated solution of sodium chloride in order to form the acid ammonium carbonate, NH_4HCO_3 . Then, by means of the double saline decomposition of this salt, sodium chloride is decomposed, and in virtue of its slight solubility acid sodium carbonate, NaHCO_3 , is precipitated and ammonium chloride, NH_4Cl , is obtained in solution (with a portion of sodium chloride and acid sodium carbonate). The ammonia is removed from the solution by heating with lime or magnesia, and the precipitated acid sodium carbonate is converted into the normal salt by heating. It is thus obtained in a very pure state.

Sodium carbonate,¹⁷ like sodium sulphate, loses all its water on being heated, and when anhydrous fuses at a bright-red heat (814°). A small quantity of sodium carbonate placed in the loop of a platinum wire volatilises in the heat of a gas flame, and therefore in the furnaces of glass works part of the soda is always transformed into the condition of vapour. Sodium carbonate resembles sodium sulphate in its relation to water.¹⁸ Here also its greatest solubility is at the temperature of

process. In Grant's method sodium sulphate is transformed into sodium sulphide, and the latter is decomposed by a stream of carbonic anhydride and steam, when hydrogen sulphide is disengaged and sodium carbonate formed.

Sodium carbonate may likewise be obtained from cryolite (page 484); the method of treating this will be mentioned under aluminium.

¹⁶ This process (*see* Note 21) was first pointed out by Turck, worked out by Schloesing, and finally applied industrially by Solvay. The first (1883) large soda works erected in Russia for working this process are on the banks of the Kama at Bereznik, near Ousolia, and belong to Lubimoff. But Russia, which still imports from abroad a large quantity of bleaching powder and exports a large amount of manganese ore, most of all requires works carrying on the Leblanc process. Such are in course of construction, but this branch of industry is still in embryo in Russia.

¹⁷ Commercial soda ash (calcined, anhydrous) is rarely pure; the crystallised soda is generally purer. In order to purify it further it is best to boil a concentrated solution of soda ash until two-thirds of the liquid remain, collect the soda which settles, wash with cold water, and then shake up with a strong solution of ammonia, pour off the residue, and heat. Then the impurities will remain in the mother liquors, &c.

¹⁸ The resemblance is so great that, notwithstanding the difference in the molecular composition of Na_2SO_4 and Na_2CO_3 , they ought to be classed under the type $(\text{NaO})_2\text{R}$, where $\text{R} = \text{SO}_2$ or CO . Many other sodium salts also contain 10 mol. H_2O .

Some numerical data may be given for sodium carbonate. The specific gravity of the anhydrous salt is 2.48, that of the decahydrated salt = 1.46. Two varieties are known of the heptahydrated salt (Löwel, Marignac, Rammelsberg), which are formed together by allowing a saturated solution to cool under a layer of alcohol; the one is less stable (like the corresponding sulphate) and at 0° has a solubility of 32 parts (of anhydrous salt) in 100 water; the other is more stable, and the solubility 20 parts (of anhydrous salt) per 100 of water. The solubility of the decahydrated salt in 100 water = at 0° , 7.0; at 20° , 21.7; at 30° , 37.2 parts (of anhydrous salt). At 80° the solubility is only 46.1, at 90° 45.7, at 100° 45.4 parts (of anhydrous salt). The specific gravity (Note 7) of the solutions of sodium carbonate, according to the data of Gerlach and Kohlrausch, at 15° 4° is expressed by

37°; both salts, on crystallising at the ordinary temperature, combine with ten molecules of water, and such crystals of soda, like crystals of Glauber's salt, fuse at 34°. Sodium carbonate also forms a super-saturated solution, and, according to the conditions, gives various combinations with water of crystallisation (mentioned on page 107), &c.

At a red heat superheated steam liberates carbonic anhydride from sodium carbonate and forms caustic soda, $\text{Na}_2\text{CO}_3 + \text{H}_2\text{O} = 2\text{NaHO} + \text{CO}_2$. Here the carbonic anhydride is replaced by water: this depends on the feebly acid character of carbonic anhydride. By direct heating, sodium carbonate is only slightly decomposed into sodium oxide and carbonic anhydride; thus, when sodium carbonate is fused, about 1 per cent. of carbonic anhydride is disengaged.¹⁹ The carbonates of many other metals—for instance, of calcium, copper, magnesium, iron, &c.—on being heated lose all their carbonic anhydride. This shows the considerable basic energy which sodium possesses. With the soluble salts of most metals, sodium carbonate gives precipitates either of insoluble carbonates of the metals, or else of the hydroxides (in this latter case carbonic anhydride is disengaged); for instance, with barium salts it precipitates an insoluble barium carbonate ($\text{BaCl}_2 + \text{Na}_2\text{CO}_3 = 2\text{NaCl} + \text{BaCO}_3$) and with the aluminium salts it precipitates aluminium hydroxide, carbonic anhydride being disengaged: $3\text{Na}_2\text{CO}_3 + \text{Al}_2(\text{SO}_4)_3 + 3\text{H}_2\text{O} = 3\text{Na}_2\text{SO}_4 + 2\text{Al}(\text{OH})_3 + 3\text{CO}_2$. Sodium carbonate, like all the salts of carbonic acid, evolves carbonic anhydride on treatment with all acids which are to any extent energetic. But if an acid diluted with water be gradually added to a solution of sodium carbonate, *at first* such an evolution does not take place, because the excess of the carbonic anhydride forms acid sodium carbonate (sodium bicarbonate), NaHCO_3 . The composition of this salt, however, may be also represented as a combination of carbonic acid, H_2CO_3 , with the normal salt, Na_2CO_3 , just as the latter also combines with water. Such a representation is all the more

the formula, $s = 9092 + 104.5p + 0.165p^2$. Weak solutions occupy a volume not only less than the sum of the volumes of the anhydrous salt and the water, but even less than the water contained in them. For instance, 1000 grams of 1 p.c. solution occupy (15°) a volume of 990.4 c.c. (sp. gr. 1.0097), but contain 900 grams of water, occupying at 15° a volume of 990.8 c.c. A similar case of solubility, which is comparatively rare (it occurs also with sodium hydroxide), occurs in those dilute solutions for which the factor A is greater than 100 if the sp. gr. of water at 4° = 100000, and if the sp. gr. of the solution be expressed by the formula $S = S_0 + Ap + Bp^2$, where S_0 is the specific gravity of the water (this is more fully discussed in my treatise, *The Investigation of Aqueous Solutions*, 1887, §§ 94 and 95). For 5 p.c. the sp. gr. 15°/4° = 1.0520; for 10 p.c. 1.1057; for 15 p.c. 1.1603. The changes in the sp. gr. with the temperature are here almost the same as with solutions of sodium chloride with an equal value of p .

¹⁹ According to the observations of Pickering. According to Rose, when solutions of sodium carbonate are boiled a certain amount of carbonic anhydride is disengaged.

likely because (1) there exists another salt, $\text{Na}_2\text{CO}_3, 2\text{NaHCO}_3, 2\text{H}_2\text{O}$ (sodium sesquicarbonate), obtained by cooling a boiling solution of sodium bicarbonate, or by mixing this salt with the normal salt; but the formula of this salt cannot be derived from that of normal carbonic acid, as the formula of the bicarbonate can;²⁰ (2) water of crystallisation does not enter into the composition of the crystals of the acid salt, so that on its formation (occurring only at low temperatures, as in the formation of crystalline compounds with water) the water of crystallisation of the normal salt separates and the water is, as it were, replaced by the elements of carbonic acid. In any case the acid sodium carbonate is an unstable salt. Not only when heated alone, but even on being slightly heated in solution, and also at the ordinary temperature in damp air, it loses carbonic anhydride and forms the normal salt. And at the same time it is easy to obtain it in a pure crystalline form, if a strong solution of sodium carbonate be cooled and a stream of carbonic anhydride gas passed through it. The acid salt is less soluble in water than the normal,²¹ and therefore a strong solution of the latter gives crystals of the acid salt if carbonic anhydride be passed through it. The acid salt may be yet more conveniently formed from effloresced crystals of sodium carbonate,

²⁰ At the same time the sesqui-salt has all the properties of a definite compound; it crystallises in transparent crystals, has a constant composition, its solubility (at 0° in 100 of water, 12·6 of anhydrous salt) differs from the solubility of the normal and acid salts, and shows changes in composition; it is found in nature, and is known by the names of *trona* and *urao*. The observations of Watts and Richards showed (1886) that on pouring a strong solution of the acid salt into a solution of the normal salt saturated by heating, crystals of the salt $\text{NaHCO}_3, \text{Na}_2\text{CO}_3, 2\text{H}_2\text{O}$ may be easily obtained, as long as the temperature is above 35°. The natural urao (Boussingault) has, according to Laurent, the same composition. This salt is very stable in air, and may be used for purifying sodium carbonate on the large scale. From the theoretical side such compounds have been little studied, yet are particularly interesting because, in all probability, they correspond with ortho-carbonic acid $\text{C}(\text{OH})_2$, and at the same time correspond with double salts like astrachanite (Chapter XIV.).

²¹ 100 parts of water at 0° dissolves 7 parts of the acid salt, which corresponds with 4·3 parts of the anhydrous normal salt, but at 0° 100 parts of water dissolves 7 parts of the latter. The solubility of the acid salt varies with considerable regularity; 100 parts of water dissolves at 15° 9 parts of the salt, at 30° 11 parts.

The ammonium, and more especially the calcium, salt, is much more soluble in water. The ammonia process (*see ante*, p. 516) is founded upon this. Ammonium bicarbonate (acid carbonate) at 0° has a solubility of 12 parts in 100 water, at 30° of 27 parts. The solubility, therefore, increases very rapidly with the temperature. But its saturated solution is more stable than a solution of sodium bicarbonate. In fact, saturated solutions of these salts have the vapour tension of a mixture of carbonic anhydride and water—namely at 15° and at 50°, for the sodium salt 120 and 750 millimetres, for the ammonium salt 120 and 563 millimetres. These data are of great importance in understanding the phenomena connected with the ammonia process. They demonstrate that with an increased pressure the formation of the sodium salt ought to increase if there be an excess of ammonium salt.

which, on being considerably heated, very easily absorb carbonic anhydride.²² The acid salt crystallises well, but not, however, in such large crystals as the normal salt; it has a brackish and not an alkaline taste like that of the normal salt, its reaction is feebly alkaline, nearly neutral. At 70° its solution begins to lose carbonic anhydride, and on boiling the evolution becomes very abundant. From the preceding remarks it is clear that in most reactions this salt, especially when heated, acts similarly to the normal salt, but has, naturally, some distinctions from it. Thus, for example, if a solution of sodium carbonate be added to a normal magnesium salt a turbidity (precipitate) is formed of magnesium carbonate, MgCO_3 . No such precipitate is formed by the acid salt, because magnesium carbonate is soluble in the presence of an excess of carbonic anhydride.

Sodium carbonate is used for the preparation of *caustic soda*²³—that is, the hydrate of sodium oxide, or the alkali which corresponds with sodium. For this purpose the action of lime on a solution of sodium carbonate is generally made use of. The process is as follows: a weak, generally 10 per cent., solution of sodium carbonate is taken,²⁴ and boiled in a cast-iron, wrought-iron, or silver boiler (sodium hydroxide does not act on these metals), and lime is added, little by little, during the boiling. This latter is soluble in water, although but very slightly. The clear solution becomes turbid on the addition of the lime because a precipitate is formed; this precipitate consists of calcium carbonate, almost insoluble in water, whilst caustic soda is formed and remains in solution. The decomposition is effected according to the equation: $\text{Na}_2\text{CO}_3 + \text{Ca}(\text{HO})_2 = \text{CaCO}_3 + 2\text{NaHO}$. On cooling the solution the calcium carbonate easily settles as a precipitate,

²² Crystalline sodium carbonate (broken into lumps) also absorbs carbonic anhydride, but the water contained in the crystals is then disengaged: $\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O} + \text{CO}_2 = \text{Na}_2\text{CO}_3 + \text{H}_2\text{CO}_3 + 9\text{H}_2\text{O}$, and dissolves part of the carbonate; therefore part of the sodium carbonate passes into solution together with all the impurities. When it is required to avoid the formation of this solution, a mixture of ignited and crystalline sodium carbonate is taken. Sodium bicarbonate is prepared chiefly for medicinal use, and is then often termed *carbonate of soda*, also, for instance in the so-called soda powders, for preparing certain artificial mineral waters, for the rapid generation of considerable quantities of carbonic anhydride in the domestic preparation of water charged with carbonic acid, for the manufacture of digestive lozenges like those made at Essentuki, Vichy (pastilles digestives de Vichy), &c.

²³ In chemistry sodium oxide is termed 'soda,' which word must be carefully distinguished from the word sodium, meaning the metal.

²⁴ With a small quantity of water, the reaction either does not take place, or even proceeds in the reverse way—that is, sodium and potassium hydroxides remove carbonic anhydride from calcium carbonate (Liebig, Watson, Mitscherlich, and others). The influence of the mass of water is evident. According to Gerberts, strong solutions of sodium carbonate are, however, decomposed by lime, which is very interesting if confirmed by further investigation.

and the clear solution or alkali above it contains the easily-soluble sodium hydroxide formed in the reaction.²⁵ After the necessary quantity of lime has been added, the solution is allowed to stand, and is then decanted off and evaporated in cast or wrought iron boilers, or in silver pans if a perfectly-pure product is required.²⁶ The evaporation cannot be conducted in china, glass, or similar vessels, because caustic soda eats into glass and china, although but slightly. The solution does not crystallise on evaporation, because the solubility of caustic soda when heated is very great, but crystals containing water of crystallisation may be obtained by cooling. If the evaporation of the alkali be conducted until the specific gravity reaches 1.38, and the liquid is then cooled to 0°, transparent crystals appear contain-

²⁵ As long as part of the undecomposed sodium carbonate remains in solution, excess of acid added to the solution disengages carbonic anhydride, and the solution after dilution gives a white precipitate with a barium salt soluble in acids, showing the presence of a carbonate in solution (if there be sulphate present, it also forms a white precipitate, but this is insoluble in acids). For the decomposition of sodium carbonate, milk of lime—that is, slaked lime suspended in water—is employed. Formerly pure sodium hydroxide was prepared (according to Berthollet) by dissolving the impure substance in alcohol (sodium carbonate and sulphate are not soluble), but now that metallic sodium has become cheap and is purified by distillation, *pure caustic soda* is prepared by acting on a small quantity of water with sodium. By allowing strong solutions to crystallise (in the cold) completely pure sodium hydroxide may also be obtained (Note 27).

In alkali works where the Leblanc process is used, caustic soda is prepared directly from the alkali remaining in the mother liquors after the separation of the sodium carbonate evaporation (Note 14). If excess of lime and charcoal has been used, much sodium hydroxide may be obtained. After the removal as far as possible of the sodium carbonate, a red liquid (from iron oxide) is left, containing sodium hydroxide mixed with compounds of sulphur and of cyanogen (formed in the Leblanc furnaces, see p. 225, and Chapter IX.) and also containing iron. This red alkali is evaporated and air is blown through it, which oxidises the impurities (for this purpose sometimes sodium nitrate is added, or bleaching powder, &c.) and leaves fused caustic soda. The fused mass is allowed to settle in order to separate the ferruginous precipitate, and poured into iron barrels, where the sodium hydroxide solidifies. Such caustic soda contains about 10 p.c. of water in excess and some saline impurities, but when properly manufactured is almost free from carbonate and from iron.

²⁶ Löwig gave a method of preparing sodium hydroxide from sodium carbonate by heating it to a dull red heat with an excess of ferric oxide. Carbonic anhydride is given off, and warm water extracts the caustic soda from the remaining mass. This reaction, as experiment shows, proceeds very easily, and is an example of contact action similar to the influence of ferric oxide on the decomposition of potassium chlorate. The reason of this may be that a small quantity of the sodium carbonate enters into double decomposition with the ferric oxide, and the ferric carbonate produced is decomposed into carbonic anhydride and ferric oxide, the action of which is renewed. Similar explanations expressing the *motive* of a reaction really add but little to that elementary conception of contact which, according to my opinion, consists in the change of motion of the atoms in the molecules under the influence of the substance in contact. In order to represent this clearly it is sufficient, for instance, to imagine that in the sodium carbonate the elements CO_2 move in a circle round the elements Na_2O , but at the points of contact with Fe_2O_3 the motion becomes elliptic with a long axis, and at some distance from Na_2O the elements of CO_2 are parted, not having the faculty of attaching themselves to Fe_2O_3 .

ing $2\text{NaHO}, 7\text{H}_2\text{O}$, they fuse at $+6^\circ$.²⁷ If the evaporation be conducted as long as water is disengaged, which requires a considerable amount of heat, then, on cooling, the hydroxide, NaHO , solidifies in semi-transparent crystals.²⁸

Caustic soda, free from water, forms a colourless crystalline mass, which eagerly absorbs moisture and carbonic anhydride from the air.²⁹ Its specific gravity is 2.13;³⁰ it is easily soluble in water, with disengagement of a considerable quantity of heat.³¹ A saturated solution at the ordinary temperature has a specific gravity of about 1.5, contains about 45 per cent. of sodium hydroxide, and boils at 130° ; at 55° water dissolves an equal weight of it.³² Caustic soda is not only soluble in water but in alcohol, and even in ether. Solutions of sodium hydroxide produce the sensation of soaping on the skin, because the active base of soap consists of caustic soda.³³

²⁷ By allowing strong solutions of sodium hydroxide to crystallise in the cold, impurities—such as, for instance, sodium sulphate—may be separated from them. The fused crystallo-hydrate $2\text{NaHO}, 7\text{H}_2\text{O}$ forms a solution having a specific gravity of 1.405 (Hernes). Let us remark that, according to certain determinations, less water—namely, only $\text{NaHO}, 3\text{H}_2\text{O}$ —enters into the composition of the crystallo-hydrate. The crystals on dissolving in water produce cold.

²⁸ In solid caustic soda there is generally an excess of water beyond that required by the formula NaHO . The caustic soda used in laboratories is generally cast in sticks, which are broken into pieces. It must be preserved in carefully closed vessels, because it absorbs water and carbonic anhydride from the air.

²⁹ By the way it changes in air it is easy to distinguish caustic soda from caustic potash, which in general resembles it. Both alkalis absorb water and carbonic anhydride from the air, but caustic potash forms a deliquescent mass of potassium carbonate, whilst caustic soda forms a dry powder of efflorescent salt.

³⁰ As the molecular weight of $\text{NaHO} = 40$, the volume of its molecule $= 40 \cdot 2.13 = 18.5$, which very nearly approaches the volume of a molecule of water. The same in general refers to the compounds of sodium—for instance, its salts have a molecular volume approaching the volume of the acids from which they are derived.

³¹ The molecular quantity of sodium hydroxide (40 grams), on being dissolved in a large mass (200 gram molecules) of water, develops, according to Berthelot 9780, and according to Thomsen 9940, heat-units, but at 100° about 13000 (Berthelot). Solutions of $\text{NaHO} + n\text{H}_2\text{O}$, on being mixed with water, evolve heat if they contain less than $6\text{H}_2\text{O}$, but if more they absorb heat.

³² The specific gravity of solutions of sodium hydroxide at 15° is given in the short table below:—

NaHO , p.c. . .	5	10	15	20	30	40
Sp. gr. . . .	1.057	1.113	1.169	1.224	1.331	1.436

1000 grams of a 5 p.c. solution occupies a volume of 946 c.c.; that is, less than the water serving to make the solution (see Note 18).

³³ Sodium hydroxide (and other alkalis) is capable of hydrolysing—saponifying, as it is termed—the compounds of acids with alcohols. If RHO (or $\text{R}(\text{HO})_n$) represent the composition of an alcohol—that is, of the hydroxide of a hydrocarbon radicle—and QHO an acid, then the compound of the acid with the alcohol or ethereal salt of the given acid will have the composition RQO . Ethereal salts, therefore, present a similitude to metallic salts, just as alcohols resemble basic hydroxides. Sodium hydroxide acts on

The chemical *reactions of sodium hydroxide* serve as a type for those of a whole class of alkalis—that is, of soluble basic hydroxides which may be obtained from water and a metallic oxide, and whose composition is expressed as a compound of the metal, M, and hydroxyl, OH; MOH. The solution of sodium hydroxide is a very caustic liquid—that is to say, it acts in a destructive way on most substances, for instance, on most organic tissues—hence caustic soda, like all soluble alkalis, is a poisonous substance; acids, for instance, hydrochloric, forming common salt, serve as antidotes. The action of caustic soda on bones, fat, starch, and similar vegetable and animal substances explains its action on organisms. Thus bones, when plunged into a weak solution of caustic soda, fall to powder,³⁴ and evolve a smell of ammonia, which is due to the caustic soda changing the gelatinous organic substance (it contains carbon, hydrogen, nitrogen, oxygen, and sulphur, like albumin) of the bones, dissolving it and in part destroying it, whence ammonia is disengaged. Fats, tallow, and oils become

etheral salts in the same way that it acts on the majority of metallic salts—namely, it liberates alcohol, and forms the sodium salt of that acid which was in the etheral salt. The reaction takes place in the following way:—



Such a decomposition is termed saponification, because similar reactions were known very long ago for the etheral salts corresponding with glycerin, $\text{C}_5\text{H}_5(\text{OH})_5$ (Chapter IX.), found in animals and plants, and composing what are called fats or oils. Caustic soda, acting on fat and oil, forms glycerin, and sodium salts of those acids which were in union with the glycerin in the fat, as Chevreul showed at the beginning of this century. The sodium salts of the fatty acids are known in practice as soaps. That is to say, that soap is made from fat and caustic soda, glycerin being separated and a sodium salt formed. As glycerin is usually found in union with certain acids, so also are the sodium salts of certain acids found in soap. The greater part of the acids found in conjunction with glycerin in fats are the solid, palmitic and stearic acids, $\text{C}_{16}\text{H}_{32}\text{O}_2$ and $\text{C}_{18}\text{H}_{36}\text{O}_2$, and the liquid, oleic acid, $\text{C}_{18}\text{H}_{34}\text{O}_2$; hence soap principally contains a mixture of the sodium salts of these acids. In preparing soap the fatty substances are mixed with a solution of caustic soda until an emulsion is formed; the proper quantity of caustic soda is then added in order to produce saponification when heated, the soap being separated from the solution either by means of an excess of caustic soda or else by common salt, which displaces the soap from the aqueous solution (salt water does not dissolve soap, neither does it form a lather). The water, acting on the soap, partly decomposes it (because the acids of the soap are feeble), and the alkali set free acts during the application of soap. Hence it may be replaced by a very feeble alkali. Strong solutions of alkali corrode the skin and tissues. They are not formed from soap, because the reaction is reversible, and the alkali is only set free by the excess of water. Thus we see how the teaching of Berthollet renders it possible to understand many phenomena which occur during everyday experience.

³⁴ On this is founded the process of Henkoff and Engelhardt for treating bones. The bones are mixed with ashes, lime, and water: it is true in this case that more potassium hydroxide than sodium hydroxide is formed, but their action is almost identical.

saponified with a solution of caustic soda—that is to say, they form with it *soaps* soluble in water, or sodium salts of the organic acids contained in the fats.³⁵ The clearest reactions of sodium hydroxide are determined by the fact that it *saturates all acids forming salts with them*, which are almost all soluble in water, and in this respect caustic soda is as characteristic amongst the bases as nitric acid is among the acids. It is impossible to detect sodium by means of the formation of precipitates of insoluble sodium salts, as may be done with other metals, many of whose salts are but slightly soluble. The powerful alkaline properties of caustic soda determine its capacity for combining with even the feeblest acids, its property of disengaging ammonia from ammonium salts, its faculty of acting on salts whose bases are insoluble in water, &c. If a solution of the salt of almost any metal be mixed with caustic soda, then a soluble sodium salt will be formed, and an insoluble hydroxide of the metal will be separated—for instance, copper nitrate yields copper hydroxide, $\text{Cu}(\text{NO}_3)_2 + 2\text{NaHO} = \text{Cu}(\text{HO})_2 + 2\text{NaNO}_3$. Even many *basic oxides*—as, for instance, the oxides of zinc and aluminium—precipitated by caustic soda, *are capable of combining* with it and forming soluble compounds, and therefore caustic soda in the salts of such metals first forms a precipitate of hydroxide, and then, employed in excess, dissolves this precipitate. This phenomenon occurs, for instance, when caustic soda is added to the salts of aluminium. This shows the property of such an alkali as caustic soda of combining not only with acids, but also with feeble basic oxides. For this reason caustic soda *acts on most elements* which are capable of forming acids or oxides similar to them; thus, for instance, the metal aluminium gives hydrogen with caustic soda in consequence of the formation of alumina, which combines with the caustic soda—that is, in this case, the caustic alkali acts on the metal just like an acid. If the substance which is mixed with the caustic soda is capable of combining with the hydrogen evolved (aluminium does not form such a compound), then such a compound will be formed. Thus, for instance, in this way phosphorus acts on caustic soda, yielding hydrogen phosphide. If the hydrogen compound disengaged is capable of combining with the alkali, then, naturally, a salt of the corresponding acid is formed. For instance, chlorine and sulphur act thus on caustic soda. Chlorine, with the hydrogen of the caustic soda, forms hydrochloric acid, and the latter forms common salt with the sodium hydroxide, whilst the other atom in the molecule of chlorine, Cl_2 , takes the place of the hydrogen, and

³⁵ As explained in Note 33.

forms the hypochlorite, NaClO . In the same way, by the action of sodium hydroxide on sulphur, hydrogen sulphide is formed, which acts on the soda forming sodium *sulphide*, in addition to which sodium thiosulphate is formed (*see* sulphur). In virtue of the possibility of similar reactions, sodium hydroxide acts on many metals and non-metals. Such action is often accelerated by the presence of the oxygen of the air, as by this means the possibility of the formation of acids and oxides rich in oxygen is increased. Thus many metals and their lower oxides, in the presence of an alkali, absorb oxygen and form acids. Even manganese peroxide, when mixed with caustic soda, is capable of absorbing the oxygen of the air, because sodium manganate is formed. Organic acids, when heated with caustic soda, give up to it the elements of carbonic anhydride, forming sodium carbonate, and separating that hydrocarbon group which exists, in combination with carbonic anhydride, in the organic acid.

Thus sodium hydroxide, like the soluble alkalis in general, ranks amongst the most active substances in the chemical sense of the term ; but few substances are capable of resisting it. Even the rocky siliceous substances, as we shall see further on, are transformed by it, forming vitreous slags with it, at all events on fusion. Sodium hydroxide, as a typical example of the basic hydrates, in distinction from many other basic oxides, easily *forms acid salts* with acids (for instance, NaHSO_4 , NaHCO_3), and does not form any basic salts at all ; whilst many less energetic bases, such as the oxides of copper and lead, easily form basic salts, but acid salts only with difficulty. This capability of forming acid salts, particularly with polybasic acids, may be explained by the energetic character of the basic properties of sodium hydroxide, and the small development of these properties in the bases which easily form basic salts. These latter bases are even capable of combining with such bases as sodium hydroxide and ammonium hydroxide. An energetic base is capable of retaining a considerable quantity of acid, which a slightly energetic base would not have the power of doing. Certain feeble bases, particularly intermediate ones (like alumina) are not at all capable of retaining such feeble acids as carbonic, or, if they form compounds with them, they are very unstable and basic. The formation of acid salts with such acids as carbonic, oxalic, sulphuric, phosphoric, &c., which contain two or more atoms of hydrogen, capable of being replaced by metals, is explained by the fact that the normal salt represents the substitution of sodium for all the atoms of hydrogen. Such monobasic acids as nitric, hydrochloric, &c., do not form any stable acid salts (although they form unstable compounds of the normal salt with the

acid), because they contain only one atom of hydrogen capable of being replaced by the metal. Also, as will be shown in the subsequent chapters, sodium belongs to the univalent metals, exchangeable for hydrogen atom for atom; amongst metals sodium may, like chlorine amongst the non-metals, serve as a representative of the univalent properties. Most of the other elements which are not capable of forming acid salts are bivalent, from whence it may be understood that in a bibasic acid—for instance, carbonic, H_2CO_3 , or sulphuric, H_2SO_4 —the hydrogen may be exchanged, atom for atom, for sodium, and yield an acid salt by means of the first substitution and a normal salt by means of the second—for instance, NaHSO_4 , and Na_2SO_4 , whilst such bivalent metals as calcium or barium do not form acid salts because one of their atoms at once takes the place of both hydrogen atoms, forming, for instance, CaCO_3 and CaSO_4 . It may be expected, from what has been mentioned above, that bivalent metals easily form acid salts with acids containing more than two atoms of hydrogen for instance, with tribasic acids, such as phosphoric acid, H_3PO_4 —and actually such salts do exist; but all such relations are complicated by the fact that the character of the base very often changes and becomes weakened with the increase of valency and the change of atomic weight, and feebler bases (for instance, silver oxide), although corresponding with univalent metals, do not form acid salts, and the feeblest bases (for instance, CuO , PbO) easily form basic salts, and, notwithstanding their valency, do not form any acid salts which are in any degree stable—for instance, which are undecomposable by water. In addition, basic and acid salts ought to be regarded rather as compounds similar to crystallo-hydrates, because such acids as sulphuric form with sodium not only an acid and a normal salt, as might be expected judging from the valency of sodium, but in addition to these also salts containing a greater quantity of acid. In sodium sesquicarbonate we saw an example of such compounds. Taking all this into consideration, we ought to say that the property of more or less easily forming acid salts more readily accords with the energy of the base than with the valency, and it is truest of all to state that *the faculty of a base to form acid and basic salts is its characteristic*, just as the faculty of forming compounds with hydrogen is a characteristic property of elements. In this respect sodium hydroxide distinguishes itself by the facility with which it forms acid salts and an absence of the faculty of forming basic salts. This property is also shared with sodium by the bases formed from the metals potassium and lithium. The metals lead and copper do not form acid salts, but easily give basic salts. Barium,

calcium, and silver form acid and basic salts with difficulty, although they easily form normal ones.

We have seen the transformation of common salt into sodium sulphate, of this latter into sodium carbonate, and of sodium carbonate into caustic soda. Lavoisier still regarded sodium hydroxide as an element, because he was unacquainted with its decomposition with the elimination of oxygen and its formation by means of metallic sodium, which separates the hydrogen from water, forming caustic soda. The preparation of *metallic sodium* was one of the greatest discoveries in chemistry, not only because through it the conception of elements became broader and more regular, but especially because in sodium chemical properties were observed which were but feebly shown in the other metals more familiarly known. This discovery was made in 1807 by the English chemist *Davy* by means of the galvanic current. By connecting with the positive pole (of copper or charcoal) a piece of moist (in order to obtain electrical conductivity) caustic soda, and boring a hole in it filled with mercury connected with the negative pole of a strong Volta's pile, Davy observed that on passing the current, a peculiar metal dissolved in the mercury, less volatile than mercury, and capable of decomposing water, again forming caustic soda. In this way (by analysis and synthesis) Davy demonstrated the complexity of alkalis, which up to that time had been regarded as undecomposable substances. On being decomposed by the galvanic current, caustic soda disengages hydrogen and sodium at the negative pole and oxygen at the positive pole. Davy showed that the metal formed volatilises at a red heat, which is the most important physical property for extracting sodium, because all further methods are founded on the volatility of sodium. Besides this Davy observed that sodium easily oxidises, that its vapours take fire in air, and the latter circumstance was for a long time an obstacle to the easy preparation of this metal. The properties of sodium were later on more thoroughly investigated by Gay-Lussac and Thenard, who furnished easier means of obtaining sodium, and observed that metallic iron at a high temperature was capable of reducing sodium from caustic soda.⁵⁶ Brunner latterly discovered that not only iron,

⁵⁶ Deville supposes that such a decomposition of sodium hydroxide by metallic iron depends solely on the dissociation of the alkali at a white heat into sodium, hydrogen, and oxygen. Here the part played by the iron is only that it retains the oxygen formed, otherwise the decomposed elements would again reunite upon cooling, as in other cases of dissociation. If it be supposed that the temperature at the commencement of the dissociation of the iron oxides is higher than that of sodium oxide, then the decomposition may be explained by the hypothesis of Deville. Deville demonstrates his views by the following experiment:—An iron bottle, filled with iron shavings, was heated in such a way that the upper part became red hot, the lower part remaining cooler; sodium

but also charcoal, has this property, although hydrogen does not reduce sodium.³⁷ But still the methods of extracting sodium were very troublesome, and consequently sodium was a great rarity. The principal obstacle to its production was that they endeavoured to condense the easily-oxidising vapours of sodium in vacuum in complicated apparatus. For this reason, when Donny and Maresca, having thoroughly studied the matter, constructed a specially simple condenser, the production of sodium was much facilitated. Furthermore, in practice the most important epoch in the history of the production of sodium is comprised in the investigation of Sainte-Claire Deville, who avoided the complex methods in vogue up to that time, and furnished those simple means by which the production of sodium is now rendered feasible in chemical works.


For the production of sodium according to the method of Deville, a mixture of sodium carbonate (7 parts) free from water, charcoal (two parts), and lime or chalk (7 parts) is heated. This latter ingredient is only added in order that the sodium carbonate, on fusing, shall not separate from the charcoal.³⁸ The chalk on being heated loses carbonic anhydride, leaving infusible lime, which is permeated by the sodium carbonate and forms a thick mass, in which the charcoal is situated, in immediate contact with the sodium carbonate. That is to say, the lime only serves as a mechanical admixture. When the charcoal is heated

hydroxide was introduced into the upper part. The decomposition was then effected—that is, sodium vapours were produced (this experiment was done really with potassium hydroxide). On unfastening the bottle it was found that the iron in the upper part was not oxidised, but only that in the lower part. This may be explained by the decomposition of the alkali into sodium, hydrogen, and oxygen taking place in the upper part, whilst the iron in the lower part absorbed the oxygen set free. If the whole bottle be subjected to the same moderate heat as the lower extremity, no metallic vapours are formed. Then, according to the hypothesis, the temperature would be insufficient for the dissociation of the sodium hydroxide.

³⁷ It has been previously remarked (Chapter II. Note 9) that Beketoff showed the displacement of sodium by hydrogen, not from sodium hydroxide but from the oxide Na_2O ; then, however, only one half is displaced, with the formation of NaHO .

³⁸ In latter times in England, where the preparation of sodium is at present carried on on a large commercial scale (from 1860 to 1870 it was only manufactured in a few works in France), they have begun to add to Deville's mixture more iron, or iron oxide, which, with the charcoal, gives metallic and carburated iron, which still further facilitates the decomposition. At present a kilogram of sodium may be purchased for about the same sum (2/-) as a gram cost thirty years ago. The industrial preparation of sodium in large quantities ought not only to influence the extraction of such metals as aluminium (metal of clay and alun), but also many other branches of industry. The method of preparation by means of the action of the galvanic current, proposed and tried many times, still requires further improvement. Deville overcame the practical difficulties connected with his process, which is that in use at present, and is distinguished by its simplicity and cheapness; but so far industry has but scantily availed itself of the possibility of obtaining cheap sodium.

with the sodium carbonate, at a white heat, carbonic oxide and vapours of sodium are disengaged, according to the equation :



On cooling the vapours and gases disengaged, the vapours condense into molten metal (in this form sodium does not easily oxidise, whilst in vapour it burns) and the carbonic oxide remains as gas.

Here are the simple means by which metallic sodium may be obtained. An iron tube, about a metre long and a decimetre in diameter, is made out of boiler plate. The pipe is cemented into a furnace having a strong




FIG. 71.—Manufacture of sodium by Deville's process. A C, iron tube containing a mixture of soda, charcoal, and chalk. B, condenser.

draught, capable of giving a high temperature, and the tube is charged with the mixture required for the preparation of sodium. One end of the tube is closed with a cast-iron stopper A with clay luting, and the other with the cast-iron stopper C provided with an aperture. On heating, first of all the moisture contained in the various substances is given off, then carbonic anhydride and the products of the dry distillation of the charcoal, then the latter begins to act on the sodium carbonate, and carbonic oxide and vapours of sodium appear. It is easy to observe the appearance of the latter, because on issuing from the aperture in the stopper C they take fire spontaneously and burn with a very bright yellow flame. The pipe of the condenser is then introduced into the aperture C, compelling in this way the vapours and gases formed to pass through the condenser B. This condenser consists of two square cast-iron trays, A and A', Fig. 72, with wide edges firmly screwed together. Between these two trays there is a space in which the condensation of the vapours of sodium is accomplished, because the thin metallic walls of the condenser

are cooled by the air but remain sufficiently heated to preserve the sodium in a liquid state, and so it does not choke the apparatus, but continually flows from it. The vapours of sodium, condensing in the cooler, flow in the shape of liquid metal into a vessel containing some non-volatile naphtha or hydrocarbon. This is used in order to prevent the sodium oxidising as it issues from the condenser at a somewhat high temperature. During the operation it is necessary (with an iron rod) to occasionally clear the pipe which conducts the vapours to the condenser, because it becomes choked up with solid compounds formed by the sodium. In order to obtain sodium of a pure quality it is necessary to distil it once more, which may even be done in porcelain retorts, but the distillation must be conducted in a stream of some gas on which sodium does not act, for instance in a stream of nitrogen; carbonic anhydride is not applicable, because sodium partially decomposes it, absorbing the oxygen from it.




FIG. 72. Donny and Maresca's sodium condenser, consisting of two cast-iron plates screwed together.

Pure sodium is a lustrous metal, white as silver, soft as wax; it becomes brittle in the cold. In ordinary moist air it quickly tarnishes and becomes covered with a film of hydroxide, NaHO , formed at the expense of the water in the air. In completely dry air sodium retains its lustre for an indefinite time. Its density at the ordinary temperature is equal to 0.98, so that it is lighter than water; it fuses very easily at a temperature of 95° , and distils at a bright red heat (about 900°). It forms alloys with most metals, combining with them, heat being sometimes evolved and sometimes absorbed. Thus if sodium (having a clean surface) be thrown into mercury, especially when heated, there is a flash, and such a considerable amount of heat is evolved that part of the mercury is transformed into vapour.³⁹ Compounds or solutions of sodium

³⁹ By dissolving sodium amalgams in water and acids, and deducting the heat of solution of the sodium, Berthelot found that *for each atom of the sodium* in amalgams containing a large amount of mercury (more than 90 p.c.) the amount of heat evolved increases with the quantity of sodium, and also that when a composition is reached which approaches NaHg_5 , the heat evolved decreases. In the formation of the latter compound, about 18500 calories are evolved; when NaHg_5 is formed, about 14000; and for NaHg about 10000 calories. Kraut and Popp regarded the definite crystalline amalgam as having the composition of NaHg_6 , but at the present time, in accordance with Grimaldi's results, it is thought to be NaHg_5 . A similar amalgam is very easily obtained if a 3 p.c. amalgam be left several days in a solution of sodium hydroxide until a crystalline mass is formed, from which the mercury may be removed by strongly pressing in chamois leather. This amalgam with a solution of potassium hydroxide forms a potassium amalgam, KHg_{10} (Crookewitt, Grimaldi). It may be mentioned here that

in mercury, or *amalgams* of sodium, even when containing 2 parts of sodium to 100 parts of mercury, are solids. Only those amalgams which are the very poorest in sodium are liquid. Such alloys of sodium with mercury are often used instead of sodium in chemical investigations, because in combination with mercury sodium is not easily acted on by air, and is a mass heavier than water, and therefore more convenient to handle, whilst at the same time it retains the principal properties of sodium.⁴⁰

It is easy to form an alloy of mercury and sodium having a crystalline structure, and a definite atomic composition NaHg_5 . The alloy of sodium with hydrogen or *sodium hydride*, Na_2H , which has the external appearance of a metal,⁴¹ is a most instructive example of the characteristics of alloys. At the ordinary temperature sodium does not absorb hydrogen, but from 300° to 421° the absorption takes place at the ordinary pressure (and at an increased pressure even at higher temperatures), as shown by Troost and Hautefeuille (1874). One volume of sodium absorbs as much as 238 vols. of hydrogen. The metal increases in volume, and when once formed the alloy can be preserved for some time without change at the ordinary temperature. The appearance of sodium hydride resembles that of sodium itself; it is as soft as this latter, when heated it becomes brittle, and decomposes above 300° , evolving hydrogen. In this decomposition all the phenomena of dissociation are very clearly shown—that is, the hydrogen gas evolved has a definite tension,⁴² which corresponds with each definite temperature. This confirms the fact, that the formation of substances capable of dissociation is only accomplished within the limits of the dissociation. Sodium hydride melts more easily than sodium itself, and

the latent heat of fusion (of atomic quantities) of $\text{Hg} = 360$ (Personne), $\text{Na} = 730$ (Joannis), and $\text{K} = 610$ calories (Joannis).

⁴⁰ Alloys are so similar to solutions (exhibiting such complete parallelism in properties) that they are contained in the same class of so-called indefinite compounds (Chapter I.). But in alloys, as substances passing from the liquid to the solid state, it is easier to discover the formation of definite chemical compounds, and therefore, in order to arrive at a correct understanding of solutions, it is very important to study alloys. In addition to this, they are of themselves of considerable interest. The combination of sodium with hydrogen, where the change of physical properties is so evident and where the conservation of chemical properties and easy dissociation are so apparent, ought in this respect to supply much towards an understanding of alloys and also of solutions. Alloys and solutions are homogeneous; if the decomposition has commenced or increased we may not perceive it, but the products of the splitting up of the alloy Na_2H are heterogeneous; they are visible.

⁴¹ Potassium forms a similar compound, but lithium, under the same circumstances, does not.

⁴² Namely, the tension of dissociation of hydrogen, p , in millimetres of mercury, is:—

$t =$	330°	350°	380°	400°	420°	430°
$p =$	28	57	150	447	752	900

then does not undergo decomposition if it is in an atmosphere of hydrogen. It oxidises easily in air, but not so easily as potassium hydride. The chemical reactions of sodium are retained in its hydride, and, if we may so express it, they are even increased by the addition of hydrogen. At all events, in the properties of sodium hydride⁴³ we see other properties than in such hydrogen compounds as HCl , H_2O , H_3N , H_4C , or even in the gaseous metallic hydrides AsH_3 , TeH_2 . But platinum, palladium, nickel, and iron, in absorbing hydrogen form compounds in which hydrogen is in a similar state. In them, as in sodium hydride, the hydrogen is compressed, absorbed, occluded (page 141).

The most important property of sodium is its power of easily decomposing water and *evolving hydrogen* from the majority of the hydrogen compounds, and especially from all acid and hydrate compounds in which hydroxyl ought to be recognised. This depends on the power of sodium of combining with the elements which are in combination with the hydrogen. We already know that sodium disengages hydrogen, not only from water, hydrochloric acid,⁴⁴ and all other acids, but also from ammonia, although it does not displace hydrogen from the hydrocarbons.⁴⁵

⁴³ In general, during the formation of alloys the volumes change very slightly, and therefore from the volume of Na_2H some idea may be formed of the volume of hydrogen in a solid or liquid state. Archimedes even concluded that there was gold in an alloy of copper and gold by reason of its volume and density. From the fact that the density of Na_2H is equal to 0.959, it may be seen that the volume of 47 grams (the gram molecule) of this compound = 49.0 c.c. The volume of 46 grams of sodium contained in the Na_2H is equal (the density in the same conditions 0.97) to 47.4 c.c. Therefore the volume of 1 gram of hydrogen in Na_2H is equal to 1.6 c.c., and consequently the density of metallic hydrogen, or the weight of 1 c.c., approaches 0.6 gram. This density is also proper to the hydrogen alloyed with potassium and palladium. Judging from the scanty information which is at present available, liquid hydrogen near its absolute boiling-point (Chapter II.) has a far less density.

It ought to be mentioned that sodium hydride, according to the usual equivalency of H_2 with O, corresponds, not with the oxide Na_2O , but with the suboxide of sodium, Na_2O , and if we judge the atomicity of elements by hydrogen compounds, sodium ought to be counted as semivalent. According to the law of substitution, Na ought to be taken as univalent in all its ordinary combinations: Na_2O , NaCl , NaHO , NaHSO_4 , &c. Therefore sodium hydride belongs to the series Na_2X , and not NaX .

⁴⁴ H. A. Schmidt remarked that completely dry hydrogen chloride is decomposed with great difficulty by sodium, although the decomposition proceeds easily with potassium and with sodium in moist hydrogen chloride. Wanklyn also remarked that sodium burns with great difficulty in dry chlorine. Probably in relation to this there is a correspondence with other phenomena observed by Dixon, who found that completely dry carbonic oxide does not explode with oxygen on passing an electric spark.

⁴⁵ As sodium does not displace hydrogen from the hydrocarbons, it *may be preserved* in liquid hydrocarbons. Naphtha is generally used for this purpose, as it consists of a mixture of various liquid hydrocarbons. However, in naphtha sodium usually becomes coated with a crust composed of matter produced by the action of the sodium on certain of the substances contained in the mixture composing naphtha. In order that sodium may retain its lustre in naphtha, secondary octyl alcohol is added. (This alcohol is obtained by distilling castor oil with caustic potash.) Potassium and sodium keep well in a mixture of pure benzene and naphthalene.

Sodium burns both in chlorine and in oxygen, evolving much heat. These properties of sodium are closely connected with its power of taking up oxygen, chlorine, and similar elements from most of their compounds. Just as sodium removes the oxygen from the oxides of nitrogen and from carbonic anhydride, so also does it decompose the majority of oxides at definite temperatures. Here the essence of the matter is the same as in the decomposition of water. Thus, for instance, when acting on magnesium chloride, the sodium displaces the magnesium, or when acting on aluminium chloride sodium displaces metallic aluminium. Sulphur, phosphorus, arsenic, and a whole series of other elements, also combine with sodium.⁴⁶

With oxygen sodium unites in three degrees of combination, forming a suboxide, Na_4O , an oxide, Na_2O , and a peroxide, NaO . They are thus termed because Na_2O is a basic oxide (with water it forms a basic hydroxide), but Na_4O and NaO do not form corresponding saline compounds. The suboxide is a grey inflammable substance which easily decomposes water, disengaging hydrogen; it is formed by the slow oxidation of sodium at the ordinary temperature. The peroxide is a greenish yellow substance, fusing at a bright red heat; it is produced by burning sodium in an excess of oxygen, and it yields oxygen when treated with water:



⁴⁶ If sodium does not directly displace the hydrogen in hydrocarbons, still by indirect means compounds may be obtained which contain sodium and hydrocarbon groups. Some of these compounds have been produced, although not in a pure state. Thus, for instance zinc ethyl $\text{Zn}(\text{C}_2\text{H}_5)_2$, when treated with sodium, loses zinc and forms sodium ethyl, $\text{C}_2\text{H}_5\text{Na}$, but this decomposition is not complete, and the compound formed cannot be separated by distillation from the remaining zinc ethyl. In this combination the energy of the sodium clearly appears, for which reason it reacts with substances containing haloids, oxygen, &c., and directly absorbs carbonic anhydride, forming a salt of a carboxylic acid (propionic).

⁴⁷ A compound, Na_2Cl , which corresponds with the suboxide, is evidently formed when a galvanic current is passed through fused common salt; the sodium liberated dissolves in the common salt, and does not separate from the compound either on cooling or on treatment with mercury. It is therefore supposed to be Na_2Cl ; the more so as the mass obtained gives hydrogen when treated with water: $\text{Na}_2\text{Cl} + \text{H}_2\text{O} = \text{H} + \text{NaHO} + \text{NaCl}$, that is, it acts like suboxide of sodium. If Na_2Cl really exists as a salt, then the corresponding base Na_4O , according to the example of other bases of the composition M_4O , ought to be called a quaternary oxide. According to certain evidence, a suboxide is formed when thin sheets or fine drops of sodium slowly oxidise in moist air.

⁴⁸ According to observations easily made, sodium when fused in air oxidises but does not burn, the combustion only commencing with the formation of vapour—that is, when considerably heated. Davy and Karsten obtained the oxides of potassium, K_2O , and of sodium,

All three oxides form sodium hydroxide with water, but only the oxide, Na_2O , is directly transformed into a hydrate. The other oxides either liberate hydrogen or oxygen; they also present a similar distinction with reference to many other agents. Thus carbonic anhydride combines directly with the oxide Na_2O , which when heated in the gas burns, forming sodium carbonate, whilst in this case the peroxide⁴⁹ also yields oxygen. When treated with acids, sodium and all its oxides only form the salts corresponding with sodium oxide—that is, of the formula or type NaX . Thus the oxide of sodium Na_2O is *the only salt-forming oxide* of this metal, as water is in the case of hydrogen. Although the peroxide H_2O_2 is derived from hydrogen, yet there are no corresponding salts known, and if they are formed they are probably as unstable as hydrogen peroxide itself. Although carbon forms carbonic oxide, CO , still it has only one salt-forming oxide—carbonic anhydride, CO_2 . Nitrogen and chlorine both give several salt-forming oxides and types of salts. But of the oxides of nitrogen, NO and NO_2 do not form salts, as do N_2O_3 , N_2O_4 , and N_2O_5 , but N_2O_4 does not form special salts, and N_2O_5 corresponds with the highest form of the saline compounds of nitrogen. Such distinctions between the elements, according to their power of giving one or several saline forms, is a radical property of no less importance than the basic or acid properties of the oxides produced. Sodium as a typical metal does not form any acid oxides,

Na_2O , by heating the metals with their hydroxides, whence $\text{NaHO} + \text{Na} = \text{Na}_2\text{O} + \text{H}$, but N. N. Beketoff failed to obtain oxides by this means. He prepared them by directly igniting the metals in dry air, and afterwards heating with the metal in order to destroy any peroxide. The oxide Na_2O produced, when heated in an atmosphere of hydrogen, gave a mixture of sodium and its hydroxide: $\text{Na}_2\text{O} + \text{H} = \text{NaHO} + \text{Na}$ (see Chapter II. Note 9). If both the observations mentioned are accurate, then the reaction is reversible. Sodium oxide ought to be formed during the decomposition of sodium carbonate by oxide of iron (see Note 26), and during the decomposition of sodium nitrite. According to Karsten, its specific gravity is 2.8, according to Beketoff 2.3. The difficulty in obtaining it is owing to an excess of sodium forming the suboxide, and an excess of oxygen the peroxide. The grey colour peculiar to the suboxide and oxide perhaps shows that they contain metallic sodium. In addition to this, in the presence of water it may contain sodium hydride.

⁴⁹ Of the oxides of sodium, that easiest to form is the peroxide NaO or Na_2O_2 ; this is obtained when sodium is burnt in an excess of oxygen. When heated with iodine vapour, it loses oxygen: $\text{Na}_2\text{O}_2 + \text{I}_2 = \text{Na}_2\text{OI}_2 + \text{O}$. The compound Na_2OI_2 is akin to the compound Cu_2OCl_2 obtained by oxidising CuCl . This reaction is one of the few where iodine directly displaces oxygen. The substance Na_2OI_2 is soluble in water, and when acidified gives free iodine and a sodium salt. Carbonic oxide is absorbed by heated sodium peroxide with formation of sodium carbonate: $\text{Na}_2\text{CO}_3 = \text{Na}_2\text{O}_2 + \text{CO}$, whilst carbonic anhydride liberates oxygen from it. With nitrous oxide it reacts thus: $\text{Na}_2\text{O}_2 + 2\text{N}_2\text{O} = 2\text{NaNO}_2 + \text{N}_2$; with nitric oxide it combines directly, forming a nitrite, $\text{NaO} + \text{NO} = \text{NaNO}_2$. Sodium peroxide, when treated with water, does not give hydrogen peroxide, because the latter in the presence of the alkali formed ($\text{Na}_2\text{O}_2 + 2\text{H}_2\text{O} = 2\text{NaHO} + \text{H}_2\text{O}_2$) decomposes into water and oxygen.

whilst chlorine, being a typical non-metal, does not form bases with oxygen. Therefore sodium *as an element* may be thus characterised: it forms one very stable salt-forming oxide, Na_2O , having powerful basic properties, its salts are of the general formula, NaX , therefore in saline compounds it is, like hydrogen, a univalent element.⁵⁰

On comparing sodium and its analogues, which will be described later with other metallic elements, it will be seen that those properties, together with the relative lightness of the metal itself and its compounds, and the magnitude of the atomic weight of sodium, comprise the most essential properties of this element, clearly distinguishing it from others, and enabling us easily to recognise its analogues.

⁵⁰ By heating sodium in dry ammonia, Gay-Lussac and Thénard obtained an olive-green, easily-fusible mass, *sodamide*, NH_2Na , hydrogen being separated. This substance with water forms sodium hydroxide and ammonia; with carbonic oxide, CO , it forms sodium cyanide, NaCN , and water H_2O ; and with dry hydrogen chloride it forms sodium and ammonium chlorides. These and other reactions of sodamide show that the metal in it preserves its energetic properties in reaction, and that this compound of sodium is but little more stable than the corresponding chlorine amide, although it does not show its property of spontaneous decomposition, which is evident from the difference between the properties of metallic sodium and gaseous chlorine. When heated, sodamide, NH_2Na , only partially decomposes, with evolution of hydrogen, the principal part of it giving ammonia and sodium nitride, Na_5N , according to the equation $3\text{NH}_2\text{Na} \rightarrow 2\text{NH}_3 + \text{NNa}_5$. The latter is an almost black powdery mass, decomposed by water into ammonia and sodium hydroxide.

CHAPTER XIII

POTASSIUM, RUBIDIUM, CÆSIUM, AND LITHIUM. SPECTRUM ANALYSIS

JUST as the series of halogens, fluorine, bromine, and iodine, correspond with the chlorine contained in common salt, so there also exists a corresponding series of elements: lithium, $\text{Li}=7$, potassium, $\text{K}=39$, rubidium, $\text{Rb}=85$, and cæsium, $\text{Cs}=133$, which are analogous to the sodium in common salt. These elements bear as great a resemblance to sodium, $\text{Na}=23$, as fluorine, $\text{F}=19$, bromine, $\text{Br}=80$, and iodine, $\text{I}=127$, have to chlorine, $\text{Cl}=35.5$. Indeed, in a free state, these elements are, like sodium, soft metals, which rapidly oxidise in moist air, and decompose water at the ordinary temperature, forming soluble hydroxides, having clearly-defined basic properties, and the composition RHO , like that of caustic soda. The resemblance between these metals is sometimes seen with striking clearness, especially in compounds such as salts. The corresponding salts of nitric, sulphuric, carbonic, and nearly all acids with these metals have many points in common. The metals which resemble sodium so much in their reactions are termed the *metals of the alkalis*.

Among the metals of the alkalis, the most widely distributed in nature, after sodium, is *potassium*. Like sodium, it does not appear either in a free state or as oxide or hydroxide, but in the form of salts, which present much in common with the salts of sodium in the manner of their occurrence. The compounds of potassium and sodium in the earth's crust occur as mineral compounds of silica. With silica, SiO_2 , potassium oxide, like sodium oxide, forms saline mineral substances like glass. If different other oxides, such as lime, CaO , and alumina, Al_2O_3 , combine with these compounds, there is formed glass, or a glassy stony mass, which is distinguished by its great stability. It is such complex silicious compounds as these which contain potash (potassium oxide), K_2O , or soda (sodium oxide), Na_2O , and sometimes both together, silica, SiO_2 , lime, CaO , alumina, Al_2O_3 , and other oxides, that form the chief mass of rocks, out of which, judging by the distribution of the strata, the chief mass of the accessible crust (envelope) of the earth is made up. The primary rocks, like granite,

porphyry, &c.,¹ are formed of such crystalline silicious rocks as these. The oxides entering into the composition of these rocks do not form a homogeneous amorphous mass like glass, but are distributed in a series of peculiar, and in the majority of cases crystalline, compounds, into which the primary rocks may be divided. Thus, as has been already mentioned, granite contains felspar, quartz, and mica. Potash and soda, &c., are generally found in these component parts of rocks. Thus a felspar (orthoclase) in granite contains from 8 to 15 per cent. of potassium, whilst another variety (plagioclase) which also occurs in granite contains 1·2 to 6 per cent. of potassium, and 6 to 12 per cent. of sodium. The mica in granite contains 3 to 10 per cent. of potassium. As has already been mentioned, and will be further explained, the friable, crumbling, and stratified formations which in our times cover a large part of the earth's surface have been formed from these primary rocks by the action of the atmosphere, and of water containing carbonic acid. It is evident that in the formation of these friable formations from the primary rocks by the action of water, the compounds of potassium, as well as the compounds of sodium, must have been dissolved by the water (as they are soluble in water), and, therefore, the compounds of potassium must be accumulated together with those of sodium in sea water. And, indeed, compounds of potassium are always, as we have already pointed out (Chaps. I. and X.) found in *sea water*. This forms one of the sources from which they are extracted. After the evaporation of sea water, there remains a mother liquor, which contains potassium chloride and a large proportion of magnesium chloride. On cooling this solution crystals separate out, which contain chlorides of magnesium and potassium. A double salt of this kind, called *carnallite*, $\text{KMgCl}_3 \cdot 6\text{H}_2\text{O}$, occurs at Stassfurt. This carnallite² is now employed as a material for the extraction of potassium chloride, and of all the compounds of this element.³ Besides which, potassium

¹ The origin of the primary rocks has been mentioned in Chap. X. Note 2.

² Carnallite belongs to the number of double salts which are directly decomposed by water, and it only crystallises from solutions which contain an excess of magnesium chloride. It may be prepared artificially by mixing strong solutions of potassium and magnesium chlorides, when colourless crystals of sp. gr. 1·60 separate, whilst the Stassfurt salt is usually of a reddish tint, owing to traces of iron. At the ordinary temperature sixty-five parts of carnallite are soluble in one-hundred parts of water in the presence of an excess of the salt. It deliquesces in the air, forming a solution of magnesium chloride and leaving potassium chloride.

³ The method of separating sodium chloride from potassium chloride has been described on p. 72. On evaporation of a mixture of the saturated solutions, sodium chloride separates; and then, on cooling, potassium chloride separates, owing to the difference of the variation of their solubilities with the temperature. The following are the most trustworthy figures for the solubility of *potassium chloride* in one hundred parts of water (for sodium chloride, see Chap. X. Note 13):—

10°	20°	40°	60°	100°
32	35	40	40	57

chloride itself is sometimes found at Stassfurt as *sylvine*. By a method of double saline decomposition, the chloride of potassium may be converted into all the other potassium salts,⁴ some of which are of practical use. The potassium salts have, however, their greatest importance as an indispensable component of the food of plants.⁵

When mixed with solutions of other salts the solubility of potassium chloride naturally varies, but not to any great extent. The specific gravity of the solid salt is 1.99—that is, less than that of sodium chloride. All the salts of sodium are specifically heavier than the corresponding salts of potassium, as are also their solutions for equal percentage compositions. If the specific gravity of water at 4°=10000, then at 15° the specific gravity of a solution of p p.c. potassium chloride = $9992 + 63.29p + 0.226p^2$, and therefore for 10 p.c.=10647, 20 p.c.=11348, &c.

Potassium chloride combines with iodine trichloride to form a compound $KCl + ICl_3 = KICl_4$, of a yellow colour, which is fusible, loses the iodine trichloride at a red heat, and gives potassium iodate and hydrochloric acid with water. It is not only formed by direct combination, but also by many other methods; for instance, by passing chlorine into a solution of potassium iodide so long as the gas is absorbed $KI + 2Cl_2 = KCl, ICl_5$. Potassium iodide, when treated with potassium chlorate and strong hydrochloric acid, also gives this compound; another method for the formation of which is shown by the equation $KClO_3 + I + 6HCl = KCl, ICl_3 + 3Cl + 3H_2O$. This is a kind of a salt corresponding with KIO_3 (unknown) in which the oxygen is replaced by chlorine. If atomicity is taken as a starting point in the study of chemical compounds, and if the elements are considered as having a constant atomicity (number of bonds)—that is, if K, Cl, and I be counted as univalent elements—then it is impossible to explain the formation of such a compound, because, according to this view, univalent elements are only able to form dual compounds with each other; for example, KCl , CH , KI , &c., whilst here they are grouped together in the molecule $KICl_4$.

⁴ It is possible to directly extract the compounds of potassium from the primary rocks which are, especially in some localities, so widely distributed over the earth's surface. From a chemical point of view this problem presents no difficulty; for instance, by fusing powdered orthoclase with lime and fluor spar (Ward's method) and then, extracting the alkali with water (in the fusion the silica gives an insoluble compound with lime), or by treating the orthoclase with hydrofluoric acid (in which case silicon fluoride is evolved as a gas) it is possible to transfer the alkali of the orthoclase to an aqueous solution, and to separate it in this manner from the other insoluble oxides. Thus after treating with hydrofluoric acid, many fluorides are obtained in solution, chiefly the fluorides of aluminium and potassium. If the solution be evaporated and sulphuric acid then added, hydrofluoric acid is evolved and the metals are obtained as sulphates. On adding ammonia to the solution of these salts, the aluminium is precipitated as hydroxide, and the salts of ammonia and potassium remain in solution. The ammonia salt is then decomposed by igniting, and the potassium sulphate is obtained alone. However, as yet there is no profit in, nor necessity for, having recourse to this treatment, as there still exist abundant sources for the extraction of potassium compounds by cheaper methods. Furthermore, the salts of potassium are now in the majority of chemical reactions replaced by salts of sodium, especially since the preparation of sodium carbonate has been facilitated by Leblanc's method. The replacement of potassium compounds by sodium compounds not only presents the advantage that the salts of sodium are in general cheaper than those of potassium, but also that a less quantity of a sodium salt is needed for a given reaction than of a potassium salt, because the combining weight of sodium (23) is less than that of potassium (39).

⁵ It has been shown by direct experiment on the cultivation of plants in artificial soils and in solutions that under conditions (physical, chemical, and physiological) otherwise identical plants are able to thrive and become fully developed in the entire absence of sodium salts, but that their development is impossible without potassium salts.

The primary rocks contain an almost equal proportion of potassium and sodium. But in sea water the compounds of the latter metal predominate. It may be asked, what became of the compounds of potassium in the disintegration of the primary rocks, if so small a quantity went to the sea water? They remained with the other products of the decomposition of the primary rocks. When granite or any other similar rock formation is disintegrated, there are formed, besides the soluble substances, also insoluble substances—sand and finely-divided clay, containing water, alumina, and silica. This clay is carried away by the water, and is then deposited in strata. It, and especially its admixture with vegetable remains, retain compounds of potassium in a greater quantity than those of sodium. This has been proved, with absolute certainty, to be the case, and is due to the *absorptive power of the soil*. If a dilute solution of a potassium compound be filtered through common mould used for growing plants, and containing clay and the remains of vegetable decomposition, it will be found to have retained a somewhat considerable percentage of the potassium compounds. If a salt of potassium be taken, then during the filtration an equivalent quantity of a salt of calcium—which is also found, as a rule, in soils—is set free. Such a process of filtration through finely-divided earthly substances proceeds in nature, and the compounds of potassium are everywhere retained by the friable earth in considerable quantity. This explains the presence of so small an amount of potassium salts in the water of rivers, lakes, streams, and oceans, where the lime and soda have accumulated. The compounds of potassium retained by the friable mass of the earth are absorbed as an aqueous solution by the roots of *plants*. Plants, as every one knows, when burnt leave an ash, and this ash, besides various other substances, without exception contains compounds of potassium. Many land plants contain a very small amount of sodium compounds,⁶ whilst potassium and its compounds occur in all kinds of vegetable ash. Among the generally cultivated plants, grass, potatoes, the turnip, and buckwheat are particularly rich in potassium compounds. The ash of plants, and especially of herbaceous plants, buckwheat straw, sunflower and potato leaves are used in practice for the extraction of potassium compounds. There is no doubt that potassium occurs in the plants themselves in the form of complex compounds, and often as salts of organic acids. In certain cases such salts of potassium are even extracted from the juice of plants. Thus, sorrel and *oxalis* for example, contain in their juices the acid oxalate of potassium, C_2HKO_4 , which is

⁶ If herbaceous plants contain much sodium salts, it is evident that these salts mainly proceed from the sodium compounds in the water absorbed by the plants.

employed for removing ink stains. Grape juice contains the so-called cream of tartar, which is the acid tartrate of potassium, $C_4H_5KO_6$.⁷ This salt also separates as a sediment from wine. When the plants, containing one or more of the salts of potassium, are burnt, then the carbonaceous matter is oxidised, and in consequence the potassium is obtained in the ash as carbonate, K_2CO_3 , which is generally known as *potashes*. Hence potashes occur ready prepared in the ash of plants, and therefore the ash of land plants is employed as a source for the extraction of potassium compounds. Potassium carbonate is extracted by lixiviating the ash with water.⁸ Potassium carbonate

⁷ As plants always contain mineral substances and cannot thrive in a sphere which does not contain them, especially which is free from the salts of the four basic oxides, K_2O , CaO , MgO , and Fe_2O_3 , and of the four acid oxides, CO_2 , N_2O_5 , P_2O_5 , and SO_5 , the question involuntarily arises as to what part these play in the development of plants. With the present store of chemical data only one answer is possible to this question, and it is still only a hypothesis. This answer was particularly clearly expressed by Professor Gustavson of the Petroffsky Agricultural Academy. Starting from the fact (Chap. XI. Note 55) that a small quantity of aluminium renders possible and facilitates the reaction of bromine on hydrocarbons at the ordinary temperature, it is easy to arrive at the conclusion, which is very probable and in accordance with many data respecting the reactions of organic compounds, that the addition of mineral substances to organic compounds lowers the temperature of reaction and in general facilitates chemical reactions in plants, and thus aids the conversion of the most simple nourishing substances into the complex component parts of the plant organism. The province of chemical reactions proceeding in organic substances in the presence of a small quantity of mineral substances has as yet been but little investigated, although there are already several disconnected data of this kind, and although a great deal is known concerning such reactions among inorganic compounds. The essence of the matter may be expressed thus—two substances, A and B, do not react on each other of their own accord, but the addition of a small quantity of a third particularly active substance, C, produces the reaction of A on B, because A combines with C, forms AC, and B reacts on this new compound, which has a different store of chemical energy, forming the compound AB or its products, and setting C free again.

It may here be remarked that all the mineral substances necessary for plants (those enumerated at the beginning of the note) are the highest saline compounds of their elements, that they enter into the plants as salts, that the lower forms of oxidation of the same elements (for instance, sulphites and phosphites) are harmful to plants (poisonous), and that strong solutions of the salts assimilated by plants (their osmotic pressure is great and contracts the cells, as De Vries showed, see p. 322) not only do not enter into the plants but kill them (poison them).

Besides which, it will be understood from the preceding paragraph that the salts of potassium may become exhausted from the soil by long cultivation, and that there may therefore be cases when the direct fertilisation by salts of potassium may be profitable. But manure and animal excrements, ashes, and, in general, nearly all refuse which may serve for fertilising the soil, contain a considerable quantity of potassium salts, and therefore, as regards the natural salts of potassium (Stassfurt), and especially potassium sulphate, if they often improve the crops, it is in all probability because they influence the properties of the soil. The agriculturist cannot therefore be advised to add potassium salts, without making special experiments showing the advantage of such a fertiliser on a given kind of soil and plant.

⁸ The animal body also contains potassium compounds, which is natural, since animals consume plants. For example, milk, and especially woman's milk, contains a somewhat

may also be obtained from the chloride by a method similar to that by which sodium carbonate is prepared from sodium chloride. There

considerable quantity of potassium compounds. However, cow's milk contains but little potassium salts. Sodium compounds generally predominate in animal bodies. The excrement of animals, and especially of herbivorous animals, on the contrary, often contains a large proportion of potassium salts. Thus sheep's dung is rich in them, and in washing sheep's wool salts of potassium pass into the water.

The ash of tree stems, as the already dormant portion of the plant (Chap. VIII. Note 1), contains little potash. For the extraction of potash, which was formerly (before the discovery of the Stassfurt salt) carried on extensively in the east of Russia, the ash of grasses, and the green portions of potatoes, buckwheat, &c., are taken and treated with water (lixivated), the solution is evaporated, and the residue ignited in order to destroy the organic matter present in the extract. The residue thus obtained is composed of raw potash. It is refined by a second dissolution in a small quantity of water, because the potash itself is very soluble in water, whilst the impurities are sparingly soluble. The solution thus obtained is again evaporated, and the residue ignited, and this potash is then called refined potash, pearlash. This method of treatment cannot give chemically pure potassium carbonate. A certain amount of impurities remain. To obtain chemically pure potassium carbonate, some other salt of potassium is generally taken and purified by crystallisation. Potassium carbonate crystallises with difficulty, and it cannot therefore be purified by this means, whilst other salts, such as the tartrate, acid carbonate, sulphate, or nitrate, &c., crystallise easily and may thus be directly purified. The tartrate is most frequently taken, all the more as it is prepared in large quantities for medicinal use under the name of cream of tartar. When ignited without the access of air, it leaves a mixture of charcoal and potassium carbonate. The charcoal is then obtained in a finely-divided condition (this mixture is called 'black flux,' and is sometimes used for reducing metals from their oxides, by the aid of heat). A certain quantity of nitre is added to burn the charcoal formed by heating the cream of tartar. Potassium carbonate thus prepared is further purified by converting it into the acid salt, by passing a current of carbonic anhydride through a strong solution. KHCO_3 is then formed, which is less soluble than the normal salt (as is the case with the corresponding sodium salts), and therefore crystals of the acid salt separate from the solution on cooling. When ignited, they part with their water and carbonic anhydride, and pure potassium carbonate remains behind. The physical properties of potassium carbonate distinguish it with sufficient distinctness from sodium carbonate; it is obtained from solutions as a powdery white mass, having an alkaline taste and reaction, and, as a rule, shows only traces of crystallisation. It also attracts the moisture of the air with great energy. The crystals do not contain water, but absorb it from the air, deliquescent into a saturated solution. It melts at a red heat (830°), and at a still higher temperature is even converted into vapour, as has been observed at glass works where it is employed. It is very soluble. At the ordinary temperature, water dissolves an equal weight of the salt. Crystals containing two equivalents of water separate from such a saturated solution when strongly cooled. There is no necessity to describe its reactions, because they are entirely analogous to those of sodium carbonate. When manufactured sodium carbonate was but little known, the consumption of potassium carbonate was very considerable, and even now washing soda is frequently replaced for household purposes by 'ley'—*i.e.* an aqueous solution obtained from ashes. It contains potassium carbonate, which acts like the sodium salt in washing tissues, linen, &c.

A mixture of potassium and sodium carbonate fuses with much greater ease than the separate salts, and a mixture of their solutions gives salts of a fine crystalline form—for instance (Marguerite's salt), $\text{K}_2\text{CO}_3 \cdot 6\text{H}_2\text{O} \cdot 2\text{Na}_2\text{CO}_3 \cdot 6\text{H}_2\text{O}$. Crystallisation also proceeds in other multiple proportions of K and Na (in the above case 1 : 2, but 1 : 1 and 1 : 3 are known), and always with 6 mol. H_2O . This is evidently a combination *by analogy*, as in alloys, solutions, &c.

is no difficulty in obtaining any salt of potassium—for example, the sulphate,⁹ bromide, and iodide¹⁰—by the action of the corresponding

⁹ *Potassium sulphate*, K_2SO_4 , crystallises from its solutions in an anhydrous condition, in which respect it differs from the corresponding sodium salt, just as potassium carbonate differs from sodium carbonate. In general, it must be observed that the majority of sodium salts combine more easily with water of crystallisation than the potassium salts. The solubility of *potassium sulphate* does not show the same peculiarities as sodium sulphate, because it does not combine with water of crystallisation; at the ordinary temperature 100 parts of water dissolve about 10 parts of the salt, at 0° 8·3 parts, and at 100° about 26 parts. The *acid sulphate*, $KHSO_4$, obtained easily by heating crystals of the normal salt with sulphuric acid, is frequently employed in chemical practice. On heating the mixture of acid and salt, fumes of sulphuric acid are at first given off; when they cease to be evolved, the acid salt is contained in the residue. At a higher temperature (of above 600°) the acid salt parts with all the acid contained in it, the normal salt being re-formed. The definite composition of this acid salt, and the ease with which it decomposes, render it exceedingly valuable for certain chemical transformations accomplished by means of sulphuric acid at a high temperature, because it is possible to take, in the form of this salt, a strictly definite quantity of sulphuric acid, and to act on a given substance at a high temperature, which it is often necessary to do, more especially in chemical analysis. In this case, the acid salt acts in exactly the same manner as sulphuric acid itself, but the action of the latter is inconvenient at temperatures above 400° , because it would all evaporate, while at that temperature the acid salt still remains in a fused state, and acts with the elements of sulphuric acid on the substance taken. Hence by its means the boiling-point of sulphuric acid is raised. Thus the acid potassium sulphate is employed, for example, where for conversion of certain oxides, such as the oxides of iron, aluminium, and chromium, into salts, a high temperature is required.

Weber, by heating potassium sulphate with an excess of sulphuric acid at 100° , observed the formation of a lower stratum, which was found to contain a definite compound containing eight equivalents of SO_5 per equivalent of K_2O . The salts of rubidium, caesium, and thallium give a similar result, but those of sodium and lithium do not.

¹⁰ The *bromide* and *iodide* of potassium are used, like the corresponding sodium compounds, in medicine and photography. Potassium iodide is easily obtained in a pure state by saturating a solution of hydriodic acid with caustic potash. In practice, however, this method is rarely had recourse to, other more simple processes being employed although they do not give so pure a product. They aim at the direct formation of hydriodic acid in the liquid in the presence of potassium hydroxide or carbonate. Thus iodine is thrown into a solution of pure potash, and hydrogen sulphide passed through the mixture, the iodine being thus converted into hydriodic acid. Or a solution is prepared from phosphorus, iodine, and water, containing hydriodic and phosphoric acid: lime is then added to this solution, and calcium iodide is obtained in solution, and calcium phosphate as a precipitate. The solution of calcium iodide gives, with potassium carbonate, insoluble calcium carbonate and a solution of potassium iodide. If iodine is added to a slightly-heated solution of caustic potash (free from carbonate—that is, freshly prepared), so long as the solution is not coloured from the presence of an excess of iodine, then there is formed (as in the action of chlorine on a solution of caustic potash) a mixture of potassium iodide and iodate. On evaporating the solution thus obtained and igniting the residue, the iodate is destroyed and converted into iodide, the oxygen being disengaged, and potassium iodide only is left behind. On dissolving the residue in water and then evaporating, cubical crystals of the anhydrous salt are obtained, which are soluble in water and alcohol, fuse and give an alkaline reaction, owing to the fact that when ignited a portion of the salt decomposes, forming potassium oxide. The neutral salt may be obtained by adding hydriodic acid to this alkaline salt until it gives an acid reaction. It is best to add some finely-divided charcoal to the mixture of iodate

acid on the carbonate, whilst the hydroxide, *caustic potash*, KHO , which is in many respects analogous to caustic soda, is easily obtained by means of lime in exactly the same manner as sodium hydroxide is prepared from sodium carbonate.¹¹ Therefore, in order to complete our knowledge of the alkali metals, we will only describe two salts of potassium which are of practical importance, and whose analogues have not been described in the preceding chapter.

Potassium cyanide, which presents in its chemical relations a certain analogy with the halogen salts of potassium, is not only formed according to the equation, $\text{KHO} + \text{HCN} = \text{H}_2\text{O} + \text{KCN}$, but also whenever a nitrogenous carbon compound—for instance, animal matter—is heated in the presence of metallic potassium, or of a compound of potassium, and even when a mixture of potash and carbon is heated in a stream of nitrogen. Potassium cyanide is obtained from yellow prussiate (p. 401), which has been already mentioned and whose preparation on a large scale will be described in speaking of iron. If the yellow prussiate be ground to a powder and dried, so that it loses its water of crystallisation, then it melts at a red heat, and decomposes into carbide of iron, nitrogen, and potassium cyanide, $\text{FeK}_4\text{C}_6\text{N}_6 = 4\text{KCN} + \text{FeC}_2 + \text{N}_2$. After the decomposition it is found that the yellow salt has been converted into a white mass of potassium cyanide. The carbide of iron formed collects at the bottom of the vessel. If

and iodide before igniting it, as it facilitates the evolution of the oxygen from the iodate. The iodate may also be converted into iodide by the action of certain reducing agents, such as zinc amalgam, which, when boiled with a solution containing an iodate, converts it into iodide. Potassium iodide may also be prepared by mixing a solution of ferrous iodide (it is best if the solution contains an excess of iodine) and potassium carbonate, in which case ferrous carbonate, FeCO_3 , is precipitated (with an excess of iodine the precipitate is granular, and contains a compound of the suboxide and oxide of iron), while potassium iodide remains in solution. Ferrous iodide, FeI_2 , is obtained by the direct action of iodine on iron in water. Potassium iodide considerably lowers the temperature (even by 24°), when it dissolves in water, 100 parts of the salt dissolve in 73.5 parts of water at 12.5° , in 70 parts at 18° , whilst the saturated solution which boils at 120° contains 100 parts of salt per 45 parts of water. Solutions of potassium iodide dissolve a considerable amount of iodine; strong solutions even dissolving as much or more iodine than they contain as potassium iodide (*see* Chap. XI. Note 64).

¹¹ Caustic potash is not only formed by the action of lime on dilute solutions of potassium carbonate (as sodium hydroxide is prepared from sodium carbonate), but also by igniting potassium nitrate with finely-divided copper (*see* Note 15), and also by mixing solutions of potassium sulphate (or even of alum, KAlS_2O_8) and barium hydroxide, BaH_2O_2 . It is sometimes purified by dissolving it in alcohol (the impurities, for example, potassium sulphate and carbonate, are not dissolved) and then evaporating the alcohol.

The specific gravity of potassium hydroxide is 2.04, but that of its solutions (*see* Chap. XII. Note 18) at $15^\circ \text{S} = 9992 + 90.4p + 0.28p^2$ (here p is +, and for sodium hydroxide it is -). Strong solutions, when cooled, yield a crystallo-hydrate, $\text{KHO} \cdot 4\text{H}_2\text{O}$, which dissolves in water, producing (like $2\text{NaHO} \cdot 7\text{H}_2\text{O}$) cold, whilst potassium hydroxide in solution develops a considerable amount of heat.

the mass thus obtained be treated with water, the potassium cyanide is partially decomposed by the water, but if it be treated with alcohol, then the cyanide is dissolved, and on cooling separates in a crystalline form.¹² A solution of potassium cyanide has a powerfully alkaline reaction, a smell like that of bitter almonds, peculiar to prussic acid, and acts as a most powerful poison. Although exceedingly stable in a fused state, potassium cyanide easily changes when in solution. Prussic acid is so very feebly energetic that even water decomposes potassium cyanide. A solution of the salt, even without access of air, easily turns brown and decomposes, and when heated evolves ammonia and forms potassium formate; this is easily comprehensible from the representation of the cyanogen compounds which was developed in Chap. IX., $\text{KCN} + 2\text{H}_2\text{O} = \text{CHKO}_2 + \text{NH}_3$. Furthermore, as carbonic anhydride acts on potassium cyanide with evolution of prussic acid, and as potassium cyanate, which is also unstable, is formed by the action of air, it will be easily seen that solutions of potassium cyanide are very unstable. Potassium cyanide, containing as it does carbon and potassium, is a substance which can act in a very vigorously reducing manner, especially when fused; it is therefore used as a powerful reducing agent at a red heat. A considerable quantity of potassium cyanide is used in the arts, more particularly for the preparation of metallic solutions which are decomposed by the action of a galvanic current; thus it is very frequently employed in electro-silvering and

¹² In this case it is evident that all the cyanogen which was in combination with the iron is decomposed into nitrogen, which is evolved as gas, and into carbon, which combines with the iron. In order to avoid this, potassium carbonate is added to the yellow prussiate while it is being fused. A mixture of 8 parts of anhydrous yellow prussiate and 3 parts of pure potassium carbonate is generally taken. On fusing, double decomposition takes place, resulting in the formation of ferrous carbonate and potassium cyanide. But by this method, as by the first, a pure salt is not obtained, (1) because a portion of the potassium cyanide is oxidised at the expense of the iron carbonate and forms potassium cyanate, $\text{FeCO}_3 + \text{KCN} = \text{CO}_2 + \text{Fe} + \text{KCNO}$; (2) a portion of the iron under the action of the water again passes into solution; and (3) the potassium cyanide very easily forms oxide, which acts on the sides of the vessel in which the mixture is heated (to avoid this iron vessels should be used), &c. By adding one part of charcoal powder to the mixture of 8 parts of anhydrous yellow prussiate and 3 parts of potassium carbonate a mass is obtained which is free from cyanate, because the carbon absorbs the oxygen, but then it is impossible to obtain a colourless potassium cyanide by simple fusion, although this may be easily done by dissolving it in alcohol. Naturally, pure potassium cyanide may be easily obtained if hydrocyanic acid be saturated with caustic potash, and especially if caustic potash be dissolved in alcohol and hydrocyanic acid gas be passed through this solution; crystals of potassium cyanide then separate directly from the solution. Potassium cyanide is now prepared in large quantities from yellow prussiate for gilding and silvering. When fused in large quantities the action of the oxygen of the air is limited, and the entire operation may be conducted with great care, and therefore, on a large scale very pure salt is sometimes obtained. When slowly cooled, the fused salt separates in cubical crystals like potassium chloride.

gilding. An alkaline solution is prepared,¹³ which is moderately stable owing to the fact that potassium cyanide in the form of certain double salts—that is, combined with other cyanides—is far more stable than when alone (yellow prussiate, which contains potassium cyanide in combination with ferrous cyanide, is an example of this). The property of potassium cyanide of giving double salts with other cyanides is very clearly shown by the fact that many metals dissolve in a solution of potassium cyanide, with the evolution of hydrogen. For example, iron, copper, and zinc act in this manner. In which case potassium hydroxide is formed ; for example—



Gold and silver are soluble in potassium cyanide in the presence of air, in which case the hydrogen, which might be evolved in the reaction, combines with the oxygen of the air, forming water. Platinum, mercury, and tin are not dissolved in a solution of potassium cyanide, even with the access of air.

Potassium nitrate, or common *nitre* or *saltpetre*, KNO_3 , is chiefly used as a component part of gunpowder, in which it cannot be replaced by the sodium salt, because the latter is deliquescent. It is necessary that the nitre in gunpowder should be perfectly pure, as even small traces of sodium, magnesium, and calcium salts, especially chlorides, render the nitre and gunpowder capable of attracting moisture. Nitre may easily be obtained pure, owing to its great disposition to form crystals both large and small, which aids its separation from other salts. The considerable differences between the solubility of nitre at different temperatures aids this crystallisation. A solution of nitre saturated at its boiling point (116°) contains 335 parts of nitre to 100 parts of water, whilst at the ordinary temperature—for instance, 20° —the solution is only able to retain 32 parts of the salt. Therefore, in the preparation and refining of nitre, its solution, saturated at the boiling point, is cooled, and nearly all the nitre is obtained in the form of crystals. If the solution be quietly and slowly cooled in large quantities then large crystals are formed, but if it be rapidly cooled and agitated then small crystals are obtained. In this manner, if not all at all events the majority of the impurities present in small quantities remain in the mother liquor. If an unsaturated solution of nitre be rapidly cooled, so as to prevent the formation of large crystals (in whose crevices the mother liquor, together with the impurities, would remain), the very minute crystals of nitre known as *saltpetre flour* are obtained.

¹³ The electro-deposition of metals generally proceeds more uniformly and gives a purer deposit from alkaline, than from acid, solutions.

Common nitre occurs in nature, but only in small quantities in admixture with other nitrates, and especially with sodium, magnesium, and calcium nitrates. Such a mixture of salts of nitric acid is formed in nature in fertile earth, and in those localities where, as in *the soil*, nitrogenous organic remains are decomposed in the presence of alkalis or alkaline bases with free access of air. This method of the formation of nitrates requires moisture, besides the free access of air, and takes place principally during warm weather. Besides which Schloessing and Müntz, by employing similar methods to Pasteur, showed that the formation of nitre in the decomposition of nitrogenous substances is accomplished by the aid of peculiar micro-organisms (ferments) without which the simultaneous action of the other necessary conditions (alkalis, moisture, a somewhat elevated temperature, air, and nitrogenous substances) cannot give nitre. In warm countries, and in temperate climates during the summer months, fertile soils produce a small quantity of nitre. In this respect India is especially known as affording a considerable supply of nitre extracted from the soil. The soil, which contains nitre, after the rainy season sometimes becomes covered during the summer with crystals of nitre, formed by the evaporation of the water in which it was previously dissolved. This soil is collected, subjected to repeated lixiviations, and treated for nitre, as will be presently described. In temperate climates nitrates are obtained from the lime rubbish of demolished buildings which have stood for many years, and especially from those portions which have touched the ground. The conditions are there very propitious to the formation of nitre, because the lime used as a cement in buildings contains the base necessary for the formation of nitrates, while the excrement, urine, and other animal refuse are sources of nitrogen. By the methodical lixiviation of this kind of rubbish a like solution of nitrogenous salts is obtained as by the lixiviation of fertile soil. A similar solution is also obtained by the lixiviation of the so-called *nitre plantations*. They are composed of manure interlaid with brush-wood, and strewn over with ashes and other alkaline and lime rubbish. These nitre plantations are set up in those localities where the manure is not required for the fertilisation of the soil, as, for example, in the south-eastern 'black earth' governments of Russia. The same process of oxidation of nitrogenous matter free to the access of air and moisture during the warm season in the presence of alkalis takes place in nitre plantations as is accomplished in the fertile soil and in the walls of buildings. From all these sources there is obtained a solution containing different salts of nitric acid mixed with soluble organic matter. The simplest method of treating this impure solution of nitre

is to add a solution of potassium carbonate, or to simply treat it with ashes containing this substance. The potassium carbonate enters into double decomposition with the calcium and magnesium salts, forming insoluble carbonates of these bases and leaving the nitre in solution. Thus, for instance, $K_2CO_3 + Ca(NO_3)_2 = 2KNO_3 + CaCO_3$. Both calcium and magnesium carbonates are insoluble, and therefore after treatment with potassium carbonate the solution no longer contains salts of these metals but only the salts of sodium and potassium together with organic matter. The latter partially separates on heating in an insoluble form, and is entirely destroyed by heating the nitre to a low red heat. The nitre thus obtained is easily purified by repeated crystallisation. The greater part of the nitre used for making gunpowder is now obtained from the sodium salt *Chili saltpetre* or *cubic nitre*, which occurs, as has been already mentioned, in nature. The conversion of this salt into common nitre is also carried on by means of a double decomposition. This is done either by adding potassium carbonate (when, on mixing the strong and hot solutions, sodium carbonate is directly obtained as a precipitate), or as is now most frequent, potassium chloride. When a mixture of strong solutions of potassium chloride and sodium nitrate is evaporated, sodium chloride first separates, because this salt, which is formed by the double decomposition $KCl + NaNO_3 = KNO_3 + NaCl$, is almost equally soluble in hot and cold water; on cooling, therefore, a large amount of potassium nitrate separates from the saturated solution, while the sodium chloride remains dissolved. The nitre is ultimately purified by recrystallisation and by washing with a saturated solution of nitre, which cannot dissolve a further quantity of nitre but only the impurities.

Nitre is a colourless salt having a peculiar cool taste. It easily crystallises in long striated six-sided rhombic prisms terminating in similar pyramids. Its crystals (sp. gr. 1.93) do not contain water, but their cavities generally contain a certain quantity of the solution from which they have crystallised. For this reason in refining nitre, large crystals are not obtained but *saltpetre flour* is prepared. At a low red heat (339°) nitre melts to a colourless liquid.¹⁴ Potassium nitrate at the ordinary temperature and in a solid form is inactive and stable,

¹⁴ Before fusing, the crystals of potassium nitrate change their form, and take the same form as sodium nitrate—that is, they change into rhombohedra. Nitre crystallises from hot solutions, and in general under the influence of a rise of temperature, in a different form from that given at the ordinary or lower temperatures. Fused nitre solidifies into a radiated crystalline mass; but it does not exhibit this structure if metallic chlorides be present, so that this method may be taken advantage of to determine the degree of purity of nitre. With a small trace of sodium chloride, the mass of nitre solidified after fusion does not present any signs of crystallisation in the middle.

Carnelley and Thomson (1888) determined the fusing point of mixtures of potassium

but at a high temperature it acts as a powerful oxidising agent, because it gives up a considerable amount of oxygen to substances mixed with it.¹⁵ When thrown on incandescent charcoal it brings about its rapid combustion, and a mechanical mixture of powdered charcoal and nitre ignites when brought into contact with a red-hot substance, and continues to burn by itself. In this action, nitrogen is evolved, and the oxygen goes to oxidise the charcoal, in consequence of which potassium carbonate and carbonic anhydride are formed: $4\text{KNO}_3 + 5\text{C} = 2\text{K}_2\text{CO}_3 + 3\text{CO}_2 + 2\text{N}_2$. This phenomenon depends on the fact that oxygen in combining with carbon evolves more heat than it does in combining with nitrogen. Hence when once the combustion has been started at the expense of the nitre, it is able to go on without requiring the aid of external heat. A like oxidation or combustion at the expense of the contained oxygen proceeds when nitre is heated with different combustible substances. If a mixture of sulphur and nitre be thrown upon a red-hot surface, then the sulphur burns, forming potassium sulphate and sulphurous anhydride. In this case, also, the nitrogen of the nitre is evolved as gas: $2\text{KNO}_3 + 2\text{S} = \text{K}_2\text{SO}_4 + \text{N}_2 + \text{SO}_2$. A similar phenomenon takes place when nitre is heated with

and sodium nitrates. The first salt fuses at 339° and the second at 316° , and if p be the percentage amount of potassium nitrate, then the result obtained—

$p = 10$	20	30	40	50	60	70	80	90
298°	283°	268°	242°	231°	231°	242°	284°	306°

which confirms Shaffgotsch's observation (1857) that the lowest fusing point (about 231°) is given by mixing molecular quantities ($p = 54.3$) of the salts—that is, in the formation of the alloy, $\text{KNO}_3, \text{NaNO}_3$.

A somewhat similar result was discovered by the same observers for the solubility of mixtures of these salts at 20° in 100 parts of water. Thus, if p be the weight of potassium nitrate mixed with $100 - p$ parts by weight of sodium nitrate taken for solution, and c be the quantity of the mixed salts which dissolves in 100, the solubility of sodium nitrate being 85, and of potassium nitrate 34, parts in 100 parts of water, then—

$p = 10$	20	30	40	50	60	70	80	90
$c = 110$	136	136	138	106	81	73	54	41

The maximum solubility proved not to answer to the most fusible mixture, but to one much richer in sodium nitrate.

Both these phenomena show that in homogeneous liquid mixtures the chemical forces that act between substances are the same as those that determine the molecular weights of substances, even when the mixture consists of such analogous substances as potassium and sodium nitrates, between which there is no direct chemical interchange. It is instructive to note also that the maximum solubility does not correspond with the minimum fusing point, which naturally depends on the fact that a third substance, namely water, participates in solution, although an attraction between the salts, like that which exists between sodium and potassium carbonates (Note 8), also partially acts.

¹⁵ Fused nitre, with a further rise of temperature, disengages oxygen and then nitrogen. The nitrite KNO_2 is first formed and then potassium oxide. The admixture of certain metals—for example, of finely-divided copper—aids the last decomposition. The oxygen in this case naturally passes over to the metal.

many metals. The oxidation of those metals which are able to form acid oxides with an excess of oxygen is especially remarkable. In this case they remain in combination with potassium oxide as potassium salts. Manganese, antimony, arsenic, iron, chromium, &c., are instances of this kind. These elements, like carbon and sulphur, displace free nitrogen. The lower oxides of these metals when fused with nitre pass into the higher oxides. Organic substances are also oxidised when heated with nitre—that is, they burn at the expense of the nitre. It will be readily understood from this that nitre is frequently used in chemical practice and the arts as an oxidising agent at high temperatures. Its application in *gunpowder* is based on this ; gunpowder consists of a mechanical mixture of finely-ground sulphur, nitre, and charcoal. The relative proportion of these substances varies according to the destination of the powder and to the kind of charcoal employed (a friable, incompletely-burnt charcoal, containing therefore hydrogen and oxygen, is employed). Gases are formed in its combustion, chiefly nitrogen and carbonic anhydride, which create a considerable pressure if their escape be in any way impeded. This action of gunpowder may be expressed by the equation : $2\text{KNO}_3 + 3\text{C} + \text{S} = \text{K}_2\text{S} + 3\text{CO}_2 + \text{N}_2$.

It is found by this equation that gunpowder should contain thirty-six parts of charcoal (13·3 p.c.), and thirty-two parts (11·9 p.c.) of sulphur, to 202 parts (74·8 p.c.) of nitre, which is very near to its actual composition.¹⁶

¹⁶ In China, where the manufacture of gunpowder has long been practised, they use 75·7 of nitre, 14·4 of charcoal, and 9·9 of sulphur. Ordinary powder for sporting purposes contains 80 parts of nitre, 12 of charcoal, and 8 of sulphur, whilst the gunpowder used in cannons contains 75 of nitre, 15 of charcoal, and 10 of sulphur. Gunpowder explodes when heated to 300°, when struck, or by contact with a spark. A compact or finely-divided mass of gunpowder burns slowly and has but little dynamic action, because it burns by degrees (consecutively). To act properly the gunpowder must have a known rate of combustion, so that the pressure should increase and not diminish during the passage of the projectile along the barrel of the fire-arm. This is done by making the powder granular or in the shape of 6-sided prisms with holes through them (prismatic powder).

The products of combustion are of two kinds: (1) gases which produce the pressure and form the reason of the dynamical action of gunpowder, and (2) a solid residue, usually of a black colour owing to its containing unburnt particles of charcoal. Besides charcoal, the residue generally contains potassium sulphide, K_2S , and a whole series of other salts—for instance, carbonate and sulphate. This already shows that the combustion of gunpowder is not so simple as it appears to be from the above formula, and hence the weight of the residue is also greater than indicated by that formula. According to the formula, 270 parts of gunpowder give 110 parts of residue—that is, 100 parts of powder gives 37·4 parts of residue, K_2S , whilst in reality the weight of the residue varies from 40 p.c. to 70 p.c. (generally 52 p.c.). This difference depends on the fact that so much oxygen (of the nitre) remains in the residue, and it is evident that if the residue varies the composition of the gases evolved by the powder will vary also, and therefore

Potassium was obtained like sodium ; first by the action of a galvanic current, then by reduction of the hydroxide by means of metallic iron, and lastly, by the action of charcoal on the carbonate at a high temperature. The preparation of *metallic potassium* differs, however, from that of sodium in that it *easily* combines with carbonic oxide, forming an explosive and inflammable mass.¹⁷

However, in its essential points the method of its extraction is not different from that of sodium, because potassium is quite as volatile as sodium, if not more so. At the ordinary temperature, potassium is even softer than sodium, its freshly-cut surfaces present a whiter colour than sodium, but, like the latter, and with even greater ease, it oxidises in moist air. It is brittle at low temperatures, but is quite soft at 25°, and melts at 58°. At a low red heat (720°) it distils without change, forming a green vapour, whose density,¹⁸ according to

the entire process will be different in different cases. The difference in the composition of the gases and residue depends, as the researches of Gay-Lussac, Shishkoff and Bunsen, Noble and Abel, Federoff, &c., show, on the conditions under which the combustion of the powder proceeds. When gunpowder burns in an open space, the gaseous products which are formed do not remain in contact with the residue, and then a considerable portion of the charcoal entering into the composition of the powder remains unburnt because the charcoal burns after the sulphur at the expense of the oxygen of the nitre. In this extreme case the commencement of the combustion of the gunpowder may be expressed by the equation, $2\text{KNO}_3 + 3\text{C} + \text{S} = 2\text{C} + \text{K}_2\text{SO}_4 + \text{CO}_2 + \text{N}_2$. The residue in a blank cartridge often consists of a mixture of C, K_2SO_4 , K_2CO_3 , and $\text{K}_2\text{S}_2\text{O}_5$. If the combustion of the gunpowder be impeded—if it take place in a cartridge in the barrel of a gun—the quantity of potassium sulphate will first be diminished, then the amount of sulphite, whilst the amount of carbonic anhydride in the gases and the amount of potassium sulphide in the residue will increase. The quantity of charcoal entering into the action will then be also increased, and hence the amount in the residue will decrease. Under these circumstances the weight of the residue will be less—for example, $4\text{K}_2\text{CO}_3 + 4\text{S} = \text{K}_2\text{SO}_4 + 3\text{K}_2\text{S} + 4\text{CO}_2$. Besides which, carbonic oxide has been found in the gases, and potassium bisulphide, K_2S_2 , in the residue of gunpowder. The amount of potassium sulphide, K_2S , increases with the completeness of the combustion, and is formed in the residue at the expense of the potassium sulphite. In recent times the knowledge of the action of gunpowder and other explosives has made much progress, and has developed into a vast province of artillery science.

¹⁷ The substances obtained in this case are mentioned in Chap. IX. Note 31.

¹⁸ A. Scott (1887) determined the vapour densities of many of the compounds of the alkali elements in a platinum vessel heated in a furnace and previously filled with nitrogen. But these, the first data concerning a subject of great importance, have not yet been sufficiently fully described, nor have they received as much attention as could be desired. Taking the density of hydrogen as unity, Scott found the vapour densities of the following substances to be—

Na	12·75 (12·5).	KI	92 (84).
K	19 (19·5).	RbCl	70 (60).
CsCl	89·5 (84·2).	CsI	133 (130).
FeCl ₅	68	AgCl	80 (71·7).

In brackets are given the densities corresponding with the formulæ, according to Avogadro-Gerhardt's law. This figure is not given for FeCl₅, because in all probability

A. Scott, is equal to 19 (if that of hydrogen=1). This shows that the molecule of potassium (like that of sodium, mercury, and zinc) contains but one atom. This is also the case with other metals, judging by recent researches.¹⁹ The specific gravity of potassium at 15° is 0.87, and is therefore less than that of sodium, as is also the case with all its compounds.²⁰ Potassium decomposes water with great ease at the ordinary temperature, evolving 45000 heat units per atomic weight. The heat evolved is sufficient to inflame the hydrogen, the flame being coloured violet from the presence of particles of potassium.²¹

With regard to the relation of potassium to hydrogen and oxygen, it is closely analogous to sodium in this respect. Thus, with hydrogen it forms potassium hydride, K_2H (between 200° and 411°), and with oxygen it gives a suboxide K_4O , oxide K_2O , and peroxide, only more oxygen enters into the composition of the latter than in sodium per-

under these conditions (the temperature at which it was determined) a portion of the $FeCl_3$ was decomposed. If it was not decomposed, then a density 81 would correspond with the formula $FeCl_3$, and if the decomposition were $Fe_2Cl_6 = 2FeCl_2 + Cl_2$, then the density should be 54. With regard to the silver chloride, there is reason to think that the platinum decomposed this salt.

The majority of Scott's results so closely correspond with the formulæ that a better concord cannot be expected in such determinations.

¹⁹ The molecules of non-metals are more complex—for instance, H_2 , O_3 , Cl_2 , &c. But arsenic, whose superficial appearance recalls that of metals, but whose chemical properties approach more nearly to the non-metals, has a complex molecule containing As_4 . With respect to the vapour of iodine, see Chap. VII. p. 313.

²⁰ As the atomic weight of potassium is greater than that of sodium, therefore the volumes of the molecules, or the quotients of the molecular weight by the specific gravity, for potassium compounds are greater than those of sodium compounds, because both the denominator and numerator of the fraction augment. We cite for comparison the volumes of the corresponding compounds—

Na 24	NaHO 18	NaCl 28	NaNO ₃ 37	Na ₂ SO ₄ 54
K 45	KHO 27	*KCl 39	KNO ₃ 48	K ₂ SO ₄ 66

²¹ The same precautions must be taken in decomposing water by potassium as have to be observed with sodium (Chap. II. Note 8).

It must be observed that potassium decomposes carbonic anhydride and carbonic oxide when heated, the carbon being liberated and the oxygen taken up by the metal, whilst on the other hand charcoal takes up oxygen from potassium, as is seen from the preparation of potassium by heating potash with charcoal, hence the reaction $K_2O + C = K_2 + CO$ is reversible and the relation is the same in this case as between hydrogen and zinc. Nothing of the kind could be expected from a comparison of the quantities of heat evolved in the formation of these compounds, for charcoal in combining with oxygen to form carbonic oxide evolves (for its molecular weight) only about 30000 heat units (Chap. IX. Note 25), whilst potassium in forming the oxide K_2O gives about 100000 units, and iron in forming ferrous oxide, FeO , evolves about 70000 units. It is evident that the decomposition of potassium oxide by charcoal is accompanied by the absorption of a large amount of heat, and the reverse reaction—which, however, proceeds with greater difficulty—with the development of heat, which again shows the impossibility of judging the direction in which a reaction will proceed from thermal data.

oxide ; potassium peroxide contains KO_2 , but it is probable that in the combustion of potassium an oxide KO is also formed. Potassium, like sodium, is soluble in mercury.²² In a word, the relation between sodium and potassium is as close as that between chlorine and bromine, or, better still, between fluorine and chlorine, as the atomic weight of sodium, 23, is as much greater than that of fluorine, 19, as that of potassium, 39, is greater than that of chlorine, 35.5.

The resemblance between *potassium* and *sodium* is so great that *their compounds* can only be easily *distinguished* in the form of certain of their salts. For instance, the acid potassium tartrate, $\text{C}_4\text{H}_5\text{KO}_6$ (cream of tartar), is distinguished by its sparing solubility in water and in alcohol, and in a solution of tartaric acid, whilst the corresponding sodium salt is easily dissolved. Therefore, if a solution of tartaric acid be added in considerable excess to the solutions of the majority of potassium salts, then a precipitate of the sparingly-soluble acid salt is formed, which does not occur with salts of sodium. The chlorides KCl and NaCl in solutions easily give double salts K_2PtCl_6 and Na_2PtCl_6 , with platinic chloride, PtCl_4 , and the solubility of these salts is very different, especially in a mixture of alcohol and ether. The sodium salt is easily soluble, whilst the potassium salt is insoluble or almost so, and therefore the reaction with platinic chloride is that most often used for the separation of potassium from sodium, as is more fully described in works on analytical chemistry.

It is possible to discover the least traces of these metals in admixture together, by means of their property of imparting different colours to a flame. The presence of a salt of sodium in a flame is recognised by a brilliant yellow coloration, and a pure potassium salt colours a colourless flame violet. However, in the presence of a sodium salt the pale violet coloration given by a potassium salt is quite undistinguishable, and it is at first sight impossible in this case to discover the potassium salt in the presence of that of sodium. But by decomposing the light given by a flame coloured by these metals, or a mixture of them, by means of a prism, they are both easily distinguishable, because

²² The definite crystalline amalgam of potassium contains twice as much mercury, KHg_2 (as the potassium peroxide contains twice as much oxygen, Chap. XII. Note 39).

Potassium forms *alloys with sodium* in all proportions. The alloys containing 1 and 3 equivalents of potassium to one equivalent of sodium are *liquids*, like mercury at the ordinary temperature. Joannis, by determining the amount of heat developed by these alloys in decomposing water, found the evolution for Na_2K , NaK , NaK_2 , and NaK_3 to be 44.5, 44.1, 43.8 and 44.4 thousand heat units respectively (for Na 42.6 and for K 45.4). The formation of the alloy NaK_2 is therefore accompanied by the development of heat, whilst the other alloys may be regarded as solutions of potassium or sodium in this alloy. In any case a fall of the temperature of fusion is evident in this instance as in the alloys of nitre (Note 14).

the yellow light emitted by the sodium salt depends on a group of light rays having a definite index of refraction which corresponds with the yellow portion of the solar spectrum, having the index of refraction of the Fraunhofer line (strictly speaking, group of lines) D, whilst the salts of potassium give a light in which these rays are entirely wanting, but which contain rays of a red and violet colour. Therefore, if a potassium salt occur in a flame, then, on decomposing the light (from




Fig. 72A. — Spectroscope. The prism and table are covered with an opaque cover. The spectrum obtained from the flame coloured by a substance introduced on the wire is viewed through B. A light is placed before the scale D in order to illuminate the image of the scale reflected through B by the side of the prism.

a flame coloured by the salt) after passing through a narrow slit by means of a prism, there will be obtained red and violet bands of light situated at a considerable distance from each other; whilst if a sodium salt be present a yellow line will also appear. If both metals simultaneously occur in a flame and emit light, then the spectrum lines corresponding to the potassium and the sodium will simultaneously appear.

For convenience in carrying on this form of testing, *spectroscopes* (fig. 72A) are constructed,²³ consisting of a refracting prism

and three tubes directed on the plane of the refracting angle of the prism. One of the tubes, C, has a vertical slit at the end, giving access to the light to be tested, which then passes into the tube (collimator),

²³ For accurate measurements and comparative researches more complicated spectroscopes are required which give a greater dispersion, and which are furnished for this purpose with several prisms—for example, in Browning's spectroscope the light passes through six prisms, and then, having undergone an entire internal reflection, passes through the upper portion of the same six prisms, and again by an entire internal reflection passes into the ocular tube. With such a powerful dispersion the relative position of the spectral lines may be determined with accuracy. For the absolute and exact determination of the wave lengths it is particularly important that the spectroscope should be furnished with diffraction gratings. The construction of spectroscopes destined for special purposes (for example, for investigating the light of stars, or for determining the absorption spectra in microscopic preparations, &c.) is exceedingly varied. Details of the subject must be looked for in works on physics and on spectrum analysis. Among the latter the best known for their completeness and merit are those of Roscoe, Kayser, Vogel, and Lecoq de Boisbaudran.

which gives the rays a parallel direction. The rays of light having passed through the slit, and having become parallel, are refracted and dispersed in the prism, and the spectrum formed is observed through the orifice of the other telescope B. The third tube D contains a horizontal transparent scale (at the exterior end) which is divided into equal divisions. The light from a source such as a gas burner or candle placed before this tube, passes through the scale, and its image is thus reflected on that face of the prism which stands before the telescope B, so that the image of the scale is seen through this telescope simultaneously with the spectrum given by the rays passing through the slit of the tube C. In this manner the image of the scale and the spectrum given by the source of light under investigation are seen simultaneously. If the sun's rays be directed through the slit of the tube C, then the observer looking through the orifice of B will see the solar spectrum, and (if the aperture of the slit be narrow and the apparatus truly adjusted) the dark Fraunhofer lines in it.²⁴ Small-sized spectroscopes are usually so adjusted that (looking through B) the violet portion of the spectrum is seen to the right and the red portion to the left, and the Fraunhofer line D (in the bright yellow portion of the spectrum) is situated on the 50th division of the scale.²⁵ If the light emitted by an incandescent solid—for example, the Drummond light—be passed through the spectroscope, then all the colours of the solar spectrum are seen, but not the Fraunhofer lines. Let us now consider what will happen if the light from a flame coloured by various salts be passed through the spectroscope. This is done by placing a Bunsen gas burner (or the pale flame of hydrogen gas issuing from a platinum orifice) giving so pale a flame that its spectrum will be invisible before the slit. If any compound of sodium be placed in the flame of

²⁴ The arrangement of all the parts of the apparatus so as to give the clearest possible vision and accuracy of observation must evidently precede every kind of spectroscopic determination. Details concerning the practical use of the spectroscope must be also looked for in special works on the subject. In this treatise the reader is supposed to have a certain knowledge of the physical data respecting the refraction of light, and its dispersion and diffraction, and the theory of light, which allows of the determination of the length of the waves of light in absolute measures on the basis of observations with diffraction gratings, the distance between whose divisions may be easily measured in fractions of a millimetre: by such means it is possible to determine the wave lengths of definite rays of light.

²⁵ In order to give an idea of the several sizes of the scale, we may observe that the common spectrum extends from the zero of the scale (where the red portion is situated) to the 170th division (where the end of the visible violet portion of the spectrum is situated), and that the Fraunhofer line A (the extreme prominent line in the red) corresponds with the 17th division of the scale; the Fraunhofer line F (at the beginning of the blue, near the green colour) is situated on the 90th division, and the line G, which is clearly seen in the beginning of the violet portion of the spectrum, corresponds with the 127th division of the scale.

the gas burner (for which purpose a platinum wire on whose end sodium chloride is fused is fixed to the stand), then the flame is dyed a yellow colour, and on looking through the spectroscope the observer will see a bright *yellow* line falling upon the 50th division of the scale, which is seen together with the spectrum in the telescope. No yellow lines of other refractive index, nor any rays of any other colour, will be seen, and, therefore, the spectrum corresponding with sodium compounds consists of yellow rays of that index of refraction which belong to the Fraunhofer (black) line D of the solar spectrum. If a potassium salt be introduced into the flame instead of a sodium salt, then two bands will be seen which are much feebler than the bright sodium band—namely, one red line near the Fraunhofer line A and another violet line. Besides which, a pale, almost continuous, spectrum will be observed in the central portions of the scale. If a mixture of sodium and potassium salts be now introduced into the flame, three lines will be simultaneously seen—namely, the red and pale violet lines of potassium and the yellow line of sodium. In this manner it is possible, by the aid of the spectroscope, to determine the relation between the spectra of metals and known portions of the solar spectrum. The continuity of the latter is interrupted by dark lines (that is, by an absence of light of a definite index of refraction), termed the Fraunhofer lines of the solar spectrum. It has been shown by careful observations (by Fraunhofer, Brewster, Foucault, Ångström, Kirchhoff, Cornu, Lockyer, Dewar, and others), that there exists an exact *agreement between the spectra* of certain *metals* and certain of the *Fraunhofer* lines. Thus the bright yellow sodium line exactly corresponds with the dark Fraunhofer line D of the solar spectrum. A similar agreement is observed in the case of many other metals. This is not an approximate or chance correlation. In fact, if a spectroscope having a large number of refracting prisms and a high magnifying power be used, then it is seen that the dark line D of the solar spectrum consists of an entire system of closely adjacent but definitely situated fine and wide (sharp, distinct) dark lines,²⁶ and an exactly similar group of bright lines is obtained when the yellow sodium line is examined through the same apparatus, so that each bright sodium line exactly corresponds with a dark line in the solar spectrum. In the common spectroscopes which are usually employed in chemical research, one yellow band, which does not split

²⁶ The two most distinct lines of D, or of sodium, have wave lengths of 589.5 and 588.0 millionths of a millimeter, besides which fainter and fainter lines are seen whose wave lengths in millionth parts of a millimeter are 588.7 and 588.1, 616.0 and 615.4, 515.5 and 515.2, 498.3 and 498.2, &c., according to Liveing and Dewar. Many strive to find a simple relation, subject to a law, in the wave lengths, both of these pairs of lines and those of other elements.

up into thinner lines, is seen instead of the system of sodium lines, owing to the small dispersive power of the prism and the considerable aperture of the slit of the object tube.

This conformity of the bright lines formed by sodium with the dark lines of the solar spectrum cannot be accidental. This conclusion is further confirmed by the fact that the bright lines of other metals correspond with dark lines of the solar spectrum. Thus, for example, a series of sparks passing between the iron electrodes of a Ruhmkorff coil gives 450 very distinct lines characterising this metal. All these 450 bright lines, or the whole spectrum corresponding with iron, is repeated, as Kirchhoff showed, in the solar spectrum as dark Fraunhofer lines which occur in exactly the same situations as the bright lines occur in the iron spectrum, just as the sodium lines correspond with the band D in the solar spectrum. Many observers have in this manner simultaneously studied the solar spectrum and the spectra of different metals, and discovered in the former lines which correspond not only with sodium and iron, but also with many other metals.²⁷ The spectra of such elements as hydrogen, oxygen, nitrogen, and other gases may be observed in the so-called Geissler's tubes—that is, in glass tubes filled with rarefied gases, through which the discharge of a Ruhmkorff's coil is passed. Thus hydrogen gives a spectrum composed

²⁷ The most accurate investigations made in this respect are carried on with spectra obtained by diffraction, because in this case the position of the dark and bright lines does not depend on the index of refraction of the material of the prism, nor on the dispersive power of the apparatus. The best—that is, the most general and accurate—method of expressing the results of such determinations consists in determining the lengths of the waves corresponding to the rays of a definite index of refraction. We will express this *wave length* in *millionth parts of a millimetre* (the ten millionth parts are already doubtful, and fall within the limits of error). In order to illustrate the relation between the wave lengths and the positions of the spectrum, we will cite the wave lengths corresponding with the chief Fraunhofer lines and colours of the spectrum.

Fraunhofer line	A	B	C	D	E	b	F	G	H
Wave length .	761.0	687.5	656.6	589.5-588.9	527.3	518.7	486.5	431.0	397.2
Colour . . .	red			orange	yellow	green	blue		violet

In the following table are given the *wave lengths* of the light rays (the longest and most distinct, *see* later) for certain elements, those in black type being the most clearly defined and distinct lines, which are easily obtained either in the flame of a Bunsen's burner, or in Geissler's tubes, or in general, by an electric discharge. These lines refer to the elements (the lines of compounds are different, as will be afterwards explained, but many compounds are decomposed by the flame or by an electric discharge), and furthermore to the elements in an incandescent and rarefied gaseous state, for the spectra sometimes vary considerably with a variation of temperature and pressure.

It may be said that the *red* colour corresponds with lines having a wave length of from 780 (with a greater wave length the lines are hardly visible, and are ultra red) to 650, the *orange* from 650 to 590, the *yellow* from 590 to 520, the *green* from 520 to 490, the

sponding with one of the lines between G and H. Of these rays the red is the brightest, and therefore the general colour of luminous hydrogen (with an electric discharge through a Geissler tube) is reddish.

The correlation of the Fraunhofer lines with the spectra of metals depends on the phenomenon of the so-called *reversed spectrum*. This phenomenon consists in that instead of the bright spectrum corresponding with a metal, under certain circumstances a similar dark spectrum in the form of Fraunhofer lines may be obtained, as will be directly explained. In order to clearly understand the phenomenon of reversed spectra, it must be known that in the passage of light through certain transparent substances these substances retain rays of a certain refrangibility. The colour of solutions is a proof of this. Light which has passed through a yellow solution of a uranium salt contains no violet rays, and after having passed through a red solution of a permanganate, does not contain many rays in the yellow, blue, and green portions of the spectrum. Solutions of copper salts absorb nearly all red rays. Sometimes colourless solutions also absorb rays of certain definite refractive indexes, and give *absorption spectra*. Thus solutions of salts of didymium absorb rays of a certain refrangibility, and therefore an impression of black lines is received,²⁸ as shown in fig.

spectra (see later). Consequently, these lines are the most characteristic. Only the longest and most brilliant are given in our table, which is composed on the basis of a collection of the data at our disposal for *bright spectra of the incandescent and rarefied vapours of the elements*. As the spectra change with great variations of temperature and vapour density (the faint lines become brilliant whilst the bright lines sometimes disappear), which is particularly clear from Ciamician's researches on the halogens, therefore, until the method of observation and the theory of the subject are enlarged, particular theoretical importance should not be given to the wave lengths showing the maximum brilliancy, and which only possess any significance in a practical respect for the common methods of spectroscopic observations.

²⁸ The ocular impressions of light (it is essentially the same with all other impressions received by the senses) are all relative; in those portions of a spectrum, received through an absorptive medium, where there appears to be an absence of light, it may be only rendered fainter, and for absorption spectra this is directly proved to be the case both by experiment (by employing solutions of different strengths or strata of different thicknesses), and by direct measurement by the aid of the spectroscope—for instance, by Vierordt's apparatus, which is described in works on physics. The relative distinctness of the dark lines in an absorption spectrum, and of the bright coloured lines in luminous spectra of vapours and gases, which are self-evident in making observations, offer great difficulty with regard to precise measurement, just as is the case, for instance, with the relative brilliancy of the stars.

The method of observing absorption spectra consists in taking a continuous spectrum (one which does not give either dark lines or particularly bright luminous bands in the spectrum) of white light—for instance, the light of a candle, lamp, or other source. The collimator (that is, the tube with the slit) is directed towards this light, and then all the colours of the spectrum are visible in the ocular tube. A transparent absorptive medium—for instance, a solution or tube containing a gas—is then placed between the source of light and the apparatus (or anywhere inside the apparatus itself in the path of the rays). In this case either the entire spectrum is uniformly fainter, or absorption

73. Many vapours (iodine) and gases (nitric peroxide) give similar spectra. Light which has passed through a deep layer of aqueous vapour, oxygen, or nitrogen also gives its absorption spectrum. For this reason the peculiar (winter) dark lines discovered by Brewster are




FIG. 73.—Absorption spectrum (Lecoq de Boisbaudran) of salts of didymium in concentrated and dilute solutions.

observed in sunlight, especially in the evening and morning, when the sun's rays pass through the atmosphere (containing these substances) by a longer path than at mid-day. It is evident that the Fraunhofer

bands appear on the bright field of the continuous spectrum in definite positions along it. These bands have different lengths and positions, and distinctness and intensity of absorption, according to the properties of the absorptive medium. Like the luminous spectra given by incandescent gases and vapours, the absorption spectra of a number of substances have already been studied, and some with great precision—as, for example, the spectrum of the brown vapours of nitrogen dioxide by Hasselberg (at Pulkowa), or




FIG. 74.—Absorption spectra of nitrogen dioxide oxide and iodine.

the spectra of colouring matters (Eder and others), and especially those applied to orthochromatic photography, or the spectra of blood, chlorophyll (the green constituent of leaves), and other similar substances, all the more as by the aid of their spectra the presence of these substances may be discovered in small quantities (even in microscopical quantities, by the aid of special appliances or the microscope), and the changes they undergo investigated.

The absorption spectra, obtained at the ordinary temperature and proper to substances in all physical states, offer a most vast but as yet little studied field, both for the theory of all spectroscopy, and for gaining an insight into the structure of substances. The investigation of colouring matters has already shown that in certain cases a definite change of composition and structure entails not only a definite change of the colours but also a displacement of the absorption bands by definite wave lengths. This subject, which has only begun to be worked out, promises great scientific fruition.

lines may be ascribed to the absorption of certain rays of light in its passage from the luminous mass of the sun to the earth. The remarkable progress made in all spectroscopic research dates from the *investigations made by Kirchhoff* (1859) on the relation between absorption spectra and the spectra of luminous incandescent gases. It had already been long since observed (by Fraunhofer, Foucault, Ångström) that the bright spectrum of the sodium flame gives exactly the same two bright lines which are known as the line D in the solar spectrum, and expressed by black lines which evidently belong to an absorption spectrum. When Kirchhoff caused moderated sunlight to fall upon the slit of a spectroscope, and placed a sodium flame before it, a perfect superposition was observed—the bright sodium lines completely covered the black lines D of the solar spectrum. When later the continuous spectrum of a Drummond light appeared with the black line D on placing a sodium flame between it and the slit of the spectroscope—that is, when the Fraunhofer line of the solar spectrum was artificially produced then there was no doubt that it was seen in the solar spectrum because the light somewhere travelled through incandescent vapours of sodium. Hence a new theory of *reversed spectra*²⁹ arose—that is, respecting the relation between the waves of light emitted and absorbed by a substance under given conditions of temperature, which is expressed by Kirchhoff's law discovered by a careful analysis of the relations between the luminous rays absorbed and emitted by a substance. This law of the theory of light may be formulated in an elementary form in the following manner: At a given temperature the relation between the intensity of the light emitted (of a definite wave length) and the absorptive capacity with respect to the same colour (of the same wave length) is a constant quantity.³⁰ As a black dull surface emits a considerable

²⁹ A number of methods have been invented to demonstrate the reversibility of spectra; among these methods we will cite two which are most easily carried out. In Bunsen's method sodium chloride is put into an apparatus for evolving hydrogen (the spray of the salt is then carried off by the hydrogen and colours the flame with the yellow sodium colour), and the hydrogen is ignited in two burners—in one large one with a wide flame giving a bright yellow sodium light, and in another with a small fine orifice whose flame is pale: this flame will throw a dark patch on the large bright flame. In Ladoffsky's method the front tube (p. 552) is unscrewed from a spectroscope directed towards the light of a lamp (a continuous spectrum), and the flame of a spirit lamp coloured by a small quantity of NaCl is placed between the tube and the prism; a black band corresponding to sodium will then be seen on looking through the ocular tube. This experiment is always successful if there be only the requisite relation between the strength of the light of both lamps.

³⁰ The absorptive capacity is the relation between the intensity of the light (of a given wave length) falling upon and retained by a substance. Bunsen and Roscoe showed by direct experiment that this ratio is a constant quantity for every substance. If A stand for this ratio for a given substance at a given temperature—for instance, for a flame coloured by sodium—and E be the intensity of the light of the same wave length

quantity of heat rays and also absorbs a considerable quantity, whilst a polished metallic surface both absorbs but few and emits but few, so a flame coloured by sodium emits a considerable quantity of yellow rays of a definite refrangibility, and has the property of retaining a considerable quantity of the rays of the same refractive index. In general, the sphere which evolves definite rays also retains them.

Thus the bright spectral rays characteristic of a given metal may be reversed—that is, converted into dark lines—by passing light which gives a continuous spectrum through a space containing the heated vapours of the given metal. A similar phenomenon to that thus artificially produced may be observed naturally in sunlight, which shows dark lines characteristic of known metals—that is, the Fraunhofer lines form an absorption spectrum or depend on a reversed spectrum; it being presupposed that the sun itself, like all known sources of artificial light, gives a continuous spectrum without Fraunhofer lines.³¹ We must imagine that the sun, owing to the high temperature which is proper to it, emits a brilliant light which gives a continuous spectrum, and that this light, before reaching our eyes, passes through a space full of the vapours of different metals and their compounds. As the earth's atmosphere³² contains no, or very little, metallic vapours, and as they cannot be supposed to exist in the heavenly space, therefore the only place in which the existence of such vapours can be admitted is in the *atmosphere surrounding the sun itself*. As the cause of the sun's luminosity must be looked for in its high temperature, therefore the existence of an atmosphere containing metallic vapours is readily understood, because at its high temperature such metals as sodium, and even iron, are separated from their compounds and converted into vapour. The sun must be imagined as surrounded by an atmosphere of incandescent vaporous emitted at the same temperature by the same substance, then Kirchhoff's law, the explanation and deduction of which must be looked for in text books of physics, states that the fraction A/E is a constant quantity depending on the nature of a substance (as A depends on it) and determined by the temperature and wave length.

³¹ Heated metals begin to emit light (only visible in the dark) at about 420° (varying with the metal). On further heating solids first emit red, then yellow, and lastly white light. Compressed or heavy gases (see Chap. III. Note 44), when strongly heated, also emit white light. Heated liquids (for example, molten steel or platinum) also give a white compound light. This is readily understood. In a dense mass of matter the collisions of the molecules and atoms are so frequent that waves of only a few definite lengths cannot appear; the reverse is possible in rarefied gases or vapours.

³² Brewster, as is mentioned above, first distinguished the atmospheric, cosmical Fraunhofer lines from the solar lines. Janssen showed that the spectrum of the atmosphere contains lines which depend on the absorption produced by aqueous vapour. Egoroff, Olszewski, Janssen, and Liveing and Dewar showed by a series of experiments that the oxygen of the atmosphere determines certain lines of the solar spectrum, especially the line A.

and gaseous matter,³³ including those elements whose reversed spectra correspond with the Fraunhofer lines—namely, sodium, iron, hydrogen, lithium, calcium, magnesium, &c. Thus in spectrum analysis we find a means of determining the composition of the inaccessible heavenly luminaries, and much has been done in this respect since Kirchhoff's theory was formulated. By observations on the spectra of many heavenly bodies, changes have been discovered going on in them,³¹ and certain of the elements known to us have been found with certainty in them.³⁵ From this it must be concluded that the same elements which exist on the earth occur throughout the whole universe, and that at

³³ Eruptions, like our volcanic eruptions, but on an incomparably larger scale, are a frequent occurrence on the sun. They are seen as protuberances visible during a total eclipse of the sun, in the form of vaporous masses on the edge of the solar disc and emitting a faint light. These protuberances of the sun are now observed at all times by means of the spectroscope (Lockyer's method), because they contain luminous vapours (giving bright lines) of hydrogen and other elements.

³⁴ The great interest and vastness of astro-physical observations concerning the sun, comets, stars, nebulae, &c., render this new province of natural science very important, and necessitate referring the reader to special works on the subject. I cannot, however, but caution the reader against those premature conclusions which many form on a first acquaintance with the subject. Just as the astronomer may easily arrive at an arbitrary conclusion about the composition of elements, from observations upon the spectra of the heavenly bodies, so the chemist may easily fall into error as to the nature of the phenomena of the heavens by only judging from spectroscopic observations.

The most important astro-physical data since the time of Kellner are those referring to the *displacement* of the lines of the spectrum. Just as a musical note changes its pitch with the approach or withdrawal of the resonant object or the ear, so the pitch of the luminous note or wave length of the light varies if the luminous vapour and the earth from which we observe it approach or recede from each other; this expresses itself in a visible displacement of the spectral lines. The solar eruptions even give broken lines in the spectrum, because the rapidly moving eruptive masses of vapour and gases either travel in the direction of the eye or fall back towards the sun. As the earth travels with the solar system among the stars, so it is possible to determine the direction and velocity with which the sun travels in space by the displacement of the spectral lines and light of the stars.

The changes proceeding on the sun in its mass, which must be pronounced as vaporous, and in its atmosphere, are now studied by means of the spectroscope. For this purpose, there now exist many special astro-physical observatories where these investigations are carried on.

³⁵ Spectrum analysis has proved the indubitable existence in the sun and stars of a number of elements known in chemistry. Huggins, Secchi, and others have furnished a large amount of material upon this subject. A compilation of existing information on this subject has been given by Prof. S. A. Kleiber, in the *Journal of the Russian Physico-chemical Society* for 1885 (vol. xviii. p. 146). Besides which, a peculiar element called helium has been discovered, which is characterised by a line (whose wave length is 587.5, situated near D), which is seen very brightly in the projections (protuberances) and spots of the sun, but which does not belong to any known element and is not reproducible as a reversed, dark line. This may be a right conclusion—that is to say, it is possible that an element may be discovered to which the spectrum of helium corresponds—but it may be that the helium line belongs to one of the known elements, because spectra vary in the brilliancy and position of their lines with changes of temperature and pressure. Thus, for instance, Lockyer could only see the line 423, at the very end

that degree of heat which is proper to the sun those simple matters which we accept as the elements in chemistry are still undecomposed

of the calcium spectrum, at comparatively low temperatures, whilst the lines 397 and 398 appear at a higher temperature, and at a still higher temperature the line 423 becomes quite invisible.

Lockyer, to whom spectroscopy is indebted for many excellent spectroscopic observations, supposes that the elements existing on the earth are decomposed at the temperature of the sun—for instance, that iron decomposes into two new elements having particular spectra, because an unequal intensity of all the lines of iron is observed in different portions of the sun (spots, prominences, &c.), and because a *displacement* (Note 34) of certain of the lines of this metal may be observed in the sun's spots at the same time that other lines remain undisplaced. Lockyer supposes this to depend on the movement of one component part of iron with an immobility of the position (in space) of the other product of the decomposition of iron which remains in a lower stratum. Prof. Kleiber explains these phenomena by the fact that the visible spectrum of the sun is determined by the entire thickness of the atmosphere of the sun, by the inequality of the movement of different strata of the sun's atmosphere, and by the fact that lines of different wave lengths offer a different constant with reference to Kirchhoff's law. It is enough if the thickness, pressure, and temperature of an incandescent vapour be different in a laboratory experiment and in a given stratum of the solar atmosphere to obtain a marked difference in the intensity of the light of different bands of the spectrum of one and the same element. As regards the displacement of only one *portion* of the iron lines, Kleiber supplements Liveing and Dewar's observation that the displaced lines are those emitted by the most rarefied vapours (Note 27), by pointing out that in the first place one and the same line is sometimes observed on the sun both in a contorted (broken) and normal position (as Lockyer himself observed), and in the second place that the intensity of the light of different lines depends on the different temperatures and densities of the strata of the solar atmosphere, and therefore the lines determined by the upper strata may, by their movement, be displaced, whilst the other lines determined by the lower strata may remain unchanged. Besides which I may observe, for my part, that if, under ordinary conditions, we see the normal spectrum of iron in the sun, Lockyer's supposed component parts of iron must occur together in the sun, and therefore it is difficult to understand how one component part of iron is able to move whilst the other remains at rest. Furthermore, as the solar spectrum of iron entirely corresponds with that obtained by experiment at the comparatively low temperatures obtainable in the laboratory, it is necessary to admit one of the two following propositions—either the decomposition of iron does not require so high a temperature as that on the sun, and then it would be easy to prove this supposed complexity of iron by a laboratory experiment, or it must be admitted that the two component parts of iron when combined together (forming undecomposed iron) do not alter the positions of their spectral lines, whilst, as we shall see later, the spectra of elements change when they combine together, and therefore that in the case of iron a proposition must be made contradictory to this fact. Other data put forward by Lockyer in favour of the decomposability of certain elements proved when re-investigated (by Liveing and Dewar), by means of spectroscopes of high dispersive power, to be only founded on the confusion of dissimilar lines. The arguments of Lockyer concerning the decomposability of elements, which at one time made a great impression, do not thus appear to support the doctrine of a single common material (p. 20, Note 26), but must be made use of for the further development of spectroscopic science. Besides which I consider it well to turn attention to the facts (1) that the conception of the elements stands in all respects more firmly than any deductions obtained by the spectroscope; (2) this comparatively young doctrine of the spectra of elements is only the fruit of the chemical doctrine of elements; and (3) that as yet no generalisations, besides Kirchhoff's law, have appeared for spectroscopic phenomena, which could allow predictions being made, whilst the conception of elements has already arrived at this stage. When, however, spectroscopic science has been developed to the same extent

and remain unchanged. A high temperature forms one of those conditions under which compounds most easily decompose ; and therefore if sodium or a similar element were a compound, then in all probability it would be decomposed into component parts at the high temperature of the sun. This may already be concluded from the fact that in ordinary spectroscopic experiments the spectra obtained often belong to the metals and not to the compounds taken ; this depends on the decomposition of these compounds in the heat of the flame. If common salt be introduced into the flame of a gas-burner, a portion of it is decomposed, first forming, in all probability, with water, hydrochloric acid and sodium hydroxide, and the latter is then partially decomposed by the hydrocarbons, giving metallic sodium, whose incandescent vapour emits light of a definite refrangibility. This conclusion is arrived at from the following experiment :—If hydrochloric acid gas be introduced into a flame coloured by sodium it is observed that the sodium spectrum disappears, owing to the fact that metallic sodium cannot remain in the flame in the presence of an excess of hydrochloric acid. The same thing takes place on the addition of sal-ammoniac, which in the heat of the flame gives hydrochloric acid. If a porcelain tube containing sodium chloride (or sodium hydroxide or carbonate), and closed at both ends by glass plates, be so powerfully heated that the salt volatilises, then the sodium spectrum is not observable ; but if the salt be replaced by sodium, then both the bright line and the absorption spectra are obtained, according to whether the light emitted by the incandescent vapour be observed, or only that which passes through the tube. Thus the above spectrum is not given by sodium chloride or other sodium compound, but is proper to the metal sodium itself. It is the same with other analogous metals. The chlorides and other halogen *compounds* of barium, calcium, copper, &c., give independent spectra which differ from those of the metals. If barium chloride be introduced into a flame, it gives a mixed spectrum belonging to metallic barium and barium chloride. If besides barium chloride, hydrochloric acid or sal-ammoniac be introduced into the flame, then the spectrum of the metal disappears, and that of the chloride remains, which differs distinctly from the spectrum of barium fluoride, barium bromide, or barium iodide. A certain common resemblance and certain common lines are observed in the spectra of two different compounds of one and the same element obtained in the above-described manner, and also in the spectrum of the metal, but they all have their peculiarities. The

as chemical learning, then, perhaps, the present ideas will undergo a deep change and approach perfection. As yet spectroscopic science is still, for want of laws, at the epoch of the accumulation of facts and not of their possession.

independent spectra of the compounds of copper are easily observed (fig. 75). Thus certain compounds which exist and are luminous at a




Fig. 75.— Bright Spectra of Copper Compounds.

high temperature give their independent spectra. In the majority of cases the spectra of compounds are composed of indistinct luminous lines and complete bright bands, whilst metallic elements generally give a few clearly-defined spectral lines.³⁶ There is no reason for thinking

³⁶ Spectroscopic observations are still further complicated by the fact that one and the same substance gives different spectra at different temperatures. This is especially the case with gases whose spectra are obtained by an electric discharge in tubes. Plücker, Wüllner, Schuster, and others showed that at different temperatures and pressures the spectra of iodine, sulphur, nitrogen, oxygen, &c., are quite different from the spectra of the same elements at high temperatures and pressures. This may either depend on the fact that the elements change their molecular structure with a change of temperature, just as ozone is converted into oxygen, or else because at low temperature certain rays have a greater relative intensity than those which appear at higher temperatures. If we suppose that the molecules of a gas are in continual movement, with a velocity dependent on the temperature, then it must be admitted that they often strike against each other and rebound, and thus communicate peculiar movements to each other and the supposed ether, which express themselves in luminiferous phenomena. A rise of the temperature or an increase in the density of a gas must have an influence on the collision of its molecules and luminiferous movements thus produced, and this may be the cause of the difference of the spectra under these circumstances. It has been shown by direct experiment that gases compressed by pressure, when the collision of the molecules must be frequent and varied, exhibit a more complex spectrum on the passage of an electric spark than rarefied gases, and that even a continuous spectrum appears. In order to show the variability of the spectrum according to the circumstances under which it proceeds, it is enough to say that potassium sulphate fused on a platinum wire gives, on the passage of a series of sparks, a distinct system of lines, 583–578, whilst when a series of sparks is passed through a solution of this salt this system of lines is faint, and when Roscoe and Schuster observed the absorption spectrum of the vapour of metallic potassium (which is green) they remarked a number of lines of the same intensity as the above system in the red, orange, and yellow portions.

The spectra of solutions are best observed by means of Lecoq de Boisbaudran's arrangement, shown in fig. 76. A bent capillary tube, D F, inside which a platinum wire,

that the spectrum of a compound is equal to the sum of the spectra of its elements—that is, *every compound* which is not decomposed by heat *has its own proper spectrum*. This is best proved by absorption spectra, which are essentially only reversed spectra observed at low temperatures. If every salt of sodium, lithium, and potassium gives one and the same spectrum, this must be ascribed to the presence in the flame of the free metals liberated by the decomposition of their salts. Therefore *the phenomena of the spectrum are determined by molecules, and not by atoms*—that is, the molecules of the metal sodium, and not its atoms, produce those forms of vibrations which are expressed in the spectrum of a sodium salt. Where there is no free metallic sodium there is no sodium spectrum.

Spectrum analysis has not only endowed science with a representation of the composition of the distant heavenly bodies (of the sun, stars, nebulae, comets, &c.), but has also given a new *method* for studying the matter of the earth's surface. Bunsen by its means discovered two new elements belonging to the group of the alkali metals, and thallium, indium, and gallium were afterwards discovered by the same means. The spectroscope is employed in the study of rare metals (which in solution often give distinct absorption spectra), of dyes, and in general of many organic substances, &c.³⁷ With respect to the

A *a* (from 0·3 to 0·5 mm. in diameter) is fused, is immersed in a narrow cylinder, C (in which it is firmly held by a cork). The projecting end, *a*, of the wire is covered by a fine capillary tube, *d*, which extends 1·2 mm. beyond the wire. Another straight capillary tube, E, with a platinum wire, B *b*, about 1 mm. in diameter (a finer wire soon becomes hot), is held (by a cork or in a stand) above the end of the tube, D. If the wire A be now connected with the positive, and the wire B with the negative, terminal of a Ruhmkorff's coil (if the wires be connected in the opposite order, the spectrum of air is obtained), a series of sparks rapidly following each other appear between *a* and *b*, and their light may be examined by placing the apparatus in front of the slit of a spectroscope. The variations to which a spectrum is liable may easily be observed by increasing the distance between the wires, altering the direction of the current or strength of the solution, &c.

³⁷ The importance of the spectroscope for the purpose of chemical research was already shown by Gladstone in 1856, but it did not become an accessory to the laboratory until after the discoveries of Kirchhoff and Bunsen. It may be hoped that in time spectroscopic researches will explain certain wants of the theoretical (philosophical) side of chemistry, but as yet all that has been done in this respect can only be regarded as attempts which have not yet led to any trustworthy conclusions. Thus many, by collating the wave lengths of all the light vibrations excited by a given element, endeavour to find the law governing their mutual relations; others (especially Hartley and Ciamician), by comparing the spectra of analogous elements (for instance, chlorine, bromine, and iodine), have succeeded in noticing definite features of resemblance in them, whilst others (Grünwald) search for relations between the spectra of compounds




FIG. 76.—Method of slowing the spectrum of substances in solution.

metals which are analogous to sodium, they all give such very volatile salts and such very characteristic spectra that the least traces of them³⁸ are discovered with great ease by means of the spectroscope. For instance, *lithium* gives a very brilliant red coloration to a flame and a very bright red spectral line (wave length, 670 millionths mm.), which indicates the presence of this metal in admixture with compounds of other alkali metals.

Lithium, $\text{Li}=7$, is, like potassium and sodium, somewhat widely spread in siliceous rocks, but only occurs in small quantities and as mere traces in considerable masses of potassium and sodium salts. Only a very few minerals contain more than traces of it.³⁹ The compounds of lithium are in all respects closely analogous to the corresponding compounds of sodium and potassium; but the *carbonate* is sparingly

and their component elements, &c.; but—owing to the multiplicity of the spectral lines proper to many elements, and (especially in the ultra-red and ultra-violet ends of the spectrum) the existence of lines which are undistinguishable owing to their faintness, and also owing to the comparative novelty of spectroscopic research—this subject cannot be considered as in any way perfected in any of its branches.

³⁸ In order to show the degree of sensitiveness of spectroscopic reactions it will be enough to cite the following observation of Dr. Bence Jones. If a solution of 3 grains of a lithium salt be injected under the skin of a guinea-pig, then, after the lapse of four minutes, lithium may already be discovered in the bile and liquids of the eye, and, after ten minutes, in all parts of the animal.

³⁹ Thus *spodumene* contains up to 6 p.c. of lithium oxide, and *petolite*, and *lepidolite* or lithia mica, about 3 p.c. of lithium oxide. This mica is met with in certain granites in a somewhat considerable quantity, and is therefore most frequently employed for the preparation of lithium compounds. The treatment of lepidolite is carried on on a large scale, because certain salts of lithium are employed in medicine as a remedy for certain diseases (stone, gouty affections), as they have the power of dissolving the insoluble uric acid which is then deposited. Lepidolite, which is unacted on by acids in its natural state, decomposes under the action of strong hydrochloric acid after it has been fused. After being subjected to the action of the hydrochloric acid for several hours all the silica is obtained in an insoluble form, whilst the metallic oxides pass into solution as chlorides. This solution is mixed with nitric acid to convert the ferrous salts into ferric, and sodium carbonate is then added until the liquid becomes neutral, by which means a precipitate is formed of the oxides of iron, alumina, magnesia, &c., as insoluble oxides and carbonates. The solution (with an excess of water) then contains the chlorides of the alkaline metals KCl , NaCl , LiCl , which do not give a precipitate with sodium carbonate in a dilute solution. It is then evaporated, and a strong solution of sodium carbonate added. This precipitates lithium carbonate, which, although soluble in water, is much less so than sodium carbonate, and therefore the latter precipitates lithium from strong solutions as carbonate $2\text{LiCl} + \text{Na}_2\text{CO}_3 = 2\text{NaCl} + \text{Li}_2\text{CO}_3$. *Lithium carbonate*, which resembles sodium carbonate in many respects, is a substance which is very slightly soluble in cold water and is only somewhat soluble in boiling water. In this respect lithium forms a transition between the metals of the alkalis and other metals, especially the metals of the alkaline earths (magnesium, barium), whose carbonates are only sparingly soluble. Oxide of lithium, Li_2O , may be obtained by heating lithium carbonate with charcoal. Lithium oxide in dissolving gives (per molecule) 26000 heat units; but the combination of Li_2 with O evolves 140000 calories—that is, more than Na_2O (100000 calories) and K_2O (97000 calories), as shown by Beketoff (1887).

soluble in cold water, which fact is taken advantage of for separating lithium from potassium and sodium. This salt, Li_2CO_3 , is easily converted into the other compounds of lithium. Thus, for instance, the lithium hydroxide, LiHO , is obtained in exactly the same way as caustic soda, by the action of lime on the carbonate, and it is soluble in water and crystallises (from its solution in alcohol) as $\text{LiHO}\cdot\text{H}_2\text{O}$. Metallic *lithium* is obtained by the action of a galvanic current on fused lithium chloride; for this purpose a cast-iron crucible, furnished with a stout cover, is filled with lithium chloride; heated until the latter fuses, and then a strong galvanic current is passed through the molten mass. The positive pole (fig. 77) consists of a dense carbon rod C (surrounded by a porcelain tube P fixed in an iron tube B B), and the negative pole of an iron wire, on which the metal is deposited after the current has passed the molten mass for a certain length of time. Chlorine is evolved at the positive pole. When a somewhat considerable quantity of the metal has accumulated on the wire it is withdrawn, the metal is collected from it, and the experiment is then carried on as before. Lithium is the lightest of all metals, its specific gravity is 0.59, owing to which it even floats on naphtha; it melts at 180° , but does not volatilise at a red heat. Its appearance recalls that of sodium, and, like it, it has a yellow tint. At 200° it burns in air with a very bright flame, forming lithium oxide. In decomposing water it does not ignite the hydrogen. The characteristic test for lithium compounds is the *red coloration* which they impart to a colourless flame.⁴⁰




FIG. 77.—Preparation of lithium by the action of a galvanic current on fused lithium chloride.

Bunsen tried to determine by means of the spectroscope whether any other as yet unknown metals do not occur in different natural products together with lithium, potassium, and sodium, and he soon discovered two new alkali metals showing independent spectra. They are named after the characteristic coloration which they impart to the

⁴⁰ In determining the presence of lithium in a given compound, it is best to treat the material under investigation with acid (in the case of mineral silicon compounds hydrofluoric acid must be taken), and to treat the residue with sulphuric acid, evaporate to dryness, and extract with alcohol, which dissolves a certain amount of the lithium sulphate. It is easy to discover lithium in such an alcoholic solution by means of the coloration imparted to the flame on burning it, and in case of doubt by investigating its light in a spectroscope, because lithium gives a red line, which is very characteristic and is found as a dark line in the solar spectrum. Lithium was first discovered in 1817 in petolite by Arfvedson.

flame. One which gives a red and violet band is named *rubidium*, from *rubidius* (dark red), and the other is called *caesium*, because it colours a pale flame sky blue, which depends on its containing bright blue rays, which appear in the spectrum of caesium as two blue bands. Both metals accompany sodium, potassium, and lithium, but in small quantities; rubidium occurs more frequently than caesium. The amount of the oxides of caesium and rubidium in lepidolite does not generally exceed one-half p.c. Rubidium has also been found in the ashes of many plants, but it does not seem to accompany potassium in sea water. Rubidium also occurs, although in very small quantities, in the majority of mineral waters. In a very few cases caesium is not accompanied by rubidium; thus, in a certain granite on the Isle of Elba, caesium has been discovered, but not rubidium. This granite contains a very rare mineral called *pollux*, which contains as much as 34 p.c. of caesium oxide.⁴¹ Guided by the spectroscope, and aided by the fact that the double salts of platinic chloride and rubidium and caesium chlorides are still less soluble in water than the corresponding potassium salt, K_2PtCl_6 , Bunsen succeeded in separating both metals from each other and from potassium, and demonstrated the great resemblance they bear to each other. The isolated metals,⁴² rubidium and caesium, have

⁴¹ The salts of the majority of metals are precipitated as carbonates on the addition of ammonium carbonate—for instance, the salts of calcium, iron, &c. The alkalis whose carbonates are soluble are not, however, precipitated in this case. On evaporating the resultant solution and igniting the residue (to remove the ammonium salts), we obtain salts of the alkali metals. They may be separated by adding hydrochloric acid with a solution of platinic chloride. The chlorides of lithium and sodium give easily-soluble double salts with platinic chloride, whilst the chlorides of potassium, rubidium and caesium form double salts which are sparingly soluble. A hundred parts of water at 0° dissolve 0.74 part of the potassium platinochloride; the corresponding rubidium platinochloride is only dissolved to the amount of 0.134 part, and the caesium salt, 0.024 part; at 100° 5.13 parts of potassium platinochloride, K_2PtCl_6 , is dissolved, 0.634 parts of rubidium platinochloride, and 0.177 parts of caesium platinochloride. From this it is clear how the salts of rubidium and caesium may be isolated. The separation of caesium from rubidium by this means is very lengthy. It is better effected by taking advantage of the difference of the solubility of their carbonates in alcohol; caesium carbonate, Cs_2CO_3 , is soluble in alcohol, whilst the corresponding salts of rubidium and potassium are almost insoluble. Setterberg separated these metals as alums, but the best method, that given by Scharples, is founded on the fact that from a mixture of the chlorides of potassium, sodium, caesium, and rubidium in the presence of hydrochloric acid stannic chloride precipitates a double salt of caesium, which is very slightly soluble. The salts of Rb and Cs are closely analogous to those of potassium.

⁴² Bunsen obtained rubidium by distilling a mixture of the tartrate with soot, and Beketoff (1888) by heating the hydroxide with aluminium $2RbHO + Al = RbAlO_2 + H_2 + Rb$. By the action of 85 grams of rubidium on water, 94000 heat units are evolved. Setterberg obtained caesium (1882) by the electrolysis of a fused mixture of cyanide of caesium and of barium.

specific gravities of 1.52 and 1.88 respectively, and melt at 39° and 27° .

Judging by the properties of the free metals, and of their corresponding and even very complex compounds, lithium, sodium, potassium, rubidium, and caesium present an indubitable chemical resemblance. The fact that the metals easily decompose water, and that their hydroxides RHO and carbonates R_2CO_3 are soluble in water, whilst the hydroxides and carbonates of nearly all other metals are insoluble, confirms this, and if the resemblance between the corresponding salts be taken into consideration there is no doubt that the resemblance in the chemical character of these metals is very considerable : therefore they form a natural group of *alkali metals*. The halogens and the alkali metals form, by their character, the two extremes of the elements. Some of the other elements are metals approaching in a certain degree the alkali metals, both in their capacity of forming salts and in not forming acid compounds, but are not so energetic as the alkali metals, and are displaced by the latter from the majority of their compounds ; they also evolve less heat in combining with the halogens, and form less energetic bases than the alkali metals. Such are the common metals, silver, iron, copper, &c. Some other elements, in the character of their compounds, approach the halogens, and, like them, combine with hydrogen, but these compounds do not show the energetic property of the halogen acids ; in a free state they easily combine with metals, but they do not then form such saline compounds as the halogens do-- in a word, the halogen properties are less sharply defined in them than in the halogens themselves. Sulphur, phosphorus, arsenic, &c., belong to this order of elements. Lastly, there is yet another order of elements, like carbon and nitrogen, in which neither the metallic nor the halogen properties are clearly defined, and which in this respect occupy an intermediate position between the two above-mentioned orders of elements.

The clear distinction of the properties of the halogens and alkali metals is expressed in the fact that the former give acids and do not form bases, whilst the latter, on the contrary, only give bases. The first are true *acid elements*, the latter clearly-defined *basic or metallic elements*. On combining together, the halogens form, in a chemical sense, unstable compounds, and the alkali metals alloys in which the character of the metals remains unaltered, just as in the compound ICl the character of the halogens remains undisguised ; thus both classes of elements on combining with members of their own class form non-characteristic compounds, which have the properties of their components. On the other hand, the halogens on combining with the alkali

metals form compounds which are, in all respects, stable, and in which the original characters of the halogens and alkali metals have entirely disappeared. The formation of such compounds is accompanied by evolution of a large amount of heat; and by an entire change of both the physical and chemical properties of the substances originally taken. The alloy of sodium and potassium, although liquid at the ordinary temperature, is perfectly metallic, like both its components. The compound of sodium and chlorine has neither the appearance nor the properties of the original elements; sodium chloride melts at a higher temperature, and is more difficultly volatile, than either sodium or chlorine.

With all these qualitative differences there is, however, an important quantitative *resemblance between the halogens and the alkali metals*. This resemblance is clearly expressed by stating that both orders of elements belong to those which are univalent with respect to hydrogen. It is thus possible to express that both the above-named orders of elements replace hydrogen atom for atom. Chlorine is able to take the place of hydrogen by metalepsis, and the alkali metals take the place of hydrogen in water and acids. As it is possible to consecutively replace every equivalent of hydrogen in a hydrocarbon by chlorine, so it is possible in an acid containing several equivalents of hydrogen to replace the hydrogen consecutively equivalent after equivalent by an alkali metal; hence an atom of these elements is analogous to an atom of hydrogen, which is taken, in all respects, as the unit for the comparison of the other elements. In ammonia and in water chlorine and sodium are able to bring about a direct replacement. According to the law of substitution, the formation of sodium chloride, NaCl , already shows the equivalence of the atoms of the alkali metals and the halogens. The halogens and hydrogen and the alkali metals combine with such elements as oxygen, and it is easily seen that in such compounds one atom of oxygen is able to retain two atoms of the halogens, of hydrogen, and of the alkali metals. In this respect it is enough to compare the compounds KHO , K_2O , HClO , and Cl_2O , with water. It must not be forgotten, however, that with oxygen the halogens give higher acid grades of oxidation, besides compounds of the type R_2O , which the alkali metals and hydrogen are not capable of forming. We shall soon see that these relations are also subject to a special law, showing the gradual transition of the properties of the elements from the alkali metals to the halogens.⁴³

⁴³ We may here observe that the halogens, and especially iodine, may play the part of metals (hence iodine is more easily replaced by metals than the other halogens, and it approaches nearer to the metals in its physical properties than the other halogens).

The atomic weights of the alkali metals, lithium 7, sodium 23, potassium 39, rubidium 85, and caesium 133, show that here, as in the halogens, the elements may be arranged according to their atomic weights in order to compare the properties of the analogous compounds of the members of this group. Thus, for example, the platinochlorides of lithium and sodium are soluble in water; those of potassium, rubidium, and caesium sparingly soluble, and the greater the atomic weight of the metal the less soluble is the salt. In other cases the reverse is observed—the greater the atomic weight the more soluble are the corresponding salts. The variation of properties with the variation in atomic weights even shows itself in the metals themselves; thus lithium volatilises with difficulty, whilst sodium is obtained by means of distillation, potassium volatilises more easily than sodium, and rubidium and caesium, as we have seen, are still more volatile.

Schützenberger obtained a compound $C_2H_5O(OCI)$, which he called chlorine acetate, by acting on acetic anhydride, $(C_2H_5O)_2O$, with chlorine monoxide, Cl_2O . With iodine this compound disengages chlorine and forms iodine acetate, $C_2H_5O(OI)$, which also is formed by the action of iodine chloride on sodium acetate, $C_2H_5O(ONa)$. Such compounds are very unstable, decompose with an explosion when heated, and are changed by the action of water and of many other re-agents, which is in accordance with the fact that they contain very closely-allied elements, as Cl_2O itself, or ICl or KNa . By the action of chlorine monoxide on a mixture of iodine and acetic anhydride, Schützenberger also obtained the compound $I(C_2H_5O_2)_5$, which is analogous to ICl_5 , because the group $C_2H_5O_2$ is, like Cl , a halogen, forming salts with the metals.

CHAPTER XIV

THE VALENCY AND SPECIFIC HEAT OF THE METALS. MAGNESIUM,
CALCIUM, STRONTIUM, BARIUM, AND BERYLLIUM

It is easy by investigating the composition of corresponding compounds, to establish the *equivalent weights* of the metals—that is, the quantity which replaces one part by weight of hydrogen. If a metal directly decomposes acids, with the evolution of hydrogen, then the equivalent weight of the metal may be determined by taking a definite weight of it and measuring the volume of hydrogen evolved by its action on an excess of acid; then it is easy to calculate the weight of the hydrogen from its volume.¹ The same result may be arrived at by determining the composition of the normal salts of the metal; for instance, by finding the weight which combines with 35·5 parts of chlorine or 80 parts of bromine.² The equivalent of a metal may be also learnt by simultaneously (*i.e.*, in one circuit) decomposing an acid and a fused salt of a given metal by an electric current and determining the relation between the amounts of hydrogen and metal separated, because, according to Faraday's law, electrolytes (conductors of the second order) are always decomposed in equivalent quantities. The equivalent of a metal may even be found by simply determining the relation between the weight of a metal and of its salt giving oxide, as by this weight we know the weight of the metal which combines with 8 parts by weight of oxygen, and this will be the weight of an equivalent, because 8 parts of oxygen combine with 1 part by weight of

¹ Under favourable circumstances (by taking all the requisite precautions), the weight of the equivalent may be accurately determined by this method. Thus Reynolds and Ramsay (1887) determined the equivalent of zinc to be 32·7 by this method (from the average of 23 experiments), whilst by other methods it has been fixed (by different observers) between 32·55 and 33·95.

The difference in their equivalents may be demonstrated by taking equal weights of different metals, and by collecting the hydrogen evolved by them (under the action of an acid or alkali).

² The most accurate determinations of this kind were carried on by Stas, and will be described in speaking of silver.

hydrogen. One method is verified by another, and all the processes for the accurate determination of the equivalents require the most accurate methods to avoid the absorption of moisture, of further oxidation, volatility, and other like circumstances which influence exact weighings. The description of the methods necessary for the attainment of exact results belongs to the province of analytical chemistry.

For univalent metals, like those of the alkalis, the weight of the equivalent is equal to the weight of the atom. For bivalent metals the atomic weight is equal to the weight of two equivalents, for n -valent metals it is equal to the weight of n equivalents. Thus aluminium, $\text{Al}=27$, is trivalent, that is, its equivalent $= 9$; magnesium, $\text{Mg}=24$, is bivalent, and its equivalent $= 12$. Therefore, if potassium or sodium, or in general a univalent metal, M , gives compounds M_2O , MHO , MCl , MNO_3 , M_2SO_4 , &c., and in general MX , then for bivalent metals like magnesium or calcium the corresponding compounds will be MgO , $\text{Mg}(\text{HO})_2$, MgCl_2 , $\text{Mg}(\text{NO}_3)_2$, MgSO_4 , &c., or in general MX_2 .

By what are we to be guided in ascribing to some metals univalency and to others bi-ter-quadri- . . . n -valency? What obliges us to make this difference? Why are not all metals given the same valency—for instance, why is not magnesium considered as univalent? If this be done, taking $\text{Mg}=12$ (and not 24 as now used), not only is a simplicity of expression of the composition of all the compounds of magnesium attained, but also we gain the advantage that their composition will be the same as those of the corresponding compounds of sodium and potassium. These compositions were so expressed before, why has this been changed now?

These questions could only be answered after the establishment of the conceptions of multiples of the atomic weights as the minimum quantities of the elements combining together to form compounds—in a word, since the time of the establishment of Avogadro-Gerhardt's law (Chap. VII.). By taking such an element as arsenic, which has many volatile compounds, it is easy to determine the density of these compounds, and therefore to establish their molecular weights, and hence to find the indubitable atomic weight, exactly as for oxygen, nitrogen, chlorine, carbon, &c. It appears that $\text{As}=75$, and its compounds correspond, like the compounds of nitrogen, with the forms AsX_3 and AsX_5 ; for example, AsH_3 , AsCl_3 , AsFl_5 , As_2O_5 , &c. It is evident that we are here dealing with a metal (or, better, element) of two valencies, and which is furthermore in no way univalent, but tri- or quinquivalent. This example alone is sufficient for the recognition of the existence of polyvalent atoms among the metals. And as antimony

and bismuth are closely analogous to arsenic in all their compounds, as potassium is analogous to rubidium and caesium; therefore, although very few volatile compounds of bismuth are known, it was necessary to ascribe to them formulae corresponding with those ascribed to arsenic.

As we shall see in describing them, there are also many analogous metals among the bivalent elements, some of which also give volatile compounds. For example, zinc, which is itself volatile, gives several volatile compounds (for instance, zinc ethyl, $\text{ZnC}_4\text{H}_{10}$, which boils at 118° , vapour density = 61.3), and in the molecules of all these compounds there is never less than 65 parts of zinc, which is equivalent to H_2 , because 65 parts of zinc displace 2 parts by weight of hydrogen; so that zinc is just such an example of the bivalent metals as oxygen, whose equivalent = 8 (because H_2 is replaced by $\text{O} = 16$), is a representative of the bivalent elements, or as arsenic is of the tri- and quinquivalent elements. And, as we shall afterwards see, magnesium is in many respects closely analogous to zinc, which fact obliges us to regard magnesium as a bivalent metal.

Such metals as mercury and copper, which are able to give not one but two bases, are of particular importance for distinguishing univalent and bivalent metals. Thus copper gives the suboxide Cu_2O and the oxide CuO —that is, the compounds CuX corresponding with the suboxide are analogous (in the quantitative relations, by their composition) to NaX or AgX , and the compounds of the oxide CuX_2 to MgX_2 , ZnX_2 , and in general to the bivalent metals. It is clear that in such examples we must distinguish metals of varying atomicity.

In this manner the valency of many metals may be established by means of certain and comparatively few volatile metallic compounds, and by the aid of a search into their analogies (concerning which see Chap. XV.). *The law of specific heats* discovered by Dulong and Petit has frequently been applied to the same purpose³ in the

³ The chief means by which we determine the valency of the elements, or what multiple of the equivalents should be ascribed to the atom, are: (1) The law of Avogadro-Gerhardt. This method is the most general and trustworthy, and has already been applied to a great number of elements. (2) The different grades of oxidation and their isomorphism or analogy in general; for example, $\text{Fe} = 56$ because the suboxide (ferrous oxide) is isomorphous with magnesium oxide, &c., and the oxide (ferric oxide) contains $1\frac{1}{2}$ times as much oxygen as the suboxide. Berzelius, Marignac, and others took advantage of this method for determining the composition of the compounds of many elements. (3) The specific heat, according to Dulong and Petit's law. Regnault, and more especially Cannizzaro, used this method to distinguish univalent from bivalent metals. (4) The periodic law (see Chapter XV.) has served as a means for the determination of the atomic weights of cerium, uranium, yttrium, &c., and more especially of gallium, scandium, and germanium. The correction of the results of one method by those

history of chemistry, especially since the development given to this law by the researches of Regnault, and since Cannizzaro (1860) showed the agreement between the deductions of this law and the consequences arising from Avogadro-Gerhardt's law.

Dulong and Petit, having determined the specific heat of a number of solid elementary substances, observed that as the atomic weights of the elements increase, their specific heats decrease, and that *the product of the specific heat Q into the atomic weight A is an almost constant quantity*. This means that to bring different elements into a known thermal state, an equal amount of work is required if atomic quantities of the elements are taken; that is, the amounts of heat expended in heating equal quantities by weight of the elements are far from equal, but are in inverse proportion to the atomic weights. For thermal changes the atom is a unit; all atoms, notwithstanding the difference of weight and nature, are equal. This is the simplest expression of the fact discovered by Dulong and Petit. The specific heat measures that quantity of heat which is required to raise the temperature of *one unit of weight* of a substance by one degree. If the magnitude of the specific heat of elements be multiplied by the atomic weight, then we obtain the atomic heat—that is, the amount of heat required to raise the temperature of the atomic weight of an element by one degree. It is these products which for the majority of the elements prove to be approximately, if not quite, identical. A complete identity cannot be expected, because the specific heat of one and the same substance varies with the temperature, with its passage from one state into another, and frequently with even a simple mechanical change of density (for instance by hammering), not to speak of allotropic changes, &c. We will

of others is generally had recourse to, and is quite necessary, because phenomena of dissociation, polymerisation, &c., may complicate the individual determinations by each method.

It will be well to observe that a number of other methods, especially from the province of those physical properties which are clearly dependent on the magnitude of the atom (or equivalent, or of the molecule, may lead to the same result. I may point out, for instance, that even the specific gravity of solutions of the metallic chlorides (Chapter VII. p. 322) may serve for this purpose. Thus if beryllium be taken as trivalent—that is, if the composition of its chloride be taken as BeCl_3 (or a polymeride of it), then the specific gravity of solutions of beryllium chloride will not fit into the series of the other metallic chlorides. But on ascribing to it an atomic weight $\text{Be} = 7$, or taking Be as bivalent, the composition of its chloride as BeCl_2 , we arrive at the general rule given on p. 318. Thus W. G. Burdakoff determined in my laboratory, that the specific gravity at 15° , 1° of the solution $\text{BeCl}_2 + 200\text{H}_2\text{O} = 1.0138$ —that is, greater than the corresponding solution $\text{KCl} + 200\text{H}_2\text{O} (= 1.0121)$, and less than the solution $\text{MgCl}_2 + 200\text{H}_2\text{O} (= 1.0203)$, as would follow from the magnitude of the molecular weight $\text{BeCl}_2 = 80$, because $\text{KCl} = 74.5$ and $\text{MgCl}_2 = 95$ (see my work *Investigation of Aqueous Solutions*, 1887. p. 425).

cite several figures⁴ proving the truth of the conclusions arrived at by Dulong and Petit.

	Li	Na	Mg	P
A=	7	23	24	31
Q=	0.9408	0.2934	0.245	0.202
AQ=	6.59	6.75	5.88	6.26

	Fe	Cu	Zn	Br
A=	56	63	65	80
Q=	0.112	0.093	0.093	0.0843
AQ=	6.27	5.86	6.04	6.74

	Pd	Ag	Sn	I
A=	106	108	118	127
Q=	0.0592	0.056	0.055	0.541
AQ=	6.28	6.05	6.49	6.87

	Pt	Au	Hg	Pb
A=	196	198	200	206
Q=	0.0325	0.0324	0.0333	0.0315
AQ=	6.37	6.41	6.66	6.49

It is seen from this that the product of the specific heat of the element into the atomic weight is an almost constant quantity, which is nearly 6. Therefore the possibility arises of judging the valency with a sufficient degree of exactitude, by the specific heats of the

⁴ The specific heats here given refer to different limits of temperature, but in the majority of cases between 0° and 100°; only in the case of bromine the specific heat is taken (for the solid state) at a temperature below -7°, according to Regnault's determination. *The variation of the specific heat with a change of temperature* forms a very complex phenomenon, the consideration of which I think would here be out of place. I will only cite certain figures as an example. According to Bystrom, the specific heat of iron at 0° = 0.1116, at 100° = 0.1114, at 200° = 0.1188, at 300° = 0.1267, and at 1400° = 0.4031. Between these last limits of temperature a change takes place in iron (a spontaneous heating, *recalcescence*), as we shall afterwards see. For quartz SiO₂, Pionchon gives $Q = 0.1737 + 394t10^{-6} - 27t^210^{-9}$ up to 400°; consequently, as a rule, the specific heat varies with the temperature. Still more remarkable are H. E. Weber's observations on the great variation of the specific heat of charcoal, the diamond and boron:

	0°	100°	200°	600°	900°
Wood charcoal	0.15	0.23	0.29	0.44	0.46
Diamond	0.10	0.19	0.22	0.44	0.45
Boron	0.22	0.29	0.35	—	—

These determinations (they have been verified by Dewar) are of especial importance as confirming the universality of Dulong and Petit's law, because the elements mentioned above form exceptions to the general rule when the mean specific heat for temperatures between 0° and 100° is taken. Thus in the case of the diamond the product of $A \times Q$ at 0° = 1.2, and for boron = 2.4. But if we take the specific heat towards which there is evidently a tendency with a rise of temperature, then we obtain a product approaching

metals. Thus, for instance, the specific heats of lithium, sodium, and potassium convince one of the fact that their atomic weights are indeed those which we took, because by multiplying the specific heats found by experiment by the corresponding atomic weights we obtain the following figures: Li, 6.59, Na, 6.75 and K, 6.47. Of the alkaline earth metals the specific heats have been determined: of magnesium = 0.245 (Regnault and Kopp), of calcium = 0.170 (Bunsen), and of barium = 0.05 (Mendeléeff). If the same composition be ascribed to the compounds of magnesium as to the corresponding compounds of potassium, then the equivalent of magnesium will be equal to 12. On multiplying this atomic weight by the specific heat of magnesium, we obtain a figure 2.94, which is half that which is given by the other elements, and therefore the atomic weight of magnesium must be taken as equal to 24 and not to 12. Then the atomic heat of magnesium = $24 \times 0.245 = 5.9$; for calcium, giving its compounds a composition CaX_2 —for example CaCl_2 , CaSO_4 , CaO ($\text{Ca} = 40$)—we obtain an atomic heat = $40 \times 0.17 = 6.8$, and for barium it is equal to $137 \times 0.05 = 6.8$; that is, they must be counted as bivalent, or that their atom replaces H_2 , Na_2 , or K_2 . This conclusion may be confirmed by a method of analogy, as we shall afterwards see. A strict application of the principle of specific heats to the determination of the magnitudes of the atomic weights of those metals, the magnitude of whose atomic weights

to 6 as with other elements. Thus with the diamond and charcoal, it is evident that the specific heat tends towards 0.47, which multiplied by 12 gives 5.6, the same as for magnesium and aluminium. I may here turn the reader's attention to the fact that for solid elements having a small atomic weight, the specific heat varies considerably if we take the average figures for temperatures 0° to 100° :

Li = 7	Be = 9	B = 11	C = 12
Q = 0.94	0.42	0.24	0.20
AQ = 6.6	3.8	2.6	2.4

It is therefore clear that the specific heat of beryllium determined at a low temperature cannot serve for establishing its atomicity. On the other hand, the low atomic heat of charcoal, graphite, and the diamond, boron, &c., may perhaps depend on the complexity of the molecules of these elements. The necessity for acknowledging a great complexity of the molecules of carbon was explained in Chapter VIII. In the case of sulphur the molecule contains at least S_8 and its atomic heat = $32 \times 0.163 = 5.22$, which is distinctly below the normal. If a great number of atoms of carbon are gathered together in the molecule of charcoal, this would to a certain extent account for its comparatively small atomic heat. With respect to the specific heat of compounds it will not be out of place to here mention the conclusion arrived at by Kopp, that the molecular heat (that is, the product of MQ) may be looked on as the sum of the atomic heats of its component elements; but as this rule is not a general one, and can only be applied to an approximate judgment of the specific heats of substances, I do not think it necessary to go into the details of the conclusions described in Liebig's 'Annalen Supplement-Band,' 1864; which includes a number of determinations made by Kopp.

could not be determined according to Avogadro-Gerhardt's law, was made about 1860 by the Italian professor Cannizzaro.

Exactly the same conclusions respecting the bivalence of magnesium and its analogues are obtained by comparing the specific heats of their compounds, especially of the halogen compounds as the most simple, with the specific heats of the corresponding alkali compounds. Thus, for instance, the specific heat of magnesium and calcium chlorides, MgCl_2 and CaCl_2 , equal 0.194 and 0.164, and of sodium and potassium chlorides, NaCl and KCl , 0.214 and 0.172, and therefore their molecular heats (or the products QM , where M is the weight of the molecule) are 18.4 and 18.2, 12.5 and 12.8, and therefore the atomic heats (or the quotient of QM by the number of atoms) are all nearly 6, as with the elements. Whilst if, instead of the actual atomic weights $\text{Mg}=24$ and $\text{Ca}=40$, their equivalents 12 and 20 be taken, then the atomic heats of the chlorides of magnesium and calcium would be about 4.6, whilst those of potassium and sodium chlorides are about 6.3.⁵

As the specific heat or the amount of heat required to raise the temperature of a unit of weight one degree ⁶ is a complex quantity—

⁵ It must be remarked that in the case of oxygen (hydrogen and carbon) compounds the quotient of MQ/n , where n is the number of atoms in the molecule, is always less than 6 for solids; for example, in the case of $\text{MgO} = 5.0$, $\text{CuO} = 5.1$, $\text{MnO}_2 = 4.6$, ice ($Q = 0.504$) — 3, $\text{SiO}_2 = 3.5$, &c. At present it is impossible to say whether this depends on the smaller specific heat of the atoms of oxygen in its solid compounds (Kopp, Note 4) or on some other reason; but, nevertheless, taking into account this decrease, depending on the presence of oxygen, a reflection of the atomicity of the elements may to a certain extent be seen in the specific heat of the oxides. Thus in the case of alumina, Al_2O_3 ($Q = 0.217$), $MQ = 22.3$, and therefore the quotient $MQ/n = 4.5$, which is nearly that given by magnesium oxide, MgO . But if we ascribe the same composition to alumina as to magnesia—that is, if aluminium were counted as divalent—we should obtain the figure 3.7, which is much less. In general, in compounds of identical atomic composition and of analogous chemical properties the molecular heats MQ are nearly equal, as many investigators have long remarked. For example, $\text{ZnS} = 11.7$ and $\text{HgS} = 11.8$; $\text{MgSO}_4 = 27.0$ and $\text{ZnSO}_4 = 28.0$, &c.

⁶ If W be the amount of heat contained in a mass m of a substance at a temperature t , and dW the amount expended in heating it from t to $t + dt$, then the specific heat $Q = dW/(m \times dt)$. The specific heat not only varies with the composition and complexity of the molecules of a substance, but also with the temperature, pressure, and physical state of a substance. Even for gases the variation of Q with t is to be observed. Thus it is seen from the experiments of Regnault and Wiedemann that the specific heat of carbonic anhydride at $0^\circ = 0.19$, at $100^\circ = 0.22$, and at $200^\circ = 0.24$. But the variation of the specific heat of permanent gases with the temperature is, as far as we know, very inconsiderable. Therefore the specific heat of those permanent gases which contain two atoms in the molecule (H_2 , O_2 , N_2 , CO , and NO) may be, as is shown by experiment, taken as not varying with the temperature. The constancy of the specific heat of perfect gases forms one of the fundamental propositions of the whole theory of heat, and supports the determination of temperatures by means of gas-thermometers containing hydrogen, nitrogen, or air. Le Chatelier (1887), on the basis of existing determinations, concludes that the molecular heat—that is, the product MQ —of all gases varies in proportion to the temperature, and tends to become equal ($= 6.8$) at the temperature of absolute zero (that is, at -273°); and therefore $MQ = 6.8 + a(273 + t)$, where a is a constant quantity

including not only the increase of the energy of a substance with its rise in temperature, but also the external work of expansion⁷ and the

which increases with the complexity of the gaseous molecule. The magnitude $1000a$ for ammonia = 6.11, for chloric anhydride = 7.42, for ethylene, C_2H_4 = 12.7, for chloroform, $CHCl_3$ = 29.5, &c. For permanent gases $a = 0$, and $MQ = 6.8$ —that is, the atomic heat (if the molecule contains two atoms) = 3.4, as it is in reality. As regards liquids (as well as the vapours formed by them), the specific heat always rises with the temperature: Thus for benzene, it equals $0.38 + 0.0014t$. R. Schiff (1887) showed that the variation of the specific heat of many organic liquids is proportional to the change of temperature (as in the case of gases, according to Le Chatelier), and reduced these variations into dependence with their composition and absolute boiling point. It is very probable that the theory of liquids will make use of these simple relations, which recall the simplicity of the variation of the specific gravity (Chap. II. Note 34), cohesion, and other properties of liquids with the temperature. They are all expressed by the linear function of the temperature, $a + bt$, with the same degree of proximity as the property of gases is expressed by the equation $pv = Rt$.

As regards the relation between the specific heats of liquids (of solids) and of their vapours, the specific heat of the vapour (and also of the solid) is always less than that of the liquid. For example, benzene vapour 0.22, liquid 0.38; chloroform vapour 0.13, liquid 0.23; steam 0.475, liquid water 1.0. But the whole complexity of the relations existing in specific heat is seen from the fact that the specific heat of ice = 0.502 is less than that of liquid water. According to Regnault, in the case of bromine the specific heat of the vapour = 0.55 (at 150°), of the liquid = 0.107 (at 30°), and of solid bromine = 0.084 (at -15°). The specific heat of solid benzoic acid (according to experiment and calculation, Hess 1888) between 0° and 100° is 0.31, and of liquid benzoic acid 0.50. One of the problems of the present day is the explanation of those complex relations which exist between the composition and such properties as specific heat, latent heat, expansion by heat, compression, internal friction, cohesion, and other like properties. They can only be connected by a complete theory of liquids, which may now soon be expected, more especially as many sides of the subject have already been partially explained.

⁷ According to the above reasons the quantity of heat, Q , required to raise the temperature of one part by weight of a substance by one degree may be expressed by the sum $Q = K + B + D$, where K is the heat actually expended in heating the substance, or that which is termed the absolute specific heat, B the amount of heat expended in the internal work accomplished with the rise of temperature, and D the amount of heat expended in external work. In the case of gases the last quantity may be easily determined, knowing their coefficient of expansion, which is approximately 0.00368. By applying to this case the same argument given at the end of Note 11, Chap. I., we find that one cubic metre of a gas heated by 1° produces an external work of 10333×0.00368 , or 38.02 kilogrammetres, on which 38.02 424 or 0.0897 heat units are expended. This is the heat expended for the external work produced by one cubic metre of a gas, but the specific heat refers to units of weight, and therefore it is necessary in order to know D to reduce the above quantity to a unit of weight. One cubic metre of hydrogen at 0° and 760 mm. pressure weighs 0.0896 kilo, a gas of molecular weight M has a density $M/2$, consequently a cubic metre weighs (at 0° and 760 mm.) $0.0448M$ kilo, and therefore 1 kilogram of the gas occupies a volume $1/0.0448M$ cubic metres, and hence the external work D in the heating of 1 kilo. of the given gas by $1^\circ = 0.0896/0.0448M$, or $D = 2/M$.

Taking the magnitude of the internal work B for gases as minute if permanent gases are taken, and therefore supposing $B = 0$, we find the specific heat of gases at a constant pressure $Q = K + 2/M$, where K is the specific heat at a constant volume, or the true specific heat, and M the molecular weight. Hence $K = Q - 2/M$. The magnitude of the specific heat Q is given by direct experiment. According to Regnault's experiments, for oxygen it = 0.2175, for hydrogen 3.405, for nitrogen 0.2438; the molecular weights of these gases are 32, 2, and 28, and therefore for hydrogen $K = 0.2438 - 0.0714 = 0.1724$. These true

internal work accomplished in the molecules inciting them to decomposition according to the rise of temperature ⁸—therefore it is impos-

specific heats of elements are in inverse proportion to their atomic weights—that is, their product by the atomic weight is a constant quantity. In reality, for oxygen this product = $0.155 \times 16 = 2.48$, for hydrogen 2.40 , for nitrogen $0.7724 \times 14 = 2.414$, and therefore if A stand for the atomic weight we obtain the expression $K \times A = \text{a constant}$, which may be counted as 2.45 ; and this is the true expression of Dulong and Petit's law, because K is the true specific heat and A the weight of the atom. It should be remarked, moreover, that the product of the observed specific heat Q into A is also a constant quantity (for oxygen = 3.48 , for hydrogen = 3.40), because the external work D is also inversely proportional to the magnitude of the atomic weight.

In the case of gases we distinguish the specific heat at a constant pressure c' (we designated this quantity above by Q), and at a constant volume c . It is evident that *the relation between both specific heats, k* , judging from the above, is the ratio of Q to K , or equal to the ratio of $2.45n + 2$ to $2.45n$. When $n = 1$ this ratio $k = 1.8$; when $n = 2$ $k = 1.4$, when $n = 3$ $k = 1.3$, and with an exceedingly large number, n , of atoms in the molecule, $k = 1$. That is, the ratio between the specific heats decreases from 1.8 to 1.0 as the number of atoms, n , contained in the molecule increases. This deduction is verified to a certain extent by direct experiment. For such gases as hydrogen, oxygen, nitrogen, carbonic oxide, air, and others in which $n = 2$, the magnitude of k is determined by methods described in physics (for example, by the change of temperature with an alteration of pressure, by the velocity of sound, &c.), and is found in reality to be nearly 1.4 , and for such gases as carbonic anhydride, nitric peroxide, and others it is nearly 1.3 . Kundt and Warburg (1875), by means of the approximate method mentioned on p. 321, determined k for mercury vapour when $n = 1$, and found it to be $= 1.67$ —that is, a larger quantity than for air, as would be expected from the above.

It may be admitted that the true atomic heat of gases = 2.43 , only under the condition that they are distant from a liquid state, and do not undergo a chemical change when heated—that is, when no internal work is produced in them ($B = 0$). Therefore this work may to a certain extent be judged by the observed specific heat. Thus, for instance, for chlorine ($Q = 0.12$, Regnault; $k = 1.33$, according to Straker and Martin, and therefore $K = 0.09$, $MK = 6.4$), the atomic heat (3.2) is much greater than for other gases containing two atoms in a molecule, and one must consider, therefore, that when heated some great internal work is accomplished of whose nature it is at present impossible to form an opinion. And as in the case of such gases as ethylene, C_2H_4 ($Q = 0.39$), according to Wiedemann $k = 1.2$, $K = 0.33$, $MK = 9.2$; hence the true atomic heat is less than for constant gases = 1.5 . Therefore the question as to the relation between the specific heats of gases and the number of atoms and composition cannot be counted as sufficiently general if we do not consider Le Chatelier's deduction (Note 6) as proved by the association of data. If the latter be verified, then it will have to be admitted that Dulong and Petit's law is not applicable to any gases besides those which are permanent and possess a comparatively low molecular weight. The question might be solved by determining the specific heat of mercury vapour at different temperatures, but as yet there are no exact methods of doing this.

All the more remarkable is the adaptability of Dulong and Petit's law to the mass of the common elements in a solid state. In order to generalise the facts concerning the specific heat of gases and solids, it appears to me possible to accept the following general proposition: *the atomic heat* (that is, AQ or QM/n , where M is the molecular weight and n the number of molecules) *is less (greatest for solids, 6.8; for gases, 3.4) the more complex the molecule (that is, the greater the number (n) of the atoms forming it), and to a certain extent (with similar physical states of substances) the less the mean (M/n) weight of the atom.*

⁸ For an example, it is enough to point out the specific heat of nitrogen tetroxide, N_2O_4 , which, when heated, gradually passes into NO_2 —that is, chemical work of decom-

sible to expect in the magnitude of the specific heat the great simplicity of relation to composition which we see, for instance, in the density of gaseous substances. Therefore, although the specific heat gives one of the important means of judging the atomicity of the elements, still the mainstay for a true judgment of atomicity is only given by Avogadro-Gerhardt's law. All other means can only be accessory or preliminary, until it be possible to have direct recourse to the determination of the vapour density.

Among the bivalent metals the first place, with respect to their distribution in nature, is occupied by *magnesium* and *calcium*, just as sodium and potassium stand first amongst the univalent metals. The relation which exists between the atomic weights of these four metals confirms the above comparison. In fact, the combining weight of magnesium is equal to 24, and of calcium 40; whilst the combining weights of sodium and potassium are 23 and 39—that is, the latter are one unit less than the former.⁹ They all belong to the number of *light metals*, as they have but a small specific gravity, in which they differ from the ordinary, generally known heavy, or ore, metals (for instance, iron, copper, silver, and lead), which are distinguished by a much greater specific gravity. There is no doubt that their low specific gravity has a significance, not only as a simple point of distinction, but also as a property which determines the fundamental properties of these metals. Indeed, all the light metals have a series of points of resemblance which approximates them to the metals of the alkalis; thus both magnesium and calcium, like the metals of the

position proceeds, which consumes heat. Speaking generally, specific heat is a complex quantity, in which it is clear that thermal data (for instance, the heat of reaction) alone cannot give an idea either of chemical or of physical changes individually, but always depend on an association of the one and the other. If a substance be heated from t_0 to t , it cannot but suffer a chemical change (that is, the state of the atoms in the molecules changes more or less in one way or another) if dissociation sets in at a temperature t_1 . Even in the case of the elements whose molecules contain only one atom, a true chemical change is possible with a rise of temperature, because more heat is evolved in chemical reactions than that quantity which participates in purely physical changes. One gram of hydrogen (specific heat = 3.4 at a constant pressure) cooled to the temperature of absolute zero will evolve altogether about one thousand units of heat, 8 grams of oxygen half this amount, whilst in combining together they evolve in the formation of 9 grams of water more than thirty times as much heat. Hence the store of chemical energy (that is, of the movement of the atoms, vortex, or other) is much greater than the physical store proper to the molecules, but it is the change accomplished by this store that is the cause of chemical transformations. Here we evidently touch on those limits of existing knowledge beyond which the discipline of science does not yet allow us to pass. A number of new scientific conquests are necessary before this can become possible.

⁹ As if $\text{NaH}=\text{Mg}$ and $\text{KH}=\text{Ca}$, which is in accordance with their valency, KH including two monovalent elements is a bivalent group like Ca .

alkalis, decompose water (without the addition of acids), although not so easily as the latter metals. The process of the decomposition is essentially one and the same; for example, $\text{Ca} + 2\text{H}_2\text{O} = \text{CaH}_2\text{O}_2 + \text{H}_2$ —that is, hydrogen is liberated and a hydroxide of the metal formed. These hydroxides are bases which saturate nearly all acids. However, the hydroxides RH_2O_2 of calcium and magnesium are in no respects so energetic as the hydroxides of the true metals of the alkalis; thus when heated they lose water, are not so soluble, develop less heat with acids, and form various salts, which are less stable and more easily decomposed by heat than the corresponding salts of sodium and potassium. Thus calcium and magnesium carbonates easily part with carbonic anhydride when ignited; the nitrates are also very easily decomposed by heat, calcium and magnesium oxides, CaO and MgO , being left behind. The chlorides of magnesium and calcium, when heated with water, evolve hydrogen chloride, forming the corresponding hydroxides, and when ignited the oxide itself. All these points already evince a weakening of the alkaline properties.

These metals have been termed *the metals of the alkaline earths*, because they, like the alkali metals, form energetic bases. They are called *alkaline earths* because they are met with in nature in a state of combination, forming the insoluble mass of the earth, and because as oxides, RO , they themselves have an earthy appearance. Not a few salts are known of these metals which are insoluble in water, whilst the corresponding salts of the alkali metals are generally soluble—for example, the carbonates, phosphates, borates, and other salts of the alkaline earth metals are nearly insoluble. This serves to distinguish the metals of the alkaline earths from the metals of the alkalis. For this purpose a solution of ammonium carbonate is added to a mixed solution of salts of both metals, when by a double decomposition the insoluble carbonates of the metals of the alkaline earths are formed and pass into a precipitate, whilst the metals of the alkalis remain in solution: $\text{RX}_2 + \text{Na}_2\text{CO}_3 = \text{RCO}_3 + 2\text{NaX}$.

We may here remark that the oxides of the metals of the alkaline earths are frequently called by special names: MgO is called magnesia or bitter earth; CaO , lime; SrO , strontia; and BaO , baryta.

In the primary rocks the oxides of calcium and magnesium are combined with silica, sometimes in variable quantities, so that in some cases the lime predominates and in other cases the magnesium. Both oxides, being analogous to each other, replace each other in equivalent quantities. The various forms of *augite*, *hornblende* or *amphibole*, and of similar minerals, which enter into the composition of nearly all rocks,

contain lime and magnesia and silica. The majority of the primary rocks also contain alumina, potash, and soda. These rocks, under the action of water (containing carbonic acid) and air, give up lime and magnesia to the water, and therefore they are contained in all kinds of water, and especially sea water. *The carbonates, CaCO_3 and MgCO_3 , frequently met with in nature, are soluble in an excess of water saturated with carbonic anhydride,*¹⁰ and therefore many natural waters contain these salts, and are able to yield them when evaporated. However, one kilogram of water saturated with carbonic anhydride does not dissolve more than three grams of calcium carbonate. By gradually expelling the carbonic anhydride from such water, an insoluble precipitate of calcium carbonate separates out. It may confidently be stated that the formation of the very widely distributed strata of calcium and magnesium carbonates was of this nature, because these strata are of a sedimentary character—that is, that which would be exhibited by a gradually accumulating deposit on the bottom of the sea. Furthermore, the remains of sea organisms, plants, ferns, &c., are frequently found amongst these deposits. These deposits of calcium and magnesium carbonates are the most important sources of these metals. Lime generally predominates, because it is present in rocks and stream water in greater quantity than magnesia, and in this case these sedimentary rocks are termed *limestone*. Some common flagstones used for paving, &c., and chalk may be taken as examples of this kind of formation. Those limestones in which a considerable portion of the calcium is replaced by magnesium are termed *dolomites*. The dolomites are distinguished by their hardness, and by their not parting with the whole of their carbonic anhydride so easily as the limestones under the action of acids. Dolomites¹¹ sometimes contain an equal number of molecules of calcium carbonate and magnesium carbonate, and they also sometimes appear in a crystalline form, which is easily understood, because calcium carbonate itself is exceedingly common in this form in nature, and is then known as *calc spar*, whilst natural

¹⁰ Sodium carbonate and other carbonates of the alkalis give acid salts which are less soluble than the normal; here, on the contrary, with an excess of carbonic anhydride, a salt is formed which is more soluble than the normal, but this acid salt is more unstable than sodium hydrogen carbonate, NaHCO_3 .

¹¹ The formation of dolomite may be explained, if only we imagine that a solution of a magnesium salt acts on calcium carbonate. Magnesium carbonate may be formed by double decomposition, and it must be supposed that this process is able to cease at a certain limit (Chapter XII.), when we shall obtain a mixture of the carbonates of calcium and magnesium. Haitinger heated a mixture of calcium carbonate, CaCO_3 , with a solution of an equivalent quantity of magnesium sulphate, MgSO_4 , in a closed tube at 200° , and then a portion of the magnesia actually passed into the state of magnesium carbonate, MgCO_3 , and a portion of the lime was converted into gypsum, CaSO_4 .

crystalline magnesium carbonate is termed *magnesite*. The formation of the crystalline varieties of the insoluble carbonates is explained by the possibility of a slow deposition from solutions containing carbonic acid. Besides which the calcium and magnesium sulphates are obtained from sea water, and therefore they are met with both as deposits and in springs. It must be observed that magnesium is held in considerable quantities in sea water, because the sulphate and chloride of magnesium are very soluble in water, whilst calcium sulphate is but little soluble; and therefore if the occurrence of considerable deposits of magnesium sulphate cannot be expected in nature, still, on the other hand, one would expect (and they do actually occur) large masses of calcium sulphate or *gypsum*, $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$. Gypsum sometimes forms strata of immense size, which extend over many tens of kilometres—for example, in Russia on the Volga, and in the Donetz and Baltic provinces.

Lime and magnesia also, but in much smaller quantities (often to the amount of several fractions of a per cent. and rarely more), enter *into the composition* of every fertile soil, and without these bases the soil is unable to support vegetation. Lime is particularly important in this respect, and its presence in a larger quantity generally improves the harvest, although purely calcareous soils are generally infertile. For this reason the soil is fertilised both with lime¹² itself and with marl—that is, with clay mixed with a certain quantity of calcium carbonate, strata of which are found nearly everywhere.

From the soil the lime and magnesia (in a smaller quantity) pass into the substance of *plants*, where they occur as salts. Certain of these salts separate in the interior of plants in a crystalline form—for example, calcium oxalate. The lime occurring in plants serves as the source for the formation of the various calcareous secretions which are so common in *animals* of all classes. The bones of the highest animal orders, the shells of mollusca, the covering of the sea-urchin, and similar solid secretions of sea animals, contain calcium salts; namely, the shells mainly calcium carbonate, and bones mainly calcium phosphate. Certain limestones are almost entirely formed of such deposits. Odessa is situated on a limestone of this kind, composed of shells. Thus magnesium and calcium occur throughout the entire realm of nature.

¹² The indubitable action of lime in increasing the fertility of soils—if not in every case, at all events, with ordinary soils which have long been under corn—is based not so much on the requirements of plants for the lime itself as on those chemical and physical changes which lime produces in the soil; particularly as a powerful base which aids the alteration of the mineral and organic elements of the soil.

As lime and magnesia form bases which are in many respects analogous, they were not distinguished from each other for a long time. Magnesia was obtained for the first time in the seventeenth century from Italy, and used as a medicine; and it was only in the last century that Black, Bergmann, and others distinguished magnesia from lime.

Metallic magnesium (and calcium also) is not obtained by heating magnesium oxide or the carbonate with charcoal, as the alkali metals are obtained,¹³ but is liberated by the action of a galvanic current on fused magnesium chloride (best mixed with potassium chloride); but Davy and Bussy first obtained metallic magnesium by acting on magnesium chloride with the vapours of potassium. At the present time (Deville's process) magnesium is prepared in rather considerable quantities by a similar process, only the potassium is replaced by sodium. Anhydrous magnesium chloride, together with sodium chloride and calcium fluoride, is fused in a closed crucible. The latter substances only serve to facilitate the formation of a fusible mass before and after the reaction, which is indispensable in order to prevent the access and action of air. One part of finely-divided sodium to five parts of magnesium chloride is thrown into the strongly-heated molten mass, and after stirring the reaction proceeds very quickly, and magnesium separates, $\text{MgCl}_2 + \text{Na}_2 = \text{Mg} + 2\text{NaCl}$. In working on a large scale, the powdery metallic magnesium is then subjected to distillation at a white heat. The distillation of the magnesium is necessary, because the undistilled metal is not homogeneous¹⁴ and burns unevenly: the metal is prepared for the purpose of illumination. Magnesium

¹³ Sodium and potassium only decompose magnesium oxide at a white heat and very feebly, probably for two reasons. In the first place, because the reaction $\text{Mg} + \text{O}$ develops more heat (about 140 thousand calories) than $\text{K}_2 + \text{O}$ or $\text{Na}_2 + \text{O}$ (about 100 thousand calories); and, in the second place, because magnesia is not fusible at the heat of a furnace and cannot act on the charcoal, sodium, or potassium—that is, it does not pass into that mobile state which is necessary for reaction. The first reason alone is not sufficient to explain the absence of the reaction between charcoal and magnesia, because iron and charcoal in combining with oxygen evolve less heat than sodium or potassium, yet, nevertheless, they can displace them. With respect to magnesium chloride, it acts on sodium and potassium, not only because their combination with chlorine evolves more heat than the combination of chlorine and magnesium ($\text{Mg} + \text{Cl}_2$ gives 150 and $\text{Na}_2 + \text{Cl}_2$ about 195 thousand calories), but also because a fusion, both of the magnesium chloride and of the double salt, takes place under the action of heat. It is probable, however, that a reverse reaction will take place.

¹⁴ Commercial magnesium generally contains a certain amount of magnesium nitride (Deville and Caron), Mg_3N_2 —that is, a product of substitution of ammonia which is directly formed when magnesium is heated in nitrogen. It is yellowish green powder, which gives ammonia and magnesia with water, and cyanogen when heated with carbonic anhydride. Perfectly pure magnesium may be obtained by the action of a galvanic current.

is a white metal, like silver ; it is not soft like the alkali metals, but is, on the contrary, hard like the majority of the ordinary metals. This is natural from the fact that it melts at a rather high temperature—namely, about 500° —and boils at about 1000° . It is malleable and ductile, like the generality of metals, so that it can be drawn into wires and rolled into ribbon ; it is most frequently used for lighting purposes in the latter form. Unlike the alkali metals, magnesium does not decompose the atmospheric moisture at the ordinary temperature, so that it is almost unacted on by air ; it is not even acted on by water at the ordinary temperature, so that it may be washed to free it from sodium chloride. Magnesium only decomposes water with the evolution of hydrogen at the boiling point of water,¹⁵ and especially at still higher temperatures ; but even this is accomplished with difficulty. This is explained by the fact that in decomposing water magnesium forms an insoluble hydroxide, MgH_2O_2 , which covers the metal and hinders the further action of the water. Magnesium easily displaces hydrogen from acids, forming magnesium salts. When ignited it *burns*, not only in oxygen but in air (and even in carbonic anhydride), forming a white powder of magnesium oxide, or magnesia ; in burning it emits a white and exceedingly *brilliant light*. The strength of this light naturally depends on the fact that magnesium (24 parts by weight) in burning evolves about 140 thousand heat units, and that the product of combustion, MgO , is infusible by heat ; and therefore the vapour of the burning magnesium will contain an ignited powder of non-volatile and infusible magnesia, and will consequently present all the conditions for the production of a brilliant light. The light emitted by burning magnesium contains many rays which act chemically, and are situated in the violet and ultra-violet parts of the spectrum. For this reason burning magnesium may be employed for taking photographic images.¹⁶

Owing to its great affinity for oxygen, magnesium *reduces* many metals (zinc, iron, bismuth, antimony, cadmium, tin, lead, copper, silver, and others) from solutions of their salts at the ordinary temperature,¹⁷

¹⁵ Hydrogen peroxide (Welsing) dissolves magnesium. The reaction has not been investigated.

¹⁶ A special form of apparatus is used for burning magnesium. It is a clockwork arrangement in which a cylinder rotates, round which a ribbon or wire of magnesium is wound. The wire is subjected to a uniform unwinding and burning as the cylinder rotates, and in this manner the combustion may continue uniform for a certain time. The same is attained in special lumps, by causing a mixture of sand and finely-divided magnesium to fall from a funnel-shaped reservoir on to the flame. In photography it is best to blow finely-divided magnesium into a colourless (spirit or gas) flame.

¹⁷ According to the observations of Maack, Comaille, Büttger, and others. The reduction by heat mentioned further on was pointed out by Geuther, Phipson, Parkinson and Gattermann.

and at a red heat finely-divided magnesium takes up the oxygen from silica, alumina, boric anhydride, &c.; so that silicon and similar elements may be obtained by directly heating a mixture of powdered silica and magnesium in an infusible glass tube.¹⁸ Magnesium acts on fused potassium and sodium hydroxides, with an energetic evolution of hydrogen.

The affinity of magnesium for the halogens is much more feeble than for oxygen,¹⁹ as is already evident from the fact that a solution of iodine reacts feebly on magnesium; still magnesium burns in the vapours of iodine, bromine, and chlorine. The character of magnesium is also determined by the fact that all its salts, especially in the presence of water, are decomposable at a comparatively moderate temperature, the elements of the acid being evolved, and the magnesium oxide, which is non-volatile and unchangeable by heat, remaining behind. This naturally refers to those acids which are themselves volatilised by heat. Even magnesium sulphate is completely decomposed at the temperature at which iron melts, oxide of magnesium remaining behind. This decomposition of magnesium salts by heat proceeds much more easily than with calcium salts. For example, magnesium carbonate is totally decomposed at 170°, magnesium oxide being left behind. This *magnesia*, or *magnesium oxide*, is met with both in an anhydrous and hydrated state in nature (the anhydrous magnesia as the mineral *periclase*, MgO , and the hydrated magnesia as *brucite*, MgH_2O_2). Magnesia is a well-known medicine (calcined magnesia—*magnesia usta*). It is a white, extremely fine, and very voluminous powder, of specific gravity 3.4; it is infusible by heat, and only shrinks or sinters in an oxyhydrogen flame. After long contact the anhydrous magnesia combines with water, although very slowly, forming the hydroxide $\text{Mg}(\text{HO})_2$, which, however, parts with its water with great ease when heated even below a red heat, and again yields anhydrous magnesia. This hydroxide is obtained directly as a gelatinous amorphous substance when a soluble alkali is mixed with a solution of any magnesium salt, $\text{MgCl}_2 + 2\text{KHO} = \text{Mg}(\text{HO})_2 + 2\text{KCl}$. This decomposition proceeds to the end, and nearly all the magnesium passes into the precipitate; and this clearly shows the almost perfect insolubility of magnesia in water. Water dissolves a scarcely per-

¹⁸ This action of metallic magnesium in all probability depends, although only partially (see Note 13), on its volatility, and on the fact that, in combining with a given quantity of oxygen, it evolves more heat than aluminium, silicon, potassium, and other elements.

¹⁹ Davy, on heating magnesia in chlorine, observed a complete substitution, because the volume of oxygen was half the volume of chlorine; it is probable, however, that owing to the formation of chlorine oxide (Chapter XI. Note 30) the decomposition is not complete and is limited by a reverse reaction if the mass of the oxygen have no effect.

ceptible quantity of magnesium hydroxide—namely, one part is dissolved by 55000 parts of water. Such a solution, however, has an alkaline reaction, and gives, with a salt of phosphoric acid, a precipitate of magnesium phosphate, which is still more insoluble. Magnesia is not only dissolved by acids, forming salts, but it also displaces certain other bases—for example, ammonia from ammonium salts when boiled; and the hydroxide also attracts carbonic anhydride from the air. The magnesium salts, like those of calcium, potassium, and sodium, are colourless if they are formed from colourless acids. Those which are soluble have a bitter taste, whence magnesia has been termed *bitter-earth*. In comparison to the alkalis magnesia is a feeble base, inasmuch as it forms somewhat unstable salts, easily gives basic salts, forms acid salts with difficulty, and is able to give double salts with the salts of the alkalis, which facts are proper to feeble bases, as we shall see in becoming acquainted with the different metals.

The power of magnesium salts to form double and basic salts is very frequently shown in reactions, and is specially marked as regards ammonium salts. If saturated solutions of magnesium and ammonium sulphates are mixed together, then a crystalline double salt, $\text{Mg}(\text{NH}_4)_2(\text{SO}_4)_2 \cdot 6\text{H}_2\text{O}$,²⁰ is immediately precipitated. A strong solution of ordinary ammonium carbonate dissolves magnesium oxide or carbonate, and precipitates crystals of a double salt, $\text{Mg}(\text{NH}_4)_2(\text{CO}_3)_2 \cdot 4\text{H}_2\text{O}$, from which water extracts the ammonium carbonate. With an excess of an ammonium salt the double salt passes into solution,²¹ and therefore if a solution contain a magnesium salt and an excess of an ammonium salt for instance, sal-ammoniac—then sodium carbonate will no longer precipitate magnesium carbonate. A mixture of solutions of magnesium and ammonium chlorides, on evaporation or refrigeration, gives a double salt, $\text{Mg}(\text{NH}_4)\text{Cl}_3 \cdot 6\text{H}_2\text{O}$.²²

²⁰ Even a solution of ammonium chloride gives this salt with magnesium sulphate. Its sp. gr. is 1.72; 100 parts of water at 0° dissolve 9, at 20° 17.9 parts of the anhydrous salt. At about 130° it loses all its water.

²¹ This is an example of equilibrium and of the influence of mass; the double salt is decomposed by water, but if we take a solution of that part which is formed in the decomposition then water dissolves all.

²² If an excess of ammonia be added to a solution of magnesium chloride, then only half the magnesium is separated in the precipitate, $2\text{MgCl}_2 + 2\text{NH}_4\text{OH} = \text{Mg}(\text{OH})_2 + \text{Mg} \cdot \text{NH}_4\text{Cl}_2 + \text{NH}_4\text{Cl}$. A solution of ammonium chloride reacts with magnesia, evolving ammonia and forming a solution of the same salt, $\text{MgO} + 3\text{NH}_4\text{Cl} = \text{MgNH}_4\text{Cl}_3 + \text{H}_2\text{O} + 2\text{NH}_3$.

Among the double salts of ammonium and magnesium, the phosphate, $\text{MgNH}_4\text{PO}_4 \cdot 6\text{H}_2\text{O}$, is almost insoluble in water (0.07 grams are dissolved in a litre), even in the presence of ammonia. Magnesia is very frequently precipitated as this salt from solutions in which it is held by ammonium salts. As lime is not retained in solution by the presence of

The salts of potassium, like those of ammonium, are able to enter into combination with the magnesium salts.²³ For instance, the double salt, $\text{MgKCl}_3 \cdot 6\text{H}_2\text{O}$, which is known as *carnallite*,²⁴ and occurs in the salt mines of Stassfurt, may be formed by freezing a saturated solution of potassium chloride with an excess of magnesium chloride. A saturated solution of magnesium sulphate dissolves potassium sulphate, and solid magnesium sulphate is soluble in a saturated solution of potassium sulphate. A double salt, $\text{K}_2\text{Mg}(\text{SO}_4)_2 \cdot 6\text{H}_2\text{O}$, which closely resembles the above-mentioned ammonium salt, crystallises from these solutions.²⁵

ammonia salts, but is then precipitated by sodium carbonate, &c., it is therefore very easy to separate calcium from magnesium on the basis of these properties.

²⁵ In order to see the nature and cause of the formation of double salts, it is sufficient to regard them from the aspect (although this does not embrace the whole essence of the matter) that one of the metals of such salts (for instance, potassium) easily gives acid salts, and the other (in this instance, magnesium) basic salts; the properties of distinctly basic elements predominate in the former, whilst in the latter these properties are enfeebled, and the salts formed by them bear the character of acids—for instance, the salts of aluminium or magnesium act in many cases like acids. By their mutual combination both these properties of the salts are satisfied.

²⁴ Carnallite has been mentioned in Chapter X. (Note 4) and in Chapter XIII. These deposits also contain much *kainite*, $\text{KMgCl}(\text{SO}_4) \cdot 3\text{H}_2\text{O}$ (sp. gr., 2.13; 100 parts of water dissolve 79.6 parts at 18°). This double salt contains two metals and two haloids.

²⁵ The component parts of certain double salts diffuse at different rates, and as the diffused solution contains a different proportion of the component salts than the solution taken of the double salt, it shows that such salts are decomposed by water. According to Rüchhoff, the double salts, like carnallite, $\text{MgK}_2(\text{SO}_4)_2 \cdot 6\text{H}_2\text{O}$, and the alums, all belong to this order (1888). But such salts as tartar emetic, the double oxalates, and double cyanides are not separated by diffusion, which in all probability depends both on the relative rate of the diffusion of the component salts and on the measure of affinity acting between them. Those complex states of equilibrium which exist between water, the individual salts MX and NY, and the double salt MNXY, have been already partially analysed (as will be shown hereafter) in that case when the system is heterogeneous (that is, when something separates out in a solid state from the liquid solution), but in the case of equilibria in a homogeneous liquid medium (in a solution) the phenomenon is not so clear, because it concerns that very theory of solution which cannot yet be considered as established (Chapter I. Note 9, and others). As regards the heterogeneous decomposition of double salts, it has long been known that such salts as carnallite and $\text{K}_2\text{Mg}(\text{SO}_4)_2$ give up the more soluble salt of magnesium if an insufficient quantity of water for their complete solution be taken. The complete saturation of 100 parts of water requires at 0° 14.1, at 20° 25, and at 60° 50.2 parts of the latter double salt (anhydrous), while 100 parts of water dissolve 27 parts of magnesium sulphate at 0°, 36 parts at 20°, and 55 parts at 60°, of the anhydrous salt taken.

Of all the states of equilibrium exhibited by double salts the most fully investigated as yet is the system containing water, sodium sulphate, magnesium sulphate, and their double salt, $\text{Na}_2\text{Mg}(\text{SO}_4)_2$, which crystallises with 4 and 6 mol. OH_2 . The first crystallhydrate, $\text{MgNa}_2(\text{SO}_4)_2 \cdot 4\text{H}_2\text{O}$, occurs at Stassfurt, and as a sedimentary deposit in many of the salt lakes near Astrakhan, and is therefore called *astrakhanite*. The specific gravity of the monoclinic prisms of this salt is 2.22. If this salt, in a finely-divided state, be mixed with the necessary (according to the equation) quantity of water, then the mixture solidifies like plaster of Paris into a homogeneous mass if the temperature be below 22° (Van't Hoff und Van Deventer, 1886; Bakhius Roozeboom, 1887); but if the temperature be above this *transition-point* then the water and double salt do not react

The nearest analogues of magnesium are able to give exactly similar double salts, both in crystalline form (monoclinic system) and composition; they, like this salt (*see* Chapter XV.), are easily able to (140°) part with all their water of crystallisation, and correspond with the salts of sulphuric acid, whose type may be taken as *magnesium sulphate*, MgSO_4 .²⁶ It occurs at Stassfurt as *kieserite*, $\text{MgSO}_4 \cdot \text{H}_2\text{O}$,

on each other: $\text{MgNa}_2(\text{SO}_4)_2 \cdot 4\text{H}_2\text{O} + 13\text{H}_2\text{O} = \text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O} + \text{MgSO}_4 \cdot 7\text{H}_2\text{O}$; that is, they do not solidify or give a mixture of sodium and magnesium sulphates. If a mixture (in equivalent quantities) of solutions of these salts be evaporated, and crystals of astrakhanite and of the individual salts capable of proceeding from it be added to the concentrated solution to avoid the possibility of a supersaturated solution, then at temperatures above 22° astrakhanite is exclusively formed (this is the method of its production), but at lower temperatures the individual salts are alone produced. If equivalent amounts of Glauber's salt and magnesium sulphate be mixed together in a solid state, then there is no change at temperatures below 22°, but at higher temperatures astrakhanite and water are formed. The volume corresponding with $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ in grams = 322.146 = 220.5 cubic centimetres, and of $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$ = 246.168 = 146.4; hence their mixture in equivalent quantities occupies a volume of 366.9 c.c. The volume of astrakhanite = $334/2.22 = 150.5$, and the volume of $13\text{H}_2\text{O}$ = 234, hence their sum = 380.5 c.c., and therefore it is easy to follow the formation of the astrakhanite in a suitable apparatus (a kind of thermometer containing oil and a powdered mixture of sodium and magnesium sulphates), and to see by the variation in volume that before 22° it remains unchanged, and at higher temperatures proceeds more quickly the higher the temperature. At the transition temperature the solubility of astrakhanite and of the mixture of the component salts is one and the same, whilst at higher temperatures a solution which is saturated for a mixture of the individual salts would be supersaturated for astrakhanite, and at lower temperatures the solution of astrakhanite will be supersaturated for the component salts, as has been shown with especial detail by Karsten, Diacon, and others. Roozeboom showed that there are two limits to the composition of the solutions which can exist for a double salt; these limits are respectively obtained by dissolving a mixture of the double salt with each of its component simple salts. Van't Hoff demonstrated, besides this, that the tendency towards the formation of double salts has a distinct influence on the progress of double decomposition, because at temperatures above 31° the mixture $2\text{MgSO}_4 \cdot 7\text{H}_2\text{O} + 2\text{NaCl}$ passes into $\text{MgNa}_2(\text{SO}_4)_2 \cdot 4\text{H}_2\text{O} + \text{MgCl}_2 \cdot 6\text{H}_2\text{O} + 4\text{H}_2\text{O}$, whilst below 31° there is not this double decomposition, but it proceeds in the opposite direction, as may be demonstrated by the above-described methods.

From these examples on double salts we see that there is as close a dependence between the temperature and the formation of substances as there is between the temperature and a change of state. It is a case of the conceptions of Deville concerning dissociation, but extended in the direction of the passage of a solid into a liquid. On the other hand, we here see how essential a rôle water plays in the formation of compounds, and how the affinity for water of crystallisation is essentially analogous to the affinity between salts, and hence also to the affinity of acids for bases, because the formation of double salts does not in any essential point (except the measure of affinity—that is, from a quantitative aspect) differ from the formation of salts themselves. When sodium hydroxide with nitric acid gives sodium nitrate and water the phenomenon is essentially the same as in the formation of astrakhanite from the salts $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$ and $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$. Water is disengaged in both cases, and hence the volumes are altered.

²⁶ This salt, and especially its crystallo-hydrate with $7\text{H}_2\text{O}$, is generally known as Epsom salts. It has long been used as a purgative. It is easily obtained from magnesia and sulphuric acid, and it separates on the evaporation of sea water and of many saline springs. When carbonic anhydride is obtained by the action of sulphuric acid on

and generally separates from solutions as a heptahydrated salt, $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$, and from supersaturated solutions as a hexahydrated salt, $\text{MgSO}_4 \cdot 6\text{H}_2\text{O}$; at temperatures below 0° it crystallises out as a dodecahydrated salt, $\text{MgSO}_4 \cdot 12\text{H}_2\text{O}$, and a solution of the composition $\text{MgSO}_4 \cdot 2\text{H}_2\text{O}$ completely solidifies at 5° .²⁷ Thus between water and magnesium sulphate there may exist several definite and more or less stable degrees of equilibrium, and the double salt $\text{MgSO}_4 \cdot \text{K}_2\text{SO}_4 \cdot 6\text{H}_2\text{O}$ may be regarded as one of these equilibrated systems, all the more as it contains $6\text{H}_2\text{O}$, whilst MgSO_4 is able to

magnesite, magnesium sulphate remains in solution. When dolomite—that is, a mixture of magnesium and calcium carbonates—is subjected to the action of a solution of hydrochloric acid until about half of the salt remains, then the calcium carbonate is chiefly dissolved and magnesium carbonate is left, and, by treatment with sulphuric acid, gives a solution of magnesium sulphate.

²⁷ The anhydrous salt, MgSO_4 (sp. gr., 2.61), attracts moisture (7 mol. H_2O) from moist air; when heated in steam or hydrogen chloride it gives sulphuric acid, and when heated with carbon is decomposed, according to the equation $2\text{MgSO}_4 + \text{C} = 2\text{SO}_2 + \text{CO}_2 + 2\text{MgO}$. The monohydrated salt (kieserite), $\text{MgSO}_4 \cdot \text{H}_2\text{O}$ (sp. gr., 2.56), dissolves in water with difficulty, and remains when the other crystallo-hydrates are heated to 135° . The hexahydrated salt is dimorphous. If a solution, saturated at the boiling-point, be prepared, and cooled without access of crystals of the heptahydrated salt, then $\text{MgSO}_4 \cdot 6\text{H}_2\text{O}$ crystallises out in *monoclinic* prisms (Loewel, Marignac), which are quite as unstable as the salt, $\text{NaSO}_4 \cdot 7\text{H}_2\text{O}$ (p. 509); but if prismatic crystals of the cubic system of the copper-nickel salts of the composition $\text{MSO}_4 \cdot 6\text{H}_2\text{O}$ be added, then crystals of $\text{MgSO}_4 \cdot 6\text{H}_2\text{O}$ are deposited on them as prisms of the *cubic* system (Lecoq de Boisbaudran). The common crystallo-hydrate, $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$, Epsom salts, belongs to the *rhombic* system, and is obtained by crystallisation below 30° . Its specific gravity is 1.69. In a vacuum, or at 100° , it loses $5\text{H}_2\text{O}$, at 132° $6\text{H}_2\text{O}$, and at 210° all the $7\text{H}_2\text{O}$ (Graham). If crystals of ferrous or cobaltic sulphate be placed in a saturated solution, then *hexagonal* crystals of the heptahydrated salt are formed (Lecoq de Boisbaudran); they present an unstable state of equilibrium, and soon become cloudy, probably owing to their transformation into the more stable common form. Fritzsche, by cooling saturated solutions below 0° , obtained a mixture of crystals of ice and of a dodecahydrated salt, which easily split up at temperatures above 0° . Guthrie showed that dilute solutions of magnesium sulphate, when refrigerated, separate ice until the solution attains a composition $\text{MgSO}_4 \cdot 24\text{H}_2\text{O}$, which will completely freeze into a crystallo-hydrate at -5.3° (p. 97). According to Coppet and Rüchhoff, the temperature of the formation of ice falls by 0.073° for every part by weight of the heptahydrated salt per 100 of water. This figure gives (Chapter I. Note 49) $i = 1$ for both the heptahydrated and the anhydrous salt, from which it is clearly seen that it is impossible to judge the state of combination in which a dissolved substance occurs by the temperature of the formation of ice.

The solubility of the different crystallo-hydrates of magnesium sulphate, according to Loewel, also varies, like those of sodium sulphate or carbonate (*see* Chapter XII. Notes 7 and 18). At 0° 100 parts of water dissolves 40.75 MgSO_4 in the presence of the hexahydrated salt, 34.67 MgSO_4 in the presence of the hexagonal heptahydrated salt, and only 26 parts of MgSO_4 in the presence of the ordinary heptahydrated salt—that is, solutions giving the remaining crystallo-hydrates will be supersaturated for the ordinary heptahydrated salt.

All this shows how many diverse aspects of more or less stable equilibria may exist between water and a substance dissolved in it; this has already been enlarged on in Chapter I.

Carefully purified magnesium sulphate in its aqueous solution gives, according to

combine into a most stable system with $7\text{H}_2\text{O}$; and the double salt may be considered as this crystallo-hydrate, in which one molecule of water is replaced by the molecule K_2SO_4 .²⁸

The power of forming basic salts is a very remarkable peculiarity of magnesia and other feeble bases, and especially of those corresponding with polyvalent metals. The very powerful bases corresponding with univalent metals—like potassium and sodium—do not form basic salts, and, indeed, are more prone to give acid salts, whilst magnesium easily and frequently forms basic salts, especially with feeble acids, although there are oxides—as, for example, copper and lead oxides—which still more frequently give basic salts. If a cold solution of magnesium sulphate be mixed with a solution of sodium carbonate there is formed a gelatinous precipitate of a basic salt, $\text{Mg}(\text{HO})_2, 4\text{MgCO}_3, 9\text{H}_2\text{O}$; but all the magnesia is not precipitated in this case, as a portion of it remains in solution as an acid double salt. If sodium carbonate be added to a boiling solution of magnesium sulphate there is formed a precipitate of a still more basic salt, $4\text{MgSO}_4 + 4\text{Na}_2\text{CO}_3 + 4\text{H}_2\text{O} = 4\text{Na}_2\text{SO}_4 + \text{CO}_2 + \text{Mg}(\text{OH})_2, 3\text{MgCO}_3, 3\text{H}_2\text{O}$. This basic salt forms the ordinary medicine, *magnesia* (*magnesia alba*), in the form of light porous lumps. Other basic salts are formed under certain modifications of temperature and conditions of decomposition. But the normal salt, MgCO_3 , which occurs in nature as magnesite in the form of rhombohedra of sp. gr. 3.056, cannot be obtained by such a method of precipitation. In fact the formation of the different basic salts shows the power of water to decompose the normal salt. It is possible, however, to obtain this salt by artificial means, both in an anhydrous and hydrated state. A solution of magnesium carbonate in water containing carbonic acid is taken for this purpose. The reason of this is readily understood—carbonic anhydride is one of the products of the decomposition of magnesium Sticherbakoff, an alkaline reaction with litmus, and an acid reaction with phenolphthalein.

The specific gravity of solutions of certain salts of magnesium and calcium reduced to $15^\circ/4^\circ$ (see my work cited, Chapter I. Note 19), are, if water at $4^\circ = 10000$,

$$\text{MgSO}_4 : s = 9992 + 99.89p + 0.553p^2$$

$$\text{MgCl}_2 : s = 9992 + 81.31p + 0.372p^2$$

$$\text{CaCl}_2 : s = 9992 + 80.24p + 0.476p^2$$

$$15^\circ \frac{ds}{dt} = -(1.5 + 0.12p) \text{ for } \text{CaCl}_2$$

²⁸ Graham even distinguished the last equivalent of the water of crystallisation of the heptahydrated salt as that which is replaced by other salts, pointing out that double salts like $\text{MgK}_2(\text{SO}_4)_2, 6\text{H}_2\text{O}$ lose all their water at 135° , whilst $\text{MgSO}_4, 7\text{H}_2\text{O}$ only parts with $6\text{H}_2\text{O}$. However, Pickering afterwards showed the easy decomposability of such double salts, and determined that their formation is accompanied by a small development of heat, and showed that, in general (Chapter I. Note 56), the combination of water of crystallisation is accompanied by a small development of heat.

carbonate in the presence of water. If this solution be left to evaporate spontaneously the normal salt separates in a hydrated form, but in the evaporation of a heated solution, through which a stream of carbonic anhydride is passed, the anhydrous salt is formed as a crystalline mass, which remains unaltered in the air, like the natural mineral.²⁹ The decomposing influence of water on the salts of magnesium, which is directly dependent on the feeble basic properties of magnesia,³⁰ is most clearly seen in *magnesium chloride*, MgCl_2 . This salt is contained,³¹ as we have already seen (Chapter X.), in sea water, and remains in the last mother liquors of its evaporation. On cooling a sufficiently concentrated solution, the crystallo-hydrate, $\text{MgCl}_2 \cdot 6\text{H}_2\text{O}$, separates;³² but if it be further heated (above 106°) to remove the water, then hydrochloric acid passes off together with the latter, so that there ultimately remains magnesia with a small quantity of magnesium chloride.³³ From what has been said it is evident that anhydrous magnesium chloride cannot be obtained by simple evaporation. But if sal-ammoniac or sodium chloride be added to a solution of magnesium chloride, then the evolution of hydrochloric acid does not take place, and after complete evaporation the remaining mass is entirely soluble in water. This renders it possible to obtain anhydrous

²⁹ The crystalline form of the anhydrous salt obtained in this manner is not the same as that of the natural salt. The former gives rhombohedra, like those in which calcium carbonate appears as calc spar, whilst the natural salt appears as rhombic prisms, like those sometimes presented by the same carbonate, as aragonite, which will soon be described.

³⁰ Magnesium sulphate enters into certain reactions which are proper to sulphuric acid itself. Thus, for instance, if a carefully-prepared mixture of equivalent quantities of hydrous magnesium sulphate and sodium chloride be heated to a red heat, the evolution of hydrochloric acid is observed just as in the action of sulphuric acid on common salt, $\text{MgSO}_4 + 2\text{NaCl} + \text{H}_2\text{O} = \text{Na}_2\text{SO}_4 + \text{MgO} + 2\text{HCl}$. Magnesium sulphate acts in a similar manner on nitrates, with the evolution of nitric acid. A mixture of it with common salt and manganese peroxide gives chlorine. Sulphuric acid is sometimes replaced by magnesium sulphate in galvanic batteries—for example, in the well-known Meidinger battery. In the above-mentioned reactions we see a striking example of how alike the reactions of acids and salts are, especially of salts which are formed by such feeble bases as magnesia.

³¹ As sea water contains many salts, MCl and MgX_2 , it follows, according to Berthollet's teaching, that MgCl_2 is also present.

³² As the crystallo-hydrates of the salts of sodium often contain $10\text{H}_2\text{O}$, so many of the salts of magnesium contain $6\text{H}_2\text{O}$.

³³ This decomposition is most simply defined as the result of the two reverse reactions, $\text{MgCl}_2 + \text{H}_2\text{O} = \text{MgO} + 2\text{HCl}$ and $\text{MgO} + 2\text{HCl} = \text{MgCl}_2 + \text{H}_2\text{O}$, or as a distribution between O and Cl_2 on the one hand and H_2 and Mg on the other. It is then clear that according to Berthollet's doctrine, the mass of the hydrochloric acid converts the magnesium oxide into chloride, and the mass of the water converts the magnesium chloride into oxide. The crystallo-hydrate, $\text{MgCl}_2 \cdot 6\text{H}_2\text{O}$, forms the limit of the reversibility. But an intermediate state of equilibrium may exist in the form of basic salts. On mixing ignited magnesia with a solution of magnesium chloride of specific gravity about 1.2, a solid mass is obtained which is scarcely decomposed by water at the ordinary temperature (see Zinc).

magnesium chloride from its aqueous solution. Indeed the mixture with sal-ammoniac (in excess) may be dried (the residue consists of an anhydrous double salt, $\text{MgCl}_2 \cdot 2\text{NH}_4\text{Cl}$) and then ignited (460°), when the sal-ammoniac is converted into vapour and a fused mass of anhydrous magnesium chloride remains behind. The anhydrous chloride evolves a very considerable amount of heat on the addition of water, which shows the great affinity the salt has for water.³⁴ Anhydrous magnesium chloride is not only obtained by the above method, but is also formed by the direct combination of chlorine and magnesium, and by the action of chlorine on magnesium oxide, oxygen being evolved; this proceeds still more easily *by heating magnesia with charcoal in a stream of chlorine*, when the charcoal serves to take up the oxygen. This latter method is also employed for the preparation of chlorides which are formed in an anhydrous form with still greater difficulty than magnesium chloride. Anhydrous magnesium chloride forms a colourless, transparent mass, composed of flexible crystalline plates of a pearly lustre. It fuses at low red heat (708°) into a colourless liquid, remains unchanged in a dry state, but under the action of moisture is partially decomposed even at the ordinary temperature, with formation of hydrochloric acid.

Calcium compounds in many respects present a great resemblance to magnesium compounds, but are also clearly distinguished from them by many properties.³⁵ In general calcium stands to magnesium in the same relation as potassium occupies in respect to sodium. Davy obtained metallic calcium, like potassium, as an amalgam by the action of a galvanic current; but neither charcoal nor iron decomposes calcium oxide, and even sodium decomposes calcium chloride³⁶ with difficulty. But a galvanic current easily decomposes calcium chloride, and metallic sodium somewhat easily decomposes calcium iodide when heated. As in the case of hydrogen, potassium,

³⁴ According to Thomsen, the combination of MgCl_2 with $6\text{H}_2\text{O}$ evolves 33000 calories, and its solution in an excess of water 36000 heat units.

³⁵ There are many other methods of separating calcium from magnesium besides that mentioned above (Note 22). Among them it will be sufficient to mention the behaviour of these bases toward a solution of sugar; hydrated *lime* is exceedingly *soluble in an aqueous solution of sugar*, whilst *magnesia* is little soluble. All the lime may be extracted from dolomite by burning it, slaking the mixture of oxides thus obtained, and adding a 10 p.c. solution of sugar. Carbonic anhydride precipitates calcium carbonate from this solution. The addition of sugar (molasses) to the lime used for building purposes powerfully increases the binding power of the mortar, as I have myself found. I have been told that in the East (India, Japan) the addition of sugar to cement has long been practised.

³⁶ Moreover Caron obtained an alloy of calcium and zinc by fusing calcium chloride with zinc and sodium. The zinc vaporised off from this alloy at a white heat, and calcium remained behind.

and magnesium, the affinity of iodine for calcium is feebler than that of chlorine (and oxygen), and therefore it is not astonishing that calcium iodide may be subjected to that decomposition, into which the chloride and oxide enter with difficulty.³⁷ *Metallic calcium* is of a yellow colour, and has a considerable lustre, which it preserves in dry air. Its specific gravity is 1.58. Calcium is distinguished by its great ductility; it melts at a red heat and then burns in the air with a very brilliant flame, which is easily understood from the fact that finely-divided infusible calcium oxide is formed. Judging from the fact that in burning calcium gives a very large flame, it is probable that this metal is volatile. Calcium decomposes water at the ordinary temperature, and is oxidised in moist air, but not so rapidly as sodium. In burning, calcium gives its oxide or *lime*, CaO , a substance which is familiar to every one, and of which we have already frequently had occasion to speak. This oxide is not met with in nature in a free state, because it is an energetic base which everywhere encounters acid substances, with which it forms salts. Generally it is combined with silica, or occurs as calcium carbonate or sulphate. The calcium carbonate and nitrate are decomposed, at a red heat, with the formation of lime. As a rule, the carbonate, which is so frequently met with in nature, serves as the source of the calcium oxide, both commercial and pure. When heated calcium carbonate dissociates: $\text{CaCO}_3 = \text{CaO} + \text{CO}_2$. In practice the decomposition is conducted at a bright red heat, in the presence of steam, or a current of a foreign gas, in heaps or in special kilns.³⁸

³⁷ Calcium iodide may be prepared by saturating lime with hydriodic acid. It is a very soluble salt (at 20° one part of the salt requires 0.49 parts and at 43° 0.35 parts of water for solution), is deliquescent in the air, and resembles calcium chloride in many respects. It changes but little when evaporated, and, like calcium chloride, fuses when heated, and therefore all the water may be driven off by heat. If anhydrous calcium iodide be heated with an equivalent quantity of sodium in a closely-covered iron crucible, sodium iodide and metallic calcium are formed (Lié's-Bodart). Dumas advises carrying on this reaction in a closed space under pressure.

³⁸ Kilns which act either intermittently or continuously are built for this purpose. The kilns of the first kind are filled with alternate layers of fuel and limestone; the fuel is lighted, and the heat developed by its combustion serves for decomposing the limestone. When the process is completed the kiln is allowed to cool somewhat, the lime raked out, and the same process repeated. In the continuously-acting furnaces, constructed like that shown in fig. 78, the kiln itself only contains limestone, and there are lateral hearths for burning the fuel, whose flame passes through the limestone and serves for its decomposition. Such furnaces are able to work continuously because the unburnt limestone may be charged from above, and the burnt lime raked out from below.

It is not every limestone that is suitable for the preparation of lime, because many contain impurities, especially clay, dolomite, and sand. Such limestones when burnt either partially fuse or give an impure lime, called *poor* lime in distinction from that pure lime which is obtained from purer limestone, and which is called *rich* lime. The latter quality is characterised by its disintegrating into a fine powder when treated with water, and is suitable for the majority of uses to which lime is applied, and for which

Calcium oxide—that is, quicklime—is a substance (sp. gr. 3.15)

the poor lime is sometimes quite unfit. However, certain kinds of poor lime (as we shall see in the chapter on silicon) are used in the preparation of hydraulic limes, which solidify into a hard mass under water.

In order to obtain quite pure lime it is necessary to take the purest possible materials. In the laboratory, marble or shells are used for this purpose as a pure form of calcium carbonate. They are first burnt in a furnace, and then put in a crucible and




FIG. 78.—Continuously-acting kiln for burning lime. The lime is charged from above and calcined by four lateral grates, R, M. D, fire-bars. B, space for withdrawing the burnt lime. K, stoke-house. M, fire-grate. Q, R, under grate.

moistened with a small quantity of water, and then again strongly ignited, by which means a purer lime is obtained. Pure lime may be more rapidly prepared by taking calcium nitrate, CaN_2O_6 , which is easily obtained by dissolving limestone in nitric acid. The solution obtained is boiled with a small quantity of lime in order to precipitate the foreign oxides which are insoluble in water. The oxides of iron, aluminium, &c., are precipitated by this means. The salt is then crystallised and ignited: $\text{CaN}_2\text{O}_6 = \text{CaO} + 2\text{NO}_2 + \text{O}$.

In the decomposition of calcium carbonate the lime preserves the form of the lumps, subjected to ignition; this is one of the signs distinguishing quicklime when it is freshly

which is unaffected by heat,³⁹ and may therefore serve as a fire-resisting material, and was employed by Deville for the construction of furnaces in which platinum was melted, and silver volatilised by the action of the heat evolved by the combustion of detonating gas. The hydrated lime, slaked lime, or calcium hydroxide, CaH_2O_2 (sp. gr. 2·07) is a most common alkaline substance, which is employed largely in building for making mortars or cements, in which case its binding property is mainly due to the absorption of carbonic anhydride.⁴⁰ Lime, like other alkalis, acts on many animal and vegetable substances, and for this reason has many practical uses—for example, for removing fats, and in agriculture for accelerating the decomposition of organic substances in the so-called *composts* or accumulations of vegetable and animal remains used for fertilising land. Calcium hydroxide easily loses its water at a moderate heat (530°), but it does not part with water at 100° . When mixed with water lime forms a pasty mass, which is known as *slaked lime*, and in a more dilute form as *milk of lime*, because when shaken up in water

burnt and unaltered by air. It attracts moisture from the air and then disintegrates into a powder; if left long exposed in the air it also attracts carbonic anhydride and increases in volume; it does not entirely pass into carbonate, but forms a compound of the latter with caustic lime.

³⁹ Lime, when heated to a white heat in the vapour of potassium, gives calcium, and in chlorine it disengages oxygen. Sulphur, phosphorus, &c., when heated with lime, are absorbed by it.

⁴⁰ The greater quantity of lime is used in making mortar for binding bricks or stones together, in the form of *lime* or *cement*, or the so-called *slaked lime*. For this purpose the lime is mixed with water and sand, which serves to separate the particles of lime from each other. If only lime paste were put between two bricks they would not hold firmly together, because after the water had evaporated the lime would occupy a smaller space than before, and therefore cracks and powder would form in its mass, so that it would not at all produce that complete cementation of the bricks which it is desired to attain. Pieces of stone—that is, sand—mixed with the lime hinder this process of disintegration, because the lime binds together the individual grains of sand mixed with it, and forms one concrete mass, in consequence of a process which proceeds after the desiccation or removal of the water. The process of the solidification of lime, taken as slaked lime, consists first in the direct evaporation of the water and crystallisation of the hydrate, so that the lime binds the stones and sand mixed with it, just as glue binds two pieces of wood. But this preliminary binding action of lime is feeble (as is seen by direct experiment) unless there be further alteration of the lime leading to the formation of carbonates, silicates, and other salts of calcium which are distinguished by their great cohesion. With the progress of time the cement is partially subjected to the action of the carbonic anhydride in the air, owing to which calcium carbonate is formed, but not more than half the lime is thus converted into carbonate. Besides which, the lime partially acts on the silica of the bricks, and it is owing to these new combinations simultaneously forming in the cement that it gradually becomes stronger and stronger. Hence the binding action of the lime becomes stronger with the progress of time. This is the reason (and not, as is sometimes said, because the ancients knew how to build stronger than we) why buildings which have stood for centuries possess a very strongly binding cement. Hydraulic cements will be described in the chapter on silicon.

it remains suspended in it for a long time, and gives it the appearance of a milky liquid. But, besides this, lime is directly soluble in water, not to any considerable extent, but still in such a quantity that *lime water* is precipitated by carbonic anhydride, and has clearly distinguishable alkaline properties. One part of lime requires at the ordinary temperature about 800 parts of water for solution. At 100° it requires about 1500 parts of water, and therefore lime-water becomes cloudy when boiled. If lime-water be evaporated in a vacuum, then calcium hydroxide separates in six-sided crystals.⁴¹ If lime-water be mixed with hydrogen peroxide then minute crystals of *calcium peroxide*, $\text{CaO}_2 \cdot 8\text{H}_2\text{O}$, separate; this compound is very unstable and, like barium peroxide, is decomposed by heat. Lime, as a powerful base, combines with all acids, and in this respect presents a transition from the true alkalis to magnesia. Many of the salts of calcium (the carbonate, phosphate, borate, and oxalate) are insoluble in water; besides which the sulphate is only sparingly soluble in water. As a more energetic base than magnesia, lime forms salts, CaX_2 , which are distinguished by their constancy in comparison with the salts, MgX_2 ; neither does lime so easily form basic and double salts as magnesia.

Just as oxygen does not combine with hydrogen unless aided by a rise of temperature, so also *lime does not absorb dry carbonic anhydride at the ordinary temperature*. This was already known by Scheele, and Prof. Schuliachenko showed that there is no absorption even at 360° . It only proceeds at a red heat,⁴² and then the absorption only leads to

⁴¹ Professor Glinka measured the transparent bright crystals of calcium hydroxide which are formed in common hydraulic (Portland) cement.

⁴² The act of heating brings the substance into that state of internal movement which is required for reaction. One would think that by the act of heating not only is the bond between the parts, or cohesion of the molecules, altered (generally diminished), not only is the movement or store of energy of the whole molecule increased, but also that in all probability the very movement of the atoms in molecules undergoes a change. The same kind of change is accomplished by the act of solution, or of combination in general, judging from the fact that a dissolved or combined substance—for instance, lime with water—reacts on carbonic anhydride as it does under the action of heat. For the comprehension of chemical phenomena it is exceedingly useful to clearly see this parallelism. Rose's observation on the formation (by the slow diffusion of solutions of calcium chloride and sodium carbonate) of aragonite from dilute, and of calc spar from strong, solutions, is easily understood from this point of view. As aragonite is always formed from hot solutions, therefore dilution with water acts like heat. The following experiment of Kuhlmann is particularly instructive in this sense. Anhydrous (perfectly dry) barium oxide does not react with monohydrated sulphuric acid, H_2SO_4 (containing neither free water nor anhydride, SO_3). But directly an incandescent object or a moist substance is brought into contact with the mixture a violent reaction immediately begins (it is essentially the same as combustion), and the whole mass reacts.

The influence of solution on the process of reaction is instructively illustrated by the

the formation of a mixture of calcium oxide and carbonate (Rose). But if the lime be slaked or taken in solution, then the absorption of carbonic anhydride proceeds rapidly and to the end. These phenomena are connected with the *dissociation of calcium carbonate*, studied by Debray (1867) under the influence of the conceptions of dissociation introduced into science by Henri Sainte-Claire Deville. Just as there is no vapour tension for non-volatile substances, so there is no dissociation tension of carbonic anhydride for calcium carbonate at the ordinary temperature. Just as every volatile substance has a maximum possible vapour tension for every temperature, so also calcium carbonate has its corresponding *dissociation tension*; thus at 770° (the boiling point of cadmium) about 85 mm. (of the mercury column), and at 930° (the boiling point of Zn) it is about 520 mm. As, if the tension be greater, there will be no evaporation, so also there will be no decomposition. Debray took crystals of calc spar, and could not observe the least change in them at the boiling point of zinc (930°) in an atmosphere of carbonic anhydride taken at the atmospheric pressure (760 mm.), whilst, on the other hand, calcium carbonate may be completely decomposed at a much lower temperature if the tension of the carbonic anhydride be less than the dissociation tension, which may be arrived at either by directly pumping away the gas with an air-pump, or by mixing it with some other gas—that is, by diminishing the partial pressure of the carbonic anhydride,⁴³ just as an object may be dried at the ordinary temperature by removing the aqueous vapour or by carrying it off in a stream of another gas. Thus it is possible to obtain calcium carbonate from lime and carbonic anhydride at a certain temperature above that at which dissociation begins, and conversely to decompose calcium carbonate at the same temperature into lime and carbonic anhydride.⁴⁴

following experiment. Lime, or barium oxide, is placed in a flask or retort having an upper orifice and connected with a tube immersed in mercury. A funnel furnished with a stopcock and filled with water is fixed into the upper orifice of the retort, which is then filled with dry carbonic anhydride. There is no absorption. When the temperature of equilibrium is arrived at, the unslaked oxide is made to absorb all the carbonic anhydride by carefully letting in water. A vacuum is formed, as is seen by the mercury rising up the neck of the retort. With water the absorption goes on to the end, whilst under the action of heat there remains the dissociating tension of the carbonic anhydride. Furthermore, we here see that, with a certain resemblance, there is also a distinction, depending on the fact that at low temperatures calcium carbonate does not dissociate; this determines the complete absorption of the carbonic anhydride in the aqueous solution.

⁴³ Experience has long shown that by moistening partially-burnt lime with water and re-heating it, it is easy to drive off the last traces of carbonic anhydride from it, and that, in general, by blowing air or steam through the lime, and even by using moist fuel, it is possible to accelerate the decomposition of the calcium carbonate. The partial pressure is decreased by these means.

⁴⁴ Before Deville's conception of dissociation, the *modus operandi* of decompo-

At the ordinary temperature the reaction of the first order (combination) cannot proceed because the second (decomposition, dissociation)

sitions like that under consideration was understood in the sense that decomposition starts at a certain temperature, that it is accelerated by a rise of temperature, but it was not considered possible that combination could proceed at the same temperature as that at which decomposition goes on. Berthollet and Deville introduced the conception of equilibrium into chemical science, and elucidated the question of reversible reactions. Naturally the subject is yet far from being clear—the questions of the rate and completeness of reaction, of contact, &c., still intrude themselves—but an important step has been made in chemical mechanics, and it has been made in this direction thanks to the working out of many data in the sense indicated by the doctrines of Berthollet and Deville. Besides Deville himself, the French chemists Debray, Troost, Lemoine, Hautefeuille, Le Chatelier, and others have done much in working out the problems touching on dissociation.

In order to show the exact resemblance between the phenomena of evaporation and dissociation, it will be enough to mention that the amount of heat absorbed by a dissociating substance may be calculated according to the law of the variation of dissociation-pressure, in exactly the same manner as it is possible to calculate the latent heat of the evaporation of water, knowing the variation of the tension with the temperature, on the basis of the second law of the mechanical theory of heat. This dependence may be expressed by the equation: $424L = T \left(\frac{1}{d} - \frac{1}{D} \right) \frac{d(p)}{d(t)}$, where L is the latent heat of evaporation, 424 the mechanical equivalent of heat, T the absolute temperature of transformation, $T = 273 + t$, d the weight of a cubic measure of the substance before, and D after, the transformation into vapour; and therefore $1/d - 1/D$ is the *change of volume* proceeding in the transformation, and lastly $d(p)/Dd(t)$ is the product of the pressure by the temperature, or the variation of tension (expressed in units of weight and length) divided by the variation of temperature. In the case of steam, taking the metre and kilogram as units, we find, according to the data given in Chapter I., that when $t = 100^\circ$ —that is, when $T = 373^\circ$ —the change of volume is 1.652 (because one cubic metre of steam at 100° weighs 0.605 kilo., whilst a cubic metre of water at 100° weighs 960 kilo.). The magnitude of the product for steam at 100° is found from the fact that vapour tension of steam at 100° varies by 27 mm. of the mercury column for a variation of 1° temperature. Hence the magnitude of the variation of pressure in kilograms per square metre $= 0.027 \times 13596 = 367$. Hence the magnitude of the right-hand side of the equation is $373 \times 1.652 \times 367 = 226144$; and the other side of the equation is $536 \times 424 = 227264$. That is, both parts are equal within the limits of accuracy of the data, and therefore the quantity of heat, L , expended in evaporation is determined from the variation of tension and density. It is the same with dissociation. As an example we will cite the data obtained by Troost and Hautefeuille for the hydrides of potassium and sodium, t being the temperature, and h the dissociation pressure corresponding with it in millimetres of the mercury column—

t	$= 330^\circ$	340°	350°	360°	400°	430
K_2H, h	$= 45$	58	72	98	548	1100
Na_2H, h	$= 28$	40	57	75	447	910

Hence it follows that in the case of K_2H the rise of pressure per degree at about 350° is approximately equal to 2 mm. of the mercury column, or the product $= 27$ kilo. per square metre. The magnitude of the variation of volume is found from the fact that the weight of a cubic metre of hydrogen at 350° and 72 mm. pressure $= 0.0037$ kilo. Hence the variation of volume is nearly 270. As $t = 350^\circ$, therefore $T = 623$, and therefore we find the magnitude of L from the equation to be nearly 10000 calories—that is, judging from the variation of the dissociation pressure of potassium hydride, there is developed in its formation about 10000 calories per gram of hydrogen combined. This figure has

cannot take place, and thus all the most important phenomena with respect to the behaviour of lime towards carbonic anhydride are explained by starting from one common basis.⁴⁵

Calcium carbonate, CaCO_3 —which occurs, as has already been mentioned, in limestone, marble, &c.—is sometimes met with in nature in a crystalline form, and it forms an example of the phenomenon termed *dimorphism*—that is, it appears in two crystalline forms. When it exhibits combinations of forms belonging to the hexagonal system (six-sided prisms, rhombohedra, &c.) it is called *calc spar*. Calc spar has a specific gravity of 2·7, and is further characterised by a distinct cleavage along the planes of the fundamental rhombohedron having an angle of 105° . Perfectly transparent Iceland spar presents a clear example of double refraction (for which reason it is frequently

not been verified by experiment, nor has the calculated figure of 13 calories for the formation of sodium hydride, Na_2H , at 300 been verified; but the figure of 4·1 calories calculated (20°) by Moutier from Troost's data for the dissociation pressure of palladium hydride, entirely agrees with the direct results of Favre, which showed that each gram of hydrogen which combines with palladium at the ordinary temperature develops 4·174 calories, and therefore *one and the same conception* of the mechanical theory of heat is applicable to dissociation and evaporation. The heat evolved in the absorption of hydrogen depends, naturally, not only on the physical process of the condensation of the gas, but also on the formation of a new chemical compound, as is seen from the fact that different metals in absorbing a gram of hydrogen develop a different amount of heat—namely, palladium 4 calories, potassium 10 calories, sodium 13 calories, platinum 20 calories—and therefore in the concordance of calculation with fact we should see, not an identity, but only a resemblance between the phenomena of dissociation and evaporation.

⁴⁵ But still the question as to the formation of a basic calcium carbonate remains undecided. According to certain data one would think that, with a rise of temperature, not only calcium carbonate but also a basic salt may be formed, which, however, is denied by certain investigators. Probably the presence of water complicates all the relations between lime and carbonic anhydride, all the more as the existence of an attraction between calcium carbonate and water is seen from its being able to give a *crystallohydrate*, $\text{CaCO}_3 \cdot 5\text{H}_2\text{O}$ (Pelouze, Salm-Horstmar), which crystallises in rhombic prisms of sp. gr. about 1·77 and loses its water at 20° . These crystals are obtained when a solution of lime in sugar and water is left long exposed to the air and slowly attracts carbonic anhydride from it, and also by the evaporation of such a solution at a temperature of about 3° . On the other hand, it is probable that an *acid salt* $\text{CaH}_2(\text{CO}_3)_2$ is formed in an aqueous solution, not only because water containing carbonic acid dissolves calcium carbonate, but more especially judging by the researches of Schloesing (1872), which showed that at 16° a litre of water in an atmosphere of carbonic anhydride (pressure 0·984 atmosphere) dissolves 1·086 grams of calcium carbonate and 1·778 grams of carbonic anhydride, which corresponds with the formation of calcium hydrogen carbonate, and the solution of carbonic anhydride in the remaining water. Caro showed that a litre of water is able to dissolve as much as 3 grams of calcium carbonate if the pressure be increased to 4 and more atmospheres. The calcium carbonate is precipitated when the carbonic anhydride passes off in the air or in a current of another gas; this also takes place in many natural springs. Tufa, stalactites, and other like formations from waters containing calcium carbonate and carbonic acid in solution, are formed in this manner. The solubility of calcium carbonate itself at the ordinary temperature does not exceed 13 milligrams per litre of water.

employed in physical apparatus). The other form of calcium carbonate occurs in crystals belonging to the rhombic system, and it is then called *aragonite*; its specific gravity is 3.0. If calcium carbonate is artificially produced by slow crystallisation at the ordinary temperature, then it appears in the rhombohedral form, but if the crystallisation be aided by heat then it appears as aragonite. One may suppose, therefore, that calc spar presents the form corresponding with a low temperature, and aragonite with a higher temperature during crystallisation.⁴⁶

Calcium sulphate in combination with two equivalents of water, $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$, is very widely distributed in nature, and is known as *gypsum*. Gypsum loses its two equivalents of water at a moderate temperature,⁴⁷ and anhydrous or burnt gypsum is then obtained, which is also known as plaster of Paris, and is employed in large quantities for modelling.⁴⁸ This use depends on the fact that burnt and finely-divided and sifted gypsum forms a paste when mixed with water; after a certain time this paste becomes slightly heated and solidifies, owing to the fact that the anhydrous calcium sulphate, CaSO_4 , again combines with water. When the plaster of Paris and water are first made into a paste they form a mechanical mixture, but when the mass

⁴⁶ When calcium carbonate separates out from solutions, it at first has a gelatinous appearance, which leads one to think that this salt appears in a colloidal state. It only crystallises with the progress of time. The colloidal state of calcium carbonate is particularly clear from the following observations made by Prof. Famintsin, who showed that when it separates from solutions it is obtained under certain conditions in the form of grains having the peculiar paste-like structure proper to starch, which fact has not only an independent interest, but presents an example of a mineral substance being obtained in a form until then only known in the organic substances elaborated in plants. This shows that the forms (cells, vessels, &c.) in which vegetable and animal substances occur in organisms do not present in themselves anything peculiar to organisms, but are only the result of those particular conditions in which these substances are formed. Traube and afterwards Monnier and Vogt (1882) obtained formations which, under the microscope, were in every respect identical in appearance with vegetable cells, by means of a similar slow formation of precipitates (by reacting on sulphates of different metals with sodium silicate or carbonate). Owing to its insolubility in water, calcium carbonate may be easily obtained from any other soluble calcium salt by the addition of a solution of an alkali carbonate; for example, ammonium carbonate.

⁴⁷ According to Le Chatelier (1888), $1\frac{1}{2}\text{H}_2\text{O}$ is lost at 120° —that is, $\text{H}_2\text{O} \cdot 2\text{CaSO}_4$ is formed, but at 194° all the water is expelled. According to Shenstone and Cundall (1888) gypsum begins to lose water at 70° in dry air. The semi-hydrated compound, $\text{H}_2\text{O} \cdot 2\text{CaSO}_4$, is also formed when gypsum is heated with water in a closed vessel at 150° (Hoppe-Seyler).

⁴⁸ For stucco-work it is usual to add lime and sand, as the mass is then harder and does not solidify so quickly. For imitating marble, glue is added to the plaster, and the mass is polished when thoroughly dry. Reburnt gypsum cannot be used over again, as that which has once solidified is, like the natural anhydride, not able to re-combine with water. It is evident that the structure of the molecules in the crystallised mass, or in general in any dense mass, exerts an influence on the chemical action, as is particularly clearly seen in metals in their different forms (powder, crystalline, rolled, &c.).

solidifies, then a compound of the calcium sulphate with two molecules of water is produced; and this may be regarded as derived from S(OH)_6 by the substitution of two atoms of hydrogen by one atom of bivalent calcium. Natural gypsum sometimes appears as perfectly colourless, or variegated marble-like, masses, and sometimes in perfectly colourless crystals, *selenite*, of sp. gr. 2.33. The semi-transparent gypsum, or *alabaster*, is often carved into small statues. Besides which an anhydrous calcium sulphate, CaSO_4 , called *anhydrite* (sp. gr. 2.97), occurs in nature. It sometimes occurs along with gypsum. It is no longer capable of combining directly with water, and differs in this respect from the anhydrous salt obtained by gently igniting gypsum. If gypsum be very strongly heated it shrinks and loses its power of combining with water. Gypsum also passes into anhydrite if it be heated in water, if the temperature be as high as 150° . One part of calcium sulphate requires at 0° 525 parts of water for solution, at 38° 466 parts, and at 100° 517 parts of water. The maximum solubility, which is at about 36° , is nearly the same as that of sodium sulphate.⁴⁹

As lime is a more energetic base than magnesia, so *calcium chloride*, CaCl_2 , is not so easily decomposed by water, and its solutions only disengage a small quantity of hydrochloric acid when evaporated, and when the evaporation is conducted in a stream of hydrochloric acid it easily gives an anhydrous salt which fuses at 719° ; otherwise an aqueous solution yields a crystallo-hydrate, $\text{CaCl}_2 \cdot 6\text{H}_2\text{O}$, which melts at 28° .⁵⁰

⁴⁹ As Marignac showed, gypsum especially desiccated at 120° easily gives supersaturated solutions with respect to $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$, which contain as much as 1 part of CaSO_4 to 110 parts of water. Boiling dilute hydrochloric acid dissolves gypsum, forming calcium chloride. The behaviour of gypsum towards the alkali carbonates has been described in Chap. X. Alcohol precipitates gypsum from its aqueous solutions, because, like the sulphates in general, it is sparingly soluble in alcohol. Gypsum, like all the sulphates, when heated with charcoal, gives up its oxygen, forming the sulphide, CaS .

Calcium sulphate, like magnesium sulphate, is capable of forming double salts, but with difficulty, and they are chemically less stable. They contain, as is always the case with double salts, less water of crystallisation than the component salts. Rose, Phillips, Schott, Stchefarovitch, Struvé, Ditte, and others obtained the salt $\text{CaK}_2(\text{SO}_4)_2 \cdot 2\text{H}_2\text{O}$; a mixture of gypsum with an equivalent amount of potassium sulphate and water solidifies into a homogeneous mass. Fritzsche obtained the corresponding sodium salt in a hydrated and anhydrous state, by heating a mixture of gypsum with a saturated solution of sodium sulphate. The anhydrous salt occurs in nature as *glauverite*. Fritzsche also obtained *gaylussite*, $\text{Na}_2\text{Ca}(\text{CO}_3)_2 \cdot 5\text{H}_2\text{O}$, by pouring a saturated solution of sodium carbonate over freshly-precipitated calcium carbonate.

⁵⁰ Calcium chloride has a specific gravity 2.20, or, when fused, 2.12, and the sp. gr. of the crystallised salt $\text{CaCl}_2 \cdot 6\text{H}_2\text{O}$ is 1.69. If the volume of the crystals at $0^\circ = 1$, then at 29° it is 1.020, and the volume of the fused mass at the same temperature is 1.118 (Kopp) (specific gravity of solutions, see Note 27). The solution containing 50 p.c. CaCl_2 boils at 130 , 70 p.c. at 158° . Superheated steam decomposes calcium chloride with more diffi-

As for potassium, $K=39$ (and sodium, $Na=23$), there are the near analogues, $Rb=85$ and $Cs=133$, and also another, $Li=7$, so in exactly the same manner for calcium, $Ca=40$ (and magnesium, $Mg=24$), there is another analogue of lighter atomic weight, or beryllium, $Be=9$, besides the near analogues, strontium, $Sr=87$, and barium, $Ba=137$. As rubidium and caesium are more rarely met with in nature than potassium, so also strontium and barium are rarer

cultly than magnesium chloride and with greater ease than barium chloride (Kuhnheim). Sodium does not decompose fused calcium chloride even with further heating (Lié-Bodart), but an alloy of sodium with zinc, lead, or bismuth decomposes it, forming an alloy of calcium with one of the above-named metals (Caron). The zinc alloy may be obtained with as much as 15 p.c. of calcium. Calcium chloride is soluble in alcohol and absorbs ammonia.

A molecular gram weight of calcium chloride in dissolving in an excess of water evolves 18723 calories, and in dissolving in alcohol 17555 units of heat, according to Pickering.

Roozeboom made detailed researches on the crystallo-hydrates of calcium chloride (1889), and found that $CaCl_2 \cdot 6H_2O$ melts at $30 \cdot 2^\circ$, and is formed at low temperatures from solutions containing not more than 103 parts of calcium chloride per 100 parts of water; if the amount of salt (always to 100 parts of water) reaches 120 parts, then tabular crystals of $CaCl_2 \cdot 4H_2O\beta$ are formed, which at temperatures above $38 \cdot 4^\circ$ are converted into the crystallo-hydrates $CaCl_2 \cdot 2H_2O$, whilst at temperatures below 18° the variety β passes into the more stable $CaCl_2 \cdot 4H_2O\alpha$, which process is aided by mechanical friction. Hence, as is the case with magnesium sulphate (Note 27), one and the same crystallo-hydrate appears in two forms—the β , which easily forms, but does not keep and is unstable, and the other, α , which is stable. The solubility of the above-mentioned hydrates of chloride of calcium, or amount of calcium chloride per 100 parts of water, is as follows:—

	0°	20°	30°	40°	60°
$CaCl_2 \cdot 6H_2O$	60	75	100	(102·8)	
$CaCl_2 \cdot 4H_2O\alpha$	—	90	101	117	(154·2)
$CaCl_2 \cdot 4H_2O\beta$	—	104	114	—	
$CaCl_2 \cdot 2H_2O$	—	—	(308·3)	128	137

The amount of calcium chloride to 100 parts of water in the crystallo-hydrate given in brackets. The point of intersection of the curves of solubility lies at about 30° for the first two salts and about 45° for the salts with $4H_2O$ and $2H_2O$. The crystals $CaCl_2 \cdot 2H_2O$ may, however, be obtained (Ditte) at the ordinary temperature from solutions containing hydrochloric acid. The vapour tension of this crystallo-hydrate equals the atmospheric at 165° , and therefore the crystals may be dried in an atmosphere of steam and obtained without a mother liquor, whose vapour tension is greater. This crystallo-hydrate decomposes at about 175° into $CaCl_2 \cdot H_2O$ and a solution; this is easily brought about in a closed vessel when the pressure is greater than the atmosphere. This crystallo-hydrate is destroyed at temperatures above 260° , anhydrous calcium chloride being formed.

On the other hand, Hammerl showed that solutions of calcium chloride, when frozen, deposit ice if they contain less than 48 parts of salt per 100 of water, and if more the crystallo-hydrate $CaCl_2 \cdot 6H_2O$ separates, and that a solution of the above composition ($CaCl_2 \cdot 14H_2O$ requires 44·0 parts calcium chloride per 100 of water) solidifies as a cryo-hydrate at about -55° . Thus the solubility of calcium chloride is better known than that of any other salt.

Neglecting the unstable equilibrium $CaCl_2 \cdot 4H_2O\beta$, we will cite the temperatures t at which the passage of one hydrate into another takes place and at which the solution $CaCl_2 + nH_2O$, the two solids A and B and aqueous vapour, whose tension is given as p

than calcium (as also bromine and iodine are rarer than chlorine). Whilst exhibiting many points of resemblance with calcium, strontium and barium may be characterised after a very short acquaintance with their chief compounds; this shows the important advantages gained by distributing the elements according to their natural groups, to which matter we shall turn our attention in the next chapter.

Among the compounds of barium met with in nature the commonest is the *sulphate*, BaSO_4 , which forms anhydrous crystals of the rhombic system, which are identical in their crystalline form with anhydrite, and which generally occur as transparent and semi-transparent masses of tabular crystals having a high specific gravity, namely 4.45, for which reason this salt bears the name of *heavy spar* or *barytes*. Analogous to it is *celestine*, SrSO_4 , which is, however, more rarely met with; heavy spar frequently forms the gangue separated on dressing metallic ores from the vein stuff. This mineral is the source of all other barium compounds, because the carbonate, although more easily transformed into the other compounds (because acids act directly on it, evolving carbonic anhydride), is, however, a comparatively rare mineral (BaCO_3 forms the mineral *witherite*; SrCO_3 , *strontianite*; both are rare, the latter is found at Etna). The treatment of barium sulphate is rendered difficult from the fact that it is insoluble both in water and acids, and has therefore to be conducted by a method of reduction.⁵¹ Like sodium sulphate and calcium sulphate, heavy spar when heated with charcoal parts with its oxygen and forms barium sulphide, BaS . For this purpose a pasty mixture of powdered heavy spar, charcoal, and tar is subjected to the action of a strong heat, in which case $\text{BaSO}_4 + 4\text{C} = \text{BaS} + 4\text{CO}$. The residue is then treated with water, in which the barium sulphide is soluble.⁵² When boiled with hydrochloric

in millimetres, are able to exist together in stable equilibrium, according to Roozeboom's determinations—

t	n	A	B	p
-55°	14.5	ice	$\text{CaCl}_2, 6\text{H}_2\text{O}$	0
$+29.8^\circ$	6.1	$\text{CaCl}_2, 6\text{H}_2\text{O}$	$\text{CaCl}_2, 4\text{H}_2\text{O}$	6.8
45.3°	4.7	$\text{CaCl}_2, 4\text{H}_2\text{O}$	$\text{CaCl}_2, 2\text{H}_2\text{O}$	11.8
175.5°	2.1	$\text{CaCl}_2, 2\text{H}_2\text{O}$	$\text{CaCl}_2, \text{H}_2\text{O}$	842
260°	1.8	$\text{CaCl}_2, \text{H}_2\text{O}$	CaCl_2	Several atmospheres.

Solutions of calcium chloride may serve as a convenient example for the study of the supersaturated state, which easily comes about in this case, because different hydrates are formed. Thus at 25° solutions containing more than 83 parts of anhydrous calcium chloride per 100 of water will be supersaturated for the hydrate $\text{CaCl}_2, 6\text{H}_2\text{O}$.

⁵¹ The action of barium sulphate on sodium and potassium carbonates is given on p. 427.

⁵² Barium sulphide is decomposed by water, $\text{BaS} + 2\text{H}_2\text{O} = \text{H}_2\text{S} + \text{Ba}(\text{OH})_2$ (the reaction is reversible), but both substances are soluble in water, and their separation is complicated by the fact that barium sulphide absorbs oxygen and gives insoluble barium

acid, barium chloride, BaCl_2 , is obtained in solution, and the sulphur is disengaged as gaseous sulphuretted hydrogen, $\text{BaS} + 2\text{HCl} = \text{BaCl}_2 + \text{H}_2\text{S}$. In this manner barium sulphate is converted into barium chloride,⁵³ and the latter by double decomposition with strong nitric acid or nitre gives the less soluble barium nitrate, $\text{Ba}(\text{NO}_3)_2$,⁵⁴ or with sodium

sulphate. The hydrogen sulphide is sometimes removed from the solution by boiling with the oxides of copper or zinc. If sugar be added to a solution of barium sulphide, then on heating barium saccharate is precipitated; it is decomposed by carbonic anhydride, so that barium carbonate is formed. An equivalent mixture of sodium sulphate with barium or strontium sulphates when ignited with charcoal gives a mixture of sodium sulphide and barium or strontium sulphide, and if this mixture be dissolved in water and the solution evaporated, then barium or strontium hydroxide crystallises out on cooling, and sodium hydrosulphide, NaHS , is obtained in solution. The hydroxides BaH_2O_2 and SrH_2O_2 are prepared on a large scale, being applied to many reactions; for example, strontium hydroxide is prepared for sugar works for extracting crystallisable sugar from molasses.

We may remark that Boussingault, by igniting barium sulphate in hydrochloric acid gas, obtained a complete decomposition, with the formation of barium chloride. Attention should also be turned to the fact that Grouven by heating a mixture of charcoal and strontium sulphate with magnesium and potassium sulphates showed the easy decomposability depending on the formation of double salts, such as $\text{SrS}, \text{K}_2\text{S}$, which are easily soluble in water, and give a precipitate of strontium carbonate with carbonic anhydride. In such examples as these we see that the force which binds double salts may play a part in directing the course of reactions, and the number of double salts of silica on the earth's surface shows that nature takes advantage of these forces in her chemical processes.

⁵⁵ Barium sulphate is sometimes converted into barium chloride in the following manner: finely-ground barium sulphate is heated with coal and manganese chloride, forming the residue from the manufacture of chlorine. The mass becomes semi-liquid, and when it evolves carbonic oxide the heating is stopped. The following double decompositions proceed during this operation: first the carbon takes up the oxygen from the barium sulphate, and gives sulphide, BaS , which enters into double decomposition with the chloride of manganese, MnCl_2 , forming manganese sulphide, MnS , which is insoluble in water, and soluble barium chloride. This solution is easily obtained pure because many foreign impurities, such as iron, remain in the insoluble portion with the manganese. The solution of barium chloride obtained in this manner is chiefly used for the preparation of barium sulphate, which is precipitated by sulphuric acid, by which means *barium sulphate* is re-formed as a powder. This salt is characterised by the fact that it is unacted on by the majority of chemical reagents, is insoluble in water, and is not dissolved by acids, but is slightly acted on in an aqueous solution by the prolonged action of alkalis and of a solution of the alkali carbonates (with sodium carbonate, for instance, after prolonged boiling, the solution gives barium carbonate, Chapter X.). Owing to this, artificial barium sulphate forms a permanent white paint which is used instead of white lead. Barium white does not alter or blacken under the action of sulphuretted hydrogen, which affects white lead. Hence it has been termed 'blanc fixé' or 'permanent white.'

The solution of one part of calcium chloride at 20° requires 1.36 parts of water, the solution of one part of strontium chloride requires 1.88 parts of water at the same temperature, and the solution of barium chloride 2.88 parts of water. The solubility of the bromides and iodides varies in the same proportion. The chlorides of barium and strontium crystallise out from solution with great ease in combination with water; they form $\text{BaCl}_2 \cdot 2\text{H}_2\text{O}$ and $\text{SrCl}_2 \cdot 6\text{H}_2\text{O}$ (the latter resembles the salts of calcium and magnesium in its composition).

⁵⁴ The nitrates $\text{Sr}(\text{NO}_3)_2$ (in the cold its solutions give a crystallo-hydrate containing $4\text{H}_2\text{O}$) and $\text{Ba}(\text{NO}_3)_2$ are so very sparingly soluble in water that they separate in rather large amounts when a solution of sodium nitrate is added to strong solutions of barium

carbonate a precipitate of barium carbonate, BaCO_3 . Both these salts are able to give *barium oxide*, or *baryta*, BaO , and the hydroxide, $\text{Ba}(\text{HO})_2$, which differs from lime by its great solubility in water,⁵⁵ and by the ease with which it forms a crystallo-hydrate, $\text{BaH}_2\text{O}_2 \cdot 8\text{H}_2\text{O}$, from its solutions. Owing to its solubility, baryta is frequently employed in the manufactures and in chemical practice as an alkali which has the very important property that it may be always entirely removed from solution by the addition of sulphuric acid, which entirely separates the baryta as the insoluble sulphate, BaSO_4 . It may also be removed so long as it remains in an alkaline state (for example, the excess which may remain when it is taken for saturating acids) by means of carbonic anhydride, which also entirely precipitates barium oxide as a sparingly soluble, colourless, and powdery carbonate. Both these reactions show that baryta has such properties as would render its use in practice most widely extended were its compounds as widely distributed as those of sodium and calcium, and if its soluble compounds were not poisonous. Barium nitrate is directly decomposed by the action of heat, barium oxide being left behind. The same takes place with barium carbonate, especially that precipitated from solutions and when mixed with charcoal or ignited in an atmosphere of steam.

Barium oxide combines with water with the development of a large amount of heat, and the resultant hydroxide is so stable in its retention of the water that it will not part with it under the action of heat alone, although it entirely dissociates when strongly ignited in a current of hydrogen or other gas, and especially of air. With oxygen the

or strontium chlorides. They are obtained by the action of nitric acid on the carbonates or oxides. They may also be obtained by the action of nitric acid on solutions of the chlorides, all the more as they are comparatively little soluble, especially in water containing nitric acid—100 parts of water at 15° dissolve 6.5 parts strontium nitrate and 8.2 parts of barium nitrate, whilst more than 300 parts of calcium nitrate are soluble at the same temperature. Strontium nitrate communicates a crimson coloration to the flame of burning substances, and is therefore frequently used for Bengal fire, fireworks, and signal lights, for which purpose the salts of lithium are still better fitted. Calcium nitrate is exceedingly hygroscopic. The barium nitrate, on the contrary, does not show this property in the least degree, and in this respect it resembles potassium nitrate, and is therefore used instead of the latter for the preparation of a gunpowder which is called 'saxifragin powder' (76 parts of barium nitrate, 2 parts of nitre, and 22 parts of charcoal).

⁵⁵ The dissociation of the crystallo-hydrate of baryta is given in Chapter I. Note 65. 100 parts of water dissolve

	0°	20°	40°	60°	80°
BaO	1.5	3.5	7.4	18.8	90.8
SrO	0.3	0.7	1.4	3	9

Supersaturated solutions are easily formed.

The anhydrous oxide BaO fuses in the oxyhydrogen flame. When ignited in the vapour of potassium, the latter takes up the oxygen; whilst in chlorine the oxygen is separated and barium chloride formed.

anhydrous oxide gives, as has already been mentioned in Chapters III. and IV., a *peroxide*, BaO_2 .⁵⁶ Neither calcium nor strontium oxides are able to give such a peroxide directly, but they form peroxides under the action of hydrogen peroxide.

Barium oxide is decomposed when heated with potassium; and fused barium chloride is decomposed, as Davy showed, by the action of a galvanic current, forming metallic *barium*; and Crookes (1862) obtained an amalgam of barium from which the mercury could easily be driven off, by heating sodium amalgam in a saturated solution of barium chloride. The same occurs with strontium. Both metals are soluble in mercury, and seem to be non-volatile or at least very slightly volatile. They are both heavier than water; the sp. gr. of barium is 3.6, and of strontium 2.5. They both decompose water at the ordinary temperature, like the metals of the alkalis.

Barium and strontium as saline elements are characterised by their powerful basic properties, so that they form acid salts with difficulty, and scarcely form basic salts. On comparing them together and with calcium, it is evident that the alkaline properties in this group (as in the group potassium, rubidium, caesium) increase with the atomic weight, and this succession clearly shows itself in many of their corresponding compounds. Thus, for instance, the solubility of the hydroxides RH_2O_2 and the specific gravity⁵⁷ rise in passing from calcium to strontium and barium, while the solubility of the sulphates decreases,⁵⁸ and therefore in the case of magnesium and beryllium as metals whose atomic weights are still less, we should expect the solubility of the sulphates to be greater, and this is the case in reality.

⁵⁶ The property of barium oxide of absorbing oxygen when heated, and giving the peroxide BaO_2 , is very characteristic for this oxide. It is only proper to the anhydrous oxide. The hydroxide does not absorb oxygen. Peroxides of calcium and strontium may be obtained by means of hydrogen peroxide. Barium peroxide is insoluble in water, but is able to form a hydrate with it, and also to combine with hydrogen peroxide, forming a very unstable compound having the composition BaH_2O_4 (obtained by Professor Schöne), and which in the course of time evolves oxygen (Chapter IV. Note 21).

⁵⁷ Even in solutions a gradual progression in the increase of the specific gravity shows itself, not only for equivalent solutions (for instance, $\text{RCl}_2 + 200\text{H}_2\text{O}$), but even with an equal percentage composition, as is seen from the curves giving the specific gravity (water $4^\circ - 10000$) at 15° (for barium chloride, according to Bourdiakoff's determinations):

$$\begin{aligned}\text{BeCl}_2 : S &= 9992 + 67.21p + 0.111p^2 \\ \text{CaCl}_2 : S &= 9992 + 80.24p + 0.476p^2 \\ \text{SrCl}_2 : S &= 9992 + 85.57p + 0.733p^2 \\ \text{BaCl}_2 : S &= 9992 + 86.56p + 0.813p^2\end{aligned}$$

⁵⁸ One part of calcium sulphate at the ordinary temperature requires about 500 parts of water for solution, strontium sulphate about 7000 parts, barium sulphate about 400000 parts, whilst beryllium sulphate is easily soluble in water.


As in the series of the alkali metals we saw the metals potassium, rubidium, and caesium approaching near to each other in their properties, and besides them two metals having smaller combining weights—namely, sodium, and the lightest of all, lithium, which already exhibited certain particular characteristic properties—so also in the case of the metals of the alkaline earths we find, besides calcium, barium, and strontium, the metal magnesium and also *beryllium* or *glucinum*. In respect to the magnitude of its atomic weight, it occupies the same position in the series of the metals of the alkaline earths as lithium does in the series of the alkali metals, because the combining weight of beryllium, Be or Gl=9. This combining weight is greater than the combining weight of lithium (7), as the combining weight of magnesium (24) is greater than that of sodium (23), or of calcium (40) is greater than that of potassium (39), &c.⁵⁹ Beryllium was so named because it occurs in the mineral *beryl*. The metal is also called glucinum (from the Greek word γλυκός, 'sweet'), because its salts have a sweet taste. It occurs in beryl, aquamarine, the emerald, and other minerals, which are generally of a green colour, and sometimes occur in considerable masses, but which are as a rule comparatively rare and, as transparent crystals, form precious stones. The composition of beryl, the emerald, and smaragd is as follows: $\text{Al}_2\text{O}_3, 3\text{BeO}, 6\text{SiO}_2$. The Siberian and Brazilian beryls are the best known. The sp. gr. of beryl is about 2.7. Beryllium oxide, from the feebleness of its basic properties, presents an analogy to aluminium oxide in the same degree as lithium oxide is analogous to magnesium oxide.⁶⁰ Owing to its rare occur-

⁵⁹ We refer beryllium to the class of the bivalent metals of the alkaline earths—that is, we ascribe to its oxide the formula BeO, and do not count it as trivalent (Be = 135, p. 318), as has been proposed and argued by many. The true atomic composition of beryllium oxide was first given by the Russian chemist, Avdóeff (1819), in his researches on the compounds of this metal. He compared the compounds of beryllium to those of magnesium, and set aside the then reigning opinion of the resemblance between the oxides of beryllium and aluminium, by proving that beryllium sulphate presents a greater resemblance to magnesium sulphate than to aluminium sulphate. It was especially noticed that the analogues of alumina give alums, whilst beryllium oxide, although it is a feeble base, easily giving, like magnesium, basic and double salts, does not form true alums. The establishment of the periodic system of the elements (1869), which is considered in the following chapter, immediately showed that Avdóeff's view corresponded with the truth—that is, that beryllium is bivalent, and therefore necessitated the refutation of the trivalency of beryllium. This scientific controversy resulted in a vast series of researches (1870–80) concerning this element, and ended in Nilson and Pettersson—two of the chief advocates of the trivalency of beryllium—determining the vapour density of BeCl_2 (= 40, p. 318), which gave an undoubted proof of the bivalency of beryllium.

⁶⁰ Beryllium oxide, like aluminium oxide, is precipitated from solutions of its salts by alkalis as a gelatinous hydroxide BeH_2O_2 , which, like alumina, is soluble in an excess of caustic potash or soda. This reaction may be taken advantage of for distinguishing and separating beryllium from aluminium, because when the alkaline solution is diluted with water and boiled beryllium hydroxide is precipitated, whilst the alumina remains

rence in nature, to the absence of any especially distinct individual properties, and to the possibility of foretelling them to a certain extent on the basis of the periodic system of the elements given in the following chapter, and owing to the brevity of this treatise, we will not linger long over the compounds of beryllium, and will only observe that the individuality of the compounds of beryllium was pointed out in 1798 by Vauquelin, and that metallic beryllium was obtained by Wöhler and Bussy. Wöhler obtained *metallic beryllium* (like magnesium) by acting on beryllium chloride, BeCl_2 , with potassium. Metallic beryllium has a sp. gr. 1.64 (Nilsson and Pettersson). It is very infusible, melting at nearly the same temperature as silver, which it resembles in its white colour and lustre. It is characterised by the fact that it is very difficultly oxidised, and even in the oxidising flame of a blow-pipe is only superficially covered by a coating of oxide; it does not burn in pure oxygen, does not decompose water at the ordinary temperature or at a red heat, but gaseous hydrochloric acid is decomposed by it when slightly heated, with evolution of hydrogen and development of a considerable amount of heat. Even dilute hydrochloric acid acts in the same manner at the ordinary temperature. Beryllium also acts easily on sulphuric acid, but it is remarkable that neither dilute nor strong nitric acid acts on beryllium, which seems to

in solution. The solubility of the beryllium oxide already clearly indicates its feeble basic properties, and, as it were, separates this oxide from the class of the alkaline earths. But on arranging the oxides of the above-described metals of the alkaline earths according to their decreasing atomic weights we have the series



in which the basic properties and solubility of the oxides consecutively and distinctly decrease until we reach a point when, had we not known of the existence of the beryllium oxide, we should expect to find in its place an oxide insoluble in water and of feeble basic properties. So also in the series of the metals of the alkalis the basicity of lithium oxide is distinctly more feeble than sodium and potassium oxides, and lithium carbonate is insoluble in water.

Another characteristic of the salts of beryllium is that they give a gelatinous precipitate with aqueous ammonia, which is soluble in an excess of ammonium carbonate, like the precipitate of magnesia; in this beryllium oxide differs from the oxide of aluminium. Beryllium oxide easily forms a carbonate which is insoluble in water, and resembles magnesium carbonate in many respects. Beryllium sulphate is distinguished by its considerable solubility in water—thus, at the ordinary temperature it dissolves in an equal weight of water; it crystallises out from its solutions in well-formed crystals, which do not change in the air, and contain $\text{BeSO}_4 \cdot 4\text{H}_2\text{O}$. When ignited it leaves beryllium oxide, but this oxide, after prolonged ignition, is re-dissolved by sulphuric acid, whilst aluminium sulphate, after a similar treatment, leaves aluminium oxide, which is no longer soluble in acids. With a few exceptions, the salts of beryllium crystallise with great difficulty, and to a considerable extent resemble the salts of magnesium; thus, for instance, beryllium chloride is analogous to magnesium chloride. It is volatile in an anhydrous state, and in a hydrated state it decomposes, with the evolution of hydrochloric acid.

resist oxidising agents with particular ease. Potassium hydroxide acts on beryllium as on aluminium, hydrogen being disengaged and the metal dissolved, but ammonia has no action on it. These properties of metallic beryllium seem to isolate it from the series of the other metals described in this chapter, but if we compare the properties of calcium, magnesium, and beryllium we shall see that magnesium occupies an intermediate position between the other two. Whilst calcium decomposes water with great ease, magnesium does so with difficulty, and beryllium not at all. The peculiarities of beryllium among the metals of the alkaline earths recalls the fact that in the series of the halogens we saw that fluorine differed from the other halogens in many of its properties and has the smallest atomic weight. Just the same is the case with beryllium among the other metals of the alkaline earths.

CHAPTER XV

THE GROUPING OF THE ELEMENTS AND THE PERIODIC LAW

It is seen from the examples given in the preceding chapters that the sum of the data concerning the chemical transformations proper to the elements is insufficient for accurately judging the resemblance of the elements, inasmuch as this resemblance may be many-sided. Thus, lithium or barium are in certain respects analogous to sodium or potassium, and in others to magnesium or calcium. It is evident, therefore, that for a true judgment it is necessary to have exact and measurable indices.

Among these exactly measurable and common properties or indices of the elements, or of their corresponding compounds, belong : (a) isomorphism, or the analogy of crystalline forms, and, connected with it, the power to form crystalline mixtures which are isomorphous ; (b) the relation of the volumes of analogous compounds of the elements ; (c) the composition of their saline compounds ; and (d) the relation of the atomic weights of the elements. In this chapter we shall briefly consider these four aspects of the matter, which are exceedingly important for a right grouping of the elements, for facilitating their investigation, as well as for judging of their most important properties.

Historically the first, and an important and convincing, method for finding a resemblance between the compounds of two different elements is by *isomorphism*. This conception was introduced into chemistry by Mitscherlich (in 1820), who demonstrated that the corresponding salts of arsenic acid, H_3AsO_5 , and phosphoric acid, H_3PO_5 , crystallise with an equal quantity of water, show an exceedingly close resemblance

in crystalline form (as regards the angles of their faces and axes), and are able to crystallise together from solutions in the same crystals containing a mixture of the isomorphous compounds. Isomorphous substances are those which, with an equal number of atoms in their molecules, present an analogy in their chemical reactions, a close resemblance in their properties, and a similar or very nearly similar crystalline form; they often contain certain elements in common, from which it is concluded that the remaining (different) elements are analogous to each other. And inasmuch as crystalline forms are subject to exact measurement, therefore the external form, or the relation of the molecules which causes their grouping into crystalline forms, is seen to be as great a help for judging the internal forces acting between the atoms as a comparison of reactions, vapour densities, and other like relations. We have already seen examples of this in the preceding pages. It will be sufficient to recall to mind that the compounds of the alkali metals with the halogens RX , in a crystalline form, all belong to the cubic system and crystallise in octahedra or cubes—for example, sodium chloride, potassium chloride, potassium iodide, rubidium chloride, &c. The nitrates of rubidium and caesium appear in anhydrous crystals of the same form as potassium nitrate. The carbonates of the metals of the alkaline earths are isomorphous with calcium carbonate—that is, they either appear in forms like calc spar or in the rhombic system in crystals analogous to aragonite.¹ Furthermore, sodium nitrate crystallises in rhombohedra, closely resembling the rhombohedra of calc spar (calcium carbonate), $CaCO_3$, whilst potassium nitrate appears in the form of aragonite, $CaCO_3$, and the number of atoms in both kinds of salts is analogous; they contain one atom of a metal (K, Na, Ca), one atom of a non-metal (C, N), and three atoms of oxygen. The analogy of form evidently coincides with the analogy of atomic composition. But, as we have learnt from the previous description of these salts, there is not any close resemblance in their properties. It is evident that calcium carbonate approaches more nearly to magnesium carbonate than to sodium nitrate, although their crystalline forms are equally alike. Isomorphous substances which are perfectly analogous to each other are not only characterised by a close resemblance of forms (homeomorphism), but also by the

¹ The crystalline forms of aragonite, strontianite, and witherite belong to the rhombic system; the angle of the prism of $CaCO_3$ is $116^\circ 10'$, of $SrCO_3$ $117^\circ 19'$, and of $BaCO_3$ $118^\circ 30'$. On the other hand, the crystalline forms of calc spar, magnesite, and calamine, which resemble each other quite as closely, belong to the rhombohedral system, with the angle of the rhombohedra for $CaCO_3$ $105^\circ 8'$, $MgCO_3$ $107^\circ 10'$, and $ZnCO_3$ $107^\circ 40'$. From this comparison it is already evident that zinc is more closely allied to magnesium than magnesium to calcium.

faculty of entering into analogous reactions, which is not the case with RNO_3 and RCO_3 . The most important and direct method of judging perfect isomorphism—that is, the positive analogy of two compounds—is given by that property according to which analogous compounds are able to separate from solutions *in homogeneous crystals, containing the most varied quantitative proportions* of the analogous substances which enter into their composition. These quantities do not seem to be in dependence on the molecular or atomic weights, and if they are governed by any laws they must be analogous to those which refer to indefinite chemical compounds.² This will be clear from the following examples. Potassium chloride and potassium nitrate are not isomorphous with each other, and are in an atomic relation composed in a different manner. If these salts be mixed in a solution and the solution be evaporated, then individual crystals of each of these salts will separate in that crystalline form which is proper to each of them. The crystals will not contain a mixture of the two salts. But if we mix the solutions of two isomorphous salts together, then, under certain circumstances, crystals will be obtained which contain both these substances. However, this cannot be taken as an absolute rule. Thus, if we take a solution saturated at a high temperature with a mixture of potassium and sodium chlorides, then on evaporation sodium chloride only will separate, and on cooling only potassium chloride. The first will contain a very little potassium chloride, and the latter very little sodium chloride.³ But if we take, for example, a mixture of solutions of magnesium sulphate and of zinc sulphate, then they cannot be separated from each other by evaporating the mixture, notwithstanding the rather considerable difference in the solubility of

² Solutions form the commonest examples of indefinite chemical compounds. But the isomorphous mixtures which are so common among the crystalline compounds of silica forming the crust of the earth, as well as alloys, which are so important in the application of metals to the arts, are also instances of indefinite compounds. And if in Chapter I., and in many other portions of this work, it has been proved necessary to admit the presence of definite compounds (in a state of dissociation) in solutions, then the same refers with even greater force to isomorphous mixtures and alloys. For this reason in many places in this work I turn to facts which compel us to recognise the existence of definite chemical compounds in all isomorphous mixtures and alloys.

³ The cause of the difference which is observed in different compounds of the same type, with respect to their property of forming isomorphous mixtures, must not be looked for in the difference of their volumetric composition, as many, including Kopp, affirm. The molecular volumes (found by dividing the molecular weight by the density) of those isomorphous substances which do give intermixtures are not nearer to each other than the volumes of those which do not give mixtures; for example, for magnesium carbonate the combining weight is 84, density 3.06, and volume 27; for calcium carbonate in the form of calc spar the volume = 37, and in the form of aragonite 33; for strontium carbonate = 41, for barium carbonate = 46; that is, the volume of these closely-allied isomorphous substances increases with the combining weight. The same is observed if

these salts. Again, the isomorphous salts, magnesium carbonate and calcium carbonate, are found together—that is, in one crystal—in nature. The angle of the rhombohedron of these magnesia-lime spars is intermediate between the angles proper to both spars individually (for calcium carbonate, the angle of the rhombohedron, is $105^{\circ} 8'$; magnesium carbonate, $107^{\circ} 30'$; $\text{CaMg}(\text{CO}_3)_2$, $106^{\circ} 10'$). Certain of these *isomorphous mixtures* of calc and magnesia spars appear in well-formed crystals, and in this case there not unfrequently exists a simple molecular proportion of strictly definite chemical combination between the component salts—for instance, $\text{CaCO}_3, \text{MgCO}_3$ —whilst in other cases, especially in the absence of distinct crystallisation (in dolomites), no such simple molecular proportion is observable; this is also the case in many artificially prepared isomorphous mixtures. The microscopical researches (and optical, especially those as regards the rotation of the plane of polarisation) of Professor Inostrantzoff and others, show that in many cases there is really a mechanical, although microscopically minute, juxtaposition in one whole of the heterogeneous crystals of calcium carbonate (double refracting) and of the compound CaMgC_2O_6 . If we suppose the adjacent parts to be microscopically small (on the basis of the researches of Mallard, Wernhoff, and others), we obtain an idea of isomorphous mixtures. A formula of the following kind is given to isomorphous mixtures: for instance, for spars, RCO_3 , where $\text{R} = \text{Mg}, \text{Ca}$, and where it may be $\text{Fe}, \text{Mn} \dots$, &c. This means that the Ca is partially replaced by Mg or another metal. Alums form a common example of the separation of isomorphous mixtures from solutions. They are double sulphates (or seleniates) of alumina (or oxides isomorphous with it) and the alkalis, which crystallise in well-formed crystals. If aluminium sulphate be mixed with potassium sulphate, then an alum separates, having the composition $\text{KAlS}_2\text{O}_8, 12\text{H}_2\text{O}$. If sodium sulphate or ammonium sulphate, or rubidium (or thallium) sulphate, be used, we obtain alums having the composition $\text{RAlS}_2\text{O}_8, 12\text{H}_2\text{O}$. They all not only crystallise in the cubic system, but also contain an equal atomic quantity of water of crystallisation ($12\text{H}_2\text{O}$). Besides which, if we mix solutions of the potassium and ammonium ($\text{NH}_4\text{AlS}_2\text{O}_8, 12\text{H}_2\text{O}$) alums together, then the crystals

we compare sodium chloride (molecular volume = 27) with potassium chloride (volume = 37), or sodium sulphate (volume = 55) with potassium sulphate (volume = 66), or sodium nitrate = 39 with potassium nitrate = 48, although the latter are less capable of giving isomorphous mixtures than the former. It is evident that the cause of isomorphism cannot be explained by an approximation in molecular volumes. It is more likely that, given a similarity in form and composition, the faculty to give isomorphous mixtures is connected with the laws and degree of solubility.

which separate will contain different proportions of the alkalis taken, and separate crystals of the alums of one or the other kind will not be obtained, but each separate crystal will contain both potassium and ammonium. Nor is this all ; if we take a crystal of a potassium alum and immerse it in a solution capable of yielding ammonia alum, then the crystal of the potash alum will continue to grow and increase in size in this solution—that is, a layer of the ammonia or other alum will deposit itself upon the planes bounding the crystal of the potash alum. This is very distinctly seen if a colourless crystal of a common alum be immersed in a saturated violet solution of chrome alum, $\text{KCrS}_2\text{O}_8, 12\text{H}_2\text{O}$, which then deposits itself in a violet layer over the colourless crystal of the alumina alum, as was observed even before Mitscherlich noticed it. If this crystal be then immersed in a solution of an alumina alum, a layer of this salt will form over the layer of chrome alum, so that one alum is able to incite the growth of the other. If the deposition proceed simultaneously, the resultant intermixture may be minute and indivisible, but its nature is understood from the preceding experiments ; the attractive force of crystallisation of isomorphous substances is so nearly equal that the attractive power of an isomorphous substance induces a crystalline superstructure exactly the same as the attractive force of like crystalline particles. From this it is evident that one isomorphous substance may *induce the crystallisation* ⁴ of another. Such a phenomenon explains, on the one hand, the aggregation of different isomorphous substances in one crystal, whilst, on the other hand, it serves as a most exact indication of the nearness both of the molecular composition of isomorphous substances and of those forces which are proper to the elements which distinguish the isomorphous substances. Thus, for example, ferrous sulphate or green vitriol crystallises in the monoclinic system and contains seven molecules of water, $\text{FeSO}_4, 7\text{H}_2\text{O}$, whilst copper vitriol crystallises with five molecules of water in the triclinic system, $\text{CuSO}_4, 5\text{H}_2\text{O}$; nevertheless, it may be easily proved that both salts are perfectly isomorphous, that they are able to appear in identically the same forms and with an equal molecular amount of water. For instance, Marignac, by evaporating a mixture of sulphuric acid and ferrous sulphate under the receiver of an air-pump, first obtained crystals of the hepta-hydrated salt and then of the penta-hydrated salt $\text{FeSO}_4, 5\text{H}_2\text{O}$, which were perfectly similar to the crystals of copper sulphate. Furthermore, Lecoq de Boisbaudran, by immersing crystals of $\text{FeSO}_4, 7\text{H}_2\text{O}$ in a supersaturated solution of copper sulphate,

⁴ A phenomenon of a like kind is shown for magnesium sulphate in Note 27 of the last chapter. In the same example we see what a complication the phenomena of dimorphism may introduce into the matter of comparing the forms of analogous compounds.

caused the latter to deposit in the same form as ferrous sulphate, in crystals of the monoclinic system, $\text{CuSO}_4 \cdot 7\text{H}_2\text{O}$.

Hence it is evident that isomorphism—that is, the analogy of forms and the faculty to provoke crystallisation—may serve as a means for the discovery of analogies in molecular composition. We will take an example in order to render this clear. If, instead of aluminium sulphate, we add magnesium sulphate to potassium sulphate, then, on evaporating the solution, the double salt $\text{K}_2\text{MgS}_2\text{O}_8 \cdot 6\text{H}_2\text{O}$ separates instead of an alum, and in it the ratio of the component parts (in alums one atom of potassium per 2SO_4 , and here two atoms) and the amount of water of crystallisation (in alums 12 and here 6 equivalents per 2SO_4) are quite different from what they are in alums; nor is this double salt in any way isomorphous with the alums, or capable of forming an isomorphous crystalline mixture with them, nor does the one salt provoke the crystallisation of the other. From this we must conclude that although alumina and magnesia, or aluminium and magnesium, resemble each other, they are not isomorphous, and that, although they give partially similar double salts, these salts are not analogous to each other. And this is expressed in their chemical formulæ by the fact that the number of atoms in alumina or aluminium oxide, Al_2O_3 , is different from the number in magnesia, MgO . Aluminium is trivalent and magnesium bivalent. Thus, having obtained a double salt from a given metal, it is possible to judge of the analogy of the given metal with aluminium or with magnesium, or of the absence of such an analogy, from the composition and form of this salt. Thus zinc, for example, does not form alums, but forms a double salt with potassium sulphate, which has a composition exactly like that of the corresponding salt of magnesium. It is often possible to distinguish the bivalent metals analogous to magnesium or calcium from the trivalent metals, like aluminium, by a similar method. Furthermore, the specific heat and vapour density serve as guides. There are also indirect proofs. Thus iron gives ferrous compounds, FeX_2 , which are isomorphous with the compounds of magnesium, and ferric compounds, FeX_3 , which are isomorphous with the compounds of aluminium; and, in this instance, the relative composition is directly determined by analysis, because, for a given amount of iron, FeCl_2 only contains two-thirds of the amount of chlorine which occurs in FeCl_3 .

Thus in the building up of like molecules in crystalline forms we see one of the numerous means for judging of the internal world of molecules and atoms, and one of the weapons for conquests in the invisible world of molecular mechanics which forms the main object of

physico-chemical knowledge. This weapon⁵ has more than once been employed for discovering the analogy of elements and of their compounds.

⁵ The property of solids of occurring in regular crystalline forms—the occurrence of many substances in the earth's crust in these forms—and those geometrical and simple laws which govern the formation of crystals, have long ago attracted the attention of the naturalist to crystals. The crystalline form is, without doubt, the expression of the relation in which the atoms occur in the molecules, and the molecules in the mass of a substance. Crystallisation is determined by the distribution of the molecules along the direction of the greatest cohesion, and therefore those forces must take part in the crystalline distribution of matter which act between the molecules: and, as they depend on the forces binding the atoms together in the molecules, therefore a very close connection must exist between the atomic composition and the distribution of the atoms in the molecule on the one hand, and with the crystalline forms of substances on the other hand, and hence an insight into the composition may be arrived at from the crystalline form. Such is the elementary and *a priori* idea which lies at the base of all researches into the *connection between composition and crystalline form*. Haüy, in 1811, established the following fundamental law, which has been worked out by later investigators: That the fundamental crystalline form for a given chemical compound is constant (varies only in combinations), and that with a change of composition the crystalline form also changes, naturally with the exception of such limiting forms as the cube, regular octahedron, &c., which may belong to various substances of the regular system. The fundamental form is determined by the angles of certain fundamental forms (prisms, pyramids, rhombohedra), or the ratio of the crystalline axis, and is connected with the optical and many other properties of crystals. Since the establishment of this law the description of definite compounds in a solid state is accompanied by a description (measurement) of its crystals, which forms an invariable, distinct, and measurable index. The most important epochs in the further history of this question were formed by the following discoveries:—Klaproth, Vauquelin, and others showed that aragonite has the same composition as calc spar, whilst the former belongs to the rhombic and the latter to the hexagonal system. Haüy at first considered that the composition, and after that the structure, of the atoms in the molecules was different. But at present no difference in the reactions of the two varieties of calcium carbonate is known, although it cannot be positively stated that none exists (very few researches have been made in this direction). Beudant, Frankenheim, Laurent, and others found that the forms of the two nitrates, KNO_3 and NaNO_3 , exactly correspond with the forms of aragonite and calc spar; that they are able, moreover, to pass from one form into another, and that the difference of the forms is accompanied by a small alteration of the angles, because the angle of the prisms of potassium nitrate and aragonite is 119° and of sodium nitrate and calc spar, 120° ; and therefore dimorphism, or the crystallisation of one substance in different forms, does not essentially provoke a great alteration in the distribution of the molecules, although it clearly exists. The researches of Mitscherlich (1822) on the dimorphism of sulphur confirmed this conclusion, although it cannot yet be affirmed that in dimorphism the arrangement of the atoms remains unaltered, and that only the molecules are distributed differently. Leblanc, Berthier, Wollaston, and others, already knew that many substances of different composition appear in the same forms, and crystallise together in one crystal. Gay-Lussac (1816) showed that crystals of potash alum continue to grow in a solution of ammonia alum. Beudant (1817) explained this phenomenon by the *assimilation* of a foreign substance by a substance having a great force of crystallisation, which he confirmed by many natural and artificial examples. But Mitscherlich, and afterwards Berzelius and Henry Rose and others, showed that such an assimilation only exists with a similarity or nearness of the forms of the individual substances, and with a certain degree of chemical analogy. Thus was established the idea of *isomorphism*, as an analogy of forms by reason of a resemblance of atomic composition,

The regularity and simplicity expressed by the exact laws of crystalline form repeat themselves in the aggregation of the atoms to form molecules. Here, as there, there are but few forms which are essen-

and by it was explained the variability of the composition of a number of minerals as isomorphous mixtures. Thus all the garnets are expressed by the general formula: $(\text{RO})_3\text{M}_2\text{O}_5(\text{SiO}_2)_5$, where $\text{R} = \text{Ca, Mg, Fe, Mn}$, and $\text{M} = \text{Fe, Al}$, and where we may have either R and M separately, or their equivalent compounds, or their mixtures in all possible proportions.

But other facts, which render the correlation of form and composition still more complex, have accumulated side by side with a mass of data which may be accounted for by admitting the conceptions of isomorphism and dimorphism. Foremost among the former stand the phenomena of *homeomorphism*—that is, a nearness of forms with a difference of composition—and then the cases of polymorphism and hemimorphism—that is, a nearness of the fundamental forms or only of certain angles for substances which are near or analogous in their composition. Instances of homeomorphism are very numerous. Many, however, may be reduced to a resemblance of atomic composition, although they do not correspond to an isomorphism of the component elements; for example, CdS (greenockite) and AgI , CaCO_3 (aragonite) and KNO_3 , CaCO_3 and NaNO_3 , BaSO_4 (heavy spar), KMnO_4 (potassium permanganate), and KClO_4 (potassium perchlorate), Al_2O_3 (corundum) and FeTiO_3 (titanic iron ore), FeS_2 (marcasite, rhombic system) and FeSAs (arsenical pyrites), NiS and NiAs , &c. But besides these instances there are homeomorphous substances with an absolute dissimilarity of composition. Many such instances were pointed out by Dana. Cinnabar, HgS , and susannite, $\text{PbSO}_4 \cdot 3\text{PbCO}_3$, appear in very analogous crystalline forms; the acid potassium sulphate crystallises in the monoclinic system in crystals analogous to feldspar, KAlSi_3O_8 ; glauberite, $\text{Na}_2\text{Ca}(\text{SO}_4)_2$, augite, RSiO_5 ($\text{R} = \text{Ca, Mg}$), sodium carbonate, $\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O}$, glauber salt, $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$, and borax $\text{Na}_2\text{B}_4\text{O}_7 \cdot 10\text{H}_2\text{O}$, not only belong to the same system (monoclinic) but exhibit an analogy of combinations and a nearness of corresponding angles. These and many other similar cases might appear to be perfectly arbitrary (especially as a *nearness* of angles and fundamental forms is a relative idea) were there not other cases where a resemblance of properties and a distinct relation in the variation of composition is connected with a resemblance of form. Thus, for example, alumina, Al_2O_3 , and water, H_2O , are frequently found in many pyroxenes and amphiboles which only contain silica and magnesia (MgO , CaO , FeO , MnO). Scheerer and Hermann, and many others, endeavoured to explain such instances by *polymeric isomorphism*, stating that MgO may be replaced by $3\text{H}_2\text{O}$ (for example, olivine and serpentine), SiO_2 by Al_2O_3 (in the amphiboles, talcs), and so on. A certain number of the instances of this order are subject to doubt, because many of the natural minerals which served as the basis for the establishment of polymeric isomorphism in all probability no longer present their original composition but one which has been altered under the influence of solutions which have come into contact with them, and which therefore belong to the class of *pseudomorphs*, or false crystals. There is, however, no doubt of the existence of a whole series of natural and artificial homeomorphs, which differ from each other by atomic amounts of water, silicas, and some other components parts. Thus, Thomsen (1874) showed a very striking instance. The metallic chlorides, RCl_2 , often crystallise with water, and then they do not contain less than one molecule of water per atom of chlorine. The most familiar representative of the order $\text{RCl}_2 \cdot 2\text{H}_2\text{O}$ is $\text{BaCl}_2 \cdot 2\text{H}_2\text{O}$, which crystallises in the rhombic system. Barium bromide, $\text{BaBr}_2 \cdot 2\text{H}_2\text{O}$, and copper chloride, $\text{CuCl}_2 \cdot 2\text{H}_2\text{O}$, have nearly the same forms; potassium iodate, KIO_4 ; potassium chlorate, KClO_4 ; potassium permanganate, KMnO_4 ; barium sulphate, BaSO_4 ; calcium sulphate, CaSO_4 ; sodium sulphate, Na_2SO_4 ; barium formate, $\text{BaC}_2\text{H}_3\text{O}_4$, and others, have almost the same crystalline form (of the rhombic system). Parallel to this series is that of the metallic chlorides containing $\text{RCl}_2 \cdot 4\text{H}_2\text{O}$, of the sulphates of the composition $\text{RSO}_4 \cdot 2\text{H}_2\text{O}$, and the formates $\text{RC}_2\text{H}_3\text{O}_4 \cdot 2\text{H}_2\text{O}$. These compounds belong to the monoclinic system, have a close resemblance of form, and

tially different, and their observed diversity reduces itself into a few fundamental differences. There, the molecules aggregate themselves

differ from the first series by containing two more molecules of water. The addition of two more molecules of water in all the above series also gives forms of the monoclinic system closely resembling each other; for example, $\text{NiCl}_2 \cdot 6\text{H}_2\text{O}$ and $\text{MnSO}_4 \cdot 4\text{H}_2\text{O}$. Hence we see that not only is $\text{RCl}_2 \cdot 2\text{H}_2\text{O}$ analogous in form to RSO_4 and $\text{RC}_2\text{H}_2\text{O}_4$, but that their compounds with $2\text{H}_2\text{O}$ and with $4\text{H}_2\text{O}$ also exhibit closely analogous forms. If we take away the elements R and O₂ common to all these compounds, it appears that the form remains unchanged, with the substitution of Cl_2H_2 by SO_2 and $\text{C}_2\text{H}_2\text{O}_2$. An example of homeomorphism among the chlorides is also seen in the close resemblance of the forms of the hexagonal hydrated chlorides of calcium and strontium, and of the double chlorides. Thus, in $\text{CaCl}_2 \cdot 6\text{H}_2\text{O}$ and $\text{SrCl}_2 \cdot 6\text{H}_2\text{O}$ the ratio of the vertical to the horizontal axis is as 0.496 : 1, and as 0.508 : 1, and the angle of the rhombohedra = $129^\circ 1'$ and $128^\circ 2'$; and in such compounds as $\text{NiPtCl}_6 \cdot 6\text{H}_2\text{O}$, $\text{MgSnF}_6 \cdot 6\text{H}_2\text{O}$, $\text{ZnSnF}_6 \cdot \text{H}_2\text{O}$, &c., the ratio of the axes is from 0.508 to 0.519 : 1, and the angle of the rhombohedra from 127° to $128^\circ 17'$. From these examples it is evident that the conditions which determine a given form may be repeated not only in the presence of an isomorphous exchange—that is, with an equal number of atoms in the molecule—but also in the presence of an unequal number when there are peculiar and as yet ungeneralised relations in composition. Thus, ZnO and Al_2O_3 exhibit a close analogy of form. Both oxides belong to the rhombohedral system, and the angle between the pyramid and the terminal plane of the first is $118^\circ 7'$ and of the second $118^\circ 49'$. Alumina, Al_2O_3 , is also analogous in form to SiO_2 , and we shall see that these analogies of form are conjoined with a certain analogy in properties. It is not surprising, therefore, that in the complex molecule of a siliceous compound it is sometimes possible to replace SiO_2 by means of Al_2O_3 , as Scheerer admits. The oxides Cu_2O , MgO , NiO , Fe_3O_4 , CeO_2 , crystallise in the regular system, although they are of very different atomic structure. Marignac demonstrated the perfect analogy of the forms of K_2ZrF_6 and CaCO_3 , and the former is even dimorphous, like the calcium carbonate. The same salt is isomorphous with R_2NbOF_5 and $\text{R}_2\text{WO}_2\text{F}_4$, where R is an alkali metal. There is an equivalency between CaCO_3 and K_2ZrF_6 , because K₂ is equivalent to Ca, C to Zr, and F₆ to O₃, and with the isomorphism of the other two salts we find besides an equal contents of the alkali metal—an equal number of atoms on the one hand and an analogy to the properties of K_2ZrF_6 on the other. The long-known isomorphism of the corresponding compounds of potassium and ammonium, KX and NH_4X , may be taken as the simplest example of the fact that an analogy of form shows itself with an analogy of chemical reaction even without an equality in atomic composition. Therefore the ultimate progress of the entire doctrine of the correlation of composition and crystalline forms will only be arrived at with the accumulation of a sufficient number of facts collected on a plan corresponding with the problems which here present themselves. The first steps have already been made. The researches of the Geneva savant, Marignac, on the crystalline form and composition of many of the double fluorides, and the work of Wyruboff on the ferricyanides and other compounds, are particularly important in this respect. It is already evident that, with a definite change of composition, certain angles remain constant, notwithstanding that others are subject to a great alteration. Such an instance of the relation of forms was observed by Laurent, and named *hemimorphism* (an anomalous term) by him when the analogy is limited to certain angles, and *paramorphism* when the forms in general approach each other but belong to different systems. So, for example, the angle of the planes of a rhombohedra may be greater or less than 90° , and therefore such acute and obtuse rhombohedra may approach very near to the cube. Hausmannite, Mn_5O_4 , belongs to the tetragonal system, and the planes of its pyramid are inclined at an angle of about 118° , whilst magnetic iron ore, Fe_7O_4 , which resembles hausmannite in many respects, appears in regular octahedra—that is, pyramidal planes are inclined at an angle of $109^\circ 28'$. This is an example of paramorphism: the systems are different, the composi-

into crystalline forms; here, the atoms aggregate themselves into molecular forms or into *the types of compounds*. Here as there, the fundamental crystalline or molecular forms are liable to variations, conjunctions, and combinations. If we know that potassium gives compounds of the fundamental type KX , where X is a univalent element (which combines with one atom of hydrogen, and is, according to the law of substitution, able to replace it), then we know the composition of its compounds: K_2O , KHO , KCl , NH_2K , KNO_3 , K_2SO_4 , $KHSO_4$, $K_2Mg(SO_4)_2$, $6H_2O$, &c. All the possible derivative crystalline forms are not known. So also all the atomic combinations are not known for every element. In the case of potassium, KCH_3 , K_3P , K_4Pt , and other like compounds which exist for hydrogen or chlorine, are unknown.

Only a few fundamental types exist for the building up of atoms into molecules, and the majority of them are already known to us. If X stand for a univalent element, and R for an element combined with it, then eight atomic types may be observed—



Let X be chlorine or hydrogen. Then as examples of the first type we have: H_2 , Cl_2 , HCl , KCl , $NaCl$, &c. The compounds of oxygen or calcium may serve as examples of the type RX_2 : OH_2 , OCl_2 , $OHCl$,

tions are analogous, and there is a certain resemblance in form. Hemimorphism has been found in many instances of saline and other substitutions. Thus, Laurent demonstrated, and Hintze confirmed (1873), that naphthalene derivatives of analogous composition are hemimorphous. Nicklès (1849) showed that in ethylene sulphate the angle of the prism is $125^\circ 26'$, and in the nitrate of the same radicle $126^\circ 95'$. The angle of the prism of methylamine oxalate is $131^\circ 20'$, and of fluoride, which is very different in composition from the former, the angle is 132° . Groth (1870) endeavoured to indicate in general what kinds of change of form proceeds with the substitution of hydrogen by various other elements and groups, and he observed a regularity which he termed *morphotropy*. The following examples show that morphotropy recalls the hemimorphism of Laurent. Benzene, C_6H_6 , rhombic system, ratio of axis $0.891 : 1 : 0.799$. Phenol $C_6H_5(OH)$, and resorcinol, $C_6H_4(OH)_2$, also rhombic system, but the ratio of one axis is changed—thus, in resorcinol, $0.910 : 1 : 0.540$; that is, a portion of the crystalline structure in one direction is the same, but in the other direction it is changed, whilst in the rhombic system dinitrophenol, $C_6H_3(NO_2)_2(OH) = 0.833 : 1 : 0.753$; trinitrophenol (picric acid), $C_6H_2(NO_2)_3(OH) = 0.937 : 1 : 0.974$; and the potassium salt $= 0.942 : 1 : 1.354$. Here the ratio of the first axis is preserved—that is, certain angles remain constant. Laurent likens hemimorphism to architectural style. Thus, Gothic cathedrals differ in many respects, but there is an analogy expressed both in the sum total of their common relations and in certain details. It is evident that we may expect many fruitful results for molecular mechanics (which forms a problem common to many provinces of natural science) from the further working out of the data concerning those variations which take place in crystalline form when the composition of a substance is subjected to a known change, and therefore I consider it useful to the young scientific man seeking for matter for independent scientific research to point out this vast field for work which is presented by the correlation of form and composition. The geometrical regularity and varied beauty of crystalline forms offer no small attraction to research of this kind.

CaO, $\text{Ca}(\text{OH})_2$, CaCl_2 , &c. For the third type RX_3 we know the representative NH_3 and the corresponding compounds N_2O_7 , $\text{NO}(\text{OH})$, $\text{NO}(\text{OK})$, PCl_3 , P_2O_3 , PH_3 , SbH_3 , Sb_2O_3 , B_2O_3 , BCl_3 , Al_2O_3 , &c. The type RX_4 is known among the hydrogen compounds. Marsh gas, CH_4 , and its corresponding saturated hydrocarbons, $\text{C}_n\text{H}_{2n+2}$, are the best representatives. Also CH_3Cl , CCl_4 , SiCl_4 , SnCl_4 , SnO_2 , CO_2 , SiO_2 , and a whole series of other compounds come under this class. The type RX_5 is also already familiar to us, but there are no purely hydrogen compounds among its representatives. Sal-ammoniac, NH_4Cl , and the corresponding $\text{NH}_4(\text{OH})$, $\text{NO}_2(\text{OH})$, $\text{ClO}_2(\text{OK})$, as well as PCl_5 , POCl_3 , &c., are representatives of this type. In the higher types also there are no hydrogen compounds, but in the type RX_6 there is the chlorine compound WCl_6 . However, there are many oxygen compounds, and among them SO_3 is the best known representative. To this class also belong $\text{SO}_2(\text{OH})_2$, SO_2Cl_2 , $\text{SO}_2(\text{OH})\text{Cl}$, CrO_3 , &c., all of an acid character. In general of the higher types there are only oxygen and acid representatives. The type RX_7 we know in perchloric acid, $\text{ClO}_3(\text{OH})$, and potassium permanganate, $\text{MnO}_3(\text{OK})$, is also a member. The type RX_8 is very rare, osmic anhydride, OsO_4 , is the best known representative of it. The still more complex combinations—which are so clearly expressed in the crystallo-hydrates, double salts and like compounds—although they may be regarded as independent, are, however, most easily understood with our present store of knowledge as aggregations of whole molecules to which there are no corresponding double compounds, containing one atom of an element R and many atoms of other elements RX_n . The above types embrace all cases of direct combinations of atoms, and the formula $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$ cannot, without doing violence to known facts, be directly deduced from the types MgX_n or SX_n , whilst the formula MgSO_4 corresponds both with the type of the magnesium compounds MgX_2 and with the type of the sulphur compounds SO_2X_2 , or in general SX_6 , where X_2 is replaced by $(\text{OH})_2$, with the substitution in this case of H_2 by the atom Mg, which always replaces H_2 .⁶

⁶ However, one cannot but remark that the sodium crystallo-hydrates often contain $10\text{H}_2\text{O}$, the magnesium crystallo-hydrates 6 and $7\text{H}_2\text{O}$, and that the type PtM_2X_8 is proper to the double salts of platinum, &c. With the further development of our knowledge concerning crystallo-hydrates, double salts, alloys, solutions, &c., in the *chemical sense* of feeble compounds (that is, such as are easily destroyed by feeble chemical influences) it will probably be possible to arrive at a perfect generalisation for them. For the present these subjects have only been studied by the way or by chance, our knowledge of them is accidental and destitute of system, and therefore it is impossible to expect as yet any generalisation as to their nature. The days of Gerhardt are not long past when only three types were recognised: RX , RX_2 , and RX_3 ; the type RX_4 was afterwards added (by Cooper, Kekulé, Butleroff, and others), mainly for the purpose of generalising

The four lower types RX , RX_2 , RX_3 , and RX_4 are met with in compounds of the elements R with chlorine and oxygen, and also in their compounds with hydrogen, whilst the four higher types only appear for such acid compounds as are formed by chlorine, oxygen, and like elements.

Among the oxygen compounds, the *saline oxides* which are capable of forming salts either through the function of a base or through the function of an acid anhydride attract the greatest interest in every respect. Certain elements, like calcium and magnesium, only give one saline oxide—for example, MgO , corresponding with the type MgX_2 . But the majority of the elements appear in several such forms. Thus copper gives CuX and CuX_2 , or Cu_2O and CuO . If an element R gives a higher type RX_n , then there often also exist, as if by symmetry, lower types RX_{n-2} , RX_{n-4} , and in general such which differ from the type RX_n by an even number of X . Thus in the case of sulphur the types SX_2 , SX_4 , and SX_6 are known—for example SH_2 , SO_2 , and SO_3 . The last type is the highest SX_6 . The types SX_5 and SX_3 do not exist. But even and uneven types sometimes appear for one and the same element. Thus the types RX and RX_2 are known for copper and mercury.

Among the *saline oxides* only the *eight types* enumerated below are known to exist. They determine the possible formulæ of the compounds of the elements, if it be taken into consideration that an element which gives a certain type of combination may also give lower types. For this reason the rare type of the *suboxides* or quaternary oxides R_4O (for instance, Ag_4O , Ag_4Cl) is not characteristic; it is always accompanied by one of the higher grades of oxidation, and the compounds of this type are distinguished by their great chemical instability, and split up into an element and the higher compound (for instance, $Ag_4O = 2Ag + Ag_2O$). Many elements beside this form transition oxides whose composition is intermediate, and which are

the data respecting the carbon compounds. And indeed many are still satisfied with these types, and derive the higher types from them—for instance, RX_5 from RX_3 , as, for example, $POCl_3$ from PCl_3 , considering the oxygen to be bound both to the chlorine (as in $HClO$) and to the phosphorus. But the time has now arrived when it is clearly seen that the forms RX , RX_2 , RX_3 , and RX_4 do not exhaust the whole variety of phenomena. The revolution became evident when Würtz showed that PCl_5 is not a compound of $PCl_3 + Cl_2$, although it may decompose into them, but a whole molecule capable of passing into vapour, PCl_5 like PF_5 and SiF_4 . But in my opinion the time will come for the recognition of types still higher than RX_3 . In confirmation of this opinion I cite certain facts in the further exposition of this work. Oxalic acid, $C_2H_2O_4$, gives a crystallo-hydrate with $2H_2O$, but it may be referred to the type CH_4 , or rather to the type of ethane, C_2H_6 , in which all the atoms of hydrogen are replaced by hydroxyl, $C_2H_2O_4 \cdot 2H_2O = C_2(OH)_6$.

able, like N_2O_4 , to split up into the lower and higher oxides. Thus iron gives magnetic oxide, Fe_3O_4 , which is in all respects (by its reactions) a compound of the suboxide FeO with the oxide Fe_2O_3 . The independent and more or less stable saline compounds correspond with the following eight types:—

R_2O ; salts RX , hydroxides ROH . Generally basic like K_2O , Na_2O , Hg_2O , Ag_2O , Cu_2O ; if there are acid oxides of this composition they are very rare, are only formed by distinctly acid elements, and even then have only feeble acid properties; for example, Cl_2O .

R_2O_2 or RO ; salts RX_2 , hydroxides $R(OH)_2$. The most simple basic salts R_2OX_2 or $R(OH)X$; also an almost exclusively basic type, but the basic properties are more feebly developed than in the preceding type. For example, CaO , MgO , BaO , PbO , FeO , MnO , &c.

R_2O_3 ; salts RX_3 , hydroxides $R(OH)_3$, $RO(OH)$, the most simple basic salts ROX , $R(OH)X_2$. The bases are unenergetic, like Al_2O_3 , Fe_2O_3 , Tl_2O_3 , Sb_2O_3 . The acid properties are also feebly developed; for instance, in B_2O_3 , but with the non-metals the properties of acids are already clear, for instance P_2O_3 , $P(OH)_3$.

R_2O_4 or RO_2 ; salts RX_4 or ROX_2 , hydroxides $R(OH)_4$, $RO(OH)_2$. Rarely bases (feeble), like ZrO_2 , PtO_2 ; more often acid oxides, but the acid properties are in general feeble, as in CO_2 , SO_2 , SnO_2 . Many intermediate oxides appear in this and the preceding and the following types.

R_2O_5 ; salts principally of the types ROX_5 , RO_2X , $RO(OH)_3$, $RO_2(OH)$ rarely RX_5 . The basic character (X , a halogen, simple or complex—for instance, NO_3 , Cl , &c.) is feeble; the acid character predominates, as is seen in N_2O_5 , P_2O_5 , Cl_2O_7 ; then $X=OH$, OK , &c., for example $NO_2(OK)$.

R_2O_6 or RO_3 ; salts and hydroxides generally of the type RO_2X_2 , $RO_2(OH)_2$. Oxides of an acid character, as SO_3 , CrO_3 , MnO_3 . Basic properties rare and feebly developed as in UO_3 .

R_2O_7 ; salts of the form RO_3X , $RO_3(OH)$, acid oxides—for instance, Cl_2O_7 , Mn_2O_7 . Basic properties as feebly developed as the acid properties in the oxides R_2O .

R_2O_8 or RO_4 . A very rare type, and only known in OsO_4 and RuO_4 .

It is evident from the circumstance that in all the higher types the *acid hydroxides* and salts with one atom of an element contain, like the higher saline type RO_4 , *not more than four atoms of oxygen*, that the formation of the saline oxides is governed by a certain common principle which is best looked for in the properties of oxygen itself. The hydrate of the oxide RO_2 is of the higher type $RO_2 \cdot 2H_2O =$

$\text{RH}_n\text{O}_4 = \text{R}(\text{HO})_n$. Such, for example, is the hydrate of silica and the salts (orthosilicates) corresponding with it, $\text{Si}(\text{MO})_4$. The oxide R_2O_3 corresponds with the hydrate $\text{R}_2\text{O}_3 \cdot 3\text{H}_2\text{O} = 2\text{RH}_3\text{O}_4 = 2\text{RO}(\text{OH})_3$. Such is orthophosphoric acid PH_3O_3 . The hydrate of the oxide RO_3 is $\text{RO}_3 \cdot \text{H}_2\text{O} = \text{RH}_2\text{O}_4 = \text{RO}_2(\text{OH})_2$ —for instance, sulphuric acid. The hydrate corresponding to R_2O_7 is evidently $\text{RHO}_4 = \text{RO}_3(\text{OH})$ —for example, perchloric acid. Here, besides containing O_4 , it must further be remarked that *the amount of hydrogen in the hydrate is equal to the amount of hydrogen in the hydrogen compound*. Thus silicon gives SiH_4 and SiH_4O_4 , phosphorus PH_3 and PH_3O_4 , sulphur SH_2 and SH_2O_4 , chlorine ClH and ClHO_4 . This, if it does not explain, at least connects in a harmonious and general system the fact that *the elements are capable of combining with a greater amount of oxygen, the less the amount of hydrogen which they are able to retain*. In this the key to the comprehension of all further deductions must be looked for, and therefore we will formulate this rule in general terms. An element R gives a hydrogen compound RH_n , the hydrate of its higher oxide will be RH_nO_4 , and therefore the higher oxide will contain $2\text{RH}_n\text{O}_4 - n\text{H}_2\text{O} = \text{R}_2\text{O}_{2n-1}$. For example, chlorine gives ClH , hydrate ClHO_4 , and the higher oxide Cl_2O_7 . Thus carbon gives CH_4 and CO_2 . So also, SiO_2 and SiH_4 are the higher compounds of silicon with hydrogen and oxygen, like CO_2 and CH_4 . Here the amounts of oxygen and hydrogen are equivalent. Nitrogen combines with a large amount of oxygen, forming N_2O_5 , but on the other hand with a small quantity of hydrogen in NH_3 . *The sum of the equivalents of hydrogen and oxygen, occurring in combination with an atom of nitrogen, is, as always in the higher types, equal to eight*. It is the same with the other elements which combine with hydrogen and oxygen. Thus sulphur gives SO_3 ; consequently, six equivalents of oxygen fall to an atom of sulphur, and in SH_2 two equivalents of hydrogen. The sum is again equal to eight. The relation between Cl_2O_7 and ClH is the same. This shows that the property of elements of combining with such different elements as oxygen and hydrogen, is subject to one common rule, which is also formulated in the system of the elements presently to be described.⁷

In the preceding we see not only the regularity and simplicity

⁷ The hydrogen compounds, R_2H , in equivalency correspond with the type of the suboxides, R_4O . Palladium, sodium and potassium give similar hydrogen compounds, and it is worthy of remark that according to the periodic system these elements stand near to each other, and that in those groups where the hydrogen compounds R_2H appear, the quaternary oxides R_4O are also present.

Not wishing to complicate the exposition, I here only touch on the general features of the relation between the hydrates and oxides and of the oxides among themselves.

which govern the formation and properties of the oxides and of all the compounds of the elements, but also a fresh and exact means for recognising the analogy of elements. Analogous elements give compounds of analogous types, both higher and lower. If CO_2 and SO_2 are two gases which closely resemble each other both in their physical and chemical properties, the reason of this must not be looked for in an analogy of sulphur and carbon; but it lies in that identity of the type of combination, RX_2 , in which both oxides appear, and in that influence which a large mass of oxygen always exerts on the properties of its compounds. In fact, there is little resemblance between carbon and sulphur, as is seen not only from the fact that CO_2 is the *higher form* of oxidation, whilst SO_2 is able to further oxidise into SO_3 , but also from the fact that all the other compounds—for example, SH_2 and CH_4 , SCl_2 and CCl_4 , &c.—are entirely unlike both in type and in chemical properties. This absence of analogy in carbon and sulphur is clearly expressed in the fact that the higher oxides are of different composition, CO_2 for carbon, and SO_3 for sulphur. The halogens, which are analogous, give both like higher and lower compounds. So also do the metals of the alkaline earths and of the alkalis. Many such groups of analogous elements have long been known. Thus there are analogues of oxygen, nitrogen, and carbon, and we shall meet with many such groups. But an acquaintance with them involuntarily leads to the questions, what is the cause of analogy and what is the relation of one group to another? If these questions remain unanswered, it is easy to fall into error in the formation of the groups because the notions of the degree of analogy will always be relative, and will not present any accuracy or distinctness. Thus lithium is analogous in some respects to potassium and in others to magnesium; or beryllium is analogous to both aluminium and magnesium. In thallium, as we shall afterwards see and as was observed on its discovery, there is much in kindred with lead and mercury, but some of its properties appertain to lithium and potassium. Naturally, where it is impossible to make measurements one is involuntarily obliged to limit oneself to approximation or comparison, founded on

Thus, for instance, the conception of the ortho-acids and of the normal acids will be considered in speaking of phosphoric and phosphorous acids.

As in the further exposition of the periodic law only those oxides which give salts will be considered, I think it will not be superfluous to here mention the following facts relative to the peroxides. Of the *peroxides* corresponding with hydrogen peroxide, the following are at present known: H_2O_2 , Na_2O_2 , S_2O_7 (as HSO_4 ?), K_2O_4 , K_2O_2 , CaO_2 , TiO_2 , Cr_2O_7 , CuO_2 ?, Rb_2O_2 , SrO_2 , Ag_2O_2 , CsO_2 , Cs_2O_2 , BaO_2 , and MO_2 . It is probable that the number of peroxides will increase with further investigation. A periodicity is seen in those now known because the elements (excepting Li) of the first group, which gives R_2O , form peroxides, and then the elements of the fourth group seem also to be particularly inclined to form peroxides.

apparent signs which are not distinct and are void of exactitude. But in the elements there is one accurately measurable property, which is subject to no doubt—namely, that property which is expressed in their atomic weights. Its magnitude indicates the relative mass of the atom, or, if we avoid the conception of the atom, its magnitude shows the relation between the masses forming the chemical and independent individuals or elements. And according to the sense of all our physico-chemical data, the mass of a substance is that property on which all the remaining properties of matter must be dependent, because they are all determined by similar conditions or by those forces which act in the weight of a substance, and this is directly proportional to the mass of a substance. Therefore, it is most natural to seek for a dependence between the properties and analogies of the elements on the one hand and their atomic weights on the other.

This is the fundamental idea which leads to *arranging all the elements according to their atomic weights*. A repetition of properties is then immediately observed in the periods of the elements. We are already familiar with examples of this—

F = 19,	Cl = 35.5,	B = 80,	I = 127
Na = 23,	K = 39,	Rb = 85,	Cs = 133
Mg = 24,	Cu = 40,	Sr = 87,	Ba = 137.

The substance of the matter is seen in these groups. The halogens have smaller atomic weights than the alkali metals, and the latter than the metals of the alkaline earths. Therefore, *if all the elements be arranged in the order of their atomic weights a periodic repetition of properties is obtained*. This is expressed by the *law of periodicity*; *the properties of the elements, as well as the forms and properties of their compounds, are in periodic dependence or, expressing ourselves algebraically, form a periodic function of the atomic weights of the elements*.⁸ Table I. of *the periodic system of the elements*, which

⁸ The periodic law and the periodic system of the elements appeared in the same form as here given in the first edition of this work, begun in 1868 and finished in 1871. In laying out the accumulated information respecting the elements, I had occasion to reflect on their metrical relations. At the beginning of 1869 I distributed among many chemists a tract entitled, 'An Experimental System of the Elements, based on their Atomic Weights and Chemical Analogies,' and at the March meeting of the Russian Chemical Society, 1869, I communicated a paper 'On the Correlation of the Properties and Atomic Weights of the Elements.' The substance of this paper is embraced in the following conclusions: (1) The elements, if arranged according to their atomic weights, exhibit an evident *periodicity* of properties. (2) Elements which are similar as regards their chemical properties have atomic weights which are either of nearly the same value (platinum, iridium, osmium) or which increase regularly (*e.g.* potassium, rubidium, caesium). (3) The arrangement of the elements or of groups of elements in the order of their atomic weights,

is placed at the very beginning of this book, is composed according to this law. It is arranged in conformity with the eight types of oxides described in the preceding pages, and those elements which give the oxides R_2O , and consequently salts RX , form the 1st group; the elements giving R_2O_2 or RO as their highest grade of oxidation enter into the 2nd group, those giving R_2O_3 as their higher oxides form the

corresponds with their so-called *valencies*. (4) The elements, which are the most widely diffused in nature, have *small* atomic weights, and all the elements of small atomic weight are characterised by their sharply-defined properties. They are therefore typical elements. (5) The *magnitude* of the atomic weight determines the character of an element. (6) The discovery of many yet unknown elements may be expected. For instance, elements analogous to aluminium and silicon, whose atomic weights would be between 45 and 75. (7) The atomic weight of an element may sometimes be amended by aid of a knowledge of those of the contiguous elements. Thus the combining weight of tellurium must lie between 123 and 126, and cannot be 128. (8) Certain characteristic properties of the elements can be foretold from their atomic weights.

The entire periodic law is included in these lines. In the series of subsequent papers (1870-72, for example, in the *Transactions* of the Russian Chemical Society, of the Moscow meeting of Naturalists of the Petroffsky Academy, and Liebig's *Annalen*) on the same subject, we only find applications of the same principles, which were afterwards confirmed by the labours of Roscoe, Carnelley, Thorpe, and others in England, of Rammeisberg (respecting cerium and uranium), L. Meyer (respecting the specific volumes of the elements), Zimmermann (respecting uranium), and more especially of C. Winkler (who discovered germanium, and showed its identity with ekasilicon), and others in Germany; of Lecoq de Boisbaudran in France (the discovery of gallium = ekaaluminium), of Cleve respecting the atomic weights of the cerium metals), Nillson (discoverer of scandium = ekaboron), and Nillson and Pettersson (determination of the vapour density of beryllium chloride) in Sweden, and of Brauner (who investigated cerium, and determined the combining weight of tellurium = 125), in Austria.

I consider it necessary to state, that in arranging the periodic system of the elements I made use of the previous researches of Dumas, Gladstone, Pettenkofer, Kremers, and Lenssen on the atomic weights of related elements, but I was not acquainted with the works preceding mine of De Chancourtois (*vis tellurique*, or the spiral of the elements according to their properties and equivalents) in France, and of J. Newlands (Law of Octaves—for instance, H, F, Cl, Co, Br, Pd, I, Pt form the first octave, and O, S, Fe, Se, Rh, Te, Au, Th the last) in England, although certain germs of the periodic law are to be seen in these works. With regard to the work of Prof. Lothar Meyer respecting the periodic law (Notes 12 and 13), it is evident, judging from the method of investigation, and of his statement (Liebig's *Annalen Suppl. Band* 7, 1870, 354), at the very commencement of which he cites my paper of 1869 above mentioned, that he took the periodic law in the same form as it was given by me.

In conclusion to this historical statement I consider it well to observe that no law of nature, however general, has been established at once; its establishment is always preceded by many presentiments, but the acknowledgment of a law does not take place when it is recognised in all its significance, but only when it has been confirmed by experiment, which the scientific man must look to as the only proof of the correctness of his conjectures and opinions. I therefore, for my part, consider Roscoe, De Boisbaudran, Nillson, Winkler, Brauner, Carnelley, Thorpe, and others who verified the adaptability of the periodic law to chemical reality, as the true founders of the periodic law, the further development of which still awaits fresh workers. The efforts made in this direction, which are mentioned in the following notes, cannot for the present be considered as in any way elucidating many questions which involuntarily arise on an acquaintance with this law.

3rd group, and so on, whilst the elements of all the groups which are nearest in their atomic weights are arranged in series from 1 to 12. The even and uneven series of the same groups present the same forms, but differ in their properties, and therefore two contiguous series, one even and the other uneven—for instance, the 4th and 5th—form a period. Hence the elements of the 4th, 6th, 8th, 10th, and 12th, or of the 3rd, 5th, 7th, 9th, and 11th series form analogues, like the halogens, alkali metals, &c. The conjunction of two series, one even and its contiguous uneven series, thus forms one large *period*. These periods, beginning with the alkali metals, end with the halogens. The elements of the two first series have the least atomic weights, and in consequence of this very circumstance, although they bear the general properties of a group, still they show many peculiar and independent properties.⁹ Thus fluorine, as we know, differs in many points from the other halogens, and lithium from the other alkali metals, and so on. These lightest elements may be termed *typical elements*. They include—

H.

Li, Be, B, C, N, O, F.

Na, Mg

In the annexed table all the remaining elements are arranged, not in groups and series, but *according to periods*. In order to penetrate into the essence of the matter, it must be remembered that here the atomic weight gradually increases along a given line : for instance, in the line commencing with K=39 and ending with Br (the 17th)=80, the intermediate elements have intermediate atomic weights.

Even Series.														Mg	Al	Si	P	S	Cl
K	Ca	Sc	Ti	V	Cr	Mn	Fe	Co	Ni	Cu	Zn	Ga	Ge	As	Se	Br			
Rb	Sr	Y	Zr	Nb	Mo	—	Ru	Rh	Pd	Ag	Cd	In	Sn	Sb	Te	I			
Cs	Ba	La	Ce	Di ?	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
—	—	Yb	—	Ta	W	—	Os	Ir	Pt	Au	Hg	Tl	Pb	Bi	—	—			
—	—	—	Th	—	U														
														Uneven Series.					

The same degree of analogy as we know to exist between potassium, rubidium, and cesium ; or chlorine, bromine, and iodine ; or calcium, strontium, and barium also exists between the elements of the other vertical columns. Thus, for example, zinc, cadmium, and mercury,

⁹ This resembles the fact, well known to those having an acquaintance with organic chemistry, that in a series of homologues (Chap. VIII.) the first members, in which there is the least carbon, although showing the general properties of the homologous series, still present certain distinct peculiarities.

which are described in the following chapter, present a very close analogy with magnesium. All our further descriptions of the elements will be arranged according to this periodic system. The distribution of the elements in groups, series, and periods is shown in the tables given in this chapter, at the end of the preface, and at the end of the book. For a true comprehension of the matter, it is very important to see at once, that all the given aspects¹⁰ of the distribution

¹⁰ Besides arranging the elements (*a*) in a successive order according to their atomic weights, with indication of their analogies by showing some or other properties (both chemical—for instance, their power of giving one or another form of combination—and physical), both of the *elements* and of their compounds (as is done in Table III. at the beginning of this volume), (*b*) according to periods (as is done in Table I. at the commencement of volume I. after the preface), and (*c*) according to groups and series or small periods (as is done in Table II. and in Table IV. at the end of this volume). I am acquainted with the following methods of expressing the periodic relations of the elements: (1) By a curve drawn through points obtained in the following manner: The elements are arranged along the horizontal axis of abscissæ at distances from zero proportional to their atomic weights and the values for each of the elements of some property—for example, specific volumes or melting points are expressed by the ordinates. This method, although graphic, has the theoretical disadvantage that it does not in any way indicate the existence of a limited and definite number of elements in each period. There is nothing, for instance, in this method of expressing the law of periodicity to show that between magnesium and aluminium there can be no other element with an atomic weight of say 25, atomic volume 13, and in general having properties intermediate between those of these two elements. The actual periodic law does not correspond with a continuous change of properties, with a continuous variation of atomic weight—in a word, it does not express an uninterrupted function—and as the law is purely chemical, starting from the conceptions of atoms and molecules which combine in multiple proportions, with intervals (not continuously), it, *above all*, depends on there being but few types of compounds, which are arithmetically simple, *repeat themselves*, and offer no uninterrupted transitions, and therefore each period can only contain a definite number of members. For this reason there can be no other elements between magnesium, which gives the chloride $MgCl_2$, and aluminium, which forms AlX_3 ; there is a break in the continuity, according to the law of multiple proportions. The periodic law ought not, therefore, to be expressed by geometrical figures in which continuity is always understood. Owing to these considerations I have never, and will never, express the periodic relations of the elements by any geometrical figures. (2) *By a plane spiral.* Radii are traced from a centre, proportional to the atomic weights; analogous elements lie along one radius, and the points of intersection are arranged in a spiral. This method, adopted by De Chancourtois, Baumgauer, E. Huth, and others, has many of the imperfections of the preceding, although it removes the indefiniteness as to the number of elements in a period. In it one ought only to see a simple endeavour to bring the complex relations under a simple graphic representation, because the number of radii and the formulation of the spiral is not dependent on any conditions. (3) *By the lines of atomicity*, either parallel, as in Reynolds's and the Rev. S. Haughton's method, or as in Crookes's method, inclined to the right and left of an axis, along which the magnitudes of the atomic weights are counted, the points of the elements are marked off, on the one side the members of the even series (paramagnetic, like oxygen, potassium, iron), and on the other side the members of the uneven series (diamagnetic, like sulphur, chlorine, zinc, and mercury). On joining up these points a periodic curve is obtained, likened by Crookes to the oscillations of a pendulum, and, according to Haughton, representing a cubical curve. This method would be very graphic did it not require, for instance, that sulphur should be considered as bivalent and manganese as univalent, although

of the elements according to their atomic weights essentially express one and the same fundamental *dependence—periodic properties*.¹¹ The following points must then be seen in it.

neither of these elements gives stable derivatives of these natures, and although the one is taken on the basis of the lowest possible compound SX_2 , and the other of the highest, because manganese may be referred to the univalent elements only by the analogy of $KMnO_4$ to $KClO_4$. Furthermore, Reynolds and Crookes place hydrogen, iron, nickel, cobalt, and others outside the axis of atomicity, and consider uranium as bivalent without the least foundation. (4) Rantsheff endeavoured to classify the elements in their periodic relations by a system dependent on solid geometry. He communicated this mode of expression to the Russian Chemical Society, but his communication, which is apparently not void of interest, has not yet appeared in print. (5) *By algebraic formula*: for example, E. J. Mills (1886) endeavours to express all the atomic weights by the logarithmic function $A = 15 (n - 0.9375t)$, in which the variables n and t are whole numbers. For instance, for oxygen $n = 2, t = 1$, hence $A = 15.94$; for antimony $n = 9, t = 0$, whence $A = 120$, and so on. n varies from 1 to 16 and t from 0 to 59. The analogues are hardly distinguishable by this method, thus for chlorine the magnitudes of n and t are 3 and 7, for bromine 6 and 6, for iodine 9 and 9, for potassium 3 and 14, for rubidium 6 and 18, for caesium 9 and 20; but a certain regularity seems to be shown. (6) A more natural method of expressing the dependence of the properties of elements on their atomic weights is obtained by *trigonometrical functions*, because this dependence is periodic like the functions of trigonometrical lines, and therefore Ridberg in Sweden (1885) and F. Flavitzky in Russia (Kazan, 1887) have adopted a like method of expression, which must be considered as worthy of being worked out, although it does not express the absence of intermediate elements—for instance, between magnesium and aluminium, which is essentially the most important part of the matter. (7) The investigations of B. N. Tchitchérin (1888, *Journal of the Russian Physical and Chemical Society*) form the first effort in the latter direction. He carefully studied the alkali metals, and discovered the following simple relation between their atomic volumes: they can all be expressed by $A(2 - 0.0428An)$, where A is the atomic weight and $n = 1$ for lithium and sodium, $\frac{2}{3}$ for potassium, $\frac{2}{3}$ for rubidium, and $\frac{2}{3}$ for caesium. If n always = 1, then the volume of the atom would become zero at $A = 46\frac{2}{3}$, and would reach its maximum when $A = 23\frac{1}{3}$, and the density increases with the growth of A . In order to explain the variation of n , and the relation of the atomic weights of the alkali metals to those of the other elements, as also the atomicity itself, Tchitchérin supposes all atoms to be built up of a primary matter; considers the relation of the central to the peripheric mass, and, guided by mechanical principles, deduces many of the properties of the atoms from the reaction of the internal and peripheric parts of each atom. This endeavour offers many interesting points, but the value of the theory cannot be judged at present, as it is not yet fully developed. Further, it admits the hypothesis of the building up of all the elements from one primary matter, and at the present time such an hypothesis has not the least support either in theory or in fact. Besides which the starting-point of the theory is the specific gravity of the metals at a definite temperature (it is not known how the above relation would appear at other temperatures), and the specific gravity varies even under mechanical influences.

¹¹ Many natural phenomena exhibit a dependence of a periodic character. Thus the phenomena of day and night and of the seasons of the year, and vibrations of all kinds, exhibit variations of a periodic character in dependence on time and space. But in ordinary periodic functions one variable varies continuously, whilst the other increases to a limit, then a period of decrease begins, and having in turn reached its limit, a period of increase again begins. It is otherwise in the periodic function of the elements. Here the mass of the elements does not increase continuously, but abruptly, by steps, as from magnesium to aluminium. So also the valency or atomicity leaps directly from 1 to 2 to 3, &c., without intermediate quantities, and in my opinion it is these properties which

1. The formulæ of the higher oxygen compounds are determined by the groups; the first group gives R_2O , the second R_2O_2 or RO , the third R_2O_3 , &c. There are eight types of oxides and therefore eight

are the most important, and it is their periodicity which forms the substance of the periodic law. It expresses *the properties of the real elements*, and not of what may be termed their manifestations visually known to us. The external properties of elements and compounds are in periodic dependence on the atomic weight of the elements only because these external properties are themselves the result of the properties of the real elements forming the isolated elements or the compound. To explain and express the periodic law is to explain and express the cause of the law of multiple proportions, of the difference of the elements, and the variation of their atomicity, and at the same time to understand what mass and gravitation are. In my opinion this is now premature. But just as without knowing the cause of gravitation, it is possible to make use of the law of gravity, so for the aims of chemistry it is possible to take advantage of the laws discovered by chemistry without being able to explain their causes. The above-mentioned peculiarity of the laws of chemistry respecting definite compounds and the atomic weights leads one to think that the time has not yet come for their full explanation, and I do not think that it will come before the explanation of such primary laws of nature as the law of gravity.

It will not be out of place to here turn our attention to the many-sided correlation existing between the undecomposable *elements and the compound carbon radicles*, which has long been remarked (Pettenkofer, Dumas, and others), and reconsidered in recent times by Carnelley (1886), and most originally in Pelopidas's work (1883) on the principles of the periodic system. Pelopidas compares the series containing eight hydrocarbon radicles, C_nH_{2n+1} , C_nH_{2n} —for instance, C_6H_{15} , C_6H_{12} , C_6H_{11} , C_6H_{10} , C_6H_9 , C_6H_8 , C_6H_7 , and C_6H_6 —with the series of the elements arranged in eight groups. The analogy is particularly clear owing to the property of C_nH_{2n+1} to combine with X, thus reaching saturation, and of the following members with X_2 , X_3 . . . X_8 , and especially because these are followed by an aromatic radicle—for instance, C_6H_5 —in which, as is well known, many of the properties of the saturated radicle C_6H_{13} are repeated, and in particular the power of forming a univalent radicle again appears. Pelopidas shows a confirmation of the parallel in the property of the above radicles of giving oxygen compounds corresponding with the groups in the periodic system. Thus the hydrocarbon radicles of the first group—for instance, C_6H_{17} or C_6H_7 —give oxides of the form R_2O and hydroxides RHO , like the metals of the alkalis: and in the third group they form oxides R_2O_3 and hydrates RO_2H . For instance, in the series CH_3 the corresponding compounds of the third group will be the oxide $(CH)_2O_3$ or $C_2H_2O_3$ —that is, formic anhydride and hydrate, CHO_2H , or formic acid. In the sixth group, with a composition of C_2 , the oxide RO_3 will be C_2O_3 , and hydrate $C_2H_2O_4$ —that is, also a dibasic acid (oxalic) resembling sulphuric, among the inorganic acids. After carrying his views over a mass of organic compounds, Pelopidas lingers more particularly over the radicles corresponding with ammonium; for example, he takes methylammonium, $N(CH_3)_3$ or NCH_3 , in the first group, as showing many of the properties of the metals of the alkalis and giving an alkali, $NH_4(CH_3)(OH)$, like $NaHO$. In the second and following groups by the abstraction of hydrogen we obtain radicles all of higher atomicity and less alkaline character, and lastly in the seventh group we find CN , whose analogy to the halogens, corresponding with the seventh group, is well known.

With respect to this remarkable parallelism, it must above all be observed that in the elements the atomic weight increases in passing to contiguous members of a higher valency, whilst here it decreases, and therefore there is no foundation for seeing any indications in this correlation with the hydrocarbon radicles pointing towards a compound nature for the elementary substances; but rather that the periodic variability of elements and compounds is subject to some higher law whose nature, and still more whose cause, cannot at present be determined. It is probably based on the fundamental principles of the internal mechanics of the atoms and molecules, and as the periodic law has only been

groups. Two groups give a period, and the same type of oxide is met with twice in a period. For example, in the period beginning with potassium, oxides of the composition RO are formed by calcium and zinc, and of the composition RO_3 by molybdenum and tellurium. The oxides of the even series, of the same type, have stronger basic properties than the oxides of the uneven series, and the latter as a rule are endowed with an acid character. Therefore, the elements which exclusively give bases, like the alkali metals, will be at the commencement of the period, whilst such purely acid elements as the halogens will be at the end of the period. The interval will be occupied by intermediate elements, whose character and properties we shall afterwards describe. It must be observed that the acid character is chiefly proper to the elements with small atomic weights in the uneven series, whilst the basic character is exhibited by the heavier elements in the even series. Hence elements which give acids chiefly predominate among the lightest (typical) elements, especially in the last groups; whilst the heaviest elements, even in the last groups (for instance, thallium, uranium), have a basic character. Thus the basic and acid characters of the higher oxides are determined (a) by the type of oxide, (b) by the even or uneven series, and (c) by the atomic weight.

2. *The hydrogen compounds* being volatile or gaseous substances which are prone to reaction—such as HCl , H_2O , H_3N , and H_4C —are only formed by the elements of the uneven series and higher groups giving oxides of the forms R_2O_7 , RO_3 , R_2O_5 , and RO_2 .

3. If an element gives a hydrogen compound, RX_m , then it forms an *organo-metallic compound* of the same composition, where $X = C_n H_{2n+1}$: that is, X is the radicle of a saturated hydrocarbon. The elements of the uneven series, which are incapable of giving hydrogen compounds and which form oxides of the forms RX , RX_2 , RX_3 , also give organo-metallic compounds of this form proper to the higher oxides. Thus zinc forms the oxide ZnO , salts ZnX_2 , and zinc-ethyl $Zn(C_2H_5)_2$. The elements of the even series do not seem to form organo-metallic compounds at all; at least all efforts for their preparation have as yet been fruitless—for instance, in the case of titanium, zirconium, or iron.

4. The atomic weights of elements belonging to contiguous periods differ approximately by 45; for example, $K < Rb$, $Cr < Mo$, $Br < I$. But the elements of the typical series have the smallest atomic weight. The difference between the atomic weights of Li , Na , and $K = 16$,

generally recognised for a few years it is not surprising that any further progress towards its explanation can only be looked for in the development of facts touching on this subject.

between Ca, Mg, and Br also 16, and between Si and C is 16, between S and O 16, and between Cl and F 16. As a rule, there is a greater difference between the atomic weights of the elements of one group and those of its two neighbouring series ($\text{Ti}-\text{Si}=\text{V}-\text{P}=\text{Cr}-\text{S}=\text{Mn}-\text{Cl}=\text{Nb}-\text{As}$, &c.=20), and this difference attains a maximum with the heaviest elements (for example, $\text{Th}-\text{Pb}=26$, $\text{Bi}-\text{Ta}=26$, $\text{Ba}-\text{Cd}=25$, &c.). Furthermore, the difference between the atomic weights of the elements of even and uneven series also increases. In fact, the differences between Na and K, Mg and Ca, Si and Ti are less abrupt than those between Pb and Th, Ta and Bi, Cd and Ba, &c. Thus there is even in the magnitude of the differences of the atomic weights of analogous elements a certain connection observable with the gradation of their properties.¹²

5. Every element, according to the periodic system, occupies a certain position, determined by the group (indicated in Roman numerals) and series (Arabic numerals) in which it occurs. They indicate the atomic weight, the analogues, properties, and type of the higher oxide, and of the hydrogen and other compounds—in a word, all the chief quantitative and qualitative features of an element, although there yet further remain a whole series of details and peculiarities, whose cause, according to the sense of the whole doctrine lying at the base of the system, must be looked for in small differences of the atomic weights. If in a certain group there occur elements, R_1 , R_2 , R_3 , and if in that series which contains one of these elements, for instance R_2 , an element Q_2 precedes it and an element T_2 succeeds it. Then, the properties of R_2 are determined by the properties of R_1 , R_3 , Q_2 , and T_2 . Thus, for instance, the atomic weight of $R_2 = \frac{1}{4}(R_1 + R_3 + Q_2 + T_2)$.

¹² The relation between the atomic weights, and especially the difference = 16, was observed in the sixth and seventh decades of this century by Dumas, Pettenkofer, L. Meyer, and others. Thus Lothar Meyer in 1864, following Dumas and others, grouped together the tetravalent elements carbon and silicon; the trivalent elements nitrogen, phosphorus, arsenic, antimony, and bismuth; the bivalent oxygen, sulphur, selenium, and tellurium; the univalent fluorine, chlorine, bromine, and iodine; and the univalent metals lithium, sodium, potassium, rubidium, caesium, and thallium, and the bivalent metals beryllium, magnesium, strontium, and barium—observing that in the first the difference is, in general = 16, in the second about = 46, and the last about = 87–90. The first germs of the periodic law are visible in such observations as these. Since its establishment this subject has been most fully worked out by Rindberg (Note 10), who observed a periodicity in the variation of the differences between the atomic weights of two contiguous elements, and its relation to their atomicity. A. Bazaroff (1887) investigated the same subject, taking, not the arithmetical differences of contiguous and analogous elements, but the ratio of their atomic weights, and he also observed that this ratio alternately rises and falls with the rise of the atomic weights.

I will here remark that the relation of the eighth group to the others will be considered at the end of this work (it includes iron, cobalt, nickel, copper, and their analogues).

For example, selenium occurs in the same group as sulphur, $S=32$, and tellurium, $Te=125$, and in the 7th series, $As=75$ stands before it and $Br=80$ after it. Hence the atomic weight of selenium should be $\frac{1}{4}(32+125+75+80)=78$, as it is in reality. Other properties of selenium may also be determined in this manner. For example, arsenic forms H_3As , bromine gives HBr , and it is evident that selenium, which stands between them, should form H_2Se , with properties intermediate between those of H_3As and HBr . Even the physical properties of selenium and its compounds, not to speak of their composition, determined by the group in which it occurs, may be foreseen with a close approach to reality from the properties of sulphur, tellurium, arsenic, and bromine. *In this manner it is possible to foretell the properties of still unknown elements.* For instance, in the position IV, 5—that is, in the IVth group and 5th series—an element is still wanting. These unknown elements may be named after the preceding known element of the same group, by adding to the first syllable the prefix *eka*, which means *one* in Sanskrit. The element IV, 5, follows after IV, 3, and this position is occupied by silicon, and therefore we call the unknown element *ekasilicon* and its symbol, Es . The following are the properties which this element should have on the basis of the known properties of silicon, tin, zinc, and arsenic. Its atomic weight is nearly 72, higher oxide EsO_2 , lower oxide EsO , compounds of the general form EsX_4 , and chemically unstable lower compounds of the form EsX_2 . Es gives volatile organo-metallic compounds—for instance, $Es(CH_3)_4$, $Es(CH_3)_3Cl$, and $Es(C_2H_5)_4$, which boil at about 160° , &c., also a volatile and liquid chloride, $EsCl_4$, boiling at about 90° and of sp. gr. about 1.9. EsO_2 will be the anhydride of a feeble colloidal acid, metallic Es will be rather easily obtainable from the oxides and from K_2EsF_6 by reduction, EsS_2 will resemble SnS_2 and SiS_2 , and will probably be soluble in ammonium sulphide; the sp. gr. of Es will be about 5.5, EsO_2 will have a density of about 4.7, &c. Such a prediction of the properties of *ekasilicon* was made by me in 1871; and now that this element has been discovered by C. Winkler of Freiberg it has been found that its actual properties entirely correspond with those which were foretold.¹³ In this we see a most important

¹³ The laws of nature admit of no exceptions, and in this they clearly differ from such rules and maxims as are found in grammar, &c. The confirmation of a law is only possible by means of the deduction of the consequences proceeding from it, and which would without it be impossible and unforeseen, and by verifying these consequences by experiment and further proofs. Therefore, when I saw the periodic law, I (1869-1871, Note 9) deduced such logical consequences from it as could show whether it were true or not. Among them was the prediction of the properties of undiscovered elements and the correction of the atomic weights of many, and at that time little known, elements.

confirmation of the truth of the periodic law. This element is now called germanium, Ge. It is not the only one that has been foretold by the periodic law.¹⁴ We shall see in describing the elements of the third group, that properties were foretold of an element ekaaluminium, III, 5, $El=68$, and were afterwards verified when the metal termed 'gallium' was discovered. So also the properties of scandium corresponded with those predicted for ekaboron.¹⁵

Thus uranium, for example, was considered as trivalent, $U=120$; but as such it did not correspond with the periodic law. I therefore proposed to double its atomic weight— $U=240$, and the researches of Roscoe, Zimmermann, and others justified this alteration. It was the same with cerium, whose atomic weight it was necessary to change according to the periodic law. I therefore determined its specific heat, and the result I obtained was verified by the new determinations of Hillebrand. I then corrected certain formulæ of the cerium compounds, and the researches of Rammelsberg, Brauner, Cleve, and others verified the proposed alteration. It was necessary to do one or the other—either to consider the periodic law as completely true, and as forming a new instrument in chemical research, or to refute it. Acknowledging the method of experiment to be the only true one, I myself verified what I could, and gave every one the possibility of proving or confirming the law, and did not think, like L. Meyer (*Liebig's Annalen, Suppl. Band 7, 1870, 364*), when writing about the periodic law, that 'it would be rash to change the accepted atomic weights on the basis of so uncertain a starting-point.' ('Es würde voreilig sein, auf so unsichere Anhaltspunkte in eine Aenderung der bisher angenommenen Atomgewichte vorzunehmen.') In my opinion, the basis offered by the periodic law had to be verified or refuted, and experiment in every case verified it. The starting-point then became general. No law of nature can be established without such a method of testing it. Neither De Chancourtois, to whom the French ascribe the discovery of the periodic law, nor Newlands, who is put forward by the English, nor L. Meyer, who is now cited by many as its founder, ventured to foretell the *properties* of undiscovered elements, or to alter the 'accepted atomic weights,' or, in general, to regard the periodic law as a new, strictly-established law of nature, as I did from the very beginning (1869), and therefore the *regularities* observed by them, which moreover were then unknown to me, can only be considered as a preparative to the discovery of the law. So the way was prepared for the laws of spectroscopy before Kirchhoff, for the mechanical theory of heat before Meyer, Joule, and Clausius, and even for the discoveries essentially belonging to Lavoisier and Newton before they took the matter in hand. In clothing my modest labours with such great names and examples I only wish to protect myself from those reproaches to which I should be subject did I not touch on the history of the birth of the periodic law, for much has been written about it since the properties of gallium, scandium, and germanium established this law as a new truth, permitting the invisible to be seen and the unknown known.

¹⁴ When, in 1871, I wrote a paper on the application of the periodic law to the determination of the properties of yet undiscovered elements, I did not think I should live to see the verification of this consequence of the law, but such was to be the case. Three elements were described—ekaboron, ekaaluminium, and ekasilicon—and now, after the lapse of twenty years, I have had the great pleasure of seeing them discovered and named after those three countries where the rare minerals containing them are found, and where they were discovered—Gallia, Scandinavia, and Germany.

¹⁵ Taking indium, which occurs together with zinc, as our example, we will show the substance of the method employed. The equivalent of indium to hydrogen in its oxide is 37.7—that is, if we suppose its composition to be like that of water; then $In=37.7$, and the oxide of indium is In_2O . The atomic weight of indium was taken as double the equivalent—that is, indium was considered to be a bivalent element—and $In=2 \times 37.7=75.4$. If indium only formed an oxide, RO , it should be placed in the II. group. But in this

6. As a true law of nature is one to which there are no exceptions, therefore the periodic dependence of the properties and the atomic weights of the elements gives a *new means for determining the atomic weight* or valency when the equivalent of an element is known. To several elements atomic weights had been given without any very accurate foundation, and to these no other means could as yet be applied for determining the true atomic weight. At the time (1869) when the periodic law was first proposed there were not a few such elements. It became possible to learn their true atomic weights, which were verified by later researches. Among the elements thus concerned were indium, uranium, cerium, yttrium, and others.

7. The periodic variability of the properties of the elements in dependence on their masses presents a distinction from other aspects of periodic dependences (as, for example, the sines of angles vary periodically and successively with the growth of the angles, or the temperature of the atmosphere with the course of time by yearly and daily periods), in that the masses of the atoms do not increase uninterruptedly, but by bounds; that is, according to the law of multiple proportions (Dalton's), there not only are not but there cannot be any transitive or intermediate elements between two

case it appears that there would be no place for indium in the system of the elements, because the positions II., 5 = Zn = 65 and II., 6 = Sr = 87 were already occupied by known elements, and according to the periodic law an element with an atomic weight 75 could not be bivalent. As neither the vapour density nor the specific heat, nor even the isomorphism (the salts of indium crystallise with great difficulty) of the compounds of indium were known, there was no reason for considering it to be a bivalent metal, and therefore it might be looked on as trivalent, quadrivalent, &c. If it be trivalent, then $\text{In} = 3 \times 37.5 = 112.5$, and the composition of the oxide In_2O_3 , and of its salts InX_3 . In this case it at once falls into its place in the system, namely, in the III. group and 7th series, between Cl=112 and Sn=118, as an analogue of aluminium or dialuminium (dvi=2 in Sanskrit). All the properties observed in indium correspond with this position; for example, the density, cadmium = 8.6, indium = 7.4, tin = 7.2; the basic properties of the oxides CdO , In_2O_3 , SnO_2 , successively vary, so that the properties of In_2O_3 are intermediate between those of CdO and SnO_2 or Cd_2O_3 and Sn_2O_4 . The fact of indium belonging to the III. group has been confirmed by the determination of its specific heat, and also by the fact that indium forms alums like aluminium, and therefore belongs to the same group.

The same kind of considerations necessitated taking the atomic weight of titanium as nearly 48, and not as 52, the figure derived from many analyses, and of Te=125, and not 128. And both these corrections, made on the basis of the law, have now been confirmed, for Thorpe and Brauner respectively, by a series of careful experiments, found the atomic weights of titanium and tellurium to be those foreseen by the periodic law. Notwithstanding that previous analyses gave Os=199.7, Ir=198, and Pt=187, the periodic law shows, as I remarked in 1871, that the atomic weights should rise from osmium to platinum and gold, and not fall. Many recent researches, and especially those of Seubert, have fully verified this statement, based on the law. Thus a true law of nature anticipates facts, foretells magnitudes, gives a hold on nature, and leads to improvements in the methods of research, &c.

neighbouring ones (for example, $K=39$ and $Ca=40$, or $Al=27$ and $Si=28$, or $C=12$ and $N=14$, &c.). As in a molecule of a hydrogen compound there may be either one, as in HF , or two, as in H_2O , or three, as in NH_3 , &c., atoms of hydrogen, but as there cannot be molecules containing $2\frac{1}{2}$ atoms of hydrogen to one atom of an element, so there cannot be any element intermediate between N and O , with an atomic weight greater than 14 or less than 16. The nature of the periodic function of the elements is restricted by the fact that no atom retains more than 4 atoms of hydrogen, and no two atoms of an element more than 8 atoms of oxygen. This determines the eight groups of the elements.

8. The essence of the notions giving rise to the periodic law consists in a general physico-mechanical principle which recognises the correlation, transmutability, and equivalence of the forces of nature. Gravitation, attraction at small distances, and many other phenomena, are in direct dependence on the mass of matter. One cannot, therefore, but think that chemical forces also depend on mass. A dependence is shown, because the properties of elements and compounds are determined by the masses of the atoms of which they are formed. The weight of a molecule, or its mass, determines, as we have seen, many of its properties independently of its composition. Thus carbonic oxide, CO , and nitrogen, N_2 , are two gases having the same molecular weight, and many of their properties (density, liquefaction, specific heat, &c.) are similar or nearly similar. The differences dependent on the nature of a substance play a secondary part, and form magnitudes of another order. So also the properties of atoms are mainly determined by their mass or weight. Only in this case there is a peculiarity in the dependence of the properties on the mass, for this *dependence is determined by a periodic law*. As the mass increases the properties at first successively and regularly vary, and then return to their original magnitude and recommence a fresh period of variation like the first. Nevertheless, here as in other cases a small variation of the mass of the atom generally leads to a small variation of properties, and determines differences of a second order. The atomic weights of cobalt and nickel, of rhodium, ruthenium, and palladium, and of osmium, iridium, and platinum, are very close to each other and their properties are also very much alike—the differences are not very perceptible. And if the properties of atoms form a function of their weight, then many notions which have more or less rooted themselves in chemistry must suffer change and be developed and worked out in the sense of this deduction, because the common idea of the chemical elements regards their atoms as independent and

individual, and considers that they evince their independent influence as determined by the *nature* of the atoms. Instead of this idea of the nature of the elements, one of *their mass* must now be established, and consequently it is necessary to consider, not the influence of an element taken individually, but to compare its influence on the one hand with that of the elements which, in their masses, stand close to it, and on the other hand with the elements belonging to the same group but to a different period. Many chemical deductions then acquire a new sense and significance, and a regularity is observed where it would otherwise escape attention. This is seen particularly clearly in the physical properties, to the consideration of which we shall afterwards turn, and we will now point out that first Gustavson (Chap. X. Note 28^b) and then Potilitzin (Chap. XI. Note 66) demonstrated the direct dependence of the reactive power on the atomic weight and that fundamental property which is expressed in the forms of their compounds, whilst in a number of other cases the purely chemical relations of elements proved to be in connection with their periodic properties. As an instance in question, it may be mentioned that Carnelley remarked a dependence of the decomposability of the hydrates on the position of the elements in the periodic system, whilst L. Meyer, Willgerodt, and others established a connection between the atomic weight or the position of the metals in the periodic system, and their property of serving as mediums in the transference of the halogens to the hydrocarbons.¹⁶ Keeping our attention in the same direction, determined by the periodic law, we see that the most widely distributed elements in nature are those with small atomic weights, whilst in organisms the lightest elements exclusively predominate (hydrogen, carbon, nitrogen, oxygen), whose small mass facilitates those transformations which are proper to organisms. Poluta (of Kharkoff), C. C. Botkin, Blake, and others even discovered a correlation between the physiological action of salts and other reagents on organisms, and

¹⁶ Meyer, Willgerodt, and others, guided by the fact that Gustavson and Friedel had remarked that metalepsis rapidly proceeds in the presence of aluminium, investigated the action of nearly all the elements in this respect. For example, they took benzene, added the metals to be experimented on to it, and passed chlorine through the liquid in diffused light. When, for instance, sodium, potassium, barium, &c., are taken, there is no action on the benzene—that is, hydrochloric acid is not disengaged; but if aluminium, gold, or, in general, any metal having this power of aiding chlorination (Halogen-fiberträger), is employed, then the action is clearly seen from the volumes of hydrochloric acid evolved (especially if the metallic chloride formed is soluble in benzene). Thus, in the I. group, and in general among the even and light elements, there are none capable of serving as agents of metalepsis; but aluminium, gallium, indium, antimony, tellurium, and iodine, which are contiguous members in the periodic system, are excellent transmitters (carriers) of the halogens.

the positions occupied in the periodic system by the metals contained by them.¹⁷

As, from the essence of the matter, the physical properties must be in dependence on the composition of a substance and the nature of the elements forming it, so for them also one must expect a dependence on the atomic weight of the component elements, and consequently also on their periodic distribution. We shall meet with repeated proofs of this in the further exposition of our treatise, and for the present will content ourselves with citing the discovery by Carnelley in 1879 of the dependence of the magnetic properties of the elements on the position occupied by them in the periodic system. Carnelley showed that all the elements of the *even series* (beginning with lithium, potassium, rubidium, caesium) belong to the number of magnetic (paramagnetic) substances; for example, according to Faraday and others, C, N, O, K, Ti, Cr, Mn, Fe, Co, Ni, Rh, Pd, Ce, Os, Ir, Pt are magnetic. And the elements of the *uneven series are diamagnetic*, H, Na, Si, P, S, Cl, Cu, Zn, As, Se, Br, Ag, Cd, Sn, Sb, I, Au, Hg, Tl, Pb, Bi.

Then Carnelley showed that the *melting-point* of elements varies periodically, as is seen by Table III., where all the most trustworthy data are collected, and those which are of the highest and least significance are clearly seen.¹⁸ A like dependence is found on com-

¹⁷ The periodic relations enumerated above appertain to the real elements, and not to the elements in the isolated state as we know them; and it is very important to note this, because the periodic law refers to the real elements, inasmuch as the atomic weight is proper to the real element and not to the isolated element, to which, as to a compound, a molecular weight is proper. Physical properties are chiefly determined by the properties of molecules, and only indirectly depend on the properties of the atoms forming the molecules. For this reason the periods, which are clearly and quite distinctly expressed—for instance, in the forms of combination—become to some extent involved (complicated) in the physical properties of their members. Thus, for instance, besides the *maxima* and *minima* corresponding with the periods and groups, new molecules appear; thus, as regards the melting-point of germanium, a local maximum appears, which was, however, foreseen by the periodic law when the properties of germanium (ekasilicon) were forecast.

¹⁸ It is evident that many of the figures, especially those exceeding 1000, have been determined with but little exactitude, and some (between brackets) are given by me only on the basis of rough and comparative determinations, which I have calculated from the melting-points of silver and platinum, now established by many observers. Besides the large periods whose maxima correspond with carbon, silicon, titanium, ruthenium (?), and osmium (?), there are also small periods in the melting-points, and their maxima correspond with sulphur, arsenic, antimony. The minima correspond with the halogens and metals of the alkalis. In the column following the melting-points are given the coefficients of linear expansion (chiefly according to Fizeau) in order to direct attention to the connection between these magnitudes and the melting points. Raoul Pictet expressed this connection by the fact that he found the product $\alpha(t + 273)^{3/2} A d$ to be nearly constant for all elements in the free state, and nearly equal to 0.045, and being the coefficient of linear expansion, $t + 273$, the melting-point calculated from the absolute zero (-273°), and $\sqrt[3]{A} d$, the mean distance between the atoms, if A is the atomic weight and

paring the melting-points of the metallic chlorides, many of which were re-investigated for this purpose by Carnelley.¹⁹

d the sp. gr. of an element. Although the above product is not strictly constant (for example, for tin it is less than 0.03), nevertheless Pictet's rule gives an idea of the bond between magnitudes which ought to have a certain connection with each other.

¹⁹ The melting-points (and boiling-points, in brackets) of the following chlorides are known, and a certain regularity is seen to exist in them, although the number of data is insufficient for its generalisation—

LiCl 598°	BeCl ₂ 600°	BCl ₅ -20°
NaCl 772°	MgCl ₂ 708°	AlCl ₃ 187°
KCl 734°	CaCl ₂ 719°	ScCl ₃ ?
{ CuCl 434°	ZnCl ₂ 262°	GaCl ₃ 76°
{ (993°)	(680°)	(217°)
AgCl 451°	CdCl ₂ 541°	InCl ₃ ?
{ TiCl 427°	PbCl ₂ 498°	BiCl ₃ 227°
{ (713°)	(908°)	

We will also enumerate the following data, which are not void of interest for comparison: HCl (-112°) (-102°); RbCl 710°, SrCl₂ 825°, CsCl 631°, BaCl₂ 860°, SbCl₃ 78° (223°), TeCl₂ 209° (327°), ICl 27°, HgCl₂ 276° (303°), FeCl₃ 306°, NbCl₅ 194° (240°), TaCl₅ 211° (242°), WCl₆ 190°. The melting-points of the bromides and iodides are higher or lower than those of the corresponding chlorides, according to the atomic weight of the element and number of atoms of the halogen, as is seen from the following examples:—1. KCl 734°, KBr 699°, KI 684°; 2. AgCl 454°, AgBr 427°, AgI 527°; 3. PbCl₂ 498° (900°), PbBr₂ 499° (861°), PbI₂ 383° (906°); 4. SnCl₄ below -20° (114°), SnBr₂ 30° (201°), SnI₄ 146° (295°).

Laurie (1882) also observed a periodicity in the *amount of heat* developed in the formation of the chlorides, bromides, and iodides (fig. 79), as it is seen from the following




FIG. 79.—Laurie's diagram for expressing the periodic variation of the heat of formation of the chlorides. The atomic weights from 0 to 210 are laid along the abscissæ, and the amounts of heat from 0 to 220 thousand calories evolved in the combination with Cl₂ (*i.e.* with 71 parts of chlorine) are laid along the ordinates. The apexes of the curve correspond to Li, Na, K, Rb, Cs, and the lower extremities with F, Cl, Br, and I.

figures, where the heat developed is expressed in thousands of calories, and referred to a molecule of chlorine, Cl₂, so that the heat of formation of KCl is doubled, and that of SnCl₄ halved, &c.: Na 195 (Ag 59, Au 12), Mg 151 (Zn 97, Cd 93, Hg 63), Al 117, Si 79 (Sn 64), K 211 (Li 187), Ca 170 (Sr 185, Ba 194), whence it is seen that the greatest

There is no doubt that many other physical properties will, when further studied, also prove to be in periodic dependence on the atomic weights, but at present only a few are known with any completeness, and we will linger over the one which is the most easily and frequently determined—namely, the *specific gravity* in a solid and liquid state, the more especially as its connection with the chemical properties and relations of substances is shown at every step. Thus, for instance, of all the metals those of the alkalis, and of all the non-metals the halogens, are the most energetic in their reactions, and they have the least specific gravity among the adjacent elements, as is seen in Table III. Such are sodium, potassium, rubidium, cesium among the metals, and chlorine, bromine, and iodine among the non-metals; and as such unenergetic metals as iridium, platinum, and gold (and even charcoal or the diamond) have the highest specific gravity among the elements near to them in atomic weight, therefore the degree of the condensation of matter evidently influences the course of the transformations proper to a substance, and furthermore this dependence on the atomic weight is of a clearly periodic character. In order to account for this to some extent, one may imagine that the lightest elements are porous, and, like a sponge, are easily penetrated by other substances, whilst the heavier elements are more compressed, and give way with difficulty to the insertion of other elements. These relations are best understood when instead of the specific gravities referring to a unit of volume,²⁰ the *atomic volumes of the elements*—that is, the quotient A/d of

amount of heat is evolved by the metals of the alkalis, and that in each period it falls from them to the halogens, which evolve very little heat in combining together.

In this respect it may not be superfluous to remark (1) that Thomsen, whose results I have employed above, already saw a correlation in the calorific equivalents of analogous elements, although he did not remark their periodic variation; (2) that the uniformity of many thermochemical deductions must gain considerably by the application of the periodic law, which evidently repeats itself in calorimetric data, and if these data frequently lead to true forecasts, this is due to the periodicity of the thermal, as well as of many other properties, as Laurie remarked; and (3) that the heat of formation of the oxides is also subject to a periodic dependence which differs from that of the heat of formation of the chlorides, in that the greatest quantity corresponds with the bivalent metals of the alkaline earths (magnesium, calcium, strontium, barium), and not with the univalent metals of the alkalis, as is the case with chlorine, bromine, and iodine. This circumstance is probably connected with the fact that chlorine, bromine, and iodine are univalent elements, and oxygen bivalent.

²⁰ Having occupied myself since the fifties (my dissertation for the degree of M.A. concerned the specific volumes, and is partially printed in the *Russian Mining Journal* for 1856) with the problems concerning the relations between the specific gravities and volumes, and the chemical compositions of substances, I am inclined to think that the direct investigation of specific gravities gives essentially the same results as the investigation of specific volumes, only that the latter are more graphic. Table III. of the periodic properties of the elements clearly illustrates this. Thus, for those members whose volume is the greatest among the contiguous elements, the specific gravity is least

the atomic weight A by the specific gravity d —are taken for comparison. As, according to the whole sense of the atomic doctrine, the actual matter of a substance does not fill up its whole cubical contents, but is surrounded by a medium (ethereal, as is often imagined), like the stars and planets which travel in the space of the heavens and fill it, with greater or less intervals, so the quotient A/d only expresses the *mean volume* corresponding to the sphere of the atoms, and therefore $\sqrt[3]{A/d}$ is the *mean distance between the centres of the atoms*. For compounds whose molecules weigh M , the mean magnitude of the atomic volume is obtained by dividing the mean molecular volume M/d by the number of atoms n in the molecule.²¹ The above relations may easily be expressed in this sense by comparing the atomic volumes. Those comparatively light elements which easily and frequently enter into reaction have the greatest atomic volumes: sodium 23, potassium 45, rubidium 57, caesium 71, and the halogens about 27; whilst with those elements which enter into reaction with difficulty, the mean atomic volume is small; for carbon in the form of the diamond it is less than 4, as charcoal about 6, nickel and cobalt less than 7, iridium and platinum about 9. The remaining elements having atomic weights and properties intermediate between those elements mentioned above have also intermediate atomic volumes. Therefore *the specific gravities and specific volumes of solids and liquids*, like all their other properties, *stand in periodic dependence on the atomic weights*, as is seen in Table III., where both A (the atomic weight) and d (the specific gravity), and A/d (specific volumes of the atoms) are given.

Thus we find that in the periods beginning with lithium, sodium, potassium, rubidium, caesium, and ending with fluorine, chlorine, bromine, iodine, the extreme members (energetic elements) have a small density and large volume, whilst the intermediate substances gradually increase in density and decrease in volume—that is, as the

—that is, the periodic variation of both properties is equally evident. In passing, for instance, from silver to iodine we have a successive decrease of sp. gr. and successive increase of sp. volume. The periodic alternation of the rise and fall of the sp. gr. and sp. vol. of the free elements was communicated by me in August 1869 to the Moscow Meeting of Russian Naturalists. In the following year, 1870, L. Meyer's paper, also respecting the sp. vol. of the elements, appeared.

²¹ In my opinion the mean volume of the atoms of compounds deserves more attention than has yet been paid to it. I may point out, for instance, that for feebly energetic oxides the mean volume of the atom is generally nearly 7; for example, the oxides SiO_2 , Sc_2O_3 , TiO_2 , V_2O_5 , as well as ZnO , Ga_2O_3 , GeO_2 , ZrO_2 , In_2O_3 , SnO_2 , Sb_2O_3 , &c., whilst the mean volume of the atom of the alkali and acid oxides is greater than 7. Thus we find in the magnitudes of the mean volumes of the atom in oxides and salts both a periodic variation and a connection with their energy of essentially the same character as occurs in the case of the free elements.

atomic weight increases the density rises and falls, again rises and falls, and so on. Furthermore, the energy decreases as the density rises, and the greatest density is proper to the atomically heaviest and least energetic elements.

In order to explain the relation between the volumes of the elements and of their compounds, Table III. gives the densities and volumes of the higher saline oxides of the majority of the elements arranged in the same order as in the case of the elements. For convenience of comparison the volumes of the oxides are all calculated per two atoms of an element combined with oxygen. For example, the density of $\text{Al}_2\text{O}_3 = 4.0$, weight $\text{Al}_2\text{O}_3 = 102$, volume $\text{Al}_2\text{O}_3 = 25.5$. Whence it is directly seen that, knowing the volume of aluminium to be 11 in the formation of aluminium oxide, 22 of its volumes give 25.5 volumes of oxide.

Above all a distinct periodicity may also be observed with respect to the specific gravities and volumes of the higher saline oxides. So in each period, beginning with the alkali oxides, the specific gravity first rises, reaches a maximum, and then falls on passing to the acid oxides, and again becomes a minimum about the halogens. But it is especially important to turn attention to the fact that the volume of the alkali oxides is less than that of the metal contained in them, which is also expressed in the tenth column, giving this difference per one atom of oxygen.²² Thus 2 atoms of sodium, or 46 volumes, give 24 volumes of Na_2O , and about 37 volumes of 2NaHO —that is, the oxygen and hydrogen in distributing themselves in the medium of sodium, have not only not increased the distance between its atoms, but have brought them nearer together, have drawn them together by the force of their great affinity, and evidently by reason of the small mutual attraction of the atoms of sodium. Such metals as aluminium and zinc, in combining with oxygen and forming oxides of feeble salt-forming capacity, hardly vary in volume, but the common metals and non-metals, and especially those forming acid oxides, always give an increased volume when oxidised—that is, the atoms are set further apart in order to make room for the oxygen. The oxygen in them does not compress

²² The volume of oxygen (Table III. column 10) is evidently a variable quantity, forming a distinctly periodic function of the atomic weight and type of the oxide, and therefore the efforts which were formerly made to find the volume of the atom of oxygen in the volumes of its compounds may be considered to be futile. But as a distinct contraction takes place in the formation of oxides, if the volume of an oxide is frequently less than the volume in the free state of the element contained in it, one would think that the volume of oxygen in a free state is between 12 and 15, judging from the figures given in the second column, and therefore the specific gravity (Vol. I. p. 162) of solid oxygen in a free state would be about 0.9.

the molecule as in the alkalis; it is therefore comparatively easily disengaged.

As the volumes of the chlorides, organo-metallic and all other corresponding compounds also vary in a like periodic succession with a change of elements, it is evidently possible to indicate the properties of substances yet uninvestigated by experimental means, and even those of yet undiscovered elements. It was possible by following this method to foretell, on the basis of the periodic law, many of the properties of scandium, gallium, and germanium, which were verified with great accuracy after these metals had been discovered.²³ Therefore, the periodic law has not only embraced the mutual relations of the elements and expressed their analogy, but has also to a certain extent subjected to law the doctrine of the types of the compounds formed by the elements; has enabled us to see a regularity in the variation of all chemical and physical properties of elements and compounds, and has rendered it possible to foretell the properties of elements and compounds yet uninvestigated by experimental means; it therefore prepares the ground for the building up of atomic and molecular mechanics.²⁴

²³ As an example we will take indium oxide, In_2O_3 . Its sp. gr. and sp. vol. should be the mean of those of cadmium oxide, Cd_2O_3 , and stannic oxide, Sn_2O_4 , as indium stands between cadmium and tin. Thus in the seventies it was already evident that the volume of indium oxide should be about 38, and its sp. gr. about 7.2, which was confirmed by the determinations of Nilsson and Pettersson (7.179) made in 1880.

²⁴ As the distance between, and the volumes of, the molecules and atoms of solids and liquids certainly enter into the data for the solution of the problems of molecular mechanics, which as yet has only been worked out to any extent for the gaseous state, therefore the study of the specific gravity of solids, and especially of liquids, has long since had a vast literature. With respect to solids, however, a great difficulty is met with, owing to the specific gravity varying not only with a change of isomeric state (for example, for silica in the form of quartz = 2.65, and in tridymite = 2.2) but also directly under mechanical pressure (for example, in a crystalline, cast, and forged metal), and even with the extent to which they are powdered, &c., which influences are imperceptible in liquids.

Without going into further details, we may add to what has been said above that the conception of specific volumes and atomic distances has formed the subject of a large number of researches, but as yet it is only possible to mention a few generalisations given by Dumas, Kopp, and others, which are mentioned and amplified by me in my work cited in Note 20, and in my memoirs on this subject.

1 Analogous compounds and their isomorphs have frequently nearly the same molecular volumes.

2. Other compounds, analogous in their properties, exhibit molecular volumes which increase with the molecular weight.

3. When a contraction takes place in combination in a gaseous state, then contraction is in the majority of instances also to be observed in the solid or liquid state—that is, the sum of the volumes of the reacting substances is greater than the volume of the resultant substance or substances.

4. In decomposition the reverse takes place to that which occurs in combination.

5. In substitution (when the volumes in a state of vapour do not vary) a very small

change of volume generally takes place—that is, the sum of the volumes of the reacting substances is almost equal to the sum of the resultant substances.

6. Hence it is impossible to judge the volume of the component substances from the volume of a compound, although it is possible to do so from the product of substitution.

7. The replacement of H_2 by sodium, Na_2 , and by barium, Ba , as well as the replacement of SO_4 by Cl_2 , scarcely changes the volume, but the volume increases with the replacement of Na by K , and decreases with the replacement of H_2 by Li_2 , Cu , and Mg .

8. There is no foundation for comparing volumes in a solid and liquid state at the so-called corresponding temperatures—that is, at temperatures at which the vapour tension is equal in each case. The comparison of volumes at the ordinary temperature is sufficient for finding a regularity in the relations of volumes (this deduction was developed with particular detail by me in 1856).

9. Many (Persean, Schröder, Löwig, Playfair and Joule, Baudrimont, Einhardt) have sought in vain for a multiple proportion in the specific volumes of solids and liquids.

10. The truth of the above is seen very clearly in comparing the volumes of polymeric substances. The volumes of their molecules are equal in a state of vapour, but are very different in a solid and liquid state, as is seen from the close resemblance of the specific gravities of polymeric substances. But as a rule the most complex polymerides are denser than the simpler.

11. We already know that the oxides of light metals have a less volume than the metals, whilst that of magnesium hydroxide is considerably greater, which is explained by the stability of the former and instability of the latter. In proof of this we may cite that the volume of barium (36) is greater than that of its stable hydroxide (sp. gr. 4.5, vol. 30) as well as of those of the true alkalis. The volumes of the salts of magnesium and calcium are greater than the volume of the metal, with the single exception of the fluoride of calcium. With the heavy metals the volume of the compound is always greater than the volume of the metal, and moreover, for such compounds as silver iodide, AgI ($d = 5.7$), and mercuric iodide, HgI_2 ($d = 6.2$, and the volumes of the compounds 41 and 73), the volume of the compound is greater than the sum of the volumes of the component elements. Thus the sum of the volumes $Ag + I = 36$, and the volume of $AgI = 41$. This stands out with particular clearness on comparing the volumes $K + I = 71$ with the volume of KI , which is equal to 54, because its density = 3.06.

12. In such kinds of combinations, between solids and liquids, as are solutions, alloys, isomorphous mixtures, and similar feeble chemical compounds, the sum of the reacting substances is always very nearly that of the resulting substance, but here the volume is either slightly larger or smaller than the original; speaking generally, the amount of contraction depends on the force of affinity acting between the combining substances.

CHAPTER XVI

ZINC, CADMIUM, AND MERCURY

THESE three metals give, like magnesium, oxides RO , which form feebly energetic bases, and like magnesium they are volatile. The volatility increases with the atomic weight. Magnesium can be distilled at a white heat, zinc at a temperature of about 930° , cadmium about 770° , and mercury about 360° . Their oxides, RO , are more easily reducible than magnesia, and mercuric oxide is the most easily reducible. The properties of their salts, RX_2 , are very similar to the properties of MgX_2 . Their solubility, power of forming double and basic salts, and many other qualities are in many respects identical with those of MgX_2 . The greater or less ease with which they are oxidised, the instability of their compounds, the density of the metals and their compounds, their scarcity in nature, and many other properties, gradually change with the increase of atomic weight, as might be expected from the law of periodicity. Their principal characteristics, compared with magnesium, already find expression in the fact that zinc, cadmium, and mercury are heavy metals.

Zinc stands nearest to magnesium in atomic weight and in properties. Thus zinc sulphate, or white vitriol, easily crystallises with seven molecules of water, $ZnSO_4 \cdot 7H_2O$. It is isomorphous with Epsom salts, and parts with difficulty with the last molecule of water; it forms double salts—for instance, $ZnK_2(SO_4)_2 \cdot 6H_2O$, exactly as magnesium sulphate does.¹ *Zinc oxide*, ZnO , is a white powder, almost in-

¹ Zinc sulphate is often obtained as a bye-product—for instance, in the action of galvanic batteries containing zinc and sulphuric acid. When the anhydrous salt is heated it forms zinc oxide, sulphurous anhydride, and oxygen. The solubility in 100 parts of water at $0^\circ = 43$, $20^\circ = 53$, $40^\circ = 63\frac{1}{2}$, $60^\circ = 74$, $80^\circ = 84\frac{1}{2}$, $100^\circ = 95$ parts of anhydrous zinc sulphate—that is to say, it is nearly expressed by the formula $43 + 0.52t$.

An admixture of iron is often found in ordinary sulphate of zinc in the form of ferrous sulphate, $FeSO_4$, isomorphous with the zinc sulphate. In order to separate it, chlorine is passed through the solution of the impure salt (the ferrous salt then passes into ferric), the solution is then boiled, and zinc oxide is afterwards added, which, after some time has elapsed, precipitates all the ferric oxide. Ferric oxide of the form R_2O_3 is displaced by zinc oxide of the form RO .

soluble in water,² like magnesia, from which, however, it is distinguished by its solubility in solutions of sodium and potassium hydroxides.³ Zinc chloride is decomposed by water, combines with ammonium chloride, potassium chloride, &c., just like magnesium chloride.⁴ Altogether the resemblance between zinc and magnesium compounds—particularly when

² Zinc oxide is obtained both by the combustion and oxidation of zinc, and also by the ignition of some of its salts—for instance, those of carbonic and nitric acids; it is likewise precipitated by alkalis from a solution of ZnX_2 , in the form of a gelatinous hydroxide. The oxide produced by roasting zinc blende (by burning in the air when the sulphur is converted into sulphurous anhydride) contains various impurities. For purification, the oxide is mixed with water, and the sulphurous anhydride formed by roasting the blende is passed through it. Zinc bisulphite, $\text{ZnSO}_3 \cdot \text{H}_2\text{SO}_3$, then passes into solution. If a solution of this salt be evaporated, and the residue ignited, zinc oxide, free from many of its impurities, will remain.

Zinc oxide is a light white powder, used as a paint instead of *white lead*; the basic salt, corresponding with magnesia alba, is used for the same purpose (Vol. I. p. 592).

³ For the solution of one part of the oxide 55:100 parts of water are required. Nevertheless, even in such a weak solution, zinc oxide (hydroxide, ZnH_2O_2) changes the colour of red litmus paper. Zinc oxide is obtained in the wet way by adding an alkali hydroxide to a solution of a zinc salt—for instance: $\text{ZnSO}_4 + 2\text{HKO} = \text{K}_2\text{SO}_4 + \text{ZnH}_2\text{O}_2$. The gelatinous precipitate of zinc hydroxide is *soluble* in an excess of alkali, which clearly distinguishes it from magnesia. This solubility of zinc hydroxide in alkalis is due to the power of zinc oxide to form a compound, although an unstable one, with alkalis—that is to say, points to the fact that zinc oxide already partly belongs to the intermediate oxides. The oxides of the metals above-mentioned do not show this property. The property which metallic zinc itself has of dissolving in caustic alkali with the disengagement of hydrogen (the solution is facilitated by contact with platinum or iron) depends on the formation of such a compound of the oxides of zinc and the alkali metals. The solution of zinc hydroxide, ZnH_2O_2 , in potash (in a strong solution), proceeds when these hydrates are taken in proportion to $\text{ZnH}_2\text{O}_2 + \text{KHO}$. If such a solution be evaporated to dryness, water extracts only caustic potash from the fused residue. When a solution of zinc hydroxide in strong alkali is mixed with a large mass of water, nearly all the oxide of zinc is precipitated; and, therefore, in weak solutions, a large quantity of the alkali is required to effect solution, which points to the decomposition of the zinc-alkali compounds by water. If strong alcohol be added to a solution of zinc oxide in sodium hydroxide, the crystallohydrate, $2\text{Zn}(\text{OH})(\text{ONa}) \cdot 7\text{H}_2\text{O}$, separates.

⁴ *Zinc chloride*, ZnCl_2 , is generally used in the arts in the form of a solution obtained by dissolving zinc in hydrochloric acid. This solution is used for soldering metals. The reason why it is thus employed is understood from its properties. When evaporated the combination with the water of crystallisation first separates, which, however, on being further heated, loses all traces of water, and forms an oily mass of anhydrous salt which solidifies on cooling. This substance melts at 250° , and commences to volatilise at about 400° . The soldering of metals—that is, the introduction of an easily-fusible metal between two contiguous metallic objects—is hindered by any film of oxide upon them; and, as heated metals easily oxidise, they are therefore difficult to solder. Zinc chloride is used to prevent the oxidation. It fuses on being heated, and, covering the metal with an oily coating, prevents contact with the air; but even if any oxide has formed, the free hydrochloric acid generally existing in the zinc chloride solution dissolves the oxide formed, and in this way the metallic surface of the metals to be soldered is preserved fit for the adhesion of the liquid solder, which, on cooling, binds the objects together. Much zinc chloride is used also for steeping wood (telegraph-posts and sleepers on railways) in order to preserve them from decaying quickly; this preservative action is in all probability mainly due to the poisonous character of zinc salts (corrosive sublimate is still

both are in solution—is so great that it exceeds the resemblance which exists between magnesium and calcium compounds.

Zinc, like many heavy metals, is often found in nature in combination with sulphur, forming the so-called *zinc blende*,⁵ ZnS . It sometimes exists in large masses, often crystallised in cubes; it is frequently translucent, and has a metallic lustre, although this is not so clearly developed as in many other metallic sulphides with which we shall here-

more poisonous, and a still better agent to preserve wood from decay), because decay is brought about by the action of lower organisms.

The specific gravity of solutions (see my 'Treatise,' p. 50) containing p per cent. of zinc chloride, ZnCl_2 :

$p =$	10	20	30	40	50
$15^\circ/4^\circ =$	1.093	1.184	1.293	1.411	1.554
$ds/dt =$	-3	-5	-7	-8	-9

The last line shows the change of specific gravity for 1° in ten-thousandth parts for temperatures near 15° . More accurate determinations of Cheltzoff, personally communicated by him, led him to conclude that solutions of zinc chloride follow the same laws as the solutions of sulphuric acid, which will be treated in Chapter XX.: (1) from H_2O to $\text{ZnCl}_2, 120\text{H}_2\text{O}$ $s = S_0 + 92.85p + 0.1748p^2$; (2) from thence to $\text{ZnCl}_2, 40\text{H}_2\text{O}$ $s = S_0 + 93.96p - 0.0126p^2$; (3) from thence to $\text{ZnCl}_2, 25\text{H}_2\text{O}$ $s = 11481.5 + 96.45(p - 15.89) + 0.4567(p - 15.89)^2$; (4) from thence to $\text{ZnCl}_2, 10\text{H}_2\text{O}$ $s = 12212.1 + 104.82(p - 23.21) + 0.7992(p - 23.21)^2$; (5) from thence to $p = 65$ p.c. $s = 14606.3 + 140.96(p - 43.05) + 1.4905(p - 43.05)^2$, where s is the specific gravity of the solution at 15° , containing p p.c. of ZnCl_2 by weight, if the water at $4^\circ = 10000$, and where $S_0 = 9991.6$ (specific gravity of water at 15°). The compound of zinc chloride with hydrochloric acid has been mentioned in Vol. I, page 450.

Zinc chloride has a great affinity for water; it is not only soluble in it, but in alcohol, and on being dissolved in water becomes considerably heated, like magnesium and calcium chlorides. Zinc chloride is capable of taking up water, not only in a free state, but also in chemical combination with many substances. Thus, for instance, it is used in organic researches, for removing the elements of water from many of the organic compounds.

When mixed with zinc oxide it forms with remarkable ease a very hard mass of zinc oxychloride, which is applied in the arts; for instance, in painting, to resist the action of water, or for cementing such objects as are destined to remain in water. Zinc oxychloride, $\text{ZnCl}_2, 3\text{ZnO}, 2\text{H}_2\text{O}$ ($= \text{Zn}_2\text{OCl}_2, 2\text{ZnH}_2\text{O}_2$) is also formed from a solution of zinc chloride by the action of a small quantity of ammonia on it after heating the precipitate obtained by the liquid for a considerable time; the admixture of ammonium salts with a mixture of a strong solution of zinc chloride with its oxide makes a similar mass, which does not solidify so rapidly, and is therefore more useful for similar purposes. Moisture and cold do not change the hardened mass of oxychloride, and it also resists the action of many acids, and a heat of 300° , which makes it a useful cement for many purposes. A solution of magnesium chloride with magnesium oxide forms a similar oxychloride. The mass solidifies best when there is an even quantity by weight of zinc in the chloride and oxide, and, therefore, when it has the composition Zn_2OCl_2 . In preparing such a cement, naturally zinc oxide alone may be taken, and the requisite quantity of hydrochloric acid added to it.

⁵ This mineral has been given the name of 'mock-ore,' on account of its having the appearance (considerable density, 4.06, &c.) of ordinary metallic ores; it deceived the first miners, because it did not, like other ores, give metal when simply roasted in air and fused with charcoal. The white zinc oxide, formed by burning the vapours of zinc, was also called 'nihil album,' or 'white nothing,' on account of its lightness.

after become acquainted. The ores of zinc also comprise the carbonate, *calamine*, and silicate, *siliceous calamine*.

Metallic zinc (spelter) is most frequently obtained from the ores containing the carbonate⁶—that is, from *calamine*, which is sometimes found in thick veins : for instance, in Poland, Galicia, in some places on the banks of the Rhine, and in considerable masses in Belgium and England. In Russia beds of zinc ore are met with in Poland and the Caucasus ; but the output is small. In Sweden, as early as the fifteenth century, the Belgian *calamine* was worked up into an alloy of zinc and copper (brass), and Paracelsus produced zinc from *calamine* ; but the technical production of the metal itself, long ago practised in China, only commenced in Europe in 1807 in Belgium, when the Abbé Donnet discovered that zinc was volatile. From that time the production increased until it is now about 140 million kilograms in Germany alone.

The reduction of metallic zinc from its ores is based on the fact that zinc oxide⁷ is easily reduced by charcoal at a red heat : $\text{ZnO} + \text{C} = \text{Zn} + \text{CO}$. The zinc thus obtained is in a finely-divided state and impure, being mixed with other metals reduced with it. The refining depends on the zinc being *converted into vapour* at a white heat, from which it easily passes into a liquid or solid state. The distillation is carried on in earthenware retorts, filled with a mixture of the divided ore and charcoal. The vapours of zinc and gases formed during the reaction escape by means of a pipe leading downwards, and are led to a space where the vapours are




FIG. 80.—Distillation of zinc in a crucible placed in a furnace. *a c*, tubes along which the vapour passes and condenses.

⁶ Let us mention here that by the word *ore* is meant a hard, heavy substance dug out of the earth, which is used in metallurgical works for obtaining the usual heavy metals long known and used. The natural compounds of sodium, or magnesium, are not called ores, because magnesium and sodium have not been long ago obtained in works. The heavy metals, those which are easily reduced and do not easily oxidise, are exclusively those which are directly applied and obtained in works. Ores either contain the metals themselves (for instance, ores of silver or bismuth), and the metals are then in a native state, or else their sulphur compounds (blende, mock-ore, pyrites—as, for instance, galena, PbS ; zinc blende, ZnS ; copper pyrites, CuFeS) or oxides (as the ores of iron), or salts (*calamine*, for instance). Zinc is incomparably rarer than magnesium, and is only well known because it is transformed from its ores into a metal which finds direct use in many branches of industry.

⁷ Ores, when extracted from the earth by the miners, are often enriched by sorting, washing, and other mechanical operations. The sulphurous ores (and likewise others) are then generally roasted. Roasting an ore means heating it to a red heat in air. The

cooled. By this means they do not come into contact with the air, because the neck of the retort is filled with gaseous carbonic oxide, and therefore the zinc does not oxidise, otherwise its vapour would burn in the air. The vapours of zinc, entering into the cooling chamber, condense into white zinc powder or zinc dust. When the neck of the retort is heated, the zinc is obtained in a liquid state, and is cast into plates, in which form it most often enters the market.

Commercial zinc is generally impure, containing a mixture of lead, particles of carbon, iron, and other metals, carried over with the vapours, although they are not volatile at a temperature approaching 1000° . If it is required to obtain pure zinc from the commercial article it is subjected to a further distillation in a crucible with a pipe passing through the bottom, the vapours formed by the heated zinc only having exit through the pipe cemented into the bottom of the crucible. Passing through this pipe, the vapours condense to a liquid, which is collected in a receiver. Zinc thus purified is generally remelted and cast into rods, and in this form is often used for physical and chemical researches where a pure article is required.⁸

Metallic zinc has a bluish-white colour ; its lustre, compared with many other metals, is insignificant. When cast it exhibits a tabular structure. Its specified gravity is about 7—that is, varies from 6.8 to 7.2, according to the degree of compression (for instance, forging, rolling, &c.) to which it has been subjected. It is very ductile, considering its hardness. For this reason it chokes up files when being worked. Its malleability is considerable when pure, but in the ordinary impure condition in which it is sold, at the ordinary temperature it is impossible to roll it, as it breaks easily. At a temperature of 100° , however, it easily undergoes such operations, and can then be drawn into wire or sheets. If heated further it again becomes brittle, and at 200° may be even crushed into powder, so completely

sulphur then burns, and passes off in the form of sulphurous anhydride, SO_2 , and the metal oxidises. The roasting is carried on in order to obtain an oxide instead of a sulphurous compound ; the oxide being reducible by charcoal.

These methods, introduced ages ago, are met with in nearly all metallurgical works for nearly all ores. For this reason the preparatory treatment of zinc blende furnishes zinc oxide ; this is already contained in calamine.

⁸ This zinc, although homogeneous, still contains certain impurities, to remove which it is necessary to obtain some pure zinc salt and transform it into carbonate, which latter is then distilled with charcoal, and, as thin sheets of zinc can only be obtained from very pure metal, they are frequently made use of in cases where pure zinc is required. In order to remove the arsenic from zinc, it was proposed to melt it and mix it with anhydrous magnesium chloride, by which means vapours of zinc chloride and arsenic chloride are formed. Completely pure zinc is made (V. Meyer and others) by decomposing, by means of the galvanic current, a solution of zinc sulphate to which an excess of ammonia has been added.

does it lose its molecular cohesion. It melts at 433° , and distils at 930° .

Zinc does not undergo any change in the atmosphere. Even in very damp air it only becomes slowly coated with a very thin white coating of oxide. For this reason it is available for all objects which are only in contact with air. Therefore sheet zinc may be used for roofing and many other purposes.⁹ This great unchangeability of zinc in the air shows its slight energy with regard to oxygen compared with the metals already mentioned, which are capable of reducing zinc from solutions. But zinc plays this part with regard to the remaining metals—for example, with reference to lead, copper, mercury, &c. Although zinc is an almost unoxidisable metal at the ordinary temperature, it burns in the air on being heated, particularly when in the form of shavings or in the condition of vapour. At the ordinary temperature zinc does not decompose water—at any rate, not if it is in a dense mass. But even at a temperature of 100° zinc begins little by little to decompose water; it easily displaces the hydrogen of acids at the ordinary temperature, and of alkalis on being heated.

In this respect, however, the action of zinc varies a great deal with the degree of its purity. Weak sulphuric acid (corresponding with the composition $\text{H}_2\text{SO}_4, 8\text{H}_2\text{O}$) at the ordinary temperature does not act at all on chemically pure zinc, and even a stronger solution acts very slowly. If the temperature be raised, and particularly if the zinc be previously slightly heated, so as to cover its surface with a film of oxide, chemically pure zinc then acts on sulphuric acid. Thus, for example, one cubic centimetre of zinc in sulphuric acid, having a composition $\text{H}_2\text{SO}_4, 6\text{H}_2\text{O}$, at the ordinary temperature in two hours only dissolves to the extent of 0.018 gram, and at a temperature of 100° about $3\frac{1}{2}$ grams. If we compare this slow action with that rapid evolution of hydrogen which occurs in the case of commercial zinc, we see that the influence of those impurities in the zinc is very great. Every particle of charcoal or iron introduced into the mass of the zinc, and likewise the connection of the zinc with a piece of another electro-negative metal, assists such a dissolution, as all readers of books on physics are well aware. The slowness of the action of sulphuric acid on pure zinc (and likewise on amalgamated zinc) is also explained by the fact that a layer of hydrogen is then on the surface of the

⁹ Cornices and other architectural ornaments, remarkable for their lightness and beauty, are stamped out of sheet zinc. Zinc-roofing does not require painting, but it melts during a conflagration and even burns at a strong heat. Many iron vessels, &c., are covered with zinc ('galvanised') in order to prevent them from rusting.

metal, which prevents contact between the acid and the metal. The addition of cupric sulphate, or particularly a few drops of platinic chloride (the metals are reduced) to the sulphuric acid, greatly accelerates the evolution of the hydrogen, because in this case, as with commercial zinc, galvanic couples are locally formed by the copper or platinum and the zinc, under the influence of which the zinc rapidly dissolves.¹⁰

¹⁰ The action of acids on metallic zinc of various degrees of purity has been the subject of many investigations particularly important with reference to the application of zinc in galvanic batteries, whilst some investigations have direct significance for chemical mechanics, although from many points the matter is not clear. I consider it useful to stop and point out those observations which I find the most complete.

Calvert and Johnson made the following series of observations on the action of sulphuric acid of various degrees of concentration on 2 grams of pure zinc during two hours. In the cold the concentrated acid, H_2SO_4 , does not act, $\text{H}_2\text{SO}_4, 2\text{H}_2\text{O}$ dissolves about 0.002 gram, but principally forms hydrogen sulphide, which is obtained also when the dilution reaches $\text{H}_2\text{SO}_4, 7\text{H}_2\text{O}$, when 0.085 gram of zinc is dissolved. When largely diluted with water, pure hydrogen begins to be disengaged. At 130° mono- and di-hydrated sulphuric acid give sulphurous anhydride, and in two hours dissolve 0.075 and 0.142 gram of zinc. $\text{H}_2\text{SO}_4, 2\text{H}_2\text{O}$ at 130° gives a mixture of hydrogen sulphide and sulphurous anhydride dissolving 0.156 gram of zinc.

Bouchardat showed that if in a vessel made of glass or sulphur dilute sulphuric acid acting on a piece of zinc liberates one part of hydrogen, then the same acid with the same piece of zinc in the same time will liberate 4 parts of hydrogen if the vessel be made of tin—that is, zinc forms a galvanic couple with tin; in a leaden vessel 9 parts of hydrogen are developed, with a vessel of antimony or bismuth 13 parts, silver or platinum 38 parts, copper 50 parts, iron 43 parts. If a salt of platinum is added to the dilute sulphuric acid (1 part of acid and 12 parts of water), Millon determined that the rapidity of the action on the zinc is increased 149 times, and by the addition of copper sulphate is rendered 45 times greater than the action of pure sulphuric acid. The salts which are added are reduced to metals by the zinc, their contact serving to promote the reaction because they form local galvanic currents.

According to the observations of Cailletet, if, at the ordinary pressure, sulphuric acid with zinc liberates 100 parts of hydrogen, then with a pressure of 60 atmospheres 47 parts will be liberated and 1 part at a pressure of 120 atmospheres. With a reduced pressure under the receiver of an air-pump 168 parts are liberated.

Helmholtz showed that a reduced pressure also exercises its influence on galvanic elements.

Debray, Löwel, Snyders, and others showed that zinc liberates hydrogen and forms basic salts and zinc oxide with solutions of many salts—for instance, MCl_n , aluminium sulphate, and alum. Sodium and potassium carbonates scarcely act, because they form a carbonate. The salts of ammonia act more strongly than the salts of potassium and sodium; the zinc remains bright. It is evident that this action is founded on the formation of double salts and basic salts.

The difference with concentration in the rate of the action of sulphuric acid on zinc (containing impurities) under otherwise uniform conditions is in evident connection with the electrical conductivity of the solution and its viscosity, although, when largely diluted, the action is almost proportional to the amount of acid in a known volume of the solution.

Forging, casting the molten metal, and similar mechanical influences change the density and hardness of zinc, and also strongly influence its power of liberating hydrogen from acids (Muhier, Behemann).

Kayander showed (1881) that when magnesium is submitted to the action of acids :

The action of zinc on acids, and the consequent formation of zinc salts, interferes with its application in many cases, particularly for the preservation of liquids either containing, or capable of developing, acid. For this reason zinc vessels ought not to be used for the preparation or preservation of food, as this often contains acids which form poisonous salts with the zinc. Even ordinary water, containing carbonic acid, slowly but surely acts on zinc.

Finally-divided zinc, or *zinc dust*, obtained in the distillation of the metal when the receiver is not heated up to the melting point, on account of its presenting a large surface of contact and containing foreign matter (particularly zinc oxide), has in the highest degree the property of decomposing acids and even water, which it easily de-

(a) the action depends, not on the nature of the acid but on its basicity, (b) the increase of the action is more rapid than the growth of the concentration, and (c) there is a decrease of action with the increase of the coefficient of internal friction and electrical conductivity.

Spring and Aubel (1887) measured the volume of hydrogen disengaged by an alloy of zinc and a small quantity of lead (0.6 p.c.), because the action of acids is then uniform. In order to deal with a known surface, spheres were taken (9.5 millimetres diameter) and cylinders (17 mm. dia.), the sides of which were covered with wax in order to limit the action to the end surfaces. During the commencement of the action of a definite quantity of acid the rapidity increases, attains a maximum, and then declines as the acid becomes exhausted. We annex the results for 5, 10, and 15 per cent. of hydrochloric acid. H denotes the number of cubic centimetres of hydrogen, D the time in seconds elapsing after the zinc spheres have been plunged into the acid. At 15° they obtained:

H=	50	100	200	400	600	800	1000
5 p.c. D=	714	1152	1755	2731	3908	6234	15462
10 p.c. D=	301	455	649	995	1573	2746	6748
15 p.c. D=	106	151	233	440	826	1604	4289

At 35° they obtained:

5 p.c. D=	462	705	1058	1700	2525	4132	8499
10 p.c. D=	96	148	239	460	835	1594	3735
15 p.c. D=	44	64	112	255	505	1011	2457

At 55° they obtained:

5 p.c. D=	178	276	408	699	1164	2105	5093
10 p.c. D=	34	60	113	258	491	970	2457
15 p.c. D=	24	35	58	136	289	610	1593

In consequence of the complex character of the phenomenon, the authors themselves do not recognise their determinations as being absolute, and only give them a relative signification, and in this sense it is remarkable that hydrobromic acid under similar conditions (with an equivalent strength) gives a greater (from 2 to 5 times) rapidity of action than hydrochloric acid, but sulphuric acid a far less (nearly 25 times) velocity. It is also remarkable that during the reaction the metal becomes much more heated than the acid.

Let us observe that zinc dust and zinc itself, when heated with hydrated lime and similar hydrates, disengages hydrogen; this method has even been proposed for obtaining hydrogen for filling war balloons.

composes, particularly if slightly heated. On this account zinc dust is often used in laboratories and factories as a reducing agent. A similar influence of the finely-divided state is also noticed in other metals—for instance, copper and silver—which again shows the close connection between chemical and physico-mechanical phenomena. We must first of all turn to this close connection for an explanation of the widely-spread application of zinc in galvanic batteries, where the chemical (hidden, potential) energy of the acting substances is transformed into (evident, kinetic) galvanic energy, and through this latter into heat, light, or mechanical work.^{10b}

Hermann and Stromeyer, in 1819, showed that *cadmium* is almost always found with zinc, and in many respects resembles it. When distilled, the cadmium volatilises sooner, because it has a lower boiling point. Sometimes the zinc dust obtained by the first distillation of zinc contains as much as 5 per cent. of cadmium. When zinc blende, containing cadmium, is roasted, the zinc passes into the state of oxide, and the cadmium sulphide in the ore oxidises into cadmium sulphate, CdSO_4 , which fairly well resists the action of heat; therefore, if roasted zinc blende be washed with water, a solution of cadmium sulphate will be obtained, from which it is very easy to

^{10b} The relation between chemical action and galvanism is so important, and has already been so much studied, and has of late years given so many new results, that this section of our science ought now to take a prominent part in theoretical (physical) chemistry. In our comparatively short and elementary course, it is not possible to touch on this question, all the more so because even at present it contains many blank spaces with reference to the comprehension of primary phenomena; for instance, the polarisation of the current and the 'transference of the ions,' evident from the disengagement of hydrogen on the copper when a piece of zinc is plunged into sulphuric acid, in which copper is in metallic contact with the zinc. However, in latter times, thanks to the experienced investigations of Hittorf, Kohlrausch, and others, and the theoretical considerations of Clausius, Thomson, and others, the mist which enveloped this region begins to lighten; still Faraday already clearly saw that the galvanic current is nothing more than a chemical movement under a changed aspect. I only consider it possible to say a few words about this subject.

From the experiments of Favre, Thomson, Berthelot, Cheltzoff, and others on the quantity of heat developed in a closed circuit, one ought to conclude that the electromotive force, or its faculty of doing a certain work E , is *proportional* to the whole quantity of heat Q produced by the reaction serving as the source of the current. If E be expressed in volts and Q in thousands of heat units referred to molecular weights, then $E = 0.0436 Q$. For instance, in a Daniell's element $E = 1.09$ both by experiment and by calculation, because it must be granted that here takes place the decomposition of CuSO_4 into $\text{CuO} + \text{SO}_3\text{Aq}$, and the decomposition of CuO into $\text{Cu} + \text{O}$, together with the formation of $\text{Zn} + \text{O}$ and $\text{ZnO} + \text{SO}_3\text{Aq}$, for which reactions $Q = 50.13$ thousand heat units. Just the same in other primary batteries (for instance, as shown by Bunsen, Poggendorf, and others) and secondary batteries (for instance, those acting according to the reaction $\text{Pb} + \text{H}_2\text{SO}_4 + \text{PbO}_2$, as Cheltzoff showed) elements $E = 0.0436 Q$. The question becomes more complicated as the temperature rises, probably from the incompleteness of thermochemical determinations.

prepare metallic cadmium. Hydrogen sulphide may be used for separating cadmium from its solutions; it gives a *yellow precipitate of cadmium sulphide*, CdS (according to the equation $\text{CdSO}_4 + \text{H}_2\text{S} = \text{H}_2\text{SO}_4 + \text{CdS}$), which, on account of its characteristic colour, is used as a pigment. Cadmium sulphide, when strongly heated in air, leaves cadmium oxide, from which the metal may be obtained in precisely the same way as in the case of zinc. It should be remarked at the same time that zinc sulphate (especially in the presence of acids) does not give a precipitate of zinc sulphide with sulphuretted hydrogen, or, at all events, is only precipitated in very small quantity.

Cadmium is a white metal, and when freshly cut is almost as white and lustrous as tin. It is so soft that it may be easily cut with a knife, and so malleable that it can be easily drawn into wire, sheets, &c. Its specific gravity is 8.67, melting point 320° , boiling point 770° ; its vapours burn, forming a brown powder of the oxide.¹¹ Next to mercury it is the most volatile metal; hence Deville determined the density of its vapours compared with hydrogen, and found it to be equal to 57.1, therefore the molecule contains *one atom* whose weight = 112. V. Meyer found the like for zinc; the molecule of mercury also contains one atom (Vol. I. p. 312).

Mercury resembles zinc and cadmium in many respects, but presents that distinction from them which is always noticed in all the heaviest metals (with regard to atomic weight and density) compared with the lighter ones—namely, that it oxidises with more difficulty, and its

¹¹ Amongst the compounds of cadmium very closely allied to the compounds of zinc, we must mention *cadmium iodide*, CdI_2 , which is used in medicine and photography. This salt crystallises very well; it is prepared by the direct action of iodine, mixed with water, on metallic cadmium. One part of cadmium iodide at 20° requires for its solution 1.08 parts of water. It may be remarked that cadmium chloride at the same temperature requires 0.71 parts of water to dissolve it, so that the iodine compound of this metal is less soluble than the chloride, whilst the reverse relation holds in the case of the corresponding compounds of the alkali or alkaline earthy metals. Cadmium sulphate crystallises well and has the composition $3\text{CdSO}_4 \cdot 8\text{H}_2\text{O}$, thus differing from zinc sulphate.

Cadmium oxide is soluble, although sparingly, in alkalis, but in the presence of tartaric and certain other acids the alkaline solution of cadmium oxide does not change when boiled, whilst a *diluted* solution in that case deposits cadmium oxide; this may also serve for separating zinc compounds from those of cadmium. Cadmium is precipitated from its salts by zinc, which fact may also be taken advantage of for separating cadmium; for this reason in an alloy of zinc and cadmium, acids first of all extract the zinc. Cadmium is in all respects less energetic than zinc. Thus, for instance, it decomposes water with difficulty, and this only when strongly heated. It even acts but slowly on acids, but then displaces hydrogen from them. It is necessary here to turn attention to the fact that for alkali and alkaline earthy metals (of the even series) the highest atomic weight determines the greatest energy; but cadmium (of the uneven series), whilst having a larger atomic weight than zinc, is less energetic. The salts of cadmium are colourless, like those of zinc. DeSchulten obtained a crystalline oxychloride, $\text{Cd}(\text{OH})\text{Cl}$, by heating marble with a solution of cadmium chloride in a sealed tube at 200° .

compounds are more easily decomposed.¹² Besides compounds of the usual type RX_2 , it also gives those of the lower type, RX , which are unknown for zinc and cadmium.¹³ Mercury therefore gives salts of the composition HgX (mercurous salts) and HgX_2 (mercuric salts), the oxides having the formulæ Hg_2O and HgO respectively.

Mercury is found *in nature* almost exclusively in combination with sulphur (like zinc and cadmium, but is still rarer than them) in the form known as cinnabar, HgS . It is far more rarely met with in the native or metallic condition, and this in all probability has been derived from cinnabar. Mercury ore is found only in a few places—namely, in Spain (in Almaden), in Idria, Japan, Peru, and California. About the year 1880 Minenkoff discovered a rich bed of cinnabar in the Bahmout district (near the station of Nikitovka), in the government of Ekaterinoslav, so that now Russia even exports mercury into other countries. Mercury ores are easily reduced to metallic mercury, because the combination between the metal and the sulphur is one of but little stability. Oxygen, iron, lime, and many other substances, when heated, easily destroy the combination. If iron is heated with cinnabar, iron sulphide is formed; if cinnabar is heated with lime, mercury and calcium sulphide and sulphate are formed, $4HgS + 4CaO = 4Hg + 3CaS + CaSO_4$. On being heated in the air, or roasted, the sulphur burns, oxidises, forming sulphurous anhydride, and vapours of metallic mercury are formed. Mercury is more easily distilled than all other metals; its boiling point is about 360° , and therefore its separation from natural admixtures, decomposed by one of

¹² According to its atomic weight, mercury follows gold in the periodic system, just as cadmium follows silver or zinc follows copper:

Ni= 59	Cu= 63	Zn= 65
Pd=106	Ag=108	Cd=112
Pt=196	Au=198	Hg=200

Eventually we shall see the near relation of platinum, palladium, and nickel, and also of gold, silver, and copper, but we will now establish a parallel between these three groups. The relation between the physical and also chemical properties is here strikingly similar. Nickel, palladium, and platinum are very difficult to fuse (far more so than iron, ruthenium, and osmium, which stand before them). Copper, silver and gold melt far more easily in a strong heat than the three preceding metals, and zinc, cadmium, and mercury melt still more easily. Nickel, palladium, and platinum are very slightly volatile; copper, silver, and gold are more volatile; and zinc, cadmium, and mercury represent some of the most volatile metals. Zinc oxidises more easily than copper, and is reduced with more difficulty, and the same is true for mercury as compared with gold. These relations for cadmium and silver are the medium ones in the corresponding groups. Associations of a similar kind are directly conclusive of those relations which compose the essence of the law of periodicity.

¹³ Thus thallium, lead, and bismuth, following mercury according to their atomic weights, form, besides compounds of the highest types TlX_3 , PbX_4 and BiX_5 , also the lower ones TlX , PbX_2 and BiX_3 .

the above-mentioned methods, is effected at the expense of a comparatively small amount of heat. The mixture of vapours of mercury, air, and products of combustion obtained are cooled in tubes (by water or air), and the mercury condenses as liquid metal.¹⁴

Mercury, as everybody knows, is a liquid metal at the ordinary temperature. In its lustre and whiteness it resembles silver.¹⁵ At -39° mercury is transformed into a malleable crystalline metal, at 0° its specific gravity equals 13.596, and in the solid state at -40° equals 14.39.¹⁶ Mercury does not change in the air—that is to say, it does not oxidise at the ordinary temperature—but at a temperature approaching the boiling-point (360°), as was stated in the Introduction, it oxidises, forming mercuric oxide.

Both metallic mercury and its compounds in general produce salivation, trembling of the hands, and other unhealthy symptoms which are found in the workmen subjected to the influence of mercurial vapours or the dust of its compounds.

As many of the compounds of mercury decompose on being heated—for instance, the oxide or carbonate¹⁷—and as zinc, cadmium, copper,

¹⁴ During the condensation of the vapours of mercury in works, a part forms a black mass of finely-divided particles, which give metallic mercury when worked up in centrifugal machines, or on pressure, or on further distillation. In mercury we observe a tendency to easily split up into the finest drops, which are difficult to unite into a dense mass. It is sufficient to shake up mercury with nitric and sulphuric acids in order to produce such a mercury *powder*. The mercury separated (for instance, reduced by substances like sulphurous anhydride) from solutions, forms such a powder. According to the experiments of Nerst, this disintegrated mercury when entering into reactions develops more heat than the dense liquid metal—that is to say, the work of disintegration reappears in the form of heat. This example is instructive in examining thermochemical deductions.

¹⁵ Mercury may sometimes be obtained in quite a pure state from works (in iron bottles holding about 35 kilos), but by being used in laboratories (for baths, calibration, &c.) it absorbs impurities. Mercury may be mechanically purified in the following way: a paper filter with a fine hole (pricked with a needle) is placed in a glass funnel and mercury is poured into it, which slowly trickles through the hole, leaving the impurities upon the filter. Sometimes it is squeezed through chamois leather or through a block of wood (as in the well-known experiment with the air-pump). It may be purified from many metals by contact with dilute nitric acid, if small drops of mercury are allowed to pass through a thick layer of it (from the fine end of a funnel); or by shaking it up with sulphuric acid in air. But the complete purification of mercury for barometers and thermometers can only be attained by distillation, best in a vacuum. For this purpose Weingold's apparatus is most often used. The principle of this apparatus is very ingenious, the distillation being effected in a Torricellian vacuum continuously supplied with fresh mercury, whilst the condensed mercury is continuously removed. This process of distillation requires very little attention, and gives about one kilo. of pure mercury per hour.

¹⁶ If the volume of *liquid* mercury at 0° be taken as 1000000, then, according to the determinations of Regnault (re-calculated by me in 1875), at t it will be $1000000 + 180.1t + 0.02t^2$.

¹⁷ All salts of mercury, when mixed with sodium carbonate and heated, give mercurous

iron, and other metals separate mercury from its salts,¹⁸ it is evident that mercury has less chemical energy than the metals already described, even than zinc and cadmium.

Nitric acid, when acting on *an excess* of mercury at the ordinary temperature, gives mercurous nitrate, HgNO_3 .¹⁹ The same acid, under the influence of heat and when in excess (oxide of nitrogen is separated), forms mercuric nitrate, $\text{Hg}(\text{NO}_3)_2$. This,²⁰ both in its composition and properties, resembles the salts of zinc and cadmium. Dilute sulphuric acid does not act on mercury, but strong sulphuric acid dissolves it, with evolution of *sulphurous anhydride* (not hydrogen), and, on being slightly heated with an excess of mercury, forms the sparingly soluble mercurous sulphate, Hg_2SO_4 , but, if strongly heated with an excess of the acid, the mercuric salt, HgSO_4 ,²¹ is formed. Alkalis do not act on mercury, but the non-metals chlorine, bromine, sulphur, and phosphorus easily combine with it. They form, like the acids, two series of compounds, the difference in composition being that the lower degrees contain HgX and the higher HgX_2 —that is, twice as much of the haloid, or half as much mercury for the same quantity of the haloid. This shows that *mercury forms two series of compounds—mercurous, HgX , and mercuric, HgX_2* . The oxygen compound of the first series

or mercuric carbonates; these decompose on being heated, forming carbonic anhydride, oxygen, and vapours of mercury.

¹⁸ According to the determinations of Thomsen, the formation of a gram of mercurial compounds from their elements develops the following amounts of heat (in thousands of units): $\text{Hg}_2 + \text{O}$, 42; $\text{Hg} + \text{O}$, 81; $\text{Hg} + \text{S}$, 17; $\text{Hg} + \text{Cl}$, 41; $\text{Hg} + \text{Br}$, 34; $\text{Hg} + \text{I}$, 24; $\text{Hg} + \text{Cl}_2$, 63; $\text{Hg} + \text{Br}_2$, 51; $\text{Hg} + \text{I}_2$, 34; $\text{Hg} + \text{C}_2\text{N}_2$, 19. These numbers are less than the corresponding ones for potassium, sodium, calcium, barium, and for zinc and cadmium—for instance, $\text{Zn} + \text{O}$, 85; $\text{Zn} + \text{Cl}_2$, 97; $\text{Zn} + \text{Br}_2$, 76; $\text{Zn} + \text{I}_2$, 49; $\text{Cd} + \text{Cl}_2$, 93; $\text{Cd} + \text{Br}_2$, 75; $\text{Cd} + \text{I}_2$, 49.

¹⁹ This salt easily forms the crystallo-hydrate $\text{HgNO}_3 \cdot \text{H}_2\text{O}$, corresponding with ortho-nitric acid H_3NO_4 (the terms ortho-, pyro-, and meta-acids are explained in the chapter on phosphorus), with the substitution of Hg for H. In an aqueous solution this salt can only be preserved in the presence of free mercury, otherwise it forms basic salts, which will be mentioned hereafter.

²⁰ Mercuric nitrate, $\text{Hg}(\text{NO}_3)_2 \cdot 8\text{H}_2\text{O}$, crystallises from a concentrated solution of mercury in an excess of boiling nitric acid. Water decomposes this salt; at the ordinary temperature crystals of a basic salt of the composition $\text{Hg}(\text{NO}_3)_2 \cdot \text{HgO} \cdot 2\text{H}_2\text{O}$ are formed, and with an excess of water the insoluble yellow basic salt $\text{Hg}(\text{NO}_3)_2 \cdot \text{H}_2\text{O} \cdot 2\text{HgO}$. These three salts correspond with the type of ortho-nitric acid, $(\text{H}_3\text{NO}_4)_2$, when mercury is substituted for 1, 2 and 3 times H_2 . The first salt will then be $\text{HgH}_4(\text{NO}_4)_2 \cdot 6\text{H}_2\text{O}$; the second, $\text{Hg}_2\text{H}_2(\text{NO}_4)_2 \cdot \text{H}_2\text{O}$; and the third, $\text{Hg}_7(\text{NO}_4)_7 \cdot \text{H}_2\text{O}$. As all these salts still contain water, it is possible that they correspond with the tetrahydrate $= \text{N}_2\text{O}_5 + 4\text{H}_2\text{O} = \text{N}_2\text{O}(\text{OH})_5$ if ortho-nitric acid $= \text{N}_2\text{O}_5 + 3\text{H}_2\text{O} = 2\text{NO}(\text{OH})_5$.

²¹ To obtain the mercuric salt a large excess of strong sulphuric acid must be taken and strongly heated. With a small quantity of water colourless crystals of $\text{HgSO}_4 \cdot \text{H}_2\text{O}$ may be obtained. An excess of water, especially when heated, forms the basic salt (as in Note 20), $\text{HgSO}_4 \cdot 2\text{HgO}$, which corresponds with trihydrated sulphuric acid, $\text{SO}_3 + 3\text{H}_2\text{O} = \text{S}(\text{OH})_6$, with the substitution of H_6 by 3Hg , which in mercuric salts is equivalent to H_6 .

is the suboxide of mercury, or mercurous oxide, Hg_2O , and of the second order the oxide, HgO , mercuric oxide. The chlorine compound corresponding with the suboxide is HgCl (calomel), and with the oxide corresponds HgCl_2 (corrosive sublimate or mercuric chloride). In the compounds HgX , mercury resembles the metals of the first group, and more especially silver—that is, the atom of mercury is here univalent, of the type RX . In the mercuric compounds there is an evident resemblance to those of magnesium, cadmium, &c., because these form compounds of the type RX_2 . Here the atom of mercury is bivalent, as in the type RX_2 .²² Every soluble mercurous compound (corresponding with the type of the suboxide of mercury), HgX , forms a white precipitate of calomel, HgCl , with hydrochloric acid or a metallic chloride, because HgCl is very slightly soluble in water, $\text{HgX} + \text{MCl} = \text{HgCl} + \text{MX}$. In soluble mercuric compounds, HgX_2 , hydrochloric acid and metallic chlorides do not form a precipitate, because corrosive sublimate, HgCl_2 , is soluble in water. Alkali hydroxides precipitate the yellow mercuric oxide from a solution of HgX_2 , and the black mercurous oxide from HgX . Potassium iodide forms a dirty greenish precipitate, HgI , with mercurous salts, HgX , and a red precipitate, HgI_2 , with the mercuric salts, HgX_2 . These reactions distinguish the mercuric salts from the mercurous salts which represent the transition from the mercuric salts to mercury itself, $2\text{HgX} = \text{Hg} + \text{HgX}_2$. The salts, HgX , as well as HgX_2 , are reduced by hydrogen at the moment of separation by such metals as zinc and copper and acids, and also by many reducing agents—for example, hypophosphorous acid, as the lowest grade of oxidation of phosphorus, by sulphurous

²² At the time when the example of such compounds as PCl_3 and PCl_5 , &c., had not yet proved the variability of the valency of elements—that is, when atomicity was reckoned a fundamental and constant property of the elements—mercury was always regarded as bivalent (iron, quadrivalent; N and P, trivalent, &c.), and the mercuric compounds HgX_2 were alone taken as normal compounds of mercury, the mercurous compounds being regarded as Hg_2X_2 —that is to say, that one of the affinities of each atom of mercury served for the mutual connection of the atoms of mercury which made the system Hg_2 appear bivalent. This representation may be also understood thus: the molecule HgX_2 shows the equivalency of HgX with X (according to the law of substitution), and, therefore, HgXHgX , or Hg_2X_2 was formed, as O_2H_2 is formed from OH . The vapour density of calomel, which indicates the molecule HgCl , was then explained by the splitting up of Hg_2Cl_2 in the vapours into two molecules, Hg and HgCl_2 . These suppositions, at present superfluous, also suffer on account of their assuming a union between atoms of mercury, whilst in the metal itself they are separate, for the molecule of mercury contains one atom only. Besides this, experiment directly showed that the vapour density of calomel remains unchanged by the admixture of the vapours of corrosive sublimate, which would not be the case if there was only a mixture of vapours of $\text{Hg} + \text{HgCl}_2$ in the vapour of calomel, from which it must be concluded that the formula HgCl (and not Hg_2Cl_2) expresses the actual molecular weight of calomel—that is to say, that mercury is univalent in the mercurous compounds, and bivalent in the mercuric compounds.

anhydride, stannous chloride, &c. Here the mercuric salts are first transformed into the mercurous salts, and then the latter are reduced to metallic mercury. This reaction is so delicate that it serves to detect the smallest quantity of mercury. For instance, in cases of poisoning, the mercury is discovered by immersing a copper plate (particularly if a galvanic current be passed) into the solution to be tested, the mercury being then deposited upon the copper plate, which, on being rubbed, shows a silvery white colour. The copper plate, on being heated yields vapours of mercury, and then again assumes its original red colour (if it does not oxidise).


The mercurous compounds, HgX , under the action of oxidising agents, even air, pass into mercuric compounds, especially in the presence of acids (otherwise a basic salt is produced), $2\text{HgX} + 2\text{HX} + \text{O} = 2\text{HgX}_2 + \text{H}_2\text{O}$; but the mercuric compounds, when in contact with mercury, change more or less readily, and turn into mercurous compounds, $\text{HgX}_2 + \text{Hg} = 2\text{HgX}$. For this reason, in order to preserve solutions of mercurous salts, a little mercury is generally added to them.

The lowest oxygen compound of mercury that is, *mercurous oxide*, Hg_2O does not seem to exist, as the substance precipitated in the form of a black mass by the action of alkalis from a solution of mercurous salts gradually separates on keeping into the yellow mercuric oxide and metallic mercury, as also does a simple mechanical mixture of oxide, HgO , with mercury (Guibourt, Barfoed). The other compound of mercury with oxygen is already known to us as *mercuric oxide*, HgO , obtained in the form of a red crystalline substance by the oxidation of mercury in the air, and precipitated in the shape of a yellow powder by the action of sodium hydroxide on solutions of salts of the type HgX_2 . In this case it is amorphous and more amenable to the action of various reagents (Vol. I. page 474) than when it is in the crystalline state. Indeed, on trituration, the red oxide is changed into a powder of a yellow colour. It is very sparingly soluble in water, and forms an alkaline solution which precipitates magnesia from the solution of its salts.

Mercury combines directly with chlorine, and the first product of combination is *calomel* or *mercurous chloride*, HgCl . This is obtained, as above stated, in the form of a white precipitate by mixing solutions of mercurous salts with hydrochloric acid or with metallic chlorides. A precipitate of calomel is also obtained by reducing a boiling aqueous solution of corrosive sublimate, HgCl_2 , with sulphurous anhydride. It is likewise produced by heating corrosive sublimate with mercury. Calomel may be distilled; its vapour density equals 118 compared with

hydrogen—that is, the formula HgCl expresses its molecular composition. In the solid state its specific gravity is 7.0; it crystallises in rhombic prisms, is colourless, but has a yellowish tint, turns brown from the action of light, and, when boiled with hydrochloric acid, decomposes into mercury and corrosive sublimate. *Corrosive sublimate* or *mercuric chloride*, HgCl_2 , can be obtained from or converted into calomel by many methods. An excess of chlorine (for instance, *aqua regia*) converts calomel and mercury into corrosive sublimate. It is termed corrosive sublimate on account of its being volatile, and, in medicine up to the present day, it is termed *Mercurius sublimatus seu corrosus*. The vapour density, compared with hydrogen, is 135; therefore it is more complex than calomel, as the formula shows. It forms colourless prismatic crystals of the rhombic system, boils at 303° , and is soluble in alcohol. It is usually prepared by subliming a mixture of mercuric sulphate with common salt, $\text{HgSO}_4 + 2\text{NaCl} = \text{Na}_2\text{SO}_4 + \text{HgCl}_2$. Corrosive sublimate combines with mercuric oxide, forming an oxychloride or basic salt,²³ of the composition $\text{HgCl}_2 \cdot 2\text{HgO}$

²³ As feebly energetic bases (for instance, the oxides MgO , ZnO , PbO , CuO , Al_2O_3 , Bi_2O_3 , &c.), mercuric oxide (*see* Notes 20, 21) and mercurous oxides easily give basic salts, which are most often directly formed by the action of water on the normal salt, according to the general equation (for mercuric compounds, RX_2):



or else are produced directly from the normal salt and the oxide or its hydroxide. Thus mercurous nitrate, when treated with water, forms basic salts of the composition $6(\text{HgNO}_3), \text{Hg}_2\text{O}, \text{H}_2\text{O}$, $2(\text{HgNO}_3), \text{Hg}_2\text{O}, \text{H}_2\text{O}$, and $3(\text{HgNO}_3), \text{Hg}_2\text{O}, \text{H}_2\text{O}$, the first two of which crystallise well. Naturally it is possible either to refer similar salts to the type of hydrates—for instance, the second salt to the hydrate $\text{N}_2\text{O}_5 \cdot 4\text{H}_2\text{O}$ —or to view it as a compound, $\text{HgNO}_3 \cdot \text{HgHO}$, but the contemporary budget of evidence on basic salts is not sufficiently complete to admit of generalisation. However, it is already possible to view the subject in the following aspects: (1) basic salts are principally formed from feeble bases; (2) certain metals (mentioned above) form them with particular ease, so that one of the causes of the formation of many basic salts must depend on the property of the metal itself; (3) those bases which readily form basic salts as a rule also readily form double salts; (4) in the formation of basic salts, as also everywhere in chemistry, where a sufficient quantity of facts have accumulated, we clearly see the conditions of equiponderant heterogeneous systems, such as we saw, for instance, in the formation of double salts, crystallo-hydrates, &c.

The mercuric salts (confirming the third thesis) often form double salts, and mercuric chloride easily combines with ammonia, forming $\text{Hg}(\text{NH}_4)_2\text{Cl}_2$, or in general $\text{HgCl}_2 \cdot n\text{MCl}$. If a mixture of mercurous and potassium sulphates be dissolved in dilute sulphuric acid, the solution easily yields large colourless crystals of a double salt of the composition $\text{K}_2\text{SO}_4 \cdot 3\text{HgSO}_4 \cdot 2\text{H}_2\text{O}$. Boullay obtained crystalline compounds of mercuric chloride with hydrochloric acid, and mercuric iodide with hydriodic acid; and Thomsen describes the compound $\text{HgBr}_2 \cdot \text{HBr} \cdot 4\text{H}_2\text{O}$ as a well-crystallised salt, melting at 13° , and having, in a molten state, a specific gravity of 3.17 and a high index of refraction. Let us also mention that the power of salts for forming basic compounds has been considerably cleared up from the time of the investigations (Würtz, Lorenz, and others) of glycol, $\text{C}_2\text{H}_4\text{OH}_2$ (and

(magnesium and zinc form similar compounds). This compound is obtained by mixing a solution of corrosive sublimate with mercuric oxide or with a solution of sodium bicarbonate. In general, with both mercurous and mercuric salts, there is a marked tendency to form basic salts.²⁴

Mercury has a remarkable power of forming very unstable compounds with ammonia, in which the mercury replaces the hydrogen, and, if a mercuric compound be taken, its atom occupies the place of two atoms of the hydrogen in the ammonia. Thus Plantamour and Hirtzel showed that precipitated mercuric oxide dried by slightly heating, when continuously heated (up to 100°–150°) in a stream of dry ammonia, leaves a brown powder of *mercuric nitride*, N_2Hg_3 , according to the equation, $3\text{HgO} + 2\text{NH}_3 = \text{N}_2\text{Hg}_3 + 3\text{H}_2\text{O}$. This substance, which is attacked by water, acids, and alkalis (giving a white powder), is very explosive when struck or rubbed, evolving nitrogen, proving that the bond between the mercury and the nitrogen is very feeble.²⁵ By the action of liquefied ammonia on yellow mercuric oxide

polyatomic alcohols resembling it), because the ethers, $\text{C}_2\text{H}_4\text{X}_2$, corresponding with it, are capable of forming compounds containing $\text{C}_2\text{H}_4\text{X}_2 \cdot n\text{C}_2\text{H}_4\text{O}$.

On the other hand, there is reason to think that the property of forming basic salts is in connection with the polymerisation of bases, especially colloidal, as developed in the chapter on silica, lead salts, and tungstic acid.

²⁴ Mercuric iodide, HgI_2 , is obtained first as a yellow, and then as a red, precipitate on mixing solutions of mercuric salts and potassium iodide, and is soluble in an excess of the latter (in consequence of the formation of the double salt, HgKI_5); of ammonium chloride (for a similar reason), &c. It crystallises at the ordinary temperature in square prisms of a red colour. On being heated, these change into yellow rhombic crystals, isomorphous in crystalline form with mercuric chloride. This yellow form of mercuric iodide is very unstable, and when cooled and triturated easily again assumes the more stable red form. When fused, a yellow liquid is obtained. *Mercuric cyanide*, $\text{Hg}(\text{CN})_2$, forms one of the most stable metallic cyanides. It is obtained by dissolving mercuric oxide in prussic acid, and by boiling prussian blue with water and mercuric oxide, ferric iron being then obtained in the precipitate. Mercuric cyanide is a colourless crystalline substance, soluble in water, and distinguishable by its great stability; sulphuric acid does not liberate prussic acid from it, and even caustic potash does not remove the cyanogen (a complex salt is probably produced), but the halogen acids disengage HCN. Like the chloride, it combines with mercuric oxide, forming the oxycyanide, $\text{Hg}_2\text{O}(\text{CN})_2$, and it shows a very marked tendency to form double compounds—for instance, $\text{K}_2\text{Hg}(\text{CN})_4$. The alkali chlorides and iodides form similar compounds—for instance, the salt $\text{HgKI}(\text{CN})_2$ crystallises very well, and is produced by directly mixing solutions of potassium iodide and mercuric cyanide.

²⁵ The readiness with which mercuric nitride explodes shows that the connection between the nitrogen and the mercury is very unstable, and is explained by the circumstance that the so-called *mercury fulminate*, or *fulminating mercury* is an exceedingly explosive substance. This substance is prepared in large quantities for explosive mixtures; it enters into the composition of percussion caps, which explode when struck, and kindle gunpowder. Mercury fulminate was discovered by Howard, and from that time has been prepared in the following way: one part of mercury is dissolved in twelve parts of nitric acid, of sp. gr. 1.36, and when the whole of the mercury is dissolved, 5.5 parts of 90 p.e.

Weitz also obtained an explosive compound, dimercurammonium hydroxide, N_2Hg_2O , which corresponds with an ammonium oxide,

alcohol is added, and the mass is shaken. A reaction then commences, accompanied by self-heating, produced by the oxidation of the alcohol. Actually, many oxidation products are produced during the action of the nitric acid on the alcohol (glycollic acid, ethers, &c.). When the reaction becomes fairly strong, the same quantity of alcohol is added as at the commencement, and then the grey precipitate of the fulminate separates.

This salt has the composition $C_2Hg(NO_2)N$. It explodes when struck or heated. The mercury in it may be replaced by other metals—for instance, copper or zinc, and also silver. The silver salt, $C_2Ag_2(NO_2)N$, is obtained in a precisely analogous manner, and is even more explosive. Under the action of alkali chlorides, only half the silver is replaced by the alkali metal, but if the whole of the silver be replaced by an alkali metal, then the salt decomposes. This is evidently because combinations of this kind proceed in virtue of the formation of substances in which mercury, and metals akin to it, are connected in an unstable way with nitrogen. Potassium, and other light metals, are incapable of entering into such connection, and therefore, the substitution of potassium for mercury entails the splitting up of the arrangement. Investigations of the fulminates were carried on, especially by Gay-Lussac and Liebig, but only the investigations of L. N. Shishkoff fully cleared up the composition and relation of this substance to the other carbon compounds. Shishkoff showed that fulminates correspond with the nitrogen acid, $C_2H_2(NO_2)N$. The explosiveness of the group depends partly on its containing at the same time NO_2 and carbon; we already know that all such nitrogen compounds are explosive. If we imagine that the NO_2 is replaced by hydrogen, we shall have a substance of the composition, C_2H_5N . This is acetonitrile—that is, acetic acid + $NH_3 - 2H_2O$, or ethenyl nitrile, as shown in Chapter VI. The formation of an acetic compound by the action of nitric acid on alcohol is easily understood, because acetic acid is produced by the oxidation of alcohol, and the production of the elements of ammonia, indispensable for the formation of a nitrile, is accounted for by the fact that nitric acid, under the action of reducing substances, in many cases forms ammonia. And thus the formation of acetonitrile, C_2H_5N , becomes possible when alcohol acts on nitric acid. In this acetonitrile, an exchange of one atom of hydrogen with the group NO_2 is accomplished whilst the two others are replaced by mercury—that is to say, fulminating mercury, $C_2(NO_2)HgN$, is formed. The explosiveness of this compound is explained not only by the common presence of C_2 and NO_2 , but also by the presence of Hg and N, as nitride of mercury is explosive. The presence of the group NO_2 in fulminating mercury is shown by its forming chloropierin, $C(NO_2)Cl_3$, when treated with chlorine, similarly to other nitro compounds, and the formation of acetonitrile is demonstrated by the fact that fulminating mercury, when treated with bromine, forms bromonitroacetonitrile, $C_2(NO_2)Br_2N$. The explosiveness of fulminating mercury, the rapidity of its decomposition (gunpowder, and even guncotton, burn more slowly and explode less violently), and the force of its explosion, are such that the explosion of a small quantity (loosely covered) will shatter massive objects.

The investigations of Abel on the communication of explosion from one substance to another are remarkable. If guncotton be ignited in an open space, it burns quietly, but if fulminating mercury be exploded by the side of it, the decomposition of the guncotton is effected instantaneously, and it then shatters the objects upon which it lies, so rapid is the decomposition. Abel explains this by stating that the explosion of the fulminating salt brings the molecules of guncotton into a special, as it were, harmonious state of vibration, which engenders the rapid decomposition of the whole mass. This rapid decomposition of explosive substances establishes the distinction between explosion and combustion. Besides this, Berthelot showed that from that form of powerful molecular concussion which takes place during the explosion of fulminating mercury, the state of tension and stability of equilibrium of substances which are endothermal, or capable of decomposing with the disengagement of heat—for instance, cyanogen, nitro compounds,

$(\text{NH}_4)_2\text{O}$, in which the whole of the hydrogen is replaced by mercury. A solution of ammonia reacts with mercuric oxide, forming the hydroxide, $\text{NH}_2\text{Hg}\cdot\text{OH}$, to which a whole series of salts, NH_2HgX , correspond; these are generally insoluble in water and capable of decomposing with an explosion. But salts of the same type, but with one atom of mercury, NH_2HgX , are more frequently and more easily formed; they were principally studied by Kane, although known long ago. Thus, if ammonia be added to a solution of corrosive sublimate (or, still better, in reverse order), a precipitate is obtained known as white precipitate (*Mercurius præcipitatus albus*) or *mercurammonium chloride*, NH_2HgCl , which may also be regarded as HgX_2 , where one X equals Cl and the other X equals the ammonia radicle, $\text{HgCl}_2 + 2\text{NH}_3 = \text{NH}_2\text{HgCl} + \text{NH}_4\text{Cl}$. When heated, mercurammonium chloride decomposes, yielding mercurous chloride; when heated with dry hydrochloric acid it forms ammonium chloride and mercuric chloride. Other simple and double salts of mercurammonium, NH_2HgX , are also known.

Mercury as a liquid metal is capable of dissolving other metals and forming metallic solutions. These are generally called 'amalgams.' The formation of these solutions is often accompanied by the development of a large amount of heat—for instance, when potassium and sodium are dissolved; but sometimes heat is absorbed, as, for instance, when lead is dissolved. It is evident that phenomena of this kind are exceedingly similar to the phenomena accompanying the dissolution of salts and other substances in water, but here it is easy to demonstrate that which is far more difficult to observe in the case of salts: the solution of metals in mercury is accompanied by the formation of definite chemical compounds of the mercury with the metals dissolved. This is shown by the fact that when pressed (best of all in chamois leather) such solutions leave solid, definite compounds of mercury with metals. It is, however, very difficult to obtain them in a pure state, on account of the difficulty of separating the last traces of mercury, which is mechanically distributed between the crystals of the compounds. Nevertheless, in many cases such compounds have undoubtedly been obtained, and this is clearly shown by the evident crystalline structure and characteristic appearance of many amalgams. Thus, for instance, if about $2\frac{1}{2}$ p.c. of sodium is dissolved in mercury, a hard, crystalline amalgam is obtained, very friable and little changeable in air. It contains the compound NaHg_5 (Vol. I. page 529). Water decomposes

nitrous oxide, &c.—is generally destroyed. Thorpe showed that carbon bisulphide, CS_2 , as an endothermal substance, also decomposes into sulphur and charcoal, when fulminating mercury is exploded in contact with it.

it, with the evolution of hydrogen, but more slowly than other sodium amalgams, and this action of water only shows that the bond between the sodium and the mercury is weak, just like the connection between mercury and many other elements—for instance, nitrogen. Mercury directly and easily dissolves potassium, sodium, zinc, cadmium, tin, gold, bismuth, lead, &c., and from such solutions or alloys it is in most cases easy to extract definite compounds—thus, for instance, the compounds of mercury and silver have the compositions HgAg and Ag_2Hg_3 . Objects made of copper when rubbed with mercury become covered with a white coating of that metal, which slowly forms an amalgam; silver acts in the same way, and platinum combines with mercury with still greater difficulty. This metal only readily forms an amalgam when in the form of a fine powder. If salts of platinum in solution are poured on to an amalgam of sodium, the latter element reduces the platinum, and the platinum separated is dissolved by the mercury. Almost all metals readily form amalgams if their solutions are decomposed by a galvanic current, where mercury forms the negative pole. In this way an amalgam may even be made with iron, although iron in a mass does not dissolve in mercury. Some amalgams are found in nature—for instance, silver amalgams.

Amalgams are used in considerable quantities in the arts. Thus the solubility of silver in mercury is taken advantage of for extracting that metal from the ore by means of amalgamation, and for silvering by fire. The same may be said of gold. Tin amalgam, which is incapable of crystallising and is obtained by dissolving tin in mercury, composes the brilliant coating of ordinary looking-glasses, which is made to adhere to the surface of the polished glass by simply pressing tin sheets bathed in mercury on to the cleansed surface of the glass by mechanical means.²⁶

²⁶ I here consider it appropriate to turn attention to the want of an element (ekacadmium) between cadmium and mercury in the periodic system (Chapter XV.). But, as in the ninth series there is not a single known element, it may be that this series is entirely composed of elements incapable of existing. However, until this is proved in one way or another, it may be concluded that the properties of ekacadmium will be between those of cadmium and mercury. It ought to have an atomic weight of about 155, to form an oxide EcO , a slightly stable oxide Ec_2O . Both ought to be feeble bases, easily forming double and basic salts. The volume of the oxide will be nearly 17.5, because the volume of cadmium oxide is about 16, and that of mercuric oxide 19. Therefore, the density of the oxide will approach $171 \div 17.5 = 9.7$. The metal ought to be easily fusible, oxidising when heated, of a grey colour, with a specific volume, about 14 (cadmium = 13, mercury = 15), and, therefore, its specific gravity ($155 \div 14$) will nearly = 11. Such a metal is unknown. But in 1879 Dahl, in Norway, discovered in the island of Oterö, not far from Kragerö, in a vein of Iceland spar in a nickel mine, traces of a new metal which he called norwegium, and which presented a certain resemblance to ekacadmium. As little ore was found, the experiments were not continued; the first information was scanty, complete

purity of the metal was not attained, and, therefore, the properties ascribed to norwegium ought to be regarded as approximate, and likely to undergo considerable alteration on further study. A solution of the roasted mineral in acid was twice precipitated by sulphuretted hydrogen, and again ignited; the oxide obtained was easily reduced. When the metal was dissolved in hydrochloric acid largely diluted with water, and the solution boiled, the basic salt was precipitated, and thus freed from the copper which remained in the solution. The reduced metal had a density 9.44, and easily oxidised. If the composition NgO be assigned to the oxide, then $\text{Ng}=145.9$. It fused at 254° ; the hydroxide was soluble in alkalis and potassium carbonate. In any case, if norwegium is not a mixture of other metals, it belongs to the uneven series, because the heavy metals of the even series are not easily reducible. Brauner thinks that norwegium oxide is Ng_2O_3 , the atom $\text{Ng}=219$, and places it in Group VI., series 11, but then the feebly acid higher oxide, NgO_3 , ought to be formed.

Amongst those metals accompanying zinc which have been pointed out, but not authentically extracted, the *actinum* of Phipson must be ranked (1881). He remarked that certain sorts of zinc give a white precipitate of zinc sulphide which blackens on exposure to light and then becomes white in the dark again. Its oxide, closely resembling in many ways cadmium oxide, is insoluble in alkalis, and it forms a white metallic sulphide, blackening on exposure to light.

CHAPTER XVII

BORON, ALUMINIUM, AND THE ANALOGOUS METALS OF THE THIRD GROUP

IF the elements of small atomic weight which have been as yet considered by us be placed in order, it will be clearly seen that, judging by the formulæ of their higher compounds, one element is wanting between beryllium and carbon. Indeed, lithium gives LiX , beryllium forms BeX_2 , and then comes carbon, giving CX_4 . Evidently to complete the series we must look for an element forming RX_3 , and having an atomic weight greater than 9 and less than 12. And *boron* is such a one; its atomic weight is 11, and its compounds are expressed by BX_3 .

Lithium and beryllium are metals; carbon has no metallic properties; boron appears in a free state in several forms which are intermediate between the metals and non-metals. Lithium gives an energetic caustic oxide, beryllium forms a very feeble base; hence one would expect to find that the oxide of boron, B_2O_3 , has still more feeble basic properties and some acid properties, all the more as CO_2 and N_2O_5 are acid oxides. And, indeed, the only known *oxide of boron* exhibits a feeble basic character, together with the properties of a feeble acid oxide. This is even seen from the fact that a solution of boron oxide reddens blue litmus and acts on turmeric paper as an alkali, and these reactions may be used for its discovery. By themselves the alkali borates have an alkaline reaction, which clearly indicates the feeble acid character of boric acid. If they are mixed in solution with hydrochloric acid, boric acid is liberated, and if a piece of turmeric paper be immersed in this solution and then dried, the excess of hydrochloric acid volatilises, while the boric acid remains on the paper and communicates a *brown coloration* to it, just like alkalis.

Boron trioxide or boric anhydride enters into the composition of many minerals, in the majority of cases in small quantities as an isomorphous admixture, not replacing acids but bases, and most frequently (Al_2O_3) alumina, because, as a rule, the amount of alumina decreases as that of the boric anhydride increases in them. This

substitution is justified by the similarity between the atomic composition of the oxides of aluminium (alumina) and boron. The subdivision of oxides into basic and acid can in no way be sharply defined, and here we meet with the most conclusive proof of the fact, for the oxides of boron and aluminium belong to the number of intermediate oxides, closely approaching the limit separating the basic from the acid oxides. Their type (Chapter XV.) R_2O_3 is intermediate between those of the basic oxides R_2O and RO and those of the acid oxides R_2O_5 and RO_3 . If we turn our attention to the chlorides, we remark that lithium chloride is soluble in water, is not volatile, and is not decomposed by water; the chlorides of beryllium and magnesium are more volatile, and although not entirely, still are decomposed by water; whilst the chlorides of boron and aluminium are still more volatile and are decomposed by water. Thus the position of boron and aluminium in the series of the other elements is clearly defined by their atomic weights, and shows us that we must not expect any new and distinct functions in these elements.

Boron was originally known in the form of sodium borate, $Na_2B_4O_7 \cdot 10H_2O$, or *borax*, or *tincal*, which was exported from Asia, where it is met with in solution in certain lakes of Thibet; it has also been discovered in California and other localities.¹ Boric acid was afterwards found in sea-water and in certain mineral springs.² Its presence

¹ Borax is either straightway extracted from lakes (the American lakes give about 2000 tons and the lakes of Thibet about 1000), or by heating native calcium borate (see Note 2) with sodium carbonate (about 1000 tons per year), or it is obtained (up to 2000 tons) from the Tuscan impure boric acid and sodium carbonate (carbonic anhydride is evolved). Borax gives supersaturated solutions with comparative ease (Gernez), from which it crystallises, both at the ordinary and higher temperatures, in octahedra, containing $Na_2B_4O_7 \cdot 5H_2O$. Its sp. gr. is 1.81. But if the crystallisation proceeds in open vessels, then at temperatures below 56° , the ordinary prismatic crystallo-hydrate $B_4Na_2O_7 \cdot 10H_2O$ is obtained. Its sp. gr. is 1.71, it effloresces in dry air at the ordinary temperature, and at 0° 100 parts of water dissolve about 3 parts of this crystallo-hydrate, at 50° 27 parts, and at 100° 201 parts. Borax fuses when heated, loses its water and gives an anhydrous salt, which at a red heat fuses into a mobile liquid and solidifies into a transparent amorphous glass (sp. gr. 2.37), which before hardening acquires the pasty condition peculiar to common molten glass. Molten borax dissolves many oxides and on solidifying acquires the characteristic tints of these oxides; thus oxide of cobalt gives a dark blue glass, nickel a yellow, chromium a green, manganese an amethyst, uranium a bright yellow, &c. Owing to its fusibility and property of dissolving oxides, borax is employed in soldering and brazing metals. Borax frequently enters into the composition of strass and fusible glasses.

² We may mention the following among the minerals which contain boron: calcium borate, $(CaO)_3(B_2O_3)(H_2O)_6$, found and extracted in Asia Minor, near Brusa; *boracite* (stassfurtite), $(MgO)_6(B_2O_3)_3 \cdot MgCl_2$, at Stassfurt, in the regular system, large crystals and amorphous masses (specific gravity 2.95), used in the arts; *ereméefite* (Damour), $AlBO_3$ or $Al_2O_3 \cdot B_2O_3$, found in the Adulchalonsk mountains in colourless, transparent prisms (specific gravity 3.28) resembling apatite; *datholite*,

may be discovered by means of the green coloration which it communicates to the flame of alcohol, which is capable of dissolving free boric acid.³ The greater portion of the boron compounds employed in the arts is obtained from the impure boric acid which is extracted in Tuscany from the so-called *suffioni*. In these localities, which present the remains of volcanic action, steam mixed with nitrogen, hydrogen sulphide, small quantities of boric acid, ammonia, and other substances, issues from the earth. Boric acid may be contained in steam, because it partially volatilises with it, and if a solution of boric acid be boiled, the distillate will always contain a certain amount of this substance.⁴

If boric acid be introduced into an excess of a strong hot solution of sodium hydroxide, then on slowly cooling the salt $\text{NaBO}_2 \cdot 4\text{H}_2\text{O}$ crystallises out. This salt contains an equivalent of Na_2O to one equivalent B_2O_3 (it is BX_3 with the substitution of one X by the radicle NaO and of two X by oxygen). It might be termed a neutral salt did it not possess strongly alkaline reactions and easily split up into the alkali and the more stable borax or biborate of sodium mentioned

$(\text{CaO})_2(\text{SiO}_2)_2\text{B}_2\text{O}_5 \cdot \text{H}_2\text{O}$. As much as 10 p.c. of boric anhydride sometimes enters into the composition of tourmaline and axinite.

³ This green coloration is best seen by taking an alcoholic solution of volatile ethyl borate, which is easily obtained by the action of boron chloride on alcohol.

⁴ How it is that these vapours containing boric acid are formed in the interior of the earth is at present unknown. Dumas supposes that it depends on the presence of *boron sulphide*, B_2S_5 (others think boron nitride), at a certain depth in the earth. This substance may be artificially prepared by heating a mixture of boric acid and charcoal in a stream of carbon bisulphide vapour, and by the direct combination of boron and the vapour of sulphur at a white heat. The almost non-crystalline compound B_2S_5 thus obtained is somewhat volatile, has an unpleasant smell, and is very easily decomposed by water, forming boric acid and hydrogen sulphide, $\text{B}_2\text{S}_5 + 3\text{H}_2\text{O} = \text{B}_2\text{O}_5 + 3\text{H}_2\text{S}$. It is supposed that a bed of boron sulphide lying at a certain depth below the surface of the earth comes into contact with sea water which has percolated through the upper strata, becomes very hot, and gives steam, hydrogen sulphide, and boric acid. This also explains the presence of ammonia in the vapours, because the sea water certainly passes through crevices containing a certain amount of animal matter, which are decomposed by the action of heat and evolve ammonia. We have, however, only mentioned this hypothesis for the sake of showing the possibility of accounting to a certain extent for the evolution of these fumes from crevices in the earth. There are several other hypotheses for explaining the presence of the vapours of boric acid, but owing to the want of other known localities the comparison of these hypotheses is at present hardly possible. The amount of boric anhydride in the vapours which escape from the Tuscan fumerolles and *suffioni*, as they are termed by the Italians, is very inconsiderable, less than one-tenth p.c., and therefore the direct extraction of the acid would be very uneconomical, hence the heat contained in the discharged vapours is made use of for evaporating the water. This is done in the following manner. Reservoirs are constructed over the crevices evolving the vapours, and the water of some neighbouring spring is passed into them. The vapours are caused to pass through these reservoirs, and in so doing they give up all their boric acid to the water and heat it, so that after about twenty-four hours it even boils; still this water forms only a very weak solution of boric acid. This solution is then passed into lower basins and again saturated by the vapours discharged from the

above, and which contains $2\text{B}_2\text{O}_3$ to Na_2O .⁵ This salt is prepared by the action of boric acid on a solution of sodium carbonate. As borax may be perfectly purified by crystallisation, it is employed as a means for obtaining pure boric acid.

If a saturated and hot solution of borax be mixed with strong

earth, by which means a certain amount of the water is evaporated and a fresh quantity of boric acid absorbed; the same process is repeated in another reservoir, and so on until



FIG. 81.—Extraction of boric acid in Tuscany.

the water has collected a somewhat considerable amount of boric acid. The solution is drawn from the last reservoir A into settling vessels B D, and then into a series of vessels *a, b, c*. In these vessels, which are made of lead, the solution is also evaporated by the vapours escaping from the earth, and attains a density of 10° and 11° Baumé. It is allowed to settle in the vessel *c*, in which it cools and crystallises, yielding (not quite pure) crystalline boric acid.

⁵ A solution of borax, $\text{Na}_2\text{B}_4\text{O}_7$, has an alkaline reaction, decomposes ammonia salts with the liberation of ammonia (Bolley), absorbs carbonic anhydride like an alkali, dissolves iodine like an alkali (Georgiewitsch), and seems to be decomposed by water. Thus Rose showed that strong solutions of borax give a precipitate of silver borate with silver nitrate, whilst dilute solutions precipitate silver oxides, like an alkali. Georgiewitsch even supposes (1888) boric anhydride to be entirely void of acid properties, for all acids, on acting on a mixture of solutions of potassium iodide and iodate, evolve iodine, but boric acid does not do this. With dilute solutions of sodium hydroxide Berthelot obtained a development of heat equal to $11\frac{1}{2}$ thousand calories per equivalent of alkali (40 grams sodium hydroxide) when the ratio $\text{Na}_2\text{O} : 2\text{B}_2\text{O}_3$ (as in borax) was taken, and only 4 thousand calories when the ratio was $\text{Na}_2\text{O} : \text{B}_2\text{O}_3$, whence he concludes that water powerfully decomposes those sodium borates in which there is more alkali than in borax. Laurent (1849) obtained a sodium compound, $\text{Na}_2\text{O} \cdot 4\text{B}_2\text{O}_3 \cdot 10\text{H}_2\text{O}$, containing

hydrochloric acid, common salt and a normal crystalline hydrate of boric acid are formed. The composition of this hydrate is $B(OH)_3$, according to the form BX_3 —that is, of the composition $B_2O_3 \cdot 3H_2O$. This is the easiest method of obtaining pure boric acid. The water is easily expelled from this hydrate; it loses half at 100° and the remainder on further heating, after which the boric anhydride fuses (at 580° , according to Carnelley), forming at first a ductile (easily drawn out into threads), tenacious mass. The residual boric anhydride or trioxide of boron, B_2O_3 , forms a colourless liquid when fused, which solidifies into a transparent glass, which attracts moisture from the atmosphere and then becomes cloudy.⁶ Only the alkaline salts of boric acid are soluble in water, but all borates are soluble in acids, owing to their easy decomposability and the solubility of boric acid itself. Although boric anhydride, B_2O_3 , absorbs $3H_2O$ from damp air, still in the presence of water it always⁷ combines with a less quantity

twice as much boric anhydride as borax, by boiling a mixture of borax with an equivalent quantity of sal-ammoniac until the evolution of ammonia entirely ceased.

Hence it is evident that feeble acids are as prone to, and as easily, form acid salts (that is, salts containing much acid oxide) as feeble bases are to give basic salts. These relations become still clearer on an acquaintance with such feeble acids as silicic, molybdic, &c. This variety of the proportions in which bases are able to form salts recalls exactly the variety of the proportions in which water combines with crystallo-hydrates. But the want of sufficient data in the study of these relations does not yet permit of their being generalised under any common laws.

With respect to the feeble acid energy of boric anhydride I think it useful to add the following remarks. Carbonic anhydride is absorbed by a solution of borax, and displaces boric anhydride; but it is also displaced by it, not only on fusion, but also on solution, as the preparation of borax itself shows. Sulphuric anhydride is absorbed by boric acid, forming a compound $BHSO_4$, where HSO_4 is the radicle of sulphuric acid (D'Ally). With phosphoric acid, boric acid forms a stable compound, BPO_4 , or $B_2O_3 \cdot P_2O_5$, undecomposable by water, as Gustavson and others have shown. With respect to tartaric acid, boric anhydride is able to play the same part as antimonious oxide. Mannitol, glycerol, and like polyhydric alcohols also seem able to form particularly characteristic compounds with boric anhydride. All these aspects of the subject require still further explanation by a method of fresh and detailed research.

⁶ Ditte determined the sp. gr. :—

	0°	12°	80°
B_2O_3	1.8766	1.8476	1.6988
$B(OH)_3$	1.5463	1.5172	1.3828
Solubility	1.95	2.92	16.82

The last line gives the solubility, in grams, of boric acid, $B(OH)_3$, per 100 c.c. of water, also according to the determinations of Ditte.

⁷ It is evident that, in the presence of basic oxides, water competes with them, which fact in all probability determines both the amount of water in the salts of boric acid as well as their decomposition by an excess of water. The feeble salt-forming properties of boric acid very closely resemble the similar properties of water itself. In confirmation of the above-mentioned competing action between water and bases, I think it useful to point out that the crystallo-hydrate of borax containing $5H_2O$ is composed, like $B(OH)_3$, or rather like $B_2(OH)_6$, with the substitution of one of hydrogen by sodium, because

of bases (borax only contains $\frac{1}{6}$). However, fused boric anhydride forms a crystalline compound with magnesium of the same type as the hydrate $(\text{MgO})_3\text{B}_2\text{O}_3$ (Ebelmann), and even with sodium it forms $(\text{Na}_2\text{O})_3\text{B}_2\text{O}_3$ or Na_3BO_3 (Benedict). As a rule, the salts of boric acid contain less base, although they are all able to form saline compounds with bases when fused. Generally, glassy fluxes are formed by this means,⁸ which when fused recall ordinary aqueous solutions in many respects. Some of them crystallise on solidifying, and then they have, like salts, a definite composition. The property of boric anhydride of forming higher grades of combination with basic oxides when fused explains the power of fused borax to dissolve metallic oxides, and the remarkable experiments of Ebelmann on the preparation of artificial crystals of the precious stones by means of boric anhydride. Boric anhydride is, although difficultly, volatile at a strong heat, and therefore if it dissolves an oxide, it may be partially driven off from such a solution by prolonged and powerful ignition; in which case the oxides previously in solution separate out in a crystalline form, and frequently in the same forms as those in which they occur in nature—for example, crystals of alumina, which by itself fuses with difficulty, have been obtained in this manner. It dissolves in molten boric anhydride, and separates out in natural rhombohedric crystals. In this way Ebelmann also obtained *spinel*—that is, a compound of magnesium and aluminium oxides which is met with in nature.⁹

$\text{Na}_2\text{B}_4\text{O}_7 \cdot 5\text{H}_2\text{O} = 2\text{B}_2(\text{OH})_3(\text{ONa})$. As the water which is held in this salt is easily parted with, so also the water of the hydrate, $\text{B}(\text{HO})_3$, is easily parted with, and in this respect resembles water of crystallisation. These relations between boric acid, water, and bases are to a certain extent expressed by the phenomenon that molten boric anhydride dissolves bases, and leaves them behind in passing into vapour.

⁸ A glass can only be formed by those little volatile oxides which correspond with feeble acids, like silica, phosphoric and boric anhydrides, &c., which themselves give glassy masses, like quartz, glacial phosphoric acid, and boric anhydride. They are able, like aqueous solutions and like metallic alloys, to solidify either in an amorphous form or to yield (or even be wholly converted into) definite crystalline compounds. This view illustrates the position of solutions amongst the other chemical compounds, and allows all alloys to be regarded from the aspect of the common laws of chemical reactions. I therefore have frequently recurred to it in this work, and introduced it since the year 1850 into various provinces of chemistry.

⁹ If boric acid in its aqueous solutions proves to be exceedingly feeble, unenergetic, and easily displaced from its salts by other acids, yet in an anhydrous state, as anhydride, it exhibits the properties of an energetic acid oxide, and it *displaces* the anhydrides of other acids. This naturally does not signify that the acid then acquires new chemical properties, but only depends on the fact that the anhydrides of the majority of acids are much more volatile than boric anhydride, and therefore the salts of many acids—even of sulphuric acid—are decomposed when fused with boric anhydride.

By itself boric acid is used in the arts in small quantity, chiefly for the preservation of meat and fish (which must be afterwards well washed in water) and of milk, and for soaking the wicks of stearin candles; the latter application is based on the fact that the

Free *boron* was obtained (1809) by Davy, Gay-Lussac, and Thenard when they obtained the metals of the alkalis, because boric anhydride when fused with sodium gives up its oxygen to the sodium, and free boron is liberated as an *amorphous* powder like charcoal.¹⁰ It is of a brown colour, and when dry does not alter in the air at the ordinary temperature; but it burns when ignited, and in so doing combines not only with the oxygen of the air, but also with the nitrogen. However, the combustion is never complete, because the boric anhydride formed on the surface covers the remaining mass of the boron, and so preserves it from the action of the oxygen. Acids, even sulphuric and phosphoric, easily oxidise amorphous boron, especially when heated, converting it into boric acid. Alkalis have the same action on it, only in this case hydrogen is evolved. Boron decomposes steam at a red heat, also with evolution of hydrogen. Amorphous boron also easily and directly combines with the metals, and with sulphur, chlorine, and nitrogen at a red heat.

Amorphous boron, like charcoal, dissolves in certain molten metals. The property of fused *aluminium of dissolving boron* in considerable quantity is very striking; on cooling such a solution the boron, partially combined with the aluminium, separates out in a crystalline form, and its properties are then exceedingly remarkable. The crystalline boron may be obtained by heating (to 1300°) the pulverulent boron with aluminium in a well-closed crucible, the access of air being prevented as far as possible. After cooling, crystals are observed on the surface of the aluminium, and may easily be separated by dissolving the aluminium in hydrochloric acid, which does not act on the crystals. The sp. gr. of the crystals is 2.68; they are partially transparent, but are mostly coloured dark brown; they contain about 4 p.c. of carbon and up to 7 p.c. of aluminium, so that they cannot be counted as pure boron. Nevertheless, the properties of this *crystalline* substance, which

wicks, which are made of cotton twist, contain an ash which is infusible by itself but which fuses when mixed with boric acid.

¹⁰ *Amorphous boron* is prepared by mixing 100 parts of powdered boric anhydride with 50 parts of sodium in small lumps; this mixture is thrown into a powerfully-heated cast-iron crucible, covered with a layer of ignited salt, and the crucible covered. Reaction proceeds rapidly; the mass is stirred with an iron rod, and poured directly into water containing hydrochloric acid. The action is naturally accompanied by the formation of sodium borate, which is dissolved, together with the salt, by the water, whilst the boron settles at the bottom of the vessel as an insoluble powder. It is washed in water, and dried at the ordinary temperature. Magnesium, and even charcoal and phosphorus, are also able to reduce boron from its oxide. Boron, in the form of an amorphous powder, very easily passes through filter-paper, remains suspended in water, and colours it brown, so that it is considered soluble in water. Sulphur precipitated from solutions shows the same (colloidal) property.

was obtained by Wöhler and Deville, are very remarkable. It most closely resembles *the diamond in its properties* in fact, these crystals have the lustre and high refracting power proper to the diamond only, whilst their hardness competes with that of the diamond. Their powder polishes even the diamond, and, like the diamond, scratches the sapphire and corundum. Crystalline boron is much more stable with respect to chemical reagents than the amorphous variety, and as it resembles the diamond, so amorphous boron, on the other hand, distinctly recalls certain of the properties of charcoal; thus a certain resemblance exists between boron and carbon in a free state, which is further justified by the proximity of their positions in the periodic system.

Among the other compounds of boron, those with nitrogen and the halogens are the most remarkable. As has been mentioned above, amorphous boron combines directly with *nitrogen* at a red heat. If amorphous boron be heated in a glass tube in a stream of nitric oxide, then perfect combustion takes place, $5B + 3NO = B_2O_3 + 3BN$. If the residue be treated with nitric acid, the boric anhydride dissolves, whilst the *boron nitride* remains¹¹ as an extremely light white powder, which is sometimes partially crystalline and greasy to the touch, like talc. It is infusible and unchanged, even at the melting-point of nickel. In general, it is remarkable for its great stability with respect to chemical reagents. Nitric and hydrochloric acids, as well as alkaline solutions, and hydrogen and chlorine at a red heat, have no action on it. When fused with potash, it evolves ammonia, and when ignited in steam it also yields ammonia: $2BN + 3H_2O = B_2O_3 + 2NH_3$.¹²

No less remarkable is the compound of boron with fluorine—*boron fluoride*, BF_3 . It is produced in many instances when compounds of boron and of fluorine are brought together.¹³ The most convenient

¹¹ At first boron nitride was obtained by heating boric acid with potassium cyanide, or other cyanogen compounds. It may be more simply prepared by heating anhydrous borax with potassium ferrocyanide, or by heating borax with ammonium chloride. For this purpose one part of borax is mixed as carefully as possible with two parts of dry ammonium chloride, and the mixture heated in a platinum crucible. A porous mass is formed, which, after crushing and treating with water and hydrochloric acid, leaves boron nitride.

¹² When fused with potassium carbonate it forms potassium cyanate, $BN + K_2CO_3 = KBO_2 + KCNO$. All this shows that boron nitride is a nitride of boric acid, $BO(OH) - NH_3 - 2H_2O = BN$. The same is expressed by saying that boron nitride is a compound of the type of the boron compounds BX_3 , with the substitution of X_3 by nitrogen, as the trivalent radicle of ammonia, NH_3 .

¹³ Boron fluoride is frequently evolved on heating certain compounds occurring in nature containing both boron and fluorine. If calcium fluoride is heated with boric anhydride, calcium borate and boron fluoride are formed, and the latter, as a gas, is volatilised:

method of preparing it is by heating a mixture of calcium fluoride with boric anhydride and sulphuric acid, $3\text{CaF}_2 + \text{B}_2\text{O}_3 + 3\text{H}_2\text{SO}_4 = 3\text{CaSO}_4 + 3\text{H}_2\text{O} + 2\text{BF}_3$.¹⁴ It is a colourless liquefiable *gas* (the liquid boils at -100°), which on coming into contact with damp air forms white fumes, owing to its combining with water. One volume of water dissolves as much as 10.50 volumes of this gas (Bazaroff), forming a liquid which disengages boron fluoride when heated, and which distils over unaltered. Boron fluoride chars organic matter, owing to its taking up the water from it, and in this respect it acts like sulphuric acid.

The behaviour of boron fluoride with water must be understood as a reversible reaction, because with water it yields hydrofluoric and boric acids, whilst they, acting on one another, re-form boron fluoride and water. A state of equilibrium is set up between these four substances (and the two reversible reactions), which is distinctly dependent on the mass of the water.^{14b} When boron fluoride is in great excess, then the equilibrated system, which is capable of distilling over (sp. gr. of the liquid 1.77), has a composition $\text{BF}_3, 2\text{H}_2\text{O}$ (or $\text{B}_2\text{O}_3, \text{H}_2\text{O}, 6\text{HF}$). It has also its corresponding salts.¹⁵ It is a caustic liquid, having the properties of a powerful acid; but it does not act on glass, which shows that there is no free hydrofluoric acid present. Under the action of water this system changes, with the formation of boric acid and hydroborofluoric acid (HBF_4), according to the equation $4\text{BF}_3 + 4\text{H}_2\text{O} = 3\text{HBF}_4 + \text{BH}_3\text{O}_3 + 5\text{H}_2\text{O}$.¹⁶ This hydroborofluoric acid has its corresponding

$2\text{B}_2\text{O}_3 + 3\text{CaF}_2 + 2\text{BF}_3 + \text{Ca}_3\text{B}_2\text{O}_6$. The calcium borate, however, retains a certain amount of calcium fluoride.

¹⁴ The decomposition should not be carried on in glass vessels, which contain silica (in order to avoid the formation of silicon fluoride), but in lead or platinum vessels. Boron fluoride by itself does not corrode glass, but the hydrofluoric acid liberated in the reaction may bring a part of the silica into reaction. Boron fluoride should be collected over mercury, as water acts on it, as we shall see afterwards.

^{14b} It appears to me that from this point of view it is possible to understand the apparently contradictory results of different investigators, especially those of Gay-Lussac (and Thenard), Davy, Berzelius, and Bazaroff.

¹⁵ They are called fluoborates. They may be prepared directly from fluorides and borates. Such compounds of halogens with oxygen salts are known in nature (for instance, apatite and boracite), and may be artificially prepared. The composition of the fluoborates—for example, $\text{K}_2\text{BF}_4\text{O}_2$ —may be expressed as that of a double salt $\text{BO}(\text{OK})_2, 3\text{KF}$. If an excess of water decomposes them (Bazaroff), this does not signify that they do not exist, because many double salts are decomposed by water.

¹⁶ Fluoboric acid contains boron fluoride and water, hydrofluoboric acid, boron fluoride, and hydrofluoric acid. It is evident that on the one side the competition between water and hydrofluoric acid, and, on the other hand, their power to combine, are among the forces which act here. From the fact that hydroborofluoric acid, HBF_4 , can only exist in an aqueous solution, one must conclude that it forms a somewhat stable system only in the presence of $3\text{H}_2\text{O}$.

salts—for instance, KBF_4 . On evaporating the aqueous solution this free acid decomposes, with the evolution of hydrofluoric acid, and a particular system is again obtained: $2\text{HBF}_4 + 5\text{H}_2\text{O} = \text{B}_2\text{F}_6\text{H}_{10}\text{O}_5 + 2\text{HF}$. The resultant solution (containing $2\text{BF}_3, 5\text{H}_2\text{O}$, sp. gr. 1.58), which is identical with that formed by the evaporation of a solution of boric acid with hydrofluoric acid, again only contains a compound of boron fluoride with water. Probably there are various other possible and more or less stable states of equilibrium and definite compounds of boron fluoride, hydrofluoric acid, and water.

Nothing of this kind occurs with boron chloride, because hydrochloric acid does not act on boric acid. However, boron combines directly with chlorine at a red heat, forming *boron chloride*, BCl_3 . The boron burns in the chlorine, forming a gas which, in a freezing mixture, condenses into a liquid boiling at 17° , and which gives up its excess of chlorine, if there be any, to mercury. The specific gravity of this liquid is 1.35 at 12° . Boron chloride may also be directly obtained from boric anhydride by the simultaneous action of charcoal and chlorine at a high temperature: $\text{B}_2\text{O}_3 + 3\text{C} + 3\text{Cl}_2 = 2\text{BCl}_3 + 3\text{CO}$. It is also obtained by the action of phosphoric chloride on boric anhydride in a closed tube at 200° . It is completely decomposed by water, like the chloranhydride of an acid, boric acid being formed; hence it fumes in the air: $2\text{BCl}_3 + 6\text{H}_2\text{O} = 3\text{BH}_3\text{O}_3 + 6\text{HCl}$. Boron forms with bromine a similar compound, BBr_3 , boiling at 90° . The vapour densities of the fluoride, chloride, and bromide of boron, show that they contain three atoms of the halogen in the molecule—that is, that boron is a trivalent element forming BX_3 .

As in the first group lithium is followed by sodium, giving a more basic oxide, so in the second group beryllium is followed by magnesium, and so also in the third group there is, besides the lightest element, boron, whose basic character is scarcely defined, *aluminium*, $\text{Al}=27$, whose oxide, alumina, has somewhat distinct basic properties, which, although not so powerful as in magnesium oxide, are more distinct than in boric anhydride. Among the elements of the third group, aluminium is the most widely distributed in nature; it will be enough to mention that it enters into the composition of clay to clearly see the universal distribution of aluminium in the earth's crust.

Alumina is so named from its being the metal of alums (*alumen*).

Clay, which is so widely distributed and familiar to everybody, is the insoluble residue obtained after the action of water containing carbonic acid on many rocks, and especially on the felspars contained in some of them. Felspar is a compound containing potash or soda, alumina, and silica. The primary rocks, like granite, contain many

similar compounds (*see* Chapter XVIII.: Felspars). Felspar is acted on by water containing carbonic acid, all the alkalis (potash and soda), and a portion of the silica passing into the water as substances which are soluble and carried away by it, whilst the alumina and silica left from the felspar remain on the spot where the solution has taken place. This is the original method of the formation of clay in its primary deposits among rocks along whose crevices the atmospheric water has permeated. Such primary deposits often contain a white pure clay, termed *kaolin* or *porcelain clay*. But such clay is a rarity, because the conditions for its formation are rarely met with. The water whilst acting chemically on rocks, at the same time destroys them *mechanically*, and carries off the finely-divided residues of disintegration with it. Clay is most easily subjected to this mechanical action of water, because it is composed of grains of exceedingly small size and void of any visible crystalline structure, which easily remain suspended in water. The cloudy water of running mountain streams generally contains particles of clay in suspension, owing to the above-described chemical and mechanical action of the water on the minerals contained in the mountain rocks. Together with these minute particles of clay the water carries away the coarser components on which it is not able to act—for example, splinters of rock matter, grains of mica, quartz, &c. They were originally held together by those minerals which form clay. When the water acts on these binding minerals, a sandy mass is formed on which water acts mechanically with great ease, and bears away the finely-divided particles with it. The cloudy water in which the particles of clay and sand are held in suspension carries them to, and deposits them at, the estuaries of rivers, lakes, seas, and oceans. The coarser particles are first deposited and form sand and like disintegrated rocky matter, whilst the clay, owing to its finely-divided state, is carried on further, and is only deposited in the still parts of the rivers, lakes, &c. Such disintegrations of rocks and separations of clay from sand have been gradually going on during the millions of years of the earth's existence, and are now proceeding, and have been the cause of the formation of the immense deposits of sandstone and clay now forming a part of the earth's strata. Such beds of clay may have been transferred by currents and streams from one locality to another, so that we must distinguish between primary and secondary deposits of clay. In places these beds of clay have, owing to long exposure under water, and perhaps partially owing to the action of heat, undergone compression, and have formed the rocky masses known as clay slates and schists, which sometimes form entire mountains. Roofing slates belong to this class of rocks.

From what has been said above it will be clear that these deposits can never consist of a chemically pure and homogeneous substance. All kinds of extraneous insoluble matter, and especially sand—that is, fragments of rock, chiefly quartz (SiO_2)—always accompany clay in a greater or less quantity and in more or less coarse particles. But it is possible to considerably purify clay from these impurities, owing to the fact that they are the result of mechanical disintegration, whilst the clay has been formed as a residue of the chemical alteration of rocky matter, and therefore its particles are incomparably more minute than the particles of sand and other rock fragments mixed with it. This difference in the size of the grains causes the clay to remain longer in suspension when shaken up in water than the coarser grains of sand. If clay be shaken up in water, and especially if it be previously boiled in it, and if after the first portion has settled the cloudy water be decanted, it will give a deposit of a very much purer clay than the original. This method is employed for purifying kaolin designed for the manufacture of the best kinds of china, earthenware, &c. A similar method is also employed in the investigation of earths for determining the *composition of soils* chiefly composed of a mixture of sand, clay, limestone, and mould. The limestone is soluble in dilute acids, but neither the clay nor sand passes into solution by this means, and therefore the limestone is easily separated in the investigation of soils. The clay is separated from the sand by a similar method to that described above, and termed *levigation*.¹⁷


¹⁷ The process of *levigation* is based on the difference in the diameters of the particles of clay and sand. In density these particles differ but little from each other, and therefore a stream of water of a certain velocity can only carry away the particles of a certain diameter, whilst the particles of a larger diameter cannot be borne away by it. This is due to the resistance to falling offered by the water. This resistance to substances moving in it increases with the velocity, and therefore a substance falling into water will only move with an increasing velocity so long as the weight of the substance does not equal the resistance offered by the water, and then the movements will be uniform. And as the weight of the minute particles of clay is small, therefore the maximum velocity attained by them in falling is also small. A detached account of the theory of falling bodies in liquid, and of the experiments bearing on this subject, may be found in my work, *Concerning the Resistance of Liquids and Aeronautics*, 1880. The minute particles of clay remain suspended longer in water, and take longer to fall to the bottom, and have more difficulty in doing so. Heavy particles, although of small dimensions, fall more quickly, and are borne away by water with greater difficulty than the lighter. Thus gold and other heavy ores are washed free from sand and clay, and the coarser portions and heavy particles are left behind. A current of water of a certain velocity cannot carry away with it particles of more than a definite diameter and density, but by increasing the velocity of the current a point may be arrived at when it will bear away larger particles. A description of apparatus for the observation of phenomena of this kind is given by Schöne in his memoir in the Transactions of the Moscow Society of Natural Sciences for 1867. In order to be able to accurately vary the velocity of the current of water, a cylinder is employed in which the earth to be experimented on is placed, and water is in-

By treating clay with strong sulphuric acid, which dissolves the alumina in it; and then dissolving the silica (by means of an alkaline carbonate) combined with the alumina in the clay (but not that which occurs in the form of sand, &c.), we may form an idea of the proportion between the component parts of a clay; and by igniting it at a high temperature we may determine the amount of water held in it. In the purer sorts of clay this proportion is about $2\text{SiO}_2 : 2\text{H}_2\text{O} : \text{Al}_2\text{O}_3$.

introduced through the conical bottom of the cylinder. The rate at which the water rises in the cylinder will vary according to the quantity of water flowing per unit of time into the vessel, and consequently particles of various sizes will be carried away by the water flowing over the upper edges of the vessel. Schöne showed by direct experiment that a current of water having a velocity of 0.1 mm. per second will carry away particles having a diameter of not more than 0.0075 mm.—that is, only the most minute—with a velocity $v=0.2$ mm. diameter $d=0.011$ mm.; with $v=0.3$ mm. $d=0.0146$ mm.; with $v=0.4$ mm. $d=0.017$ mm.; with $v=0.5$ mm. $d=0.02$ mm.; with $v=1$ mm. $d=0.03$ mm.; with $v=4$ mm. $d=0.07$ mm.; with $v=10$ mm. $d=0.137$ mm.; with $v=12$ mm. $d=0.15$ mm.; and therefore if the current does not exceed one of these velocities it will only carry away or wash away particles having a diameter less than that indicated. The sand and other particles mixed with the clay will then remain in the vessel. The very minute particles obtained after levigation are all considered as clay, although not only clay but other rock matter may also exist in it as very fine particles. However, this is very seldom the case, and in reality the minute mud separated from all clays has the same composition as the purest kinds of kaolin.

The relation between the amounts of clay and sand in soils used for the cultivation of plants is very important, because a soil rich in clay is denser, heavier, shrinks up under the action of heat, and does not readily yield to the plough in dry or wet weather, whilst a soil rich in sand is friable, crumbling, easily parts with its moisture and dries rapidly, but is comparatively easily worked. Neither crumbling sand nor pure clay can be regarded as good *cultivating soils*. The difference in the amounts of clay and sand in a soil has also a purely chemical signification. Sand is easily permeated by the air, because its particles are not closely packed together. Hence the chemical change of manures proceeds very easily in sandy soils. But on the other hand such soils do not retain the nutritious principles contained in the manure, nor the water necessary for the nourishment of plants by means of their roots. Solutions of nutritious substances, containing salts of potassium, phosphoric acid, &c., when passed through sand only leave a portion moistening the surface of its particles. The sand has only to be washed with pure water and all the adhering portions of solution are washed away. It is not so with clay. If the above solutions be passed through a layer of clay the retention of the nutritive substances of these solutions will be very vigorous; this is partly because of the vast surface which the minute particles of clay expose. The nutritive elements dissolved in water are retained by the particles of clay in a peculiar manner—that is, the absorptive power of clay is very great compared to that of sand—and this has a great significance in the economy of nature. It is evident that for cultivation the most convenient soils in every respect will be those containing a definite mixture of clay and sand, and indeed the most fertile soils have this composition. The study of fertile soils, which is so important for a knowledge of the natural conditions of the introduction of fertilisers, belongs, strictly speaking, to the province of agriculture. In Russia the first foundation of a scientific fertilisation has been laid by Dokuchaeff. As an example only, we will give the composition of four soils: (1) The black earth of the Simbirsk Government; (2) a clay soil from the Smolensk Government; (3) a more sandy soil from the Moscow Government; and (4) a peaty soil from near St. Petersburg. These analyses were made in the laboratory of the St. Petersburg University about 1860, for the sake of experiments on fertilisation (conducted by me) by the Imperial Free Economical Society. 10000 grams of air-dried

In this case the conversion of felspar into kaolin is expressed by the equation :—



the compound $\text{K}_2\text{O}, 4\text{SiO}_2$ passes into solution.

But as a rule clays contain from 45 to 60 p.c. of silica, from 20 to 30 p.c. of alumina, and about 10 p.c. of water ; and it cannot be supposed that clays are always homogeneous, because they are an aggregation of residues (of silico-aluminous compounds) which are unacted on by water. Nevertheless, clays always contain a hydrous compound of alumina and silica, which is able to give up the alumina contained by it as a base to strong sulphuric acid, forming aluminium sulphate, which is soluble in water. After this treatment the silica remains, and is soluble in a solution of an alkaline carbonate.¹⁸

soil contain the following quantities (in grams) of substances capable of dissolving in acids, and of serving for the nourishment of plants.

	(1)	(2)	(3)	(4)
Na_2O	11	5	4	4
K_2O	58	10	7	5
MgO	92	33	19	7
CaO	134	17	14	11
P_2O_5	7	1	7	3
N	44	11	13	16
S	13	7	7	6
Fe_2O_3	341	155	111	46

By chemical and mechanical analysis, the chief component parts per 100 parts of air-dried soil are :

Clay	46	29	12	10
Sand	40	67	86	84
Organic matter	3.7	1.7	0.6	4.1
Hygroscopic water . .	6.3	1.3	0.8	1.9
Weight of a litre in grams .	1150	1270	1350	960

The black earth excels the other soils in many respects.

¹⁸ Everyone knows that a mixture of clay and water is endowed with the property of taking a given form when subjected to a moderate pressure. This peculiar property of clay renders it a precious material for practical purposes. From clay are moulded and manufactured a variety of objects, beginning with the common brick and ending with the most delicate china works of art. This *plasticity of clay* increases with its purity. The specific gravity of pure kaolin is 2.5.

When articles made of clay are dried, the well known hard mass is obtained ; but water washes it away, and furthermore, the cohesion of its particles is not sufficiently great for it to resist the impression of blows, shocks, &c. If such an article be subjected to the action of heat, its volume first decreases, then it begins to lose water, and it shrinks still further (with a continuous mass approximately by $\frac{1}{5}$ of its linear measurement). On the other hand, a great coherence of particles is obtained, and thus burnt clay has the hardness of a stone. Pure clay, however, shrinks so powerfully when burnt that the form given to it is destroyed and it easily forms cracks ; such vessels are also porous, so that they will not hold water. The addition of sand—that is, silica in fine particles—or of *chamotte*—that is, already burnt and crushed clay

Clay is the source from which alumina, Al_2O_3 , and the majority of the compounds of aluminium, are prepared. Among these compounds the most important are the alums—that is, the double sulphates of potassium (and allied metals) and aluminium, $\text{AlK}(\text{SO}_4)_2 \cdot 12\text{H}_2\text{O}$. When clay is treated with sulphuric acid diluted with a certain amount of water, aluminium sulphate, $\text{Al}_2(\text{SO}_4)_3$, is formed; and if potassium carbonate or sulphate is added to this solution, then potash alum is obtained in solution. The alums easily crystallise, and are prepared on a very large scale at works owing to their being employed in the process of dyeing. Alums are soluble in water, and, on the addition of ammonia to their solutions, they give *hydrrous alumina*, or *aluminium hydroxide*, as a white gelatinous precipitate, which is insoluble in water but easily soluble in acids, even when dilute and in aqueous soda or potash. The solubility of alumina in acids indicates the basic character of the oxide, and its solubility in alkalis and its power of forming compounds with them shows the weakness of this basic character and the existence of an intermediate character in it. However, the feeblest acids, even carbonic acid, take up the alkali from such a solution, and the alumina then separates out in a precipitate as the hydroxide. It must also be remembered as characteristic of the salt-forming properties of alumina that it does not combine with such feeble acids as carbonic, sulphurous, or hypochlorous, &c.—that is, its compounds with these acids are decomposed by water. It is also important to mark that the hydroxide is not soluble in aqueous ammonia.

Alumina, Al_2O_3 —that is, the anhydrous aluminium oxide—is met with in nature, sometimes in a somewhat pure state, having crystallised in transparent crystals, which are often coloured by impurities (chromic, cobaltic, and ferric compounds). Such are the ruby and sapphire, the former red and the latter blue. They have a specific

—renders the mass incapable of cracking in the furnace, and much more dense and less porous. Nevertheless, such clay articles (bricks, earthenware vessels, &c.) are still porous to liquids after being burnt, because the clay in the furnace is only baked and does not fuse. In order to obtain articles impervious to water the clay must either be mixed with substances which form a glassy mass in the furnace, permeating the clay and filling up its pores, or else only the surface of the article is covered with such a glassy fusible substance. In the first case the purest kinds of clay give what is known as china, in the second case porcelain or 'faïence.' So, for instance, by covering the surface of clay articles with a layer of the oxides of lead and tin, the well-known white glaze is obtained, because the oxides of these metals give a white gloss when fused with silica and clay. In the preparation of china, fluor spar and finely-ground silica is mixed up into the clay; these ingredients give a mass which is infusible but softens in the furnace, so that all the particles of the clay cohere in this softened mass, which hardens on cooling. A glaze composed of glassy substances, which only fuse at a high temperature, is also applied to the surface of china articles.

gravity 4.0, are distinguished by their very great hardness, which is only second to that of the diamond, and they represent the purest form of alumina. They are found in Ceylon and other islands of the Indian Archipelago, embedded in a rock matrix. *Corundum* is the same alumina coloured brown by a trace of oxide of iron. A very much larger proportion of this impurity occurs in *emery*, which is found in crystalline masses in Asia Minor and in Massachusetts, and which, owing to its extreme hardness, is employed for polishing stones and metals. In this anhydrous and crystalline state the aluminium oxide is a substance which very powerfully resists the action of reagents, and is insoluble both in solutions of the alkalis and of strong acids. It is only capable of passing into solution after being fused with alkalis.¹⁹ Alumina may be obtained in this form by artificial means if the hydroxide be ignited and then fused in the oxy-hydrogen flame. By mixing different oxides with the fused mass we may obtain a transparent and coloured mass of great hardness, and resembling the natural varieties of alumina²⁰ in many respects. Alumina also occurs in nature in combination with water—as, for instance, in the rather rare minerals *hydrargillite* (sp. gr. 2.3), $\text{Al}_2\text{O}_3 \cdot 3\text{H}_2\text{O} = 2\text{Al}(\text{HO})_3$, and *diaspore*, $\text{Al}_2\text{O}_3 \cdot \text{H}_2\text{O} = 2\text{AlO}(\text{HO})$ (sp. gr. 3.4). A less pure hydrate, mixed with ferric oxide, sometimes occurs in masses (at Baux, in the south of France), and is termed *bauxite*; it contains $\text{Al}_2\text{O}_3 \cdot 2\text{H}_2\text{O} = \text{Al}_2\text{O}(\text{HO})_4$ (sp. gr. 2.6). When bauxite is ignited with sodium carbonate, carbonic anhydride is liberated and the alumina then combines with the sodium oxide, forming a saline compound of the oxides of aluminium and sodium. This is taken advantage of in practice for the preparation of pure alumina compounds on a large scale, for bauxite is found in large masses (in the South of France), and the resultant compound of alumina and sodium is soluble in water and does not contain ferric oxide. This solution when subjected to the action of carbonic anhydride gives a precipitate of aluminium hydroxide,²¹ which with acids forms aluminium

¹⁹ The effects of purely mechanical subdivision on the solubility of alumina is evident from the fact that native anhydrous alumina, when converted into an exceedingly fine powder by means of levigation, dissolves in a mixture of strong sulphuric acid and a small quantity of water, especially when heated in a closed tube at 200°, or when fused with acid sulphate of potassium (*see* Vol. I. p. 541, Note 9).

²⁰ The preparation of crystallised alumina is given on p. 62. When alumina, moistened with a solution of cobalt salt, is ignited, it forms a blue mass called Thenard's salt. This coloration is not only taken advantage of in the arts, but also for distinguishing alumina from other earthy substances resembling it.

²¹ The treatment of bauxite is carried on on a large scale, chiefly to obtain alumina from alkaline solutions, free from ferric oxide, because in dyeing it is necessary to have salts of aluminium which do not contain iron. But this end, it would seem, may be also

salts. If aqueous ammonia be added to a solution of aluminium sulphate a gelatinous precipitate is formed, which at first remains suspended in the liquid, and then on settling forms a gelatinous mass, which itself indicates the *colloidal property of aluminium hydroxide*. The following points are characteristic of this colloidal state : (1) in an anhydrous state such a colloidal substance is insoluble in water, as alumina is ; (2) in the hydrated state, it is gelatinous and insoluble in water ; and (3) it is also capable of appearing in solutions, from which it separates out in a non-crystalline state, forming a substance resembling glue. These different states of colloids were distinguished by Graham, who gave them the following very characteristic names. He called the gelatinous form of the hydrate *hydrogel*, i.e. a gelatinous hydrate, and the soluble form of the aqueous compound, *hydrosol*, from the Latin for a soluble hydrate. Alumina readily and frequently assumes these states. The gelatinous hydrate of alumina is its hydrogel. It is, as has been already mentioned, insoluble in water, and, like all similar hydrogels, shows not the faintest sign of crystallisation ; it easily varies in many of its properties with the amount of water it contains, and loses its water on ignition, leaving a white powder of the anhydrous oxide. The hydrogel of alumina is soluble in both acids and alkalis. It may also be obtained by the evaporation of its solutions in such feebly energetic acids as volatile acetic acid. These properties are very frequently made use of in the arts, and especially in *the processes of dyeing*, because the hydrogel of alumina in precipitating attracts a number of colouring matters from their solutions, the precipitate being thus coloured by the dyes attracted.²²

obtained by igniting alumina containing ferric oxide in a stream of chlorine mixed with hydrocarbon vapours, because ferric chloride then volatilises. K. Bayer observed that in the treatment of bauxite with soda, about 4 molecules of sodium hydroxide pass into solution to 1 molecule of alumina, and that on agitating this solution (especially in the presence of some already precipitated aluminium hydroxide), about two-thirds of the alumina is precipitated, so that only 1 molecule of alumina to 12 molecules of sodium hydroxide remains in solution. This solution is straightway evaporated, and again used. In the ignition of sodium carbonate with bauxite, the carbonic anhydride is only completely liberated when a mixture is made in the ratio $\text{Na}_2\text{CO}_3 : \text{Al}_2\text{O}_3$. But, in dissolving, it is best to further add 2 molecules of sodium hydroxide, because otherwise a portion of the alumina remains with the ferric oxide. The hydroxide, which separates from the alkaline solution, contains $\text{Al}(\text{OH})_3$. All these relations bear a great resemblance to those of boric acid. One must imagine that the relation between sodium hydroxide and alumina in solution varies with the mass of water.

If lime be added to a solution of alumina in alkali (sodium aluminate) then calcium aluminate is precipitated, from which acids first extract the lime, leaving aluminium hydroxide, which is easily soluble in acids (Loewig). When sodium aluminate is mixed with a solution of sodium bicarbonate, a double carbonate of the alkali and aluminium is precipitated, which is easily soluble in acids.

²² These coloured precipitates of alumina are termed *lakes*, and are employed in dyeing tissues and in the formation of various pigments—such as pastels, oil colours, &c.

The preparation of fixed dyes and the employment of aluminous compounds in the processes of dyeing is founded on this fact. When precipitated upon the fibres of tissues (cloths, linens, &c.) the aluminium hydroxide renders them impermeable to water; this may be taken advantage of for the preparation of waterproof tissues.

In dye-works the aluminium acetate is generally obtained in solution by taking a solution of alum, which is mixed with a solution of lead acetate. In this case lead sulphate is precipitated and aluminium acetate remains in solution, together with either acetate or sulphate of potassium, according to the amount of acetate of lead first taken. The complete decomposition will be as follows: $\text{KAl}(\text{SO}_4)_2 + 2\text{Pb}(\text{C}_2\text{H}_3\text{O}_2)_2 = \text{K}_2\text{C}_2\text{H}_3\text{O}_2 + \text{Al}(\text{C}_2\text{H}_3\text{O}_2)_3 + 2\text{PbSO}_4$, or the less complete decomposition, $2\text{KAl}(\text{SO}_4)_2 + 3\text{Pb}(\text{C}_2\text{H}_3\text{O}_2)_2 = 2\text{Al}(\text{C}_2\text{H}_3\text{O}_2)_3 + \text{K}_2\text{SO}_4 + 3\text{PbSO}_4$.²³ If the resultant solution of aluminium acetate be

Thus, if organic colouring matters, such as logwood, madder, &c., are added to a solution of any aluminium salt, and then an alkali is added, so that alumina may be precipitated, these pigments, which are by themselves soluble in water, will come down with the precipitate. This shows that alumina is able to combine with the colouring matter, and that this compound is not decomposed by water. The dyes then become insoluble in water. If a dye be mixed with starch paste and aluminium acetate, and then, by means of engraved blocks having a design in relief, we transfer this design to a material, and the material be heated, then the aluminium acetate will leave the hydrogel of alumina which binds the colouring matter, and water will no longer be able to wash the pigment from the material—that is, a so-called ‘fixed’ dye is obtained. In the case of dyeing a material a uniform tint, it is first soaked in a solution of aluminium acetate and then dried, by which means the acetic acid is driven off, while the hydrogel of alumina adheres to the fibres of the material. If the material is then passed through a solution of a dye in water, the former will be attracted to the portions covered with alumina, and closely adhere to them. If certain parts of the material be protected by the application of an acid, such as tartaric, $\text{C}_4\text{H}_6\text{O}_6$, oxalic, citric, &c. (these acids are non-volatile), then the alumina will be dissolved in those parts, and the pigment will not adhere, so that after washing a white design will be obtained on those parts which have been protected by the acid.

²⁵ As the salt of potassium obtained in the solution passes away with the water used for washing, and the salt of lead precipitated has no practical use, this method for the preparation of aluminium acetate cannot be considered an economical one; it is retained in the process of dyeing mainly because both the salts, alum and sugar of lead, employed easily crystallise, it being easy to judge their degree of purity in this form. Indeed, it is very important to employ pure reagents in dyeing, because if impurity is present—such as a small quantity of an iron compound—the tint of the dye changes; thus madders give a red colour with alumina, but if oxide of iron be present the red changes into a violet tint. The aluminium hydroxide is soluble in alkalis, whilst ferric oxide is not. Therefore sodium aluminate—that is, the dissolved compound of alumina in caustic soda—obtained, as has been described, from bauxite, is sometimes employed in dyeing. Another direct method for the preparation of pure aluminium compounds consists in the treatment of *cryolite* containing aluminium fluoride together with sodium fluoride, AlNa_3F_6 . This mineral is exported from Greenland, and is also found in the Urals. It is crushed and heated in reverberatory furnaces with lime, and the resultant mass is treated with water; sodium aluminate is then obtained in solution, and calcium fluoride in the precipitate $\text{AlNa}_3\text{F}_6 + 3\text{CaO} = 3\text{CaF}_2 + \text{AlNa}_3\text{O}_3$. Every aluminium salt gives a solution containing sodium aluminate free from iron, when it is mixed with excess of caustic soda. This

evaporated or further boiled, then the acetic acid passes off and the hydrogel of alumina remains.

The hydrosol of alumina—i.e. the soluble aluminium hydroxide—is more difficult to obtain.²⁴ In order to obtain this soluble variety of alumina, Graham took a solution of its hydrogel in hydrochloric acid—that is, a solution of aluminium chloride, which is able to dissolve a still further quantity of the hydrogel of alumina, forming a basic salt having probably one of the compositions $\text{Al}(\text{HO})\text{Cl}_2$ or $\text{Al}(\text{HO})_2\text{Cl}$. When such a solution, considerably diluted with water, is subjected to dialysis—that is, to diffusion through a membrane²⁵—the hydrochloric acid diffuses through the membrane and leaves the alumina in the form of hydrosol. The resultant solution, even when only containing two or three per cent. of alumina, passes into the hydrogel state with such facility that it is sufficient to transfer it from one vessel to another which has not been previously washed with water, for the entire mass to solidify into a jelly. But a solution containing not more than half a per cent. of alumina may even be boiled without coagulating; however, after the lapse of several days this solution will of its own accord yield the hydrogel of alumina. The most remarkable peculiarity of Graham's solution is that it solidifies on litmus paper, and leaves a blue ring on it, which shows the alkaline—that is, basic—character of the alumina in such a solution. If in the dialysis the

solution, when mixed with a solution of ammonium chloride, gives a precipitate of the hydrogel of alumina: $\text{Al}(\text{OH})_3 + 3\text{NaHO} + 3\text{NH}_4\text{Cl} = \text{Al}(\text{OH})_3 + 3\text{NaCl} + 3\text{NH}_4\text{OH}$. There was originally free soda, and on the addition of sal-ammoniac there is free ammonia, and this does not dissolve alumina, therefore, the hydrogel of the latter is precipitated.

²⁴ Crum first prepared a solution of basic acetate of alumina—that is, a salt containing as large as possible an excess of aluminium hydroxide with as small as possible a quantity of acetic acid. The solution must be dilute—that is, not contain more than one part of alumina per 200 of water—and if this solution be heated in a closed vessel (so that the acetic acid cannot evaporate) to the boiling point of water, for one and a half to two days, then the solution, which apparently remains unaltered, loses its original astringent taste, proper to solutions of all the salts of alumina, and has instead the purely acid taste of vinegar. The solution then no longer contains the salt, but acetic acid and the hydrosol of alumina in an uncombined state; they may be isolated from each other by evaporating the acetic acid in shallow vessels at the ordinary temperature, and with a thin layer of liquid the alumina does not separate as a precipitate. When the acid vapours cease to come off there remains a solution of the hydrosol of alumina, which is tasteless and has no action on litmus paper. When concentrated, this solution acquires a more and more gluey consistency, and when entirely evaporated over a water-bath it leaves a non-crystalline glue-like hydrate, whose composition is $\text{Al}_2\text{H}_4\text{O}_5 = \text{Al}_2\text{O}_3 \cdot 2\text{H}_2\text{O}$. The smallest quantity of alkalis, and of many acids and salts, will convert the hydrosol into the hydrogel of alumina—that is, convert the aluminium hydroxide from a soluble into an insoluble form, or, as it is said, cause the hydrate to coagulate or gelatinise. The smallest amount of sulphuric acid and its salts will cause the alumina to gelatinise—that is, cause the hydrogel to separate. Many such colloidal solutions are known (Vol. I. p. 98, Note 54).

²⁵ In a dialyser, Vol. I. p. 63, Note 18.

basic chloride be replaced by a similar acetate, a hydrosol of alumina is obtained which does not act on litmus.

The different states in which the hydrates of alumina occur and are prepared resemble similar varieties of the hydrates of the oxides of iron and chromium, of molybdic and tungstic acids, as well as of phosphoric and silicic acids, of many sulphides, proteid substances, &c. We shall therefore have occasion to recur to this subject in the further course of this work.

With respect to alumina as a base, it is very important to observe that it is not only capable of combining with other bases²⁶ but that it does not give salts with feeble volatile acids (like carbonic and hypochlorous); it forms salts which are easily decomposed by water, especially when heated,²⁷ as well as double and basic salts,²⁸ so that it forms a clear example of a feeble base.²⁹ To these characteristics of alumina we must add that it not only gives compounds of the type

²⁶ Compounds of alumina with bases (aluminates, *see* Note 21) are sometimes met with in nature. Such are spinel (*see* p. 62), $\text{MgO} \cdot \text{Al}_2\text{O}_3 = \text{MgAl}_2\text{O}_4$, chrysoberyl, BeAl_2O_4 , and others. Magnetic oxide of iron, $\text{FeO} \cdot \text{Fe}_2\text{O}_3 = \text{Fe}_3\text{O}_4$, and compounds like it, belong to the same class. Here we evidently have a case of combination 'by analogy,' as in solutions and alloys, accompanied by the formation of strictly definite saline compounds, and such instances form a clear transition from so-called solutions and certain mixtures to the type of true salts. From this aspect, which I long ago introduced, many sides of chemical relations become considerably clearer.

²⁷ Not only aluminium acetate (Note 24), but also every other aluminium salt with a volatile acid, parts with its acid on heating an aqueous solution—that is, is decomposed by water. By dissolving aluminium hydroxide in nitric acid we may easily obtain a well-crystallising *aluminium nitrate*, $\text{Al}(\text{NO}_3)_3 \cdot 9\text{H}_2\text{O}$, which fuses at 73° without decomposing (Ordway), gives a basic salt, $2\text{Al}_2\text{O}_3 \cdot 6\text{HNO}_3$, at 100° , and at 140° leaves the aluminium hydroxide perfectly free from the elements of nitric acid. But the solutions of this salt, like those of the acetate, are also able to yield aluminium hydroxide. From all this it is evident that we must suppose the solutions of this and like salts to contain an equilibrated dissociated system, containing the salt, the acid, and the base, and their compounds with water, as well as partly the molecules of water itself. Such examples much more clearly confirm those conceptions of solutions which are given in the first chapter than a general preliminary acquaintance with the subject can do.

²⁸ Many double salts, especially silicates—like the orthoclases, micas, &c., cryolite (Note 23), &c.—as well as basic salts, are met with in nature, and are easily formed in a number of cases. As an example of native basic salts we may cite *alunite*, or *alum-stone* (sp. gr. 2.6), which sometimes occurs in crystals, but more frequently in fibrous masses. It has been found in masses in the Caucasus, and in Western Europe the locality of Tolfa, near Rome, is known. Its composition is $\text{K}_2\text{O} \cdot 3\text{Al}_2\text{O}_3 \cdot 4\text{SO}_3 \cdot 6\text{H}_2\text{O}$ (alunite contains $9\text{H}_2\text{O}$). It is soluble in water, but not decomposed by it, but after being slightly ignited it gives up alum to it. It may be artificially prepared by heating a mixture of alum with aluminium sulphate in a closed tube at 230° .

²⁹ As the colloidal properties are particularly sharply developed in those oxides (Al_2O_3 , SiO_2 , MoO_3 , SnO_2 , &c.) which show (like water also) the properties of feeble bases and feeble acids, there is probably some causal reason for this coincidence, all the more so as among organic substances—gelatins, albumins, &c.—the representatives of the colloids also have the property of feebly combining with bases and acids (*see* the following chapter on silica).

AlX_3 , but also the polymeric type Al_2X_6 , even when X is a simple univalent haloid like chlorine. Deville and Troost showed (1857) that the vapour density of aluminium chloride (about 400°) is 9.37 with respect to air—that is, nearly 135 with respect to hydrogen—and therefore the weight of its molecule is expressed by Al_2Cl_6 , and not $AlCl_3$,³⁰ although in the case of boron, arsenic, and antimony, which

³⁰ Since Deville's experiments the question of the density of aluminium chloride has been frequently recurred to. The subject has more especially occupied the attention of Nilson, Pettersson, Friedel and Crafts, and V. Meyer and his collaborateurs. In general, it has been found that at low temperatures (up to 440°) the density is constant, and indicates a molecule Al_2Cl_6 ; whilst depolymerisation probably (although it is not yet certain) takes place at higher temperatures, and the molecule $AlCl_3$ is obtained. Along with this there has been, and is now, a difference of opinion as to the vapour density of aluminium ethyl and methyl—for instance, as to whether $Al(CH_3)_3$ or $Al_2(CH_3)_6$ expresses the molecule of the latter. The interest of these researches is intimately connected with the question of the valency of aluminium, if we hold to the opinion (which is quite foreign to the author of this work) that elements in their corresponding compounds have a constant and strictly definite valency. In this case the molecule $AlCl_3$, or $Al(CH_3)_3$, would show that Al is trivalent, and consequently the compounds of aluminium are $Al(OH)_3$, AlO_3Al , and, in general, AlX_3 . But if the molecule be Al_2Cl_6 , then it is not compatible—for the followers of the doctrine of the invariable valency of the elements—with the idea of the trivalency of aluminium, and they recognise it to be quadrivalent like carbon by likening Al_2Cl_6 to ethane $C_2H_6 = CH_3CH_3$, although this did not explain why Al does not form $AlCl_4$, or, in general, AlX_4 . In this work another representation is introduced and, according to it, although aluminium, as an element of Group III., gives compounds of the type AlX_3 , still this does not exclude the possibility of these molecules combining with others, and consequently with *each other*—that is, forming Al_2X_6 ; just as the molecules of univalent elements appear as H_2 , or as Na, and the molecules of bivalent elements as Zn , or as S_2 , or even S_8 . It would be strange to ask whether mercury as vapour is uni- or bi-valent? does it correspond with HgX , or HgX_2 ? Evidently, neither one nor the other. Before all it must be seen that the limiting form does not exhaust all power of combination, it only exhausts the capacity for combination with those X's, but the saturated substance may afterwards combine with *whole molecules*, which fact is best proved by the capacity of substances to form crystalline compounds with water, ammonia, &c. But in some substances this faculty for further combinations is not well developed (for instance, carbon tetrachloride, CCl_4), and in others more so. AlX_3 combines with many other molecules. If a limiting form, which does not combine with new X's, combines, however, with other whole molecules, then it will naturally in some instances combine with itself, will polymerise. In this manner the mind clearly grasps that those forces which cause S_2 to unite itself to Cl_2 , or C_2H_4 to Cl_2 , &c., also unite molecules of a similar kind together; thus *polymerisation* ceases to be an isolated fragmentary phenomenon, and chemical combinations 'by analogy' receive a particular and important interest. In conformity to these views the following conclusion may be made concerning the compounds of aluminium. They are of the type AlX_3 in the limit, like BX_3 , but those limiting forms are still able to combine to form AlX_5 , RZ , and the aluminium chloride is a compound of this kind—*i.e.* $(AlX_3)_2$. In boron, in BCl_3 , this faculty to form further compounds is less developed. Hence it appears as BCl_3 , and not $(BCl_3)_2$. This is clearly proved in reality. We shall see that aluminium chloride gives a compound with many other chlor-anhydrides. Polymerisation is not only possible when a substance has not attained the limit (although it is more probable then), but also when the limiting form has been formed, if only the latter has the faculty of combining with other whole molecules. Therefore we may conclude that aluminium, like boron, is trivalent if lithium and sodium are univalent, magnesium bivalent, and carbon tetravalent. In a word, there is no

give oxides R_2O_3 of the same composition as Al_2O_3 , the chlorine compounds form non-polymeric molecules, BCl_3 , $AsCl_3$, $SbCl_3$.³¹ This duplication (polymerisation) of the form AlX_3 is connected with the facility with which the salts of aluminium combine with other salts to form double salts, and with aluminium hydroxide itself to form basic salts.

Aluminium sulphate, $Al_2(SO_4)_3$, which is obtained by treating clay or the hydrates of alumina with sulphuric acid, crystallises in the cold with $27H_2O$, or at the ordinary temperature in pearly crystals, which are greasy to the touch and contain $16H_2O$.³² Its solutions act like sulphuric acid—for instance, evolve hydrogen with zinc, forming basic salts, which are sometimes met with in nature (*aluminite*, $Al_2O_3 \cdot SO_3 \cdot 9H_2O$, *alumiane*, $Al_2O_3 \cdot 2SO_3$, and others), which may be obtained by the decomposition of normal salts and by the direct solution of the hydroxide in normal salts: these exhibiting a varying composition, $(Al_2O_3)_n(SO_3)_m(H_2O)_q$, where m/n is less than 3. With solutions of the alkali sulphates (potassium, sodium, ammonium, rubidium, and caesium sulphates), the normal salt easily forms double salts, termed *alums*—for example, the ordinary crystalline alum contains $KAl(SO_4)_2 \cdot 12H_2O$, or $K_2SO_4 \cdot Al_2(SO_4)_3 \cdot 24H_2O$. In the ammonium alums (which leave a residue of alumina when ignited) the potassium is replaced by ammonium (NH_4). Alums are used in large quantities, because there is scarcely any other salt which crystallises so easily as the last-mentioned. In this respect the alums formed by potassium and ammonium are equally convenient to purify, because they present a considerable difference in their solubility at the ordinary and higher temperatures. If the deposition be conducted rapidly, the salt separates in minute crystals, but if it be slowly deposited, especially in large masses, as at works, then crystals several centimetres long are

reason to consider that aluminium is capable of forming compounds AlX_4 , and in this manner to explain the existence of the molecule Al_2Cl_6 . The fact that it exists, together with the existence of AlX_3 , and perhaps of even $AlCl_5$, is one of the indications of the insufficiency of the doctrine of an invariable valency of the elements as their fundamental property (Note 31).

Furthermore, there are many reasons for thinking that AlF_3 , Al_2O_3 , and other empirical formulæ do not express the molecular weight of these compounds, but that it is much higher: Al_nF_{3n} , $Al_{2n}O_{3n}$.

³¹ In the case of gallium, as a close analogue of aluminium, Lecoq de Boisbaudran (1880) showed that probably the molecule gallium chloride contains Ga_2Cl_6 at low temperatures and high pressures, and that it dissociates into $GaCl_3$ at high temperatures and low pressures. According to the observations of the investigators given in Note 30, the molecule of indium chloride seems to appear in the simplest form, $InCl_3$, and does not polymerise (see Note 30).

³² The pure salt ($16H_2O$) is not hygroscopic. In the presence of impurities the amount of water increases to $18H_2O$, and the salt becomes hygroscopic.

sometimes obtained. At a higher temperature alums are very much more soluble, and crystallise with greater difficulty, and are therefore less easily freed from impurities; at 0° 100 parts of water dissolve 3 parts, at 30° 22 parts, at 70° 90 parts, and at 100° 357 parts of potassium alum.³³ The solubility of ammonium alum is slightly less. The specific gravity of potassium alum is 1.74, of ammonium alum 1.63, and of sodium alum 1.60. Alums easily part with their water of crystallisation; thus potash alum partially effloresces when exposed to the air, and loses 9 mol. H_2O under the receiver of an air-pump. At 100° dry air, if passed over alums, takes up nearly all their water. As we have already mentioned (Chap. XV.), the law of isomorphous substitutions evinces itself more clearly in the alums than in any other salts, and all alums not only contain an equal amount of water of crystallisation, $\text{MR}(\text{SO}_4)_2 \cdot 12\text{H}_2\text{O}$, where $\text{M}=\text{K}, \text{NH}_4, \text{Na}$, $\text{R}=\text{Al}, \text{Fe}, \text{Cr}$, and not only appear in crystals whose planes are inclined at equal angles, but they also give every possible kind of isomorphous mixture. The aluminium in them is easily replaced by iron, chromium, indium, and partly by others, whilst the potassium may be substituted by sodium, rubidium, ammonium, and thallium, and the sulphuric acid may be replaced by selenic and chromic acids.

Aluminium chloride, Al_2Cl_6 , is obtained, like the other similar chlorides, either directly from chlorine and the metal, or by heating to redness an intimate mixture of the amorphous anhydrous oxide and charcoal in a stream of chlorine. The resultant sublimate is very volatile,³⁴ and forms a crystalline, easily-fusible mass, which deliquesces in the air and easily dissolves in water, with the evolution of a large amount of heat. In this respect aluminium chloride resembles the chlor-anhydrides of the acids, and probably in the aqueous solution the elements of the hydrochloric acid are already separated, at least partially, from the aluminium hydroxide. The solution may also be obtained by the action of aluminium hydroxide on hydrochloric acid. On evaporating this solution, hydrochloric acid and aluminium hydroxide are liberated. But with an excess of hydrochloric acid, and if the solution be heated in a closed tube, then on cooling crystals of

³³ The common form of crystals of alums is octahedral, but if this solution contains a certain small excess of alumina above the ratio $2\text{Al}(\text{OH})_3$ to K_2SO_4 , and not more sulphuric acid than $3\text{H}_2\text{SO}_4$ to $2\text{Al}(\text{OH})_3$, then it easily forms combinations of the cube and octahedron, and these alums are called 'cubic' alums. They are valued by the dyer because they can contain no iron in solution, for oxide of iron is precipitated before alumina, and if the latter be in excess there can be no oxide of iron present. These alums were long exported from Italy, where they were prepared from alunite (Note 28).

³⁴ Aluminium chloride fuses at 178° , boils at 183° (pressure 755 mm., at 168° under a pressure of 250 mm., and at 213° under 2278 mm.), according to Friedel and Crafts.

$\text{AlCl}_3 \cdot 6\text{H}_2\text{O}$ are obtained—that is, aluminium chloride both combines with water and is decomposed by it. And the faculty of the type AlX_3 for combining with other molecules is seen in the compounds of AlCl_3 with many other chlorine compounds. So, for example, a mixture of aluminium chloride with sulphur tetrachloride gives $\text{Al}_2\text{Cl}_6 \cdot \text{SCl}_4$ under the action of chlorine, whilst with phosphorus pentachloride it forms $\text{AlCl}_3 \cdot \text{PCl}_5$; it also combines with NOCl . In all such compounds it is not Al_2Cl_6 which enters into their composition, but apparently only AlCl_3 . Thus the compounds $\text{AlCl}_3 \cdot \text{NOCl}$, $\text{AlCl}_3 \cdot \text{POCl}_3$, $\text{AlCl}_3 \cdot 3\text{NH}_3$, $\text{AlCl}_3 \cdot \text{KCl}$, $\text{AlCl}_3 \cdot \text{NaCl}$ are known.⁵⁵ The compound of aluminium and sodium chlorides, AlNaCl_4 , is very fusible and much more stable in the air than aluminium chloride itself. It seems to be of the same type as the alums. This compound, AlNaCl_4 , is employed in the extraction of metallic aluminium, as we shall presently proceed to describe. Aluminium bromide, which is obtained by the direct combination of metallic aluminium with bromine, closely resembles the chloride; it melts at 90° , volatilises at 270° , and its vapour density indicates the formula Al_2Br_6 . Aluminium iodide is obtained by heating iodine with finely-divided aluminium in a closed tube; it is so

⁵⁵ Here we see an instance in confirmation of what has been said in Note 30. We will cite still another instance confirming the power of alumina to enter into complex combinations. Alumina, moistened with a solution of calcium chloride, gives, when ignited, an anhydrous crystalline substance (tetrahedral), which is soluble in acids, and contains $(\text{Al}_2\text{O}_3)_6(\text{CaO})_{10}\text{CaCl}_2$. Even clay forms a similar stoney substance, which might be of practical use.

Among the most complex compounds of aluminium, *ultramarine*, or *lapis lazuli*, must be mentioned. It occurs in nature near Lake Baikal, in crystals, some colourless and others of various tints—green, blue, and violet. When heated it becomes dull and acquires a very brilliant blue colour. In this form it is used for ornaments (like malachite), and as a brilliant blue pigment. Now ultramarine is prepared artificially in large quantities, and this process forms one of the very important conquests of science; for the blue tint of ultramarine has been the object of many scientific researches, which have culminated in the fabrication of this native substance. The most characteristic fact bearing on ultramarine is that when placed in sulphuric acid it evolves hydrogen sulphide and becomes colourless. It is evident that the blue colour of ultramarine is due to the presence of sulphides. If clay be heated in a furnace with sodium sulphate and charcoal (sodium sulphide is formed) without the access of air, then a white mass is formed, which becomes green when heated in the air, and when treated with water it leaves a colourless substance known as ‘white ultramarine.’ When ignited in the air it absorbs oxygen and turns blue. The reason of the coloration is ascribed to the presence of metallic sulphides or polysulphides, but it is most probable that silicon sulphide, or its oxysulphide, SiOS , is present. At all events, the sulphides play an important part, but the problem is not yet quite clear. To white ultramarine the formula $\text{Na}_3\text{Al}_6\text{Si}_6\text{O}_{24}\text{S}$ is ascribed. The green probably contains more sulphur, and the blue a still larger quantity. It is supposed to contain $\text{Na}_3\text{Al}_6\text{Si}_6\text{O}_{24}\text{S}_5$. It is more probable (according to Guckelberger, 1892) that the composition of the blue varies between $\text{Si}_{18}\text{Al}_{18}\text{Na}_{20}\text{S}_8\text{O}_{71}$ and $\text{Si}_{18}\text{Al}_{12}\text{Na}_{20}\text{S}_6\text{O}_{69}$. The latter may be expressed as $(\text{Al}_2\text{O}_3)_6(\text{SiO}_2)_{18}(\text{Na}_2\text{O})_{20}\text{S}_6\text{O}_{59}$, which would indicate the presence of insufficiently-oxidised sulphur in ultramarine.

easily decomposed by oxygen that its vapour even explodes when mixed with it.³⁶

Metallic aluminium was first prepared by Wöhler, who did so much for the early study of organic chemistry and made the first synthesis (of urea, Vol. I. p. 399) of organic substances. Wöhler obtained metallic aluminium as a grey powder in 1822 by the action of potassium on aluminium chloride. He afterwards (in 1854) obtained it as a white compact metal, unoxidisable in the air, and acted on with difficulty by acids. Owing to the vast and wide occurrence of clay, many efforts have been made in investigating in detail the methods for the extraction of this metal. These efforts have been completed (1854) by Sainte-Claire Deville, who is renowned for his doctrine of dissociation. The extraction of this metal requires the preliminary preparation of sodium. Experiments on a large scale have proved that the alloys of aluminium have many valuable properties, whilst the metal itself has not proved to be so suitable for technical purposes as was at first thought. Nitric acid, indeed, does not act on it, but the alkalis, alkaline substances, and even salts—for instance, moist table salt—humidity, &c., tarnish it, and hence objects made of aluminium suffer at the surfaces, alter, and cannot, as was hoped, replace the precious metals, from which it differs in its extreme lightness. Some alloys made with aluminium are, however, very valuable in their properties and applications.

The technical method of the preparation of metallic aluminium is based on the decomposition of the above-mentioned compound of sodium and aluminium chlorides by metallic sodium. The compound is obtained by passing the vapour of aluminium chloride (evolved from an ignited mixture of alumina, extracted from bauxite or cryolite,

³⁶ At the ordinary temperature aluminium does not decompose water, but if we add to the water a small quantity of iodine, or of hydriodic acid and iodine, or of aluminium iodide and iodine, then hydrogen is abundantly evolved. It is evident that here the reaction proceeds at the expense of the formation of Al_2I_6 , and that this substance, with water, gives aluminium hydroxide and hydriodic acid, which, with aluminium, evolves hydrogen. Aluminium probably belongs to the metals having a greater affinity for oxygen than for the halogens (Chapter XI. Note 13).

All these halogen compounds of aluminium are soluble in water. *Aluminium fluoride*, AlF_3 (Al_nF_{3n}), is insoluble in water. It is obtained by dissolving alumina in hydrofluoric acid; a solution is then formed, but it contains an excess of hydrofluoric acid. When this solution is evaporated, crystals containing $\text{Al}_2\text{F}_6 \cdot \text{HF} \cdot \text{H}_2\text{O}$ are obtained. They are also insoluble in water. By saturating the above solution with a large quantity of alumina, and then evaporating, we obtain crystals having the composition $\text{Al}_3\text{F}_8 \cdot 7\text{H}_2\text{O}$. All these compounds, when ignited, leave insoluble anhydrous aluminium fluoride. It forms colourless rhombohedra, which are non-volatile, of sp. gr. 3.1, and are decomposed by steam into alumina and hydrofluoric acid. The acid solution apparently contains a compound which has its corresponding salts; by the addition of a solution of potassium fluoride, a gelatinous precipitate of AlK_3F_6 is obtained. A similar compound occurs in nature—namely, AlNa_3F_6 , or *cryolite*, sp. gr. 3.0.

with charcoal in a stream of chlorine) over red-hot salt, when, if the temperature be sufficiently high, the compound AlNaCl_4 is itself volatilised, and may in this manner be obtained pure. A mixture of this compound with salt and fluor spar, or with cryolite, is heated with a certain excess of sodium, cut into small lumps. On a large scale this operation is carried on in special furnaces with a small access of air and at a high temperature. The decomposition essentially takes place according to the equation $\text{NaAlCl}_4 + 3\text{Na} = 4\text{NaCl} + \text{Al}$. Neither charcoal nor zinc will reduce the oxygen compounds of aluminium; even sodium and potassium do not act on alumina.³⁷

Aluminium has a white colour resembling that of tin—that is, it is greyer than silver, it has the feebly dull lustre of tin, but compared to tin and pure silver aluminium is very hard. Its density is 2.67—that is, it is nearly four times lighter than silver. It melts at an incipient red heat (600°), and in so doing is so slightly oxidised that it may be easily cast into moulds, and may be obtained in large masses in this manner. At the ordinary temperature it does not alter in the air, and if taken in a compact mass it burns with great difficulty at a white heat; but in thin sheets, into which it may be rolled, or as a very fine wire, it burns with a brilliant white light, because it forms an infusible and non-volatile oxide. Aluminium itself is non-volatile at a furnace heat. Dilute sulphuric acid has no action on it, but the strong acid dissolves it, especially with the aid of heat. Nitric acid, dilute or strong, has no action whatever on it. However, hydrochloric acid dissolves aluminium with great ease, as also do solutions of caustic soda and potash. In the latter cases hydrogen is evolved.

Aluminium forms alloys with different metals with great ease. Among them the copper alloy is of practical use. It is called *aluminium bronze*. This alloy is prepared by immersing 11 p.c. to 12 p.c. by weight of metallic aluminium in molten copper at a white heat. The formation of the alloy is accompanied by the development of a considerable quantity of heat, so that the alloy glows to a bright white heat. This alloy, which corresponds with the composition AlCu_3 ,

³⁷ Originally the manufacture of aluminium was carried on at Salindres, near Alais, in the South of France. At present it is produced in very large quantities in England. A great number of methods have been tried for the preparation of aluminium and its alloys with copper and iron, from cryolite and clay, especially by the aid of the galvanic current, but as yet the most advantageous method is that given by Deville. There is no doubt that in time the alloys of aluminium will be very widely used, and therefore the manufacture of aluminium will extend; but it is difficult to imagine that the cost of extraction of the metal will decrease sufficiently for it to replace iron, copper, zinc, and other common metals, whose properties are very much altered when alloyed with aluminium (for example, their hardness, casting capacities, &c.).

presents an exceedingly homogeneous mass, especially if perfectly pure copper is taken. It is distinguished for its capacity to fill up the most minute impressions of the mould into which it may be cast, and by its extraordinary elasticity and toughness, so that objects cast from it may be hammered, drawn, &c., and at the same time it is fine-grained and exceedingly hard, takes an excellent polish, and, what is most important, its surface then remains almost unchangeable in the air, and has a colour and lustre which may be compared to that of gold alloys. Hence aluminium bronze is much used in the arts for making spoons, watches, vessels, forks, knives, and for ornaments, &c. No less important is the fact that the admixture of one-thousandth part of aluminium with steel renders its castings homogeneous (free from cavities) to an extent that could not be arrived at by other means, nor does the quality of the steel in any respect lose by this admixture, but rather is it improved. In a pure state, aluminium is only employed for such objects as require the hardness of metals with comparative lightness, such as telescopes and various physical apparatus.

According to the periodic system of the elements, the analogues of magnesium are zinc, cadmium, and mercury in the second group. So also in the third group, to which aluminium belongs, we find its corresponding analogues *gallium*, *indium*, and *thallium*. They are all three so rarely and sparingly met with in nature that they could only be discovered by means of the spectroscope. This fact shows that they are partially volatile, as should be the case according to the property of their nearest neighbours, the very volatile zinc, cadmium, and mercury. Like them, in gallium, indium, and thallium the density of the metal, decomposability of compounds, &c., rises with the atomic weight. But here we find a peculiarity which does not exist in the second group. In the latter, the fusibility increases with the atomic weight of magnesium, zinc, cadmium, and mercury; indeed, the heaviest metal—mercury—is a liquid. In the third group it is not so. In order to understand this it is sufficient to turn our attention to the elements of the further groups of the uneven series—for instance, to the V. group, containing phosphorus, arsenic, and antimony, or to the VI. group, where are sulphur, selenium, and tellurium, and also to the VII. group, where chlorine, bromine, and iodine are situated. In all these instances the fusibility decreases with a rise of atomic weight; the members of the higher series, the elements of a high atomic weight, fuse with greater difficulty than the lighter elements. The representatives of the uneven series of the III. group, aluminium, gallium, indium, thallium, forming, as they do, a transition, present

a, so to say, intermediate phenomenon. Here the most fusible of all is the medium metal gallium,³⁸ which fuses at the heat of the hand; whilst indium, thallium, and aluminium fuse at much higher temperatures.

Zinc (II. group), which has an atomic weight 65, should be followed in the III. group by an element with an atomic weight of about 69. It will be in the same group as Al, and should consequently give R_2O_3 , RCl_3 , $R_2(SO_4)_3$, alums, and like compounds analogous to those of aluminium. Its oxide should be more easily reducible to metal than alumina, just as zinc oxide is more easily reduced than magnesia. The oxide R_2O_3 should, like alumina, have feeble but clearly-expressed basic properties. The metal reduced from its compounds should have a greater atomic volume than zinc, because in the fifth series, proceeding from zinc to bromine, the volume increases. And as the volume of zinc = 9.2, and of arsenic = 18, therefore that of our metal should be near to 12. This is also evident from the fact that the volume of aluminium = 11, and of indium = 14, and our metal is situated in the III. group, between aluminium and indium. If its volume = 11.5 and its atomic weight be about 69, then its density will be nearly 5.9. The fact of zinc being more volatile than magnesium gives reason for thinking that the metal in question will be more volatile than aluminium, and therefore for expecting its discovery by the aid of the spectroscope, &c.

These properties were indicated by me for the analogue of aluminium in 1871, and I named it (*see* Chapter XV.) eka-aluminium. In 1875, Lecoq de Boisbaudran, who had done much work in spectrum analysis, discovered a new metal in a zinc blende from the Pyrenees (Pierrefitte). He recognised its individuality and distinction from zinc, cadmium, indium, and the other companions of zinc by means of the spectroscope; but he obtained only several fractions of a centigram of it free. But few of its reactions were determined, as, for instance, that barium carbonate precipitates a new oxide from its salts (alumina, as is known, is also precipitated). Lecoq de Boisbaudran named the newly-discovered metal *gallium*. As one would expect the same properties for eka-aluminium as were observed in gallium, I at the time pointed out this fact in the *Memoirs* of the Paris Academy of Sciences. All the subsequent observations of Lecoq de Boisbaudran

³⁸ It is the same in the IV. group of the uneven series, where tin is the most fusible. So the temperature of fusion rises on both sides of tin (silicon is very infusible; germanium, 900°; tin, 230°; lead, 326°); as it also does in the III. group, starting from gallium, for indium fuses at 176°, more difficultly than gallium but more easily than thallium (294°). Aluminium also fuses with greater difficulty than gallium.

confirmed the identity between the properties of gallium and those indicated for eka-aluminium. Immediately after this the ammonium alum of gallium was obtained, but the most weighty proof of all was shown in the fact that the density of gallium was first found to be different (4.7) from that indicated above, whilst afterwards, when the metal was carefully purified from sodium (which was first used as a reducing agent), it proved to be just that (5.9) which would have been looked for in the analogue of aluminium, eka-aluminium or gallium; and, what was very important, the equivalent (23.3) and atomic weight (69.8) determined by the specific heat (0.08) were shown by experiment to be such as would be expected. These facts confirmed the universality and applicability of the periodic system of the elements. It must be remarked that previous to it there was no means of either foretelling the properties or even the existence of undiscovered elements.³⁹

Much more light has been thrown on that element of the aluminium group which follows after cadmium (its position in the periodic system is III., 7, that is, it is in the III. group in the 7th series). This is *indium*, In, which also occurs in small quantities in certain zinc ores. It was discovered (1863) by Reich and Richter (and more fully investigated by Winkler) in the Freiberg zinc ores, and was named indium from the fact that it gives to the flame of a gas-burner a blue coloration, owing to the indigo blue spectral lines proper to it. The equivalent (to hydrogen) of indium = 37.7, and if it be an analogue of aluminium, and if the composition of its oxide be In_2O_3 , then its atomic weight will be $3 \times 37.7 =$ about 113—that is, near to the atomic weight of cadmium, $\text{Cd} = 112$, as aluminium is near to magnesium. If the formula of the indium oxide be taken as In_2O_3 ($\text{In} = 113$), then all its properties are known, as has been explained in Chapter XV. The specific heat of the metal confirms its atomic weight, $\text{In} = 113$. It has been shown to be equal to 0.057 (according to Bunsen) and 0.055 (according to the author's determination), and these numbers correspond

³⁹ The spectrum of gallium is characterised by a brilliant violet line having a wave length = 417 millionths of a millimetre. The metal is separated from the solution, containing a mixture of the many metals occurring in the zinc blende, on the basis of the following reactions: it is precipitated by sodium carbonate in the first portions; it gives a sulphate which, on boiling, easily decomposes into a basic salt, very slightly soluble in water; and it is deposited in a metallic state from its solutions by the action of a galvanic current. It fuses at $+80^\circ$, and, when once fused, it remains liquid for some time. It oxidises with difficulty, evolves hydrogen from hydrochloric acid and from potassium hydroxide, and, like all feeble bases (for instance, alumina and indium oxide), it easily forms basic salts. The hydroxide is soluble in a solution of caustic potash, and slightly so (like alumina) in caustic ammonia.

with the atomic weight 113, because the product of 113 into 0.56 is equal to 6.3, the atomic heat of other metals.⁴⁰

Inasmuch as we found among the analogues of magnesium in the II. group a metal, mercury, heavier and more easily reduced than the rest, and giving two grades of oxidation, so we should expect to find a metal among the analogues of aluminium in the III. group which would be heavy, easily reduced, and give two grades of oxidation, and would have an atomic weight greater than 200. Such is *thallium*. It forms compounds of a lower type, TlX , besides the higher unstable type TlX_3 , just as mercury gives HgX_2 and HgX . In the form of the thallic oxide, Tl_2O_3 , the base is but feebly energetic, as would be expected by analogy with the oxides Al_2O_3 , Ga_2O_3 , and In_2O_3 , whilst in thallic oxide, Tl_2O , the basic properties are sharply defined, as might be expected according to the properties of the type R_2O (Chapter XV.). *Thallium* was discovered in 1861 by Crookes and by Lamy in certain pyrites. When pyrites are employed in the manufacture of sulphuric acid, they are burned, and they give besides sulphurous anhydride the vapours of various substances which accompany the sulphur, and are volatile. Among these substances arsenic and selenium are found, and together with them, thallium. These substances accumulate in a more or less considerable quantity in the tubes through which the vapours formed in the combustion of the pyrites have to pass. The sulphurous anhydride passes on to the further chambers, whilst these substances condense on cooling. When the methods of spectrum analysis were discovered (1860), a great number of substances were subjected to spectroscopic research, and it was observed that those sublimations which are obtained in the combustion of certain pyrites contained an element having a very sharply-defined and characteristic spectrum—namely, in the green portion of the spectra it gave a sharp green band (wave length 535 mil-

⁴⁰ The vapour density of indium chloride, $InCl_3$ (Note 81), determined by Nillson and Pettersson, confirms this atomic weight.

Indium is separated from zinc and cadmium, with which it occurs, on the basis of the fact that its hydroxide is insoluble in ammonia, that the solutions of its salts give indium when treated with zinc (hence indium is dissolved after zinc by acids), and that they give a precipitate with hydrogen sulphide even in acid solutions. Metallic indium is grey, has a sp. gr. of 7.42, fuses at 176° , does not oxidise in the air, and, when ignited, it first gives a black suboxide, In_4O_5 , then volatilises and gives a brown oxide, In_2O_3 , whose salts, InX_3 , are also formed by the direct action of acids on the metal, hydrogen being evolved. Caustic alkalis do not act on indium, from which it is evident that it is less capable of forming alkaline compounds than aluminium; however, with potassium and sodium hydroxides, solutions of indium salts give a colourless precipitate of the hydroxide, which is soluble in an excess of the alkali, like the hydroxides of aluminium and zinc. Its salts do not crystallise.

lionth millimetres) which did not correspond with any then known element.⁴¹

Under the action of a galvanic current solutions of thallium salts deposit the metal in the form of a heavy powder. It is of a grey colour like tin, is soft like sodium, and has a metallic lustre. Its specific gravity is 11.8, it melts at 290°, and volatilises at a high temperature. When heated slightly above its melting point it forms an insoluble (in water) higher oxide, Tl_2O_3 , as a dark-coloured powder, which is, however, generally accompanied by the lower oxide Tl_2O , which is also black, but soluble in water and alcohol. This solution has a distinctly alkaline reaction. This *thallous oxide* melts at 300°, and is easily obtained from the hydroxide $TlHO$ by igniting it without access of air (in the presence of air the incandescent thallous oxide partly passes into thallic oxide). *Thallous hydroxide*, $TlOH$, crystallises with one molecule H_2O in yellow prisms, which are very easily soluble in water. Metallic thallium may be used for its preparation, as the metal in the presence of water attracts oxygen from the air and forms the hydroxide. But metallic thallium does not decompose water, although it gives a hydroxide which is soluble in water.^{41b} All the other data for the

⁴¹ Thallium was afterwards found in certain micas and in the rare mineral crookesite, containing lead, silver, thallium, and selenium. Its isolation depends on the fact that in the presence of acids thallium forms thallous compounds, TlX . Among these compounds the chloride and sulphate are only slightly soluble, and give with hydrogen sulphide a black precipitate of the sulphide Tl_2S , which is soluble in an excess of acid but insoluble in ammonium sulphide.

^{41b} The best method of preparing thallous hydroxide, $TlOH$, is by the decomposition of the requisite quantity of baryta by thallous sulphate, which is slightly soluble in water; barium sulphate is then obtained in the precipitate and thallous hydroxide in solution. This solubility of the hydroxide is exceedingly characteristic, and forms one of the most important peculiarities of thallium. These lower (thallous) compounds are of the type TlX , and recall the salts of the alkalis. The salts TlX are colourless, do not give a precipitate with the alkalis or ammonia, but they are precipitated by ammonium carbonate, because thallous carbonate, Tl_2CO_3 , is sparingly soluble in water. Platinic chloride gives the same kind of precipitate as it does with the salts of potassium—that is, thallous platinochloride, $PtTl_2Cl_6$. All these facts, together with the isomorphism of the salts TlX with those of potassium, again point out what an important significance the types of compounds have in the determination of the character of a given series of substances. Although thallium has a greater atomic weight and greater density than potassium, and although it has a less atomic volume, nevertheless thallous oxide is analogous to the potassium oxide in many respects, because they both give compounds of the same type, RX . We will further remark that thallous fluoride, TlF , is easily soluble in water as well as thallous silicofluoride, $SiTl_2F_6$, but that thallous cyanide, $TlCN$, is sparingly soluble in water. This, together with the slight solubility of thallous chloride, $TlCl$, and sulphate, Tl_2SO_4 , indicates an analogy between TlX and the salts of silver, AgX .

As regards the higher oxide or the *thallic oxide*, Tl_2O_3 , the thallium is trivalent in it—that is, it forms compounds of the type TlX_3 . The hydroxide, $TlO(OH)$, is formed by the action of hydrogen peroxide on thallous oxide, or by the action of ammonia on a solution of thallic chloride, $TlCl_3$. It is obtained as a brown precipitate, insoluble in water but easily soluble in acids, with which it gives thallic salts, TlX_3 . Thallic chloride, which

chemical and physical properties of thallium, of its two grades of oxidation and of their corresponding salts, are expressed by the position occupied by this metal in virtue of its atomic weight $Tl=204$, between mercury $Hg=200$, and lead $Pb=206$.

Gallium, indium, and thallium belong to the uneven series, and there should be elements of the even series in the III. group corresponding with calcium, strontium, and barium in the II. group. These elements should in their oxides R_2O_3 present basic characters of a more energetic kind than those shown by alumina, just as calcium, strontium, and barium give more energetic bases than magnesium, zinc, and cadmium. Such are *yttrium* and *ytterbium*, which occur in a rare Swedish mineral called *gadolinite*, and which are therefore termed the gadolinite metals. To these belong also the metal *lanthanum*, which accompanies the two other minerals *cerium* and *didymium* in the mineral *cerite*, and which therefore belong to the cerite metals. They all, and certain of the metals accompanying them, give basic oxides R_2O_3 . At first their formula was supposed to be RO , but the application of the periodic system required their being counted as elements of the III. and IV. groups, which was also confirmed by the determination of the specific heats of these metals,⁴² and better

is obtained by cautiously heating the metal in a stream of chlorine, forms an easily-fusible white mass, which is soluble in water and able to part with two-thirds of its chlorine when heated. An aqueous solution of this salt yields colourless crystals containing one equivalent of water. It is evident from the above that all the thallic salts can easily be reduced to thalious salts by reducing agents such as sulphurous anhydride, zinc, &c. Besides these salts, thallic sulphate, $Tl_2(SO_4)_5 \cdot 7H_2O$, thallic nitrate, $Tl(NO_3)_5 \cdot 4H_2O$, &c., are known. These salts are decomposed by water, like the salts of many feeble basic metals—for example, aluminium.

⁴² The specific heat of cerium determined (1870) by me, and afterwards confirmed by Hillebrand, corresponds with that atomic weight of cerium according to which the composition of two oxides should be Ce_2O_3 and CeO_2 . Hillebrand also obtained metallic lanthanum and didymium by decomposing their salts by a galvanic current, and he found their specific heats to be near that of cerium and to 0.04, and it is therefore justifiable to ascribe them an atomic weight near to that of cerium, as was done on the basis of the periodic law. Up to 1870 yttrium oxide was also given the formula RO . Having re-determined the equivalent of yttrium oxide (with respect to water), and found it to be 74.6, I considered it necessary to also ascribe to it the composition Y_2O_3 , because then it falls into its proper place in the periodic system. If the equivalent of the oxide to water = 74.6, then it contains 58.6 of metal per 16 of oxygen, and consequently one part by weight of hydrogen replaces 29.3 of yttrium, and if it be regarded as bivalent (oxide, RO), then it would not, by its atomic weight 58.6, find a place in the second group. But it it be counted as trivalent—that is, if the formula of its oxide be R_2O_3 and salts RX_3 —then $Y=88$, and a position is open for it in the third group in the sixth series after rubidium and strontium. These alterations in the atomic weights of the cerite and gadolinite metals were afterwards accepted by Cleve and other investigators, who now ascribe a formula R_2O_3 to all the newly-discovered oxides of these metals. But still the position in the periodic system of certain elements—for example, of holmium, thulium, samarium, and others—has not yet been determined for want of a sufficient knowledge of their pro-

still by the fact that Nilson and Cleve, in their researches on the gadolinite metals (1879), discovered that they contain a particular and very rare element, *scandium*, which by the magnitude of its atomic weight, $Sc=44$, and in all its properties, exactly corresponds with the metal (previously foretold on the basis of the periodic system) *ekaboron*, whose properties were determined by taking the cerite and gadolinite metals as forming oxides R_2O_3 .⁴³

perties and state of purity. The same must be said of *russium*, the new metal which accompanies thorium in monacite, and was discovered in 1889 by Chroustchoff.

⁴³ So, for example, in 1871, in the *Journal of the Russian Physico-Chemical Society* (p. 45) and in Liebig's *Annalen*, Supt. Band viii. 195, I deduced, on the basis of the periodic law, an atomic weight 44 for ekaboron, and Nilson in 1888 found that of scandium, which is ekaboron, to be $Sc=44.03$. The periodic law showed that the specific gravity of the ekaboron oxide would be about 8.5, that it would have decided but feeble basic properties, and that it would give colourless salts. And this proved to be the case in the scandium oxide. In describing scandium, Cleve and Nilson acknowledge that the particular interest attached to this element is due to its entire identity with the expected element ekaboron. And this true foretelling of properties could only be arrived at by admitting that alteration of the atomic weights of the cerite and gadolinite metals which was one of the first points of the application of the periodic system of the elements to the store of chemical facts. In my first memoirs, namely in the *Bulletin of the St. Petersburg Academy of Sciences*, vol. viii. (1870), and in Liebig's *Annalen* (l. c., p. 168) and others, I particularly insisted on the necessity of altering the then accepted atomic weights of cerium, lanthanum and didymium. Cleve, Höglund, Hillebrand, and Norton, and more especially Brauner, and others accepted the proposed alteration, confirmed my determination of the specific heat of cerium, and gave fresh proofs in favour of the proposed alterations of the atomic weights. The study of the fluorides was particularly important. Placing cerium in the fourth group, the composition of its highest oxide would then be CeO_2 , and its compounds CeX_4 , and the lower oxide Ce_2O_3 or CeX_3 . Brauner obtained the fluoride $CeF_4 \cdot H_2O$ corresponding with the first, and a double crystalline salt, $3KF \cdot 2CeF_4 \cdot 2H_2O$, without any admixture of compound of the lower grade CeX_3 , as is generally the case with the majority of salts corresponding with CeX_4 . It will be seen from these formulæ and from the tables of the elements, that cerium and didymium do not belong to the third group, which is now being described, but we mention them now for the sake of convenience, as all the cerite and gadolinite metals have much in common. These metals, which are rare in nature, resemble each other in many respects, always accompany each other, are with difficulty isolated from each other, and stand together in the periodic system of the elements; they have acquired a peculiar interest owing to their having been the objects of the study in 1870 of Marignac, Delafontaine, Soret, Lecoq de Boisbaudran, Brauner, Cleve, Nilson, the professors of Upsala, and others.

The cerite and gadolinite metals occur in rare siliceous minerals from Sweden, America, the Urals, and Baikal, such as cerite, gadolinite, and orthite; and in yet rarer minerals formed by titanic, niobic, and tantallic acids, such as euxenite in Norway and America, and samarskite in Norway, the Urals, and America, and in a few rare fluorides and phosphates. The insufficiency of material to work upon, and the difficulty and complexity of the separation of the oxides from each other, are the chief reasons why their composition is so imperfectly known. Cerite is the most accessible of these minerals. Besides silica it contains more than 50 p. c. of the oxides of cerium, lanthanum (from 4 p. c.), and didymium. The decomposition of its powder by sulphuric acid gives sulphates, all of which are soluble in water. The other above-mentioned minerals are also decomposed in the same manner. The solution of sulphates is precipitated with free oxalic acid, which forms salts insoluble in water and dilute acids with all the cerite and gadolinite oxides. The oxides themselves are obtained by igniting the oxalates. When

The brevity of this work and the great rarity of the above-mentioned elements will give me the right to exclude their description, all the more as the principles of the periodic system enable many of their

ignited in the air the cerium passes from its ordinary oxide Ce_2O_3 into the higher oxide CeO_2 , which is so feeble a base that its salts are decomposed by water, and it is insoluble in dilute nitric acid. Therefore it is always possible to remove all the cerium oxide by repeated ignitions and solutions in sulphuric acid. The further separation of the metals is mainly based on four methods employed by many investigators.

(a) A solution of the mixed salts is treated with an excess of solid potassium sulphate. Double salts, such $\text{Ce}_2(\text{SO}_4)_3 \cdot 3\text{K}_2\text{SO}_4$, are thus formed. The gadolinite metals, namely yttrium, ytterbium, and erbium, then remain in solution—that is, their double salts are soluble in a solution of potassium sulphate, whilst the cerite metals—namely, cerium, lanthanum, and didymium—are precipitated, that is, their double salts are insoluble in a saturated solution of potassium sulphate. This ordinary method of separation, however, appears from the researches of Marignac to be so untrustworthy that a considerable amount of didymium and the other metals remain in the soluble portion, owing to the fact that, although individually insoluble, they are dissolved when mixed together. Thus erbium and terbium occur both in the solution and precipitate. Nevertheless, beryllium, yttrium, erbium, and ytterbium belong to the soluble, and scandium, cerium, lanthanum, didymium, and thorium to the insoluble portion. The insoluble (in a solution of potassium sulphate) salt of scandium, for example, has a composition $\text{Sc}_2(\text{SO}_4)_3 \cdot 3\text{K}_2\text{SO}_4$.

(b) The oxides obtained by the ignition of the oxalates are dissolved in nitric acid (the nitrates of the cerite metals easily form double salts with those of the alkali metals, and some—for example, the ammonio-lanthanum salt—crystallise very well; they should be studied and applied to the analytical separation of these metals), the solution is then evaporated to dryness, and the residue fused. All nitrates are destroyed by heat; those salts of aluminium and iron, &c., very easily, the salts of the cerite and gadolinite metals also easily (although not so easily as the above), but in different degrees and sequence; so that by carrying the decomposition from the beginning it is possible to destroy the salt of only one metal without touching the others, or leaving them as soluble basic salts. This method, like the preceding and the two following, must be repeated as many as seventy times, in order to attain an in any way constant product of fixed properties, that one in which the decomposed and undecomposed portions would contain one and the same oxide. This method, due to Berlin and worked out by Bunsen, has given in the hands of Marignac and Nilson the best results, especially for the separation of the gadolinite metals, ytterbium and scandium.

(c) A solution of the salts is partially precipitated (fractional precipitation) by ammonia; that is, the solution is mixed with a small quantity of ammonia insufficient for the precipitation of the entire quantity of the bases. Thus, the didymium hydroxide is first precipitated from a mixture of the salts of didymium and lanthanum. A partial separation may be arrived at by repeating the solution of the precipitate and fractional precipitation, but a perfectly pure product is scarcely possible.

(d) The formates having different degrees of solubility (lanthanum formate 420 parts of water per one of salt, didymium formate 221, cerium formate 360, yttrium and erbium formates easily soluble) give a possibility of separating certain of the gadolinite metals from each other by a method of fractional solution and precipitation, as Bunsen, Bahr, Cleve, and others pointed out.

The best method of separating these metals is not known, for they are so like each other. There are also only a few *methods of distinguishing* them from each other, and we can only add the following four to the above.

*
a The faculty of oxidising into a higher oxide. This is very characteristic for cerium, which gives the oxides Ce_2O_3 and CeO_2 or Ce_2O_4 . Didymium also gives one colourless oxide, Di_2O_3 , which is capable of forming salts (of a lilac colour), and another, according to Brauner, Di_2O_5 which is dark brown and does not form salts, as far as is known, and

properties to be foreseen, and as their practical uses (cerium oxalate is used in medicine, and didymium oxide in the manufacture of glass)

which (like ceric oxide) acts as an oxidising agent, like the higher oxides of tellurium, manganese, lead, and others. Lanthanum, yttrium, and many others are not capable of such oxidation. The presence of the higher oxides may be recognised by ignition in a stream of hydrogen; by which means the higher oxides are reduced to the lower, which then remain unaltered.

^b The majority of the salts of the gadolinite and cerite metals are colourless, but those of didymium and erbium are rose-coloured, the salts of the higher oxide of cerium, CeX_4 , yellow, of the higher oxide of terbium, yellow, &c. Thus, the first metals obtained from gadolinite were yttrium, giving colourless, and erbium, giving rose-coloured, salts. Afterwards it was found that the salts of erbium of former investigators contained numerous colourless salts of scandium, ytterbium, &c., so that a coloration sometimes determines the presence of a small impurity, as was long known to be the case in minerals, and therefore this point of distinction cannot be considered trustworthy.

^c In a solid state and in solutions, the salts of didymium, samarium, holmium, &c., give characteristic absorption spectra, as we pointed in Chap. XIII., and this naturally is connected with the colour of these salts. The most important point is, that those metals which do not give an absorption spectrum—for example, lanthanum, yttrium, scandium, and ytterbium—may be obtained free from didymium, samarium, and the other metals giving absorption spectra, because the presence of the latter may be easily recognised by means of the spectroscope, whilst the presence of the former in the latter cannot be distinguished, and therefore the purification of the former can be carried further than that of the latter. We may further remark that the sensitiveness of the spectrum reaction for didymium is so great that it is possible with a layer of solution half a metre thick to recognise the presence of 1 part of didymium oxide (as salt) in 40000 parts of water. Cossa determined the presence of didymium (together with cerium and lanthanum) in apatites, limestones, bones, and the ashes of plants by this method. The main group of dark lines of didymium correspond with wave lengths of from 580 to 570 millionths mm.; and the secondary to about 520, 730, 480, &c. The chief absorption bands of samarium are 472–486, 417, 500, and 559. Besides which, Crookes applied the investigation of the spectra of the phosphorescent light which is emitted by certain earths in an almost perfect vacuum, when an electric discharge is passed through it, to the discovery and distinction of these rare metals. But it would seem that the smallest admixture of other oxides (for example, bismuth, uranium) so powerfully influences these spectra that the radical distinctions of the oxides cannot be seized by this method. Besides which, the spectra obtained by the passage of sparks through solutions or powders of the salts are determined and applied to distinguishing the elements, but as spectra vary with the temperature and elasticity (concentration) this method cannot be considered as trustworthy.

^d The most important point of distinction of individual metallic oxides is given by the direct *determination of their equivalent with respect to water*—that is, the amount of the oxide by weight which combines (like water) with 80 parts by weight of sulphuric anhydride, SO_3 , for the formation of a normal salt. For this purpose the oxide is weighed and dissolved in nitric acid, sulphuric acid is then added, and the whole is evaporated to dryness over a water-bath and then heated over a naked flame sufficiently strongly to drive off the excess of sulphuric acid, but not sufficiently so to decompose the salt (the salt would then not be perfectly soluble in water); then, knowing the weight of the oxide and of the anhydrous sulphate, we can find the equivalent of the oxide. The following are the most trustworthy figures in this respect: scandium oxide 45.35 (Nilson), yttrium oxide 75.7 (Cleve; according to my determination, 1871—74.6), cerous oxide—that is, the lower form of oxidation of cerium, according to various investigators (Bunsen, Brauner, and others) from 108 to 111, the higher oxide of cerium from 85 to 87, lanthanum oxide, according to Brauner, 108, didymium oxide (in salts of the ordinary lower form of oxidation) about 112 (Marignac, Brauner, Cleve), samarium oxide about 116

are very limited, by reason of their great rarity in nature, and the difficulty of separating them from one another.

(Cleve), ytterbium oxide 181.8 (Nilson). It may not be superfluous to here turn attention to the fact that the equivalent of the oxides of all the gadolinite and cerite metals for water distribute themselves into four groups with a somewhat constant difference of nearly 30. In the first group is scandium oxide with equivalent 45, in the second, yttrium oxide 76, in the third, lanthanum, cerium, didymium, and samarium oxides with equivalent about 110, and, in the fourth, erbium, ytterbium, and thorium oxides with equivalents about 181. The common difference of period is nearly 45. And if we ascribe the type R_2O_3 to all the oxides—that is, if we triple the weight of the equivalent of the oxide—we shall obtain a difference of the groups nearly equal to 90, which, for two atoms of the metal, forms the ordinary periodic difference of 45. If one and the same type of oxide R_2O_3 be ascribed to all these elements (as now generally accepted, there in many cases being insufficiently trustworthy data), then the atomic weights should be Sc = 44, Y = 89, La = 138, Ce = 140, Di = 144, Sm = 150, Yb = 173, also terbium 147, holmium 162, alpha-yttrium 157, erbium 166, thulium 170, decipium 171. But it must be observed that if thorium were counted as giving an oxide R_2O_5 , then its atomic weight would be 174, and then there would be no other place in the system of the elements, except that occupied by ytterbium. Besides which, it may be an instance of basic salts. If, for example, an element with an atomic weight 90 gave an oxide RO_2 , but salts ROX_2 , then by counting its oxide as R_2O_5 its atomic weight would be 159.

All the points distinguishing many gadolinite and cerite elements have not been sufficiently firmly established in certain cases (for example, with decipium, thulium, holmium, and others). At present the most certain are yttrium, scandium, cerium, and lanthanum. In the case of didymium, for example, there is still much that is doubtful. Didymium, discovered, in 1842, by Mpsander after lanthanum, differs from the latter in its absorption spectrum and the lilac-rose colour of its salts. Delafontaine (1878) separated samarium from it. Welsbach showed that it contains two particular elements neodymium and praseodymium, and Becquerel (1887), by investigating the spectrum of crystals, recognised the presence of six individual elements. Therefore, probably many of the now recognised elements contain a mixture of various others, and as yet there is not enough confirmation of their individuality. As regards yttrium, scandium, cerium, and lanthanum, which have been established without doubt, I think that, owing to their great rarity in nature and chemical practice, it would be superfluous to describe them further in so elementary a work as the present.

CHAPTER XVIII

SILICON AND THE OTHER ELEMENTS OF THE FOURTH GROUP

CARBON, which gives the compounds CH_4 and CO_2 , belongs to the fourth group of elements. The nearest element to carbon is silicon, which forms the compounds SiH_4 and SiO_2 ; its relation to carbon is like that of aluminium to boron or phosphorus to nitrogen. As carbon composes the principal and most essential part of animal and vegetable substances, so is silicon almost an inevitable component part of the rocky formations of the earth's crust. Silicon hydride, SiH_4 , like CH_4 , has no acid properties, but silica, SiO_2 , shows feeble acid properties like carbonic anhydride. In a free state silicon is also a non-volatile, slightly energetic non-metal, like carbon. Therefore the form and nature of the compounds of carbon and silicon are very similar. In addition to this resemblance, silicon presents one exceedingly important distinction from carbon: namely, the higher degree of oxidation. That is, silica, silicon dioxide, or silicic anhydride, SiO_2 , is a solid, non-volatile, and exceedingly infusible substance, very unlike carbonic anhydride, CO_2 , which is a gas. This expresses the essential peculiarity of silicon.

The cause of this distinction may be most probably sought for in the polymeric composition of silica compared with carbonic anhydride. The molecule of carbonic anhydride contains CO_2 , as seen by the density of this gas; whilst, on the contrary, it can be hardly possible that the density of the vapours of silica, if it were to evaporate, would correspond with the formula SiO_2 , it may be imagined that it would correspond to a far higher atomic weight of Si_nO_{2n} , principally from the basis that SiH_4 is also a gas like CH_4 , SiCl_4 is also a liquid and volatile, boiling at 57° —that is, even lower than CCl_4 , which boils at 76° . In general, analogous compounds of silicon and carbon have nearly the same boiling points if they are liquid and volatile.¹ From this it might be expected that silicic

¹ Chloroform, CHCl_3 , boils at 60° , and silicon chloroform, SiHCl_3 , at 34° ; silicon ethyl, $\text{Si}(\text{C}_2\text{H}_5)_4$, boils at about 150° , and its corresponding carbon compound, $\text{C}(\text{C}_2\text{H}_5)_4$,

anhydride, SiO_2 , would be a gas like carbonic anhydride, whilst in reality silica is a hard non-volatile substance, and therefore it may with great certainty be considered that in this condition it is polymeric with SiO_2 , as on polymerisation—for instance, when cyanogen passes into paracyanogen, or hydrocyanic acid into cyanuric acid (Chapter IX.)—very frequently gaseous or volatile substances change into solid, non-volatile, and physically denser and more complex substances.² On account of this polymerisation of silica, and its diffusion and significance in nature, we will first make acquaintance with free silicon and its volatile compounds, as substances in which the analogy of silicon with carbon is shown, not only in a chemical but also in a physical sense.³

at about 120° ; ethyl orthosilicate, $\text{Si}(\text{OC}_2\text{H}_5)_4$, boils at 160° , and ethyl orthocarbonate, $\text{C}(\text{OC}_2\text{H}_5)_4$, at 158° ; that is, generally speaking, the compounds of silicon, if they are volatile, boil at similar or lower temperatures than the compounds of carbon. Their specific volumes in a liquid state are also nearly equal—that is, those of the silicon compounds generally are slightly greater than those of the carbon compounds (hence they boil at lower temperatures); for example, the volumes of $\text{CCl}_4 = 94$, $\text{SiCl}_4 = 112$, $\text{CHCl}_3 = 81$, $\text{SiHCl}_3 = 82$, of $\text{C}(\text{OC}_2\text{H}_5)_4 = 186$, and $\text{Si}(\text{OC}_2\text{H}_5)_4 = 201$. The corresponding salts have also nearly equal specific volumes; for example, $\text{CaCO}_3 = 37$, $\text{CaSiO}_3 = 41$. It is impossible to compare SiO_2 and CO_2 , because their physical states are so widely different.

² A property of intercombination is observable in the atoms of carbon, and a faculty for intercombination, or polymerisation, is also seen in the unsaturated hydrocarbons and carbon compounds in general. In silicon a property of the same nature is found to be particularly developed in silica, SiO_2 , which is not the case with carbonic anhydride. The faculty of the molecules of silica for combining both with other molecules and among themselves is expressed in the formation of most varied compounds with bases, in the formation of hydrates with a gradually decreasing proportion of water down to anhydrous silica, in the colloid nature of the hydrate (the molecules of colloids are always complex), in the formation of polymeric ethereal salts, and in many other points which will be considered in the sequel. Having come to the conclusion as to the polymeric state of silica since the years 1850–1860, I have found it to be confirmed by all subsequent researches on the compounds of silica, and, if I mistake not, this view, partially enunciated by Graham, has now been accepted by many.

As polymerisation is always accompanied by an increase in density, not only in a gaseous but also in a liquid and solid state (for example, the density of benzene, C_6H_6 , is less than that of cinnamene, C_8H_8 , or ditolyl, $\text{C}_{14}\text{H}_{14}$), the comparatively high density of silica confirms to a certain extent the view as to its polymerised state. Indeed, a close agreement is observed on comparing the specific volumes of the corresponding compounds of carbon and silicon; for example, the specific volume of chloroform, CHCl_3 , is about 81 (according to Thorpe), and of silicon chloroform about 82 (Buff and Wöhler), and the volume of carbonic anhydride in a liquid state is about 46, and in a solid form it is naturally less, although not greatly so, whilst the specific volume of silica in an amorphous state (sp. gr. = 2.2) is 27, and in the form of quartz (sp. gr. = 2.65) less than 23.

³ It was only after Gerhardt, and, in general, subsequently to the establishment of the true atomic weights of the elements (Chapter VII.), that a true idea of the atomic weight of silicon and of the composition of silica was arrived at, from the fact that the molecules of SiCl_4 , SiF_4 , $\text{Si}(\text{OC}_2\text{H}_5)_4$, &c., never contain less than 28 parts of silicon.

The question of the composition of silica was long the subject of the most contradictory statements in the history of science. In the last century Pott, Bergmann, and Scheele distinguished silica from alumina and lime. In the beginning of the present

Free silicon is obtained in the amorphous and crystalline states. Amorphous silicon is produced, like aluminium, by decomposing the


century Smithson for the first time expressed the opinion that silica was an acid, and the minerals of rocks salts of this acid. Berzelius determined the presence of oxygen in silica—namely, that 8 parts of oxygen were united with 7 of silicon. The composition of silica was first expressed as SiO (and for the sake of shortness S only was sometimes written instead). An investigation in the amount of silica present in crystalline minerals showed that the amount of oxygen in the bases bears a very varied proportion to the amount of oxygen in the silica, and that this ratio varies from 2 : 1 to 1 : 8. The ratio 1 : 1 is also met with, but the majority of these minerals are rare. Other more common minerals contain a larger proportion of silica, the ratio between the oxygen of the bases and the oxygen of the silica being equal to 1 : 2, or about this; such are the augites, labradorites, oligoclase, talc, &c. The higher ratio 1 : 3 is known for a widely-distributed series of natural silicates—for example, the feldspars. Those silicates in which the amount of oxygen in the bases is equal to that in the silica are termed *monosilicates*; their general formula will be $(\text{RO})_2\text{SiO}_2$ or $(\text{R}_2\text{O}_3)_2(\text{SiO}_2)_5$. Those in which the ratio of the oxygen is equal to 1 : 2 are termed *bisilicates*, and their general formula will be ROSiO_2 or $\text{R}_2\text{O}_5(\text{SiO}_2)_3$. Those in which the ratio is 1 : 3 will be *trisilicates*, and their general formula $(\text{RO})_2(\text{SiO}_2)_3$ or $(\text{R}_2\text{O}_3)_2(\text{SiO}_2)_9$.

In these formulæ the now established composition of SiO_2 —that is, that in which the atom of $\text{Si} = 28$ —is employed. Berzelius, who made an accurate analysis of the composition of felspar, and recognised it as a trisilicate formed by the union of potassium oxide and alumina with silica, in just the same manner as the alums are formed by sulphuric acid, gave silica the same formula as sulphuric anhydride—that is, SiO_5 . In this case the formula of felspar would be exactly similar to that of the alums—that is, $\text{KAl}(\text{SiO}_5)_2$, like the alums, $\text{KAl}(\text{SO}_4)_2$. If the composition of silica be represented as SiO_5 , then the atom of silicon must be recognised as equal to 42 (if $\text{O} = 16$; or if $\text{O} = 8$, as it was before taken to be, $\text{Si} = 21$).


The former formulæ of silica, $\text{SiO}(\text{Si} = 14)$ and $\text{SiO}_5(\text{Si} = 42)$, were first changed into the present one, $\text{SiO}_2(\text{Si} = 28)$, on the basis of the following arguments:—An excess of silica occurs in nature, and in siliceous rocks free silica is generally found side by side with the silicates, and one is therefore led to the conclusion that it has formed acid salts. Therefore it would be untrue to consider the trisilicates as normal salts of silica, for they contain the largest proportion of silica; it is much better to admit another formula with a smaller proportion of oxygen for silica, and it then appears that the majority of minerals are normal or slightly basic salts, whilst some of the minerals predominating in nature contain an excess of silica—that is, belong to the order of acid salts.

At the present time, when there is a general method (Chapter VII.) for the determination of atomic weights, the volumes of the volatile compounds of silica show that its atomic weight $\text{Si} = 28$, and then silica is SiO_2 . Thus, for example, the vapour density of silicon chloride with respect to air is, as Dumas showed (1862), 5.94, and hence with respect to hydrogen it is 85.5, and consequently its molecular weight will be 171 (instead of 170 as per theory). This weight contains 28 parts of silicon and 142 parts of chlorine, and as an atom of the latter is equal to 35.5, the molecule of silicon chloride contains SiCl_4 . As two atoms of chlorine are equivalent to one of oxygen, the composition of silica will be SiO_2 —that is, the same as stannic oxide, SnO_2 , or titanic oxide, TiO_2 , and the like, and also as carbonic and sulphurous anhydrides, CO_2 and SO_2 . But silica bears but little physical resemblance to the latter compounds, whilst stannic and titanic oxides resemble silica both physically and chemically. They are non-volatile, crystalline, insoluble, are colloids, also form feeble acids like silica, &c., and therefore they might be expected to form analogous compounds, and be isomorphous with silica, as Marignac (1859) found actually to be the case. He obtained stannofluorides, for example—an easily soluble strontium salt, $\text{SrSnF}_6 \cdot 2\text{H}_2\text{O}$, corresponding with the already long known silicofluorides, such as $\text{SrSiF}_6 \cdot 2\text{H}_2\text{O}$. Both these salts are perfectly similar in crystalline form

double fluoride of sodium and silicon (sodium silicofluoride) by means of sodium :



By treating the mass thus obtained with water the sodium fluoride may be extracted and the residue will consist of brown, powdery silicon. In order to free it from any silica which might be formed, it is treated with hydrofluoric acid. This silicon powder is not lustrous ; when heated it easily ignites, but does not completely burn. It fuses when very strongly heated, and reminds one of carbon. Crystalline silicon is obtained in a similar way, but by substituting an excess of aluminium for the sodium :



The part of the aluminium remaining in the metallic state dissolves the silicon, and the latter separates from the solution on cooling in a crystalline form. The excess of aluminium after the fusion is removed by means of hydrochloric acid and hydrofluoric acid. Silicon obtained by means of aluminium has a laminar crystalline structure. The best silicon crystals are obtained from molten zinc ; 15 parts of sodium silicofluoride are mixed with 20 parts of zinc and 4 parts of sodium, and the mixture is thrown into a strongly-heated crucible, a layer of common salt being used to cover it over ; when the mass fuses it is stirred, cooled, treated with hydrochloric acid, and then washed with nitric acid. Silicon, especially when crystalline, like graphite and charcoal, does not in any way act on the above-mentioned acids. It forms black, very brilliant, regular octahedra having a specific gravity of 2.49 ; it is a bad conductor of electricity, and does not burn even in pure oxygen. The only acid which acts on it is a mixture of hydrofluoric and nitric acids ; but caustic alkalis dissolve it like aluminium, with evolution of hydrogen, thus showing the acid character of silicon. In general silicon strongly resists the action of reagents, as also do boron and carbon. Crystalline silicon was obtained in 1855 by Deville, and amorphous silicon in 1826 by Berzelius.⁴

(monoclinic ; angle of the prism, 83 for the former and 84 for the latter ; inclination of the axes, 103° 46' for the latter and 103° 30' for the former), as they are also similar in composition—that is, they are isomorphous. We may here add that the specific volume of silica in a solid form is 22.6, and of stannic oxide 21.5.

⁴ It is very remarkable that silicon decomposes carbonic anhydride at white heat, forming a white mass which, after being treated with potassium hydroxide and hydrofluoric acid, leaves a very stable yellow substance of the formula SiCO , which is formed according to the equation, $3\text{Si} + 2\text{CO}_2 = \text{SiO}_2 + 2\text{SiCO}$. It is also slowly formed when silicon is heated with carbonic oxide. It is not oxidised when heated in oxygen. A mixture of silicon and carbon, when heated in nitrogen, gives the compound $\text{Si}_2\text{C}_2\text{N}$, which is also very stable.


Silicon hydride, SiH_4 , analogous to marsh gas, was obtained first of all in an impure state, mixed with hydrogen, by two methods: by the action of an alloy of silicon and magnesium on hydrochloric acid,⁵ and by the action of the galvanic current on dilute sulphuric acid, using electrodes of aluminium, containing silicon. In these cases silicon hydride is set free, together with hydrogen, and the presence of the hydride is shown by the fact that the hydrogen separated ignites spontaneously on coming into contact with the air, forming water and silica. The formation of silicon hydride by the action of hydrochloric acid on magnesium silicide is perfectly akin to the formation of phosphuretted hydrogen by the action of hydrochloric acid on calcium phosphide, to the formation of hydrogen sulphide by the action of acids on many metallic sulphides, and even to the formation of hydrocarbons by the action of hydrochloric acid on white cast iron. On heating silicon hydride—that is, on passing it through an incandes-

On this basis Schützenberger recognises a group, C_2Si_2 , as capable of combining with O_2 and N , like C .

⁵ This alloy, as Beketoff and Cherikoff showed, is easily obtained by directly heating finely-divided silica (the experiment may be conducted in a test tube) with magnesium powder (Chapter XIV. Notes 17, 18). The substance formed, when thrown into a solution of hydrochloric acid, evolves spontaneously inflammable and impure silicon hydride, so that the self-inflammability of the gas is easily demonstrated by this means.

In 1850–60 Wöhler and Buff obtained an alloy of silicon and magnesium by the action of sodium on a molten mixture of magnesium chloride, sodium silicofluoride, and sodium chloride. The sodium then simultaneously reduces the silicon and magnesium.

Friedel and Ladenburg subsequently prepared silicon hydride in a pure state, and showed that it is not spontaneously inflammable in air, at the ordinary pressure, but that it easily takes fire in air, like the mixture prepared by the above methods, under a lower pressure or when mixed with hydrogen. They prepared the pure compound in the following manner: Wöhler showed that when dry hydrochloric acid gas is passed through a slightly-heated tube containing silicon it forms a very volatile colourless liquid, which fumes strongly in air; this is a mixture of silicon chloride, SiCl_4 , and *silicon chloroform*, SiHCl_3 , which corresponds with ordinary chloroform, CHCl_3 . This mixture is easily separated by distillation, because silicon chloride boils at 57° , and silicon chloroform at 38° . The formation of the latter will be understood from the equation $\text{Si} + 3\text{HCl} = \text{H}_2 + \text{SiHCl}_3$. It is an anhydrous inflammable liquid of specific gravity 1.6. It forms a transition product between SiH_4 and SiCl_4 , and may be obtained from silicon hydride by the action of chlorine, and is itself also transformed into silicon chloride by the action of chlorine. It is also formed from silicon hydride by the action of antimonie chloride. Friedel and Ladenburg, by acting on anhydrous alcohol with silicon chloroform, obtained an ethereal compound having the composition $\text{SiH}(\text{OC}_2\text{H}_5)_3$. This ether boils at 136° , and when acted on with sodium disengages silicon hydride, and is converted into ethyl orthosilicate, $\text{Si}(\text{OC}_2\text{H}_5)_4$, according to the equation $4\text{SiH}(\text{OC}_2\text{H}_5)_3 = \text{SiH}_4 + 3\text{Si}(\text{OC}_2\text{H}_5)_4$ (the sodium seems to be without action), which is exactly similar to the decomposition of the lower oxides of phosphorus, with the evolution of phosphuretted hydrogen. If we designate the group C_2H_5 , contained in the silicon ethers by Et , the parallel is found to exact:



Warren (1888) obtained silicon and its alloy with magnesium by heating magnesium in a current of silicon fluoride.

cent tube, it is decomposed into silicon and hydrogen, just like the hydrocarbons, but the caustic alkalis, although without action on the latter, react with silicon hydride according to the equation :



Silicon chloride, SiCl_4 , is obtained from amorphous anhydrous silica (made by igniting the hydrate) mixed with charcoal,⁶ heated to a white heat in a stream of dry chlorine—that is, by that general method by which many other chloranhydrides of acid properties are obtained. Silicon chloride is purified from free chlorine by distillation over metallic mercury. Free silicon forms the same substance when treated with dry chlorine. It is a volatile colourless liquid, which boils at 57° and has a specific gravity of 1.52. It fumes strongly in air, has a pungent smell, and in general has the characteristic properties of the acid chloranhydrides. It is completely decomposed by water, forming hydrochloric acid and silicic acid, according to the equation :



⁶ The amorphous silica is mixed with starch, dried, and then charred by heating the mixture in a closed crucible. A very intimate mixture of silica and charcoal is thus formed. In Chapter XI. Note 13, we saw that elements like silicon disengage more heat with oxygen than with chlorine, and therefore their oxygen compounds cannot be directly decomposed by chlorine, but that this can be effected when the affinity of carbon for oxygen is utilised to aid the action.

⁷ Silicon chloride shows a similar behaviour with alcohol. This is accompanied by a very characteristic phenomenon; on pouring silicon chloride into anhydrous alcohol a momentary evolution of heat is observed, owing to a reaction of double decomposition, but this is immediately followed by a powerful cooling effect, due to the disengagement of a large amount of hydrochloric acid—that is, there is an absorption of heat from the formation of gaseous hydrochloric acid. This is a very instructive example in this respect; here two simultaneously-accomplished processes—one chemical and the other physical—are divided from each other by time, the latter process evincing itself by a clear fall of temperature. In the majority of cases the two processes proceed simultaneously, and we only realise the difference between the heat developed and absorbed. In acting on alcohol, silicon chloride forms ethyl orthosilicate, $\text{SiCl}_4 + 4\text{HOC}_2\text{H}_5 = 4\text{HCl} + \text{Si}(\text{OC}_2\text{H}_5)_4$. This substance boils at 160° , and has a specific gravity 0.94. Another salt, ethyl metasilicate, $\text{SiO}(\text{OC}_2\text{H}_5)_2$, is also formed by the action of silicon chloride on anhydrous alcohol; it volatilises above 300° , having a sp. gr. 1.08. This is exceedingly important in this respect, that this ethereal salt is also volatile, and also corresponds with silica, SiO_2 : the first ether corresponds to the hydrate $\text{Si}(\text{OH})_4$, orthosilicic acid, and the second to the hydrate $\text{SiO}(\text{OH})_2$, metasilicic acid. As the nature of hydrates may be judged from the composition of salts, so also, and with perfect right, can ethereal salts serve the same purpose. The composition of an ethereal salt corresponds with that of an acid in which the hydrogen is replaced by a hydrocarbon radicle—for instance, by C_2H_5 —and therefore the composition of a hydrate may be realised by replacing this radicle by hydrogen. And, therefore, it may be justly said that there exist at least the two above-mentioned silicic acids. We shall afterwards see that there are really several such hydrates, and that these ethereal salts actually correspond with hydrates of silica is clearly shown from the fact that these ethers are decomposed by water, and that in

The most remarkable of the haloid compounds of silicon is *silicon fluoride*, SiF_4 , because it is a gaseous substance only liquified by intense cold, -100° , and on account of its being obtained (Chapter XI.) directly by the action of hydrofluoric acid on silica and its compounds ($\text{SiO}_2 + 4\text{HF} = 2\text{H}_2\text{O} + \text{SiF}_4$), and is even formed by heating fluorspar with silica ($2\text{CaF}_2 + 3\text{SiO}_2 = 2\text{CaSiO}_3 + \text{SiF}_4$).⁸ In order to prepare silicon fluoride, sand or broken glass is mixed with an equal quantity by weight of fluorspar and 6 parts by weight of strong sulphuric acid, and the mixture is gently heated. It fumes strongly in air, reacting with the aqueous vapours, although it is produced from silica and hydrofluoric acid with the separation of water. It is evident that a reverse reaction occurs here; that is to say, the water reacts with the silicon fluoride, but the reaction is not complete. This phenomenon is effected in a similar way to that which occurs when water decomposes aluminium chloride, but at the same time hydrochloric acid dissolves aluminium hydroxide and forms the same aluminium chloride. The relative amount of water present (together with the temperature) determines the limit and direction of the reaction. The faculty which silicon fluoride has of reacting with water is so great that it takes up the elements of water from many substances—for instance, like sulphuric acid, it chars paper. Water dissolves about 300 volumes of this gas, but in this case it is not a common solution which takes place, but a reaction; especially is this the case with a small quantity of silicon fluoride, that is, with an excess of water. During the first absorption of silicon fluoride by water, silicic acid is separated in the form of a jelly, but a certain quantity of the silicon fluoride also remains in liquid, because the hydrofluoric acid formed

moist air they give alcohol and the corresponding hydrate, although the hydrate which is obtained in the residue always corresponds with the second ethereal salt only—that is, it has the composition $\text{SiO}(\text{OH})_2$; this form corresponds also to carbonic acid in its ordinary salts. This hydrate is formed as a vitreous mass when the ethyl silicates are kept in air, owing to the action of the atmospheric moisture on them. Its specific gravity is 1.77.

Silicon bromide, SiBr_4 , as well as silicon bromoform, SiHBr_3 , are substances closely resembling the chlorine compounds in their reactions, and are obtained in the same manner. Silicon iodoform, SiHI_3 , boils at about 220° , has a specific gravity of 3.4; reacts in the same manner as silicon chloroform, and is formed, together with silicon iodide, SiI_4 , by the action of a mixture of hydrogen and hydriodic acid on heated silicon. Silicon iodide is a solid at the ordinary temperature, fusing at about 120° ; it may be distilled in a stream of carbonic anhydride, but easily takes fire in air, and behaves with water and other reagents just like silicon chloride. It may be obtained by the direct action of the vapour of iodine on heated silicon.

⁸ This property of calcium fluoride of converting silica into a gas and a vitreous fusible slag of calcium silicate is frequently taken advantage of in the laboratory and in practice in order to remove silica. The same reaction is employed for preparing silicon fluoride on a large scale in the manufacture of hydrofluosilicic acid (see sequel).

dissolves the other part of the silica⁹ and forms the so-called *hydrofluosilicic acid*: $\text{H}_2\text{SiF}_6 = \text{SiF}_4 + 2\text{HF} = \text{SiH}_2\text{O}_3 + 6\text{HF} - 3\text{H}_2\text{O}$. That is to say, a metasilicic acid, SiH_2O_3 , in which O_3 is replaced by F_6 . This view of the composition of hydrofluosilicic acid may be admitted, because it forms a whole series of highly crystallisable and well-defined salts. In general, the whole reaction of water on silicon fluoride may be expressed by the equation: $3\text{SiF}_4 + 3\text{H}_2\text{O} = \text{SiO}(\text{OH})_2 + 2\text{SiH}_2\text{F}_6$. Hydrofluosilicic acid and silicic acid resemble each other as much, and differ as much, in their chemical character as water and hydrofluoric acid. For this reason silicic acid is a feebler acid than hydrofluosilicic acid, and in addition to this the former is insoluble, and the latter soluble, in water.¹⁰

Hydrofluosilicic acid is also formed if silicic acid is dissolved in a solution of hydrofluoric acid. It is incapable of volatilising without decomposition, and on heating the concentrated acid silicon fluoride is evolved, leaving an aqueous solution of hydrofluoric acid. This is the reason why solutions of hydrofluosilicic acid corrode glass. This decomposition may be further accelerated by the addition of sulphuric


⁹ The amount of heat developed by the solution of silicic acid, $\text{SiO}_2 \cdot n\text{H}_2\text{O}$, in aqueous hydrofluoric acid, $x\text{HF} \cdot n\text{H}_2\text{O}$, increases with the magnitude of x and normally equals $x \cdot 5600$ heat units, where x varies between 1 and 8. However, when $x=10$ the maximum amount of heat is developed (=49500 units), and beyond that the amount decreases (Thomsen).

¹⁰ In reality, however, the reaction would seem to be still more complex, because the aqueous solution of silicon fluoride does not yield a hydrate of silica, but a fluohydrate (Schiff), $\text{Si}_2\text{O}_5(\text{OH})\text{F}$, corresponding to the (pyro) hydrate $\text{Si}_2\text{O}_5(\text{OH})_2$, equal to $\text{SiO}(\text{OH})_2\text{SiO}_2$, so that the reaction of silicon fluoride on water is expressed by the equation: $5\text{SiF}_4 + 4\text{H}_2\text{O} = 3\text{SiH}_2\text{F}_6 + \text{Si}_2\text{O}_5(\text{OH})\text{F} + \text{HF}$. However, Berzelius states that the hydrate, when well washed with water, contains no fluorine, which is probably due to the fact that an excess of water decomposes $\text{Si}_2\text{O}_5(\text{OH})\text{F}$, forming hydrofluoric acid and the compound $\text{Si}_2\text{O}_5(\text{OH})_2$. Water saturated with silicon fluoride disengages silicon fluoride and hydrofluoric acid when treated with hydrochloric acid, therefore the gelatinous precipitate is then dissolved. It may be further remarked that hydrofluosilicic acid has been frequently regarded as $\text{SiO}_2 \cdot 6\text{HF}$, because it is formed by the solution of silica in hydrofluoric acid, but only two of these six hydrogens are replaced by metals. On concentration, the solutions of the acid already decompose when they reach a strength of $6\text{H}_2\text{O}$ per H_2SiF_6 , and therefore the acid may be regarded as $\text{Si}(\text{OH})_4 \cdot 2\text{H}_2\text{O} \cdot 6\text{HF}$, but the corresponding salts contain less water, and there are even anhydrous salts R_2SiF_6 , so that the acid itself is most simply represented as H_2SiF_6 .

If gaseous silicon fluoride be passed directly into water, the gas-conducting tube becomes clogged with the precipitated silicic acid. This is best prevented by immersing the end of the tube under mercury, and then pouring the water over the mercury; the silicon fluoride then passes through the mercury, and only comes into contact with the water at its surface, and consequently the gas-conducting tube remains unobstructed. The silicic acid thus obtained soon settles, and a colourless solution with a pleasant but distinctly acid taste is procured.

Mackintosh, by taking 9 p.c. of hydrofluoric acid, observed that in the course of an hour its action on opal attained 77 p.c. of the possible, and did not exceed $1\frac{1}{2}$ p.c. of its possible action on quartz during the same time. This shows the difference of the structure of these two modifications of silica, which will be more fully described in the sequel.

acid, or even of other acids. Hydrofluosilicic acid, when acting on potassium and barium salts, gives precipitates, because the salts of these metals are but sparingly soluble in water : thus



The salt is obtained in the form of very fine octahedra, but the precipitate does not form quickly, and at first appears as a jelly. Nevertheless, the decomposition is complete, and it is taken advantage of for obtaining their corresponding acids from salts of potassium. The sodium salt is far more soluble in water, and crystallises in the hexagonal system. The magnesium salt, MgSiF_6 , and calcium salt are soluble in water. The salts of hydrofluosilicic acid may be obtained not only by the action of the acid on bases or by double decompositions, but also by the action of hydrofluoric acid on metallic silicates. Sulphuric acid decomposes them, with evolution of hydrofluoric acid and silicon fluoride, and the salts when heated evolve silicon fluoride, leaving a residue of metallic fluoride, R_2F_2 .

According to the principle of substitution (Vol. I. p. 256), if silicon forms SiH_4 , then a series of hydrates, or hydroxyl derivatives, ought to exist corresponding to it. The first hydrate of an alcoholic character ought to have the composition $\text{SiH}_3(\text{OH})$: the second hydrate, $\text{SiH}_2(\text{OH})_2$; the third, $\text{SiH}(\text{OH})_3$;¹¹ and the last, $\text{Si}(\text{OH})_4$. The last is a hydrate

¹¹ This circumstance is very important in explaining the nature of the lower hydrates which are known for silicon. If we suppose water to be taken up from the first hydrates (just as formic acid is $\text{CH}(\text{OH})_3$ minus water), we shall obtain the various lower hydrates corresponding with silicon hydride. When ignited they should, as phosphorous and hypophosphorous acids, disengage silicon hydride and leave a residue of silica behind—i.e., of the oxide corresponding to the highest hydrate—just as organic hydrates (for example, formic acid with an alkali) form carbonic anhydride as the highest oxygen compound. Such imperfect hydrates of silicon, or, more correctly speaking, of silicon hydride, were first obtained by Wöhler (1863) and studied by Geuther (1865), and were named after their characteristic colours.

Leucone is a white hydrate of the composition $\text{SiH}(\text{OH})_3$. It is obtained by slowly passing the vapour of silicon chloroform into cold water: $\text{SiHCl}_3 + 3\text{H}_2\text{O} \rightarrow \text{SiH}(\text{OH})_3 + 3\text{HCl}$. But this hydrate, like the corresponding hydrate of phosphorus or carbon, does not remain in this state of hydration, but loses a portion of its water. The carbon hydrate of this nature, $\text{CH}(\text{OH})_3$, loses water and forms formic acid, $\text{CHO}(\text{OH})$; but the silicon hydrate loses a still greater proportion of water, $2\text{SiH}(\text{OH})_3$, parting with $3\text{H}_2\text{O}$, and consequently leaving $\text{Si}_2\text{H}_2\text{O}_5$. This substance must be an anhydride; all the hydrogen previously in the form of hydroxyl has been disengaged, two remaining hydrogens being left from SiH_4 . The other similar hydrate is also white, and has the composition $\text{Si}_2\text{H}_2\text{O}$ (nearly). It may be regarded as the above white hydrate + SiO_2 . A yellow hydrate, known as *chryscone* (silicone), is obtained by the action of hydrochloric acid on an alloy of silicon and calcium; its composition is nearly $\text{Si}_6\text{H}_4\text{O}_5$. Most probably, however, chryscone has a more complex composition, and stands in the same relation to the hydrate $\text{SiH}_2(\text{OH})_3$ as leucone does to the hydrate $\text{SiH}(\text{OH})_3$, because this very simply expresses the transition of the first compound into the second with the loss of water,

of silica, because it is equal to $\text{SiO}_2 + 2\text{H}_2\text{O}$; and it is formed by the action of water on silicon chloride, when all four atoms of chlorine are replaced by four hydroxyl groups. It does not, however, remain in this state, but easily loses part of its water.

Silica or silicic anhydride, both in the free state and in combination with other oxides, enters into the composition of most of the rocky formations of the earth's crust. These siliceous compounds are substances varying so much in their properties, crystalline forms, and relations to one another that they are comprised in a special branch of natural science (like the carbon compounds), and are treated of in works on mineralogy; so that, in dealing with them further, we shall only give a short description of these various compounds. It is, first of all, necessary to turn to the description of silica itself, especially as it is not unfrequently met with in nature in a separate state, and often forms whole masses of rocky formations, called 'quartz.' In an anhydrous condition silica appears in the greatest variety of natural forms—sometimes in well formed crystals, hexagonal prisms, terminated by hexagonal pyramids; sometimes the prism is wanting, and it appears as hexagonal pyramids. If the crystals are colourless and transparent, they are called *rock crystal*. This is the purest form of silica. Prismatic crystals of rock crystal sometimes attain considerable size, and as they are remarkable for their unchangeability, great hardness, and considerable index of refraction, they are used for ornaments, for seals, making necklaces, &c.¹² Rock crystal, coloured with organic matter, in

$\text{SiH}_2(\text{OH})_3 - \text{H}_2 + \text{H}_2\text{O} = \text{SiH}(\text{OH})_3$. When these lower hydrates are ignited without the access of air, they are decomposed into hydrogen, silicon, and silica—that is, it may be supposed that they form silicon hydride (which decomposes into silicon and hydrogen) and silica (just as phosphorous and hypophosphorous acids give phosphoric acid and phosphuretted hydrogen). When ignited in air, they burn, forming silica. They are none of them acted on by acids, but when treated with alkalis they evolve hydrogen and give silicates; for example, leucone: $\text{SiH}_2\text{O}_3 + 4\text{KHO} = 2\text{SiK}_2\text{O}_3 + \text{H}_2\text{O} + 2\text{H}_2$. They have no acid properties. Thus, as yet we have no lower acid hydrates of silicon, corresponding, for example, to formic acid, which would give salts when acted on by alkalis. It must not, however, be forgotten that formic acid, when heated with an alkali, gives a carbonate and hydrogen, $\text{CH}_2\text{O}_2 + 2\text{KHO} = \text{CK}_2\text{O}_3 + \text{H}_2\text{O} + \text{H}_2$. Consequently, a similar decomposition is accomplished with leucone as with formic acid, only at the ordinary temperature.

¹² Two modifications of rock crystal are known. They are very easily distinguished from each other by their relation to polarised light; one rotates the plane of polarisation to the right and the other to the left—in the one the hemihedral faces are right and in the other they are left; this opposite rotatory power is taken advantage of in the construction of polarisers. But, with this physical difference—which is naturally dependent on a certain difference in the distribution of the molecules—there is not only no observable difference in the chemical properties, but not even in the density of the mass. Perfectly pure rock crystal is a substance which is most invariable with respect to its specific gravity. The numerous and accurate determinations made by Steinheil on the specific gravity of rock crystal show that (if the crystal be free from flaws) it is very constant.

contact with which it is sometimes produced in aqueous formations, has a brown or greyish colour, and then bears the name of *cairngorm* or *smoky quartz*. In this form it has the same uses as rock crystal, especially as it is often found in large masses. The same mineral, coloured red or pink by means of manganese or iron oxides, often occurs, especially in aqueous formations, and is often called *amethyst*. When finely-coloured the amethyst is used as a precious stone, but amethysts are not met with in pure crystals of such considerable size as rock crystal. They most frequently occur as small crystals in the cavities formed in other rocky formations, and especially in those formed in silica itself. A similar anhydrous silica is often found in transparent non-crystalline masses, having the same specific gravity as rock crystal itself (2.66). In this case it is called *quartz*. Sometimes it forms complete rocky formations, but more often penetrates or diffuses itself through other rocky formations, together with other siliceous compounds. Thus, in granite, quartz is mixed with felspar and similar substances. Sometimes the colouring of quartz is so considerable that it is hardly transparent in thin sheets, but it is often found in transparent masses slightly coloured with various tints. The resistance of quartz to the action of water is proved in nature on an enormous scale. When water destroys rocky formations, the siliceous minerals which they contain are partly dissolved and partly transformed into clay, &c. But the quartz remains untouched, and in the form of grains in which it existed in the rocky formation; sometimes, when crushed, it is carried away by the water and deposited as sand. Most frequently, the principal part of *sand* consists of quartz grains washed by water from the rocks which it destroys. Naturally, sometimes other rocky substances which are not changed by water, or only slightly acted on by it, are found in sand; but as these latter are more or less changed by the continuous action of water, it is not unusual to find sand which consists almost entirely of pure quartz. Common sand is generally coloured yellow or reddish-brown by foreign mineral matter, consisting principally of ferruginous minerals and clays. The purest, or so-called quartz, sand is, however, rarely found, and is recognised by the absence of colour, and also by the test that when shaken in water

It is equal to 2.66. The unchangeability of rock crystal under the action of reagents, its small hygroscopic capacity, and very great hardness render it a valuable material for certain apparatus of great accuracy; for example, in the construction of normal weights—that is, of weights for exceedingly accurate weighings. The density of rock crystal is constant, and therefore the correction for weighing with these weights in air can be made with perfect confidence in its accuracy, and their unchangeableness under friction and atmospheric action render these weights (naturally, if they are submitted to an accurate comparison between each other) much more exact than any metallic ones.

it does not form any turbidity : this shows the absence of clay ; when fused with bases it forms a colourless glass, and on this account is a valuable material for the manufacture of glass. Sands were formed at all periods of the earth's existence ; the ancient ones, compressed by strata of more recent formation and permeated with various substances (deposited from the infiltrating water), are sometimes solidified into rock, called *sandstone*, composing, in some places, whole mountain chains, and serviceable as a most excellent building material, on account of the slight change it undergoes under the influence of atmospheric agencies, and on account of the facility with which it may be wrought from rocky formations into immense regularly-shaped flags—the latter property is due to the primary laminar structure of the sand formations deposited, as above-mentioned, by water.

Completely pure anhydrous silica is not only extracted in the condition of rock crystal and quartz having a specific gravity of 2·6, but also in another special form, having other chemical and physical properties. This variety of silica has a specific gravity of 2·2, and is formed by fusing rock crystal or heating silicic acid.¹³ Silicic acid, when heated to a dull red heat, completely parts with the contained water, and leaves an exceedingly fine amorphous mass of silica (easily levigated, but difficult to moisten) ; it is characterised by such excessive friability that, when lightly blown on, a large mass of it rises into the air like a cloud of dust. A mass of anhydrous silica may be poured in this way from one vessel to another like a liquid, like which it takes a horizontal position in the containing vessel. Anhydrous silica, like quartz, does not fuse in the heat of a furnace, but it fuses in the oxy-hydrogen flame into a colourless glassy mass exactly similar to that formed in the same way from rock crystal. In this condition silica has a specific gravity of 2·2. Both forms of silica are insoluble in ordinary acids, and, when they are taken in the state of powder, alkalis in solution act very slowly and feebly on them ; in addition to which rock crystal offers much greater resistance to the action of alkalis than the powder obtained by heating the hydrate. The latter, although but slowly, is quite soluble in hot alkaline solutions. This last property appertains in a greater degree to anhydrous silica having a specific gravity of 2·2 than to that which has a specific gravity of 2·6. Hydrofluoric acid more easily transforms the former into silicon fluoride than it does the latter. Both varieties of silica, when taken in the form of

¹³ Several other modifications are known as minute crystals. For example, there is a particular mineral first found in Styria and known as *tridymite*. Its specific gravity 2·3 and form of crystals clearly distinguish it from rock crystal ; its hardness is the same as that of quartz—that is, slightly below that of the ruby and diamond.

powder, easily combine with bases, forming, on being fused with an alkali, a vitreous slag, which is a salt corresponding with silica. Glass is a similar salt, formed of alkalis and alkaline earthy bases; if the glass does not contain any of the latter—that is, if only alkaline glass be taken—a mass soluble in water is obtained. In order to obtain such *soluble glass*, potassium or sodium carbonates, or, better, a mixture of the two (a more fusible mixture), is fused with fine sand. A still better and further saturation of the alkalis with silica is effected by the action of alkaline solutions on the silicon hydrate met with in nature; for instance, an alkaline solution is often made use of to act on the so-called *tripoli*, or collection of siliceous skeletons of the lowest microscopical infusoria, which is sometimes found in considerable layers in the form of a sandy mass. Tripoli is used for polishing, not only on account of the considerable hardness of the silica, but also because the microscopic bodies of the infusoria have a pointed shape, which, however, is not angular, so that they do not scratch metals like sand.¹⁴ In a boiler, under a certain amount of pressure, tripoli may be dissolved in a solution of caustic soda (or potash), because it contains silica in the shape of hydrate of a specific gravity 2·2, with a slight amount of water. The alkaline solutions of silica obtained by these means contain various relative amounts of silica and alkali. In order to contain the greatest amount of silica, the solution ought to be heated and silicic acid added to it; in order to obtain this hydrate, it is only necessary to take any kind of solution containing silica and alkali, and to add to it, by degrees, some acid—for instance, sulphuric

¹⁴ Silica also occurs in nature in two modifications. The opal and tripoli (infusorial earth) have a specific gravity of about 2·2, and are comparatively easily dissolved in alkalis and hydrofluoric acid. Chalcedony and flint (tinted quartzose concretions of aqueous origin), agate and similar forms of silica of undubitably aqueous origin, and even still containing a certain amount of water, have a specific gravity of 2·6, and correspond with quartz in the difficulty with which they dissolve. This form of silica sometimes permeates the cellulose of wood, forming one of the ordinary kinds of petrified wood. The silica may be extracted from it by the action of hydrofluoric acid, and the cellulose remains behind, which clearly shows that silica in a soluble form (see sequel) has permeated into the cells, where it has deposited the hydrate, which has lost water, and given a silica of sp. gr. 2·6. The quartzose stalactites found in certain caves are also evidently of a like aqueous origin; however, their sp. gr. is 2·6. As crystals of amethyst are frequently found among chalcedonies, and as Friedau and Sarrau (1879) obtained crystals of rock crystal by heating soluble glass with an excess of hydrate of silica in a closed vessel, there is no doubt but that rock crystal itself is formed in the wet way from the gelatinous hydrate. Chroustchoff obtained it directly from soluble silica. Thus this hydrate is able to form both the variety having the specific gravity 2·2 and the more stable variety of sp. gr. 2·6; and they both exist with a small proportion of water and in a perfectly anhydrous state in an amorphous and crystalline form. All these facts are expressed by recognising silica as dimorphous, and their cause must be looked for in a difference in the degree of polymerisation.

or hydrochloric ; then, if the experiment be carried on carefully and the solution be concentrated, the whole mass thickens to a jelly, due to the gelatinous form of the *silicic acid* separated from the salt by the action of the acid. The decomposition may be expressed by the following equation : $\text{Si}(\text{ONa})_4 + 4\text{HCl} = 4\text{NaCl} + \text{Si}(\text{OH})_4$. The hydrate separated, $\text{Si}(\text{OH})_4$, easily loses part of the water, and forms a jelly, the whole mass gelatinising if the solution be strong enough.¹⁵

Neither of the two varieties of anhydrous silica, nor the various

¹⁵ The equation given above does not express the actual reaction, for in the first place silica has the faculty for forming compounds with bases developed to the highest degree, even to a greater degree than molybdic and tungstic anhydrides, and therefore the formula SiNa_4O_4 is not rightly deduced, if one may so express oneself. And, in the second place, silica gives several hydrates. In consequence of this, the solution does not usually contain $\text{Si}(\text{ONa})_4$, but various other grades of combination of silica with bases ; and, moreover, the hydrate precipitated does not actually contain so high a proportion of water as $\text{Si}(\text{OH})_4$, but always less. The insoluble gelatinous hydrate which separates out is able (before, but not after having been dried) to dissolve in a solution of sodium carbonate. When dried in air its composition corresponds with the ordinary salts of carbonic acid—that is, SiH_2O_5 , or $\text{SiO}(\text{OH})_2$. If gradually heated it loses water by degrees, and, in so doing, gives various degrees of combination with it. The existence of these degrees of hydration, having the composition $\text{SiH}_2\text{O}_5n\text{SiO}_2$, or, in general, $n\text{SiO}_2m\text{H}_2\text{O}$, where $m < n$, must be recognised, because most varied degrees of combination of silica with bases are known. We shall find a similar phenomenon in molybdic and tungstic acids, so that it is not exceptional. The hydrate of silica, when not dried above 30° , has a composition of nearly $\text{H}_4\text{Si}_5\text{O}_8 = (\text{H}_2\text{SiO}_5)_2\text{SiO}_2$, but at 60° contains a greater proportion of silica—that is, it loses still more water ; and at 100° a hydrate of the composition $\text{SiH}_2\text{O}_52\text{SiO}_2$, and at 250° a hydrate having approximately a composition $\text{SiH}_2\text{O}_57\text{SiO}_2$ is obtained. If the water be regarded as a base—that is, as the water of constitution of the hydrate—then the first hydrate, $\text{SiO}_2\cdot\text{H}_2\text{O}$, will be a monosilicate (silicic acid) corresponding with a series of silicates of the composition $(\text{RO})_n\text{SiO}_2$, whilst the hydrate which is obtained at 100° will correspond with the trisilicates $\text{RO}_3\cdot 3\text{SiO}_2$.

Hager (1888) obtained a crystalline hydrate, $\text{H}_2\text{SiO}_5\cdot 8\text{H}_2\text{O}$, by the action of hydrochloric acid on calcium metasilicate, CaSiO_3 .

These data and the preceding notes show the complexity of the molecules of anhydrous silica. The hydrate, $\text{Si}(\text{OH})_4$ (orthosilicic acid), is very unstable, and easily gives metasilicic acid, $\text{SiO}(\text{OH})_2$, and the latter also loses a further amount of water with facility and gives the hydrates $(\text{SiO}_2)_n(\text{H}_2\text{O})_m$, where m becomes less and less than n . In the natural hydrates, this decrement of water proceeds quite consecutively, and, so to say, imperceptibly, until n becomes incomparably greater than m , and when the ratio becomes very large, anhydrous silica of the two modifications 2·6 and 2·2 is obtained. The composition $(\text{SiO}_2)_{10}\cdot\text{H}_2\text{O}$ still corresponds with 2·9 p.c. of water, and natural hydrates often contain still less water than this. Thus some opals are known which contain only 1 p.c. of water, whilst others contain 7 and even 10 p.c. As the artificially prepared gelatinous hydrate of silica when dried has many of the properties of native opals, and as this hydrate always loses water easily and consecutively, there can be no doubt that the transition of $(\text{SiO}_2)_n(\text{H}_2\text{O})_m$ into anhydrous silica, both amorphous and crystalline (in nature, chalcedony), is accomplished gradually. This can only be the case if the magnitude of n be considerable, and therefore the molecule of silica in the hydrate is undoubtedly complex, and, therefore, the anhydrous silica of sp. gr. 2·2 and 2·6 does not contain SiO_2 , but a complex molecule, Si_nO_{2n} —that is, the structure of silica is polymeric and complex, and not simple, as represented by the formula SiO_2 .

natural gelatinous hydrates, are directly soluble in water. There is, however, a known condition of silica which is soluble in water, *soluble silica*; and silica is found in this state in nature. Small quantities of soluble silica are met with in all waters. Certain mineral springs, and especially hot springs—of which the best known are the Geysers of Iceland and in the North American National Park (Yellowstone Valley)—contain a considerable amount of silica in solution. Such water, permeating the objects it meets with—for instance, *wood*—penetrates into them and deposits silica inside them, that is, transforms them into a petrified condition. Siliceous stalactites, and also many (if not all) forms of silica, are formed by such water. Their formation is founded on the fact that aqueous solutions of silica, under many conditions, separate gelatinous silica; and the latter parts with water and turns into a stony mass. The absorption of silica by plants by means of their roots, and also by the lower organisms having siliceous bodies, is due also to their nourishing themselves with the solutions containing silica continually formed in nature. Thus, in plants, in the straws of the grasses, in hard shave-grass, and especially in the knots of bamboo and other straw-like plants, a considerable quantity of silica is deposited, which must previously have been absorbed by the plants.

Silicic acid is a colloid. The gelatinous silicon hydrate is its hydrogel, the soluble hydrate is the hydrosol (Chapter XVII.). Both varieties may easily be obtained from the alkaline silicates and water-glass. The very same substances—that is, aqueous solutions of soluble glass and acid—taken in the same proportion, may produce either the gelatinous or the soluble silica, according to the way these solutions are mixed together. If the acid be added little by little to the *alkaline silicate*, with continuous stirring, a moment arrives when the whole mass thickens to a jelly, hydrogel; in this case the silicic acid is formed in the midst of the alkaline solution and becomes insoluble. But if the mixing be done in the reverse order—that is, if the soluble glass be added to the acid, or if a quantity of acid be rapidly poured into the solution of the salt—then the separation of the silica takes place in the midst of the acid liquid, and it is obtained in the form of the soluble hydrate, the hydrosol.¹⁶

¹⁶ The presence of an excess of acid aids the retention of the silica in the solution, because the gelatinous silica obtained in the above manner, but not heated to 60°—that is, containing more water than the hydrate H_2SiO_3 —is more soluble in water containing acid than in pure water. This would seem to indicate a feeble tendency of silica to combine with acids, and it might even have been imagined that in such a solution the hydrate of silica is held in combination with an excess of acid, had Graham not obtained soluble silica perfectly free from acid, and if there were not solutions of silica free from

The hydrosol of silica prepared by mixing an excess of hydrochloric acid with a solution of sodium silicate, may be freed from the admixtures both of hydrochloric acid and salt, sodium chloride, *by means of dialysis*,¹⁷ as *Graham* showed (in 1861) in explaining the nature of colloids, and making many other important chemical investigations. The solution, containing the acid, salt, and silica, all dissolved in water, is poured into a dialyser—that is, a vessel with a porous diaphragm surrounded by water. Certain substances pass more easily through the diaphragm than others. This may be represented thus: the passage through the diaphragm proceeds in both directions, and if the solution on each side of the diaphragm be equally strong, then there will be equal numbers of molecules of the soluble substance passing into either side in a given time, some passing quickly and others slowly. The metallic chlorides and hydrochloric acid belong to the series of crystalloids which easily pass through a diaphragm, and therefore the hydrochloric acid and sodium chloride contained in the above-mentioned dialyser pass from the solution through the diaphragm into the water of the external vessel with considerable rapidity. The aqueous solution of colloidal silica also penetrates through the diaphragm, but very much more slowly. But if the amount of the substance dissolved is not equal on either side of the diaphragm, then the whole system strives to attain a state of equilibrium; that is, the given substance penetrates through the diaphragm from the side where it abounds to the part where there is a lesser quantity of it. All substances which are soluble in water have the faculty of penetrating through a membrane swollen in water, but the velocity of penetration is not equal, and in this respect the dialyser separates substances like a sieve. The silica passes less rapidly through the diaphragm than the sodium chloride and hydrochloric acid, so that by repeatedly changing the external water it is easy to effect the extraction of the chlorine compounds from the dialyser, which will finally only contain a solution of silica. This extraction may be so complete that the liquid taken from the dialyser

any acid in nature. At all events a somewhat strong solution of free silica or silicic acid may be obtained from soluble glass diluted with water. The solution, besides silica, will contain sodium chloride and an excess of the acid taken. If this solution remains for some time exposed to the air, or in a closed vessel, and under various other conditions, it is found that, after a time, insoluble gelatinous silica separates out—that is, the soluble form of silica is unstable, like the soluble form of alumina. The analogous forms of molybdic or tungstic acids may be heated, evaporated, and kept for a long period of time without the soluble form being converted into the insoluble.

¹⁷ See Vol. I. p. 63, Note 18. A solution of water-glass mixed with an excess of hydrochloric acid is poured into the dialyser, and the outer vessel is filled with water, which is renewed (from a water tap). The water carries off the sodium chloride and hydrochloric acid, and the hydrosol remains in the dialyser.

will not give any precipitate with a solution of silver nitrate. Graham thus obtained soluble silica having a distinctly acid reaction, which, however, disappeared on the addition of a very minute quantity of alkali ; for ten parts of silica in the solution it was sufficient to take one part of alkali in order to give the liquid an alkaline reaction, so slightly energetic are the acid properties of silicic acid. The solution of silica obtained by this method becomes gelatinous in time, or on being heated, or on evaporation under the receiver of an air-pump, &c. The hydrosol is transformed into the hydrogel, the soluble hydrate into the gelatinous.

Thus in addition to the gelatinous form of the silicic acid, there exists also a variety of this substance, soluble in water, as is the case with alumina. Such variation in properties and exactly the same relations with regard to water characterise an immense series of other substances having a great significance in nature. The number of such substances is especially great among organic compounds, and particularly in those classes of them which compose the principal material of the bodies of animals and plants. It is sufficient to mention, for instance, the gelatin which is familiar to all as carpenter's and other glues, and in the form of size and jelly. The same substance is also known in the solution which is used to join objects together. In a peculiar insoluble condition it enters into the composition of hides and bones. These various forms of gelatin differ in the same way as the different varieties of silica. The property of forming a jelly is exactly the same as in silica, and the adhesiveness of the solutions of both substances is identical ; soluble silica adheres like a solution of gelatin. The same properties are again shown by starch, rosin, and albumin, and by a series of similar substances. The diaphragms used in dialysis are also insoluble, gelatinous, forms of colloids. The bodies of animals and plants consist largely of similar matter, insoluble in water, corresponding with the gelatinous or insoluble silicon hydrate, or with glue. The albumin which coagulates when eggs are boiled is a typical form of the gelatinous condition of such substances in the body. These slight indications are sufficient in order to see how great is the significance of those transformations which are so sharply observable in silica. The facts discovered by *Graham* in 1861-1864 comprise the most essential acquisitions in the general association of these phenomena of nature in the history of organic forms. The facility of transit from hydrogel to hydrosol is the first condition of the possibility of the development of organisms. The blood contains hydrosols, and the hydrogels of the same substances are contained in the muscles and tissues, and especially on the surface, of the body. All tissues are formed

from the blood, and in that case the hydrosols turn into hydrogels.¹⁸ The absence of crystallisation, the property, apparently under influence of feeble agencies, of passing from the soluble condition to the insoluble, to the gelatinous condition of the hydrogel, compose the fundamental properties of all colloids.¹⁹

Silica, as regards its *salt-forming properties*, stands in the series of oxides on the boundary line on the side of the acids in just such a place as alumina occupies on the side of the bases—that is, aluminium hydroxide is the representative of the feeblest bases and silicic acid is the least energetic of acids (at least in the presence of water—that is, in aqueous solutions); in alumina, however, the basic properties are distinctly expressed, while in silica the acid properties preponderate. Like all feeble acid oxides it is capable of forming, with other acids, but slightly stable saline compounds which are very easily decomposed in the presence of water, but nevertheless it does not form compounds in the presence of water with other acids, whilst alumina, although forming saline compounds with acids, is, like all feebly basic acids, at the same time capable of combining with alkalis. The chief peculiarity of the silicates consists in the number of their types. The salts formed with nitric or sulphuric acid exist in one, two, and three fairly stable forms, but for acids like silicic acid the number of forms is very great, almost unlimited. The natural silicates in particular furnish proof of this fact; they contain various bases in combination with silica, and for one and the same base there often exist various degrees of combination. As feeble bases are capable of forming basic salts in addition to normal salts—that is, a compound of a normal salt with a feeble base (either the hydroxide or the oxide)—so the feeble acid oxides (although not all) form, in addition to normal salts, highly acid salts—that is, normal salts *plus* acid (hydrate or anhydride). Such acids are boric, phosphoric, molybdic, chromic, and especially silicic, acid. These salts are all non-volatile.

¹⁸ A similar process occurs in plants—for example, when they secrete a store of material for the following year in their bulbs, roots, &c. (for instance, the potato in its tubers), the solutions from the leaves and stems penetrate into the roots and other parts in the form of hydrosols, where they are converted into hydrogels—that is, into an insoluble form, which is acted on with difficulty and is easily kept unaltered until the period of growth—for example, until the following spring—when they are re-converted into hydrosols, and the insoluble substance re-enters into the sap, and serves as a source of the hydrogels in the leaves and other portions of plants.

¹⁹ As regards their chemical composition the colloids are very complex—that is, have a high molecular weight and a large molecular volume—in consequence of which they do not penetrate through membranes, and are easily subject to variation in their physical and chemical properties (owing to their complex structure and polymerism?) They have but little chemical energy, and are generally feeble acids.

In order to explain these relations it is necessary first to recollect the existence of the various hydrates of silica, or silicic acids,²⁰ and then to turn our attention to the similarity between silicon compounds and metallic alloys. Silica is an oxide having the appearance of, and in many respects the same properties as, those oxides which combine with it, and if two metals are capable of forming a homogeneous alloy in which there exist definite or indefinite compounds, then it is lawful to assume a similar power of forming mutual alloys in the case of oxides. Such alloys are found in indefinite, amorphous masses in the form of glass, lava, slags, and a number of similar siliceous compounds which do not contain any definite types of combination, but nevertheless are homogeneous throughout their mass. By slow cooling, or under other circumstances, definite crystalline compounds may—and sometimes do

²⁰ This is in accordance with the generally-accepted representation of the relations between salts and the hydrates of acids, but it is of little help in the study of siliceous compounds, because (1) the hydrates are nothing else but salts of hydrogen, and, therefore, they must bear the same relation to each other as salts do; (2) the hydrate $\text{SiO}_2 \cdot 2\text{H}_2\text{O}$ is almost unknown, whilst compounds of silica with a large proportion of water have long been known, and salts are known which contain a still larger relative proportion of bases. Properly speaking, it becomes necessary to explain the property of $(\text{SiO}_2)_n$ to combine with $(\text{RO})_m$, where n may be greater than m , and where R may be H_2 . There we are aided by those facts which have been attained by the investigation of carbon compounds, especially with respect to glycol. Glycol is a compound having the composition $\text{C}_2\text{H}_6\text{O}_2$, only differing from alcohol, $\text{C}_2\text{H}_6\text{O}$, by an extra atom of oxygen. This hydrate contains two hydroxyl groups, which may be successively replaced by chlorine, and the hydrogen of both may be successively substituted by sodium and various acid radicles. Therefore the composition of glycol should be represented as $\text{C}_2\text{H}_4(\text{OH})_2$. It has been found that glycol forms so-called polyglycols. Their origins will be understood from the fact that glycol as a hydrate has a corresponding anhydride of the composition $\text{C}_2\text{H}_4\text{O}$, known as ethylene oxide. This substance is ethane, C_2H_6 , in which two hydrogens are replaced by one atom of oxygen. Ethylene oxide is not the only anhydride of glycol, although it is the simplest one, because $\text{C}_2\text{H}_4\text{O} = \text{C}_2\text{H}_4(\text{OH})_2 - \text{H}_2\text{O}$. Various other anhydrides of glycol are possible, and have actually been obtained, of the composition $n\text{C}_2\text{H}_4(\text{OH})_2 - (n-1)\text{H}_2\text{O} = (\text{C}_2\text{H}_4)_n\text{O}_{n-1}(\text{OH})_2$. These imperfect anhydrides of glycol, or *polyglycols*, still contain hydroxyls like glycol itself, and therefore are of an alcoholic character in the same degree as glycol itself. They are obtained by various methods and, amongst others, by the direct combination of ethylene oxide with glycol, because $\text{C}_2\text{H}_4(\text{OH})_2 + (n-1)\text{C}_2\text{H}_4\text{O} = (\text{C}_2\text{H}_4)_n\text{O}_{n-1}(\text{OH})_2$. The most important circumstance, from a theoretical point of view, is that these polyethylenic glycols may be distilled without undergoing decomposition, and that the general formula given above expresses their actual molecular composition—that is, corresponds with their molecular weight. Hence we have here a direct combination of the anhydride with the hydrate, and, moreover, a repeated one. The formula $\text{A}_n\text{H}_2\text{O}$ may express the composition of glycol and polyglycols with respect to ethylene oxide in a most simple manner, if A stand for ethylene oxide. When $n=1$ we have glycol, when n is greater than 1 a polyglycol. Such also is the relation of the salts of hydrate of silica, if A stand for silica, and if we imagine that H_2O may also be taken m times. Such a representation of the *polysilicic acids* corresponds with the representation of the polymerism of silica. Laurent supposed the existence of several polymeric forms, Si_2O_4 , Si_5O_8 , &c., besides silica, SiO_2 . It is obvious that the letter n presupposes similar polymeric forms.

—separate from this homogeneous mass, as also sometimes definite crystalline alloys separate from metallic alloys.

The formation of crystalline rocks in nature is partly of such a nature. By aqueous or igneous agency, but in any case in a liquid condition, those oxides which form the earth's crust and her crystalline minerals came into mutual contact. First of all they formed a shapeless mass, of which lava, glass, and slags are examples, but little by little, or else suddenly, some definite compounds of certain oxides existing in this alloy or in the shapeless mass were formed. This is entirely similar to two metals forming a homogeneous alloy,²¹ and under known circumstances (for instance, on cooling the alloy, or in the case of aqueous solution, when the two metals are simultaneously liberated from the solution), crystalline definite compounds are separated. In any case there is no doubt that there is less distinction between silica and bases, than between bases and such anhydrides as, for instance, sulphuric or nitric, or even carbonic, as is seen on comparing the physical and chemical properties of silica and various kinds of oxides. Alumina, especially, is exceedingly near akin to silica; not only in the hydrated state, but also in the anhydrous condition, there even exists a certain

²¹ For us the latter have not a saline character, only because they are not regarded from this point of view, but an alloy of sodium and zinc is, in a wide sense, a salt in many of its reactions, for it is subject to the same double decompositions as sodium phosphide or sulphide, which clearly have saline properties. The latter, when heated with ethyl iodide, forms ethyl phosphide, and the former—*i.e.* the alloy of zinc and sodium—gives zinc ethyl; that is, the element (P, S, Zn) which was united with the sodium passes into combination with the ethyl: $RNa + EtI = REt + NaI$, hence the alloy of sodium and zinc is a saline substance in the same sense that sodium sulphide is. By combining sodium successively with chlorine, sulphur, phosphorus, arsenic, antimony, tin, and zinc we obtain substances having less and less the ordinary appearance of salts, but if the alloy of sodium and zinc cannot be termed a salt, then perhaps this name cannot be given to sodium sulphide, and the compounds of sodium with phosphorus. The following circumstance may also be observed: with chlorine, sodium gives one compound (with oxygen, at the most three), with sulphur five, with phosphorus probably still more, with antimony naturally still more, and the more analogous an element is to sodium, the more varied are the proportions in which it is able to combine with it; the less are the alterations in the properties which take place by this combination, and the nearer does the compound formed approach to the class of compounds known as indefinite chemical compounds. In this sense a siliceous alloy, containing silica and other acids, is a salt. The oxide to a certain extent plays the same part as the sodium, whilst the silica plays the part of the acid element which was taken successively by zinc, phosphorus, sulphur, &c., in the above examples. Such a comparison of the silica compounds with alloys presents the great advantage of including under one category the definite and indefinite silica compounds which are so analogous in composition—that is, brings under one head such crystalline substances as certain minerals, and such amorphous substances as are frequently met with in nature, and are artificially prepared, as glass, slags, enamels, &c.

If the compounds of silica are substances like the metallic alloys, then (1) the chemical union between the oxides of which they are composed must be a feeble one, as it is in all compounds formed between analogous substances. In reality such feeble agencies as

similarity between the crystalline forms of alumina and silica, taken separately. Both are very hard, transparent, inactive, non-volatile, infusible, and crystallise in the hexagonal system—in a word, they are remarkably similar, and for this reason they are capable, like two kindred metals, of entering into many various degrees of combination. Isomorphous mixtures—that is, the substitution of oxides akin both in their properties and chemical characters—are very frequently met with among minerals, and the study of the latter gave the principal support to the study of isomorphism. Thus, in a whole series of minerals, lime and magnesia are found in variable and interchangeable proportions. Exactly the same may be said of potassium and sodium, of alumina and ferric oxide, of manganous, ferrous, magnesium oxides, &c. Such isomorphous mixtures do not, however, extend without change of form and properties beyond certain rather narrow limits. What I mean by this is that lime is not always replaced totally, but often only in small quantities, by magnesia, or by the manganous and ferrous oxides, without changing the crystalline form. The same may be observed concerning potassium and lithium, which may be in part, but not completely, replaced by sodium. On the total substitution of one metal for another, often (although not invariably) the entire nature of the substance is changed; for instance, *enstatite* (or *bronzite*) is a magnesium bisilicate with a small isomorphous substitution of calcium for magnesium; its composition is expressed by the formula MgSiO_3 , it belongs to the rhombic system. On the entire substitution of calcium, *vollastonite*, CaSiO_3 , of the monoclinic system, is obtained; when manganese is substituted, *rhodonite*, of the triclinic system, is produced; but in all of them the angles of the prism are 86° to 88° .

It is, however, easy to imagine, and fact confirms the supposition, that in a complex siliceous compound containing, for instance, sodium

water and carbonic acid are able, although slowly, to act on and destroy the majority of the complex silica compounds in rocks, as we saw in the preceding chapter; (2) their formation, like that of alloys, should not be accompanied by a considerable alteration of volume; and this is actually the case. For example, feldspar has a specific gravity of about 2.6, and therefore, taking its composition to be $\text{K}_2\text{O}, \text{Al}_2\text{O}_3, 6\text{SiO}_2$, we find its volume, corresponding with this formula, to be $556.8/2.6 = 214$; the volume of $\text{K}_2\text{O} = 35$, of $\text{Al}_2\text{O}_3 = 26$, and of $\text{SiO}_2 = 22.6$. Hence the sum of the volumes of the component oxides, $35 + 26 + 6 \times 22.6 = 196$, which is very nearly equal to that of the feldspar; that is, its formation is attended by a slight expansion, and not by contraction, as is the case in the majority of other cases when combinations determined by strong affinities are accomplished. In the case in question the same phenomenon is observed as in solutions and alloys—that is, as in cases of feeble affinities. So also the specific gravity of glass is directly dependent on the amount of those oxides which enters into its composition. If in the preceding example we take the sp. gr. of silica to be, not 2.65, but 2.2, then its volume = 27.3, and then the sum of the volumes will be = 224—that is, greater than that of orthoclase.

and calcium, the whole of the sodium may be replaced by potassium, and *at the same time* the whole of the calcium by magnesium, because then the substitution of potassium for the sodium will produce a change in the nature of the substance contrary to that which will occur from the calcium being replaced by magnesium. That increase in weight, decrease in density, increase of chemical energy, which accompanies the exchange of sodium and potassium will, so to speak, be compensated by the exchange of calcium and magnesium, because both in weight and in properties the sum of $\text{Na} + \text{Ca}$ is very near to the sum of $\text{K} + \text{Mg}$. *Pyroxene* or *augite* can be taken as an example; its composition may be expressed by the formula $\text{CaMgSi}_2\text{O}_6$; that is, it corresponds with the acid H_2SiO_3 ; it is a bisilicate. In many respects it closely resembles another mineral called '*spodumene*' (they are both monoclinic). This latter has the composition $\text{Li}_6\text{Al}_3\text{Si}_{15}\text{O}_{45}$. On reducing both formulæ to an equal contents of silica the following distinction will be observed between them: *spodumene* $(\text{Li}_2\text{O})_6(\text{Al}_2\text{O}_3)_330\text{SiO}_2$; *augite* $(\text{CaO})_{15}(\text{MgO})_{15}30\text{SiO}_2$.²² That is, the difference between them consists in the sum of the magnesia and lime $(\text{MgO})_{15} + (\text{CaO})_{15}$ replacing the sum of the lithium oxide and alumina $(\text{Li}_2\text{O})_6 + (\text{Al}_2\text{O}_3)_3$; and in the chemical relation these sums are near to one another, because magnesium and calcium, both in forms of oxidation and in energy (as bases), in all respects occupy the mean between lithium and aluminium, and therefore the sum of the first may be replaced by the sum of the second.²³

²² If we take the composition of *spodumene*, as it is often represented to be, $\text{Li}_2\text{O}, \text{Al}_2\text{O}_3, 4\text{SiO}_2$, then the corresponding formula of *augite* will be $(\text{CaO})_2, (\text{MgO})_2, 4\text{SiO}_2$, and also the amount of oxygen in the sum of $\text{Li}_2\text{OAl}_2\text{O}_3$ will be the same as in $(\text{CaO})_2(\text{MgO})_2$. I may remark, for the sake of clearness, that lithium belongs to the first, aluminium to the third group, and calcium and magnesium to the intermediate second group; lithium, like calcium, belongs to the even series, and magnesium and aluminium to the uneven.

The representation of the substitutions of analogous compounds here introduced was first deduced by me in 1856. It finds much confirmation in facts which have been subsequently discovered—for example, with respect to *tourmalin*. Wülfing (1888), on the basis of a number of analyses (especially of those by Riggs), states that all its varieties contain an isomorphous mixture of alkali and magnesia *tourmalin*; into the composition of the former there enters $12\text{SiO}_2, 3\text{B}_2\text{O}_3, 8\text{Al}_2\text{O}_3, 2\text{Na}_2\text{O}, 4\text{H}_2\text{O}$, and of the latter $12\text{SiO}_2, 8\text{B}_2\text{O}_3, 5\text{Al}_2\text{O}_3, 12\text{MgO}, 3\text{H}_2\text{O}$. Hence it is seen that the former differs by the sum of $3\text{Al}_2\text{O}_3, 2\text{Na}_2\text{O}, \text{H}_2\text{O}$, and that in the latter this sum of oxides is replaced by 12MgO , in which there is as much oxygen as in the complement of the more sharply-defined base $2\text{Na}_2\text{O}$ and less basic $3\text{Al}_2\text{O}_3\text{H}_2\text{O}$ —that is, the relation is just the same here as between *augite* and *spodumene*.

²³ With respect to the silica compounds of the various oxides, it must be observed that only the *alkali salts* are known in a soluble form; all the others only exist in an insoluble form, so that a solution of the alkali compounds of silica, or soluble glass, gives a precipitate with a solution of the salts of the majority of other metals, and this precipitate will contain the silica compounds of the other bases. The silica compounds of the alkalis may be obtained by a dry or wet method by fusing the alkalis or their car-

The most remarkable complex siliceous compounds are the *jaspers*, which enter into nearly all the primary rocks like porphyry, granite,

bonates with silica, or by dissolving the hydrates of silica in the caustic alkalis, as has been already mentioned. The maximum amount of the gelatinous hydrate of silica, which dissolves in caustic potash, corresponds with the formation of a compound, $2K_2O, 9SiO_2$. But this compound is already insoluble in cold water, and is partially decomposed, with the precipitation of hydrate of silica, on cooling the solution. Solutions containing a smaller amount of silica may be kept for an indefinite time without decomposing, and silica does not separate out from the solution; but in this case a definite compound is rarely obtained, because such compounds crystallise from the solutions with difficulty. However, a crystalline bisilicate (with water) has been obtained for sodium having the composition Na_2O, SiO_2 —*i.e.*, corresponding to metasilicic acid, $SiO(OH)_2$. The whole of the carbonic acid is evolved, and a similar sodium metasilicate is obtained on fusing 3·5 parts of sodium carbonate with 2 parts of silica. If less silica is taken, a portion of the sodium carbonate remains undecomposed; however, a substance may then be obtained of the composition $Si(ONa)_4$, corresponding with orthosilicic acid. It contains the maximum amount of sodium oxide capable of combining with silica under fusion. It is a sodium orthosilicate, $(Na_2O)_2, SiO_2$. There are higher degrees of combination; thus, even tetrasilicate, $Na_4O, 4SiO_2$, is known in solution. If in fusing with sodium carbonate a larger proportion of silica is taken than is required for the formation of the metasilicate, then nevertheless all the silica passes into the alloy, although the resultant mass is less fusible and less soluble in water, but still it is homogeneous. Alkaline solutions, saturated with silica and known as *soluble glass*, are prepared on a large scale for technical purposes by the action of potassium (or sodium) hydroxide in a steam boiler on tripoli or infusorial earth, which contains a large proportion of amorphous silica. Solutions of the alkaline silicates have all an alkaline reaction, and are even decomposed by carbonic acid. They are chiefly used by the dyer, for the same purposes as sodium aluminate, and also for giving a hardness and polish to stucco and other cements, and in general to substances which contain lime. A lump of chalk when immersed in soluble glass, or, better still, when moistened with a solution and afterwards washed in water (or, better, in hydrofluosilicic acid, in order to bind together the free alkali and make it insoluble), becomes exceedingly hard and loses its friability, and is rendered cohesive, and cannot be levigated in water. This transformation is due to the fact that the hydrate of silica present in the solution acts upon the lime, forming a stony mass of calcium silicate, whilst the carbonic acid previously in combination with the lime enters into combination with the alkali and is washed away by the water.

Calcium carbonate, and the carbonates of the alkaline earths in general, also evolve all their carbonic acid when heated with silica, and in some instances even form somewhat fusible alloys. Lime forms a fusible slag of *calcium silicate*, of the composition CaO, SiO_2 and $2CaO, 3SiO_2$. With a larger proportion of silica the slags are infusible in a furnace. The magnesium *slags* are less fusible than those with lime, and are often formed in smelting metals. Many compounds of the metals of the alkaline earths with silica are also met with in nature. For instance, among the magnesium compounds there is *olivine*, $(MgO)_2, SiO_2$, sp. gr. 3·4, which occurs in meteorites, and sometimes forms a precious stone (peridot), and occurs in slags and basalts. It is decomposed by acids, is infusible before the blow-pipe, and crystallises in the rhombic system. *Serpentine* has the composition $3MgO, 2SiO_2, 2H_2O$; it sometimes forms whole mountains, and is distinguished for its great cohesiveness, and is therefore used for building purposes. It is generally tinted green; its specific gravity is 2·5; it is exceedingly infusible, even before the blow-pipe. It is acted on by acids. Among the magnesium compounds of silica, *talc* is very widely used. It is frequently met with in rocks which are widely distributed in nature, and sometimes in compact masses; it writes like a slate pencil or chalk, and is greasy to the touch, and is therefore also known as *steatite*. It crystallises in the rhombic system, and resembles mica in many respects; like it, it is divisible into laminae,

gneiss, &c. These felspars always contain, in addition to silica and alumina, oxides presenting more marked basic properties, such as potash, soda, and lime. Thus the *orthoclase* (adularia), or ordinary felspar (monoclinic) of the granites, contains $\text{K}_2\text{O}, \text{Al}_2\text{O}_3, 6\text{SiO}_2$; *albite* contains the same substances, only with Na_2O instead of K_2O (it already appertains to the triclinic system); *anorthite* contains lime, and its composition is $\text{CaO}, \text{Al}_2\text{O}_3, 2\text{SiO}_2$. On expressing the two latter in equal terms of oxygen, we have :—

Albite	Na_2	Al_2	Si_6	O_{16}
Anorthite	Ca_2	Al_4	Si_4	O_{16}

It is, then, evident that on albite turning into anorthite Na_2Si_2 is replaced by Ca_2Al_2 , and this sum, both in chemical energy and in form of oxide, may be counted as corresponding with the first, because sodium and silicon are extreme elements in chemical character (from groups I. and IV.), and calcium and aluminium are means between them (from groups II. and III.), and actually both these felspar minerals are not only of one (triclinic) system, but form (Tschermak, Schuster), judging from their composition and all their properties, all possible kinds of definite compounds (isomorphous mixtures) between

greasy to the touch, and having a sp. gr. 2·7. These laminae are very soft, lustrous, and transparent, and are infusible and insoluble in acids. The composition of talc approaches nearly to $6\text{MgO}, 5\text{SiO}_2, 2\text{H}_2\text{O}$.

Among the crystalline silicates the following minerals are known:—*Wollastonite* (tabular-spar), crystallises in the monoclinic system; sp. gr. 2·8; it is semi-transparent, difficultly fusible, decomposed by acids, and has the composition of a metasilicate, CaOSiO_2 . But isomorphous mixtures of calcium and magnesium silicates occur with particular frequency in nature. The *augites* (sp. gr. 3·3), diallages, hypersthènes, hornblendes (sp. gr. 3·1), amphiboles, common asbestos, and many similar minerals, sometimes forming the essential parts of entire rock formations, contain various relative proportions of the bisilicates of calcium and magnesium partially mixed with other metallic silicates, and generally anhydrous, or only containing a small amount of water. Many of these minerals present a composition in which there are equal atomic amounts of lime and magnesia, and sufficient silica to form a metasilicate—that is, their composition approaches to the formula $\text{MgO}, \text{CaO}, 2\text{SiO}_2$; but sometimes a considerable proportion of alumina also enters into their composition, and still more often the amount of silica exceeds that given in the above formula. In the pyroxenes, as a rule, the lime predominates, and in the amphiboles (also of the monoclinic system) the magnesia predominates.

Clay is one of the hydrous silicates of alumina, $(\text{Al}_2\text{O}_3)_m(\text{SiO}_2)_n$. These are all infusible at a furnace heat, or only soften with difficulty. The most easily softened is the compound containing $2\text{Al}_2\text{O}_3, 9\text{SiO}_2$ (trisilicate). In an anhydrous state in nature there are known, for example, the *stauroilites*, of the rhombic system, hard as quartz, sp. gr. 3·7, $3\text{R}_2\text{O}_3, 2\text{SiO}_2$, where R is aluminium partially replaced by iron in the form of ferrous and ferric oxides. This is almost a semi-silicate, because it contains O_4 in the form of silica to O_6 in the form of alumina, and we may remark that more energetic bases do not give such lower degrees of combination with silica and such basic salts, and we know that the faculty to form such salts is clearly developed in alumina.

themselves. Thus oligoclase, andesine, labradorite, &c. (plagioclases), are nothing more than mutual combinations of albite and anorthite. Thus albite, $\text{Na}_2\text{O}, \text{Al}_2\text{O}_3, 6\text{SiO}_2$, enters into the composition of labradorite in combination with one to two parts of anorthite $(\text{CaO})_2(\text{Al}_2\text{O}_3)_2(\text{SiO}_2)_4$. The class of *zeolites* corresponds to the feldspars; they are hydrated compounds of a similar composition to the feldspars. Thus *natrolite* contains $\text{Na}_2\text{O}, \text{Al}_2\text{O}_3, 3\text{SiO}_2, 2\text{H}_2\text{O}$, and *analcime* presents the same composition, but contains 4SiO_2 instead of 3SiO_2 . In general, the feldspars and zeolites contain $\text{RO}, \text{Al}_2\text{O}_3, n\text{SiO}_2$, where n varies considerably.²⁴

Such complex silicates, containing all other bases except alkalis, are generally insoluble in water,²⁵ and if they undergo change in it, it is

²⁴ The majority of the siliceous minerals have now been obtained artificially under various conditions. Thus N. N. Sokoloff showed that slags very frequently contain peridotite. Hautefeuille, Chroustchoff, Friedel, and Sarasin obtained feldspar identical in all respects with the natural minerals. The details of the methods here employed must be looked for in special works on mineralogy; but, as an example, we will describe the method of the preparation of feldspar employed by Friedel and Sarasin (1881). From the fact that feldspar gives up potassium silicate to water even at the ordinary temperature (Debray's experiments), they concluded that the feldspar in granites had an aqueous origin (and this may be supposed to be the case from geological data); then, in the first place, its formation could not be accomplished unless in the presence of an excess of a solution of potassium silicate. In order to render this argument clear I may mention, as an example, that carnallite is decomposed by water into easily soluble magnesium chloride and potassium chloride, and therefore if it is of aqueous origin it could not be formed otherwise than from a solution containing an excess of magnesium chloride, and, in the second place, from a strongly-heated solution; again, feldspar itself and its fellow components in granites are anhydrous. On these facts they based their experiments of heating hydrates of silica with alumina and a solution of potassium silicate in a closed vessel. The mixture was placed in a tightly-closed platinum tube, which was placed in a steel tube and heated to dull redness. When the mixture contained an excess of silica the residue contained many crystals of rock crystal and tridymite, together with a powder of feldspar, which formed the main product of the reaction when the proportion of hydrate of silica was decreased, and a mixture of a solution of potassium silicate with alumina precipitated together with the silica by mixing soluble glass with aluminium chloride was employed. The composition, properties, and forms of the resultant feldspar proved it to be identical with that found in nature. The experiments approach very nearly to the natural conditions, all the more as feldspar and quartz are obtained in one mixture, as they so often occur together in nature.

²⁵ The application of *cements* is based on this principle; they are those sorts of lime which generally form a stony mass, which even hardens under water, when mixed with sand and water.

The hydraulic properties of cements are due to their containing calcareous and silico-aluminous compounds which are able to combine with water and form hydrates, which are then unacted on by water. This is best proved, in the first place, by the fact that certain slags containing lime and silica, and obtained by fusion (for example, in blast-furnaces), solidify like cements when finely ground and mixed with water; and, in the second place, by the method now employed for the manufacture of artificial cements (formerly only particular and comparatively rare natural products were used). For this purpose a mixture of lime and clay is taken, containing about 25 p.c. of the latter; this mixture is then heated, not to fusion, but until the carbonic anhydride and water con-

but very slow, and more often only in the presence of carbonic acid. Some of the silicates which are insoluble in water are easily and directly decomposed by acids ; for instance, the zeolites and those fused silicates which contain a large quantity of energetic bases—such as lime. Many of the silicates, like glass,²⁵ are not changed by the action of

tained in the clay is expelled. This mass when finely ground forms Portland cement, which hardens under water. The process of hardening is based on the formation of chemical compounds between the lime, silica, alumina, and water. These substances are also found combined together in various natural minerals—for example, in the zeolites, as we saw above. At all events the hardened cement contains a considerable amount of water, and its hardening is naturally due to hydration—that is, to the formation of compounds with water. Well-prepared and very finely-ground cement is able to harden comparatively quickly (in several days, especially after being rammed down), with 3 parts (and even more) of coarse sand and with water, into a stony mass which is as hard and durable as many stones, and more so than bricks and limestone. Hence not only all maritime constructions (docks, ports, bridges, &c.), but also ordinary buildings, are made of Portland cement, and are distinguished for their great durability. A combination of ironwork (ties, girders) and cement is particularly suitable for the construction of aqueducts, arches, reservoirs, &c. The thickness of the arches and walls made of such cements may be much less than those built up of ordinary stone. Hence the production and use of cement rapidly increases from year to year. The origin of accurate data respecting cements is chiefly due to Vicat. In Russia Professor Schuliachenko has greatly aided the extension of accurate data concerning Portland cement. Many works for the manufacture of cement have already been established in various parts of Russia, and this production promises a great future in the arts of construction.

²⁵ Glass presents a similar complex composition, like that of many minerals. The ordinary sorts of white glass contain about 75 p.c. of silica, from 10 to 15 p.c., and even more, of sodium oxide, and 7 to 20 p.c. of lime ; but the lower sorts of glass sometimes contain up to 10 p.c. of alumina. The mixtures which are used for the manufacture of glass are also most varied. They take, for example, about 300 parts of pure sand, about 100 parts of sodium carbonate, and 50 of limestone, which is sometimes taken in double this proportion. Ordinary *soda-glass* contains sodium oxide, lime, and silica as the chief component parts. It is generally prepared from sodium sulphate mixed with charcoal, silica, and lime (Chapter XII.), in which case the following reaction takes place at a high temperature : $\text{Na}_2\text{SO}_4 + \text{C} + \text{SiO}_2 = \text{Na}_2\text{SiO}_3 + \text{SO}_2 + \text{CO}$. Sometimes potassium carbonate is taken for the preparation of the better qualities of glass. In this case a glass, *potash-glass*, is obtained containing potassium oxide instead of sodium oxide. The best-known of these glasses is the so-called Bohemian glass or crystal, which is prepared by the fusion of 50 parts of potassium carbonate, 15 parts of lime, and 100 parts of quartz. The preceding kinds of glass contain lime, whilst crystal glass contains lead oxide instead. Flint glass—that is, the lead glass used for optical instruments—is prepared in this manner, naturally from the purest possible materials. *Crystal glass*—i.e. glass containing lead oxide—is softer than ordinary glass, but, on the other hand, it is more fusible and has a higher index of refraction. The lower qualities of glass—for example, bottle-glass—are prepared from unsorted and impure materials, and therefore contain, besides the colourless oxides, other substances and iron oxides, which communicate different tints to the glass. However, although the materials for the preparation of glass be most carefully sorted, a certain amount of iron oxides falls into the glass and renders it greenish. This coloration may be destroyed by adding a number of substances to the glassy mass, which are able to convert the ferrous oxide into ferric oxide ; for example, manganese peroxide (because the peroxide is deoxidised to manganous oxide, which only gives a pale violet tint to the glass) and arsenious anhydride, which is deoxidised to arsenic, which is volatilised. The manufacture of glass is carried on in furnaces giving a very high tem-

acids, particularly if they contain much acid oxide (silica), whilst fusion with alkalis leads to the formation of compounds rich in bases, after which acids decompose the alloys formed.²⁷

According to the periodic law, the nearest analogues of silicon ought to be elements of the uneven series, because silicon, like sodium, magnesium, and aluminium, belongs to the uneven series.²⁸ Immediately

perature (often in regenerative furnaces, Chapter IX.). Large clay crucibles are placed in these furnaces, and the mixture destined for the preparation of the glass, having been first roasted, is charged into the crucibles. The temperature of the furnace is then gradually raised. The process is attended by three separate periods. At first the mass intermixes and begins to react; then it fuses, and evolves carbonic acid gas, and forms a molten mass; and, lastly, at the highest temperature, it becomes homogeneous and quite liquid, which is necessary for the ultimate elimination of the carbonic anhydride and solid impurities, which then collect at the bottom of the crucible. The temperature is then somewhat lowered, and the glass is taken out on tubes and blown into objects of various shapes. In the manufacture of window-glass it is blown into large cylinders, which are then cut at the ends and across, and afterwards bent back in a furnace into the ordinary sheets. After being worked up, all glass objects have to be subjected to a slow cooling (*annealing*) in special furnaces, as otherwise they are very brittle, as is seen in the so-called 'Rupert's drops,' formed by dropping molten glass into water; although these drops preserve their form, they are so brittle that they break up into a fine powder if a small piece be knocked off them. Then glass objects have frequently to be polished and chased. In the manufacture of mirrors and many massive objects the glass is cast and then ground and polished. Coloured glasses are made either by directly introducing various oxides, which give their characteristic tints into the glass itself, or a thin layer of a coloured glass is laid on the surface of ordinary glass. Green glasses are formed by the oxides of chromium and copper, blue glasses by cobalt oxide, violet glasses by manganese oxide, and red glass by cuprous oxide and by the so-called purple of cassius—*i.e.* a compound of gold and tin—which will be described later. A yellow coloration is obtained by means of the oxides of iron, silver, or antimony, and also by means of carbon, especially for the brown tints for certain kinds of bottle-glass.

From what has been said about glass it will be understood that it is impossible to give a definite formula for it, because it is a non-crystalline or amorphous alloy of silicates; but such an alloy can only be formed within certain limits in the proportions between the component oxides. With a large proportion of silica the glass very easily becomes clouded when heated; with a considerable proportion of alkalis it is easily acted on by moisture, and becomes cloudy in time on exposure to the air; with a large proportion of lime it becomes infusible and opaque, owing to the formation of crystalline compounds in it; in a word, a certain proportion is practically attained among the component oxides in order that the glass formed may have suitable properties. Nevertheless, it may be well to remark that the composition of common glass approaches to the formula $\text{Na}_2\text{O}, \text{CaO}, 4\text{SiO}_2$.

The coefficient of cubical expansion of glass is nearly equal to that of platinum and iron, being approximately 0.000027. The specific heat of glass is nearly 0.18, and the specific gravity of common soda glass is nearly 2.5, of Bohemian glass 2.4, and of bottle glass 2.7. Flint glass is much heavier than common glass, because it contains the heavier oxide of lead, its specific gravity being 2.9 to 3.2.

²⁷ It must be recollected that although acids seem to act only feebly on the majority of silicates, nevertheless a finely-leigated powder of siliceous compounds is acted on by strong acids, especially with the aid of heat, the basic oxides being taken up and gelatinous silica left behind. In this respect sulphuric acid heated to 200° with finely-divided siliceous compounds in a closed tube evinces the most energetic action.

²⁸ Such elements as silicon, tin, and lead were only brought together under one common

after silicon follows ekasilicon or *germanium*, $\text{Ge}=72$, whose properties were predicted (1871) before Winkler (1886) in Freiberg, Saxony (p. 24), discovered this element in a peculiar silver ore called *argyrodite*.²⁹ Easily reduced from the oxide by heating with hydrogen and charcoal, and separated from its solutions by zinc, metallic germanium proved to be grayish white, easily crystallisable (in octahedra), brittle, fusible (under a coating of fused borax) at about 900° , and easily oxidisable; the specific gravity $=5.469$, the volume weight $=72.3$, and the specific heat $=0.076$,³⁰ as might be expected for this element according to the periodic law. The corresponding *germanium dioxide*, GeO_2 , is a white powder having a specific gravity of 4.703 ; water, especially boiling water, dissolves this dioxide (1 part of GeO_2 requires for solution 247 parts of water at 20° , 95 parts at 100°). It forms soluble salts with alkalis and is but sparingly soluble in acids.³¹ In a stream of chlorine the metal forms *germanium chloride*, GeCl_4 , which boils at 86° , and has a specific gravity of $=1.887$ at 18° ; water decomposes it, forming the oxide. All these properties³² of germanium, showing its analogy to silicon and tin, form a most beautiful demonstration of the truth of the periodic law.³³

group by means of the periodic law, although the quadrivalency of tin and lead was known much earlier. Generally silicon was placed among the non-metals, and tin and lead among the metals.

²⁹ At first (February 1886) the want of material to work on, the absence of a spectrum in the Bunsen's flame, and the solubility of many of the compounds of germanium, presented difficulties in the researches of Professor Winkler, who, on analysing argyrodite by the usual method, obtained a constant loss of 7 p. c., and was thus led to search for a new element. The presence of arsenic and antimony in the accompanying minerals also impeded the separation of the new metal. After fusion with sulphur and sodium carbonate, argyrodite gives a solution of a sulphide which is precipitated by an *excess* of hydrochloric acid; germanium sulphide is soluble in ammonia and then precipitated by hydrochloric acid, as a *white* precipitate, which is dissolved (or decomposed) by water. The composition of argyrodite is $(\text{Ag}_2\text{S})_3\text{GeS}_2$, it contains by analysis 6.9 p. c. of germanium, whilst the formula requires 8.2 p. c.; the difference is explained by the presence of iron, zinc, and mercury. When the mineral is heated in a current of air it forms sulphurous anhydride and a sublimate of germanium sulphide, GeS_2 . After being oxidised by nitric acid, dried and ignited, this leaves the oxide GeO_2 , which is reduced to the metal when ignited in a stream of hydrogen.

³⁰ G. Kobb determined the spark spectrum of germanium, when the metal was taken as one of the electrodes of a powerful Ruhmkorff's coil. The wave lengths of the most distinct lines are 602, 583, 518, 513, 481, 474.

³¹ If germanium or germanium sulphide be heated in a stream of hydrochloric acid, it forms a volatile liquid, which boils at 72° , and which Winkler regarded as germanium chloride, GeCl_2 , or germanium chloroform, GeHCl_3 . It is decomposed by water, forming a white substance, which perhaps may be the hydrate of germanous oxide, GeO , and acts as a powerfully reducing agent in a hydrochloric acid solution.

³² Even the fact that under certain circumstances germanium gives a blue coloration like that of ultramarine, as Winkler showed, and as might be expected from the analogy of germanium with silicon.

³³ Winkler expressed this in the following words (*Jour. f. pract. Chemie*, 1886 [2], 34, 182-188): ' . . . es kann keinem Zweifel mehr unterliegen, dass das neue Element nichts

The increase of atomic weight from silicon 28 to germanium 72 is 44—that is, about the same difference as there is in the atomic weights of chlorine and bromine; between germanium and its next analogue, tin ($\text{Sn}=118$), the difference is 46—that is, almost as much as the amount by which the atomic weight of iodine exceeds that of bromine.

Tin is rarely met with *in nature*; it occurs in the veins of ancient formations, almost exclusively in the form of oxide, SnO_2 , called *tin-stone*. The best known tin deposits are in Cornwall and in Malacca. In Russia tin ores have been found in small quantities on the shores of Lake Ladoga, in Pitkarand. The crushed ore may easily be separated from the earthy matter accompanying it by washing on inclined tables, as the tin-stone has a specific gravity of 6.9, whilst the impurities are much lighter. *Tin oxide is very easily reduced* to metallic tin by heating with charcoal. For this reason tin was known in ancient times, and the Phœnicians exported it from England. Metallic tin is cast into ingots of considerable weight. Tin has a white colour, but rather duller than that of silver. Tin easily fuses at 230° , and crystallises on cooling. Its specific gravity is 7.29. The crystalline structure of ordinary tin is noticed in bending tin rods, when a peculiar sound is heard, produced by the fracture of the particles of tin along the surfaces of crystalline structure.

When pure tin is considerably cooled it splits up into separate crystals, the bond between the particles is lost, the tin assumes a grey colour, becomes less brilliant—in a word, its properties become changed, as Fritzsche showed. This depends on the peculiar structure which the tin then acquires, and is particularly remarkable because it is effected by cold in a solid. If such tin be fused, or even simply heated, it becomes like ordinary tin, but is again changed when cooled. When in this condition tin has a specific gravity of 7.19. Similarly, tin is obtained by the action of the galvanic current on a solution of tin chloride; it then appears in crystals of the cubic system, and has a specific gravity of 7.18—that is, the same as when cooled.

Tin is softer than silver and gold, and is only surpassed by lead in this respect. In addition to this it is very ductile, but its tenacity is

Anderes, als das vor fünfzehn Jahren von *Mendeléeff* prognosticirte *Ekasilicium* ist.'

'Denn einen schlagenderen Beweis für die Richtigkeit der Lehre von der Periodicität der Elemente, als den, welchen die Verkörperung des bisher hypothetischen "Ekasilicium" in sich schliesst, kann es kaum geben, und er bildet in Wahrheit mehr, als die blasse Bestätigung einer kühn aufgestellten Theorie, er bedeutet eine eminente Erweiterung des chemischen Gesichtsfeldes, einen mächtigen Schritt ins Reich der Erkenntniss.'

very slight, so that wire made from it will bear but little strain. In consequence of its ductility it is easily worked, by forging and rolling into very thin sheets (tin foil), which are used for wrapping many articles to preserve them from moisture, &c. In this case, however, and in many others, lead is mixed with the tin, which, within certain limits, does not alter the ductility. Whilst so soft at the ordinary temperatures tin becomes brittle at 200° , before fusing. Tin powder may be easily obtained, if tin be heated until fusion and then stirred whilst cooling. At a white heat tin may be distilled, but with more difficulty than zinc. If molten tin comes into contact with oxygen, it oxidises, forming stannic oxide, SnO_2 , and its vapour burns with a white flame. *At ordinary temperatures tin does not oxidise*, and this very important property of tin allows it to be applied in many cases for covering other metals to prevent their oxidising. This is termed *tinning*. Iron and copper are tinned. Iron and steel sheets, coated with tin, bear the name of tin plate (for the most part made in England), and are used for numerous purposes. Tin plate is prepared by immersing iron sheets, previously thoroughly cleansed by acid and mechanical means, into molten tin.³⁴

Tin with copper forms *bronze*, an alloy which is most extensively used in the arts. Bronze has various colours and a variety of physical properties, according to the relative amount of copper and tin which it contains. With an excess of copper the alloy has a yellow colour; the admixture of tin imparts considerable hardness and elasticity to the copper. An alloy containing 78 parts of copper and about 22 per cent. of tin is so elastic that it is used for casting bells, which naturally require a very elastic and hard alloy.³⁵ For casting

³⁴ If after this the coating of tin be rapidly cooled—for instance, by dashing water over it—it crystallises into diverse star-shaped figures, which become visible when the sheets are first immersed in dilute aqua regia and then in a solution of caustic soda.

The coating of iron by tin guards it against the direct access of air, but it only preserves the iron from oxidation so long as it forms a perfectly continuous coating. If the iron is left bare in certain places, it will be powerfully oxidised at these spots, because the tin is electro-negative with respect to the iron, and thus the oxidation is entirely limited to the iron in the presence of tin. Therefore a coating of tin over iron objects only partially preserves them from rusting. In this respect a coating of zinc is more effectual. However, a dense and invariable alloy is formed over the surface of contact of the iron and tin, which binds the coating of tin to the remaining mass of the iron. Tin may be fused with cast iron, and gives a greyish-white alloy, which is very easily cast and is used for casting many objects for which iron by itself would be unsuitable owing to its ready oxidisability and porosity. The coating of copper objects by tin is generally done to preserve the copper from the action of acid liquids, which would attack the copper in the presence of air and convert it into soluble salts. Tin is not acted on in this manner, and therefore copper vessels for the preparation of food should be tinned.

³⁵ The ancient Chinese alloys, containing about 20 p.c. of tin (specific gravity of alloys about 8.2) and which have been rapidly cooled, are distinguished for their resonance and elasticity. These alloys used to be manufactured in large quantities in China for the

statues and various large or small ornamental articles alloys containing 2 to 5 p. c. of tin, 10 to 30 p. c. of zinc, and 65 to 85 p. c. of copper are used.⁵⁶ Tin is also used (most often alloyed with lead) for making various objects—for instance, drinking vessels.

When heated, tin decomposes the vapour of water, liberating the hydrogen and forming stannic oxide. Sulphuric acid, diluted with a considerable quantity of water, does not act, or at all events acts very slightly, on tin, but tin reduces hot, strong, sulphuric acid, when not only sulphurous anhydride but also sulphuretted hydrogen is evolved. Hydrochloric acid acts very easily on tin, with evolution of hydrogen and formation of stannous chloride, SnCl_2 , in solution, which, with an excess of hydrochloric acid and access of air, is converted into stannic

musical instruments known as *gong-gongs*. Owing to their hardness, alloys of this nature are also employed for casting guns, sockets, &c., and an alloy containing about 11 p.c. of tin (corresponding with the ratio Cu_{15}Sn) is known as gun-metal. The addition of a small quantity of phosphorus, up to 2 p.c., renders bronze still harder and more elastic, and the alloy so formed is now used under the name of phosphor-bronze.

The alloy SnCu_3 is brittle, of a bluish colour, and has nothing in common with either copper or tin in its appearance or properties. It remains perfectly homogeneous on cooling, and acquires a crystalline structure (Riche). All these signs clearly indicate that the alloy SnCu_3 is a product of chemical combination, which is also seen to be the case from its density, 8.91. Had there been no contraction, the density of the alloy would be 8.21. It is the heaviest of all the alloys of tin and copper, because the density of tin is 7.29 and of copper 8.8. The alloy SnCu_4 , specific gravity 8.77, has similar properties. All the alloys except SnCu_3 and SnCu_4 split up on cooling; a portion richer in copper solidifies first (this phenomenon is termed the *liquation* of an alloy), but the above two alloys do not split up on cooling. In these and many similar facts we can clearly distinguish a *chemical union between the metals* forming an alloy. The alloys of tin and copper were known in very remote ages, before iron was used. The alloys of zinc and tin are less used, but alloys composed of zinc, tin, and copper frequently replace the more costly bronze.

⁵⁶ An excellent proof of the fact that alloys and solutions are subject to law is given, amongst others, by the application of Raoult's method (Vol. I. pp. 90 and 323) to solutions of different metals in tin. Thus Heycock and Neville (1889) showed that the temperature of solidification of molten tin (226.4°) is lowered by the presence of a small quantity of other metals in proportion to the concentration of the solution. The following were the reductions of the temperature of solidification of tin obtained by dissolving in it atomic proportions of different metals (for example, 65 parts of zinc), in 11800 parts of tin: Zn 2.58° , Cu 2.47° , Ag 2.67° , Cd 2.16° , Pb 2.22° , Hg 2.3° , Sb 2° , Al 1.34° . As Raoult's method (Vol. I. p. 323) enables the molecular weight to be determined, the almost perfect identity of the resultant figures (except for aluminium) shows that the molecules of copper, silver, lead, and antimony contain *one atom in the molecule*, like zinc, mercury, and cadmium. It should here be mentioned that Ramsay (1889) for the same purpose (the determination of the molecular weight of metals on the basis of their mutual solution) took advantage of the variation of the vapour tension of mercury (*see* Vol. I. p. 134), containing various metals in solution, and he also found that the above-mentioned metals contain but one atom in the molecule. However, both methods are based on laws concerning the magnitudes of *i* (Chapter I. Notes 12 and 49), which have only been lately discovered, are not yet sufficiently explained, and require still further development before they can acquire as great a significance as the vapour density has received in the determination of the molecular weight of a metal.

chloride: $\text{SnCl}_2 + 2\text{HCl} + \text{O} = \text{SnCl}_4 + \text{H}_2\text{O}$. The action of a mixture of hydrochloric acid and tin forms an excellent means of reducing, wherein both the hydrogen liberated by the mixture (at the moment of separation) and the stannous chloride act as powerful reducing and deoxidising agents. Thus, for instance, by this mixture nitro-compounds are transformed into amido compounds—that is, the elements of the group, NO_2 , are reduced to NH_2 . Nitric acid diluted with a considerable quantity of water dissolves tin at the ordinary temperature, whilst the nitric acid itself is reduced, forming, amongst other things, ammonia and hydroxylamine. Here the tin passes into solution in the form of stannous nitrate. Stronger nitric acid (also the more dilute when heated) transforms the tin into its highest degree of oxidation, SnO_2 , but the latter then appears as the so-called metastannic acid, which does not dissolve in nitric acid, and therefore the tin does not pass into solution. Feeble acids—for instance, carbonic and organic acids—do not act on tin even in the presence of oxygen, because tin does not form any powerful bases.

It is important to remark as a characteristic of tin that it is reduced from its solutions by many metals which are more easily oxidised, as, for instance, by zinc.

In combination, tin appears in the two types, SnX_4 and SnX_2 ,³⁷ compounds of the intermediate type, Sn_2X_6 , being also known, but these latter pass with remarkable facility in most cases into compounds of the higher and lower types, and therefore the form SnX_3 cannot be considered as independent.

Stannous oxide, SnO , in an anhydrous condition is obtained by boiling solutions of stannous salts with alkalis, the first action of the alkali being to precipitate a white hydrate of stannous oxide, $\text{Sn}(\text{OH})_2\text{SnO}$. The latter when heated parts with water as easily as the hydrate of copper oxide. In this form stannous oxide is a black crystalline powder (specific gravity 6·7, atomic volume=20) capable of further oxidation when heated. The hydrate is freely soluble in acids, and also in potassium and sodium hydroxides, but not in aqueous ammonia.³⁸

³⁷ Many volatile compounds of tin are known, which enables their molecular weights to be established from their vapour densities. Among these may be mentioned stannic chloride, SnCl_4 , and stannic ethide, $\text{Sn}(\text{C}_2\text{H}_5)_4$ (the latter boils at about 150°). But Meyer found the vapour density of stannous chloride, SnCl_2 , to be variable between its boiling point (606°) and 1100° , owing, it would seem, to the fact that the molecule then varies from Sn_2Cl_4 to SnCl_2 , but the vapour density proved to be less than that indicated by the first and greater than that shown by the second formula, although it approaches to the latter as the temperature rises—that is, it presents a similar phenomenon to that observed in the passage of N_2O_4 into NO_2 (Vol. I. p. 274).

³⁸ When rapidly boiled, an alkaline solution of stannous oxide deposits tin and forms stannic oxide, $2\text{SnO} = \text{Sn} + \text{SnO}_2$, which remains in the alkaline solution.

This property recalls the feeble basic properties of this lower oxide, which acts in many cases as a reducing agent.³⁹

Among the compounds corresponding with stannous oxide the most remarkable and the one most frequently used is stannous chloride or chloride of tin, SnCl_2 , also called protochloride of tin. It is a transparent, colourless, crystalline substance, melting at 250° and boiling at 606° . Water dissolves it, without visible change (in reality partial decomposition occurs, as the sequel will show). It is also soluble in alcohol. It is obtained by heating tin in dry hydrochloric acid gas, the hydrogen being then liberated, or by dissolving metallic tin in strong hot hydrochloric acid and then evaporating quickly. Crystals of the monoclinic system are then obtained having the composition, $\text{SnCl}_2 \cdot 2\text{H}_2\text{O}$. An aqueous solution of this substance absorbs oxygen from the atmosphere, and gives a precipitate containing stannic oxide. This naturally means that a solution of stannous chloride will act as a reducing agent, and this fact is frequently made use of in chemical investigations—for instance, for reducing metals from their solutions—because even mercury may be reduced to a metallic state from its salts by means of stannous chloride. This reducing property is also employed in practice, especially in the dyeing industry, where this substance in the form of a crystalline salt finds an extensive application, and is known as *tin salt*.

Stannic oxide, SnO_2 , found in nature (as *tinestone*, *cassiterite*), is formed during the oxidation or combustion of heated tin in air as a white or yellowish powder which fuses with difficulty. It is prepared in large quantities, because it is used in a white vitreous mixture for

³⁹ Weber (1882) by precipitating a solution of stannous chloride with sodium sulphite (this salt as a reducing agent prevents the oxidation of the stannous compound) and dissolving the washed precipitate in nitric acid, obtained crystals of *stannous nitrate*, $\text{Sn}(\text{NO}_3)_2 \cdot 20\text{H}_2\text{O}$ on refrigerating the solution. This crystallo-hydrate easily melts, and is deliquescent. Besides this, a more stable anhydrous basic salt, $\text{Sn}(\text{NO}_3)_2 \cdot \text{SnO}$, is easily formed. In general, stannous oxide as a feeble base easily forms basic salts, just as cupric and lead oxides do. For the same reason SnX_2 easily forms double salts. Thus a potassium salt, $\text{SnK}_2\text{Cl}_4 \cdot \text{H}_2\text{O}$, and especially an ammonium salt, $\text{Sn}(\text{NH}_4)_2\text{Cl}_4 \cdot \text{H}_2\text{O}$, called *pink salt*, are known. Some of these salts are used in the arts, owing to their being more stable than tin salts alone. Stannous bromide and iodide, SnBr_2 and SnI_2 , resemble the chloride in many respects.

Among other stannous salts a sulphate, SnSO_4 , is known. It is formed as a crystalline powder when a solution of stannous oxide in sulphuric acid is evaporated under the receiver of an air-pump. The feeble basic character of the stannous oxide is clearly evinced in the salt. It decomposes with extreme facility, when heated, into stannic oxide and sulphurous anhydride, but it easily forms double salts with the salts of the alkali metals.

In gaseous hydrochloric acid, stannous chloride, $\text{SnCl}_2 \cdot 2\text{H}_2\text{O}$, forms a liquid having the composition $\text{SnCl}_2 \cdot \text{HCl} \cdot 3\text{H}_2\text{O}$ (sp. gr. 2.2, freezes at 27°), and a solid salt, $\text{SnCl}_2 \cdot \text{H}_2\text{O}$ (Engel).

coating ordinary tiles and similar earthenware objects with a layer of easily fusible glass or enamel. Acid solutions of stannic oxide treated with alkalis, and alkaline solutions when treated with acids, give a precipitate of stannic hydroxide, $\text{Sn}(\text{OH})_4$, also known as stannic acid, which, when heated, gives up water and leaves the anhydride, SnO_2 , which is insoluble in acids, clearly showing the feebleness of its basic character. When fused with alkali hydroxides (not with their carbonates or acid sulphates), an alkaline compound is obtained which is soluble in water. Stannic hydroxide, like the hydrates of silica, is a colloidal substance, and presents several different modifications, depending on the method of preparation, but having an identical composition; the various hydroxides have also a different appearance, and act differently with reagents. For instance, a distinction is made between ordinary stannic acid and metastannic acid. *Stannic acid* is produced by precipitation by soda or ammonia from a freshly-prepared solution of stannic chloride, SnCl_4 , in water; on drying the precipitate thus obtained, a non-crystalline mass is formed, which is freely soluble in strong hydrochloric or nitric acids, and also in potassium and sodium hydroxides. This ordinary stannic acid may be still better obtained from sodium stannate by the action of acids. *Metastannic acid* is insoluble in sulphuric and nitric acids. It is obtained by treating tin with nitric acid, in the form of a heavy white powder; hydrochloric acid does not dissolve it immediately, but changes it to such an extent that, after pouring off the acid, water extracts the stannic chloride, SnCl_4 , already formed. Dilute alkalis not only dissolve metastannic acid, but also transform it into salts, which, although slowly, yet completely dissolve in *pure water*, but are insoluble even in dilute alkali hydroxides. Dilute hydrochloric acid, especially when boiling, changes the ordinary hydrate into metastannic acid. On this depends, by the way, the formation of a white precipitate, stannic hydroxide, from solutions of stannous and stannic chlorides diluted with water. The stannic oxide first dissolved changes under the influence of hydrochloric acid into metastannic acid, which is insoluble in water in the presence of hydrochloric acid. Solutions of metastannic acid differ from such solutions of ordinary stannic acid, and in the presence of alkali they change into solutions of ordinary acid, so that metastannic acid principally corresponds with the acid compounds of stannic oxide, and ordinary stannic acid with the alkaline compounds.⁴⁰ Graham

⁴⁰ Fremy supposes the cause of the difference to consist in a difference of polymerisation, and considers that the ordinary acid corresponds with the oxide SnO_2 , and the meta-acid with the oxide Sn_5O_{10} , but it is more probable that both are polymeric

obtained a soluble colloidal hydroxide; it is subject to the same transformations that are in general peculiar to colloids.

Stannic oxide shows the properties of a slightly energetic and intermediate oxide (like water, silica, &c.); that is to say, it forms saline compounds both with bases and with acids, but both are easily decomposed, and are but slightly stable. But still the acid character is more clearly developed than the basic, as in silica, germanic oxide, and lead dioxide. This determines the character of the compounds SnX_4 .

Stannic chloride, SnCl_4 (also called tetrachloride of tin), is one of the compounds which most characteristically correspond with stannic oxide. It is obtained in an anhydrous condition by the direct action of chlorine on tin, and is then easily purified, because it is a liquid boiling at 114° , and therefore can be easily distilled. Its specific gravity is 2.28 (at 0°), and it fumes in the open air (*spiritus fumans libarii*); it shows the properties of a chloranhydride. Water, however, does not at first decompose it, but dissolves it, and on evaporation gives the crystallo-hydrate $\text{SnCl}_4 \cdot 5\text{H}_2\text{O}$. If but little water be taken, crystals containing $\text{SnCl}_4 \cdot 3\text{H}_2\text{O}$ are formed, which part with one-third of the water when placed under the receiver of the air-pump. A large quantity of water, however, especially when heated, causes a precipitate of metastannic acid.⁴¹

The alkali compounds of stannic oxide—that is, the compounds in

but in a different degree. Stannic acid with sodium carbonate gives a salt of the composition Na_2SnO_3 . The same salt is also obtained by fusing metastannic acid with sodium hydroxide, whilst metastannic acid gives a salt, $\text{Na}_2\text{SnO}_3 \cdot 4\text{SnO}_2$ (Fremy), when treated with a dilute solution of alkali; moreover, stannic acid is also soluble in the ordinary stannate, Na_2SnO_3 (Weber), so that both stannic acids (like both forms of silica) are capable of polymerisation, and probably only differ in its degree. In general, there is here a great resemblance to silica, and Graham obtained a solution of stannic acid by the direct dialysis of its alkaline solution. The main difference between these acids is that the meta-acid is soluble in hydrochloric acid, and gives a precipitate with sulphuric acid and stannous chloride, which do not precipitate the ordinary acid.

⁴¹ The formation of the compound $\text{SnCl}_4 \cdot 3\text{H}_2\text{O}$ is accompanied by so great a contraction that these crystals, although they contain water, are heavier than the anhydrous chloride SnCl_4 . The meta-hydrated crystallo-hydrate absorbs dry hydrochloric acid, and gives a liquid of specific gravity 1.971, which at 0° yields crystals of the compound $\text{SnCl}_4 \cdot 2\text{HCl} \cdot 6\text{H}_2\text{O}$ (it corresponds with the similar platinum compound), which melt at 20° into a liquid of specific gravity 1.925 (Engel).

Stannic chloride combines with ammonia ($\text{SnCl}_4 \cdot 4\text{NH}_3$), hydrocyanic acid, phosphoretted hydrogen, phosphorus pentachloride ($\text{SnCl}_4 \cdot \text{PCl}_5$), nitrous anhydride and its chloranhydride ($\text{SnCl}_4 \cdot \text{N}_2\text{O}_5$ and $\text{SnCl}_4 \cdot 2\text{NOCl}$), and with metallic chlorides (for example, $\text{K}_2\text{SnCl}_6 \cdot (\text{NH}_4)_2\text{SnCl}_6$, &c.). In general, a highly-developed faculty for combination is observed in it. The development of this faculty in water, aluminium chloride, and other substances whose composition corresponds with the higher forms of combination of the elements, shows that they have affinities beyond those which determine the combination of their atoms. The peculiarity of these kinds of compounds is that they always combine

which it plays the part of an acid, corresponding in this way to the compounds of silica and other anhydrides of the composition RO_2 —are very easily formed. They are distinguished by their great simplicity, and are used in the arts. Their composition in most cases corresponds with the formula SnM_2O_3 —that is, $\text{SnO}(\text{MO})_2$, similar to $\text{CO}(\text{MO})_2$, where $\text{M}=\text{K}, \text{Na}$. Acids, even feeble acids like carbonic, decompose these salts, like the corresponding compounds of alumina or silica. In order to obtain *potassium stannate*, which crystallises in rhombohedra, and has the composition $\text{SnK}_2\text{O}_3, 3\text{H}_2\text{O}$, potassium hydroxide (8 parts) is fused, and metastannic acid (3 parts) gradually added. A solution of the mass thus prepared, when evaporated in a desiccator, forms crystals of the above-mentioned composition. *Sodium stannate* has a similar composition. It is prepared in practice in large quantities by heating a solution of caustic soda with lead oxide and metallic tin. In this last case an alkaline solution of lead oxide is formed, and the tin acts on the solution in such a way as to reduce the lead to the metallic state, and itself passes into solution. This is very remarkable in this respect, that the lead displaces tin when in combination with acids, and the tin, on the contrary, displaces the lead from its alkali compounds. By dissolving the mass obtained in water, and then

with whole molecules capable of individual existence, and that such compounds resemble those with water of crystallisation in many respects.

Tin does not combine directly with iodine, but if its filings be heated in a closed tube with a solution of iodine in carbon bisulphide, it forms stannic iodide, SnI_4 , in the form of red octahedra which fuse at 142° and volatilise at 295° . The fluorine compounds of tin have a special interest in the history of chemistry, because they give a series of double salts which are isomorphous with the salts of hydrofluosilicic acid, SiR_2F_6 , and this fact served to confirm the formula SiO_2 for silica, as the formula SnO_2 was indubitable. However, *stannic fluoride*, SnF_4 , is almost unknown in an isolated form, but its corresponding double salts are very easily formed by the action of hydrofluoric acid on alkaline solutions of stannic oxide; thus, for example, a crystalline salt of the composition $\text{SnK}_2\text{F}_6, \text{H}_2\text{O}$ is obtained by dissolving stannic oxide in potassium hydroxide and then adding hydrofluoric acid to the solution. The barium salt, $\text{SnBaF}_6, 3\text{H}_2\text{O}$, is sparingly soluble like its corresponding silicofluoride. The more soluble salt of strontium, $\text{SnSrF}_6, 2\text{H}_2\text{O}$, crystallises very well, and is therefore more important for the purposes of research; it is isomorphous with the corresponding salt of silicon (and titanium); the magnesium salt contains $6\text{H}_2\text{O}$.

Stannic sulphide, SnS_2 , is formed, as a yellow precipitate, by the action of sulphuretted hydrogen on acid solutions of stannic salts; it is easily soluble in ammonium and potassium sulphides, because it has an acid character, and then forms thio-stannates (see Chapter XX.). In an anhydrous state it has the form of brilliant golden yellow plates, which may be obtained by heating a mixture of finely-divided tin, sulphur, and sal-ammoniac for a considerable time. It is sometimes used in this form under the name of mosaic gold, as a cheap substitute for gold-leaf in gilding wood articles. On ignition it parts with a portion of its sulphur, and is converted into stannous sulphide, SnS . It is soluble in caustic alkalis. Hydrochloric acid does not dissolve the anhydrous, crystalline compound, but the precipitated powdery sulphide is soluble in boiling strong hydrochloric acid, with the evolution of hydrogen sulphide.

adding alcohol, sodium stannate is precipitated, which may then be dissolved in water and purified by re-crystallisation. In this case it has the composition $\text{SnNa}_2\text{O}_3 \cdot 3\text{H}_2\text{O}$ if separated from strong solutions, and $\text{SnNa}_2\text{O}_3 \cdot 10\text{H}_2\text{O}$ when crystallised at a low temperature from dilute solutions. In the arts this salt is used as a mordant in dyeing operations, especially in the colouring of cotton fabrics. With a cold solution of sodium hydroxide metastannic acid forms a salt of the composition $(\text{NaHO})_2 \cdot 5\text{SnO}_2 \cdot 3\text{H}_2\text{O}$, from which Frémy drew his conclusions concerning the polymerism of metastannic acid.

Tin occupies the same position amongst the analogues of silicon as cadmium and indium amongst the analogues of magnesium and aluminium respectively, and as in each of these cases the heavier analogues with a high atomic weight and a special combination of properties—namely, mercury and thallium—are known, so also for silicon we have *lead* as the heaviest analogue ($\text{Pb}=206$), with a series of both kindred and special properties. The principal peculiarity of the lead compounds consists in the higher type PbX_4 , for instance, PbO_2 , being in the chemical sense far less stable than the lower type PbX . The ordinary compounds of lead correspond with the latter, and in addition to this, PbO , although not particularly energetic, is still an evident base easily forming basic salts $\text{PbX}_2(\text{PbO})_n$.

Lead is found in nature in considerable masses, in the form of galena, lead sulphide, PbS . The specific gravity of galena is 7.58, colour grey; it crystallises in the regular system, and has a fine metallic lustre. Both the native and artificial sulphides are insoluble in acids (hydrogen sulphide gives a black precipitate with the salts PbX_2).⁴² When heated it melts, and in the open air is either totally or partially transformed into white lead sulphate, PbSO_4 , as it also is by many oxidising agents (hydrogen peroxide, potassium nitrate). Lead sulphate is also insoluble in water,⁴³ and lead is but rarely met with in this form in nature. The chromates, vanadates, phosphates, and similar salts of lead are also rather rare. The carbonate PbCO_3 is sometimes found in large masses, especially in the Altai region. Lead sulphide is often worked for extracting the silver which it contains; but as the lead itself also finds manifold industrial appli-

⁴² Lead sulphide in the presence of zinc and hydrochloric acid is completely reduced to metallic lead, all the sulphur being disengaged as hydrogen sulphide.

⁴³ Lead sulphate, PbSO_4 , occurs in nature (*anglesite*) in transparent brilliant crystals which are isomorphous with barium sulphate, and have a specific gravity of 6.3. The same salt is formed on mixing sulphuric acid or its soluble salts with solutions of lead salts, as a heavy white precipitate, which is insoluble in water and acids, but dissolves in a solution of ammonium tartrate in the presence of an excess of ammonia, which serves to distinguish this salt from the similar salts of strontium and barium.

cations, this work is carried on on an exceedingly large scale. Two methods are principally applied. The first consists in decomposing the lead sulphide by heating it with cast iron. The iron takes up the sulphur from the lead, and forms easily-fusible iron sulphide, which does not mix with the heavier reduced lead. But another process is more frequently used, consisting in the following: the lead ore (it must be clean, that is, free from earthy matter, which may be easily removed by washing) is heated in a reverberatory furnace to a moderate temperature with a free access of air. During this operation part of the lead sulphide oxidises and forms lead sulphate, PbSO_4 , and lead oxide. When the oxidation of part of the lead has been attained, it is necessary to shut off the air supply and increase the temperature, then the oxidised compounds of the lead enter into reaction with the remaining lead sulphide, with formation of sulphurous anhydride and metallic lead. At first from $\text{PbS} + \text{O}_3$, $\text{PbO} + \text{SO}_2$ are formed, and also from $\text{PbS} + \text{O}_4$ lead sulphate PbSO_4 , and then PbO and PbSO_4 react with the remaining PbS , according to the equations $2\text{PbO} + \text{PbS} = 3\text{Pb} + \text{SO}_2$ and also $\text{PbSO}_4 + \text{PbS} = 2\text{Pb} + 2\text{SO}_2$.⁴⁴

The appearance of lead is well known; its specific gravity is 11.3; the bluish colour and considerable metallic lustre of freshly-cut lead quickly disappears when exposed to the air, because it becomes coated with a layer—truly a very thin layer—of oxide and salts formed by the moisture and acids in the atmosphere. It melts at 326° , and crystallises in octahedra on cooling. Its softness is apparent from the flexibility of lead pipes and sheets, and also from the fact that it may be cut with a knife, and also that it leaves a grey streak when rubbed on paper. On account of its being so soft, lead naturally cannot be applied in many cases where most metals may be used; but, on the other hand, it is a metal which is not easily changed by chemical reagents, and as it is capable of being soldered and drawn into sheets, &c., lead is most valuable for many technical uses. Lead pipes are used for conveying water⁴⁵ and many other liquids, and sheet lead is used for lining all kinds of vessels containing liquids—for instance, acids, which act on other metals. This particularly refers to sulphuric and hydro-

⁴⁴ As lead is easily reduced from its ores, and the ore itself has a metallic appearance, it is not surprising that it was known to the ancients, and that its properties were familiar to the alchemists, who called it 'saturn.' Hence, metallic lead, reduced from its salts in solution by zinc, and which has the appearance of a tree-like mass of crystals, is called 'arbor saturni,' &c.

⁴⁵ Freshly laid new lead pipes contaminate the water with a certain amount of lead salts, proceeding from the presence of oxygen, carbonic acid, &c., in the water. But the lead pipes under the action of running water soon become coated with a film of salts—lead sulphate, carbonate, chloride, &c.—which are insoluble in water, and the water pipes then become harmless.

chloric acids, because at a low temperature they do not act on lead, and if they form lead sulphate, PbSO_4 , and chloride, PbCl_2 , these salts being insoluble in water and in acids, cover the lead and protect it from further corrosion.⁴⁶ All soluble preparations of lead are poisonous. At a white heat lead may be partially distilled; the vapours oxidise and burn. Lead may also be easily oxidised at low temperatures. Lead only decomposes water at a white heat, and does not liberate hydrogen from acids, with the exception only of very strong hydrochloric acid and then only when boiling. Sulphuric acid diluted with water does not act on it, or only acts very feebly at the surface; but strong sulphuric acid, when heated, is decomposed by it, with the evolution of sulphurous anhydride. The best solvent of lead is nitric acid, which transforms it into a soluble salt, $\text{Pb}(\text{NO}_3)_2$.

Although acids in this way directly have but little effect on lead, and this is one of its most important practical properties, *yet when air has free access, lead (like copper) very easily reacts with many acids*, even with those which are comparatively feeble. The action of acetic acid on lead in particular is clear and often applied in practice. If lead is plunged into acetic acid it does not change at all and does not pass into solution, but if part of the lead is immersed in the acid, and the other part remains in contact with the air, or if lead be merely covered with a thin layer of acetic acid, in such a way that the air is practically in contact with the metal, then it unites with the oxygen of the air to form oxide, which combines with the acetic acid and forms lead acetate, soluble in water. The formation of lead oxide may especially be observed from the fact that with a sufficient quantity of air, not only is the normal lead acetate formed, but also the basic salts.⁴⁷

⁴⁶ Lead is not only used in the arts for drawing into tubes and sheets, for holding or conveying liquids, but also, owing to its considerable density, for being cast, when mixed with small quantities of other metals, into shot. A considerable amount is employed (together with mercury) in extracting gold and silver from poor ores, and in the manufacture of chemical reagents, and especially of lead chromate. *Lead chromate*, PbCrO_4 , is distinguished for its brilliant yellow colour, owing to which it is employed in considerable quantities as a dye, mainly for dyeing cotton tissues yellow. It is formed on the tissue itself, by causing a soluble salt of lead to react on potassium chromate. Lead chromate is met with in nature as 'red lead ore.' It is insoluble in water and acetic acid, but it dissolves in aqueous potash. The so-called pewter vessels often consist of an alloy of 5 parts of tin and 1 part of lead, and solder is composed of 1 to 2 parts of tin with $\frac{1}{2}$ part of lead. With respect to the alloys of lead and tin, Rudberg states that the alloy PbSn_3 stands out from the rest, because, according to his observations, the fall of temperature in the solidification of the alloy stops at 184° , which is the temperature at which this alloy solidifies. The composition of this alloy is nearly 37 p.c. of lead and 63 p.c. of tin.

⁴⁷ The normal lead acetate, known in trade as *sugar of lead*, owing to its having a sweetish taste, has the formula $\text{Pb}(\text{C}_2\text{H}_3\text{O}_2)_2 \cdot 3\text{H}_2\text{O}$. This salt only crystallises from acid solutions. It is capable of dissolving a further quantity of lead oxide or of metallic lead in

When oxidising in the presence of air,⁴⁸ when heated or in the presence of an acid at the ordinary temperature, lead forms compounds of the type PbX_2 . *Lead oxide*, PbO , known in industry as *litharge*, *silberglätte* (this name is due to the fact that silver is extracted from the lead ores of this kind) and *massicot*. If the lead is oxidised in air at a high temperature, the oxide which is formed fuses, and on cooling is easily obtained in fused masses which split up into scales of a yellowish colour, having a specific gravity of 9.3; in this form it bears the name of litharge. Litharge is principally used for making lead salts, and for the extraction of metallic lead, and also during the boiling of drying oils—for instance, linseed oil—that is, in the preparation of drying oils.⁴⁹ When oxidised carefully and slightly heated lead forms a powdery (not fused) oxide known under the name of *massicot*. It is best obtained by heating lead nitrate. Massicot is produced by heating lead

the presence of air. A basic salt of the composition $Pb(C_2H_5O_2)_2 \cdot PbH_2O_2$ is then formed, which is soluble in water and alcohol. As in this salt the number of atoms is even and the same as in the hydrate of acetic acid, $C_2H_4O_2 \cdot H_2O = C_2H_5(OH)_2$, it may be represented as this hydrate in which two of hydrogen are replaced by lead—that is, as $C_2H_5(OH)(O_2Pb)$. This basic salt is used in medicine as a remedy for inflammation, for bandaging wounds, &c., and also as a means for the manufacture of white lead. Other basic acetates of lead, containing a still greater amount of lead oxide, are known. According to the above representation of the composition of the preceding lead acetate, a basic salt of the composition $(C_2H_5)_2(O_2Pb)_5$ would be also possible, but what appear to be still more basic salts are known. As the character of a salt also depends on the property of the base from which it is formed, it would seem that lead forms a hydroxide of the composition HO_2PbOH , containing two water residues, one or both of which may be replaced by the acid residues. If both water residues are replaced, a normal salt $XPbX$ is obtained, whilst if only one is replaced a basic salt, $XPbOH$, is formed. But lead does not only give this normal hydroxide, but also polyhydroxides, $Pb(OH)_n$, and if we may imagine that in these polyhydroxides there is a substitution of both the water residues by acid residues, then the power of lead for forming basic salts is explained by the properties of the base which enters into their composition.

⁴⁸ Few compounds are known of the lower type PbX , and still fewer of the intermediate type PbX_3 . To the first type belongs the so-called lead suboxide, Pb_2O , obtained by the ignition of lead oxalate, C_2PbO_4 , without access of air. It is a black powder, which easily breaks up under the action of acids, and even by the simple action of heat, into metallic lead and lead oxide. This is the character of all true suboxides. It does not give definite salts PbX , and therefore it cannot be regarded as a salt-forming oxide, neither can those forms of oxidation of lead which contain more oxygen than the oxide of lead, PbO , and less than the dioxide, PbO_2 . As we shall see, at least two such compounds are formed. Thus, for example, an oxide having the composition Pb_2O_3 is known, but it is decomposed by the action of acids into lead oxide, which passes into solution, and lead dioxide, which remains behind. Such is red lead.

⁴⁹ In the boiling of drying oils, the lead oxide partially passes into solution, forming a saponified compound capable of attracting oxygen and solidifying into a tar-like mass, which forms the oil paint. Perhaps, however, glycerol partially acts in the process.

A mixture of very finely-divided litharge with glycerol (50 parts of litharge to 5 c.c. of anhydrous glycerol) forms a very quickly hardening (two minutes) cement, which is insoluble in water and oils, and is very useful in setting up chemical apparatus. The hardening is based on the reaction of the lead oxide with glycerol (Moraffsky).

hydroxide. It has a yellow colour, and differs from litharge in the greater difficulty with which it forms lead salts with acids. Thus, for instance, when massicot is moistened with water it does not attract the carbonic acid of the air so easily as litharge does. It may, however, be imagined that the cause of the difference depends only on the formation of a portion of dioxide on the surface of the lead oxide, on which the acids do not act. In any case lead oxide is comparatively easily soluble in nitric and acetic acids. It is but slightly soluble in water, but communicates an alkaline reaction to it, naturally forming the hydroxide. But the remaining mass does not combine with the water. This hydroxide is obtained in the shape of a white precipitate by the action of a small quantity of an alkali hydroxide on a solution of a lead salt. An excess of alkali dissolves the hydroxide separated, which fact demonstrates the comparatively indistinct basic properties of lead oxide. The normal lead hydroxide, which should have the composition $\text{Pb}(\text{OH})_2$, is unknown in a separate state, but it is known in combination with lead oxide as $\text{Pb}(\text{OH})_2 \cdot 2\text{PbO}$ or $\text{Pb}_3\text{O}_2(\text{OH})_2$. The latter is obtained in the form of brilliant, white, octahedral crystals when basic lead acetate is mixed with ammonia and gently heated. The basic qualities of this hydroxide are shown distinctly by its absorbing the carbonic anhydride of the air. When an alkaline solution of the hydroxide is boiled, it deposits lead oxide in the form of a crystalline powder.

Lead oxide forms but few soluble salts—for instance, the nitrate and the acetate. The majority of its salts (sulphate, PbSO_4 ; carbonate, PbCO_3 ; iodide, PbI_2 , &c.) are insoluble in water. These salts are colourless or light yellow if the acid is colourless. In lead oxide *the faculty of forming basic salts*, $\text{PbX}_n \cdot n\text{PbO}$ or $\text{PbX}_n \cdot n\text{PbH}_2\text{O}_2$, is strongly developed. A similar property was observed in magnesium and also in the salts of mercury, but lead oxide forms basic salts with still greater facility, although double salts are in this case more rarely formed.⁵⁰

⁵⁰ It is very instructive to observe that lead not only easily forms basic salts, but also salts containing several acid groups. Thus, for example, lead carbonate occurs in nature and forms compounds with lead chloride and sulphate. The first compound, known as *corneous lead*, *phosgenite*, has the composition $\text{PbCO}_3 \cdot \text{PbCl}_2$; it occurs in nature in bright cubical crystals, and is prepared artificially by simply boiling lead chloride with lead carbonate. A similar compound of normal salts, $\text{PbSO}_4 \cdot \text{PbCO}_3$, occurs in nature as *lanarkite* in monoclinic crystals. *Leadhillite* contains $\text{PbSO}_4 \cdot 3\text{PbCO}_3$, and also occurs in yellowish, monoclinic, tabular crystals. We will turn our attention to these salts of lead, because it is very probable that their formation is allied to the formation of the basic salts, and the following considerations may guide to the explanation of the existence of one and the others. In describing silica we carefully developed the conception of polymerisation, which it is *indispensable to also recognise in the composition of many other oxides*. Thus it may be supposed that PbO_2 is a similar polymerised compound to SiO_2 —i.e., that the composition of lead peroxide will be Pb_nO_{2n} , because lead methyl,

Amongst the soluble lead salts, that best known and most often applied in practical chemistry is lead nitrate, obtained directly by dissolving lead or its oxide in nitric acid. The normal salt, $\text{Pb}(\text{NO}_3)_2$, crystallises in octahedra, dissolves in water, and has a specific gravity of 4.5. When a solution of this salt acts on white lead or is boiled with litharge, the basic salt, having a composition $\text{Pb}(\text{OH})(\text{NO}_3)$, is formed in crystalline needles, sparingly soluble in cold water but easily dissolved in hot water, and therefore in many respects resembling lead chloride. When the nitrate is heated, either lead oxide is obtained or else the oxide in combination with peroxide.

Lead chloride, PbCl_2 , is precipitated from the soluble salts of lead when a strong solution is treated with hydrochloric acid or metallic chloride. It is soluble in considerable quantities in hot water, and therefore if the solutions be dilute or hot, the precipitation of lead chloride does not occur, and if a hot solution be cooled, the salt separates in brilliant prismatic crystals. It fuses when heated (like silver chloride), but is insoluble in ammonia. This salt is rarely met with in nature, and when heated in air is capable of exchanging half the chlorine for oxygen, forming the basic salt or lead oxychloride,

PbMe_4 , and lead ethyl, PbEt_4 , are volatile compounds, whilst PbO_2 is non-volatile, and is very like silica in this respect, and not in the least like carbonic anhydride. As regards lead oxide, to it should still sooner be ascribed a polymeric structure, Pb_nO_n , all the more as it differs as little from lead dioxide in its physical properties as carbonic oxide does from carbonic anhydride, and as lead oxide is an unsaturated compound there is more likelihood for supposing it to be capable of intercombination (polymerisation) than lead dioxide. These considerations respecting the complexity of lead oxide could have no real meaning, and could not enter into the ranks of recognisable propositions, were it not for the existence of the above-mentioned basic and mixed salts. The oxide evidently corresponds with the composition Pb_nX_{2n} , and as, according to this representation, the number of X's in the salts of lead is considerable, it is obvious that they may be diverse. When a part of these X's is replaced by the water residue (OH) or by oxygen, $\text{X}_2=\text{O}$, and the other parts by an *acid residue*, X, then basic salts are obtained, but if a part of the X's is replaced by acid residues of one kind, and the other part by acid residues of another kind, then those mixed salts, about which we are now speaking, are formed. Thus, for example, we may suppose, for a comparison of the composition of the majority of the salts of lead, that $n=12$, and then the above-mentioned compounds will present themselves in the following form:—Lead oxide, $\text{Pb}_{12}\text{O}_{12}$, its crystalline hydrate, $\text{Pb}_{12}\text{O}_8(\text{OH})_8$, lead chloride, $\text{Pb}_{12}\text{Cl}_{24}$, lead oxychloride, $\text{Pb}_{12}\text{Cl}_{12}\text{O}_6$, the other oxychloride, $\text{Pb}_{12}(\text{OH})_6\text{Cl}_6\text{O}_6$, mendipite (*see* sequel), $\text{Pb}_{12}\text{Cl}_8\text{O}_8$, normal lead carbonate, $\text{Pb}_{12}(\text{CO}_3)_{12}$, crystalline basic salt, $\text{Pb}_{12}(\text{OH})_6(\text{CO}_3)_6$, white lead, $\text{Pb}_{12}(\text{CO}_3)_8(\text{HO})_8$, corneous lead, $\text{Pb}_{12}\text{Cl}_{12}(\text{CO}_3)_6$, lanarkite, $\text{Pb}_{12}(\text{CO}_3)_6(\text{SO}_4)_6$, leadhillite, $\text{Pb}_{12}(\text{CO}_3)_9(\text{SO}_4)_3$, &c. The number 12 here taken is only to avoid fractional quantities. Perhaps the polymerisation is much higher than this.

The conception of the polymerisation of oxides introduced by me in the first edition of this work (1869) is now beginning to be generally accepted. Thus Henry, Carnelley, Walker, and others see one proof of this in the fact that the hydrates of the majority of oxides only lose water little by little, and with difficulty towards the end, and also in the fact that oxides are less fusible and volatile than the corresponding chlorides, whilst oxygen is more difficultly liquefied and converted into a solid form than chlorine.

PbCl_2PbO , which may be obtained by fusing these two substances together. The reaction of lead chloride with water vapour leads to the same conclusion, showing the feeble basic character of lead and its power of entering into double decomposition with water :



When ammonia is added to an aqueous solution of lead chloride a white precipitate is formed, which parts with water on being heated, and has the composition $\text{Pb}(\text{OH})\text{Cl}, \text{PbO}$. This compound is also formed by the action of metallic chlorides on other soluble basic salts of lead.⁵¹

Lead carbonate, or *white lead*, is the most extensively used basic lead salt. It has the valuable property of 'covering,' which only to a certain extent appertains to lead sulphate and other white powdery substances used as pigments. This faculty of 'covering' consists in the fact that a small quantity of white lead mixed with oil spreads uniformly, and if such a mixture be spread over a surface (for instance, of wood or metal) the surface is quickly covered—that is, it does not shine through the thin layer of superposed white lead ; thus, for example, the grain of the wood remains invisible.⁵² White lead, or *basic lead carbonate*, after being dried at 120° , has a composition $\text{Pb}(\text{OH})_2, 2\text{PbCO}_3$.⁵³ It may be obtained by adding a solution of sodium

⁵¹ A similar basic salt having a white colour, and therefore used as a substitute for white lead, is also obtained by mixing a solution of basic lead acetate with a solution of lead chloride. Its formation is expressed by the equation: $2\text{PbX}(\text{OH}), \text{PbO} + \text{PbCl}_2 = 2\text{Pb}(\text{OH})\text{Cl}, \text{PbO} + \text{PbX}_2$. Similar basic compounds of lead are met with in nature—for instance, *mendipite*, PbCl_2PbO , which appears in brilliant yellowish-white masses. The ignition of red lead with sal-ammoniac results in similar polybasic compounds of lead chloride, forming the *Cassel's*, or *mineral yellow* of the composition PbCl_2PbO .

Lead iodide, PbI_2 , is still less soluble than the chloride, and is therefore obtained by mixing potassium iodide with a solution of a lead salt. It separates as a yellow powder, which may be dissolved in boiling water, and on cooling separates in very brilliant crystalline scales of a golden yellow colour. The salts PbBr_2 , PbF_2 , $\text{Pb}(\text{CN})_2$, $\text{Pb}_2\text{Fe}(\text{CN})_6$, are also insoluble in water, and form white precipitates.

⁵² It is remarkable that there exists a kind of peculiar attraction between boiled linseed oil and white lead, as is seen from the following experiments. White lead is triturated in water. Although it is heavier than water, it remains in suspension in it for some time and is thoroughly moistened by it, so that the trituration may be made perfect; boiled linseed oil is then added, and shaken up with it. A mixture of the oil and white lead is then found to settle at the bottom of the vessel. Although the oil is much lighter than the water it does not float on the top, but is retained by the white lead and sinks under the water together with it. There is not, however, any more perfect combination nor even any solution. If the resultant mass be then treated with ether or any other liquid capable of dissolving the oil, it passes into solution and leaves the white lead unaltered.

⁵³ It may be regarded as the type Pb_5X_6 , in which X_4 is replaced by $(\text{CO}_3)_2$, or as a salt corresponding with the normal hydrate of carbonic acid $\text{C}(\text{OH})_4$, in which three-

carbonate to a solution of one of the basic salts of lead—for instance, the basic acetate—and likewise by treating this latter with carbonic acid. For this purpose the solution of basic acetate is poured into the vessel *f*; it is prepared in the vat A, containing litharge, into which the pump P delivers the solution of the acetate, which remains after the action of carbonic anhydride on the basic salt. In A a basic salt is formed having a composition approaching to $\text{Pb}_4(\text{OH})_6(\text{C}_2\text{H}_3\text{O}_2)_2$; carbonic anhydride, 2CO_2 , is passed through this solution and precipitates




FIG. 82.—Manufacture of white lead.

white lead, $\text{Pb}_2(\text{OH})_2(\text{CO}_3)_2$, and normal lead acetate, $\text{Pb}(\text{C}_2\text{H}_3\text{O}_2)_2$, remains in the solution, and is pumped back into the vat A containing lead oxide, where the normal salt is again (on being agitated) converted into the basic salt. This is run into the vessel E, and from thence into *f*. Into the latter carbonic anhydride is delivered from the generator D, from whence the gas is led by the pipe *g* through a series of small pipes which pass the gas through the solution of basic salt; white lead is

quarters of the hydrogen is replaced by lead. This mode of regarding the salt is really applicable in this case, because a salt is also known in which all the hydrogen of this hydrate of carbonic acid is replaced by lead—namely, the salt containing CO_4Pb_2 . This salt is obtained as a white crystalline substance by the action of water and carbonic acid on lead. The normal salt, PbCO_3 , occurs in nature under the name of white lead ore (sp. gr. 6.47), in crystals, isomorphous with aragonite, and is formed by the double decomposition of lead nitrate with sodium carbonate, as a white heavy precipitate. Thus both these salts resemble white lead, but the first-named salt is exclusively used in practice, owing to its being very conveniently prepared, and its being characterised by its great covering capacity, or 'body,' due to the fine grain of this salt.

One of the many methods by which white lead is prepared consists in mixing massicot with acetic acid or sugar of lead, and leaving the mixture exposed to air (and re-mixing from time to time), which contains carbonic acid, which is absorbed from the surface by the basic salt formed. After repeated mixings (with the addition of water), the entire mass is converted into white lead, which is thus obtained very finely divided.

precipitated by the action of the carbonic anhydride upon this solution, and the normal lead acetate remains in solution.

In order to mark the transition from lead oxide, PbO , into lead dioxide, PbO_2 (plumbic anhydride), it is necessary to direct our attention to the intermediate oxide, or *red lead*, Pb_3O_4 .⁵⁴ In the arts it is used in considerable quantities, because it forms a fairly stable yellowish red paint used for colouring the resins (shellac, colophony, &c.) composing sealing wax. And it forms a very good cheap oil paint, used especially for painting metals, more particularly because drying oils—for instance, hemp seed, linseed oils—very quickly dry with red lead and with lead salts. Red lead is prepared by slightly heating massicot, for which purpose two-storied stoves are used. In the lower story the lead is turned into massicot, and in the higher one, having the lower temperature (about 300°), the massicot is transformed into red lead. Frémy and others showed the instability of red lead prepared by various methods, and its decomposition by acids, with formation of lead dioxide, which is insoluble in acids, and a solution of the salts of lead oxide. The artificial production (synthesis) of red lead by double decomposition was most important. For this purpose Frémy mixed alkaline solutions of potassium plumbate, K_2PbO_3 (prepared by dissolving the dioxide in fused potash), with an alkaline solution of lead oxide. In this way a yellow precipitate of minium hydrate is formed, which, when slightly heated, loses water and turns into bright red anhydrous minium, Pb_3O_4 .

Minium is the first and most ordinary means of producing *lead dioxide*, or plumbic anhydride, PbO_2 ,⁵⁵ because when red lead is

⁵⁴ If lead hydroxide be dissolved in potash and sodium hypochlorite be added to the solution, then the oxygen of the latter acts on the dissolved lead oxide, and partially converts it into dioxide, so that the so-called lead sesquioxide is obtained; its empirical formula is Pb_2O_3 . Probably it is nothing but a lead salt—*i.e.*, is referable to the type of dioxide of lead, or its hydroxide, $\text{PbO}(\text{OH})_2$, in which two atoms of hydrogen are replaced by lead, $\text{PbO}(\text{O}_2\text{Pb})$. We find a proof of this in the fact that the brown compound precipitated by the action of dilute acids—for example, nitric—splits up, even at the ordinary temperature, into insoluble lead dioxide and a solution of a lead salt. This compound evolves oxygen when it is heated. It dissolves in hydrochloric acid, forming a yellow liquid, which probably contains compounds of the composition PbCl_2 and PbCl_3 , but even at the ordinary temperature this compound soon loses the excess of chlorine, and then only lead chloride, PbCl_2 , remains. In order to see the relation between red lead and lead sesquioxide, it must be observed that they only differ by an extra quantity of lead oxide—that is, red lead is a basic salt of the preceding compound, and if the compound Pb_2O_3 may be regarded as PbO_3Pb , then red lead should be looked on as $\text{PbO}_3\text{Pb}, \text{PbO}$ —that is, as basic lead plumbate.

⁵⁵ Lead dioxide is often called lead peroxide, but this name leads to error, because PbO_2 does not show the properties of true peroxides, like hydrogen or barium peroxides, but is endowed with acid properties—that is, it is able to form true salts with bases, which true peroxides do not do. Lead dioxide is a normal salt-forming compound of

treated with dilute nitric acid it gives up lead oxide and PbO_2 remains, on which dilute nitric acid does not act. The empirical composition of minium is Pb_3O_4 , and therefore the action of nitric acid on it is expressed by the equation: $\text{Pb}_3\text{O}_4 + 4\text{HNO}_3 = \text{PbO}_2 + 2\text{Pb}(\text{NO}_3)_2 + 2\text{H}_2\text{O}$. This dioxide may be obtained by treating lead hydroxide suspended in water with a stream of chlorine. Here the chlorine takes up the hydrogen from the water, and the oxygen passes over to the lead oxide.⁵⁶ When a strong solution of lead nitrate is decomposed by the electric current, the appearance of crystalline lead dioxide is also observed upon the positive pole; it is also found in nature in the form of a black crystalline substance having a specific gravity of 9.4. When artificially produced it is a fine dark powder, resisting the action of acids, but nevertheless, when treated with strong sulphuric acid, it evolves oxygen and forms lead sulphate, and with hydrochloric acid it evolves chlorine. The oxidising property of lead dioxide naturally

lead, as Bi_2O_5 is for bismuth, CeO_2 for cerium, and TeO_3 for tellurium, &c. They all evolve chlorine when treated with hydrochloric acid, whilst true peroxides form hydrogen peroxide. The true lead peroxide, if it were obtained, would probably have the composition Pb_2O_5 , or, in combination with peroxide of hydrogen, $\text{H}_2\text{Pb}_2\text{O}_7 = \text{H}_2\text{O}_2 + \text{Pb}_2\text{O}_5$, judging from the peroxides corresponding with sulphuric, chromic, and other acids, as we shall afterwards consider.

As a proof of the fact, that the form PbO_2 , or PbX_4 , is the highest normal form of any combination of lead, it is most important to remark, that it might be expected that the action of lead chloride, PbCl_2 , on zinc-ethyl, ZnEt_2 , would result in the formation of zinc chloride, ZnCl_2 , and lead-ethyl, PbEt_2 , but in reality the reaction proceeds otherwise. Half of the lead is set free, and lead tetrethyl, PbEt_4 , is formed as a colourless liquid, boiling at about 200° (Butleroff, Frankland, Buckton, Cahours, and others). The type PbX_4 is not only expressed in PbEt_4 and PbO_2 , but also in PbF_4 , obtained by Brauner.

Frémy obtained saline compounds of lead dioxide with bases. He obtained potassium plumbate in the following manner. Pure lead dioxide is placed in a silver crucible, and a strong solution of pure caustic potash is poured over it. The mixture is heated and small quantities are removed from time to time for testing, which consists in dissolving in a small quantity of water and decomposing the resultant solution with nitric acid. There is a certain moment during the heating when a considerable amount of insoluble lead dioxide is precipitated on the addition of the nitric acid; the solution then contains the salt in question, and the heating must be stopped, and a small amount of water added to dissolve the potassium plumbate formed. On cooling the salt separates in rather large crystals, which have the same composition as the stannate—that is, $\text{PbO}(\text{KO})_2 \cdot 3\text{H}_2\text{O}$. This analogy between lead dioxide and stannic oxide very clearly shows that the placing of lead in the same group as silicon and tin corresponds with the actual properties of this metal.

⁵⁶ According to Carnelley and Walker, the hydrate $(\text{PbO}_2)_3 \cdot \text{H}_2\text{O}$ is then formed; it loses water at 230° . The anhydrous dioxide remains unchanged to 280° , and is then converted into the sesquioxide, Pb_2O_3 , which again loses oxygen at about 400° , and forms red lead, Pb_3O_4 . Red lead also loses oxygen at about 550° , forming lead oxide, PbO , which fuses without change at about 600° , and remains constant as far as the limit of the observations made (about 800°).

The best method for preparing pure lead dioxide consists in mixing a hot solution of lead chloride with a solution of bleaching powder (Ferman).

depends on the facility of its transition into the more stable lead oxide, which is easily understood from the whole history of lead compounds. This oxidising property of the dioxide is particularly striking in the presence of alkalis. Thus under these conditions it transforms chromium oxide into chromic acid, whilst lead chromate, PbCrO_4 , is formed, remaining, however, in solution, on account of its being soluble in caustic alkalis. The oxidising action of lead dioxide on sulphurous anhydride is most striking, as it immediately absorbs it, with formation of lead sulphate. This is accompanied by a change of colour and development of heat, $\text{PbO}_2 + \text{SO}_2 = \text{PbSO}_4$. When triturated with sulphur, lead peroxide causes flashes, because the sulphur burns at the expense of its oxygen.

Amongst the elements of the second and third groups it was observed that there were more basic elements in the even than in the uneven series. It is sufficient to remember calcium, strontium, and barium in the even and magnesium, zinc, and cadmium in the uneven series. In addition to this, as the atomic weight increases, in the same type of oxidation and group, the basic properties increase (the acid properties decrease), which is particularly striking in the even series—for example, in the second group, calcium, strontium, barium. The same also appears in the fourth and all the following groups. In the even series of the fourth group titanium, zirconium, cerium, and thorium are found. All their highest oxides, RO_2 , even the lightest titanate oxide, TiO_2 , have more highly developed basic properties than silica, SiO_2 , and in addition to this the basic properties are more distinctly seen in zirconium dioxide, ZrO_2 , than in titanate oxide, TiO_2 , although the acid property of combining with bases still remains. In the heaviest oxides, cerium dioxide, CeO_2 , and thorium dioxide, ThO_2 , no acid properties are observed. Thorium dioxide, ThO_2 , is purely a basic oxide, like cerium dioxide, CeO_2 . In Chapter XVII. we already pointed out this higher oxide of cerium. As the above-mentioned elements are rather rare in nature, have but little practical application, and do not present any new forms of combination, it is inadvisable to dwell on them in this treatise.

Titanium is found in nature in the form of its anhydride or oxide, TiO_2 , mixed with silicon in many minerals, but the oxide is also found separately (in débris and in seams) in the form of semi-metallic *rutile* (sp. gr. 4.2). Another titanate mineral is found as a mixture in many ores, known as *titanate iron ore* (in the Thuensky mountains of the southern Ural; it is known as *thuenite*), FeTiO_3 . This is a salt of ferrous oxide and titanate anhydride. It crystallises in the rhombohedral system, has a metallic lustre, grey colour, sp. gr. 4.5. The third

mineral in which titanium is found in considerable quantities in nature is *sphene* or *titanite*, $\text{CaTiSiO}_5 = \text{CaO}, \text{SiO}_2, \text{TiO}_2$, sp. gr. 3.5, colour yellow, green, or such like, crystallises in tablets. The fourth, but rare, titanite mineral consists of *perovskite*, calcium titanate, CaTiO_3 ; it forms blackish-grey or brown cubic crystals, sp. gr. 4.02, and occurs in the Ural and other localities. It may be prepared artificially by fusing sphene in an atmosphere of water vapour and carbonic anhydride. At the end of the last century Klaproth showed the distinction between titanite compounds and all others then known.⁵⁷

⁵⁷ The compounds of titanium are generally obtained from rutile; the finely-ground ore is fused with a considerable amount of acid potassium sulphate, until the titanite anhydride, as a feeble base, passes into solution. After cooling, the resultant mass is ground up, dissolved in cold water, and treated with ammonium hydrosulphide; a black precipitate then separates out from the solution. This precipitate contains TiO_2 (as hydrate) and various metallic sulphides—for example, iron sulphide. It is first washed with water, and then with a solution of sulphurous anhydride until it becomes colourless. This is due to the iron sulphide contained in the precipitate, and rendering it black, being converted into dilhionate by the action of the sulphurous acid. The titanite acid left behind is nearly pure. The considerable volatility of titanium chloride may also be taken advantage of in preparing the compounds of titanium from rutile. It is formed by heating a mixture of rutile and charcoal in dry chlorine; the distillate then contains *titanium chloride*, TiCl_4 . It may be easily purified, owing to its having a constant boiling point of 136° . Its specific gravity is 1.76; it is a colourless liquid, which fumes in the air, and is perfectly soluble in water if it be not heated. If the action of titanite chloride on water be accompanied by heat, a large portion of titanite acid separates out from the solution and passes into metatitanite acid. A like decomposition of acid solutions of titanite acid is accomplished whenever they are heated, and especially in the presence of sulphuric acid, just as with metastannic acid, which titanite acid resembles in many respects. On igniting the titanite acid a colourless powder of the anhydride, TiO_2 , is obtained. In this form it is no longer soluble in acids or alkalis, and only fuses in the oxy-hydrogen flame; but, like silica, it dissolves when fused with alkalis and their carbonates. But, as has been already mentioned, it also dissolves when fused with a considerable excess of acid potassium sulphate—that is, it then reacts as a feeble base. This shows the basic character of titanite anhydride; it has at once, although feebly developed, both basic and acid properties. The fused mass, obtained from titanite anhydride and alkali when treated with water, parts with its alkali, and a residue is obtained of a sparingly-soluble poly-titanate, $\text{K}_2\text{TiO}_5, n\text{TiO}_2$. The hydrate, which is precipitated by ammonia from the solutions obtained by the fusion of titanium compounds with acid potassium sulphate, when dried presents an amorphous mass of the composition $\text{Ti}(\text{OH})_4$. But it loses water over sulphuric acids, and gradually passes into a hydrate of the composition $\text{TiO}(\text{OH})_2$, and when heated it parts with a still larger proportion of water; at 100° the hydrate $\text{Ti}_2\text{O}_5(\text{OH})_2$ being obtained, and at 300° the anhydride itself. The higher hydrate, $\text{Ti}(\text{OH})_4$, is soluble in dilute acid, and the solution may be diluted with water; but on boiling the sulphuric acid solution (but not the solution in hydrochloric acid), all the titanite acid separates in a modified form, which is, however, not only insoluble in dilute acids, but even in strong sulphuric acid. This hydrate has the composition $\text{Ti}_2\text{O}_5(\text{OH})_2$, but shows different properties from those of the hydrate of the same composition described above, and therefore we here again encounter a phenomenon of polymerisation similar to that which we saw with stannic acid. This modified hydrate is called *metatitanite acid*. It is most important to note the property of the ordinary gelatinous hydrate (that precipitated from acid solutions by ammonia) of dissolving in acids, all the more as silica does not show

The comparatively rare element *zirconium*, $\text{Zr} = 90$, is very similar to titanium, but shows a more basic character. It is rarer in nature than titanium, and is found principally in a mineral called *zircon*, $\text{ZrSiO}_4 = \text{ZrO}_2 \cdot \text{SiO}_2$, crystallising in square prisms, sp. gr. 4.5. It has considerable hardness and a characteristic brownish-yellow colour, and is occasionally found as transparent crystals, as a precious stone called *hyacinth*.⁵⁴ Metallic zirconium was obtained, by Berzelius and Troost,

this property. In this property a transition apparently appears between the cases of common solution (based on a capacity for unstable combination) and the case of the formation of a hydrosol (the solubility of germanium oxide, GeO_2 , perhaps presents another similar instance). If titanium chloride be added drop by drop to a dilute solution of alcohol and hydrogen peroxide, and then ammonia be added to the resultant solution, there separates out a yellow precipitate of *titanium trioxide*, $\text{TiO}_3 \cdot 3\text{H}_2\text{O} = \text{Ti}(\text{OH})_6$, as Picini, Weller, and Classen showed. This substance evidently belongs to the category of true peroxides, which we shall consider in Chapter XX.

Titanium chloride absorbs ammonia and forms a compound, $\text{TiCl}_4 \cdot 4\text{NH}_3$, as a red-brown powder which attracts moisture from the air, and when ignited forms *titanium nitride*, Ti_3N_4 . Phosphuretted hydrogen, hydrocyanic acid, and many like compounds are also absorbed by titanium chloride, with the evolution of a considerable amount of heat. Thus, for example, a yellow crystalline powder of the composition $\text{TiCl}_4 \cdot 2\text{HCN}$ is obtained by passing dry hydrocyanic acid vapour into cold titanium chloride. Titanium chloride combines in a similar manner with cyanogen chloride, phosphorus pentachloride, and phosphorus oxychloride, forming molecular compounds, for example, $\text{TiCl}_4 \cdot \text{POCl}_3$. This faculty for further combination probably stands in connection, on the one hand, with the capacity of titanium oxide to give polytitanates, $\text{TiO}(\text{MO})_3 \cdot n\text{TiO}_2$; on the other hand, it corresponds with the kindred faculty of stannic chloride for the formation of poly-compounds (Note 14), and lastly it is probably related to the remarkable bearings of titanium towards nitrogen. Metallic titanium, obtained as a grey powder by reducing potassium titanofluoride, K_2TiF_6 , with iron in a charcoal crucible, combines directly with nitrogen at a red heat. If titanic anhydride be ignited in a stream of ammonia, all the oxygen of the titanic oxide is disengaged, and the compound TiN_2 is formed as a dark violet substance having a copper-red lustre. A compound Ti_5N_6 is also known; it is obtained by igniting the compound Ti_3N_4 in a stream of hydrogen, and is of a golden-yellow colour with a metallic lustre. To this order of compounds there also belongs the well-known and chemically historical compound known as *titanium nitrocyanide*; its composition is Ti_5CN_4 . This substance appears as infusible, sometimes well-formed, cubical crystals of sp. gr. 4.3, and having a red copper colour and metallic lustre; it is found in blast furnace slags. It is insoluble in acids, but is acted on by chlorine at a red heat, forming titanium chloride. It was at first regarded as metallic titanium; it is formed in the blast furnaces at the expense of those cyanogen compounds (potassium cyanide and others) which are always present, and at the expense of the titanium compounds which accompany the ores of iron. Wöhler, who investigated this compound, obtained it artificially by heating a mixture of titanic oxide with a small quantity of charcoal, in a stream of nitrogen, and thus proved the direct power for combination between nitrogen and titanium. When fused with caustic potash, all the nitrogen compounds of titanium evolve ammonia and form potassium titanate. Like metals they are able to reduce many oxides—for example, oxides of copper—at a red heat. Among the compounds of titanium, the crystalline compound Al_4Ti is also remarkable. It is obtained by directly dissolving titanium in fused aluminium; its specific gravity is 8.11. The crystals are very stable, and are only soluble in aqua regia and alkalis.

⁵⁴ The formula ZrO was first given to the oxide of zirconium as a base, in this case $\text{Zr} = 45$, whilst the present atomic weight is $\text{Zr} = 90$ —that is, the formula of the oxide is now recognised as being ZrO_2 . The reasons for ascribing this formula to the compounds

by the action of aluminium on potassium zirconofluoride in just the same way as silicon is prepared; it forms a crystalline powder, similar in appearance to graphite and antimony, but having a very considerable hardness, not much lustre, sp. gr. 4.15. In many respects it resembles silicon; it does not fuse when heated, and even oxidises with difficulty, but liberates hydrogen when fused with potash. When fused with silica it liberates silicon; hydrochloric and nitric acids act feebly on it, but aqua regia easily dissolves it. It is distinguished from silicon by the fact that hydrofluoric acid acts on it with great facility, even in the cold and when diluted, whilst on silicon this acid does not act at all.

Berzelius distinguished from zirconium the very similar element *thorium* ($\text{Th}=232$). It is very rarely met with, in *thorite* and

of zirconium are as follows: in the first place, the investigation of the crystalline forms of the zirconofluorides—for example, K_2ZrF_6 , $\text{MgZrF}_6 \cdot 5\text{H}_2\text{O}$ —which proved to be analogous in composition and crystalline form with the corresponding compounds of titanium, tin, and silicon. In the second place, the specific heat of Zr is 0.067, which corresponds with the combining weight 90. The third and most important reason for doubling the combining weight of zirconium was given by Deville's determination of the vapour density of *zirconium chloride*, ZrCl_4 . This substance is obtained by igniting zirconium oxide mixed with charcoal in a stream of dry chlorine, and is a colourless, saline substance which is easily volatile at 440° . Its density referred to air was found to be 8.15, that is 117 in relation to hydrogen, as it should be according to the above-cited molecular formula of this substance. It exhibits, however, in many respects a saline character, and that of an acid chloranhydride, for zirconium oxide itself presents very feebly developed acid properties but clearly marked basic properties. Thus zirconium chloride dissolves in water, and on evaporation the solution only partially disengages hydrochloric acid—like magnesium chloride, for example. Zirconium was discovered and characterised as an individual element by Klaproth.

Pure compounds of zirconium are generally prepared from zircon, which is finely ground, but as it is very hard it is first heated and thrown into cold water, by which means it is disintegrated. Zircon is decomposed or dissolved when fused with acid potassium sulphate, or still more easily when fused with acid potassium fluoride (a double soluble salt, K_2ZrF_6 , is then formed); however, zirconium compounds are generally prepared from the powdered zircon by fusing it together with sodium carbonate and then boiling in water. An insoluble white residue is obtained consisting of a compound of the oxides of sodium and zirconium, which is then treated with hydrochloric acid and the solution evaporated to dryness. The silica is thus converted into an insoluble form, and zirconium chloride obtained in solution. Ammonia precipitates *zirconium hydroxide* from this solution, as a white gelatinous precipitate $\text{ZrO}(\text{OH})_2$. When ignited this hydroxide loses water, and in so doing undergoes a spontaneous recalcination, and leaves a white, insoluble, and exceedingly hard mass of *zirconium oxide*, ZrO_2 , having a specific gravity of 5.4. Owing to its infusibility, zirconium oxide is used as a substitute for lime and magnesia in the Drummond light. This oxide, in contradistinction to titanium oxide, is soluble even after prolonged ignition in strong hot sulphuric acid. The hydroxide is easily soluble in acids. The composition of the salts is ZrX_4 , or ZrOX_2 , or $\text{ZrOX}_2 \cdot \text{ZrO}_2$, just as with those of its analogues. But although zirconium oxide forms salts in the same way with acids, it also gives salts with bases. Thus it liberates carbonic anhydride when fused with sodium carbonate, forming the salts $\text{Zr}(\text{NaO})_4$, $\text{ZrO}(\text{NaO})_2$, &c. However, water destroys these salts and extracts the soda.

orangeite, $\text{ThSiO}_4 \cdot 2\text{H}_2\text{O}$. The latter is isomorphous with zircon (sp. gr. 4.8).⁵⁹

⁵⁹ Thorium has also been found in the form of oxide in certain pyroclorites, euxinites, and other rare minerals containing salts of niobium. The compounds of thorium are prepared by decomposing thorite or orangeite with strong sulphuric acid at its boiling-point; this renders the silica insoluble, and the thorium oxide passes into solution, when the residue is treated with cold water, after having been previously boiled with water (boiling water does not dissolve the oxide of thorium). Lead and other impurities are then separated by passing sulphuretted hydrogen through the solution, and then the thorium hydroxide is precipitated by ammonia. If this hydroxide be dissolved in the smallest possible amount of hydrochloric acid, and oxalic acid be then added, thorium oxalate is obtained as a white precipitate, which is insoluble in an excess of oxalic acid; this reaction is taken advantage of for separating this metal from many others. However, it resembles the cerite metals (Chapter XVII. Note 48) in this and many other respects. The thorium hydroxide is gelatinous; on ignition it leaves an infusible oxide, ThO_2 , which, when fused with borax, gives crystals of the same form as stannic oxide or titanic anhydride; sp. gr., 9.7. But the basic properties are much more developed in thorium oxide than in the preceding oxides, and it does not even disengage carbonic acid when fused with sodium carbonate—that is, it is a much more energetic base than zirconium oxide. Thorium chloride is obtained as a distinctly crystalline sublimate when thorium oxide, mixed with charcoal, is ignited in a stream of dry chlorine. When heated with potassium, thorium chloride gives a metallic powder of thorium having a sp. gr. 11.1. It burns in air, and is but slightly soluble in dilute acids. The atomic weight of thorium was established by Chydenius and Delafontaine on the basis of the isomorphism of the double fluorides.

CHAPTER XIX

PHOSPHORUS AND THE OTHER ELEMENTS OF THE FIFTH GROUP

NITROGEN is the lightest and most widely distributed representative of the elements of the fifth group, which form a higher saline oxide of the form R_2O_5 , and a hydrogen compound of the form RH_3 . Phosphorus, arsenic, bismuth, and antimony belong to the uneven series of this group, and vanadium, niobium, and tantalum to the even series. The latter do not form compounds with hydrogen, like the elements of the even series in general (Chapter XV.) ; whilst phosphorus, arsenic, and antimony, on the other hand, are analogous to nitrogen, even in their property of forming RH_3 . Phosphorus is the most widely distributed of these elements. There is hardly any mineral substance composing the mass of the earth's crust which does not contain some—it may be small—amount of phosphorus compounds in the form of the salts of phosphoric acid. The soil and earthy substances in general usually contain from one to ten parts of phosphoric acid in 10000 parts. This amount, which appears so small, has, however, a very important significance in nature. No plant can attain its natural growth if it be planted in an artificial soil completely free from phosphoric acid. Plants equally require the presence of potash, magnesia, lime, and ferric oxide, among basic, and of carbonic, sulphuric, nitric, and phosphoric anhydrides, among acid, oxides. In order to increase the fertility of a more or less poor soil, the above-named nutritive elements are introduced into it by means of fertilisers. Direct experiment has proved that these substances are inevitably necessary to plants, but that they must be all present simultaneously and in small quantities, and that an excess, like an insufficiency, of one of these elements is necessarily followed by a bad harvest, or the impossibility of a perfect growth, if the sum of all other conditions (light, heat, water, air) is normal. The phosphoric compounds of the soil accumulated by plants pass into the organism of animals, in which these substances are assimilated in many cases in large quantities. Thus

the chief component part of bones is calcium phosphate, $\text{Ca}_3\text{P}_2\text{O}_8$, on which the hardness of bones depends.¹



Phosphorus was first extracted by Brand in 1669, by the ignition of evaporated urine. After the lapse of a century Scheele, who knew of the existence of a more abundant source of phosphorus in bones, pointed out the method which is now employed for the extraction of this element. Calcium phosphate in bones permeates a nitrogenous organic substance, which is called ossein, and forms a gelatin. When bones are treated exclusively for the extraction of phosphorus, neglecting the gelatin, they are burnt, in which case all the ossein is burnt away. When, however, it is desired to preserve the gelatin, the bones are immersed in cold dilute hydrochloric acid, which dissolves the calcium phosphate and leaves the gelatin untouched; calcium chloride and acid calcium phosphate, $\text{CaH}_4(\text{PO}_4)_2$, are then obtained in the solution. When the bones are directly burnt in an open fire, their mineral components only are left, as an ash, containing about 90 per cent. of calcium phosphate, $\text{Ca}_3(\text{PO}_4)_2$, mixed with a small amount of calcium carbonate and other salts. This mass is treated with sulphuric acid, and then the same substance is obtained in the solution as was obtained from the unburnt bones immersed in hydrochloric acid—*i.e.* the

¹ Dry bones contain about one-third of gelatinous matter and about two-thirds of ash, chiefly calcium phosphate.

The salts of phosphoric acid are also found in the mass of the earth as separate minerals; for example, the *apatites* contain this salt in a crystalline form, combined with calcium chloride or fluoride, $\text{CaR}_2, 3\text{Ca}_5(\text{PO}_4)_2$, where $\text{R}=\text{F}$ or Cl , sometimes in a state of isomorphous mixture. This mineral often crystallises in fine hexagonal prisms; sp. gr., 3.17 to 3.22. Vivianite is a hydrated ferrous phosphate, $\text{Fe}_3(\text{PO}_4)_2, 8\text{H}_2\text{O}$. Phosphates of copper are frequently found in copper mines; for example, *tagilite*, $\text{Cu}_5(\text{PO}_4)_2, \text{Cu}(\text{OH})_2, 2\text{H}_2\text{O}$. Lead and aluminium form similar salts. They are nearly all insoluble in water. Sea and other waters always contain a small amount of phosphates. The ash of sea-plants, as well as of land-plants, always contains phosphates. Deposits of calcium phosphate are often met with; they are termed *phosphorites* and *osteolites*, and are composed of the fossil remains of the bones of animals; they are used for manure. Of the same nature are the so-called guano deposits from Baker's Island, and entire strata in Spain, France, and in the Governments of Orloff and Kursk in Russia. It is evident that if a soil destined for cultivation contain very little phosphoric acid, then the fertilisation by means of these minerals will be beneficial, but, naturally, only if the other elements necessary to plants be present in the soil.

Not unfrequently an untrue explanation of the conclusions made by Liebig with respect to the nourishment of plants by the component parts of the soil has led to a fervent and superfluous preaching in favour of manuring with phosphoric compounds. They are indispensable; but at the same time they are best and most economically applied together with other manures, whilst manuring with phosphoric compounds alone is not advantageous, and is therefore only necessary in very few cases—it cannot serve as a universal medicine for agriculture. It is not wise to introduce phosphoric manures in a given locality and under given conditions without making preliminary experiments.

acid calcium phosphate soluble in water, in which reaction naturally the chief part of the sulphuric acid is converted into calcium sulphate :



On evaporating the solution, crystallisable acid calcium phosphate is obtained. The extraction of the phosphorus from this salt consists in *heating it with charcoal to a white heat*. When heated, the acid phosphate, $\text{CaH}_4(\text{PO}_4)_2$, first parts with water, and forms the metaphosphate, $\text{Ca}(\text{PO}_3)_2$, which, for the sake of simplicity, may be looked on, like the acid salt, as composed of pyrophosphate and phosphoric anhydride, $2\text{Ca}(\text{PO}_3)_2 = \text{Ca}_2\text{P}_2\text{O}_7 + \text{P}_2\text{O}_5$. The latter, with charcoal, gives phosphorus and carbonic oxide, $\text{P}_2\text{O}_5 + 5\text{C} = \text{P}_2 + 5\text{CO}$. So that, in reality, a somewhat complicated process takes place here, which, in ultimate products, will be as follows :



After the steam has come over, phosphorus and carbonic oxide distil over from the retort, and calcium pyrophosphate remains behind.²

As phosphorus melts at about 40° , it condenses at the bottom of the receiver in a molten liquid mass, which is cast under water in tubes, and is sold in the form of sticks. This is common or *yellow phosphorus*. It is a transparent, waxy, yellowish substance, which is not brittle, almost insoluble in water, and easily undergoes change in its external appearance and properties, under the action of light, heat, and of various substances. It crystallises (by sublimation or from its solution in carbon bisulphide) in the regular system, and is especially characterised (in contradistinction to the other varieties) by its easy solubility in carbon bisulphide, and also partially in other oily liquids. In this it recalls common sulphur. Its specific gravity is 1.84. It fuses at 44° , and passes into vapour at 290° ; it is easily inflammable, and must therefore be handled with great caution; careless rubbing is enough to cause phosphorus to ignite. Its application in the manufacture of matches is based on this. It emits light in the air owing to its oxidising, and is therefore kept under water (such water is phosphorescent in the dark, like phosphorus itself). It is also very easily oxidised by various oxidising agents, takes up the oxygen from many substances, and enters into direct combination with many metals and with sulphur, chlorine, &c., with development of a considerable amount of heat. It is very poisonous, although not soluble in water.

² By subjecting the pyrophosphate to the action of sulphuric or hydrochloric acid it is possible to obtain a fresh quantity of the acid salt from the residue, and in this manner

Besides this, there is a red variety of phosphorus, which differs considerably from the above. *Red phosphorus*, also called *amorphous phosphorus*, owing to its showing no sign of crystallisation, is partially formed when ordinary phosphorus remains long exposed to the action of light. It is also formed in many reactions; for example, when ordinary phosphorus combines with chlorine, bromine, iodine, or oxygen, a portion of it is converted into red phosphorus. Schrötter, in Vienna, investigated this variety of phosphorus, and pointed out by what methods it may be produced in considerable quantities. Red phosphorus is a powdery red-brown opaque substance of specific gravity 2.14. It does not combine so energetically with oxygen and other substances as yellow phosphorus, and evolves less heat in combining with them.³ Common phosphorus easily oxidises in the air; red phos-

to extract all the phosphorus from the original normal salt $\text{Ca}_5(\text{PO}_4)_2$. It is usual to take burnt bones, but mineral phosphorites, osteolites, and apatites may also be employed as materials for the extraction of phosphorus. Its extraction for the manufacture of

matches is everywhere extending, and in Russia, in the Urals, in the Government of Perm, it has attained such proportions that the district is able to supply other countries with phosphorus. A great many methods have been proposed for facilitating the extraction of phosphorus, but they none of them essentially differ from the usual one, because the problem is dependent on the liberation of phosphoric acid by the action of acids, and on its ultimate reduction by charcoal. Thus the calcium phosphate may be mixed directly with charcoal and quartz (silica), and phosphorus will be liberated on heating the mixture, because the silica displaces the phosphoric anhydride, which gives carbonic oxide and phosphorus with the charcoal. It has also been proposed to pass hydrochloric acid over an incandescent mixture of calcium phosphate and charcoal; the acid then acts just as the silica does, liberating phosphoric anhydride, which is reduced by the charcoal. It is necessary to prevent the access of air in the condensation of the vapours of phosphorus, because they take fire very easily; hence they are condensed under water by causing the gaseous products to pass through a vessel full of water. For this purpose the condenser shown in fig. 83 is usually employed.




FIG. 83.—Preparation of phosphorus. The mixture is calcined in the retort *b*. The vapours of phosphorus pass through *a* into water without coming into contact with air. The phosphorus condenses in the water, and the gases accompanying it escape through *i*.

⁵ The thermochemical determinations for phosphorus and its compounds date from the last century, when Lavoisier and Laplace burnt phosphorus in oxygen in an ice calorimeter. Andrews, Despretz, Favre, and others have studied the same subject. The most accurate and complete data are due to Thomsen. In order to give an idea of the indirect and complex methods by which the figures cited hereafter are obtained, it will be enough to point out that Thomsen employed the following method to determine the heat of combustion of yellow phosphorus. Phosphorus was oxidised in a calorimeter by iodic acid in the presence of water, and a mixture of phosphorous and phosphoric acids was thus formed (was not any hypophosphoric acid formed?—Salzer), and the iodic acid converted into hydriodic acid. It was first necessary to introduce two corrections into the calorimetric result obtained, one for the oxidation of the phosphorous into phosphoric acid, knowing their relative amounts by analysis, and the other for the deoxidation of

phorus does not oxidise at all at the ordinary temperature; hence it does not phosphoresce in the air, and may be very conveniently kept in the form of powder. It does not fuse at 44° . Having been converted into vapour at 290° or 300° , it, when slowly cooled, again passes into the ordinary variety. Red phosphorus is not soluble in carbon bisulphide and other oily liquids, which permits of its being freed from any admixture of the ordinary phosphorus. It is not poisonous. It is used in many cases for which the ordinary phosphorus is unsuitable or dangerous; for example, in the manufacture of matches, which are then no longer poisonous or inflammable by accidental friction, and therefore the red variety has now replaced the ordinary phosphorus.⁴

the iodic acid. The result then obtained expresses the conversion of phosphorous into hydrated phosphoric acid. This must be corrected for the heat of solution of the hydrate in water, and for the heat of combination of the anhydride with water, before we can obtain the heat evolved in the reaction of P_2 with O_5 in the proportion for the formation of P_2O_5 . It is natural that with so complex a method there is a possibility of many small errors, and the resultant figures will only present a certain degree of accuracy after repeated corrections by various methods. Of such a kind are the following figures determined by Thomsen, which we express in thousands of calories:— $P_2 + O_5 = 370$; $P_2 + O_5 + 3H_2O = 400$; $P_2 + O_5 + \text{a mass of water} = 405$. Hence we see that $P_2O_5 + 3H_2O = 80$; $2PH_3O_4 + \text{a mass of water} = 5$. Experiment further showed that crystallised PH_3O_4 , in dissolving in water, evolves 2·7 thousand calories, and fused (39°) PH_3O_4 5·2 thousand calories, hence the heat of fusion of $H_3PO_4 = 2\cdot5$ thousand calories. For phosphorous acid, H_3PO_3 , Thomsen obtained $P_2 + O_5 + 3H_2O = 250$, and the solution of crystallised H_3PO_3 in water $= -0\cdot13$, and of fused $H_3PO_3 = +2\cdot9$. For hypophosphorous acid, H_3PO_2 , the heats of solution are nearly the same ($-0\cdot17$ and $+2\cdot1$), and the heat of formation $P_2 + O + 3H_2O = 75$; hence its conversion into $2H_3PO_5$ evolves 175 thousand calories, and the conversion of $2H_3PO_3$ into $2H_3PO_4 = 150$ thousand calories. For the sake of convenience we will express the combination of chlorine with phosphorus, also according to Thomsen, per 2 atoms of phosphorus, $P_2 + 3Cl_2 = 151$, $P_2 + 5Cl_2 = 210$ thousand calories. In their reaction on a mass of water (with the formation of a solution), $2PCl_3 = 130$, $2PCl_5 = 247$, and $2POCl_3 = 142$ thousand calories.

Besides which we will cite the following data given by various observers: heat of fusion for P (that is, for 31 parts of phosphorus by weight) $-0\cdot15$ thousand calories; the conversion of yellow into red phosphorus for P, from $+19$ to $+27$ thousand calories; $P + H_3 = 4\cdot3$, $HI + PH_3 = 24$, $PH_3 + HBr = 22$ thousand calories.

⁴ At the ordinary temperature ($20^{\circ}C.$) phosphorus is not oxidised by pure oxygen; oxidation only takes place with a slight rise of temperature, or the dilution of the oxygen with other gases (especially nitrogen or hydrogen), or a direct decrease of pressure. Ordinary phosphorus takes fire at a temperature (60°) at which no other known substance will burn. Its application to the manufacture of matches is based on this property. The majority of *phosphorus matches* are composed of common phosphorus mixed with some oxidising substance which easily gives up oxygen, such as lead dioxide, potassium chlorate, nitre, &c. For this purpose common phosphorus is carefully triturated under warm water containing a little gum; lead dioxide, and potassium nitrate are then added to the resultant emulsion, and the match ends, previously coated with sulphur or paraffin, are dipped into this preparation. After this the matches are dipped into a solution of gum and shellac, in order to preserve the phosphorus from the action of the air. When such a match containing particles of yellow phosphorus is rubbed over a rough surface, it becomes (especially at the point of rupture of the brittle gummy coating) slightly heated, and this is sufficient for the phosphorus to take fire and burn at the

This red phosphorus is prepared by heating the ordinary phosphorus at 230° to 270° ; it is evident that this must be done in an atmosphere incapable of supporting combustion—for example, in nitrogen, carbonic anhydride, steam, &c. On a large scale, ordinary phosphorus is placed in closed iron vessels,⁵ fitted with a gas-conducting tube, and immersed in a bath of different proportions of tin and lead, by which means the temperature of 250° necessary for the conversion is easily attained. It is kept at this temperature for some time. The temperature is at first cautiously raised, and the air is thus partially expelled by the heat, and also by the evolution of steam (the phosphorus is damp when put in), whilst the remaining oxygen is also partially absorbed by the phosphorus, so that an atmosphere of nitrogen is produced in the iron vessel. Care must naturally be taken that no more air enters into the apparatus, and this is done by the aid of the gas-conducting tube, the end of which is immersed in mercury or other liquid. Red phosphorus enters into all the reactions proper to the common phosphorus, only with greater difficulty and more slowly;⁶ and, as its vapour tension

expense of the oxygen of the other ingredients. In the so-called safety or Swedish matches (which are not poisonous, and do not take fire from accidental friction) a mixture of red phosphorus and glass is applied to the surface on which the matches are struck, and the matches themselves do not contain any phosphorus at all, but a mixture is taken of antimonious sulphide, Sb_2S_3 (because combustible substances act very well on it) and potassium chlorate (or other oxidising agents). The combustion, when once started by contact with the red phosphorus, proceeds by itself at the expense of the inflammantory and combustible elements contained in the tip of the match. The mixture applied on the match itself must not be liable to take fire from a blow or friction. In order to illustrate the easy inflammability of common (yellow) phosphorus, its solution in carbon bisulphide may be poured over paper; this solvent quickly evaporates, and the free phosphorus spread over a large surface takes fire spontaneously, notwithstanding the cooling effect produced by the evaporation of the bisulphide. The oxidation of phosphorus also proceeds at the expense of many other oxidising substances. Not only those oxidising agents like nitric, chromic, and other similar acids, but even alkalis, act as oxidising agents on phosphorus—that is, the latter acts as a reducing agent. Thus phosphorus is able to de-oxidise many compounds—for example, it reduces copper from its salts. Phosphorus, when heated with sodium carbonate, reduces a portion of the carbon. If phosphorus be placed under water, slightly heated, and a current of oxygen be passed over it, it will burn under the water.

⁵ Phosphorus only acts on iron at a red heat. The iron vessel is furnished with a safety valve.

⁶ The specific heat of the yellow variety is 0.189—that is, greater than that of the red variety, which is 0.170. The sp. gr. of the yellow is 1.84, and of the red prepared at 260° 2.15, and of that prepared at 580° and above (this is 'metallic' phosphorus) = 2.34. At 230° the pressure of the vapour of ordinary phosphorus = 514 millimetres of mercury, and of the red = 0—that is to say, the red phosphorus does not form any vapour at this temperature; at 447° the vapour tension of ordinary phosphorus is at first = 5500 mm., but it gradually diminishes, whilst that of red phosphorus is equal to 1636 mm.

Hittorf, by heating the lower portion of a closed tube containing red phosphorus to 530° and the upper portion to 447° , obtained crystals of the so-called 'metallic' phosphorus at the upper extremity. This gives reason for thinking that the latter is crystallised

(volatility) is less than that of the yellow variety, one is led to think that a polymerisation proceeds in the passage of the yellow into the red modification, just as in the passage of cyanogen into paracyanogen, or of cyanic acid into cyanuric acid (Chapter IX. Vol. I. p. 398).

red phosphorus. But as the vapour tension (according to Hittorf, at 580° the vapour tension of yellow phosphorus = 8040 mm., of red = 6139 mm., and of metallic = 4130 mm.) and their reactions are different, *metallic phosphorus* may be regarded as a distinct variety. It is still less energetic in its chemical reaction than red phosphorus, and it is denser than the two preceding varieties: sp. gr. = 2.34. It does not oxidise in the air; is crystalline, and has a metallic lustre. It is obtained when ordinary phosphorus is heated with lead for several hours at 400° in a closed vessel, from which the air has been exhausted. The resultant mass is then treated with dilute nitric acid, which first dissolves the lead (phosphorus is electro-negative to lead, and does not, therefore, act on the nitric acid at first) and leaves brilliant rhombohedral crystals of phosphorus of a dark violet colour with a slight metallic lustre, which conduct an electric current incomparably better than the yellow variety; this also forms one of the signs of the metallic state of phosphorus.

The researches of Lemoine partially explained the passage of yellow (ordinary) phosphorus into its other varieties. He heated a closed glass globe containing ordinary and red phosphorus, in the vapour of sulphur (440°), and then determined the amount of the red and yellow varieties after various periods of time, by dissolving them in carbon bisulphide. It appeared that after the lapse of a certain time a mixture of definite and equal composition is obtained from both—that is, between the red and yellow varieties a state of equilibrium sets in, like that of dissociation, or that observed in double decompositions. But at the same time, the progress of the transformation appeared to be dependent on the relative quantity of phosphorus taken per given volume of the globe. Neglecting the latter, we will cite as an example the amounts of the red phosphorus transformed into the ordinary, and of the ordinary not converted into red, per 30 grams of red or yellow taken per litre of the capacity of the globe, heated to 440° . When red phosphorus was taken 4.75 grams of yellow phosphorus was formed after two hours, four grams after eight hours, three grams after twenty-four hours, and the last limit remained constant after further heating. When thirty grams of yellow phosphorus was taken, five grams remained unaltered after two hours, four grams after eight hours, and after twenty-four hours and more the same three grams as before. Troost and Hautefeuille showed that liquid phosphorus in general changes more easily into the red than does phosphorus vapour, which, however, is able, although slowly, to deposit red phosphorus.

The question presents itself as to whether phosphorus in a state of vapour is the ordinary or some other variety? Hittorf (1865) gave many data for the solution of this problem, among which there is no doubt that (as experimental figures show) the density of the vapour of phosphorus is always the same, although the vapour tension of the different varieties and their mixtures is very variable. This shows that the different varieties of phosphorus only appear in a liquid and solid state, which indeed expresses itself in the idea of polymerisation. Strictly speaking, the vapour of phosphorus is a particular state of this substance, and the molecular formula P_4 refers only to it, and not to any other definite state of phosphorus. But Raoult's method of solution (Vol. I. p. 90) showed that in a benzene solution the fall of the freezing point indicates a molecule P_4 , perhaps mixed with P_2 , for ordinary phosphorus, judging by the determination of Paterno and Nasini (1888), who for sulphur obtained by this method a molecular weight = S_6 , as follows from the vapour density. Further research in this direction will perhaps show the possibility of finding the molecular weight of red phosphorus, if a means be discovered for dissolving it without converting it into the yellow variety. But as solution corresponds in many respects with evaporation (Chap. I.), and as in evaporation one density is obtained answering to P_4 , it may be that in this case Raoult's method will prove

The vapour of phosphorus is colourless ; its density remains constant between 300° and 1000° (Dumas, 1833 ; Mitscherlich, Deville, and Troost, 1859, and others). The density with respect to air has been determined as from 4.3 to 4.5. Hence, referred to hydrogen, it is $4.4 \times 14.4 = 63$; and it corresponds with a molecular weight 124, or the molecule of phosphorus in a state of vapour contains P_4 . The reader will remember that the molecule of nitrogen contains N_2 , of sulphur S_8 and S_2 , and of oxygen O_2 and O_3 .

The chemical energy of phosphorus in a free state more nearly approaches that of sulphur than nitrogen. Phosphorus is combustible, inflames at 60° ; but having parted with a portion of its energy in the act of combination, in the form of heat, it becomes analogous to nitrogen, so long as there be no question of its reduction back again into phosphorus. Nitric acid is easily reduced to nitrogen, whilst phosphoric acid is very much more difficultly reduced. All the compounds of phosphorus are less volatile than those of nitrogen. Nitric acid, HNO_3 , is easily distilled ; metaphosphoric acid, HPO_3 , is, as is generally said, non-volatile ; triethylamine, $N(C_2H_5)_3$, boils at 90° , and triethylphosphine, $P(C_2H_5)_3$, at 127° .

Phosphorus not only combines easily and directly with oxygen, but also with chlorine, bromine, iodine, sulphur, and with certain metals. So, for instance, when fused with sodium under naphtha, phosphorus gives the compound Na_3P_2 . Zinc, absorbing the vapour of phosphorus, gives the phosphide Zn_3P_2 (sp. gr. 4.76) ; tin, SnP ; copper, Cu_3P ; even platinum combines with phosphorus (PtP_2 , sp. gr. 8.77), and forms a brittle mass. Iron, when combined with even a small quantity of phosphorus, becomes brittle.⁷ Some of these compounds of phosphorus are obtained by the action of phosphorus on the solutions of metallic

to be inapplicable to the accurate solution of the problem. One cannot but hope, however, that in the course of time new methods will be discovered, permitting the attainment of this purpose.

I think it will not be out of place to here turn the reader's attention to the fact that red phosphorus, which we must recognise as polymeric to the yellow, stands nearer to nitrogen, whose molecule is N_2 , in its small inclination towards chemical reactions.

⁷ The metallic compounds of phosphorus possess a great chemical interest, because they show a transition from metallic alloys (for instance, of Sb, As) to the sulphides, halogen salts, and oxides, and on the other hand to the nitrides. Although there are already many fragmentary data on the subject, still the interesting province of the metallic phosphides cannot yet be regarded as in any way generalised. The varied applications (phosphor-iron, phosphor-bronze, &c.), which the phosphides have recently acquired should give a most incentive reason for the complete and detailed study of this subject, which would, in my opinion, help to the explanation of chemical relations beginning with alloys (solutions) and ending with salts and the compounds of hydrogen (hydrides), because the phosphor-metals, as is proved by direct experiment, stand in the same relation to phosphuretted hydrogen as the sulphides do towards sulphuretted hydrogen, or as the metallic chlorides to hydrochloric acid.

salts, and by the ignition of metallic oxides in the vapour of phosphorus, or by heating mixtures of phosphates with charcoal and metals. Phosphides do not exhibit the external properties of salts, which are so clearly seen in the chlorides and still distinctly observable in the sulphides. *The phosphides of the metals* of the alkalis and of the alkaline earths are even immediately and very easily decomposed by water, which is found to be the case with only a very few sulphides, and still more rarely and indistinctly with the chlorides. This is the most remarkable property of the phosphides of the metals of the alkalis and alkaline earths. Take calcium phosphide, for example. Phosphorus is laid in a deep crucible, and covered with a clay plug, over which lime is strewn. At a red heat the vapours of phosphorus combine with the oxygen of the lime and form phosphoric anhydride, which forms a salt with another portion of the lime ; while the liberated calcium combines with the phosphorus and forms calcium phosphide. Its composition is not quite certain ; it may be CaP (corresponding with liquid phosphuretted hydrogen). This substance is remarkable for the following reaction : if we take water—or, better still, a dilute solution of hydrochloric acid—and throw calcium phosphide into it, then bubbles of gas are evolved, which take fire spontaneously in the air and form white rings. This is owing to the fact that the liquid hydrogen phosphide, PH_2 , is first formed ; thus, $\text{CaP} + 2\text{HCl} = \text{CaCl}_2 + \text{PH}_2$, which, owing to its instability, very easily splits up into the solid phosphide, P_2H , and gaseous phosphide, PH_3 ; $5\text{PH}_2 = \text{P}_2\text{H} + 3\text{PH}_3$; the latter corresponds with ammonia. The mixture of the gaseous and liquid phosphides takes fire spontaneously in the air, forming phosphoric acid. The same hydrogen phosphides are formed when water acts on sodium phosphide (P_2Na_3). Hence we see that there are *three compounds of phosphorus with hydrogen* : (1) The first or solid yellow phosphide, P_2H (more probably P_4H_2), is obtained by the action of strong hydrochloric acid on sodium phosphide ; it takes fire when struck or at 175° . (2) The liquid, PH_2 , or, more truly (molecule), P_2H_4 , is a colourless liquid which takes fire spontaneously in the air, boils at 30° , is very unstable, and is easily decomposed (by light, hydrochloric acid) into the two other phosphides of hydrogen. It is prepared by passing the gases evolved by the action of water on calcium phosphide through a freezing mixture.⁸ And, lastly, (3) gaseous hydrogen phosphide, *phosphine*, PH_3 , which is distinguished as being the most stable. It is a colourless gas, which does not take fire in the air. It has an odour of garlic, and is very poisonous.

⁸ The spontaneous inflammability of the hydride PH_2 in air is very remarkable, and it is particularly interesting that its analogues in composition $\text{P}(\text{C}_2\text{H}_5)_2$ (the formula must be doubled) and $\text{Zn}(\text{C}_2\text{H}_5)_2$ also take fire spontaneously in air.

It resembles ammonia in many of its properties. It is easily decomposed by heat, like ammonia, forming phosphorus and hydrogen; but it is very slightly soluble in water, and does not saturate acids, although it forms compounds with some of them which resemble ammonium salts in their form and properties. Among them the compound with *hydriodic acid*, PH_4I , analogous to ammonium iodide, is remarkable. This compound crystallises by sublimation in well-formed cubes, like sal-ammoniac, which it resembles in many respects. However, this compound does not enter into those reactions of double decomposition which are proper to sal-ammoniac, because its saline properties are very feebly developed. Phosphuretted hydrogen also combines, like ammonia, with certain chloranhydrides; but they are decomposed by water, with the evolution of phosphine. Ogier (1880) showed that hydrochloric acid also combines with phosphine under a pressure of 20 atmospheres at $+18^\circ$, and under the ordinary pressure at -35° , forming the crystalline phosphonium chloride, PH_4Cl , corresponding to sal-ammoniac. Hydrobromic acid does the same with greater ease, and hydriodic acid with still greater facility, forming phosphonium iodide, PH_4I .⁹

Phosphuretted hydrogen, phosphine, PH_3 , is generally prepared by the action of caustic potash on phosphorus.¹⁰ Small pieces of phos-


⁹ The periodic law and direct experiment (the molecular weight) show that phosphine is more simple than the solid hydride, just as methane, CH_4 , is more simple than ethane, C_2H_6 , whose empirical composition is CH_5 . The formation of liquid phosphuretted hydrogen may be understood from the law of substitution. The univalent radicle of PH_3 is PH_2 , and if it is combined with H in PH_3 , it replaces H in liquid phosphuretted hydrogen, which thus gives P_2H_4 . This substance corresponds with free amidogen (hydrazine), N_2H_4 (Vol. I. p. 287). Probably P_2H_4 is able to combine with HI, and perhaps also with 2HI , or other molecules—that is, to give a substance corresponding to phosphonium iodide.

Phosphonium iodide, PH_4I , may be prepared, according to Baeyer, in large quantities in the following manner:—100 parts of phosphorus are dissolved in dry carbon bisulphide in a tubulated retort: when the mixture has cooled, 175 parts of iodine are added little by little, and the carbon bisulphide is then distilled off, this being done towards the end of the operation in a current of dry carbonic anhydride at a moderate temperature. The neck of the retort is then connected with a wide glass tube, and the tubulure with a funnel furnished with a stop-cock, and containing 50 parts of water. This water is added drop by drop to the phosphorous iodide, and a violent reaction takes place, with the evolution of hydriodic acid and phosphonium iodide. The latter collects as crystals in the glass tube and the retort itself. It is purified by further distillations; more than 100 parts may be obtained. Baeyer expresses the reaction by the equation $\text{P}_2\text{I} + 2\text{H}_2\text{O} = \text{PH}_4\text{I} + \text{PO}_2$; and the compound PO_2 may be represented as phosphorous phosphoric anhydride: $\text{P}_2\text{O}_5 + \text{P}_2\text{O}_3 = 4\text{PO}_2$. As a better proportion we may take 400 grams of phosphorus, 680 grams of iodine, and 240 grams of water, and express the formation thus:— $18\text{P} + 9\text{I} + 21\text{H}_2\text{O} = 3\text{H}_4\text{P}_2\text{O}_7 + 7\text{PH}_4\text{I} + 2\text{HI}$ (Vol. I. p. 499).

Phosphonium iodide and even phosphine act as reducing agents on the solutions of many metallic salts. Cavazzi showed that with a solution of sulphurous anhydride, phosphine gives sulphur and phosphoric acid.

¹⁰ The air must first be expelled from the flask by hydrogen, or some other gas which

phorus are dropped into a flask containing a strong solution of caustic potash and heated. Potassium hypophosphite, H_2KPO_2 , is then obtained in solution; gaseous phosphuretted hydrogen is evolved:



Liquid phosphuretted hydrogen is also formed, together with the phosphine, so that the gaseous product, on escaping from the water into the air, takes fire spontaneously, forming beautiful white rings of phosphoric acid. In this experiment, like that with calcium phosphide, it is the liquid, P_2H_4 , that takes fire; but the phosphine set light to by it also burns, $\text{PH}_3 + \text{O}_4 = \text{PH}_3\text{O}_4$. The same phosphuretted hydrogen, PH_3 , may be obtained pure, and not spontaneously combustible, by igniting the hydrates of phosphorous acid ($4\text{PH}_3\text{O}_3 = \text{PH}_3 + 3\text{PH}_3\text{O}_4$) and hypophosphorous acid ($2\text{PH}_3\text{O}_2 = \text{PH}_3 + \text{PH}_3\text{O}_4$); or, more simply, by the decomposition of calcium phosphide by hydrochloric acid, because then all the liquid phosphide, P_2H_4 , is decomposed into non-volatile P_2H and gaseous PH_3 .

Pure phosphine liquefies when cooled to -90° , boils at -85° , and solidifies at -135° (Olszewski).

When phosphorus burns in an excess of *dry* oxygen, then only *phosphoric anhydride*, P_2O_5 , is formed. It is prepared by throwing pieces of phosphorus through a wide tube, fixed into the upper neck of

will not support combustion, as otherwise an explosion might take place owing to the spontaneous inflammability of the phosphuretted hydrogen.

The following is another method by which gaseous phosphuretted hydrogen may be easily prepared: a mixture of one part of zinc dust to two parts of red phosphorus is put in an atmosphere of hydrogen or coal gas (it burns in air). Combination takes place, accompanied by a flash, and a green mass of zinc phosphide, Zn_3P_2 , is formed, which gives phosphine with dilute sulphuric acid. The combustion of phosphuretted hydrogen in oxygen also takes place under water when the bubbles of both gases meet, and it is very brilliant. The phosphuretted hydrogen obtained by the action of phosphorus on caustic potash always contains free hydrogen, and often even the greater part of the gas evolved consists of hydrogen.

Pure phosphuretted hydrogen (not containing hydrogen or liquid or solid phosphide) is obtained by the action of a solution of potash on phosphonium iodide: $\text{PH}_4\text{I} + \text{KHO} = \text{PH}_3 + \text{KI} + \text{H}_2\text{O}$ (in just the same way as ammonia is from ammonium chloride). The reaction proceeds easily, and the purity of the gas is seen from the fact that it is entirely absorbed by bleaching powder and is not spontaneously inflammable. The vapours of bromine, nitric acid, &c., cause it to again acquire the property of inflaming in the air; that is, they partially decompose it, forming the liquid hydride, P_2H_4 . Oppenheim shows that when red phosphorus is heated at 200° with hydrochloric acid in a closed tube forms the compound $\text{PCl}_3(\text{H}_3\text{PO}_3)$ together with phosphine.

The analogy between phosphine and ammonia is particularly clearly shown in the hydrocarbon derivatives. Just as the compounds NH_2R , NHR_2 , and NR_3 , where R is CH_3 , and other hydrocarbon radicles, correspond with NH_3 , so also there are exact corresponding compounds answering to PH_3 . The study of these compounds belongs to organic chemistry.

a large glass globe, on to a cup suspended in the centre of the globe. These lumps are set light to by touching them with a hot wire, and the phosphorus burns into P_2O_5 . The dry air necessary for its combustion is forced into the globe through a lateral neck, and the white flakes of phosphoric anhydride formed are carried by the current of air through a second lateral neck into a series of Woulfe's bottles, where they settle as friable white flakes. Phosphoric anhydride may also be formed by passing dry air through a solution of phosphorus in carbon bisulphide. All the materials for the preparation of this substance must be carefully dried, because it *combines* with great eagerness *with water*, at the same time developing a large amount of heat and forming metaphosphoric acid, HPO_3 , from which the water cannot be separated by heat. Phosphoric anhydride is a colourless snow-like substance, which attracts moisture from the air with the utmost avidity. It fuses at a red heat, and then *volatilises*. Its affinity for water is so great that it takes it up from many bodies. Thus it converts sulphuric acid into sulphuric anhydride, and carbohydrates (wood, paper) are carbonised, and give up the elements of water to it when brought into contact with it.

When moist phosphorus slowly oxidises in the air, it not only forms phosphorous and phosphoric acids, but also *hypophosphoric acid*, $H_4P_2O_6$, which when in a dry state easily splits up at 60° into phosphorous and metaphosphoric acids ($H_4P_2O_6 = H_3PO_3 + HPO_3$), but differs from a mixture of these acids in that it forms well-characterised salts, of which the sodium salt, $H_2Na_2P_2O_6$, is but slightly soluble in water (the sodium salts of phosphoric and phosphorous acids are easily soluble), and that it does not act as a reducing agent, like mixtures containing phosphorous acid.¹¹ Thorpe, by oxidising phosphorus in

¹¹ Salzer proved the existence of hypophosphoric acid (it is also called subphosphoric acid), in which many chemists did not believe. Drawe (1888) investigated its salts. It may be obtained in a free state by the following method. The solution of acid produced by the slow oxidation of moist phosphorus is mixed with a solution (25 p.c.) of sodium acetate. A salt, $Na_2H_2P_2O_6 \cdot 6H_2O$, crystallises out on cooling; it is soluble in 45 parts of water, and gives a precipitate of $Pb_2P_2O_6$ with lead salts ($Ag_4P_2O_6$ with salts of silver). The lead salt is decomposed by a current of hydrogen sulphide, when lead sulphide is precipitated, while the solution, evaporated under the receiver of an air-pump, gives crystals of $H_4P_2O_6 \cdot 2H_2O$, which easily loses water and gives $H_4P_2O_6$. The salts, in which the H_4 is replaced by Ni_2 , or $NiNa_2$, or $CdNa_2$, &c., are insoluble in water.

In order to see the relation between phosphoric acid and hypophosphoric acid which does not contain the elements of phosphorous acid (because it does not reduce either gold or mercury from their solutions), but which is nevertheless capable of being oxidised (for example, by potassium permanganate) into phosphoric acid, it is simplest to apply the law of substitution. This clearly indicates the relation between oxalic acid $(COOH)_2$ and carbonic acid, $OH(COOH)$, but the relation between the above acids is exactly the same if we express phosphoric acid as $OH(POO_2H_2)$, because in this case $P_2H_4O_6$, or $(POO_2H_2)_3$, will correspond with it just as oxalic does to carbonic acid. The relation

dry air, observed the formation of a volatile phosphorous oxide, P_2O_4 , giving phosphoric and phosphorous acids with water, but which by its composition is the anhydride of hypophosphoric acid, $P_2O_4 = H_4P_2O_2 - 2H_2O$.

Judging by the common law of the formation of acids (Chapter XV.), the series of phosphorus compounds should include the following *ortho-acids* and their corresponding anhydrides, answering to phosphuretted hydrogen, H_3P :—

H_3PO_4 , phosphoric acid, and	P_2O_5 , anhydride,
H_3PO_3 , phosphorous acid, and	P_2O_3 , anhydride,
H_3PO_2 , hypophosphorous acid, and	P_2O , anhydride. ¹²

The last of these (the analogue of N_2O) is almost unknown, and the second is very little known. Phosphoric anhydride (P_2O_5) with a small quantity of water does not at first give orthophosphoric acid, PH_3O_4 , but a compound $P_2O_5 \cdot H_2O$, or PHO_5 , whose composition corresponds with that of nitric acid; this is *metaphosphoric acid*. Even with an excess of water, combining with phosphoric anhydride, this metaphosphoric acid, and not the ortho-, passes at first into solution. Metaphosphoric acid in solution only passes into orthophosphoric acid when the solution is heated or after the lapse of time.

Orthophosphoric acid¹³ is obtained by oxidising phosphorus with nitric acid until the phosphorus entirely passes into solution and the lower oxides of nitrogen cease to be evolved. The reaction takes place best with dilute nitric acid, and when aided by heat. The resultant solution is evaporated to a syrup. If a weighed quantity of phosphorus

between hyposulphuric or dithionic acid, $(SO_2OH)_2$, and sulphuric acid, $OH(SO_2OH)$, is just the same, as we shall find in the following chapter. Dithionic acid corresponds with the anhydride S_2O_5 , intermediate between SO_2 and SO_3 ; oxalic acid with C_2O_5 , intermediate between CO and CO_2 ; hypophosphoric acid corresponds with the anhydride P_2O_4 , also intermediate between P_2O_3 and P_2O_5 .

¹² Besides the above enumerated hydrates, a compound, PH_3O , should correspond with PH_5 . This hydrate, which is analogous to hydroxylamine, is not known in a free state, but it is known as triethylphosphine oxide, $P(C_2H_5)_3O$, which is obtained by the oxidation of triethylphosphine, $P(C_2H_5)_3$. It must be observed that there may also be lower oxides of phosphorus corresponding with PH_3 , like N_2O and NO , and there are even indications of the formation of such compounds, but the data concerning them cannot be considered as firmly established.

¹³ Phosphoric acid, being a soluble and non-volatile substance, cannot be prepared like hydrochloric and nitric acids by the action of sulphuric acid on the alkali phosphates, although it is partially liberated in the process. For this purpose the salts of barium or lead may be taken, because they give insoluble salts, thus $Ba_3(PO_4)_2 + 3H_2SO_4 = 3BaSO_4 + 2H_3PO_4$. Bone ash contains, besides calcium phosphate, sodium and magnesium phosphates, and fluorides and other salts, so that it cannot directly give a pure phosphoric acid.

(dried in a current of dry carbonic anhydride) be taken, then a crystalline mass of the acid can be obtained by evaporating the solution until it consists only of the quantity¹⁴ of phosphoric acid corresponding with the amount of phosphorus taken (from 31 parts of P, 98 parts of solution). It fuses at $+39^{\circ}$; sp. gr. of the liquid 1.88. Phosphorus pentachloride, PCl_5 , and oxychloride, POCl_3 (see further on), give orthophosphoric acid and hydrochloric acid with water. The two other varieties of phosphoric acid, with which we shall presently become acquainted, give the same ortho-acid when in the presence of acids, with particular ease when boiled and more slowly in the cold. By itself orthophosphoric acid does not pass into the other varieties; it does not oxidise, and therefore forms the limiting and stable form. When heated to 300° , it loses water and passes into pyrophosphoric acid, $2\text{H}_3\text{PO}_4 = \text{H}_2\text{O} + \text{H}_4\text{P}_2\text{O}_7$, whilst at a red heat it loses twice as much water and is converted into metaphosphoric acid, $\text{H}_3\text{PO}_4 = \text{H}_2\text{O} + \text{HPO}_3$. In solution orthophosphoric acid exists as H_3PO_4 , and not as pyro- or meta-phosphoric acids, because the solutions of these latter acids give different reactions: thus orthophosphoric acid does not precipitate albumin, does not give a precipitate with barium chloride, and forms a yellow precipitate of silver orthophosphate, Ag_3PO_4 , with silver nitrate (in the presence of alkalis, but not otherwise); whilst a solution of pyrophosphoric acid, $\text{H}_4\text{P}_2\text{O}_7$, although it does not precipitate albumin or barium chloride, gives a white precipitate of silver pyrophosphate, $\text{Ag}_4\text{P}_2\text{O}_7$, with silver nitrate; and a solution of metaphosphoric acid, HPO_3 , precipitates both albumin and barium chloride, and gives a white precipitate of silver metaphosphate, AgPO_3 , with silver nitrate. These points of distinction were studied by Graham, and are exceedingly instructive. They show that the solution of a substance does not determine the maxima of chemical combination with water, that solutions may contain various degrees of combination with water, and that there is a clear difference between the water serving for solution and that entering into chemical combination. Graham's experiments also showed that the water whose removal or combination determines the conversion of ortho- into meta- and pyro-phosphoric acids differs distinctly from water of crystallisation, for he obtained the salts of ortho-, meta-, and pyrophosphoric acids with water of crystallisation, and they differed in their reactions, like the acids themselves, although their crystals contained water of crystallisation. This water was expelled with greater ease than the water of constitution of the hydrates in question.

¹⁴ If this is not done the orthophosphoric acid, PH_3O_4 , loses a portion of its water, and then, as with an excess of water, it does not crystallise.

Orthophosphoric acid has a pleasant acid taste and a distinctly acid reaction; it is used as a medicine, and is not poisonous (phosphorous acid is poisonous). Alkalis, like sodium, potassium, and ammonium hydroxides, saturate the acid properties of phosphoric acid when taken in the ratio $2\text{NaHO} : \text{H}_3\text{PO}_4$ —that is, when salts of the composition HNa_2PO_4 are formed. When taken in the ratio $\text{NaHO} : \text{H}_3\text{PO}_4$, then a solution having an acid reaction is obtained, and when $3\text{NaHO} : \text{H}_3\text{PO}_4$ —that is, when the salt Na_3PO_4 is formed—an alkaline reaction is obtained. Therefore many chemists (Berzelius) even regarded the salts of composition R_2HPO_4 as normal, and considered phosphoric acid to be bibasic. However, the salt Na_2HPO_4 also shows a feeble alkaline reaction, so that it is impossible to judge the characteristic peculiarities of acids by the reactions on litmus paper, as we already know from many examples. Orthophosphoric acid is tribasic, because it contains three equivalents of hydrogen replaceable by metals, forming salts, such as NaH_2PO_4 , Na_2HPO_4 , and Na_3PO_4 . It is also tribasic, because with silver nitrate its soluble salts always give Ag_3PO_4 ,¹⁵ a salt with three equivalents of silver, and because by double decomposition with barium chloride it forms a salt of the composition $\text{Ba}_3(\text{PO}_4)_2$, and silver and barium hardly ever give basic salts. With the metals of the alkalis, phosphoric acid forms soluble salts, but the normal salts of the metals of the alkaline earths, $\text{R}_3(\text{PO}_4)_2$ and even $\text{R}_2\text{H}_2(\text{PO}_4)_2$, are insoluble in water, but dissolve in feeble acids, like phosphoric and acetic, because they then form soluble acid salts, especially $\text{RH}_4(\text{PO}_4)_2$.¹⁶

¹⁵ Silver orthophosphate, Ag_3PO_4 , is yellow, sp. gr. 7.32, and insoluble in water. When heated it fuses like silver chloride, and if kept fused for some length of time it gives a white pyrophosphate (the decomposition which causes this is not known). It is soluble in aqueous solutions of phosphoric, nitric, and even acetic acids, of ammonia, and many of its salts. If silver nitrate acts on a dimetallic orthophosphate—for instance, Na_2HPO_4 —it still gives Ag_3PO_4 , nitric acid being disengaged: $\text{Na}_2\text{HPO}_4 + 3\text{AgNO}_3 = \text{Ag}_3\text{PO}_4 + 2\text{NaNO}_3 + \text{HNO}_3$. This is due to the property of silver of only giving normal salts by double decompositions in the presence of water. Of which fact the case in question is a proof, for when alcohol is added to silver orthophosphate, Ag_3PO_4 , dissolved in syrupy phosphoric acid, it precipitates a white salt (the alcohol takes up the free phosphoric acid) having the composition Ag_2HPO_4 , which is immediately decomposed by water into the normal salt and phosphoric acid.

¹⁶ The researches of Thomsen showed that in very dilute aqueous solutions the majority of monobasic acids—nitric, acetic, hydrochloric, &c. (but hydrofluoric acid more and hydrocyanic less)— HR evolve the following amounts of heat (in thousands of calories) with caustic soda: $\text{NaHO} + 2\text{HR} = 14$; $\text{NaHO} + \text{HR} = 14$; $2\text{NaHO} + \text{HR} = 14$; that is, if n be a whole number $n\text{NaHO} + \text{HR} = 14$ and $\text{NaHO} + n\text{HR} = 14$. Hence reaction here only takes place between one molecule of NaHO and one molecule of acid, and the remaining quantity of acid or alkali does not enter into the reaction. In the case of bibasic acids, $\text{H}_2\text{R}''$ (sulphuric, dithionic, oxalic, sulphuretted hydrogen, &c.), $\text{NaHO} + 2\text{H}_2\text{R}'' = 14$; $\text{NaHO} + \text{H}_2\text{R}'' = 14$; $2\text{NaHO} + \text{H}_2\text{R}'' = 28$; $n\text{NaHO} + \text{H}_2\text{R}'' = 28$; that is, with an excess of acid ($\text{NaHO} + 2\text{H}_2\text{R}''$) 14 thousand units of heat are developed, and with an excess of alkali 28. When phosphoric acid is taken (but not all tribasic acids—for instance, not citric) the

Phosphoric anhydride, or any of its hydrates, when ignited with an excess of sodium hydroxide, carbonate, &c., forms normal or *trisodium orthophosphate*, Na_3PO_4 , but when a solution of sodium carbonate is decomposed by orthophosphoric acid, the salt Na_2HPO_4 only is formed; and when an excess of sodium chloride is ignited with orthophosphoric acid then hydrochloric acid is evolved, and the acid salt H_2NaPO_4 is alone formed. These facts clearly indicate the small energy of phosphoric acid with respect to the formation of the trimetallic salt, which is seen further from the fact that the salt Na_3PO_4 has an alkaline reaction, decomposes in the presence of water and carbonic acid, forming Na_2HPO_4 , corrodes glass vessels in which it is boiled or evaporated, just like solutions of the alkalis, disengages, like them, ammonia from ammonium chloride, and crystallises from solutions, as $\text{Na}_3\text{PO}_4 \cdot 12\text{H}_2\text{O}$, only in the presence of an excess of alkali. At 15° the crystals of this salt require five parts of water for solution; they fuse at 77° .

Disodium orthophosphate, or common sodium phosphate, Na_2HPO_4 , is more stable both in solution and in the solid state. As it is used in

general character of the phenomenon is similar to the preceding, namely, $\text{NaHO} + 2\text{H}_5\text{PO}_4 = 14.7$; $\text{NaHO} + \text{H}_5\text{PO}_4 = 14.8$; $2\text{NaHO} + \text{H}_5\text{PO}_4 = 27.1$; $3\text{NaHO} + \text{H}_5\text{PO}_4 = 84.0$; $6\text{NaHO} + \text{H}_5\text{PO}_4 = 35.3$; or, in general terms, $\text{NaHO} + n\text{H}_5\text{PO}_4 = 14$ (approximately), and $n\text{NaHO} + \text{H}_5\text{PO}_4 = 35$ and not 42, which shows a peculiarity of phosphoric acid. In the case of energetic acids, when one equivalent (23 grams) of sodium (in the form of hydroxide) replaces one equivalent (1 gram) of hydrogen (with the formation of water and in dilute solutions), 14000 heat units are evolved; and this is true for phosphoric acid when in H_5PO_4 , Na or Na_2 replaces H or H_2 , but when Na_5 replaces H_5 less heat is developed. This will be seen from the following arrangement based on the preceding figures: $\text{H}_5\text{PO}_4 + \text{NaHO} = 14.8$; $\text{NaH}_3\text{PO}_4 + \text{NaHO} = 12.3$; $\text{Na}_2\text{HPO}_4 + \text{NaHO} = 5.9$; with $\text{Na}_3\text{PO}_4 + \text{NaHO}$, a very small amount of heat is evolved, as may be judged from the fact that $\text{Na}_3\text{PO}_4 + 3\text{NaHO} = 1.8$, but still heat is evolved. One must suppose that in acting on phosphoric acid in the presence of a large quantity of water, a certain portion of the sodium hydroxide remains as alkali uncombined with the acid. Hence, on increasing the mass of the alkali, heat is still evolved, and a fresh interchange between Na and H takes place. Hence water shows a decomposing action on the alkali phosphates. When $n\text{H}_5\text{PO}_4$ is mixed with $n\text{NaHO}$ in a dilute solution, $n\text{Na}_5\text{PO}_4$ and $n3\text{H}_2\text{O}$ are not formed, but this reaction only takes place between $(n-m)\text{H}_5\text{PO}_4$ and $(n-m)3\text{NaHO}$, and hence the result will be a mixture of the solutions of $(n-m)\text{Na}_5\text{PO}_4$, $m\text{H}_5\text{PO}_4$ (or more probably of acid salts), $m\text{NaHO}$ and OH_2 , and therefore the solution of Na_3PO_4 has an alkaline reaction. The same decomposing action of water is seen, but to a less extent, with Na_2HPO_4 , as may be judged both from the reactions of this salt and from the amount of heat developed by NaH_2PO_4 with NaHO . Such an explanation is in accordance with many facts concerning the decomposition of salts by water already known to us, and shows that in the presence of a mass of water thermochemical data cannot be the means of discovering the nature of acids, but rather the means for demonstrating the effects of water on salts, if the data obtained by this means be compared with other data relative to the salts. Recent researches made by Berthelot and Louguinine have confirmed the above deductions made by me in the first edition (1871) of this work. Now views of this nature are already somewhat generally accepted, although they are not sufficiently strictly applied in other cases.

medicine and in dyeing, it is prepared in considerable quantities, most frequently from the impure phosphoric acid obtained by the action of sulphuric acid on bone ash. The solution thus formed—which contains, besides phosphoric and sulphuric acids, salts of sodium, calcium, and magnesium—is heated, and sodium carbonate added so long as carbonic anhydride is disengaged. A precipitate is formed containing the insoluble salts of magnesium and calcium, while the solution contains sodium phosphate, Na_2HPO_4 , with a small quantity of other salts, from which it may be easily purified by crystallisation. At the ordinary temperature its solutions, especially in the presence of a small amount of sodium carbonate, give finely-formed inclined prismatic crystals, $\text{Na}_2\text{HPO}_4 \cdot 12\text{H}_2\text{O}$; ¹⁷ when the crystallisation takes place at above 30° they only contain $7\text{H}_2\text{O}$. The former crystals even lose a portion of their water of crystallisation at the ordinary temperature (the salt effloresces), and form the second salt with $7\text{H}_2\text{O}$; whilst under the receiver of an air-pump and over sulphuric acid they also part with this water. When ignited they lose the last molecule of water of constitution, and give sodium pyrophosphate, $\text{Na}_2\text{P}_2\text{O}_7$. The crystals of $\text{Na}_2\text{HPO}_4 \cdot 12\text{H}_2\text{O}$ have a sp. gr. of 1.53, and dissolve in 4.9 parts of water at 16° . The solution has a feeble alkaline reaction, and absorbs carbonic anhydride.

Monosodium orthophosphate, NaH_2PO_4 , crystallises with one equivalent of water; its solution has an acid reaction. At 100° the salt only loses this water of crystallisation, and at 200° to 240° it parts with all its water, forming the metaphosphate NaPO_3 . It is prepared from ordinary sodium phosphate by adding phosphoric acid until the solution does not give a precipitate with barium chloride, and then evaporating and crystallising the solution. The solution of this salt does not absorb carbonic anhydride, and does not give a precipitate with salts of calcium, barium, &c.¹⁸

¹⁷ $\text{Na}_2\text{HPO}_4 \cdot 12\text{H}_2\text{O}$ has a sp. gr. 1.53. Poggiale determined the solubility in 100 parts of water (1) of the anhydrous ortho-salt Na_2HPO_4 , and (2) of the corresponding pyro-salt $\text{Na}_2\text{P}_2\text{O}_7$:—

	0°	20°	40°	80°	100°
I.	1.5	11.1	30.9	81	108
II.	3.2	6.2	13.5	30	40

At temperatures of 20° to 100° the ortho-salt is so very much less soluble that this difference alone already indicates the deeply-seated alteration in constitution which takes place in the passage from the ortho- to the pyro-salts.

¹⁸ The ammonium *orthophosphates* resemble the sodium salts in many respects, but the instability of the di- and tri-metallic salts is seen in them still more clearly than in the sodium salts; thus $(\text{NH}_4)_3\text{PO}_4$, and even $(\text{NH}_4)_2\text{HPO}_4$ lose ammonia in the air (especially when heated, even in solutions); $\text{NH}_4\text{H}_2\text{PO}_4$ alone does not disengage ammonia and has an acid reaction. The crystals of the first salt contain $3\text{H}_2\text{O}$, and are only

As a hydrate, orthophosphoric acid should be expressed, after the fashion of other hydrates, as containing three water residues (hydroxyl

formed in the presence of an excess of ammonia; both the others are anhydrous, and may be obtained like the sodium salts. When ignited these salts leave metaphosphoric acid behind; for example, $(\text{NH}_4)_2\text{HPO}_4 = 2\text{NH}_3 = \text{H}_2\text{O} + \text{HPO}_5$. Ammonia also enters into the composition of many double phosphates. Ammonium sodium orthophosphate, or simply phosphate, $\text{NH}_4\text{NaHPO}_4 \cdot 4\text{H}_2\text{O}$, crystallises in large transparent crystals from a mixture of the solutions of disodium phosphate and ammonium chloride (in which case sodium chloride is obtained in the mother liquid), or, better still, from a solution of monosodium phosphate saturated with ammonia. It is also formed from the phosphates in urine when it ferments. This salt is frequently used in testing metallic compounds by the blow-pipe, because when ignited it leaves a vitreous metaphosphate, NaPO_3 , which, like borax, dissolves metallic oxides, forming characteristic tinted glasses.

When a solution of trisodium phosphate is added to a solution of a magnesium salt it gives a white precipitate of the normal orthophosphate $\text{Mg}_2(\text{PO}_4)_2 \cdot 7\text{H}_2\text{O}$. If the trisodium salt be replaced by the ordinary salt, Na_2HPO_4 , a precipitate is also formed, and $\text{MgHPO}_4 \cdot 7\text{H}_2\text{O}$ is obtained. It might be thought that the normal salt $\text{Mg}_5(\text{PO}_4)_2$ would be precipitated if disodium phosphate was added to ammonia and a salt of magnesium, but in reality *ammonium magnesium orthophosphate*, $\text{MgNH}_4\text{PO}_4 \cdot 6\text{H}_2\text{O}$, is precipitated as a crystalline powder, which loses ammonia and water when ignited, and gives a pyrophosphate, $\text{Mg}_2\text{P}_2\text{O}_7$. This salt occurs in nature as the mineral struvite, and in various products of the changes of animal matter. If we consider that the above salt parts with ammonia with difficulty, and that the corresponding salt of sodium is not formed under the same conditions ($\text{MgNaPO}_4 \cdot 9\text{H}_2\text{O}$ is obtained by the action of magnesia on disodium phosphate), if we turn our attention to the fact that the salts of calcium and barium do not form double salts as easily as magnesium, and if we recollect that the salts of magnesium in general easily form double ammonium salts, then we are led to think that this salt is not really a normal, but an acid salt, corresponding with Na_2HPO_4 , in which Na_2 is replaced by the group NH_4Mg , equivalent to two of sodium.

The common normal *calcium phosphate*, $\text{Ca}_3(\text{PO}_4)_2$, occurs in minerals, in animals, especially in bones, and also probably in plants, although the ash of many portions of plants, as a rule, contains less lime than the formation of the normal salt requires. Thus 100 parts of the ash (from 5000 parts of grain) of rye grain contain 47.5 of phosphoric anhydride and only 2.7 of lime, and even the ash of all the rye (including straw) contains twice as much phosphoric anhydride as lime, and the normal salt contains almost equal weights of these substances. Only the ash of grasses, and especially of clover, and of trees, contain in the majority of cases more lime than is required for the formation of $\text{Ca}_3\text{P}_2\text{O}_8$. This salt, which is insoluble in water, dissolves even in such feeble acids as acetic and sulphurous, and even in water containing carbonic acid. The latter fact is of immense importance in nature, because by its means rain water is able to transfer the calcium phosphates in the soil into solutions which are absorbed by plants. The solubility of the normal salt in acids takes place in virtue of the formation of an acid salt, which is evident from the quantity of acid required for its solution, and more especially from the fact that the acid solutions when evaporated give crystalline scales of the acid calcium phosphate, $\text{CaH}_4(\text{PO}_4)_2$, soluble in water. This solubility of the acid salt forms the basis of the treatment by acids of bones, phosphorites, guano, and other natural products containing the normal salt and employed for fertilising the soil. The perfect decomposition requires at least $2\text{H}_2\text{SO}_4$ to $\text{Ca}_3(\text{PO}_4)_2$, but in reality less is taken, so that only a portion of the normal salt is converted into the acid salt. Hydrochloric acid is sometimes used. (In practice such mixtures are known as *superphosphates*.) Certain experiments, however, show that a careful grinding, the presence of organic, and especially of nitrogenous, substances, and the porous structure of calcium phosphates (for example, as in burnt bones), render the treatment of phosphoric manures by acids superfluous—that is, the crop is not bettered by it.

groups), i.e. as $\text{PO}(\text{OH})_3$. This method of expression indicates that the type PX_3 , seen in PH_3I , is here preserved, with the substitution of X_2 by oxygen and X_3 by three hydroxyl groups. The same type appears in POCl_3 , PCl_5 , PF_5 , &c. And if we recognise phosphoric acid as $\text{PO}(\text{OH})_3$, we should expect to find three anhydrides corresponding with it: (1) $[\text{PO}(\text{OH})_2]_2\text{O}$, in which two of the three hydroxyls are preserved; this is pyrophosphoric acid, $\text{H}_4\text{P}_2\text{O}_7$. (2) $\text{PO}(\text{OH})\text{O}$, where only one hydroxyl is preserved. This is metaphosphoric acid. (3) $(\text{PO})_2\text{O}_3$ or P_2O_5 , that is, perfect phosphoric anhydride. Therefore, *pyro- and meta-phosphoric acids are imperfect anhydrides (or anhydro-acids) of orthophosphoric acid*.¹⁹

Pyrophosphoric acid, $\text{H}_4\text{P}_2\text{O}_7$, is formed by heating orthophosphoric acid to 300° , which then loses water. Its normal salts are formed by igniting the dimetallic salts of orthophosphoric acid of the types HM_2PO_4 . Thus from the disodium salt we obtain sodium pyrophosphate $\text{Na}_4\text{P}_2\text{O}_7$ (it crystallises from water with $10\text{H}_2\text{O}$, is very stable, fuses when heated, has an alkaline reaction, and does not form ortho-salts when its solution is boiled): and from the monosodium salt NaH_2PO_4 the acid salt $\text{Na}_2\text{H}_2\text{P}_2\text{O}_7$ (easily soluble in water) is formed; this has an acid reaction, and when ignited further gives the meta-salt.²⁰

¹⁹ In this sense the ortho-acid itself might be regarded as an anhydro-acid, counting $\text{P}(\text{HO})_3$ as the perfect hydrate, if PH_5 existed; but as in general the normal hydrates correspond with the existing hydrogen compounds with the addition of up to 4 atoms of oxygen, therefore PH_3O_4 is the normal acid, just as SH_2O_4 and ClHO_4 ; but NHO_3 , CH_2O_3 are meta-acids, or higher normal acids (NH_3O_4 and CH_4O_4) with the loss of a molecule of water.

In order to see the relation between the ortho-, pyro-, and meta-phosphoric acids, the first thing to remark is that in them the anhydride P_2O_5 is combined with 3, 2, and 1 molecule of water. But such an empirical relation does not express the entire reality, because the pyrophosphoric acid is not obtained (?) in the conversion of the meta- into the ortho-acid; for instance, when the former is obtained from the anhydride and converted into the ortho-acid by heating its solution. The intimate relation between the ortho- and meta-acids is better expressed by the ordinary formulæ, which show that the ortho-acid, H_3PO_3 , and the meta-acid, HPO_3 , contain one atom of phosphorus, whilst the molecule of the pyro-acid, $\text{H}_4\text{P}_2\text{O}_7$, has two. Still, even this expression of the composition of these acids does not correspond with facts, because all the data, hereafter considered, respecting metaphosphoric acid show (Note 21) that its molecule is much more complex, is polymerised, and contains at least $\text{H}_3\text{P}_3\text{O}_9$; the like cannot be said as to nitric acid. The explanation of the problems which here present themselves can, it seems to me, be only looked for after a detailed study of the phenomena of the polymerisations of mineral substances, and of those complex acids, such as phosphomolybdic, which we shall hereafter (Chapter XXI.) describe. A similar instance is exhibited in the solubility of hydrate of silica (produced by the action of silicon fluoride on water) in fused metaphosphoric acid, with the formation, on cooling, of an octahedral compound (sp. gr. 3.1) containing $\text{SiO}_2\text{P}_2\text{O}_5$.

²⁰ The method of preparation of the acid itself consists in converting the sodium salt, $\text{Na}_4\text{P}_2\text{O}_7$, by double decomposition with water and a salt of lead, into insoluble lead

Metaphosphoric acid, HPO_3 (the analogue of nitric acid), is formed by the ignition of the pyro- and ortho-acids (or, better, of their ammonium salts), as a glassy, hygroscopic, fused mass (glacial phosphoric acid, *acidum phosphoricum glaciæ*), soluble in water and volatilising without decomposition. It is also formed in the first slow action of cold water on the anhydride, but metaphosphoric acid gradually changes into the ortho-acid when its solution is boiled, or when it is kept for any length of time, especially in the presence of acids.²¹

pyrophosphate, $\text{Pb}_2\text{P}_2\text{O}_7$, which is then shaken up in water and decomposed by sulphuretted hydrogen; lead sulphide is thus precipitated, and pyrophosphoric acid remains in solution. This solution cannot be heated, or the pyro-acid will pass into the ortho-, but must be evaporated under the receiver of an air-pump. It concentrates to a syrup and crystallises, and when ignited in this form it loses water, and forms metaphosphoric acid. It resembles orthophosphoric acid in many respects; its salts with the alkalis are also soluble, and the others insoluble in water but soluble in acids. When heated in solution with acid it gives orthophosphoric acid, as well as when fused with an excess of alkali.

I may here remark that Witt heated ammonium chloride with phosphoric acid (hydrochloric acid was evolved), ignited the residue to drive off ammonia, and obtained pyrophosphoric acid in the residue.

²¹ As when using phenolphthalein as an indicator in neutralising by an alkali metaphosphoric acid is monobasic, and orthophosphoric acid is bibasic, it is possible by means of this difference to follow the transition of meta- into ortho-phosphoric acid. Sabatier (1888) carried on an investigation of this nature, and found that the rate of transformation is dependent on the temperature, and is subject to the general laws of the rate of chemical transformations, to whose consideration we shall return in the following chapter.

Metaphosphoric acid has a particular interest in respect to the variations to which its salts are subject. The metaphosphates are formed by the ignition of the acid orthophosphates, MH_2PO_4 , or MNH_4HPO_4 , or of the acid pyrophosphates, $\text{M}_2\text{H}_2\text{P}_2\text{O}_7$, or $\text{M}_2(\text{NH}_4)_2\text{P}_2\text{O}_7$, water and ammonia being given off in the process. The properties of the metaphosphates, which have a similar composition to nitrates—for instance, NaPO_3 , or $\text{Ba}(\text{PO}_3)_2$ —vary according to the duration of the ignition to which the ortho-, or pyrophosphates from which they are prepared have been subjected. When the salts NaH_2PO_4 or $\text{NH}_4\text{NaHPO}_4$ are strongly ignited, a salt NaPO_3 is formed, which deliquesces in the air, and gives a gelatinous precipitate with salts of the alkaline earths. But, as Graham (in 1830–40) and many others, especially Fleitmann and Henneberg (in 1840–50), observed, under other conditions the salts of the same composition acquire other properties. The above chemists recognise five polymeric forms of metaphosphates, $(\text{HPO}_3)_n$, where n varies from 1 to 6. We will mention certain of these varieties, following the nomenclature and researches of Fleitmann.

Monometaphosphoric acid. The salts are distinguished for their insolubility in water; even the salts NaPO_3 , KPO_3 , are insoluble. They are obtained by igniting the monometallic orthophosphates—for example, RH_2PO_4 —up to the temperature at which all water is evolved (316°), but not to fusion. No double salts are known.

Dimetaphosphoric acid, on the contrary, easily forms double salts—for example, KNaP_2O_6 , and also the copper potassium salt, &c. The copper salt is obtained by evaporating a solution of copper oxide in orthophosphoric acid. A blue ortho-salt, CuHRO_4 , first separates from the solution, then a light-blue pyro-salt, $\text{Cu}_2\text{P}_2\text{O}_7$; and above 350° , when metaphosphoric acid itself begins to volatilise, the dimetaphosphate, CuP_2O_6 , is formed. The residue is washed with water, and decomposed with a hot solution of sodium sulphide, and then the sodium salt, $\text{Na}_2\text{P}_2\text{O}_6$, is obtained in solution. This salt, when evaporated with alcohol, gives crystals containing 2 mol. H_2O , which, however, retain their solubility (in 7 parts of water) after the water is driven off at 100° . When fused, these

In order to see the relation between phosphoric acid and the lower acids of phosphorus, it is simplest to imagine the substitution of hydroxyl by hydrogen. Then from orthophosphoric acid, $\text{PO}(\text{OH})_3$, we shall obtain phosphorous acid, $\text{POH}(\text{OH})_2$ and hypophosphorous acid, $\text{POH}(\text{OH})$; and, furthermore, phosphorous acid should be bibasic if orthophosphoric acid was tribasic, and hypophosphorous acid should be monobasic. This conclusion is indeed true, and this shows that all the acids of phosphorus may be referred to one common type PX_5 , whose representatives are PH_3I and PCl_5 .

Phosphorous acid, PH_3O_3 , is generally obtained from phosphorus trichloride, PCl_3 , by the action of water: $\text{PCl}_3 + 3\text{H}_2\text{O} = 3\text{HCl} + \text{PH}_3\text{O}_3$. Both acids formed are soluble in water, but are easily separated, because hydrochloric acid is volatile whilst phosphorous acid volatilises with difficulty, and if a small amount of water be originally taken the hydrochloric acid nearly all passes off directly. Concentrated solutions of phosphorous acid give crystals of H_3PO_3 , which fuse at 70° , attract moisture from the air, and deliquesce when ignited, giving phosphine and phosphoric acid,²² and are oxidised into orthophosphoric acid by

crystals give a deliquescent salt (hexa-metaphosphate). The solution of the salt has a neutral reaction, which only after prolonged boiling becomes acid, owing to the formation of orthophosphate, NaH_2PO_4 . The soluble salts of dimetaphosphoric acid give the insoluble silver salt, $\text{Ag}_2\text{P}_2\text{O}_6$, with silver nitrate, and a precipitate of $\text{BaP}_2\text{O}_6 \cdot 2\text{H}_2\text{O}$ with barium chloride.

Trimetaphosphoric acid is obtained as the sodium salt $\text{Na}_5\text{P}_3\text{O}_9$ when any other metaphosphate of sodium is fused and *slowly* cooled, then dissolved in a slight excess of warm water, and the resultant solution evaporated. The crystals contain 6 mol. H_2O , and dissolve in four parts of water. An acid reaction is only obtained, as with the preceding salt, after prolonged boiling with water. The acid is a true analogue of nitric acid, because *all its metallic salts are soluble*.

Hexametaphosphoric acid. Fleitmann so named the ordinary metaphosphoric acid (glacial) which attracts moisture. The deliquescent sodium salt is obtained, like the trimetaphosphate, only by *rapid* cooling. It is also formed by fusing silver oxide with an excess of phosphoric acid. The sodium salt is soluble in water, and gives viscous, elastic precipitates with salts of Ba, Ca, and Mg.

Jawein and Thillot (1889), who investigated the sodium salts of metaphosphoric acid by Raoult's method, came to the conclusion that the salts of di- and tri-metaphosphoric acid behave in such a manner that their molecule must be represented as non-polymerised NaPO_3 , whilst those of hexametaphosphoric acid behave as $(\text{NaPO}_3)_4$. At all events, the series of salts which Fleitmann and Henneberg regard as monometaphosphates are, in my opinion, most probably the most polymerised, because they are insoluble.

²² Phosphorous acid, when subjected to the action of nascent hydrogen (zinc and sulphuric acid), evolves phosphine, and when boiled with an excess of alkali it evolves hydrogen ($\text{PH}_3\text{O}_3 + 3\text{KHO} = \text{PK}_3\text{O}_4 + 2\text{H}_2\text{O} + \text{H}_2$); owing to its liability to oxidation, it is a reducing agent—for instance, it reduces cupric chloride to cuprous chloride, and precipitates silver from the nitrate and mercury from its salts. According to Amat, phosphorous acid easily gives corresponding salts with NH_3 and 2NH_5 , and forms a pyrophosphorous acid, $\text{P}_2\text{H}_4\text{O}_5$.

These reactions are perhaps connected with the fact that in this acid one atom of hydrogen should be considered as in the same condition as in phosphuretted hydrogen,

many oxidising agents. In its salts only two hydrogen atoms are replaced by metals (Würtz); the salts of the alkaline metals are soluble, and give precipitates with salts of the majority of other metals.

The monobasic *hypophosphorous acid*, PH_3O_2 , gives salts $\text{PH}_2\text{O}_2\text{Na}$, $(\text{PH}_2\text{O}_2)_2\text{Ba}$, &c.; the two remaining atoms of hydrogen (which exist in the same form as in phosphine, PH_3) are not replaceable by metals, and this determines the property of these salts of evolving phosphuretted hydrogen when heated (especially with alkalis). In acting on substances liable to reduction it is this hydrogen which acts, and, for example, *reduces* gold and mercury from the solutions of their salts, or converts cupric into cuprous salts. In all these instances the hypophosphorous acid is converted in phosphoric acid. Under the action of zinc and sulphuric acid it gives phosphine, PH_3 . Nevertheless, neither hypophosphorous acid nor its dry salts absorb oxygen from the air. The salts of hypophosphorous acid are more soluble than those of the preceding acids of phosphorus. Thus the sodium salt PNaH_2O_2 does not give a precipitate with barium chloride, and the salts of calcium, barium, and many other metals are soluble.²³ The hypophosphites are prepared by boiling an alkali with phosphorus so long as phosphuretted hydrogen is evolved. The acid itself is obtained from barium hypophosphite (prepared in the same manner by boiling phosphorus in baryta water), by decomposing its solution with sulphuric acid. By concentration of the solution of hypophosphorous acid (it must not be heated above 130° , at which temperature it decomposes) a syrup is formed which is able to crystallise. In the

which is expressed by the formula $\text{PHO}(\text{OH})_2$, if we represent it as PH_1X , with the substitution of two of the hydrogen atoms by oxygen and of HX by two of hydroxyl. The direct passage of phosphorous chloride into phosphorous acid would, however, indicate that all the three atoms of hydrogen in it occur in the form of hydroxyl, because no difference is known between the three atoms of chlorine in PCl_5 —they all react alike, as a rule. However, Menshutkin, by acting on alcohol, $\text{C}_2\text{H}_5\text{OH}$, with phosphorous chloride, obtained hydrochloric acid and a substance $\text{P}(\text{C}_2\text{H}_5\text{O})\text{Cl}_2$, and from it by the action of bromine he obtained ethyl bromide, $\text{C}_2\text{H}_5\text{Br}$, and a compound PBrOCl_2 , which proves, to a certain extent, the existence of a difference between the three atoms of chlorine in phosphorous chloride.

If we turn our attention to the formation of phosphine by the ignition of phosphorous acid, then we see that $4\text{PH}_3\text{O}_3$ only evolve 3H in the form of PH_3 , and therefore the residue—that is, $3\text{PH}_3\text{O}_4$ —will still contain one hydrogen of the same nature as in phosphine, because in $4\text{PH}_3\text{O}_3$ we should recognise four such hydrogens as in phosphine. We arrive at the same conclusion by examining the decomposition of hypophosphorous acid, $2\text{PH}_3\text{O}_2 = \text{PH}_3 + \text{PH}_3\text{O}_4$. In the two molecules of the monobasic hypophosphorous acid taken, there are only two atoms of hydrogen replaceable by metals, whilst in the molecule of the resultant phosphoric acid there are three. Perhaps relations of this nature determine the relative stability of the di-metallic salts of orthophosphoric acid.

²³ Calcium hypophosphite is used in medicine. According to Cavazzi, a mixture of sodium hypophosphite, NaH_2PO_2 , and sodium nitrate explodes violently.

solid state hypophosphorous acid fuses at $+17^{\circ}$, and has the properties of a clearly-defined acid.

The types PX_4 and PX_5 , which are evident for the hydrogen and oxygen compounds of phosphorus, are most clearly seen in its halogen compounds,²⁴ to the consideration of which we will proceed, fixing our attention more especially on the chlorine compounds, as being the most important from the historical, theoretical, and practical point of view.

Phosphorus burns in chlorine, forming phosphorous chloride, PCl_3 , and with an excess of chlorine, phosphoric chloride, PCl_5 . The oxychloride, $POCl_3$, as the simplest chloranhydride according to the type PX_5 , and also phosphoric chloride, correspond with orthophosphoric acid, $PO(OH)_3$, and phosphorous chloride, PCl_3 , corresponds with phosphorous acid and the type PX_3 . Phosphoric oxychloride, $POCl_3$, is a colourless liquid, boiling at 110° . Phosphorus trichloride is also a colourless liquid, boiling at 73° ,²⁵ whilst phosphoric chloride is a solid

²⁴ Fluorine and bromine give PX_3 and PX_5 like chlorine. With respect to iodine PI_5 is, in a chemical sense, a very unstable substance. *Phosphorus tri-iodide* is easily formed (from yellow or red phosphorus and iodine in the requisite proportions). It is a red crystalline substance, fuses at 55° , is easily decomposed by water, forming phosphorous and hydriodic acids, and when heated it evolves iodine vapours and forms phosphorus di-iodide, PI_2 . This substance may be obtained in the same manner as the preceding by taking a smaller proportion of iodine (8 parts of iodine to 1 part of water, whilst the tri-iodide requires 12.8); it also forms red crystals, which melt at 110° . When decomposed by water it not only gives phosphorous and hydriodic acids, but also phosphine and a yellow substance (a lower oxide of phosphorus). In its composition di-iodide of phosphorus corresponds with liquid phosphuretted hydrogen, PH_2 , and probably its molecular weight is much higher: P_2I_4 or P_5I_6 , &c. As the iodine compounds of phosphorus give hydriodic and phosphorous acids with water, and as both these substances are reducing agents in the presence of water (and hydrates), iodide of phosphorus also acts as a reducing agent.

²⁵ In a liquid state the density of phosphorous chloride at $10^{\circ}=1.597$, and therefore, its molecular volume $=137.5/1.597=86.0$, and that of phosphorus oxychloride is equal to $153.5/1.693=90.7$; hence the addition of oxygen has produced considerable increase in volume, just as in the conversion of sulphur dichloride, SCl_2 , into sulphuryl chloride, $SOCl_2$, the volume varies from 64 to 71. It is the same with the boiling points; phosphorus trichloride boils at 70° , the oxychloride at 100° , sulphur dichloride at 64° , and sulphuryl chloride at 78° —that is, the addition of oxygen raises the boiling points.

The vapour density of phosphorus trichloride and oxychloride corresponds with their formulæ—namely, is equal to half the molecular weight referred to hydrogen. In reality, the observed vapour density of phosphorus trichloride with respect to air $=4.8$ (Cahours)—that is, 69.1 referred to hydrogen, whilst according to its formula it should be 68.7 ; in the case of phosphorus oxychloride, the observed vapour density referred to air $=5.4$ (Würtz), and 5.3 (Cahours at 275°), hence the mean referred to hydrogen $=77$, whilst according to the formula it should be 72.7 . Hence the formulæ of phosphorus trichloride and oxychloride correspond with two volumes, as do those of all whole molecules. But it is not so with phosphorus pentachloride. Cahours showed that the vapour density of phosphorus pentachloride referred to air $=8.65$, to hydrogen $=52.6$, whilst according to the formula PCl_5 it should be $=104.2$. Hence this formula corresponds with four, and not with two, molecules. This shows that the vapour of phosphoric chloride contains two and not one molecule, that in a state of vapour it splits up, like sal-ammoniac (Vol. I.

yellowish substance, infusible but straightway volatilising at about 168° . They are all heavier than water, and form types of the *chloranhydrides* or chlorine compounds of the non-metallic elements whose hydrates are acids, just as NaCl or BaCl_2 are types of the saline metals.

If a piece of phosphorus be dropped into a flask containing chlorine, it burns when touched with a red-hot wire, and combines with the chlorine. If the phosphorus be in excess, then liquid *phosphorus trichloride*, PCl_3 , is always formed, but if the chlorine be in excess then the solid pentachloride is obtained. The trichloride is generally prepared in the following manner. Dry chlorine (passed through a series of Woulfe's bottles containing sulphuric acid) is led into a retort containing sand and phosphorus. The retort is heated, and the phosphorus melts into a liquid, spreads through the sand, and gradually forms the trichloride, which distils over into a receiver, where it condenses. *Phosphoric chloride*, or *phosphorus pentachloride*, PCl_5 , is prepared by passing dry chlorine into a vessel containing phosphorus trichloride (purified by distillation). Phosphorous chloride combines directly with oxygen, but more rapidly with ozone, or with the oxygen of potassium chlorate ($3\text{PCl}_3 + \text{KClO}_3 = 3\text{POCl}_3 + \text{KCl}$), forming *phosphorus oxychloride*, POCl_3 (Brodie). This compound is also formed by the first action of water on phosphoric chloride; for example, if two vessels, one containing phosphoric chloride and the other water, are placed under a bell jar, after a certain time the crystals of the chloride disappear and hydrochloric acid passes into the water. The aqueous vapour acts on the pentachloride, and the following reaction occurs: $\text{PCl}_5 + \text{H}_2\text{O} =$

p. 310, sulphuric acid, &c. The products of disruption must here be phosphorous chloride, PCl_3 , and chlorine, Cl_2 , bodies which easily re-form phosphoric chloride, PCl_5 , at a lower temperature, because the latter may be distilled. This decomposition of phosphoric chloride in its conversion into vapour is confirmed by the fact that the vapour of this almost colourless substance shows the greenish yellow colour proper to chlorine. This dissociation of phosphoric chloride has been considered by some chemists as a sign that phosphorus, like nitrogen, does not give volatile compounds of the type PX_5 , and that such substances are only obtained as unstable molecular compounds which break up when distilled; for example, PH_3HI ; PCl_5Cl_2 , NH_3HCl , &c. However this may be, there are perfectly definite, although perhaps unstable, compounds belonging to the type PX_5 . Furthermore, Würtz in 1870 observed that when mixed with the vapour of phosphorous chloride, the vapour of phosphoric chloride distils (from 160° to 190°) over perfectly colourless, and has a density which is really near to the formula—namely, to 104—and the same density was determined for the pentachloride in an atmosphere of chlorine. Hence at low temperatures and in admixture with one of the products of dissociation, there is no longer that decomposition which occurs at higher temperatures—that is, we here have a case of dissociation proceeding at moderate temperatures.

An important proof in favour of the type PX_5 is exhibited by phosphorus pentafluoride PF_5 , obtained by Thorpe as a colourless gas which only corrodes glass after the lapse of time; it may be kept under mercury, and has a normal density. It is formed when liquid arsenic trifluoride, AsF_3 , is added to phosphoric chloride surrounded by a freezing mixture: $3\text{PCl}_5 + 5\text{AsF}_3 = 3\text{PF}_5 + 5\text{AsCl}_3$.

$\text{POCl}_3 + 2\text{HCl}$, the result being that liquid phosphorus oxychloride is found in one vessel, and a solution of hydrochloric acid in the other. However, an excess of water directly transforms phosphoric chloride into orthophosphoric acid, $\text{PCl}_5 + 4\text{H}_2\text{O} = \text{PH}_3\text{O}_4 + 5\text{HCl}$.²⁶

The above chlorine compounds serve not only as a type of the chloranhydrides, but also as a means for the preparation of other *acid chloranhydrides*. Thus the conversion of acids RHO into chloranhydrides, RCl , is generally accomplished by means of *phosphorus pentachloride*. This fact was discovered by Chancel, and adopted by Gerhardt as an important means for studying organic acids. By this means organic acids, containing, as we know, RCOOH (where R is a hydrocarbon group, and where carboxyl may repeat itself several times by replacing the hydrogen of hydrocarbon compounds), are converted into their chloranhydrides, RCOCl . With water they again form the acid, and resemble the chloranhydrides of mineral acids in their general properties.

As carbonic acid, $\text{CO}(\text{OH})_2$, contains two hydroxyl groups, therefore its perfect chloranhydride, COCl_2 , *carbonic oxychloride*, *carbonyl chloride*, or *phosgene gas*, contains two atoms of chlorine, and differs from the chloranhydrides of organic acids in that in them one atom of chlorine is replaced by the hydrocarbon radicle RCOCl , if R is a monatomic radicle giving a hydrocarbon RH . It is evident, on the one hand, that in RCOCl the hydrogen is replaced by the radicle COCl , which is also able to replace several atoms of hydrogen (for example, $\text{C}_2\text{H}_4(\text{COCl})_2$ corresponds with the bibasic succinic acid); and, on the other hand, that the reactions of the chloranhydrides of organic acids will answer to the reactions of carbonyl chloride, as the reactions of the acids themselves answer to carbonic acid. Carbonyl

²⁶ Phosphorus oxychloride is obtained by the action of phosphoric chloride on hydrates of acids (because alkalis decompose phosphorus oxychloride), according to the equation $\text{PCl}_5 + \text{RHO} = \text{POCl}_3 + \text{RCl} + \text{HCl}$, where RHO is an acid. The reaction only proceeds according to this equation with monobasic acids, but then RCl is volatile, and therefore a mixture is obtained of two volatile substances, the acid chloride and phosphorus oxychloride, which are sometimes difficult to separate; whilst if the hydrate be polybasic the reaction frequently proceeds so that an anhydride is formed: $\text{RH}_2\text{O}_2 + \text{PCl}_5 = \text{RO} + \text{POCl}_3 + 2\text{HCl}$. If the anhydride is non-volatile (like boric), or easily decomposed (like oxalic), then it is easy to obtain pure oxychloride. Thus phosphorus oxychloride is often prepared by acting on boric or oxalic acid with phosphoric chloride. It is also formed when the vapour of phosphoric chloride is passed over phosphoric anhydride, $\text{P}_2\text{O}_3 + 3\text{PCl}_3 = 5\text{POCl}_3$. This forms an excellent example in proof of the fact that the formation of one substance from two does not necessarily show that the resultant compound contains the molecules of these substances in its molecule. But other oxychlorides of phosphorus are also formed by the interaction of phosphoric anhydride and chloride; thus at 200° the chloranhydride, PO_2Cl , or chloranhydride of metaphosphoric acid, is formed.

chloride is obtained directly from dry carbon monoxide and chlorine²⁷ exposed to the action of light, and forms a colourless gas, which easily condenses into a liquid, boiling at $+8^{\circ}$, sp. gr. 1.43, and having the suffocating odour proper to all chloranhydrides. Like all chloranhydrides, it is immediately decomposed by water, forming carbonic anhydride, according to the equation $\text{COCl}_2 + \text{H}_2\text{O} = \text{CO}_2 + 2\text{HCl}$, and thus expresses the type proper to all chloranhydrides of both mineral and organic acids.²⁸

In order to show the general method for the preparation of acid chloranhydrides, we will take that of acetic acid, $\text{CH}_3\cdot\text{COOH}$, as an example. Phosphorus pentachloride is placed in a glass retort, and acetic acid poured over it; hydrochloric acid is then evolved, and the substance distilling over directly after is a very volatile liquid, boiling at 50° , and having all the properties of the chloranhydrides. With water it forms hydrochloric and acetic acids. The reaction here taking place may be explained thus: the substitution of the oxygen taken from the

²⁷ The direct action of the sun's rays, or of magnesium light, is necessary to start the reaction between carbonic oxide and chlorine, but when once started it will proceed rapidly in diffused light. An excess of chlorine (which gives its coloration to the colourless phosgene) aids the completion of the reaction, and may afterwards be removed by metallic antimony. Porous substances, like charcoal, aid the reaction. Phosgene may be prepared by passing a mixture of carbonic anhydride and chlorine over incandescent charcoal. Lead or silver chloride, when heated in a current of carbonic oxide, also partially form phosgene gas. Carbon tetrachloride, CCl_4 , also forms it when heated with carbonic anhydride (at 400°), with phosphoric anhydride (200°), and most easily of all with sulphuric anhydride ($2\text{SO}_2 + \text{CCl}_4 = \text{COCl}_2 + \text{S}_2\text{O}_3\text{Cl}_2$, this is pyrosulphuryl chloride). Chloroform, CHCl_3 , is converted into carbonyl chloride when heated with $\text{SO}_2(\text{OH})\text{Cl}$ (the first chloranhydride of sulphuric acid); $\text{CHCl}_3 + \text{SO}_2\text{HCl} = \text{COCl}_2 + \text{SO}_2 + 2\text{HCl}$ (Dewar), and when oxidised by chromic acid.

Among the reactions of phosgene we may mention the formation of urea (Vol. I. p. 397) with ammonia, and of carbonic oxide when heated with metals.

²⁸ Among the chloranhydrides of the inorganic acids we shall describe some which correspond with sulphuric acid in the following chapter; and here we will mention that when hydrochloric acts on nitric acid (aqua regia, Vol. I. p. 461) there is formed, besides chlorine, the oxychlorides NOCl and NO_2Cl , which may be regarded as chloranhydrides of nitric and nitrous acids (nitrogen chloride, Vol. I. p. 470). The former boils at -5° , the latter at $+5^{\circ}$, the specific gravity of the first at $-12^{\circ} = 1.416$, and at $-18^{\circ} = 1.433$ (Geuther), and of the second $= 1.3$; the first is obtained from nitric oxide and chlorine, the second from nitric peroxide and chlorine, and also by the action of phosphoric chloride on nitric acid. If the gases evolved by aqua regia be passed into cold and strong sulphuric acid, they form crystals of the composition NH_2SO_3 (like chamber crystals), which melt at 86° , and with sodium chloride form acid sodium sulphate and the oxychloride NOCl . This chloranhydride of nitric acid is termed *nitrosyl chloride*.

Cyanogen chloride, CNCl , is the gaseous chloranhydride of cyanic acid; it is formed by the action of chlorine on aqueous mercury cyanide, $\text{Hg}(\text{CN})_2 + 2\text{Cl}_2 = \text{HgCl}_2 + 2\text{CNCl}$. When chlorine acts on cyanic acid, it forms not only this cyanogen chloride, but also polymerides of it—a liquid one, boiling at 18° , and a solid one, boiling at 190° . The latter corresponds with cyanuric acid, and consequently contains $\text{C}_3\text{N}_3\text{Cl}_3$. Details concerning these substances must be looked for in works on organic chemistry.

acetic acid (from its carboxyl) by two atoms of chlorine from the PCl_5 should be as follows: $\text{CH}_3\cdot\text{COOH} + \text{PCl}_5 = \text{CH}_3\cdot\text{COHCl}_2 + \text{POCl}_3$. But the compound $\text{CH}_3\cdot\text{COHCl}_2$ does not exist in a free state (because it would indicate the possibility of the formation of compounds of the type CX_6 , and carbon only gives those of the type CX_4); it therefore splits up into HCl and the chloranhydride $\text{CH}_3\cdot\text{COCl}$. The general scheme for the reaction of phosphorus pentachloride with hydrates ROH is exactly the same as with water; namely, ROH with PCl_5 gives $\text{POCl}_3 + \text{HCl} + \text{RCl}$ —that is a chloranhydride.^{28b}

Containing, as they do, chlorine, which easily reacts with hydrogen, phosphorus pentachloride, trichloride, and oxychloride enter into

^{28b} The same phenomenon takes place in the reaction of phosphorus pentachloride with water, H_2O , and other hydrates, RHO : $\text{R(OH)} + \text{PCl}_5 = \text{RCl} + \text{HCl} + \text{POCl}_3$. This reaction indeed proceeds very easily and cleanly with a number of hydroxides, if they do not react on hydrochloric acid and phosphorus oxychloride, which is the case when they have alkaline properties. When the hydroxide is taken in excess, it not unfrequently happens that the elements of water are taken up: $\text{R(OH)}_2 + \text{PCl}_5 = \text{RO} + 2\text{HCl} + \text{POCl}_3$. The phosphorus pentachloride and the anhydride RO may then be converted into chloranhydride, $\text{RO} + \text{PCl}_5 = \text{RCl}_2 + \text{POCl}_3$ —that is, it aids the substitution of O by Cl_2 . Thus carbonyl chloride, COCl_2 , boron chloride, 2BCl_3 , and succinic chloride, $\text{C}_4\text{H}_4\text{O}_2\text{Cl}_2$, &c., are respectively obtained by the action of phosphoric chloride on carbonic, boric, and succinic anhydrides. Phosphorus pentachloride reacts in a similar manner on the aldehydes, RCHO , forming RCHCl_2 , and on the chloranhydrides themselves—for example, with acetic chloride, $\text{CH}_3\cdot\text{COCl}$ (when heated in a closed tube), it forms a substance having the composition $\text{CH}_3\cdot\text{CCl}_3$. Similar chlorine products are formed together with phosphorus oxychloride, but they are often easily separated from it.

Phosphorus trichloride and oxychloride act in a similar manner to phosphoric chloride. When phosphorus trichloride acts on an acid, then $3\text{RHO} + \text{PCl}_3 = 3\text{RCl} + \text{P(OH)}_3$. If a salt is taken, then by the action of phosphorus oxychloride, a corresponding chloranhydride and salt of orthophosphoric acid are easily formed: $3\text{R(KO)} + \text{POCl}_3 = 3\text{RCl} + \text{PO(KO)}_3$. The chloranhydride RCl is always more volatile than its corresponding acid, and distils over before the hydrate RHO . Thus acetic acid boils at 117° , and its chloranhydride at 50° . Phosphoric and phosphorous acids are very slightly volatile, whilst their chloranhydrides are comparatively easily converted into vapour. The faculty of the chloranhydrides to react at the expense of their own chlorine determines their great importance in chemistry. For instance, suppose we require to know the molecular formula of some hydrate which does not pass into a state of vapour and does not give a chloranhydride with hydrochloric acid—that is, which has not any basic or alkaline properties; we must then endeavour to obtain this chloranhydride by means of phosphoric chloride, and it frequently happens that the corresponding chloranhydride is volatile. The resultant chloranhydride is then converted into vapour, and its composition is determined; and if we know its composition we are able to judge that of its corresponding hydrate. So, for example, from the formula of silicon chloride, SiCl_4 , or of boron chloride, BCl_3 , we can judge the composition of their corresponding hydrates, Si(OH)_4 , B(OH)_3 . Having obtained the chloranhydride RCl or RCl_n , it is possible by its means to obtain many other compounds of the same radicle R according to the equation $\text{MX} + \text{RCl} = \text{MCl} + \text{RX}$. M may be $=\text{H}$, K , Ag , or other metals. * The reaction proceeds thus if M forms a stable compound with chlorine—for example, silver chloride, hydrochloric acid, and R , an unstable substance. Therefore, a chloranhydride is frequently employed for the formation of other compounds of a given radicle; for instance, with ammonia they form amides RNH_2 , and with salts ROK anhydrides R_2O , &c.

reaction with ammonia, and give a series of amide and nitrile compounds of phosphorus. Thus, for example, when ammonia acts on the oxychloride we obtain sal-ammoniac (which is afterwards removed by water) and an orthophosphoric triamide, $\text{PO}(\text{NH}_2)_3$, as a white insoluble powder on which dilute acids and alkalis do not act, but which, when fused with potassium hydroxide, gives potassium phosphate and ammonia like other amides. When ignited, the triamide disengages ammonia and forms the nitrile PON , just as urea, $\text{CO}(\text{NH}_2)_2$, disengages ammonia and forms the nitrile CONH . This nitrile, called *monophosphamide*, PON , naturally corresponds with metaphosphoric acid, namely, with its ammonium salt. $\text{NH}_4\text{PO}_3 - \text{H}_2\text{O} = \text{PO}_2 \cdot \text{NH}_2$, an as yet unknown amide, and $\text{PO}_2 \cdot \text{NH}_2 - \text{H}_2\text{O}$ gives the nitrile PON . This relation is confirmed by the fact that PON , moistened with water, gives metaphosphoric acid when ignited. It is the analogue of nitrous oxide, NON . It is a very stable compound, more so than the preceding.²⁹

²⁹ The reaction of ammonia on phosphorus pentachloride is more complex than the preceding. This is readily understood: to the oxychloride, POCl_3 , there corresponds a hydrate $\text{PO}(\text{OH})_3$, and a salt $\text{PO}(\text{NH}_4\text{O})_3$, and consequently also an amide $\text{PO}(\text{NH}_2)_3$, whilst the pentachloride, PCl_5 , has no corresponding hydrate $\text{P}(\text{OH})_5$, and therefore there is no amide $\text{P}(\text{NH}_2)_5$. The reaction with ammonia will be of two kinds: either instead of 5 mol. NH_3 , only 3 mol. NH_3 or still less acts; *i.e.*, $\text{PCl}_2(\text{NH}_2)_3$, $\text{PCl}_3(\text{NH}_2)_2$, &c., are formed, or else the pentachloride acts like a mixture of chlorine with the trichloride, and then as the result there are obtained the products of the action of chlorine on those amides which are formed from phosphorus trichloride and ammonia. It would appear that both kinds of reaction proceed simultaneously, but both kinds of products are unstable, at all events complex, and in the result there is obtained a mixture containing sal-ammoniac, &c. The products of the first kind should react with water, and we shall obtain, for example, $\text{PCl}_2(\text{NH}_2)_2 + 2\text{H}_2\text{O} = 3\text{HCl}$ and $\text{PO}(\text{HO})(\text{NH}_2)_2$. This substance has not actually been obtained, but the compound $\text{PONH}(\text{NH}_2)$ derived from it by elimination of the elements of water is known, and is termed *diphosphamide*; it is, however, more probable that it is a nitrile than an amide, because amides only contain the group NH_2 . It is a colourless, stable, insoluble powder, which possibly corresponds with pyrophosphoric acid, more especially as when heated it evolves ammonia and gives and leaves phosphoryl nitride, PON —that is, the nitrile of metaphosphoric acid. The amide corresponding with the pyrophosphate $\text{P}_2\text{O}_5(\text{NH}_4\text{O})_4$ should be $\text{P}_2\text{O}_5(\text{NH}_2)_4$, and the nitriles corresponding to the latter would be $\text{P}_2\text{O}_5\text{N}(\text{NH}_2)_3$, $\text{P}_2\text{ON}_2(\text{NH}_2)_2$, and $\text{P}_2\text{N}_3(\text{NH}_2)$. The composition of the first is the same as that of the above diphosphamide. The third pyrophosphoric nitrile has a formula $\text{P}_2\text{N}_4\text{H}_2$, and this is the composition of the body known as *phospham*, PHN_2 . Indeed, phospham has been obtained by heating the products of the action of ammonia on phosphoric chloride, as an insoluble and alkaline powder, which gives ammonia and phosphoric acid when subjected to the action of water. The same substance is obtained by the action of ammonium chloride on phosphoric chloride (PNCl_2 is first formed, and reacts further with ammonia, forming phospham), and by igniting the mass which proceeds from the action of ammonia on phosphorus trichloride. Formerly the composition of phospham was supposed to be PHN_2 , now there is reason to think that its molecular weight is $\text{P}_3\text{H}_3\text{N}_6$ (see later).

The above compounds correspond with normal salts, but nitriles and amides corresponding to acid salts are also possible, and they will be acids. For example, the amide

The most important analogue of phosphorus is *arsenic*, the metallic aspect of which and the general character of its compounds at once recalls the metals. The hydrate of its highest oxide, arsenic acid (ortho-arsenic acid), H_3AsO_4 , is an oxidising agent, and gives up a portion of its oxygen to many other substances; but, nevertheless, it is very like phosphoric acid. Mitscherlich established the conception of isomorphism by comparing the salts of these acids together.³⁰

$\text{PO}(\text{HO})_2(\text{NH}_2)$, and its nitrile, which will be either $\text{PN}(\text{HO})_2$ or $\text{PO}(\text{HO})(\text{NH})$, but at all events of the composition PNH_2O_2 , and having acid properties. The ammonium salt of this *phosphonitrilic acid* (it is called phosphamic acid), $\text{PNH}(\text{NH}_4)\text{O}_2$, is obtained by the action of ammonia on phosphoric anhydride, $\text{P}_2\text{O}_5 + 4\text{NH}_3 = \text{H}_2\text{O} + 2\text{PNH}(\text{NH}_4)\text{O}_2$. A non-crystalline soluble mass is thus formed, which is dissolved in a dilute solution of ammonia and precipitated with barium chloride, and the resultant barium salt is then decomposed with sulphuric acid, and thus a solution of the acid of the above composition is obtained.

It is evident from the theory of the formation of amides and nitriles (Chapter IX.) that very many compounds of this kind can correspond with the acids of phosphorus; but as yet only a few are known. The easy transitions of the ortho-, meta-, and pyrophosphoric acids, by means of the hydrogen of ammonia, into the lower acids, and conversely, tend to complicate the study of this vast class of compounds, and it is rarely that the nature of a product thus obtained can be judged from its composition; and this all the more that instances of isomerism and polymerism, of mixture between water of crystallisation and of constitution, &c., are here possible. Many data are yet wanting in order to be able to form a true judgment as to the composition and structure of such compounds. As the best proof of this we will describe the very interesting and most fully investigated compound of this class, PNCl_2 , called *chlorophosphamide*, or nitrogen chlorophosphorite. It is formed in small quantities when the vapour of phosphoric chloride is passed over ignited sal-ammoniac. It is clear that phosphorous chloride, ammonia, chlorine, and hydrochloric acid are all acting in this case. It might be thought that the formation of PNCl_2 corresponds with the simple reaction $\text{PCl}_5 + \text{NH}_3 = 3\text{HCl} + \text{PNCl}_2$, but in reality the reaction is more complex, as is seen by the properties of the product. The chlorine in it is very stable—quite different from that in phosphoric chloride. Indeed, the resultant substance is not only insoluble in water (but soluble in alcohol and ether), but it is not moistened by it, and distils over, together with steam, without being decomposed. In a free state it easily crystallises in colourless prisms, fuses at 114° , boils at 250° (Gladstone, Wichelhaus), and when fused with potash gives potassium chloride and the amidonitril of phosphoric acid. Judging from its formula and the simplicity of composition and reactions, it might be thought that the molecular weight of this substance would be expressed by the formula PCl_2N , that it corresponds with PON and with PCl_3 (like POCl_3), with the substitution of Cl_2 by N , just as in POCl_3 two of chlorine are replaced by oxygen; but all these approximations are incorrect, because its vapour density (referred to hydrogen—Gladstone, Wichelhaus) = 182—that is, the molecular formula must be three times greater, $\text{P}_3\text{N}_3\text{Cl}_6$. The polymerisation (tripling) is here of exactly the same kind as with the nitriles.

³⁰ It is necessary to remark that although arsenic is so closely analogous to phosphorus (especially in the higher forms of combination, RX_3 and RX_5), at the same time it exhibits a certain resemblance and even isomorphism with the corresponding compounds of sulphur (especially the metallic compounds of the type MAS , corresponding with MS). Thus compounds containing metals, arsenic, and sulphur are very frequently met with in nature. Sometimes the relative amounts of arsenic and sulphur varies, so that an isomorphous substitution between the arsenides and sulphides must be recognised. Besides ordinary pyrites, FeS_2 , iron forms an arsenide, FeAs_2 , and an arsenical

Arsenic occurs *in nature*, not only combined with metals, but also, although rarely, native and also in combination with sulphur in two minerals—one red, *realgar*, As_2S_2 , and the other yellow, *orpiment*, As_2S_3 . Arsenic occurs, but more rarely, in the form of salts of arsenic acid—for instance, the so-called cobalt and nickel blooms, two minerals which are found together with other cobalt ores, are the arsenates of these metals. Arsenic is also found in certain clays (ochres), and has been discovered in small quantities in some mineral springs, but it is in general of rarer occurrence in nature than phosphorus. Arsenic is most frequently extracted from arsenical pyrites, FeSAs , which, when roasted without access of air, evolves the vapour of arsenic, ferrous sulphide being left behind. It is also obtained by heating arsenious anhydride with charcoal, in which case carbonic oxide is evolved. In general, the oxides and other compounds are very easily reduced to metals. Solid *arsenic* is a steel-grey, brittle *metal*, having a bright lustre and scaly structure. Its sp. gr. is 5.7. It is opaque and infusible, but volatilises as a yellow vapour, which on cooling deposits rhombohedral crystals. The vapour density of arsenic is 150 times greater than that of hydrogen—that is, its molecule, like that of phosphorus, contains 4 atoms, As_4 . When heated in the air, arsenic easily oxidises into white arsenious anhydride, As_2O_3 , but even at the ordinary temperature it loses its lustre (becomes dull), owing to the formation of a coating of a lower oxide. The latter appears to be as volatile as arsenious anhydride, and it is probable that it is owing to the presence of this compound that the vapours of arsenious compounds, when heated with charcoal (for example, in the reducing flame of a blow-pipe), have the characteristic smell of garlic, because the vapour of arsenic itself has not this odour.

Arsenic easily combines with bromine and chlorine;³¹ nitric acid

pyrites containing both sulphur and arsenic, which from its composition, FeAsS or $\text{FeS}_2\text{FeAs}_2$, resembles the two preceding.

³¹ Hydrochloric acid dissolves arsenious anhydride in considerable quantities, and this is probably owing to the formation of unstable compounds in which the arsenious anhydride plays the part of a base. A compound called *arsenious oxychloride*, having the composition AsOCl , is even known. It is formed when arsenious anhydride is added little by little to boiling arsenic trichloride, $\text{As}_2\text{O}_3 + \text{AsCl}_3 = 3\text{AsOCl}$. It is a transparent substance, which fumes in air, and combines with water to form a crystalline mass having the composition $\text{As}_2(\text{OH})_4\text{Cl}_2$. When heated it decomposes into arsenious chloride and a fresh oxychloride of a more complex composition, $\text{As}_5\text{O}_5\text{Cl}_2$. Arsenic trichloride, when treated with a small quantity of water, forms the crystalline compound, $\text{As}_2(\text{HO})_4\text{Cl}_2$, mentioned above. These compounds resemble the basic salts of bismuth and aluminium. The existence of these compounds shows that arsenic is of a more metallic or basic character than phosphorus, because phosphorus trichloride does not form such oxychlorides. Nevertheless *arsenic trichloride*, AsCl_3 , resembles phosphorus trichloride in many respects. It is obtained by the direct action of chlorine on arsenic, or by

and aqua regia also oxidise it into the higher oxide, or rather its hydrate, arsenic acid.³² As far as is known, it does not decompose steam, and

distilling a mixture of common salt, sulphuric acid, and arsenious anhydride. The latter mode of preparation already indicates the basic properties of the oxide. Arsenious chloride is a colourless oily liquid, boiling at 180° , and having a sp. gr. of 2.20. It fumes in air like other chloranhydrides, but is much more slowly and feebly decomposed by water than phosphorus trichloride. A considerable quantity of water is required for its perfect decomposition into hydrochloric acid and arsenious anhydride. It forms an excellent example of the transition from true metallic chlorides to true chloranhydrides of the acids. It does not combine with chlorine, so that it does not form a pentachloride, AsCl_5 , like phosphorus. *Arsenic tribromide*, AsBr_3 , is formed as a crystalline substance, fusing at 20° and boiling at 220° , by the direct action of metallic arsenic on a solution of bromine in carbon bisulphide, the latter being then evaporated. The specific gravity of arsenic tribromide is 3.36. Crystalline arsenic tri-iodide, AsI_3 , having a sp. gr. 4.39, may be obtained in a like manner; it may be dissolved in water, and on evaporation separates out from the solution in an anhydrous state—that is, it is not decomposed—and consequently behaves like metallic salts. *Arsenic trifluoride*, AsF_3 , is obtained by heating fluor spar and arsenious anhydride with sulphuric acid. It is a fuming, colourless, and very poisonous liquid, which boils at 63° and has a sp. gr. of 2.73. It is decomposed by water, but the products of decomposition have not yet been investigated. It is very remarkable that fluorine forms a pentafluoride of arsenic also, although this compound has not yet been obtained in a separate state, but only in combination with potassium fluoride. This compound, K_3AsF_6 , is formed as prismatic crystals when potassium arsenate, K_3AsO_4 , is dissolved in hydrofluoric acid.

³² *Arsenic acid*, H_3AsO_4 , corresponding with orthophosphoric acid, is formed by oxidising arsenious anhydride with nitric acid, and evaporating the resultant solution until it attains a sp. gr. of 2.2; on cooling it separates in crystals having the above composition. This hydrate corresponds with the normal salts of arsenic acid; but on dissolving in water (without heating) and cooling a strong solution, crystals containing a greater amount of water, namely, $(\text{AsH}_2\text{O}_4)_2 \cdot \text{H}_2\text{O}$, separate. This water, like water of crystallisation, is very easily expelled at 100° . At 120° crystals having a composition identical with that of pyrophosphoric acid, $\text{As}_2\text{H}_4\text{O}_7$, separate, but water, on dissolving this hydrate with the development of heat, forms a solution in no way differing from a solution of ordinary arsenic acid, so that it is not an independent pyroarsenic acid that is formed. Neither is there any true analogue of metaphosphoric acid, although the compound AsHO_3 is formed at 200° , and on solidifying forms a mass having a pearly lustre and sparingly soluble in cold water; but on coming into contact with warm water it becomes very hot, and gives ordinary ortharsenic acid in solution. Arsenic acid forms three series of salts, which are perfectly analogous to the three series of orthophosphates. Thus the normal salt, K_3AsO_4 , is formed by fusing the other potassium arsenates with potassium carbonate; it is soluble in water, and crystallises in needles, which do not contain water. Di-potassium arsenate, K_2HAsO_4 , is formed in solution by mixing potassium carbonate and arsenic acid until carbonic anhydride ceases to be evolved; it does not crystallise, and has an alkaline reaction; hence it corresponds perfectly with the sodium phosphate. As was mentioned above, arsenic acid itself acts as an oxidising agent; for example, it is used in the manufacture of aniline dyes, for oxidising the aniline, and it is prepared in large quantities for this purpose. When sulphuretted hydrogen is passed through its solution, sulphuric acid and arsenious anhydride are obtained in solution. Arsenic acid is very easily soluble in water, and its solution has an exceedingly acid reaction, and when boiled with hydrochloric acid evolves chlorine, like selenic, chromic, manganic, and certain other higher metallic acids.

Arsenic anhydride, As_2O_5 , is produced when arsenic acid is heated to redness. It must be carefully heated, as at a bright red heat it decomposes into oxygen and arsenious anhydride. Arsenic anhydride is an amorphous substance almost entirely insoluble in

it acts exceedingly slowly on those acids, like hydrochloric, which are not capable of oxidising.

Arseniuretted hydrogen, arsine, AsH₃, resembles phosphuretted hydrogen in many respects. This colourless gas, which liquefies into a mobile liquid at -40° , has a disagreeable garlic-like odour, is only slightly soluble in water, and is exceedingly poisonous. Even in a small quantity it causes great suffering, and if present to any considerable amount in air it even causes death. The other compounds of arsenic are also equally poisonous, with the exception of the insoluble sulphur compound and arsenic acid. Arseniuretted hydrogen, AsH₃, is obtained by the action of water on the alloy of arsenic and sodium, sodium hydroxide and arseniuretted hydrogen being formed. It is also formed by the action of sulphuric acid on the alloy of arsenic and zinc : $\text{Zn}_3\text{As}_2 + 3\text{H}_2\text{SO}_4 = 2\text{AsH}_3 + 3\text{ZnSO}_4$.³³ The oxygen compounds of arsenic are very easily reduced by the action of hydrogen at the moment of its evolution from acids, and the reduced arsenic then combines with the hydrogen; therefore, if a certain amount of an oxygen compound of arsenic be put into an apparatus containing zinc and sulphuric acid (and thus serving for the evolution of hydrogen) then the hydrogen evolved will contain arseniuretted hydrogen. In this case it is diluted with a considerable amount of hydrogen. But its presence in the most minute quantities may be easily recognised from the fact that it is *easily decomposed* by heat into metallic arsenic and hydrogen, and therefore if such impure hydrogen be passed through a moderately-heated tube metallic arsenic will be deposited as a bright layer on the part of the tube which was heated. This reaction is so sensitive that it enables the most minute traces of arsenic to be discovered; hence it is employed in medical jurisprudence, as a test in poisoning cases. It is easy to discover the presence of arsenic in common zinc, copper, sulphuric and hydrochloric acids, &c., by this method. It is evident that in testing for poison by Marsh's apparatus it is necessary to take zinc and sulphuric acid quite free from arsenic. The arsenic deposited in the tube may be driven from one place to another in the current of hydrogen evolved, owing to its volatility. This forms a distinctive feature between arseniuretted and antimonuretted hydrogen, which is decomposed by heat in just the same way as arseniuretted hydrogen.

water, but it attracts moisture from the air, deliquesces, and passes into the acid. Hot water produces this transformation with great ease.

³³ The formation of arseniuretted hydrogen is accompanied by the absorption of 37000 heat units, while phosphine evolves 18000 (Ogier), and ammonia 27000. Sodium (0.6 p.c.) amalgam, with a strong solution of As₂O₃, gives a gas containing 86 vols. of arsenic and 14 vols. of hydrogen (Cavazzi).

If hydrogen contains arseniuretted hydrogen it also gives metallic arsenic when it burns, because in the reducing flame of hydrogen the oxygen attracted combines entirely with the hydrogen and not with the arsenic, so that if a cold object, such as a piece of china, be held in




FIG. 84.—Formation and decomposition of arseniuretted hydrogen. Hydrogen is evolved in the Woulfe's bottle, and when the gas comes off, a solution containing arsenic is poured through the funnel. The presence of AsH_3 is recognised from the deposition of a mirror of arsenic when the gas-conducting tube is heated. If the escaping hydrogen be lighted, and a porcelain dish be held in the flame, then a patch of arsenic is deposited on it. The gas is dried by passing through the tube containing calcium chloride. This apparatus is used for the detection of arsenic by Marsh's test.

the hydrogen flame the arsenic will be deposited upon it as a metallic spot.³⁴

The most common compound of arsenic is the solid and volatile *arsenious anhydride*, As_2O_3 , which corresponds with phosphorous and nitrous anhydrides. This very poisonous, colourless, and sweet-tasting

³⁴ This spot, or the metallic ring which is deposited on the heated tube, may easily be tested as to whether it is really due to arsenic or proceeds from some other substance reduced in the hydrogen flame—for instance, carbon or antimony. The necessity for distinguishing arsenic from antimony is all the more frequently encountered in medical jurisprudence, from the fact that preparations of antimony are very frequently used as medicine, and antimony behaves in the hydrogen apparatus just like arsenic, and therefore in making an investigation for poisoning by arsenic it is easy to mistake it for antimony. The best method to distinguish between the metallic spots of arsenic and antimony is to test them with a solution of sodium hyochlorite, free from chlorine, because this will dissolve arsenic and not antimony. Such a solution is easily obtained by the double decomposition of solutions of sodium carbonate and bleaching powder. A solution of potassium chlorate acts in the same manner, only more slowly. Further particulars must be looked for in analytical works.

Arseniuretted hydrogen, like phosphuretted hydrogen, is only slightly soluble in water, and has no alkaline properties—that is, it does not combine with acids, and acts as a reducing agent. When passed into a solution of silver nitrate it gives a blackish brown precipitate of metallic silver, the arsenic being oxidised. In acting on copper sulphate and similar salts, arseniuretted hydrogen sometimes forms arsenides—*i.e.*, it reduces the metallic salt with its hydrogen, and is itself reduced to arsenic. Sulphuric, and even hydrochloric, acid reduces arseniuretted hydrogen to arsenic, and it is still more easily decomposed by arsenious chloride, and with phosphorous chloride it gives the compound PAS . Arseniuretted hydrogen gives metallic arsenic with an acid solution of arsenious anhydride.

substance is generally known under the name of arsenic, or *white arsenic*. The corresponding hydrate is as yet unknown, although the anhydride is soluble in water; but its solutions, when heated, yield crystals of arsenious anhydride. It is mainly prepared for the dyer, and as a means for poisoning vermin, sometimes in medicine, and also as a means for the preparation of all other compounds of arsenic. It is obtained as a bye product in roasting cobalt and other ores containing arsenic. Arsenical pyrites are sometimes purposely roasted for the extraction of arsenious anhydride. When arsenical ores are burnt in the air the sulphur and arsenic are converted into the oxides As_2O_3 and SO_2 . The former is a solid at the ordinary temperature, and the latter gaseous, and therefore the arsenious anhydride is deposited as a sublimate in the cooler portion of the flues through which the vapours escape from the furnace. It collects in condensing chambers especially constructed in the flues. The deposit is collected, and after being distilled gives arsenious anhydride in the form of a vitreous non-crystalline mass. This is one of the varieties of arsenious anhydride, which is also known in two crystalline forms. When sublimed—*i.e.*, when it rapidly passes from the state of vapour to the solid state—it appears in the regular system in the form of octahedra.³⁵ It is obtained in the same form when it is crystallised from acid solutions. The sp. gr. of the crystals is 3.7. The other crystalline form (in prisms) belongs to the rhombohedral system, and is also formed by sublimation, when the crystals are deposited on a heated surface, or when it is crystallised from alkaline solutions.³⁶

³⁵ According to Mitscherlich's determination, the vapour density of arsenious anhydride is 199($\text{H}=1$)—that is, it answers to the molecular formula As_4O_6 . Probably this is connected with the fact that the molecule of free arsenic contains As_4 . Meyer and Biltz, however, showed (1889) that at a temperature of about 1700° the vapour density of arsenic corresponds with the molecule As_2 , and not As_4 , as at lower temperatures.

³⁶ Arsenious anhydride is obtained in an amorphous form after prolonged heating at a temperature near to that at which it volatilises, or, still better, by heating it in a closed vessel. It then fuses to a colourless liquid, which on cooling forms a transparent vitreous mass, whose specific gravity is almost the same as that of the crystalline anhydride (slightly less). On cooling, this vitreous mass undergoes an internal variation, in which it crystallises and becomes opaque, and acquires the appearance of porcelain. The following difference between the vitreous and opaque varieties is very remarkable: when the vitreous variety is dissolved in strong and hot hydrochloric acid it gives crystals of the anhydride on cooling, and this is accompanied by the emission of light (which is visible in the dark), and the entire liquid glows as the crystals begin to separate. The opaque variety does not emit light when the crystals separate from its hydrochloric acid solution. It is also remarkable that the vitreous variety passes into the opaque form when it is pounded—that is, under the action of a series of blows. Thus, several varieties of arsenious anhydride are known, but as yet they are not characterised by any special chemical distinctions, and even differ but little in their specific gravities, and therefore it cannot be said that the above differences are due to any isomeric transformations—that

Solutions of arsenious anhydride have a sweet metallic taste, and give a *feeble acid reaction*. Its solubility increases with the admixture of acids and alkalis. This shows the property of arsenious anhydride of forming salts with acids and alkalis. And, in fact, compounds of it with hydrochloric acid and with the alkali oxides are known.³⁷ If silver nitrate be added to a solution of arsenious anhydride, it does not give any precipitate unless a certain amount of the arsenious anhydride is saturated with an alkali—for instance, ammonia. It then gives a precipitate of silver arsenite, Ag_3AsO_3 . This is yellow, soluble in an excess of ammonia, and anhydrous; it distinctly shows that arsenious acid is tribasic, and that it differs in this respect from phosphorous acid, in which only two atoms of hydrogen can be replaced by metals.³⁸ The feeble acid character of arsenious anhydride is

is, to a replacement of the atoms in the molecule—but probably only depend on a difference in the distribution of the molecules, or, in other terms, are physical and not chemical variations. One part of the vitreous anhydride requires twelve parts of boiling water for its solution, or twenty-five parts at the ordinary temperature. The opaque variety is less soluble, and at the ordinary temperature requires about seventy parts of water for its solution.

³⁷ Arsenious anhydride does not oxidise in air, either in a dry state or in solution, but in the presence of alkalis it absorbs oxygen from the air, and acts as an excellent reducing agent. This probably is connected with the fact that arsenic acid is much more energetic than arsenious acid, and that it is arsenic acid which is formed by the oxidation of the latter in the presence of alkalis. Arsenious anhydride is easily reduced to arsenic by many metals, even by copper.

³⁸ The feeble acid properties of arsenious anhydride are seen from the fact that if it be dissolved in ammonia water, and then a still stronger solution of ammonia be added, prismatic crystals separate, having the composition of ammonium metarsenite, NH_4AsO_5 . This ammonium salt deliquesces in air, and loses all its ammonia. The magnesium salt is tri-metallic, $\text{Mg}_3(\text{AsO}_5)_2$; it is insoluble in water, and is formed by mixing an ammoniacal solution of arsenious anhydride with an ammonical solution of a magnesium salt. It is insoluble even in ammonia, although it dissolves in an excess of acids. Magnesium hydroxide gives the same salt with arsenious solutions, and hence magnesia is one of the best antidotes against arsenic poisoning. *The arsenites of copper* are much used in the manufacture of dyes, and more especially of pigments. They are distinguished by their insolubility in water and by their remarkably vivid green colour, but at the same time by their poisonous character. Not only do such pigments applied to wall papers or materials easily dust off from them, but they give exhalations containing arsenic. The cupric salts, CuX_2 , when mixed with an alkaline solution of arsenious acid, give a green precipitate of a copper salt called *Scheele's green*. Its composition is probably CuHAsO_5 . Ammonia dissolves it, and gives a colourless solution, containing cuprous arsenate—that is, the cupric compound is reduced and the arsenic subjected to a further oxidation. The so-called *Schweinfurt green* was still more used, especially in former times; it is also an insoluble green cupric salt, which resembles the preceding in many respects, but has a different tint. It is prepared by mixing boiling solutions of arsenious acid and cupric acetate. Arsenious acid forms an insoluble compound with ferric hydroxide, resembling the phosphate; and this is the reason why freshly-precipitated oxide of iron is employed as an *antidote for arsenic*. The freshly-precipitated oxide of iron, taken immediately after poisoning by arsenic, converts the arsenious acid into an insoluble state, and forms a compound on which the acids of the stomach have no action, and therefore the poisoning cannot proceed. It must be further observed that *arsenic is poisonous*

confirmed by the formation of saline compounds with acids. In this respect the most remarkable example is the anhydrous compound with sulphuric acid, and having the composition $\text{As}_2\text{O}_3\cdot\text{SO}_3$. It is formed in the roasting of arsenical pyrites in those spaces where the arsenious anhydride condenses, and this is the more remarkable as sulphurous anhydride is converted into sulphuric anhydride, SO_3 , at the expense of the oxygen of the air in the process, which would seem to be a consequence of the character of arsenious anhydride. The compound in question forms colourless tabular crystals, which are decomposed by water, with formation of sulphuric acid and arsenious anhydride. Compounds of As_2O_3 with 1, 2, 4, and 8 SO_3 are known.

Antimony (stibium), $\text{Sb}=120$,³⁹ is another analogue of phosphorus. In its external appearance and the properties of its compounds it resembles the metals still more closely than arsenic. In fact, antimony has the appearance, lustre, and many of the characteristic properties of the metals. Its oxide, Sb_2O_3 , already shows the earthy appearance of rust or of lime, and has distinctly basic properties, although it corresponds with nitrous and phosphorous anhydride, and is able, like them, to give saline compounds with bases. At the same time, antimony presents, in the majority of its compounds, an entire analogy with phosphorus and arsenic. Its compounds belong to the type, SbX_3 and SbX_5 . It is found in nature, chiefly in the form of sulphide, Sb_2S_3 . This substance sometimes occurs in large masses in mineral veins, and is known in mineralogy under the name of antimony glance, or *stibnite*, and in trade as *antimony*. Besides which antimony partially or totally replaces arsenic in some minerals; thus, for example, a compound of antimony sulphide and arsenic sulphide with silver sulphide is found in red silver ore. But in every case antimony is a rather rare metal found in few localities. It is extracted chiefly for the preparation of alloys with lead and tin, which are used for casting printing type. Some of its compounds are also used in medicine, the most important in this respect being antimony pentasulphide, Sb_2S_5 (*sulfur auratum antimonii*), and tartar emetic, which is a double salt derived from tartaric acid and has the composition, $\text{C}_4\text{H}_4\text{K}(\text{SbO})\text{O}_6$. Even the native antimony sulphide is

even in very small quantities—several centigrammes. It is all the more remarkable that the inhabitants of certain mountainous countries accustom themselves to taking arsenic, as a means which, from their experience, helps to overcome the fatigue of mountain ascents. Arsenious anhydride and certain of its salts are also used in medicine, only naturally in small quantities. When taken internally arsenic passes into the blood, and is mainly excreted by the urine, in which it may be recognised for some length of time after it has been taken, if the amount of arsenic taken has not produced those inflammatory symptoms which form the main cause of death from arsenic poisoning as from other similar mineral poisons.

³⁹ This atomic weight was determined by Cooke.

used in large quantities as a purgative for horses and dogs. Metallic antimony is extracted from the glance, Sb_2S_3 , by roasting, when the sulphur burns away and the antimony oxidises, forming the oxide Sb_2O_3 which is then heated with charcoal, and thus reduced to a *metallic state*. The reduction may be carried on in the laboratory on a small scale, by fusing the sulphide with iron, which takes up the sulphur.⁴⁰

Metallic antimony has a white colour and a brilliant lustre, which remains untarnished in the air, because the metal does not oxidise at the ordinary temperature. It crystallises in rhombohedra, and always shows a distinctly crystalline structure, which gives it quite a different aspect from the majority of the metals yet known. It is most like tellurium in this respect. Antimony is brittle, so that it is very easily converted into a powder; its specific gravity is 6·7, it melts at about 432° but only volatilises at a bright red heat. When heated in the air—for instance, before the blow-pipe—it burns and gives white odourless fumes, consisting of the oxide. This oxide is termed antimonious oxide although it might as well be termed antimonious anhydride. It is given the first name because in the majority of cases its compounds with acids are used, but it forms compounds with the alkalis just as easily.

Antimonious oxide, like arsenious anhydride, crystallises either in regular octahedra or in rhombic prisms; its sp. gr. is 5·56; when heated it becomes yellow and then fuses, and when further heated in air it oxidises, forming an oxide of the composition Sb_2O_4 . Antimonious oxide is insoluble in water and in nitric acid, but it easily dissolves in strong hydrochloric acid and in alkalis, as well as in tartaric acid or solutions of its acid salts. When dissolved in the latter it forms tartar emetic. It is precipitated from its solutions in alkalis and acids (by the action of acids on the former and alkalis on the latter) in an anhydrous form and not as hydrate. It occurs native but rarely. As a base it gives salts of the type, SbOX (as if the basic salts $=\text{SbX}_3, \text{Sb}_2\text{O}_3$) and hardly ever forms salts, SbX_3 . In the antimonyl salts, SbOX , the group SbO is univalent, like potassium or silver. The oxide itself is $(\text{SbO})_2\text{O}$, the hydroxide, $\text{SbO}(\text{OH})$, &c.; tartar emetic is a salt in which one hydrogen of tartaric acid is replaced by potassium and the other by

⁴⁰ Antimony is prepared in a state of greater purity by heating with charcoal the oxide obtained by the action of nitric acid on the impure commercial metallic antimony. This is based on the fact that by the action of the acid, antimony forms the oxide Sb_2O_3 which is but slightly soluble in water. The arsenic, which is nearly always present, forms soluble arsenious and arsenic acids, and remains in solution. The purest antimony is easily obtained from tartar emetic, by heating it with a small quantity of nitre. Metallic antimony also occurs, although rarely, native; and as it is very easily obtained, it was known to the alchemists of the fifteenth century. Very pure metallic antimony may be deposited by the electric current from a solution of antimonious sulphide in sodium sulphide after the addition of sodium chloride to the solution.

antimonyl, SbO . Antimonious oxide is very easily separated from its salts by any base, but it must be observed that this separation does not take place in the presence of tartaric acid, owing to the property of tartaric acid of forming a soluble double salt—*i.e.* tartar emetic.⁴¹

If metallic antimony, or antimonious oxide, be oxidised by an excess of nitric acid and the resultant mass be carefully evaporated to dryness, then *metantimonious acid*, SbHO_3 , is formed. Its corresponding potassium salt, $2\text{SbKO}_3 \cdot 5\text{H}_2\text{O}$, is prepared by fusing metallic antimony with one-fourth of its weight of nitre and washing the resultant mass with cold water. This potassium salt is only slightly soluble in water (in 50 parts) and the sodium salt is still less so. An ortho-acid, SbH_3O_4 , also appears to exist; it is obtained by the action of water on antimony pentachloride, but it is very unstable, like the pentachloride, SbCl_5 , itself, which easily gives up Cl_2 , leaving antimony trichloride, SbCl_3 , which is decomposed by water, forming an oxychloride—for example, SbOCl , only slightly soluble in water. When antimonious acid is heated to an incipient red heat, it parts with water and forms the anhydride, Sb_2O_3 , of a yellow colour and sp. gr. 6.5.⁴²

⁴¹ As antimonious oxide answers to the type SbX_3 , it is evident that compounds may exist in which antimony will replace three atoms of hydrogen; such compounds have been to some extent obtained, but they are easily converted by water into substances corresponding with the ordinary formulæ of the compounds of antimony. Thus tartar emetic, $\text{C}_4\text{H}_4(\text{SbO})\text{K}_2\text{O}_6$, loses water when heated, and forms $\text{C}_4\text{H}_4\text{Sb}_2\text{K}_2\text{O}_6$ —that is, tartaric acid, $\text{C}_4\text{H}_6\text{O}_6$, in which one atom of hydrogen is replaced by potassium and three by antimony. But this substance is re-converted into tartar emetic by the action of water.

A similar compound is seen in that *intermediate oxide of antimony* which is formed when antimonious oxide is heated in air: its composition is SbO_2 or Sb_2O_4 . This oxide may be regarded as orthantimonious acid, $\text{SbO}(\text{HO})_3$, in which three atoms of hydrogen are replaced by antimony in that state in which it occurs in oxide of antimony—*i.e.* $\text{SbO}(\text{SbO}_3) = \text{Sb}_2\text{O}_4$. This supposition clearly explains the existence of this most stable oxide of antimony, which is also formed when antimonious acid is ignited; it then loses water and oxygen, and gives this intermediate oxide as a white infusible powder, of sp. gr. 6.7. It is somewhat soluble in water, and gives a solution which turns litmus paper red.

⁴² Among the other compounds of antimony, *antimoniuretted hydrogen*, SbH_3 , resembles arseniuretted hydrogen in its mode of formation and properties (when liquefied, it boils at -65° , solidifies at -92°), whilst the halogen compounds differ in many respects from those of arsenic. When chlorine is passed over an excess of antimony powder, it forms *antimony trichloride*, SbCl_3 , but if the chlorine be in excess it forms the *pentachloride*, SbCl_5 . The trichloride is a crystalline substance which melts at 72° , and distils at 230° , whilst the pentachloride is a yellow liquid, which splits up into chlorine and the trichloride when heated; at 140° it begins to give off chlorine abundantly, carrying away the vapour of the trichloride with it; and at 200° the decomposition is complete, and pure antimonious chloride only passes over. This property of antimony pentachloride has caused it to be applied in many cases for the transference of chlorine; all the more that when it has given up its chlorine, it leaves the trichloride, which is able to absorb a fresh amount of chlorine; and therefore many substances which are unable to react directly with gaseous chlorine do so with antimony pentachloride, and in the presence of a small quantity of it chlorine will act on them, just as oxygen is able, in the presence of nitrogen oxides, to oxidise substances which could not be oxidised at the

The heaviest analogue of nitrogen and phosphorus is *bismuth*, $\text{Bi} = 208$. Here, as in the other groups, the basic, metallic properties increase with the atomic weight. Bismuth does not give any hydrogen compound, and the highest oxide, Bi_2O_5 , is a very feeble acid oxide. Bismuthous oxide, Bi_2O_3 , is a base, and bismuth itself a perfect metal. To explain the other properties of bismuth it must further be remarked that in the eleventh series it follows mercury, thallium, and lead, whose atomic weights are near to that of bismuth, and that therefore it resembles them and more especially its nearest neighbour, lead. Although PbO and PbO_2 represent different types from Bi_2O_3 and Bi_2O_5 , they resemble them in many respects, even in their external appearance, and especially in their mutual compounds, the lower basic and the higher acid, which easily evolve oxygen. But judging by the formula, Bi_2O_3 is a more feeble base than PbO . They both easily give basic salts.

This gives nearly the whole history of the compounds of bismuth. Thus *bismuth* forms compounds of two types BiX_3 and BiX_5 ,⁴³ which

expense of free oxygen. Thus carbon bisulphide is not acted on by chlorine at low temperatures—this reaction requires a high temperature—but in the presence of antimony pentachloride its conversion into carbon tetrachloride takes place at low temperatures. Antimony tri- and pentachloride, having the character of chloranhydrides, fume in air attract moisture, and are decomposed by water, forming antimonious and antimonic acids. But in the first action of water the trichloride does not evolve all its chlorine as hydrochloric acid, which is understood from the fact that antimonious anhydride is also a base; it is therefore able to react on acids, and indeed even antimony sulphide dissolved in an excess of hydrochloric acid (hydrogen sulphide is evolved) gives an aqueous solution of antimony trichloride, which, when carefully distilled, even gives the anhydrous compound. Antimony trichloride is only decomposed by an excess of water, and then not completely, for with a large mass of water it forms *powder of algaroth*—i.e. antimony oxychloride. The first action of water consists in the formation of *oxychloride*, SbOCl —that is, a salt corresponding to oxide of antimony as a base. If antimony oxide or antimony chloride be dissolved in an excess of hydrochloric acid, and the solution diluted with a considerable amount of water, then this same powder of algaroth is precipitated. The composition varies with the relative amount of water; namely between the limits SbOCl and $\text{Sb}_4\text{O}_5\text{Cl}_2$. The latter compound is, as it were, a basic salt of the former, because its composition = $2(\text{SbOCl})\text{Sb}_2\text{O}_5$.

With bromine and iodine, antimony forms compounds similar to those with chlorine. Antimonious bromide, SbBr_3 , crystallises in colourless prisms, melts at 94° , and boils at 270° ; antimonious iodide, SbI_3 , forms red crystals of sp. gr. 5.0; antimony trifluoride, SbF_3 , separates from a solution of antimonious oxide in hydrofluoric acid, and SbF_5 is formed by a similar treatment of antimonic acid. The latter gives easily-soluble double salts with the fluoride of the metals of the alkalis.

De Haën (1887) obtained very stable double soluble salts, $\text{SbF}_3 \cdot \text{KCl}$ (100 parts of water dissolve 57 parts of salt), $\text{SbF}_3 \cdot \text{K}_2\text{SO}_4$, &c., which he proposed to make use of in the arts as very easily crystallisable and soluble salts of antimony.

Engel, by passing hydrochloric acid gas into a saturated solution of antimonious chloride at 0° , obtained a compound $\text{HCl} \cdot 2\text{SbCl}_3 \cdot 2\text{H}_2\text{O}$, and with the pentachloride a compound $\text{SbCl}_5 \cdot 5\text{HCl} \cdot 10\text{H}_2\text{O}$. Bismuth trichloride, BiCl_3 , gives a similar compound.

⁴³ Metallic bismuth is very easily obtained when the compounds of the oxide are

entirely recall the two types which we have already seen for the compounds of lead. Just as in the case of lead, the type PbX_2 is basic, stable, as a rule easily formed, and passes with difficulty into the higher and lower types, which are unstable, so also in the case of bismuth the type of combination BiX_3 is the usual basic form. The higher type of combination BiX_5 ,⁴⁴ in fact, behaves towards this stable type BiX_3 in exactly the same manner as lead dioxide does to the monoxide; and bismuthic acid is obtained by the action of chlorine on bismuth oxide shaken in water, in exactly the same way as lead dioxide is obtained from lead oxide. It is an oxidising agent, like lead dioxide, and even the acid character in bismuthic acid is only slightly more developed than in lead dioxide. Here, as in the case of lead (minium), intermediate compounds are easily formed, in which the bismuth of the lower oxide plays the part of a base combined with the acid which is formed by the higher form of the oxidation of bismuth. In this resemblance of the neighbouring elements, $\text{Bi}=208$ and $\text{Pb}=206$, of different groups, we find the explanation of many facts of chemistry, and we see in them the naturalness of the periodic system of the elements.




FIG. 85.—Furnace used for the extraction of bismuth from its ores.

In nature, bismuth occurs in only a few localities and in small quantities, most frequently in a native state, and more rarely as oxide and as a compound of bismuth sulphide with the sulphides of other metals. It is extracted from its ores by simple fusion in the furnace shown in fig. 85. This furnace contains an inclined iron retort, into

reduced by powerful reducing agents, but when less powerful reducing agents—for example, stannous oxide—are taken, then bismuth suboxide is formed as a black crystalline powder. It is a compound of the type BiX_2 , its composition being BiO ; it is decomposed by acids into the metal and oxide, which passes into solution.

⁴⁴ The type BiX_5 is represented by the pentoxide, Bi_2O_5 , its metahydrate, $\text{Bi}_2\text{O}_5 \cdot \text{H}_2\text{O}$, or BiHO_5 , known as bismuthic acid, and the pyrohydrate, $\text{Bi}_2\text{H}_4\text{O}_7$. *Bismuth pentoxide* is obtained by the prolonged passage of chlorine through a boiling solution of

the upper extremity of which the ore is charged, and the molten *metal* flows from the lower extremity. It is refined by re-melting, and the pure metal may be obtained by dissolving in nitric acid, decomposing the resultant salt with water, and reducing the precipitate by heating it with charcoal. Bismuth is a metal which crystallises very well from a molten state. Its sp. gr. is 9.8; it melts at 268° , and if it be melted in a crucible, allowed to slowly cool, and the crust broken and the remaining molten liquid poured out, perfect rhombohedral crystals of bismuth are obtained on the sides of the crucible. It is brittle, has a grey-coloured fracture with a reddish lustre, is not hard, and is but very slightly ductile and malleable; it volatilises at a white heat and easily oxidises. It recalls antimony and lead in many of its properties. When oxidised in air, or when the nitrate is ignited, bismuth forms the *oxide* Bi_2O_3 as a white powder, which fuses when heated and resembles massicot. The addition of an excess of caustic potash to a solution of a bismuthous salt gives a white precipitate of the hydroxide, $\text{BiO}(\text{OH})$, which loses its water and gives the anhydrous oxide when boiled with a solution of caustic potash. Both the hydroxide and oxide easily dissolve in acids, and form bismuthous salts.

Bismuthous oxide, Bi_2O_3 , is a feeble and unenergetic base. The normal hydroxide of the oxide Bi_2O_3 is $\text{Bi}(\text{OH})_3$; it parts with water and forms a metahydroxide (bismuthyl hydroxide), $\text{BiO}(\text{OH})$. Both of these hydroxides have their corresponding saline compounds of the composition BiX_3 and BiOX . And the form BiOX is nothing else but the type of the basic salt, because $3\text{ROX} = \text{RX} + \text{R}_2\text{O}_3$. It is evident that in the type BiX_3 the bismuth replaces three atoms of hydrogen. And, indeed, with phosphoric acid, solutions of the bismuthous salts give a precipitate of the composition BiPO_4 . On the other hand, in the form of compounds BiOX or $\text{Bi}(\text{OH})_2\text{X}$, the univalent group (BiO) or (BiH_2O_2) is combined with X. Many bismuth salts are formed according to the type BiOX . For instance, the carbonate $(\text{BiO})_2\text{CO}_3$, which corresponds with the other carbonates M_2CO_3 . It is obtained as a white precipitate when a solution of sodium carbonate is added to

potassium hydroxide (sp. gr. 1.38), containing bismuth oxide in suspension; the precipitate is washed with water, boiling nitric acid (but not long, as otherwise the bismuthic acid is decomposed), then again with water, and then the resultant bright red powder of the hydrate BiHO_3 is dried at 125° . The prolonged action of nitric acid on bismuthic anhydride, Bi_2O_5 , results in the formation of the compound $\text{Bi}_2\text{O}_4\cdot\text{H}_2\text{O}$, which decomposes in moist air, forming Bi_2O_5 . The density of bismuthic anhydride is 5.10, of the tetroxide, Bi_2O_4 , 5.60, and of bismuthic acid, BiHO_3 , 5.75. *Pyrobismuthic acid*, $\text{Bi}_2\text{H}_4\text{O}_7$, forms a brown powder, which loses a portion of its water at 150° , and decomposes on further heating, with the evolution of oxygen and water. It is obtained by the action of potassium cyanide on a solution of bismuth nitrate.

a solution of a bismuth salt.⁴⁵ The complex radicle BiO is naturally not any particular special grouping, as was represented in former times in speaking of complex radicles ; it is simply only a form of expression of the composition of a given oxide according to its relation to the compounds of other oxides.

Three *salts of nitric acid* are known corresponding with bismuthous oxide. If metallic bismuth or its oxide be dissolved in nitric acid, it forms a colourless, transparent solution, containing a salt, which separates in large transparent crystals containing $\text{Bi}(\text{NO}_3)_3 \cdot 5\text{H}_2\text{O}$. When heated at 80° , these crystals melt in their water of crystallisation, and in so doing lose a portion of their nitric acid, together with water, forming a salt whose empirical formula is $\text{Bi}_2\text{N}_2\text{H}_2\text{O}_9$. If the preceding salt belongs to the type BiX_3 , then this one should belong to the form BiOX , because it contains one equivalent of the radicle of nitric acid, NO_3 , per one equivalent of bismuth, and one is led to suppose that this salt has a composition $\text{Bi}(\text{OH})_2\text{NO}_3$ in combination with $\text{BiO}(\text{NO}_3)$. This salt may be heated to 150° without change. When the first colourless crystalline salt dissolves in water *it is decomposed*. There is no decomposition if an excess of acid be added to the water—that is to say, the salt is able to exist in an acid solution without decomposing, without separation of the so-called basic salt—but by itself it cannot be kept in solution ; water decomposes this salt, acts on it like an alkali. Hence the basic properties of bismuthic oxide are so feeble that even water, with its at all events little developed alkaline properties, acts by taking up a portion of the acid from it. Here we see one of the most striking facts, long since observed, confirming that action of water on salts about which we have spoken in Vol. I. p. 426 and elsewhere. This action of water may be expressed thus : $\text{BiX}_3 + 2\text{H}_2\text{O} = \text{Bi}(\text{OH})_2\text{X} + 2\text{XH}$. A salt of the type BiX_3 is decomposed by an excess of water, and a salt of the type $\text{Bi}(\text{OH})_2\text{X}$ is obtained in the precipitate. But if the quantity of acid, HX , be increased, then the salt BiX_3 is again formed and passes into solution. The quantity of the salt BiOX which passes into solution on the addition of a given quantity of acid depends indubitably on the amount of water (Muir). The solution, which is perfectly transparent with a small amount of water, becomes cloudy and separates out the salt of the type BiOX , when diluted. The white flaky precipitate of $\text{Bi}(\text{OH})_2\text{NO}_3$ formed from the normal salt $\text{Bi}(\text{NO}_3)_3$ by mixing it with five parts of water, and in general with a small amount of water, is used in medicine under the name of *magistery of bismuth*.⁴⁶

⁴⁵ Basic bismuth carbonate is employed for whitening the skin (*veloutine*, &c.).

⁴⁶ With an excess of water a further quantity of acid is separated and a still more basi

Metallic bismuth is used for solders and in the preparation of fusible alloys. The addition of bismuth to many metals renders them very hard, and at the same time generally lowers their melting point to a considerable extent. Thus Wood's metal, which contains one part of cadmium, one part of tin, two parts of lead, and four parts of bismuth, fuses at about 60° , and in general many alloys composed of bismuth, tin, lead, and antimony melt below or about the boiling-point of water.⁴⁷

Just as in the II. group, besides the elements zinc, cadmium, and mercury in the uneven series, we saw calcium, strontium, and barium in the even series; and as in the IV. group, besides silicon, germanium, tin, and lead, we saw thallium, zirconium, cerium, and thorium; so also in the V. group we find, besides those elements of the uneven series just considered by us, a series of analogues in the even series, which, with a certain degree of similarity (mainly quantitative, or relative to the atomic weights), also present a series of particular (qualitative) independent points of distinction. In the even series are known *vanadium*, which stands between titanium and chromium, *niobium*, between zirconium and molybdenum, and *tantalum*, situated near

salt formed. The ultimate product, on which an excess of water has apparently no action whatever, is a substance having the composition $\text{BiO}(\text{NO}_3)\cdot\text{BiO}(\text{OH})$. In the latter salts we already see the limit of change, and this limit appears to show that the form of the saline compound of bismuthic oxide are of the forms Bi_2X_6 , and not BiX_3 , and it is very probable, on the basis of the examples which we considered in the case of lead, that this type should be still further polymerised in order to have an idea of the type of the bismuthous compounds. If we refer all the bismuthous compounds to this type, Bi_2X_6 , we shall obtain the following expression for the composition of the nitrates: normal salt, $\text{Bi}_2(\text{NO}_3)_6$, first basic salt, $\text{Bi}_2\text{O}(\text{OH})_2(\text{NO}_3)_2$, magistery of bismuth, $\text{Bi}_2(\text{OH})_4(\text{NO}_3)_2$, and the limiting form $\text{Bi}_2\text{O}_2(\text{OH})(\text{NO}_3)$.

The character of bismuthous oxide in its compounds is clearly seen in the example of the nitrate, because, for example, bismuthous chloride, BiCl_3 , which is obtained by heating bismuth in chlorine, or by dissolving it in aqua regia, and then distilling without the access of air, is also decomposed by water in exactly the same manner, and forms basic salts—for instance, first, BiOCl , like the above salt of nitric acid. Bismuth chloride is volatile, and perhaps its formula is BiCl_3 , and not Bi_2Cl_6 . Polymerisation may take place in some compounds and not in others. A volatile compound of the composition $\text{Bi}(\text{C}_2\text{H}_5)_3$ is also known as a liquid which is insoluble in water and decomposes with explosion when heated to 130° .

⁴⁷ As the metals contained in alloys like the above (bismuth, lead, tin, cadmium) are difficultly volatile and their alloys are fusible, they may be employed in the place of mercury in many physical experiments conducted at 70° and above, and they offer the advantage that they do not give any vapour having a tension (mercury at 100° , 0.75 mm.). These alloys may, for example, be used in thermometers, manometers, baths, &c. It must, however, be borne in mind that in solidifying they expand, and glass vessels in which they have solidified always break after a certain time. Bismuth expands in passing into a molten state, but it has a temperature of maximum density. According to Luedeking the mean coefficient of expansion of liquid bismuth is 0.0000442 (between 270° and 303°), and of solid bismuth 0.0000411.

tungsten, an element of the VI. group, like chromium and molybdenum. Just as bismuth is similar in many respects to its neighbour lead, so also do these neighbouring elements resemble each other, even in their external appearance, not to mention the quality of their compounds, naturally taking into account the difference of the types corresponding with the different groups. The occurrence in the V. group determines the types of the oxides R_2O_3 and R_2O_5 , and the development of an acid character in the higher oxides. The occurrence in the even series determines the absence of volatile compounds, RH_3 , for these metals, and a more basic character of the oxides of a given composition than in the uneven series, &c.⁴⁸ Vanadium, niobium, and tantalum belong to the number of rare metals, and are exceedingly difficult to obtain pure, more especially owing to their similarity to and occurrence with chromium, tungsten, and other metals, and also in combination among themselves; therefore it is natural that they have been far from completely studied, although since 1860 chemists have devoted not a little time to the investigation of these elements. The researches carried out by Marignac, of Geneva, on niobium, and by Sir Henry Roscoe, of Manchester, on vanadium, deserve special attention. The undoubted external resemblance between the compounds of chromium and vanadium, as well as the want of completeness in the knowledge of the compounds of vanadium, long caused its oxides to be considered analogous in atomic composition with those formed by chromium. The higher oxide of vanadium was therefore supposed to have the formula VO_3 . But the fact of the matter is, that the chemical analogy of the elements does not proceed in one direction only; vanadium is at one and the same time the analogue of chromium, and consequently of the elements like sulphur of the VI. group, and also the analogue of phosphorus, arsenic, and antimony; just as bismuth stands in respect to lead and antimony. Investigation has shown that the compounds of vanadium are always accompanied by those of phosphorus as well as of iron, and that it is even more difficult to separate it from the compounds of phosphorus than from those of iron and tungsten. We should have to considerably extend our description if we wished to give the complete history, even of vanadium alone, not to mention niobium and tantalum, all the more as not unfrequently many questions concerning the compounds of these elements have not yet been fully explained. Therefore we shall limit ourselves to pointing out the

⁴⁸ Although, guided by Brauner, who showed that didymium gives a higher oxide, Di_2O_5 , I place this element in the fifth group, still I am not certain as to its position, because I consider that the questions bearing on this metal are still far from being definitely answered.

most important points in the history of this element, all the more as the very minerals in which these elements occur are excessively rare and accessible to only a few investigators.

An important point in the history of the members of this group is seen in the circumstance that they form volatile compounds with chlorine, similar to the like compounds of the elements of the phosphorus group, namely, of the type RX_5 , or one corresponding to it. The vapour densities of the compounds of this nature were determined, and served as the most important basis for the explanation of the atomic composition of these molecules. In this we see the power of those general and fundamental laws, like the law of Avogadro-Gerhardt. An oxychloride, $VOCl_3$, is known for vanadium, which is the perfect analogue of phosphorus oxychloride. It was formerly considered to be vanadium chloride, for exactly the same story was repeated over vanadium as over uranium (Chapter XXI.); its lower oxide, VO , was considered to be the metal, because it is exceedingly difficultly reduced—even potassium does not remove all the oxygen, besides which it has a metallic appearance, and decomposes acids like a metal; in a word, it in every respect resembles a metal. *Vanadium oxychloride* is obtained by heating the trioxide, V_2O_3 , mixed with charcoal, in a current of hydrogen; the lower oxide of vanadium is then formed, and it, when heated in a current of dry chlorine, gives the oxychloride $VOCl_2$ as a reddish liquid, which does not act on sodium, and may be purified by distillation over this metal. It fumes in the air, forming reddish fumes; it reacts on water, forming hydrochloric and vanadic acids; hence, on the one hand it is very similar to phosphorus oxychloride, and on the other hand to chromium oxychloride, CrO_2Cl_2 (Chapter XXI.). It is of a yellow colour, its sp. gr. is 1.83, it boils at 120° , and its vapour density is 86 with respect to hydrogen, and therefore the above formula expresses its molecular weight.⁴⁹

Vanadic anhydride, V_2O_5 , is obtained either in small quantities from certain clays where it accompanies the oxides of iron (hence some sorts of iron contain vanadium) and phosphoric acid, or from the rare

⁴⁹ When the vapours of vanadium oxychloride are heated together with zinc in a closed tube at 400° , they lose a portion of their chlorine and form a green crystalline mass of sp. gr. 2.88, which is deliquescent in air and has the composition $VOCl_2$. Only its vapour density is unknown, and it would be extremely important to determine whether its molecular composition is that given above, or if it corresponds with the formula $V_2O_3Cl_4$. Another less volatile oxychloride, $VOCl$, is formed together with it as a brown insoluble substance, which is, however, soluble in nitric acid like the preceding. Roscoe obtained even a still less chlorinated substance, namely, $(VO)_2Cl$; but it may only consist of a mixture of VO and $VOCl$. At all events, we here find such a graduated series as is met with for very few other elements.

minerals : *colborthite*, CuHVO_4 , or basic vanadate of copper ; *vanadinite*, $\text{PbCl}_2\cdot 3\text{Pb}_3(\text{VO}_4)_2$; lead vanadate, $\text{Pb}_3(\text{VO})_{4,2}$, &c. The latter salts are carefully ignited for some time with one-third of their weight of nitre ; the fused mass thus formed is powdered and boiled in water : the yellow solution obtained contains potassium vanadate. The solution is neutralised with acid, and barium chloride added ; a meta-salt, $\text{Ba}(\text{VO}_3)_2$, is then precipitated as an almost insoluble white powder, which gives a solution of vanadic acid when boiled with sulphuric acid. (The precipitate is at first yellow, as long as it remains amorphous, but it afterwards becomes crystalline and white.) The solution thus obtained is neutralised with ammonia, which thus forms ammonium (meta) vanadate, NH_4VO_3 , which, when evaporated, gives colourless crystals, insoluble in water, containing sal-ammoniac ; hence this salt is precipitated by adding a piece of sal-ammoniac to the solution. Ammonium vanadate, when ignited, leaves vanadic acid behind. In this it differs from the corresponding chromium salt, which is deoxidised into chromium oxide when ignited. In general, vanadic acid has but a small oxidising action. It is reduced with difficulty, like phosphoric or sulphuric acid, and in this differs from arsenic and chromic acids. Vanadic acid, like chromic acid, separates from its solution as the anhydride V_2O_5 , and not in a hydrous state. Vanadic anhydride, V_2O_5 , forms a reddish brown mass, which easily fuses and solidifies into transparent crystals having a violet lustre (another point of resemblance to chromic acid), and dissolves in water, forming a yellow solution with a slightly acid reaction.⁵⁰

⁵⁰ Strong acids and alkalis dissolve vanadic anhydride in considerable quantities, forming yellow solutions. When it is ignited, especially in a current of hydrogen, it evolves oxygen and forms the lower oxides ; V_2O_4 (acid solutions of a green colour, like the salts of chromic oxide), V_2O_3 , and the lowest oxide, VO . The latter is the metallic powder which is obtained when the vanadium oxychloride is heated in an excess of hydrogen, and was formerly mistaken for metallic vanadium. When a solution of vanadic acid is treated with metallic zinc it forms a blue solution, which seems to contain this oxide. It acts as a reducing agent (and forms an intimate analogue to chromous oxide, CrO). Metallic *vanadium* can only be obtained from vanadium chloride, which is quite free from oxygen. The specific gravity of this metal is 5.5. It is of a grey-white colour, is not decomposed by water, is not oxidised in air, but burns when strongly heated, and can be fused in a current of hydrogen. It is insoluble in hydrochloric acid, but easily dissolves in nitric acid, and when fused with caustic soda it forms sodium vanadate.

As regards the salts of vanadic acid, three different classes of salts are known ; the first correspond with metavanadic acid, $\text{VMO}_3 = \text{M}_2\text{OV}_2\text{O}_5$, the second correspond with the dichromates—that is, have the composition $\text{V}_4\text{M}_2\text{O}_{11}$, which is equal to $\text{M}_2\text{O} + 2\text{V}_2\text{O}_5$ —and the third correspond with orthovanadic acid, VM_2O_4 or $3\text{M}_2\text{O} + \text{V}_2\text{O}_5$. The latter are formed when vanadic anhydride is fused with an excess of an alkaline carbonate. A fourth type of salts is also known corresponding with the trichromates, and having the composition $\text{M}_2\text{V}_6\text{O}_{18} = \text{M}_2\text{O} + 3\text{V}_2\text{O}_5$. The latter are formed by the metals of the alkalis and have the appearance of red crystals, resembling chromates. They are formed from

Niobium and tantalum occur as acids in rare minerals, and are mainly extracted from *tantalite* and *columbite*, which are found in Bavaria, Finland, North America, and in the Urals. These minerals are composed of the ferrous salts of niobic and tantalic acids; they contain about 15 per cent. of ferrous oxide in isomorphous mixture with manganous oxide, in combination with various relative amounts of tantalic and niobic anhydrides. These minerals are first fused with a considerable amount of potassium bisulphate, and the fused mass is boiled in water, which dissolves the ferrous salt and leaves an insoluble residue of impure niobic and tantalic acids, &c. This raw product is then treated with ammonium sulphide, in order to extract the tin and tungsten, which pass into solution. The residue containing the acids (according to Marignac) is then treated with hydrofluoric acid, in which it entirely dissolves, and potassium fluoride is added to the resultant hot solution; on cooling, a sparingly-soluble double fluoride of potassium and tantalum separates out in fine crystals, while the much more soluble niobium salt remains in solution. The difference in the solubility of these double salts in water acidified with hydrofluoric acid (in pure water the solution becomes cloudy after a certain time) is so great that the tantalum compound requires 150 parts

the bivanadates by the action of a solution of acetic acid; hence they in this respect also resemble many chromates, which are also formed directly by the removal of an alkali by an acid, although it would be nitric and not acetic acid.

Vanadium was discovered at the beginning of this century by Del-Rio, and afterwards investigated by Sefström, but it was only in 1868 that Roscoe established the above formulæ of the vanadic compounds. The researches made by Roscoe were preceded by those of Marignac in 1865, on the *compounds of niobium and tantalum*, to which were also ascribed different formulæ from those now recognised. Tantalum was discovered simultaneously with vanadium by Hatchett and Ekeberg, and was afterwards studied by Rose, who in 1844 discovered niobium in it. Notwithstanding the numerous researches of Hermann (in Moscow), Kobell, Rose, and Marignac, still there is not yet any certainty as to the purity of, and the results obtained for, the compounds of these elements. They are difficult to separate from each other, and especially from the cerite metals and titanium, &c., which accompany them. Before the investigations of Rose the highest oxide of tantalum was supposed to belong to the type TaX_5 —that is, its composition was taken as TaO_5 , and to the lower oxide was ascribed a formula TaO_2 . Rose gave the formula TaO_2 to the higher oxide, and discovered a new element called niobium in the substance previously supposed to be the lower oxide. He even admitted the existence of a third element occurring together with tantalum and niobium, which he named pelopium, but he afterwards found that pelopic acid was only another oxide of niobium, and he considered it probable that the higher oxide of this element is NbO_5 , and the lower Nb_2O_3 . Hermann found that niobic acid which was considered pure contained a considerable quantity of tantalic acid, and besides this he admitted the existence of another special metallic acid, which he called ilmenic acid, after the locality (the Ilmen mountains of the Urals) of the mineral from which he obtained it. V. Kobell recognised still another acid, which he called dianic acid, and these different testimonies were only brought in agreement in the sixties by Marignac. He first of all indicated an accurate method for the separation of tantalic and niobic compounds, which are always obtained in admixture.

of water for its solution, and the niobium compound only requires 13 parts of water. The Greenland columbite (sp. gr. 5.36) only contains niobic acid, and that from Bodenmais (Bavaria, sp. gr. 6.06) almost equal quantities of tantalic and niobic acids. Having isolated tantalic and niobic salts, Marignac found that the relation between the potassium and fluorine in them is very variable—that is, that there exist various double salts of fluoride of potassium, and of the fluorides of the metals of this group, but that with an excess of hydrofluoric acid both the tantalum and niobium compounds contain seven atoms of fluorine to two of potassium, whence it must be concluded that the simplest formula for these double salts will be $K_2RF_7 = RF_5, 2KF$ —that is, that the type of the higher compounds of niobium and tantalum is RX_5 , and hence is similar to phosphoric acid. A chloride $TaCl_5$ may be obtained from pure tantalic acid by heating it with charcoal in a current of chlorine. This is a yellow crystalline substance, which melts at 211° , and boils at 241° ; its vapour density with respect to hydrogen is 180, as would follow from the formula $TaCl_5$. It is completely decomposed by water into tantalic and hydrochloric acids. *Niobium pentachloride* may be prepared in the same manner; it fuses at 194° , and boils at 240° . When treated with water this substance gives a solution containing niobic acid, which only separates out on boiling the solution. Delafontaine and Deville found its vapour density to be 9.3.⁵¹

⁵¹ If niobic acid be mixed with a small quantity of charcoal and ignited in a stream of chlorine, then a difficultly-fusible and difficultly-volatile oxychloride, $NbOCl_5$, separates. The vapour density of this compound with respect to air is 7.5, and this vapour density gives a perfect certainty to the accuracy of the formulæ given by Marignac, and shows the quantitative analogy between the compounds of niobium and tantalum, and those of phosphorus and arsenic, and consequently also of vanadium. In their qualitative relations (as is seen from the correspondence of the atomic weights also), the compounds of tantalum and niobium exhibit a great analogy with the compounds of molybdenum and tungsten. Thus zinc, when acting on acid solutions of tantalic and niobic compounds, gives a blue coloration, exactly as it does with those of tungsten and molybdenum (titanium also). These acids form the same large number of salts as those of tungsten and molybdenum. The anhydrides of the acids are also insoluble in water, but as colloids are sometimes held in solution, just like those of titanic and molybdic acids. Furthermore, niobium is in every respect the nearest analogue of molybdenum, and tantalum of tungsten. *Niobium* is obtained by reducing the double fluoride of niobium and sodium, with sodium. It is difficult to obtain in a pure state. It is a metal on which hydrochloric acid acts with some energy, as also does hydrofluoric acid mixed with nitric acid, and also a boiling solution of caustic potash. *Tantalum*, which is obtained in exactly the same way, is a much heavier metal. It is infusible, and is only acted on by a mixture of hydrofluoric and nitric acids. Rose in 1868 showed that in the reduction of the double fluoride, $NbF_5, 2KF$, by sodium, a greyish powder is obtained after treating with water. The specific gravity of this powder is 6.8, and he considers it to be niobium hydride, NbH . Neither did he obtain metallic niobium when he reduced with magnesium and aluminium, but an alloy Al_3Nb , having a sp. gr. of 4.5.

Niobium, as far as is known, unites in three proportions with oxygen. NbO , which is

formed when $\text{NbOF}_5 \cdot 2\text{KF}$ is reduced by sodium; NbO_2 , which is formed by igniting niobic acid in a stream of hydrogen, and niobic anhydride, Nb_2O_5 , a white infusible substance, which is insoluble in acids, and has a specific gravity of 4.5. Tantalie anhydride closely resembles niobic anhydride, and has a specific gravity of 7.2. *The tantalates and niobates* present the type of ortho-salts—for example, $\text{Na}_2\text{HfNbO}_4 \cdot 6\text{H}_2\text{O}$, and also of pyro-salts, such as $\text{K}_5\text{HfNb}_2\text{O}_7 \cdot 6\text{H}_2\text{O}$, and of meta-salts—for example, $\text{KNbO}_3 \cdot 2\text{H}_2\text{O}$. And, besides these, they give salts of a more complex type, containing a larger amount of the elements of the anhydride; thus, for instance, when niobic anhydride is fused with caustic potash it forms a salt which is soluble in water, and crystallises in monoclinic prisms, having the composition $\text{K}_8\text{Nb}_6\text{O}_{19} \cdot 16\text{H}_2\text{O}$. There is a perfectly similar isomorphous salt of tantalie acid. Tantalite is a salt of the type of metatantalie acid, $\text{Fe}(\text{TaO}_5)_2$. The composition of Yttrotantalite appears to correspond with orthotantalie acid.

CHAPTER XX

SULPHUR, SELENIUM, AND TELLURIUM

THE acid character of the higher oxides RO_3 of the elements of the VI. group is still more clearly defined than that of the higher oxides of the preceding groups, whilst feeble basic properties only appear in the oxides RO_3 of the elements of the even series, and then only for those elements having a high atomic weight—that is, under those two conditions in which, as a rule, the basic characters increase. Even the lower types RO_2 and R_2O_3 , &c., formed by the elements of the VI. group, are acid anhydrides in the uneven series, and only those of the elements of the even series have the properties of peroxides or even of bases.

Sulphur is the representative of the VI. group both owing to the fact that the acid properties of the group are sharply defined in it, and also because it is more widely distributed in nature than any of the other elements belonging to this group. As an element of the uneven series of the VI. group, sulphur gives H_2S , sulphuretted hydrogen, SO_3 , sulphuric anhydride, and SO_2 , sulphurous anhydride. And in all of them we find acid properties— SO_3 and SO_2 are anhydrides of acids, and H_2S is an acid, although a feeble one. As an element sulphur has all the properties of a true non-metal; it has not a metallic lustre, does not conduct electricity, is a bad conductor of heat, is transparent, and combines directly with metals—in fact, all the properties of the non-metals, like oxygen and chlorine. Furthermore, sulphur exhibits a great qualitative and quantitative *resemblance to oxygen*, especially from the fact that it, like oxygen, combines *with two atoms of hydrogen*, and forms compounds like oxides with metals and non-metals. In this sense and aspect sulphur is bivalent, if the halogens are univalent.¹ The chemical character of sulphur is expressed by the fact

¹ The character of sulphur is very clearly defined in the organo-metallic compounds. Without lingering over this vast subject, which belongs to the province of organic chemistry, I think it will be enough for our purpose to compare the physical properties of the ethyl compounds of mercury, zinc, sulphur and oxygen. They have the common

that it forms a very slightly stable and feebly energetic acid with hydrogen, which, on the one hand, resembles water in its atomic composition, and, on the other hand, the halogen acids in its property of forming salts. The salts corresponding with this acid are the sulphides, just as the oxides correspond to water or the chlorides to hydrochloric acid. However, as we shall afterwards see more fully, the sulphides are more analogous to the former than to the latter. But although combining with metals, like oxygen, sulphur also forms chemically stable compounds with oxygen, and this fact impresses a peculiar character on all the relations of this element.²

Sulphur belongs to the number of those elements which *are very widely distributed in nature*, and occurs both free and combined in various forms. The atmosphere, however, is almost entirely free from compounds of sulphur, although a certain amount of them should be present, if only from the fact that sulphurous anhydride is emitted from the earth in volcanic eruptions. Sea and river water generally contain more or less sulphur in the form of sulphates. The beds of gypsum, sodium sulphate, magnesium sulphate, and the like are formations of undoubtedly aqueous origin. The sulphates contained in the soil are the source of the sulphur found in plants, and are indispensable to their growth. Among vegetable substances, the proteids always contain from one to two per cent. of sulphur. From plants these albuminous substances, together with their sulphur, pass into the animal organism, and therefore the decomposition of animal matter is accompanied by the odour of sulphuretted hydrogen, as the product into which the sulphur passes in the decomposition of the albuminous substances. Thus a rotten egg emits sulphuretted hydrogen. Sulphur occurs largely in nature, as the various insoluble sulphides of the metals. Iron, copper, zinc, lead, antimony, arsenic, &c., occur in nature combined with sulphur. These *sulphides* frequently have a metallic lustre, and in the majority of cases occur crystallised, and also very often several sulphides occur combined or mixed together in these crystalline compounds. If they are yellow and have a metallic lustre they are called pyrites. Such are, for example,

composition $(C_2H_5)_2R$, where $R = Hg, Zn, S, \text{ or } O$. They are all volatile: mercury ethyl, $Hg(C_2H_5)_2$, boils at 159° , its sp. gr. is 2.444, molecular volume = 106; zinc ethyl boils at 118° , sp. gr. 1.882, volume 101; ethyl sulphide, $S(C_2H_5)_2$, boils at 90° , sp. gr. 0.825, volume 107; common ether, or ethyl oxide, $O(C_2H_5)_2$, boils at 35° , sp. gr. 0.736, volume 101, in addition to which diethyl itself, $(C_2H_5)_2 = C_4H_{10}$, boils about 0° , sp. gr. about 0.62, volume about 94. Thus the substitution of Hg, S, and O scarcely changes the volume, notwithstanding the difference of the weights; the physical influence, if one may so express oneself, of these elements, which are so very different in their atomic weights, is almost alike.

² Therefore in former times sulphur was known as the amphoteric element.

copper pyrites, CuFeS_2 , and iron pyrites, FeS_2 , which is the commonest of all. They are all also known as glances or blendes if they are greyish and have a metallic lustre—for example, zinc blende, lead glance, PbS , antimony glance, Sb_2S_3 , &c. And, lastly, sulphur occurs *native*. It occurs in this form in the most recent geological formations in admixture with limestone and gypsum, and most frequently in the vicinity of active or extinct volcanoes. As the gases of volcanoes contain sulphur compounds—namely, sulphuretted hydrogen and sulphurous anhydride, which by reacting on one another may produce sulphur, which also frequently appears in the craters of volcanoes as a sublimate—it might be imagined that the sulphur was of volcanic origin. But on a nearer acquaintance with its mode of occurrence, and more especially considering its relation to gypsum, CaSO_4 , and limestone, the present general opinion leads to the conclusion that the sulphur has been formed by the reduction of the gypsum by organic matter and that its occurrence is only indirectly connected with volcanic agencies. Near Tetush, on the Volga, there are beds containing gypsum, sulphur, and asphalt (mineral tar). In Europe the most important deposits of sulphur are in the south of Sicily from Catania to Girgenti.³ There are very rich deposits of sulphur in Daghestan near Cherkai and Cherkat in Khyut, and in the Trans-Caspian provinces; which are able to supply the whole of Russia with this mineral. Abundant deposits of sulphur have also been found in Kamtchatka in the neighbourhood of the volcanoes. The method of separation of the sulphur from its earthly impurities is based on the fact that sulphur melts when it is heated. The fusion is carried on at the expense of a portion of the sulphur, which is burnt, so that the remainder may melt and run from the mass of the earth. This is carried on in special furnaces called *calcaroni*.⁴

³ When I was in Sicily, I found, near Caltanissetta, a specimen of sulphur with mineral tar. In the same neighbourhood there are naphtha springs and mud volcanoes. It may be that these substances have reduced the sulphur from gypsum.

The chief proof in favour of the origin of sulphur from gypsum is that in treating the deposits for the extraction of the sulphur it is found that the proportion between the sulphur and calcium carbonate never exceeds that which it would be had they both been derived from calcium sulphate.

⁴ Naturally only those ores of sulphur which contain a considerable amount of sulphur can be treated by this method. With poor ores it is necessary to have recourse to distillation or mechanical treatment in order to separate the sulphur, but its price is so low that this is often not profitable.

The sulphur obtained by the above-described method still contains some impurities, but it is frequently made use of in this form for many purposes, and especially in considerable quantities for the manufacture of sulphuric acid, and for strewing over grapes. For other purposes, and especially in the preparation of gunpowder, a purer sulphur is required. Sulphur may be purified by distillation. The crude sulphur is called *rough*,

Sulphur is purified by distillation in special retorts (see fig. 86) by passing the vapour into a chamber G built of stone. The first portions of the vapour entering into the condensing chamber are condensed straightway from the vapour into a solid state, and form a fine powder known as *flowers of sulphur*.⁵ But when the temperature of the




FIG. 86.—Refining sulphur by sublimation.

receiver attains the melting point of sulphur, it passes into a liquid state and is cast into moulds (like sealing wax), and it is then known under the name of *roll sulphur*.⁶

and the distilled sulphur *refined*. The arrangement given in fig. 86 is employed for refining sulphur. The rough sulphur is melted in the boiler *d*, and as it melts it is run through the tube *F* into an iron retort *B* heated by the naked flame of the furnace. Here the sulphur is converted into vapour, which passes through a wide tube into the chamber *G*, surrounded by stone walls and furnished with a safety-valve *S*.

⁵ Flowers of sulphur always contains a certain amount of the oxides of sulphur.

⁶ Sulphur may be extracted by various other means. It may be extracted from iron pyrites, FeS_2 , which is very widely distributed in nature. From 100 parts of iron pyrites about half the sulphur contained, namely—about 25 p.c.—may be extracted by heating without the access of air, a lower sulphide of iron, which is more stable under the action

In an uncombined state sulphur exists in *several modifications*, and it forms an example of the facility with which an alteration of properties can take place without a change of composition—that is, as regards the material of a substance. Common sulphur has the well-known yellow colour. This colour fades as the temperature falls, and at -50° sulphur is almost colourless. It is very brittle, so that it may be easily converted into a powder, and it presents a crystalline structure, which, by the way, shows itself in the unequal expansion of lumps of sulphur by heat. Hence when a piece of sulphur is heated by the warmth of the hand, it emits sounds and sometimes cracks, which probably also depends on the bad heat-conducting power of sulphur. It is easily obtained in a crystalline form by artificial means, because although insoluble in water it dissolves in carbon bisulphide, and in certain oils.⁷ Solutions of sulphur in carbon bisulphide when evaporated at the ordinary temperature yield well-formed transparent crystals of sulphur in the form of rhombic octahedra, in which form it occurs native. The specific gravity of these crystals is 2.045. Fused sulphur, cast into moulds and cooled, has, after being kept a long time, a specific gravity 2.066; almost the same as that of the crystalline sulphur of the above form, which shows that common sulphur is the same as that which crystallises in octahedra. The specific heat of octahedral sulphur is 0.17; it melts at 114° , and forms a mobile bright yellow liquid. On further heating the fused sulphur undergoes an alteration, which we shall presently describe, first observing that the above octahedral state of sulphur is its most stable form. Sulphur may be kept at the ordi-

of heat, being left behind. Alkali waste (Vol. I. p. 514), containing calcium sulphide and gypsum, CaSO_4 , may be used for the same purpose, but native sulphur is so cheap that recourse can only be had to these sources when the calcium sulphide appears as a worthless bye-product. The most simple process for the extraction of sulphur from alkali waste, in a chemical sense, consists in evolving sulphuretted hydrogen from the calcium sulphide by the action of hydrochloric acid. The sulphuretted hydrogen when burnt gives water and sulphurous anhydride, which reacts on fresh sulphuretted hydrogen with the separation of sulphur. The combustion of the sulphuretted hydrogen may be so conducted that a mixture of $2\text{H}_2\text{S}$ and SO_2 is straightway formed, and this mixture will deposit sulphur (Chapter XII. Note 14). Gossage and Chance treat alkali waste with carbonic anhydride, and subject the sulphuretted hydrogen evolved to incomplete combustion (this is best done by passing a mixture of sulphuretted hydrogen and air, taken in the requisite proportions, over red-hot ferric oxide), by which means water and the vapour of sulphur are formed: $\text{H}_2\text{S} + \text{O} = \text{H}_2\text{O} + \text{S}$.

⁷ One hundred parts of liquid carbon bisulphide, CS_2 , dissolve 16.5 parts of sulphur at -11° , 24 parts at 0° , 37 parts at 15° , 46 parts at 22° , and 181 parts at 55° . The saturated solution boils at 55° , whilst pure carbon bisulphide boils at 47° . The solution of sulphur in carbon bisulphide reduces the temperature, just as in the solution of salts in water. Thus the solution of 20 parts of sulphur in 50 parts of carbon bisulphide at 20° lowers the temperature by 5° ; 100 parts of benzene, C_6H_6 , dissolves 0.965 parts of sulphur at 26° , and 4.377 parts at 71° ; chloroform, CHCl_3 , dissolves 1.2 parts of sulphur at 22° , and 16.35 parts at 174° .

nary temperature in this form for an indefinite length of time, and many other modifications of sulphur pass into this form after being left for a certain time at ordinary temperature.

If sulphur be melted and then slightly cooled, so that it forms a crust on the surface and over the sides of the crucible, while the internal mass remains liquid, then the sulphur takes another crystalline form as it solidifies. This may be seen by breaking the crust, and pouring out the remaining molten sulphur.⁸ It is then found that the sides of the crucible are covered with *prismatic crystals* of the monoclinic system; they have a totally different appearance from the above-described crystals of rhombic sulphur. The prismatic crystals are brown, transparent, and less dense than the crystals of rhombic sulphur, their specific gravity being only 1.93, and their melting point is higher—about 120°. These crystals of sulphur cannot be kept at the ordinary temperature, which is already seen from the fact that in time they turn yellow; also the specific gravity changes, and they pass completely into the ordinary modification. This is accompanied by a considerable development of heat, so that the temperature of the mass may rise 12°. Thus sulphur is *dimorphous*—that is, it exists in two crystalline forms, and in both forms it has independent physical properties. However, no chemical reactions are known which distinguish the two modifications of sulphur, just as there are none distinguishing aragonite from calcspar.⁹

If molten sulphur be heated to 150°, it loses its mobility, and becomes thick and very dark-coloured, so that the vessel containing it may be inverted without the sulphur running out. When heated above 300°, the sulphur again becomes liquid, although it does not acquire its original colour, and at 440° it boils. These modifications in the properties of sulphur depend not only on the variations of temperature, but also on a change of structure. If sulphur, heated to about 350°,

⁸ If the experiment be made in a vessel with a narrow capillary tube, the sulphur fuses at a lower temperature (occurs, as it were, in a supersaturated state), and, solidifying at 90°, appears in a rhombic form (Schützenberger).

⁹ If sulphur be cautiously melted in a U tube immersed in a salt bath, and then gradually cooled, it is possible for all the sulphur to remain liquid at 100°. It will now be in a state of superfusion; thus also by careful refrigeration water may be obtained in a liquid state at -10°, and a lump of ice then causes such water to separate out ice, and the temperature rises to 0°. If a prismatic crystal of sulphur be thrown into one branch of the U tube containing the liquid sulphur at 100°, and an octahedral crystal be thrown into the other branch, then, as Gernez showed, the sulphur in each branch will crystallise in corresponding forms, and both forms are obtained at the same temperature; therefore it is not the influence of temperature only which causes the molecules of sulphur to distribute themselves in one or another form, but also the influence of the crystalline parts already formed. This phenomenon is essentially analogous to the phenomena of supersaturated solutions.

be poured in a thin stream into cold water, it does not solidify into a solid mass, but retains its brown colour and *remains soft*, may be stretched out into threads, and is elastic, like guttapercha. But in this soft and ductile state, also, it does not remain for a long time. After the lapse of a certain period this soft transparent sulphur hardens, becomes opaque, passes into the ordinary yellow modification of sulphur, and, in so doing, develops heat, just as in the conversion of the prismatic into the octahedral variety. The soft sulphur is characterised by the fact that a certain portion of it is insoluble in carbon bisulphide. When soft sulphur is immersed in this liquid, then only a portion of common sulphur passes into solution, whilst a certain portion is quite insoluble, and remains so for a long time. The maximum proportion of insoluble sulphur is obtained by heating slightly above 170° . It melts at 114° . An exactly similar *insoluble amorphous sulphur* is obtained in certain reactions in the wet way, when sulphur separates out from solutions. Thus sodium thiosulphate, $\text{Na}_2\text{S}_2\text{O}_3$, when treated with acids, gives a precipitate of sulphur, which is insoluble in carbon bisulphide. The action of water on sulphur chloride also gives a similar modification of sulphur. Certain sulphides, when treated with nitric acid, also yield sulphur in this form.¹⁰

¹⁰ A certain amount of insoluble sulphur remains for a long time in the mass of soft sulphur, changing into the ordinary variety. Freshly-cooled soft sulphur contains about one-third of insoluble sulphur, and after the lapse of two years it still contains about 15 p.c. Flowers of sulphur, obtained by the rapid condensation of sulphur from a state of vapour, also contains a certain amount of insoluble sulphur. *Rapidly distilled and condensed sulphur* also contains some insoluble sulphur. Hence a certain amount of insoluble sulphur is frequently found in roll sulphur. The action of light on a solution of sulphur converts a certain portion into the insoluble modification. Insoluble sulphur is of a lighter colour than the ordinary variety. It is best prepared by vaporising sulphur in a stream of carbonic anhydride, hydrochloric acid, &c., and collecting the vapour in cold water. When condensed in this manner it is nearly all insoluble in carbon bisulphide. It then has the form of hollow spheroids, and is therefore lighter than the common variety: sp. gr. 1.82. An idea of the modifications taking place in sulphur between 110° and 250° may be formed from the fact that, at 150° liquid sulphur has a coefficient of expansion of about 0.0005, whilst between 150° and 250° it is less than 0.0003.

When a solution of sulphuretted hydrogen in water is decomposed by an electric current the sulphur is deposited on the positive pole, and has therefore an electro-negative character, and this sulphur is soluble in carbon bisulphide. When a solution of sulphurous acid is decomposed in the same manner, the sulphur is deposited on the negative pole, and is therefore electro-positive, and the sulphur so deposited is insoluble in carbon bisulphide. The sulphur which is combined with metals must have the properties of the sulphur contained in sulphuretted hydrogen, whilst the sulphur combined with chlorine is like that which is combined with oxygen in sulphurous anhydride. Hence Berthelot recognises the presence of soluble sulphur in metallic sulphides, and of the insoluble modification of amorphous sulphur in sulphur chloride. Cloez showed that the sulphur precipitated from solutions is either soluble or insoluble, according as to whether it separates from an alkaline or acid solution. If sulphur be melted with

At temperatures of 440° to 700° the vapour density of sulphur is 6.6 referred to air—i.e., about 96 referred to hydrogen. Hence, at these temperatures *the molecule of sulphur contains six atoms*; it has the composition S_6 . The agreement between the observations of Dumas, Mitscherlich, Bineau, and Deville confirms the accuracy of this result. When heated to temperatures above this—namely, *at a temperature above 800° to 1000°* —sulphur rapidly changes its vapour density with respect to that of hydrogen or air. At these temperatures the vapour density of sulphur referred to air is 2.2, which is equal to about 32 referred to hydrogen. At this temperature *the molecule of sulphur*, like that of hydrogen, oxygen, nitrogen, and chlorine, contains *two atoms*; hence the molecular formula is then S_2 . This variation in the vapour density of sulphur evidently corresponds with a polymeric modification of sulphur, and may be likened to the transformation of ozone, O_3 , into oxygen, O_2 , or, better still, of benzene, C_6H_6 , into acetylene, C_2H_2 .¹¹

a small quantity of iodine or bromine, then on pouring out the molten mass it forms amorphous sulphur, which keeps for a very long time, and is insoluble, or nearly so, in carbon bisulphide. This is taken advantage of for casting certain articles in sulphur, which retain their tenacity for a long time; for example, the discs of electrical machines.

¹¹ Here, however, it is very important to remark that both benzene and acetylene can exist at the ordinary temperature, whilst the sulphur molecule S_2 only exists at high temperatures; and if this sulphur be allowed to cool, it first passes into S_6 and then into a liquid state. Were it possible to have sulphur at the ordinary temperature in both the above modifications, then in all probability the sulphur in the state S_2 would present totally different properties from those which it has in the form S_6 , just as the properties of gaseous acetylene are far from being similar to those of liquid benzene, which boils at 80° . Sulphur, in the form S_2 , is probably a substance which boils at a much lower temperature than the variety with which we are now dealing. Paterno and Nasini (1888), following Raoult's method (that is, the fall of freezing-point in a benzene solution), found that the molecule of sulphur in solution contains S_6 . But the problem of this aspect of the matter cannot as yet be considered as ultimately solved.

One cannot but here turn attention to the fact that sulphur, with all its analogy to oxygen (which also shows itself in its faculty to give the modification S_2), is also able to give a series of compounds containing more sulphur than the analogous compounds of oxygen. So, for instance, compounds of 5 atoms of sulphur with 2 atoms of potassium, or with 1 atom of barium, are known. In every case one cannot but see in sulphur a faculty for the union of a greater number of atoms than with oxygen. With oxygen the form of ozone, O_3 , is very unstable, the stable form is O_2 ; whilst with sulphur S_6 is the stable form, and S_2 is exceedingly unstable. Furthermore, it is remarkable that sulphur gives a higher degree of oxidation H_2SO_4 , corresponding, as it were, with its complex composition, if we suppose that in S_6 four atoms of sulphur are replaced by oxygen and one by two atoms of hydrogen. The formulæ of its compounds, K_2SO_4 , $K_2S_2O_5$, K_2S_5 , BaS_3 , and many others, have no analogues among the compounds of oxygen. They all correspond with the form S_6 (one portion of the sulphur being replaced by oxygen and another by metals), which is not repeated by oxygen. In this faculty of sulphur to hold many atoms of other substances the same forces appear which cause many atoms of sulphur to form one complex molecule. This is also seen in other examples: oxygen gives H_2O and H_2O_2 , and in an uncombined state O_2 and O_3 ; chlorine gives only HCl , and in a free state Cl_2 ; sulphur gives both H_2S and H_2S_2 , and also H_2S_3 , because

In its faculty for combination sulphur most closely resembles oxygen and chlorine; like them, it combines with nearly all elements, with the development of heat and light, forming sulphur compounds which, as was said above, resemble the analogous oxygen compounds. Like oxygen, sulphur only combines with the majority of elements at a high temperature. At the ordinary temperature it does not enter into reactions, owing, amongst other things, to the fact that it is a solid. In a molten state it acts on the majority of substances—on the metals and the halogens. It combines with oxygen at about 400° , and with carbon at a red heat; but it does not combine with nitrogen. The products of these reactions will be afterwards described, and we will now turn to the compounds of sulphur with hydrogen and the metals.

The majority of metals, when fused or heated with sulphur, combine with it. Fine wires, or the powders of the greater number of metals, burn in the vapour of sulphur. The direct combination of hydrogen with sulphur is restricted by a limit—that is, at a given temperature and other conditions it does not proceed unrestrictedly; there is no explosion or recalescence. Sulphuretted hydrogen, H_2S , decomposes at its temperature of combination—that is, it is easily dissociated.¹² The same thing is repeated here as with water, only the limits of the temperatures at which the attraction of hydrogen for sulphur begins and ceases are much closer than in the case of oxygen and hydrogen. The temperature at which combination takes place is here, as in many other instances, the same as that at which dissociation begins. Therefore, *sulphuretted hydrogen* is formed in a small quantity

in a free state it is able to contain S_2 and S_6 , and probably also S_4 . If, as we know, there is an atomic analogy between ozone, O_3 , and H_2O_2 , so in H_2S_5 there would be an atomic analogy to S_6 .

¹² In the formation of potassium sulphide, K_2S (that is, in the combination of 32 parts of sulphur with 78 parts of potassium), about 100 thousand heat units are developed. Nearly as much heat is developed in the combination of an equivalent quantity of sodium; about 90 thousand heat units in the formation of calcium or strontium sulphide, about 40 thousand for zinc or cadmium sulphide, and about 20 thousand for iron, cobalt, or nickel sulphide. Less heat is evolved in the combination of sulphur with copper, lead, and silver. According to Thomsen, sulphur develops heat with hydrogen in solutions; thus the reaction $\text{I}_2, \text{Aq}, \text{H}_2\text{S} = 21830$ calories—that is (in the presence of excess of water), a sufficient amount of heat is developed to raise the temperature of 21830 grams of water 1°C . But, as the reaction $\text{I}_2 + \text{H}_2 + \text{Aq}$ develops 26342 calories, it follows that the reaction $\text{H}_2 + \text{S}$ develops 4512 calories. We here add the amounts of heat developed by the combination of the other non-metals with hydrogen, also according to Thomsen, $(\text{H}, \text{Cl}) = 22001$; $(\text{H}, \text{Br}) = 8440$; $(\text{H}, \text{I}) = -6036$ (heat is absorbed); $(\text{N}, \text{H}_3) = 26707$; $(\text{C}, \text{H}_4) = 20420$; $(\text{C}_2, \text{H}_4) = 10880$; $(\text{C}_2, \text{H}_2) = -55010$. For the present it can only be said, with respect to combination with hydrogen, that in each group of non-metals the elements with small atomic weights (carbon, nitrogen, oxygen, chlorine) develop heat in combining with hydrogen, and those having larger atomic weights either develop less heat or absorb it (arsenic?, selenium, tellurium?, iodine).

by the direct ignition of a mixture of the vapour of sulphur and hydrogen. However, the temperature must not be high, because otherwise the whole of the sulphuretted hydrogen is decomposed: but at lower temperatures a small amount of sulphuretted hydrogen is formed by direct combination.¹³ Sulphuretted hydrogen, like all other hydrogen compounds, may be easily obtained by the double decomposition of its corresponding metallic compounds, by replacing the metal by hydrogen by the action of acids on their sulphides. The metallic sulphides are, as a rule, easily formed, and some are even met with in nature. A sulphide, when mixed with a non-volatile acid, may give, by double decomposition, a salt of the acid taken and sulphuretted hydrogen, $M_2S + H_2SO_4 = H_2S + M_2SO_4$. However, it is not all sulphides nor solutions of all acids that will evolve sulphuretted hydrogen, which is exceedingly characteristic, because, for example, all carbonates evolve carbonic anhydride when treated with any acid. Sulphuric acid will only evolve sulphuretted hydrogen from those sulphides which contain a metal capable of decomposing the acid with the evolution of hydrogen. Thus zinc, iron, calcium, magnesium, manganese, potassium, sodium, &c., form sulphides which evolve sulphuretted hydrogen when treated with sulphuric acid, and the metals themselves evolve hydrogen with acids.¹⁴ The sulphides of those metals which do not liberate

¹³ If sulphur is melted in a flask and heated to nearly its boiling point, then, as Lidoff showed, the addition, drop by drop (from a funnel with a stop-cock) of heavy (0.9) naphtha oil (of lubricating oleonaphtha), &c., is followed by a regular evolution of sulphuretted hydrogen. This is analogous to the action of bromine or iodine on paraffin and other oils, because hydrobromic or hydriodic acid is then formed (Chapter XI). A certain amount of hydrogen sulphide is even formed when sulphur is boiled with water.

¹⁴ However, the matter is really much more complicated. Thus zinc sulphide evolves sulphuretted hydrogen with sulphuric or hydrochloric acids, but does not react with acetic acid and is oxidised by nitric acid. So, also, ferrous sulphide evolves sulphuretted hydrogen with acids, whilst the bisulphide, FeS_2 , on the contrary, does not react with feeble acids. This absence of action depends, among other things, on the form in which the native iron pyrites occurs; it is a crystalline, compact, and very dense substance, which is totally insoluble in water; and acids in general react with great difficulty on such metallic sulphides. This is seen very clearly in the case of zinc sulphide; if this substance is obtained by double decomposition, it separates as a white precipitate which evolves sulphuretted hydrogen with great ease when treated with acids. Zinc sulphide is obtained in the same form when zinc is fused with sulphur, but native zinc sulphide—which occurs in compact masses, known under the name of zinc blende, and has a metallic lustre—is not decomposed or scarcely decomposed by sulphuric acid.

Another source of complication in the behaviour of the metallic sulphides towards acids depends on the action of water, and is shown in the fact that the action varies with different degrees of dilution or proportion of water present. The best known example of this is seen with antimonious sulphide, Sb_2S_3 , because strong hydrochloric acid, containing not more water than corresponds with $HCl, 6H_2O$, even decomposes native antimony glance, with evolution of sulphuretted hydrogen, whilst dilute acid has no action, and in the presence of an excess of water the reaction $2SbCl_5 + 3H_2S = Sb_2S_3 + 6HCl$ occurs, whilst in the presence of a small amount of water the reaction proceeds in

hydrogen from acids do not generally act on acids—that is, do not form sulphuretted hydrogen with them; such are, for example, the sulphides of lead, silver, copper, mercury, tin, &c. Therefore, the *modus operandi* of the formation of sulphuretted hydrogen by the action of acids on metallic sulphides may be looked on as a phenomenon of the combination of hydrogen, at the moment of its evolution, with the sulphur, which is combined with the metal. Such a representation is all the more simple, as all the circumstances under which sulphuretted hydrogen is formed are exactly similar to the conditions of the formation of hydrogen itself. Thus the usual mode of preparing sulphuretted hydrogen is by the action of *sulphuric acid on ferrous sulphide*, in which the same apparatus and method is employed as in the preparation of hydrogen, only replacing the metallic iron or zinc by ferrous sulphide or zinc sulphide. The reaction between sulphide of iron and sulphuric acid takes place at the ordinary temperature, and is accompanied by the same inconsiderable development of heat as in the liberation of hydrogen itself, $\text{FeS} + \text{H}_2\text{SO}_4 = \text{FeSO}_4 + \text{H}_2\text{S}$.¹⁵

In nature sulphuretted hydrogen is formed by many means. The most usual method of its formation is by the decomposition of albuminous substances containing sulphur, as has been mentioned above. Another method by which sulphuretted hydrogen is formed in nature is by the reducing action of organic matter on sulphates, and by the

exactly the opposite direction. Here the participation of water in the reaction and its affinity are evident, and this is clearly expressed in the thermochemical data, as has been partially explained previously, especially in Chap. X. Note 27.

The facts that lead sulphide is insoluble in acids, that zinc sulphide is soluble in hydrochloric acid but insoluble in acetic acid, that calcium sulphide is even decomposed by carbonic acid, &c.—all these peculiarities of the sulphides are in correlation with the amount of heat evolved in the reaction of the oxides with hydrogen sulphide and with acids, as is seen from the observations of Favre and Silberman, and from the comparisons made by Berthelot in the Proceedings of the Paris Academy of Sciences, 1870, to which we refer the reader for further details.

¹⁵ *Ferrous sulphide* is formed by heating a piece of iron to an incipient white heat, and then removing it from the furnace and bringing it into contact with a piece of sulphur. Combination then proceeds, accompanied by the development of heat, and the ferrous sulphide formed fuses (Vol. I. p. 3). The sulphide of iron thus formed is a black, easily fusible substance, insoluble in water. When damp it attracts oxygen from the air, and is converted into green vitriol, FeSO_4 . If all the iron does not combine with the sulphur in the method described above, the action of sulphuric acid will evolve hydrogen as well as hydrogen sulphide.

We will not describe the details respecting the preparation of sulphuretted hydrogen employed as a reagent in the laboratory, because, in the first place, the methods are essentially the same as in the preparation of hydrogen, and, in the second place, because the apparatus and method employed are always described in text-books of analytical chemistry. Ferrous sulphide may be advantageously replaced by calcium sulphide or a mixture of calcium and magnesium sulphides. A solution of magnesium hydrosulphide, $\text{MgS}, \text{H}_2\text{S}$, is very convenient, as at 60° it evolves a stream of pure hydrogen sulphide.

action of water and carbonic acid on the sulphides formed by this reduction. A third source of sulphuretted hydrogen in nature is by volcanic eruptions. Although sulphuretted hydrogen is formed in small quantities everywhere in nature, it nevertheless soon disappears from the atmosphere, owing to its being easily decomposed by oxidising agencies. Many mineral waters contain sulphuretted hydrogen, and smell of it; they are called 'sulphur waters.'

Sulphuretted hydrogen, at the ordinary temperature, is a colourless gas, having a very unpleasant odour. It has, as its composition H_2S shows, a specific gravity seventeen times greater than hydrogen, and therefore it is somewhat heavier than air. Sulphuretted hydrogen *liquefies* at about -74° , and at the ordinary temperature when subjected to a pressure of 10 to 15 atmospheres; at -85° it is converted into a solid crystalline mass. Liquid sulphuretted hydrogen is most easily obtained by the decomposition of hydrogen polysulphide, which we shall presently describe, by the action of heat, and in the presence of a small amount of water. If poured into a bent tube, like that described for the liquefaction of ammonia (Vol. I. p. 248), the hydrogen polysulphide is decomposed by heat, in the presence of water, into sulphur and sulphuretted hydrogen, which condenses in the cold end of the tube into a colourless liquid. The easy liquefaction of sulphuretted hydrogen is evidently allied to its solubility. One volume of water at 0° dissolves 4.37 volumes of sulphuretted hydrogen, at 10° 3.58 volumes, and at 20° 2.9 volumes.¹⁶ The solutions impart a very feeble red coloration to litmus paper. This gas not only has a very unpleasant odour, but it is poisonous. One part in fifteen hundred parts of air will kill birds. Mammalia die in an atmosphere containing $\frac{1}{200}$ of this gas.

Sulphuretted hydrogen is very easily *decomposed* into its component parts by the action of heat or a series of electric sparks. Hence it is not surprising that sulphuretted hydrogen undergoes change under the action of many substances having a considerable affinity for hydrogen and oxygen. Very many metals¹⁷ evolve hydrogen with sulphuretted

¹⁶ Sulphuretted hydrogen is still more soluble in alcohol than in water; one volume at the ordinary temperature dissolves as much as eight volumes of the gas. The solutions in water and alcohol undergo change, especially in open vessels, owing to the fact that the water and alcohol dissolve oxygen from the atmosphere, and this acts on the sulphuretted hydrogen, forming water and sulphur. The solution may be so altered in this manner that every trace of sulphuretted hydrogen disappears. Solutions of sulphuretted hydrogen in glycerin change much more slowly, and may therefore be kept for a long time as reagents. De Forcrand obtained a hydrate, $\text{H}_2\text{S} \cdot 16\text{H}_2\text{O}$, resembling the hydrates given by many gases. The data given by Caillietet and De Forcrand show that at 30° this crystallo-hydrate breaks up, even under pressure.

¹⁷ Some metals evolve hydrogen from sulphuretted hydrogen at the ordinary tem-

hydrogen, so that in this respect it presents the property of an acid; for instance, $2\text{H}_2\text{S} + \text{Sn} = 2\text{H}_2 + \text{SnS}_2$. This may be taken advantage of for determining the composition of sulphuretted hydrogen, because a given volume then leaves the same volume of hydrogen. On the other hand, oxygen,¹⁸ chlorine,¹⁹ and even iodine decompose sulphuretted hydrogen, removing the hydrogen from it and leaving free sulphur, so that in this reaction the sulphur is replaced by the above-named elements; for example, $\text{H}_2\text{S} + \text{Br}_2 = 2\text{HBr} + \text{S}$. In no other hydrogen compound is it so easy to show the *substitution*, both of hydrogen and of the element combined with it, as in hydrogen sulphide. This clearly shows the feeble union between the elements forming this gas. Compounds containing a considerable amount of oxygen, and which easily part with it, can accomplish the separation of the sulphur very easily. Such are, for instance, nitrous acid, chromic acid, and even ferric oxide and the higher oxides like it. Thus, if sulphuretted hydrogen be passed into a solution of chromic acid or an acid solution of ferric oxide, then the oxygen of the substance in solution acts on the hydrogen of the sulphuretted hydrogen and forms water, *and the sulphur is separated in a free state*. Thus, sulphuretted hydrogen acts as a *reducing agent*, in virtue of the hydrogen it contains. Salts of iodic, chlorous, chloric, and other acids are reduced by sulphuretted hydrogen, their oxygen acting mainly on the hydrogen of the sulphuretted hydrogen; but, in the presence of an excess of a powerful oxidising agent a portion of the sulphur may also be oxidised into sulphurous anhydride. The reducing action of sulphuretted hydrogen is frequently applied in chemical manipulations for the preparation of lower oxides, and for the conversion of certain oxygen compounds into hydrogen compounds; thus, the higher oxides of nitrogen are converted into ammonia by it, and in the presence of alkalis the nitro-compounds are converted into ammonia derivatives. The reaction of sulphuretted

perature. For example, the light metals, and copper and silver (especially with the access of air?) among the heavy metals. Hence articles made of silver turn black in the presence of vapours containing sulphuretted hydrogen, because silver sulphide is black. Mercury also decomposes sulphuretted hydrogen at the ordinary temperature, but slowly, like the above two metals, and therefore although sulphuretted hydrogen may be collected over mercury, it cannot be kept along with it. Zinc and cadmium act at a red heat, but not completely.

¹⁸ If sulphuretted hydrogen escapes from a fine orifice into the air, it will burn when lighted, and be transformed into sulphurous anhydride and water. But if it burns in a limited supply of air—for instance, when a cylinder is filled with it and lighted—then only the hydrogen burns, which has, judging from the amount of heat developed in its combustion and from all its properties, a greater affinity for oxygen than sulphur. In this respect the combustion of sulphuretted hydrogen resembles that of hydrocarbons.

¹⁹ Hence bleaching powder and chlorine destroy the stench of sulphuretted hydrogen. (For the reaction of hydrogen sulphide and iodine, *see* Vol. I. p. 498.)

hydrogen on sulphurous anhydride belongs to this class of phenomena, the chief products of which are sulphur and water, $2\text{H}_2\text{S} + \text{SO}_2 = 2\text{H}_2\text{O} + \text{S}_3$.

The acid character of sulphuretted hydrogen is clearly seen in its action on alkalis and salts. Thus free lead oxide and its salts in the presence of sulphuretted hydrogen form water or an acid (if a salt were taken), and sulphide of lead: $\text{PbX}_2 + \text{H}_2\text{S} = \text{PbS} + 2\text{HX}$. This reaction even proceeds in the presence of powerful acids, because lead sulphide is one of those sulphides which are unacted on by acids, and the reaction proceeds to the end in solutions. This reaction is taken advantage of for the preparation of many acids, by first converting them into a lead salt, and then submitting this salt to the action of sulphuretted hydrogen. For example, lead formate with sulphuretted hydrogen gives formic acid and lead sulphide: $\text{C}_2\text{H}_2\text{PbO}_4 + \text{H}_2\text{S} = \text{PbS} + 2\text{CH}_2\text{O}_2$. But sulphuretted hydrogen acts in a similar manner also on a number of metallic acid substances in solution or in an anhydrous state: (1) if it does not reduce the acid; (2) if the sulphur compound corresponding with the anhydride of the acid be insoluble in water, the reaction proceeds in solutions; (3) if the sulphuretted hydrogen and the acid taken do not come in contact with an alkali, on which they would be able to act first; and (4) if the sulphur compound be not decomposed by water. Thus solutions of arsenious acid give a precipitate of arsenious sulphide, As_2S_3 , with sulphuretted hydrogen. This reaction proceeds not only in the presence of water, but also of acids, because the latter do not decompose the resultant sulphur compounds. The type of the decomposition is the same as with bases—that is, the sulphur and oxygen change places: $\text{RO}_n + n\text{H}_2\text{S} = \text{RS}_n + n\text{H}_2\text{O}$. Some sulphides corresponding with acid anhydrides are decomposed by water, and therefore are not formed in the presence of water. Such, for example, are the sulphides of phosphorus.²⁰

²⁰ The sulphide P_4S is obtained by cautiously fusing the requisite proportions of common phosphorus and sulphur under water; it is a liquid which solidifies at 0° , and may be distilled without undergoing change, but it fumes in air and easily takes fire. The higher sulphide, P_2S_5 , has similar properties. But little heat is evolved in the formation of these compounds, and it may be thought that they are formed by the direct conjunction of whole molecules of phosphorus and sulphur; but if the proportion of sulphur be increased, the reaction is accompanied by so considerable a rise of temperature that an explosion takes place, and for the sake of safety red phosphorus must be used and mixed as intimately as possible with powdered sulphur and heated in an atmosphere of carbonic anhydride. The higher compounds are decomposed by water. By increasing the proportion of sulphur, the following compounds have been obtained: P_4S_3 as prisms (fuses at 165° , Rebs), soluble in carbon bisulphide, and unaltered by air and water; *phosphorus trisulphide*, P_2S_5 , is the analogue of P_2O_5 ; it is a light yellow crystalline compound only slightly soluble in carbon bisulphide, fusible and volatile and decomposed into hydrogen sulphide and phosphorous acid by water, and, like the highest compound of

The metallic sulphides corresponding with the metallic oxides have either a feeble alkaline or a feeble acid character, according to the character of the corresponding oxide, and therefore by combining together they are able to form saline substances—that is, salts in which the oxygen is replaced by sulphur. Thus sulphuretted hydrogen having the properties of a feeble acid²¹ has, at the same time, the properties of water, and forms the type of the sulphur derivatives, which may also be formed by means of sulphuretted hydrogen, just as the oxides may be formed by the aid of water. But as sulphuretted hydrogen has acid properties, it combines more easily with the basic

sulphur and phosphorus, P_2S_5 , it forms thio- salts with potassium sulphide, &c. This *phosphorus pentasulphide* corresponds with phosphoric anhydride; like the trisulphide, it gives hydrogen sulphide and phosphoric acid with an excess of water. It reacts in many respects like phosphoric chloride. The sulphide PS_2 is also known; the vapour density of this compound seems to indicate a molecule P_2S_6 .

Phosphorus sulphochloride, $PSCl_5$, corresponds with phosphorus oxychloride. It is a colourless, pleasant-smelling liquid, boiling at 124° , and of sp. gr. 1.63; it fumes in air and is decomposed by water: $PSCl_5 + 4H_2O = PH_3O_4 + H_2S + 8HCl$. It is obtained when phosphoric chloride is treated with hydrogen sulphide, hydrochloric acid being also formed: it is also formed by the action of phosphoric chloride on certain sulphides—for example, on antimonious sulphide, also by the (cautious) action of phosphorus on sulphur chloride: $2P + 8S_2Cl_2 = 2PSCl_5 + 4S$, and even in the reaction $3PCl_5 + SOCl_2 = PCl_5 + POCl_3 + PSCl_5$, showing the reducing action of phosphorus trichloride, which is especially clear in the reaction $SO_2 + PCl_5 = SO_2 + POCl_3$. Thorpe and Rodger (1889), by heating lead fluoride with phosphorus pentasulphide, obtained thiophosphoryl fluoride as a colourless, spontaneously-inflammable gas.

²¹ In characterising the acid properties of sulphuretted hydrogen it is very important, however, to remark that sulphuretted hydrogen, like water, does not saturate the alkaline properties of alkali hydroxides, so that a solution of potassium hydroxide will not under any circumstances give a neutral liquid with sulphuretted hydrogen. In this case the sulphuretted hydrogen forms in solution only an acid salt with the potassium: $KHO + H_2S = KHS + H_2O$. One must suppose that the normal salt is not formed in the solution—that is, that the reaction $2KHO + H_2S = K_2S + 2H_2O$ does not take place. This is seen from the fact that a development of heat, depending on the formation of potassium hydrosulphide, KHS , is remarked when as much hydrogen sulphide is passed into a solution of potassium hydroxide as it will absorb. But if a further quantity of potassium hydroxide be added to the resultant solution, heat is not developed, whilst if alkali be added to potassium acid sulphate or sodium acid carbonate heat is developed. From this it must not be concluded (as Thomsen concludes) that hydrogen sulphide is a monobasic acid. The impropriety of this conclusion is not only seen from the decomposing action of water on potassium sulphide, but also from the fact that for the formation of this salt there must react ($KHS + KHO = K_2S + H_2O$) substances which closely resemble each other, and in such cases hardly any heat is developed—for example, in double decompositions between salts. The resultant substances, potassium sulphide and water, undoubtedly act on each other, and thus would cause the absorption of heat did not the reaction of potassium hydrosulphide with potassium hydroxide also develop heat. Furthermore, it must be taken into account that potassium oxide, K_2O , and the anhydrous oxides like it, also do not exist in solutions, and whenever they might be formed they immediately react with the water, forming caustic potash, KHO , &c. In this sense, directly potassium sulphide, K_2S , is formed in water it is decomposed into potassium hydroxide and hydrosulphide: $K_2S + H_2O = KHO + KHS$. Potassium sulphide, K_2S , in a solid state corresponds with K_2O , although neither can exist in solution.

metallic sulphides. Hence, for instance, there exists a compound of sulphuretted hydrogen with potassium sulphide, potassium hydrosulphide, $2\text{KHS}=\text{K}_2\text{S}+\text{H}_2\text{S}$, just as there are potassium hydroxides; but there are scarcely any compounds of sulphuretted hydrogen with the sulphides corresponding with acids. Thus sulphuretted hydrogen corresponds with the sulphides of the metals, and these may be regarded either as salts of sulphuretted hydrogen or as oxides of the metals in which the oxygen is replaced by sulphur. In general terms the sulphides exhibit the same degrees of difference with respect to their solubility in water as do the oxides. Thus the oxides of the alkali metals, and of some of the metals of the alkaline earths, are soluble in water, whilst those of nearly all the other metals are insoluble. The same may be said as to the sulphides; the sulphides of the metals of the alkalis and of the alkaline earths are soluble in water, whilst those of the other metals are insoluble. Those metals, like aluminium, whose oxides—for example, Al_2O_3 —have intermediate properties and do not form compounds with feeble acids, at least in a wet way, also do not form sulphides by this method, although these may be obtained indirectly. The sulphides of the other metals are even formed in a wet way, and with particular ease if they are insoluble in water. In this case their salts enter into double decomposition with sulphuretted hydrogen, or with soluble sulphides, and give an insoluble sulphide—for instance, a salt of lead gives lead sulphide with sulphuretted hydrogen. The sulphuretted hydrogen then separates the metal from its salts in a state of combination with sulphur, if the corresponding sulphide be insoluble in acid, as, for example, lead sulphide. This depends on the fact that by the action of sulphuretted hydrogen on a salt of such a metal, a free acid must be formed besides the metallic sulphide. Thus if a metal M be in a state of combination MX_2 , then by the action of sulphuretted hydrogen there will be formed, besides MS ,²² an acid 2HX . It is evident that sulphuretted hydrogen will not precipitate an insoluble sulphide from the salts of those metals whose sulphides react with free acid, such as

²² During the last seven years (Schulze, 1882) it has been found that many metallic sulphides which were considered totally insoluble do, under certain circumstances, form very unstable solutions in water, as has been mentioned in Vol. I. p. 96, Note 57. To what has already been mentioned in that note it is impossible to add anything more definite than that a colloidal state and a passage into solution are also known for many oxides (silica, alumina, stannic oxide, molybdic acid, and others), and the analogy of the phenomena of this class leads one to hope for the appearance of further generalisation and systematic research in this direction. Arsenic sulphide is very easily obtained in the form of a solution (hydrosol). Solutions of copper and cadmium sulphides may also be easily obtained by precipitating their salts CuX_2 , or CdX_2 , with ammonium sulphide, and washing the precipitate; but they are re-precipitated by the addition of foreign salts.

zinc, iron, manganese, &c., because free acid would be formed by the reaction of the sulphuretted hydrogen, and would be able to act on the sulphide formed. The reaction $\text{FeCl}_2 + \text{H}_2\text{S} = \text{FeS} + 2\text{HCl}$, and the like, do not take place, because the acid acts on the ferrous sulphide. Antimonious sulphide is not acted on by dilute hydrochloric acid, but it is decomposed by strong acid, and therefore in presence of an excess of hydrochloric acid antimonious chloride does not entirely react with hydrogen sulphide, whilst the reaction $2\text{SbCl}_3 + 3\text{H}_2\text{S} = \text{Sb}_2\text{S}_3 + 6\text{HCl}$ will go on to the end in a dilute solution and with a small quantity of acid. Those metallic sulphides which are decomposed by acids may be obtained in a wet way by the double decomposition of the salts of the metals, not with hydrogen sulphide, but with soluble metallic sulphides, such as sulphide of ammonium or of potassium, because then no free acid is formed, but a salt of the metal (potassium or ammonium) which was taken as a soluble sulphide. So, for example, $\text{FeCl}_2 + \text{K}_2\text{S} = \text{FeS} + 2\text{KCl}$.²³

²⁵ In reality, the preceding reaction should be expressed thus: $\text{FeCl}_2 + 2\text{KHS} = \text{FeS} + 2\text{KCl} + \text{H}_2\text{S}$. But as the sulphuretted hydrogen takes no part in the reaction, it is usual to express the formation of such sulphides without taking the hydrogen sulphide proceeding from the potassium or ammonium hydrosulphides into account. It is not usual to employ potassium sulphide but ammonium sulphide—or, to speak more truly, ammonium hydrosulphide—in order to avoid the formation of a non-volatile salt of potassium in the solution, and to have, together with the formation of the sulphide, a salt of ammonium in solution, which can always be driven off by evaporating the solution and igniting the residue—for instance:



Thus the metallic sulphides may be divided into three chief classes: (1) *those soluble in water*, (2) *those insoluble in water but reacting with acids*, and (3) *those insoluble in both water and acids*. The third class may be easily subdivided into two groups; to the first group belong those sulphides which correspond with bases or basic oxides, and are therefore unable to play the part of an acid with the sulphides of the alkalis, and are insoluble in the alkali sulphides; whilst the sulphides of the second group are of an acid character, and give soluble salts with the sulphides of the alkaline metals, in which they play the part of an acid. To this group belong those metals whose corresponding oxides have very feeble basic properties or sharply-defined acid properties. It must be observed, however, that not all metallic acids have corresponding sulphides, partly owing to the fact that certain acids are reducible by sulphuretted hydrogen, especially when their lower degrees of oxidation are of a basic character. Such are, for instance, the acids of chromium, manganese, &c. Sulphuretted hydrogen converts them into lower oxides, having the properties of bases. Those bases which do not combine with feeble acids, such as carbonic acid and hydrogen sulphide, give a precipitate of hydroxide with ammonium sulphide—for example, aluminium salts react in this manner. Thus aluminium sulphide, Al_2S_3 , is decomposed by water, and magnesium sulphide, MgS , gives magnesium hydrosulphide, $\text{Mg}(\text{SH})_2$, and hydroxide, MgH_2O_2 , with water. This difference of the metals in their behaviour towards sulphuretted hydrogen gives a very valuable means of separating them from each other, and is taken advantage of in analytical chemistry. If, for instance, the metals of the first and third groups occur together, it is enough to convert them into soluble salts, and to act on the solution of the salts with sulphuretted hydrogen; it will precipitate the

Metallic sulphides may be obtained by many other means besides the action of sulphuretted hydrogen on salts and oxides, or by the simple combination of metals with sulphur when heated or fused. Thus they may also be formed by the reduction of sulphates by heating them with charcoal or other means. Charcoal takes up the oxygen from many sulphates, leaving corresponding sulphides. Thus sodium sulphate, Na_2SO_4 , when heated with charcoal, forms sodium sulphide, Na_2S , carbonic oxide and carbonic anhydride being evolved. Besides which metallic sulphides are also obtained by heating metals or their oxides in the vapours of many sulphur compounds—for example, in the vapour of carbon bisulphide, when the carbon takes up the oxygen of the oxide and the sulphur combines with the metal. The sulphides formed in this manner are often crystalline—that is, appear with those properties and in that crystalline form in which they occur in nature. Besides which we must mention the following general reactions common to all the sulphides of the metals. They are oxidised in air at the

metals of the third group in the form of sulphides, whilst the metals of the first group will not be in the least acted on. Such a method of separating the metals is more fully considered in analytical chemistry, and therefore we will here limit ourselves to pointing out to which groups the most common metals belong, and the colour which is proper to the sulphide precipitated.

Metals which are precipitated by sulphuretted hydrogen, as sulphides from a solution of their salts, even in the presence of free acid :

The precipitate is soluble in ammonium sulphide :

<i>Platinum</i> (dark brown)		<i>Antimony</i> (orange)
<i>Gold</i> (dark brown)		<i>Arsenic</i> (yellow).
<i>Tin</i> (yellow and brown)		

The precipitate is insoluble in ammonium sulphide :

<i>Copper</i> (black)		<i>Mercury</i> (black)
<i>Silver</i> (black)		<i>Lead</i> (black).
<i>Cadmium</i> (yellow)		

Metals which are precipitated by ammonium sulphide from neutral solutions, but not precipitated from acid solutions by sulphuretted hydrogen :

The sulphide precipitated is soluble in hydrochloric acid :

<i>Zinc</i> (white)		<i>Manganese</i> (rose colour)		<i>Iron</i> (black)
---------------------	--	--------------------------------	--	---------------------

The sulphide precipitated is not soluble in dilute hydrochloric acid :

<i>Nickel</i> (black)		<i>Cobalt</i> (black)
-----------------------	--	-----------------------

A hydroxide, and not a sulphide, is precipitated :

<i>Chromium</i> (green)		<i>Aluminium</i> (white).
-------------------------	--	---------------------------

The metals of the alkalis and of the alkaline earths are not precipitated by either sulphuretted hydrogen or ammonium sulphide. The metals of the alkaline earths when in acid solutions in the form of phosphates and many other salts are precipitated by ammonium sulphide, because it neutralises the free acid, with formation of an ammonium salt of the acid and evolution of sulphuretted hydrogen.

ordinary, and especially at a higher, temperature, forming sulphates in the majority of cases. This oxidation proceeds with particular ease, even at the ordinary temperature, when a metallic sulphide is precipitated from its solutions, as a fine powder containing water. The sulphides of iron and manganese, &c., are very easily oxidised in this manner. But if these hydrates be ignited, they lose their water (the ignition must be carried on in a stream of hydrogen to prevent their oxidation during the process), and then they are no longer oxidised at the ordinary temperature. Those sulphides whose corresponding sulphates are decomposed by heat part with their sulphur in the form of sulphurous anhydride, when they are ignited in air, and the metal, as a rule, remains behind as oxide. This is taken advantage of in the treatment of sulphurous ores. The process is called *roasting*.

Hydrogen not only forms sulphuretted hydrogen with sulphur, but it also combines with it in several other proportions, just as it combines with oxygen, forming not only water, but also hydrogen peroxide. And these *polysulphides of hydrogen* are also unstable, like hydrogen peroxide, and are also obtained from the corresponding polysulphides of the metals of the alkaline earths, just as hydrogen peroxide is obtained from barium peroxide—that is, from a polyoxygen compound. Thus calcium combines with sulphur in several proportions, forming not only calcium sulphide, CaS , but also as bi-, tri-, and pentasulphide, CaS_5 , and all these compounds are soluble in water. Sodium also combines with sulphur in the same proportions, forming sulphides from Na_2S to Na_2S_5 . If an acid is added to a solution of a polysulphide, it gives sulphur, sulphuretted hydrogen, and a salt of the metal. For instance, with a pentasulphide: $\text{MS}_5 + 2\text{HCl} = \text{MCl}_2 + \text{H}_2\text{S} + 4\text{S}$. If we reverse the operation, and pour a solution of a polysulphide into an acid, then sulphur is not precipitated, but an oily liquid is formed, which is heavier than water and insoluble in it. This oily substance is the polysulphide of hydrogen: $\text{MS}_5 + 2\text{HCl} = \text{MCl}_2 + \text{H}_2\text{S}_5$. As Rebs showed (1888), whatever polysulphide be taken—of sodium, for instance—it always gives one and the same *hydrogen pentasulphide*,²¹ of specific gravity 1.71 (15°). It can only be preserved in the absence of water and at low temperatures, and then not for long; for, especially

²¹ Rebs took di-, tri-, tetra-, and penta-sulphides of sodium, potassium, and barium, which he prepared by dissolving sulphur in solutions of the normal sulphides; on adding hydrochloric acid he always obtained hydrogen pentasulphide, whence it is evident that $4\text{H}_2\text{S}_n = (n-1)\text{H}_2\text{S}_5 + (5-n)\text{H}_2\text{S}$. For example, if H_2S_2 were formed, it would decompose according to the equation $4\text{H}_2\text{S}_2 = \text{H}_2\text{S}_5 + 3\text{H}_2\text{S}$. The hydrogen pentasulphide formed breaks up into hydrogen sulphide and sulphur when brought into contact with water. Previous to Rebs' researches many chemists stated that all polysulphides gave the bisulphide H_2S_2 , and Hofman recognised only hydrogen tri-sulphide, H_2S_3 .

in the presence of alkalis and when slightly warmed, it splits up very easily into sulphuretted hydrogen and sulphur.²⁵

The soluble sulphides and polysulphides of the metals of the alkalis and alkaline earths—for example, of ammonium,²⁶ potassium,²⁷ and

²⁵ The formation of the polysulphides of hydrogen, H_2S_n , is easily understood from the law of substitution, like that of the saturated hydrocarbons, C_nH_{2n+2} , knowing that sulphur gives H_2S and carbon CH_4 , because the molecule of sulphuretted hydrogen may be divided into H and HS. This radicle, HS, is equivalent to H. But substituting this radicle for hydrogen in H_2S we obtain $(HS)HS = H_2S_2$, $(HS)(HS)S = H_2S_3$, &c., in general H_2S_n . The homologues of CH_4 , C_nH_{2n+2} are thus formed from CH_4 , and consequently the polysulphides H_2S_n are the homologues of H_2S . The question arises why in H_2S_n the the apparent limit of n is 5—that is, why does the substitution end with the formation of H_2S_5 ? The answer appears to me to be clearly because in the molecule of sulphur, S_8 , there are six atoms of sulphur. The forces in one and the other case are the same. In the one case they hold S_8 together, in the other S_3 and H_2 ; and, judging from H_2S , the two atoms of hydrogen are equal in power and significance to the atom of sulphur. Just as hydrogen peroxide, H_2O_2 , expresses the composition of ozone, O_3 , in which O is replaced by H_2 , so also H_2S_5 corresponds with S_6 .

²⁶ *Ammonium sulphide*, $(NH_4)_2S$, may be prepared by passing sulphuretted hydrogen into a vessel full of dry ammonia, or if both dry gases be passed together into a very cold receiver. In the latter case it is necessary to prevent the access of air, and to have an excess of ammonia. Under these circumstances, two volumes of ammonia combine with one volume of sulphuretted hydrogen, and form a colourless, very volatile, crystalline substance having a very unpleasant odour, and which is very poisonous and exceedingly unstable. When exposed to the air it absorbs oxygen and acquires a yellow colour, and already contains oxygen and polysulphide compounds (because a portion of the hydrogen sulphide gives water and sulphur). It is soluble in water, and forms a colourless solution, which, however, in all probability contains free ammonia and the acid salt—that is, ammonium hydrosulphide, NH_4HS , or $(NH_4)_3S_2H_2S$. This salt is formed when dry ammonia is mixed with an excess of dry sulphuretted hydrogen. When both gases come into contact at the ordinary or a higher temperature, they always combine in equal volumes: $(NH_4)HS = NH_3 + H_2S$. This compound crystallises in an anhydrous state in colourless plates, and may be easily volatilised (dissociating like ammonium chloride), even at the ordinary temperature; it has an alkaline reaction, absorbs oxygen from the air, is soluble in water, and its solution is usually prepared by saturating an aqueous solution of ammonia with sulphuretted hydrogen. According to the common rule, these salts, like other ammonium salts, split up into ammonia and sulphuretted hydrogen when they are distilled.

A solution of ammonium sulphide is able to dissolve sulphur, and it then contains compounds of hydrogen polysulphide and ammonia. Some of these compounds may be obtained in a crystalline form. Thus Fritzsche obtained a compound of ammonia with hydrogen pentasulphide, or ammonium pentasulphide, $(NH_4)_2S_5$, in the following manner. He saturated an aqueous solution of ammonia with sulphuretted hydrogen, added powdered sulphur to it, and then passed ammonia gas into the solution, which then absorbed a fresh amount. After this he again passed sulphuretted hydrogen into the solution, and then added sulphur, and then again ammonia. After repeating this several times, orange-yellow crystals separated out from the liquid. These crystals melted at 40° to 50° , and were very unstable.

When a solution of ammonium hydrosulphide, prepared by saturating a solution of ammonia with sulphuretted hydrogen, is exposed to the air it turns yellow, owing to the presence of an ammonium polysulphide, whose formation is due to the sulphuretted hydrogen being oxidised by the air and converted into water and sulphur, which is dis-

²⁷ See page 213.

calcium,²⁸—have the appearance and properties of salts, just as the

solved by the ammonium sulphide. In certain analytical reactions it is usual to employ a solution of ammonium sulphide which has been kept for some time and acquired a yellow colour. This yellow sulphide of ammonium deposits sulphur when saturated with acids, whilst a freshly-prepared solution only evolves sulphuretted hydrogen. The yellow solution furthermore contains ammonium thiosulphate, which is derived not only from the oxidation of the ammonium sulphide, but also from the action of the liberated sulphur on the ammonia, just as an alkaline salt of thiosulphuric acid and a sulphide are formed by the action of sulphur on a solution of a caustic alkali.

²⁷ *Potassium sulphide*, K_2S , is obtained by heating a mixture of potassium sulphate and charcoal to a bright-red heat. It may be prepared in solution by taking a solution of potassium hydroxide, dividing it into two equal parts, and saturating one portion with sulphuretted hydrogen so long as it is absorbed. This portion will then contain the acid salt KHS. The two portions are then mixed together, and the potassium sulphide will then be obtained in the solution. This solution has a strongly alkaline reaction, and is colourless when freshly prepared, but it very easily undergoes change when exposed to the air, forming potassium thiosulphate and polysulphides. When the solution is evaporated at low temperatures under the receiver of an air-pump, it yields crystals containing $K_2S_5 \cdot 5H_2O$. If left under the receiver of the air-pump, or heated at 150° , they part with 3 mol. H_2O , and at higher temperatures they lose nearly all their water without evolving sulphuretted hydrogen. When they are ignited in glass vessels they corrode the glass. When a solution of caustic potash, perfectly saturated with sulphuretted hydrogen, is evaporated under the receiver of an air-pump it forms colourless rhombohedra of *potassium hydrosulphide*, $2(KHS) \cdot H_2O$. These crystals are deliquescent in the air, but do not change in a vacuum when heated up to 170° , and at higher temperatures they lose water but do not evolve sulphuretted hydrogen. The anhydrous compound, KHS, fuses at a dark-red heat into a very mobile yellow liquid, which gradually becomes darker in colour and solidifies into a red mass. It is remarkable that when a solution of the compound KHS is boiled it somewhat easily evolves half of its sulphuretted hydrogen, leaving potassium sulphide, K_2S , in solution; and a solution of the latter in water is also able to evolve sulphuretted hydrogen under prolonged boiling, but the evolution cannot be rendered complete, and therefore, with a certain rise of temperature, a solution of potassium sulphide will not be capable of absorbing sulphuretted hydrogen at all. From this we must conclude that potassium hydroxide, water, and sulphuretted hydrogen form a system whose complex equilibrium is subject to the laws of dissociation, depends on the relative mass of each substance, on the temperature, and the dissociation pressure of the component elements. Potassium sulphide is not only soluble in water, but also in alcohol.

Berzelius showed that besides potassium sulphide there exists potassium bisulphide, K_2S_2 ; trisulphide, K_2S_3 ; tetrasulphide, K_2S_4 ; and pentasulphide, K_2S_5 . According to the researches of Schöne, the three last are the most stable. These different compounds of potassium and sulphur may be prepared by fusing potassium hydroxide or carbonate with an excess of sulphur in a porcelain crucible in a stream of carbonic anhydride. At about 600° potassium pentasulphide is formed; this is the highest sulphur compound of potassium. When heated to 800° it loses one-fifth of its sulphur and gives the tetrasulphide, which at this temperature is as stable as the pentasulphide is at the lower temperature—that is, sulphur is not given off by it at this temperature. At a bright-red heat—namely, at about 900° —the trisulphide is formed. This compound may be also formed by igniting potassium carbonate in a stream of carbon bisulphide, in which case a compound, K_2CS_3 , is first formed corresponding to potassium carbonate, and carbonic anhydride is evolved. On further ignition this compound splits up into carbon and potassium trisulphide, K_2S_3 . The tetrasulphide may also be obtained in solution if a solution of potassium sulphide be boiled with the requisite amount of sulphur without

²⁸ See page 214.

hydrated oxides have the same appearance, whilst the sulphides of

the access of air. This solution yields red crystals of the composition $K_2S_4 \cdot 2H_2O$ when it is evaporated in a vacuum. These crystals are very hygroscopic, easily soluble in water, but very sparingly in alcohol; when ignited they give off water, sulphuretted hydrogen, and sulphur. If a solution of potassium sulphide be boiled with an excess of sulphur it forms the pentasulphide, which, however, is decomposed by prolonged ebullition into sulphuretted hydrogen and potassium thiosulphate: $K_2S_5 + 3H_2O = K_2S_2O_3 + 3H_2S$. A substance called *liver of sulphur* was formerly frequently used in chemical practice and medicine. Under this name is known the substance which is formed by boiling a solution of caustic potash with an excess of flowers of sulphur. This solution contains a mixture of potassium pentasulphide and thiosulphate, $6KHO + 12S = 2K_2S_5 + K_2S_2O_3 + 3H_2O$. The substance obtained by fusing potassium carbonate with an excess of sulphur was also known as liver of sulphur. If this mixture be heated to an incipient dark-red heat it will contain potassium thiosulphate, but at higher temperatures potassium sulphate is formed. In either case a polysulphide of potassium is also present.

²⁸ The metals of the alkaline earths, like those of the alkalis, form several compounds with sulphur; thus calcium forms compounds with one and with five atoms of sulphur. There are doubtless also intermediate sulphides, because the other metals of the alkaline earths form compounds with four and three atoms of sulphur. If sulphuretted hydrogen be passed over ignited lime it forms water and *calcium sulphide*, which may also be formed by heating calcium sulphate with charcoal, whilst if sulphur be heated with lime or with calcium carbonate, then naturally oxygen compounds (calcium thiosulphate and sulphate) are formed at the same time as calcium sulphide. The prolonged action of the vapour of carbon bisulphide, especially when mixed with carbonic anhydride, on strongly ignited calcium carbonate entirely converts it into sulphide. Calcium sulphide is generally obtained as a colourless, or slightly yellow, opaque, brittle mass, which is infusible at a white heat, and is soluble in water. When heated, dry calcium sulphide does not absorb oxygen from the air. An excess of water decomposes it, like many other metallic sulphides, precipitating lime and forming a hydrosulphide, CaH_2S_2 , in solution. This compound is also formed by passing sulphuretted hydrogen through an aqueous solution of calcium sulphide or lime. Its solution, like that of calcium sulphide, has an alkaline reaction. It decomposes when evaporated, and absorbs oxygen from the air. *Calcium pentasulphide*, CaS_5 , is not known in a pure state, but may be obtained in admixture with calcium thiosulphate by boiling a solution of lime or calcium sulphide with sulphur: $3CaH_2O_2 + 12S = 2CaS_5 + CaS_2O_3 + 3H_2O$. A similar compound in an impure form is formed by the action of air on alkali waste, and is used for the preparation of thiosulphates.

Many of the sulphides of the metals of the alkaline earths are phosphorescent—that is, they have the faculty of *emitting light in the dark*, after having been subjected to the action of sunlight, or of a bright source of light in general (Canton phosphorus, &c.). The luminosity lasts some time, but it is not durable, and gradually disappears. This faculty of being phosphorescent is proper, in a greater or less degree, to nearly all substances (Becquerel), but for a very short time, whilst with calcium sulphate it is comparatively durable, lasting for several hours. It is due to the excitation of the surfaces of substances by the action of light, and is determined by those rays which exhibit a chemical action. Hence daylight or the light of burning magnesium, &c., acts more powerfully than the light of a lamp, &c. Warnerke has recently shown that a small quantity of magnesium lighted near the surface of a phosphorescent substance rapidly excites the greatest possible intensity of luminosity; this enabled him to find a method of measuring the intensity of light—*i.e.*, to obtain a constant unit of light—and to apply it to photography. The nature of the change which is accomplished on the surface of the luminous substance is at present unknown, but in any case it is a renewable one, because the experiment may be repeated for an infinite number of times and takes place in a vacuum. The intensity and tint of the light emitted depend on the method of preparation of the calcium sulphide, and on the degree of ignition and purity of the calcium

the metals of the higher groups resemble their oxides and have not at all the appearance of salts, and this is especially true in the crystalline forms in which they frequently occur in nature.²⁹

carbonate taken. According to the observations of Becquerel, the presence of compounds of manganese, bismuth, &c., sodium sulphide (but not potassium sulphide), &c., although in minute traces, is perfectly indispensable. This gives reason for thinking that the formation (in the dark) and decomposition (in light) of double salts like $\text{MnS}_2\cdot\text{Na}_2\text{S}$ perhaps forms the chemical cause of the phenomena. Compounds of strontium and barium have this property to even a greater extent than calcium sulphide. These compounds may be prepared as follows. For example, a mixture of sodium thiosulphate and strontium chloride is prepared; a double decomposition takes place between the salts, and, on the addition of alcohol, strontium thiosulphate, $\text{SrS}_2\cdot\text{O}_5$, is precipitated, which, when ignited, leaves strontium sulphide behind. The strontium sulphide thus prepared emits (when dry) a greenish yellow light. It contains a certain amount of sulphur, sodium sulphide, and strontium sulphate. By ignition at various temperatures, and by different methods of preparation, it is possible to obtain mixtures which emit different coloured lights.

²⁹ As examples, we will describe the sulphides of arsenic, antimony, and mercury. Arsenic trisulphide, or *orpiment*, As_2S_3 , occurs native, and is formed in a pure form when a solution of arsenious anhydride in the presence of hydrochloric acid comes into contact with sulphuretted hydrogen (there is no precipitate in the absence of free acid). A beautiful yellow precipitate is then obtained: $\text{As}_2\text{O}_3 + 3\text{H}_2\text{S} = 3\text{H}_2\text{O} + \text{As}_2\text{S}_3$; it fuses when heated, and volatilises without decomposition. When fused it forms a semi-transparent, yellow mass, and it is thus that it enters the market. The specific gravity of native orpiment is 3.4, and that of the artificially-fused mass is 2.7. It is used as a yellow pigment, and owing to its insolubility in water and acids it is less injurious than the other compounds corresponding to arsenious acid. According to the type AsX_3 , realgar, AsS , is known, but it is probable that the true composition of this compound is As_4S_4 —that is, it presents the same relation to orpiment as liquid phosphuretted hydrogen does to gaseous. *Realgar* (*Sandaraca*) occurs native as brilliant red crystals of specific gravity 3.59, and may be prepared artificially by fusing arsenic and sulphur in the proportions indicated by its formulæ. It is prepared in large quantities by distilling a mixture of sulphur and arsenical pyrites. Like orpiment it dissolves in calcium sulphide, and even in caustic potash. It is used for signal lights and fireworks, because it deflagrates and gives a large and very brilliant white flame with nitre.

With antimony, sulphur gives a tri- and a penta-sulphide. The former, Sb_2S_3 , which corresponds with antimonious oxide, occurs native (Chap. XIX.) in a crystalline form; its sp. gr. is then 4.9, and it presents brilliant rhombic crystals of a grey colour, which fuse when heated. A substance of the same composition is obtained as an amorphous orange powder by passing sulphuretted hydrogen into an acid solution of antimonious oxide. In this respect antimonious oxide again reacts like arsenious acid, and the sulphides of both are soluble in ammonium and potassium sulphides, and, especially in the case of arsenious sulphide, are easily obtained in colloidal solutions. By prolonged boiling with water, antimonious sulphide may be entirely converted into the oxide, hydrogen sulphide being evolved (Elbers). Native antimony sulphide, or the orange precipitated trisulphide when fused with dry, or boiled with dissolved, alkalis, forms a dark-coloured mass (Kermes mineral) formerly much used in medicine, and which contains a mixture of antimonious sulphide and oxide. There are also compounds of these substances. A so-called antimony vermilion is much used as a dye; it is prepared by boiling sodium thiosulphate (six parts) with antimony trichloride (five parts) and water (fifty parts). This substance probably contains an oxysulphide of antimony—that is, a portion of the oxygen in the oxide of antimony in it is replaced by sulphur. Red antimony ore, and antimony glass, which is obtained by fusing the trisulphide with antimonious oxide, has a similar composition, Sb_2OS_2 . In practice, the *antimony penta-*

As the acids corresponding with chlorine, phosphorus, and carbon are the oxidised hydrogen compounds of these elements, so also we can form an idea of the acid hydrates of sulphur, or of *the normal acids of*

sulphide, Sb_2S_3 , is the most frequently used of the sulphur compounds of antimony. It is formed by the action of acids on the so-called Schlippe's salt, which is a *sodium thiorthantimonate*, $\text{SbS}(\text{NaS})_3$, corresponding with orthantimonic acid, $\text{SbO}(\text{OH})_3$, with the replacement of oxygen by sulphur. It is obtained by boiling finely-powdered native antimony trisulphide with twice its weight of sodium carbonate, and half its weight of sulphur and lime, in the presence of a considerable quantity of water. The processes taking place are as follows:—The sodium carbonate is converted into hydroxide by the lime, and then forms sodium sulphide with the sulphur; the sodium sulphide then dissolves the antimony sulphide, which in this form already combines with the greatest amount of sulphur, so that a compound is formed corresponding with antimony pentasulphide dissolved in sodium sulphide. The solution is filtered and crystallised, care being taken to prevent access of air, which oxidises the sodium sulphide. This salt crystallises in large, yellowish crystals, which are easily soluble in water and have the composition $\text{Na}_3\text{SbS}_4 \cdot 9\text{H}_2\text{O}$. When heated they lose their water of crystallisation and then fuse without alteration; but when in solution, and even in crystalline form, this salt turns brown in air, owing to the oxidation of the sulphur and the breaking up of the compound. As it is used in medicine, especially in the preparation of antimony pentasulphide, it is kept under a layer of alcohol, in which it is insoluble. Acids precipitate antimony pentasulphide from a solution of this salt, as an orange powder, insoluble in acids and very frequently used in medicine. This substance when heated evolves vapours of sulphur, and leaves antimony trisulphide behind.

Mercury forms compounds with sulphur of the same types as it does with oxygen. Mercurous sulphide, Hg_2S , easily splits up into mercury and mercuric sulphide. It is obtained by the action of potassium sulphide on mercurous chloride, and also by the action of sulphuretted hydrogen on solutions of salts of the type HgX . Mercuric sulphide, HgS , corresponding with the oxide, is *cinnabar*; it is obtained as a black precipitate by the action of an excess of sulphuretted hydrogen on solutions of mercuric salt. It is insoluble in acids, and is therefore precipitated in their presence. If a certain amount of water containing sulphuretted hydrogen be added to a solution of mercuric chloride, it first gives a white precipitate of the composition $\text{Hg}_3\text{S}_2\text{Cl}_2$ —that is, a compound $\text{HgCl}_2 \cdot 2\text{HgS}$, a sulphochloride of mercury like the oxychloride. But in the presence of an excess of sulphuretted hydrogen, the black precipitate of mercuric sulphide is formed. In this state it is not crystalline, but if it be heated to its temperature of volatilisation, it forms a red crystalline sublimate which is identical with native cinnabar. In this form its specific gravity is 8.0, and it forms a red powder, owing to which it is used as a red pigment (vermilion) in oil, pastel, and other paints. It is so little attacked by reagents that even nitric acid has no action on it, and the gastric juices do not dissolve it, so that it is not poisonous. When heated in air, the sulphur burns away and leaves metallic mercury. On a large scale cinnabar is usually prepared in the following manner: 300 parts of mercury and 115 parts of sulphur are mixed together as intimately as possible and poured into a solution of 75 parts of caustic potash in 425 parts of water, and the mixture is heated at 50° for several hours. Red mercury sulphide is thus formed, and separates out from the solution. The reaction which takes place is as follows: A soluble compound, K_2HgS_2 , is first formed; this compound is able to separate in colourless silky needles, which are soluble in the caustic potash, but are decomposed by water, and at 50° ; this solution (perhaps by attracting oxygen from the air) slowly deposits HgS in a crystalline form. A similar vermilion may be obtained by heating a mixture of mercury and sulphur; heat is evolved at the moment of combination, and a portion of the mass is volatilised.

I may here remark that lead sulphide in contact with zinc and hydrochloric acid gives sulphuretted hydrogen and metallic lead.

sulphur, by representing them as the oxidised products of sulphuretted hydrogen—

HCl	H ₂ S	H ₃ P	H ₄ C
HClO	H ₂ SO(?)	H ₃ PO(?)	H ₄ CO
HClO ₂	H ₂ SO ₂ (?)	H ₃ PO ₂	H ₄ CO ₂
HClO ₃	H ₂ SO ₃	H ₃ PO ₃	H ₄ CO ₃
HClO ₄	H ₂ SO ₄	H ₃ PO ₄	H ₄ CO ₄ ³⁰

In the case of chlorine, if not all the hydrates, at all events salts of all the normal hydrates are known, whilst in the case of sulphur only the acids H₂S, H₂SO₃, and H₂SO₄ are known. But on the other hand, the latter are obtained not only as hydrates, but also as stable anhydrides, SO₂ and SO₃, which are formed with the evolution of heat from sulphur and oxygen; 32 parts of sulphur in combining with 32 parts of oxygen—that is, in forming SO₂—evolve 71000 heat units,³¹ and if the oxidation proceeds to the formation of SO₃, 103000 heat units are evolved. These figures may be compared with those which correspond with the passage of carbon into CO and CO₂, when 29000 and 97000 units of heat are evolved. This determines the stability of the higher oxides of sulphur, and this expresses the peculiarity of sulphur as an element which, although an analogue of oxygen, forms stable compounds with it, and thus fundamentally differs from chlorine. The higher and lower oxides of chlorine are powerful oxidising agents, whilst the higher oxide of sulphur, SO₃, has but feeble oxidising powers, and the lower oxide, SO₂, frequently acts as a reducing agent, and is formed by the direct combustion of sulphur, just as carbonic anhydride, CO₂, proceeds from the combustion of carbon.

In the combustion of sulphur, and also in the oxidation of the sulphides and polysulphides by their ignition in air, *sulphurous oxide*, or *sulphurous anhydride*, or *sulphur dioxide*, SO₂, is exclusively formed. It is prepared on a large scale for the manufacture of sulphuric acid (Vol. I. p. 246), and for direct application in the manufacture of wine or for bleaching tissues and other purposes. In the latter instances its application is based on the fact that sulphurous anhydride acts on certain vegetable matters, and has the property of a reducing and feeble

³⁰ CH₄ gives CH₄O or CH₃(OH), wood spirit; CH₄O₂ or CH₂(OH)₂, which decomposes into water and CH₂O—that is, methylene oxide or formaldehyde; CH₄O₃ = CH(OH)₃ = H₂O + CHO(OH), or formic acid and CH₄O₄ = C(OH)₄ = 2H₂O + CO₂. There are four typical hydrogen compounds, RH, RH₂, RH₃, and RH₄, and each of them has its typical oxide. Beyond H₄ and O₄ combination does not proceed.

³¹ Rhombic sulphur, 71080 heat units; monoclinic sulphur, 71720 units, according to Thomsen.

acid. For these purposes it is prepared by burning sulphur or iron pyrites, FeS_2 .³²

In the laboratory—that is, on a small scale—sulphurous anhydride is best prepared by deoxidising sulphuric acid by heating it with charcoal, or copper, sulphur, mercury, &c. Charcoal produces this decomposition of sulphuric acid at but moderately high temperatures; it is itself converted into carbonic anhydride, and therefore when sulphuric acid is heated with charcoal it evolves a mixture of sulphurous and carbonic anhydrides: $\text{C} + 2\text{H}_2\text{SO}_4 = \text{CO}_2 + 2\text{SO}_2 + 2\text{H}_2\text{O}$. The metals which are unable to decompose water, and which do not, therefore, evolve hydrogen from sulphuric acid, are frequently capable of decomposing sulphuric acid, with the evolution of sulphurous anhydride, just as they decompose nitric acid, forming the lower oxides of nitrogen. These metals are silver, mercury, copper, lead, and others. Thus, for example, the action of copper on sulphuric acid may be expressed by the following equation: $\text{Cu} + 2\text{H}_2\text{SO}_4 = \text{CuSO}_4 + \text{SO}_2 + 2\text{H}_2\text{O}$. In the laboratory this reaction is carried on in a flask with a gas-conducting tube, and does not proceed unless aided by heat.³³

³² Sulphurous anhydride is also obtained by the decomposition of many sulphates, especially of the heavy metals, by the action of heat; but this requires a very powerful heat. This formation of sulphurous anhydride from sulphates is based on the decomposition proper to sulphuric acid itself. When sulphuric acid is powerfully heated (for instance, by dropping it upon an incandescent surface) it is decomposed into water, oxygen, and sulphurous anhydride—that is, into those compounds from which it is formed. A like decomposition proceeds during the ignition of many sulphates. In this case an oxide of the metal, oxygen, and sulphurous anhydride are formed. Even so stable a sulphate as gypsum does not resist the action of very high temperatures, but is decomposed in the same manner, lime being left behind. The decomposition of sulphates by heat is accomplished with still greater facility in the presence of sulphur, because in this case the liberated oxygen combines with the sulphur and the metal is able to form a sulphide. Thus when ferrous sulphate (green vitriol) is ignited with sulphur, it gives ferrous sulphide and sulphurous anhydride: $\text{FeSO}_4 + 2\text{S} = \text{FeS} + 2\text{SO}_2$, and this reaction may even be used for the preparation of this gas. At 400° sulphuric acid and sulphur give an extremely uniform stream of pure sulphurous anhydride, so that it is best prepared on a large scale at works by this method. Iron pyrites, FeS_2 , when heated to 150° with sulphuric acid (sp. gr. 1.75) in cast-iron vessels also gives an abundant and uniform supply of sulphurous anhydride.

³³ This reaction is connected with thermochemical data in the following manner. A molecule of hydrogen, H_2 , in combining with oxygen ($\text{O}=16$) develops about 69000 heat units, whilst the molecule of SO_2 in combining with oxygen only develops about 32000 heat units—that is, about half as much—and therefore those metals which cannot decompose water are still able to deoxidise sulphuric into sulphurous acid. Those metals which decompose water and sulphuric acid with the evolution of hydrogen, evolve in combining with sixteen parts by weight of oxygen nearly as much if not more heat than hydrogen—for example, K_2 , Na_2 , Ca develop about or more than 100000 heat units; Fe , Zn , Mn about 70000 to 80000 heat units; whilst those metals which neither decompose water nor evolve hydrogen from sulphuric acid, but are yet capable of evolving sulphurous anhydride from it, develop less heat with oxygen than hydrogen, but nearly the same amount, if not more, than sulphurous anhydride—for example, Cu and Hg develop about 40000, and Pb about

In its physical and chemical properties sulphurous anhydride presents a great *resemblance to carbonic anhydride*. It is a heavy gas, somewhat considerably soluble in water, very easily condensed into a liquid; it forms normal and acid salts, does not evolve oxygen under the direct action of heat,³⁴ although such metals as sodium and magnesium burn in it, just as in carbonic anhydride. It has a suffocating odour, which is well known, owing to its being evolved when sulphur or sulphur matches are burnt. In characterising the properties of sulphurous anhydride, it is very important to remember (Chapter II.), also, that it is more easily liquefied (at -10° , or at 0° under two atmospheres pressure) than carbonic anhydride (thirty-six atmospheres at 0°),³⁵ that it is more soluble than carbonic anhydride (Vol. I. p. 78) (namely at 0° , 100 vols. of water dissolve 180 vols. of carbonic anhydride and 688 vols. of sulphurous anhydride), that the molecular weight of $\text{SO}_2=64$ and of $\text{CO}_2=44$, the density of liquid sulphurous anhydride at $0^{\circ}=1.43$ (molecular volume = 45) and that of carbonic anhydride = 0.95 (molecular volume = 49). The resemblance of the physical properties of carbonic and sulphurous anhydrides is also expressed in the great resemblance of the chemical characters of both anhydrides. Although sulphur dioxide is the anhydride of an acid, nevertheless, like carbonic anhydride, it does not form any stable compounds with water, but gives a solution from which it may be entirely expelled by the action of heat.³⁶ The acid character of sulphurous anhydride is clearly expressed by the fact that it is entirely absorbed by alkalis, with which it forms acid and normal salts easily soluble in water. With salts of barium, calcium, and the heavy metals, the normal salts of the alkalis, M_2SO_3 , give precipitates exactly like those formed by the carbonates. In general, the salts of sulphurous acid are closely analogous to the corresponding carbonates.

50000, heat units. Naturally the affinity of the metallic oxide formed for the remaining sulphuric acid plays a part in the decomposition; and, as usual in thermochemical data, the experimental figure is complex, but still the general connection between the thermochemical phenomenon and the course of the reaction is evident.

³⁴ That is, it only dissociates and re-forms the original product on cooling.

³⁵ May not this be the reason why sulphurous anhydride has a more distinctly acid character? At a given temperature the pressure of this gas in any salt will be less than that of carbonic anhydride, if we compare the separation of a gas from its salts with the phenomenon of evaporation, as was pointed out in the decomposition of calcium carbonate.

Liquid sulphurous anhydride is used on a large scale (Pictet) for the production of cold.

³⁶ De la Rive, Pierre, and more especially B. Roozeboom, have investigated the crystallo-hydrate which is formed by sulphurous anhydride and water at temperatures below 7° under the ordinary pressure, and in closed vessels (at temperatures below 12°). Its composition is $\text{SO}_2 \cdot 7\text{H}_2\text{O}$, and density 1.2. This hydrate corresponds with the similar hydrate $\text{CO}_2 \cdot 8\text{H}_2\text{O}$ obtained by Wrobleffsky.

Acid sodium sulphite, NaHSO_3 , may be obtained by passing sulphurous anhydride into a solution of sodium hydroxide. It is also formed by saturating a solution of sodium carbonate with the gas (carbonic anhydride is then given off), and as the solubility of the acid sulphite is much greater than that of the carbonate, a further quantity of the latter may be dissolved after the passage of the sulphurous anhydride, so that ultimately a very strong solution of the sulphite may be formed in this manner, from which it may be obtained in a crystalline form, either by cooling and evaporating (without heating, for otherwise the salt will give off sulphurous anhydride) or by adding alcohol to the solution. When exposed to the air this salt loses sulphurous anhydride and attracts oxygen, which converts it into sodium sulphate. The acid sulphites of the alkali metals are not only able to combine with oxygen, but also with many other substances—for example, a solution of the sodium salt dissolves sulphur, forming sodium thiosulphate, gives crystalline compounds with the aldehydes and ketones, and dissolves many bases, converting them into double sulphites. Having the faculty of attracting or absorbing oxygen, acid sodium sulphite is also able to absorb chlorine, and is therefore employed, like sodium thiosulphate, for the removal of chlorine (as an antichlor), especially in the bleaching of fabrics, when it is necessary to remove the last traces of the chlorine held in the tissues, which might otherwise have an injurious effect on them. If a solution of an alkali hydroxide be divided into two parts, and one half is saturated with sulphurous anhydride, and then the other half added to it, a normal salt will be obtained in the solution, having an alkaline reaction, like a solution of sodium carbonate. The acid salt has a neutral reaction. Like sodium carbonate, *normal sodium sulphite* has the composition $\text{Na}_2\text{SO}_3 \cdot 10\text{H}_2\text{O}$, and its maximum solubility is at 33° —in a word, it very closely resembles sodium carbonate. Although this salt does not give off sulphurous anhydride from its solution, it is able, like the acid salt, to absorb oxygen from the air, and is then converted into sodium sulphate.³⁷

Besides the acid character we must also point out the reducing character of sulphurous anhydride. *The reducing action* of sulphurous acid, its anhydride and salts, is due to their faculty of passing into sulphuric acid and sulphates. The reducing action of the sulphites is particularly energetic, so that they even convert nitric oxide into

³⁷ The normal salts of calcium and magnesium are slightly, and the acid salts easily, soluble in water. These acid sulphites are much used in practice; thus calcium bisulphite is employed in the manufacture of cellulose from sawdust, for mixing with fibrous matter in the manufacture of paper.

nitrous oxide: $\text{K}_2\text{SO}_3 + 2\text{NO} = \text{K}_2\text{SO}_4 + \text{N}_2\text{O}$. The salts of many of the higher oxides are converted into those of the lower—for example, FeX_3 into FeX_2 , CuX_2 into CuX , HgX_2 into HgX ; thus $2\text{FeX}_3 + \text{SO}_2 + 2\text{H}_2\text{O} = 2\text{FeX}_2 + \text{H}_2\text{SO}_4 + 2\text{HX}$. In the presence of water, sulphurous anhydride is oxidised by chlorine ($\text{SO}_2 + 2\text{H}_2\text{O} + \text{Cl}_2 = \text{H}_2\text{SO}_4 + 2\text{HCl}$), iodine, nitrous acid, hydrogen peroxide, hypochlorous acid, chloric acid, and other oxygen compounds of the halogens, chromic, manganic, and many other metallic acids and higher oxides, as well as all peroxides. Free oxygen in the presence of spongy platinum is able to oxidise sulphurous anhydride even in the absence of water, in which case sulphuric anhydride SO_3 is formed, so that the latter may be prepared by passing a mixture of sulphurous anhydride and oxygen over incandescent spongy platinum, or, as it is now prepared on a large scale in chemical works, by passing this mixture over asbestos or pumice stone moistened with a solution of platinum salt and ignited. Sulphurous anhydride is completely absorbed by certain higher oxides—for instance, by barium peroxide and lead dioxide ($\text{PbO}_2 + \text{SO}_2 = \text{PbSO}_4$).³⁸

There are, however, cases when sulphurous anhydride acts as an oxidising agent—that is, it is *deoxidised* in the presence of substances which are capable of absorbing oxygen with still greater energy than the sulphurous anhydride itself. This oxidising action proceeds with the formation of sulphuretted hydrogen or of sulphides, while the reducing agent is oxidised at the expense of the oxygen of the sulphurous anhydride. In this respect, the action of stannous salts is particularly remarkable. Stannous chloride, SnCl_2 , in an aqueous solution gives a precipitate of stannic sulphide, SnS_2 , with sulphurous anhydride—that is, the latter is deoxidised to sulphuretted hydrogen. A solution of sulphurous anhydride has also an oxidising action on zinc. The zinc passes into solution, but no hydrogen is evolved,³⁹ because a

³⁸ This reaction is taken advantage of in removing sulphurous anhydride from a mixture of gases. Lead dioxide, PbO_2 , is brown, and when combined with sulphurous anhydride it forms lead sulphate, PbSO_4 , which is white, so that the reaction is evident both from the change in colour and development of heat. Sulphurous anhydride is slowly decomposed by the action of light, with the separation of sulphur and formation of sulphuric anhydride. This explains the fact that sulphurous anhydride prepared in the dark gives a white precipitate of silver sulphite, Ag_2SO_3 , with silver chlorate, AgClO_4 , but when prepared, even in diffused light, it gives a dark precipitate. This naturally depends on the fact that the sulphur liberated then forms silver sulphide, which is black.

³⁹ Schönebein observed that the liquid turns yellow, and acquires the faculty of decolorising litmus and indigo. Schützenberger showed that this depends on the formation of a zinc salt of a peculiar and very powerfully-reducing acid, for with cupric salts the yellow solution gives a red precipitate of cuprous hydride or metallic copper, and it reduces salts of silver and mercury entirely. An exactly similar solution is obtained by the action of zinc on sodium bisulphite without access of air and in the cold. The

salt of *hyposulphurous acid*, $\text{Zn}_2\text{S}_2\text{O}_4$, is formed. The free acid is still less stable than the salt.

The faculty of sulphurous anhydride of combining with various substances is evident from the above-cited reactions, where it combines with hydrogen and with oxygen, and this faculty also appears in the fact that, like carbonic oxide, it combines with chlorine, forming a chloranhydride of sulphuric acid, SO_2Cl_2 , to which we shall afterwards return. The same faculty for combination also appears in the salts of sulphurous acid, in their liability to oxidation and in the exceedingly characteristic formation of a peculiar series of salts obtained by Pelouze and Frémy. At a temperature of -10° or below, nitric oxide is absorbed by alkaline solutions of the alkali sulphites, forming a peculiar series of *nitrosulphates*. At a higher temperature, these salts are not formed, but the nitric oxide is reduced to nitrous oxide. But in the cold, the liquid saturated with nitric oxide after a certain time gives prismatic crystals resembling those of nitre. The composition of the potassium salt is $\text{K}_2\text{SN}_2\text{O}_5$ —that is, the salt contains the elements of potassium sulphite and of nitric oxide.⁴⁰

yellow liquid absorbs oxygen from the air with great avidity, and forms a sulphate. If the solution be mixed with alcohol, it deposits a double sulphite of zinc and sodium, $\text{ZnNa}_2(\text{SO}_3)_2$, which does not decolorise litmus or indigo. The remaining alcoholic solution deposits colourless crystals in the cold, which absorb oxygen with great energy in the presence of water, but are somewhat stable when dried under the receiver of an air-pump. When these crystals are oxidised in the presence of air and water they give sodium bisulphite. The solution of these crystals has the above-mentioned decolorising and reducing properties. These crystals contain a sodium salt of a lower acid; their composition was at first supposed to be HNaSO_2 , but it was afterwards proved that they did not contain hydrogen, and present the composition $\text{Na}_2\text{S}_2\text{O}_4$ (Bernthsen). The same salt is formed by the action of a galvanic current on a solution of sodium bisulphite, owing to the action of the hydrogen at the moment of its liberation.

⁴⁰ The instability of this salt is very great, and may be likened to that of the compound of ferrous sulphate with nitric oxide, because when heated under the contact influence of spongy platinum, charcoal, &c., it splits up into potassium sulphate and nitrous oxide. At 130° the dry salt gives off nitric oxide, and re-forms potassium sulphite. The free acid has not yet been obtained. These salts resemble the series of *sulphonitrites* discovered by Frémy in 1845. They are obtained by passing sulphurous anhydride through a strong and highly alkaline aqueous solution of potassium nitrite. They are soluble in water, but are precipitated by an excess of alkali. The first product of the action has the composition $\text{K}_3\text{NS}_3\text{HO}_9$. It is then converted by the further action of sulphurous anhydride, cold water, and other reagents into a series of similar complex salts, many of which give well-formed crystals. One must suppose that the chief cause of the formation of these very complex compounds is that they contain unsaturated compounds, NO , KNO_2 , and KHSO_5 , all of which are subject to oxidation and further combination, and therefore easily combine among each other. The decomposition of these compounds, with the evolution of ammonia, when their solutions are heated is due to the fact that the molecule contains the deoxidant, sulphurous anhydride (Vol. I. p. 258), which reduces the nitrous acid, $\text{NO}(\text{OH})$, to ammonia. In my opinion the composition of the sulphonitrites may be very simply referred to the composition of ammonia, in which the hydrogen is partly replaced by the radicle of the sulphates. If we represent the compo-

There are yet several other substances, formed by the oxides of nitrogen and sulphur, which belong to this class of complex and, under some circumstances, unstable compounds. In the manufacture of sulphuric acid, both these classes of oxides come into contact with each other in the lead chambers, and if there be insufficient water for the formation of sulphuric acid they give crystalline compounds, termed *chamber crystals*. As a rule, the composition of the crystals is expressed by the formula NHSO_5 . This is a compound of the radicles, NO_2 , of nitric acid and, HSO_3 , of sulphuric acid, or nitrosulphuric acid, $\text{NO}_2\cdot\text{SHO}_3$, if sulphuric acid be expressed as $\text{OH}\cdot\text{SHO}_3$ and nitric by $\text{NO}_2\cdot\text{OH}$. The tabular crystals of this substance fuse at about 70° , are formed both by the direct action of nitrous anhydride or nitric peroxide on sulphuric acid (Weltzen and others), and especially on sulphuric acid containing anhydride—for example, by means of the lower oxides of nitrogen and the higher oxides of sulphur—and also by the action of the lower oxides of sulphur and nitric acid.⁴¹

sition of potassium sulphate as $\text{KO}\cdot\text{KSO}_5$, then the group KSO_5 will be equivalent (according to the law of substitutions) to HO and to hydrogen. It combines with hydrogen, forming the potassium acid sulphite, KHSO_5 . Therefore the group KSO_5 may also replace the hydrogen in ammonia. Judging by my analysis (1870) the extreme limit of this substitution, $\text{N}(\text{HSO}_5)_5$, agrees with that of the sulpho-nitrite, which is easily formed, simultaneously with alkali, by the action of potassium sulphite on potassium nitrite, according to the equation $3\text{K}(\text{KSO}_5) + \text{KNO}_2 + 2\text{H}_2\text{O} = \text{N}(\text{KSO}_5)_5 + 4\text{HKO}$. The researches of Berglund, and especially of Raschig (1887), fully verified my conclusions, and showed that we must distinguish the following types of salts, corresponding with ammonia, where X stands for the sulphonic group, HSO_5 , in which the hydrogen is replaced by potassium; hence $\text{X} = \text{KSO}_5$: (1) NH_2X , (2) NHX_2 , (3) NX_3 , (4) $\text{N}(\text{OH})\text{XH}$, (5) $\text{N}(\text{OH})\text{X}_2$, (6) $\text{N}(\text{OH})_2\text{X}$, just as $\text{NH}_2(\text{OH})$ is hydroxylamine, $\text{NH}(\text{OH})_2$ is the hydrate of nitrous oxide, and $\text{N}(\text{OH})_3$ is orthonitrous acid, as follows from the law of substitutions. This class of compounds is in most intimate relation with the series of sulphonitrous compounds, corresponding with 'chamber crystals' and their acids, which we shall consider later.

⁴¹ In the sulphuric acid chambers the lower oxides of nitrogen and sulphur take part in the reaction. They are oxidised by the oxygen of the air, and form nitro-sulphuric acid—for example, $2\text{SO}_2 + \text{N}_2\text{O}_5 + \text{O}_2 + \text{H}_2\text{O} = 2\text{NHSO}_5$. This compound dissolves in strong sulphuric acid without changing, and when this solution is diluted (when the sp. gr. falls to 1.5) it splits up into sulphuric acid and nitrous anhydride, and by the action of sulphurous anhydride is converted into nitric oxide, which by itself (in the absence of nitric acid or oxygen) is insoluble in sulphuric acid. These reactions are taken advantage of in retaining the oxides of nitrogen in the Gay-Lussac coke-towers, and for extracting the absorbed oxides of nitrogen from the resultant solution in the Glover's tower (Vol. I. p. 284). Although nitric oxide is not absorbed by sulphuric acid, it reacts (Rose, Brüning) on its anhydride, and forms sulphurous anhydride and a crystalline substance, $\text{N}_2\text{S}_4\text{O}_9 = 2\text{NO} + 3\text{SO}_5 - \text{SO}_3 = \text{N}_2\text{O}_5\cdot 2\text{SO}_5$. This may be regarded as the anhydride of nitro-sulphuric acid, because $\text{N}_2\text{S}_4\text{O}_9 = 2\text{NHSO}_5 - \text{H}_2\text{O}$; like nitro-sulphuric acid, it is decomposed by water into nitro-sulphuric acid and nitrous anhydride. Since boric and arsenious anhydrides, alumina and other oxides of the form R_2O_3 are able to combine with sulphuric anhydride to form similar compounds decomposable by water, the above compound does not present any exceptional phenomenon.

Thiosulphuric acid, $\text{H}_2\text{S}_2\text{O}_3$ —that is, a compound of sulphurous acid and sulphur—also belongs to the products of combination of sulphurous acid. In a free state it is very unstable and it is only known in the form of its salts proceeding from the direct action of sulphur on the normal sulphites; if endeavours be made to separate it in a free state, it immediately splits up into those elements from which it might be formed—that is, into sulphur and sulphurous acid. The most important of its salts is the *sodium thiosulphate*, $\text{Na}_2\text{S}_2\text{O}_3 \cdot 5\text{H}_2\text{O}$, which occurs in colourless crystals, which are unacted on by atmospheric oxygen either when in a dry state or in solution. Many other salts of this acid are easily formed by means of this salt, although this cannot be done with all bases, for such bases as alumina, ferric oxide, chromium oxide, and others do not give compounds with thiosulphuric acid, just as they do not form stable compounds with carbonic acid. Whenever these salts might be formed, they (like the acid) split up into sulphurous acid and sulphur, and furthermore the elements of thiosulphuric acid in many cases act in a reducing manner, forming sulphuric acid and taking up the oxygen from reducible oxides. Thus, when treated with a thiosulphate the soluble ferric salts give a precipitate of sulphur and form ferrous salts, in which case it is the elements of sulphurous acid which act: $\text{H}_2\text{S}_2\text{O}_3 = \text{SO}_2 + \text{S} + \text{H}_2\text{O}$. The thiosulphates of the metals of the alkalis are obtained directly by boiling a solution of their sulphites with sulphur: $\text{Na}_2\text{SO}_3 + \text{S} = \text{Na}_2\text{S}_2\text{O}_3$. The same salts are formed by the action of sulphurous anhydride on solutions of the sulphides: thus, sodium sulphide dissolved in water gives sulphur and sodium thiosulphate, when a stream of sulphurous anhydride is passed through it: $2\text{Na}_2\text{S} + 3\text{SO}_2 = 2\text{Na}_2\text{S}_2\text{O}_3 + \text{S}$. The polysulphides of the alkali metals when left exposed to the air attract oxygen and also form thiosulphates.⁴²

⁴² Thus when alkali waste, which contains calcium sulphide, undergoes oxidation in the air it first forms a calcium polysulphide, and then calcium thiosulphate, CaS_2O_5 . If iron or zinc acts on a solution of sulphurous acid, then, besides the hyposulphurous acid first formed, a mixture of sulphite and thiosulphate is obtained. Thus, for example, with zinc, $8\text{SO}_2 + \text{Zn}_2 = \text{ZnSO}_3 + \text{ZnS}_2\text{O}_5$. In this case, as in the formation of hyposulphurous acid, there is no hydrogen liberated. One of the most common methods for preparing thiosulphates consists in the *action of sulphur on the alkalis*. The reaction is accompanied by the formation of sulphides and thiosulphates, just as the reaction of chlorine on alkalis is accompanied by the formation of hypochlorites and chlorides; hence in this respect the thiosulphates hold the same position in the order of the compounds of sulphur as the hypochlorites do among the chlorine compounds. The reaction of caustic soda on an excess of sulphur may be expressed thus: $6\text{NaHO} + 12\text{S} = 2\text{Na}_2\text{S}_5 + \text{Na}_2\text{S}_2\text{O}_5 + 3\text{H}_2\text{O}$. Thus sulphur is soluble in alkalis. On a large scale sodium thiosulphate, $\text{Na}_2\text{S}_2\text{O}_3$, is prepared by first heating sodium sulphate with charcoal, to form sodium sulphide, which is then dissolved in water and treated with sulphurous anhydride. The reaction is completed when the solution becomes slightly acid. A certain amount of caustic alkali is

Although sulphur, in combining directly with oxygen, only forms a small quantity of sulphuric anhydride, SO_3 , and nearly all passes into sulphurous anhydride, still the latter may be converted into the higher oxide, or *sulphuric anhydride*, SO_3 , by many methods. Sulphuric anhydride is a solid crystalline substance at the ordinary temperature; it is easily fusible (16°), and volatile, and attracts moisture with great

added to the slightly acid solution; a portion of the sulphur is thus precipitated, and the solution is then boiled and evaporated in order to crystallise out the salt. The saturation of the solution of sodium sulphide by sulphurous anhydride is carried on in different ways—for example, by means of coke towers, by causing the solution of sulphide to trickle over the coke, and the sulphurous anhydride, obtained by burning sulphur, to pass up the coke tower from below. An excess of sulphurous anhydride must be avoided, as otherwise sodium trithionate is formed. Sodium thiosulphate is also prepared by the double decomposition of the soluble calcium thiosulphate with sodium sulphate or carbonate, in which case calcium sulphate or carbonate is precipitated. The calcium thiosulphate is prepared by the action by sulphurous anhydride on either calcium sulphide or alkali waste. A dilute solution of calcium thiosulphate may be obtained by treating alkali waste which has been exposed to the action of air with water. On evaporation, this solution gives crystals of the salt containing 5 molecules H_2O . A solution of calcium thiosulphate must be evaporated with great care, because otherwise the salt breaks up into sulphur and calcium sulphide. Even the crystallised salt sometimes undergoes this change.

The crystals of sodium thiosulphate are stable, do not effloresce, and at 0° dissolve in one part of water, and at 20° in 0.6 part. The solution of this salt does not undergo any change when boiled for a short time, but after prolonged boiling it deposits sulphur. The crystals fuse at 56° , and lose all their water at 100° . When the dry salt is ignited it gives sodium sulphide and sulphate. With acids, a solution of the thiosulphate soon becomes cloudy and deposits an exceedingly fine powder of sulphur. If the amount of acid added be considerable it also evolves sulphurous anhydride, owing to the instability of the hyposulphurous acid itself: $\text{H}_2\text{S}_2\text{O}_3 = \text{H}_2\text{O} + \text{S} + \text{SO}_2$. Sodium thiosulphate has many practical uses; it is used in photography for dissolving silver chloride and bromide. Its solvent action on silver chloride may be taken advantage of in extracting this metal as chloride from its ores. In dissolving, it forms a double salt of silver and sodium: $\text{AgCl} + \text{Na}_2\text{S}_2\text{O}_5 = \text{NaCl} + \text{AgNaS}_2\text{O}_5$. Sodium thiosulphate is an *anti-chlor*—that is, a substance which hinders the destructive action of free chlorine owing to its being very easily oxidised by chlorine into sulphuric acid and sodium chloride. The reaction with iodine is different, and is remarkable for the accuracy with which it proceeds. The iodine takes up half the sodium from the salt and converts it into a tetrathionate; $2\text{Na}_2\text{S}_2\text{O}_5 + \text{I}_2 = 2\text{NaI} + \text{Na}_2\text{S}_4\text{O}_6$. Hence a solution of sodium thiosulphate may be employed for the determination of free iodine. As iodine is expelled from potassium iodide by chlorine, it is possible also to determine the amount of chlorine by this method if potassium iodide be added to a solution containing chlorine. And as many of the higher oxides are able to evolve iodine from potassium iodide, or chlorine from hydrochloric acid (for example, the higher oxides of manganese, chromium, &c.), it is also possible to determine the amounts of these higher oxides by means of sodium thiosulphate and liberated iodine. The details of these methods must be looked for in books on analytical chemistry.

On adding a solution of a *lead salt* gradually to a solution of sodium thiosulphate, there is formed a white precipitate of lead thiosulphate, PbS_2O_5 (at first in this reaction a soluble double salt, and if the action be rapid, lead sulphide). When this substance is heated at 200° , it undergoes a change and takes fire. Sodium thiosulphate in solution soon reduces the cupric salts into cuprous salts by means of the sulphurous acid contained in the thiosulphate, but the resultant cuprous oxide is not precipitated, because it passes into the state of a thiosulphate and forms a double salt with the hyposulphite taken. These double cuprous

energy. Although it is formed by the combination of sulphurous anhydride with oxygen, it is liable to further combination. Thus it combines with water, hydrochloric acid, ammonia, with many hydrocarbons, and even with sulphuric acid, boric and nitrous anhydrides, &c., not to mention bases which burn directly in its vapour, forming sulphates. The oxidation of sulphurous anhydride, SO_2 , into sulphuric anhydride, SO_3 , is accomplished by passing a mixture of the former and dry oxygen or air over incandescent spongy platinum, by means of which a combination takes place between the two gases. An increase of pressure accelerates the reaction (Hänisch). If the product be passed into a cold vessel, crystalline sulphuric anhydride is deposited upon the sides of the vessel, but as it is difficult to avoid all traces of moisture it always contains compounds of its hydrates: $\text{H}_2\text{S}_2\text{O}_7$ and $\text{H}_2\text{S}_4\text{O}_{13}$, whose presence so modifies the properties of the anhydride (Weber) that formerly two modifications of the anhydride were recognised (Marignac, Schultz-Sellack, and others). The same (an impure but perfectly anhydrous anhydride is formed by distilling over phosphoric anhydride) sulphuric anhydride may be obtained from certain anhydrous, or almost so, sulphates, which are decomposed by heat. Such are, for instance, the acid sodium sulphate, NaHSO_4 , and the pyro- or di-sulphate, $\text{Na}_2\text{S}_2\text{O}_7$ (Vol. I. p. 510), formed from it, which when ignited evolve sulphuric anhydride; also ferrous sulphate, and certain other salts which are easily decomposed by the action of heat. If the sulphate taken decomposes at a very high temperature, sulphuric anhydride is not obtained, but is split up into oxygen and sulphurous anhydride. Green vitriol—that is, ferrous sulphate, FeSO_4 —belongs to the number of those sulphates which easily give off sulphuric anhydride. It contains water of crystallisation, and parts with it when it is heated, but the last equivalent of water is driven off with difficulty, just as is the case with magnesium sulphate; however, under the action of a powerful heat this evolution of sulphuric anhydride does take place,

salts are excellent reducing agents. The solution becomes colourless on the formation of cuprous salts, and when heated it gives a black precipitate of copper sulphide.

The following formulæ sufficiently explain the position held by thiosulphuric acid among the other acids of sulphur:

Sulphurous acid	$\text{SO}_2\text{H}(\text{OH})$
Sulphuric acid	$\text{SO}_3\text{OH}(\text{OH})$
Thiosulphuric acid	$\text{SO}_2\text{SH}(\text{OH})$
Hyposulphurous acid	$\text{SO}_2\text{H}(\text{SO}_2\text{H})$
Dithionic acid	$\text{SO}_2\text{OH}(\text{SO}_2\text{OH})$

At one time it was thought that all the salts of thiosulphuric acid only existed with water, and it was then supposed that their composition was $\text{H}_4\text{S}_2\text{O}_4$, or H_2SO_2 , but Popp obtained the anhydrous salts.

although not completely, because at a high temperature a portion of it is decomposed by the ferrous oxide ($\text{SO}_3 + 2\text{FeO}$), which is converted into ferric oxide, Fe_2O_3 , and in consequence a portion of the sulphuric anhydride is converted into sulphurous anhydride. Thus the products of the decomposition of ferrous sulphate will be : ferric oxide, Fe_2O_3 , sulphurous anhydride, SO_2 , and sulphuric anhydride, SO_3 , according to the equation: $2\text{FeSO}_4 = \text{Fe}_2\text{O}_3 + \text{SO}_2 + \text{SO}_3$. As water still remains with the ferrous sulphate when it is heated, the result will partially consist of the hydrate H_2SO_4 , with anhydride, SO_3 , dissolved in it. Sulphuric acid was for a long time prepared in this manner ; this process was formerly carried on on a large scale in the neighbourhood of Nordhausen, and, therefore, the sulphuric acid prepared from ferrous sulphate is called *fuming Nordhausen acid*. At the present time the fuming acid is prepared by passing the volatile products of the decomposition of ferrous sulphate through strong sulphuric acid prepared by the ordinary method. The sulphurous anhydride is insoluble in it, but it absorbs the sulphuric anhydride. Sulphuric anhydride may be better prepared by igniting a mixture of sodium pyrosulphate, $\text{Na}_2\text{S}_2\text{O}_7$, and magnesium sulphate (Walters ; the decomposition proceeds at 600°) than from ferrous sulphate or sodium pyrosulphate alone ; because in the former case there remains a stable double salt $\text{MgNa}(\text{SO}_4)_2$. Nordhausen sulphuric acid fumes in air, owing to its containing and easily giving off sulphuric anhydride, and it is therefore also called *fuming sulphuric acid* ; these fumes are nothing but the vapour of sulphuric anhydride combining with the moisture in the air, and forming non-volatile sulphuric acid (hydrate).⁴³

Nordhausen sulphuric acid as a solution of sulphuric anhydride in

⁴³ Nordhausen sulphuric acid may serve as a very simple means for the preparation of sulphuric anhydride. For this purpose the Nordhausen acid is heated in a glass retort, whose neck is firmly fixed in the mouth of a well-cooled flask. The access of moisture is prevented by connecting the receiver with a drying tube. On heating the retort the vapours of the volatile sulphuric anhydride will pass over into the receiver, where they condense ; the anhydride thus prepared will, however, contain traces of sulphuric acid—that is, of the hydrate—because it rapidly attracts moisture from the air and forms sulphuric acid. By repeatedly distilling over phosphoric anhydride, it is possible to obtain the pure anhydride, SO_3 , especially if the process be carried on without access of air.

The ordinary sulphuric anhydride, which is imperfectly freed from the hydrate, is a snow-white, exceedingly volatile substance ; it fuses at 16° into a colourless liquid having a specific gravity at $26^\circ = 1.91$, and at $47^\circ = 1.81$; it volatilises at 46° . After being kept for some time this substance undergoes a change, a small quantity of sulphuric acid combining by degrees with a large proportion of the anhydride, forming polysulphuric acids, $\text{H}_2\text{SO}_4, n\text{SO}_3$, which fuse with difficulty (even at 100° , Marignac), but decompose when heated. In the entire absence of water this rise in the fusing point does not occur (Weber), and then the anhydride long remains liquid, and solidifies at about $+15^\circ$, volatilises at 40° , and has a specific gravity 1.94 at 16° .

sulphuric acid contains a peculiar compound of these substances, or *pyrosulphuric acid*; an imperfect anhydride of sulphuric acid, $\text{H}_2\text{S}_2\text{O}_7$, analogous in composition with the salts, $\text{Na}_2\text{S}_2\text{O}_7$, $\text{K}_2\text{Cr}_2\text{O}_7$, and similar pyro-salts or anhydro-acid salts. At all events the bond holding the sulphuric acid and anhydride together is unstable. This is obvious from the fact that the anhydride may easily be separated from this compound by the action of heat. In order to obtain the definite compound, the Nordhausen acid is cooled to 5° , or, better still, a portion of it is distilled until all the anhydride and a certain amount of sulphuric acid have passed over into the distillate, which will then solidify at the ordinary temperature, because the compound $\text{H}_2\text{SO}_4\cdot\text{SO}_3$ fuses at 35° . Although this substance reacts on water, bases, &c., like a mixture of $\text{SO}_3 + \text{H}_2\text{SO}_4$, still as a definite compound, $\text{H}_2\text{S}_2\text{O}_7$, exists in a free state and gives salts and a chloranhydride, $\text{S}_2\text{O}_3\text{Cl}_2$,⁴⁴ we must admit the existence of a particular pyrosulphuric acid, like pyrophosphoric acid, remarking only that the latter imperfect anhydride has a far greater stability and is not even converted into a perfect hydrate by water. Further, the salts $\text{M}_2\text{S}_2\text{O}_7$ dissolved in water react in the same manner as the acid salts MHSO_4 , whilst the imperfect hydrates of phosphoric acid (for example, PHO_3 , $\text{H}_4\text{P}_2\text{O}_7$) have independent reactions even in an aqueous solution which distinguish them and their salts from the perfect hydrates.

Sulphuric acid, H_2SO_4 , is formed by the combination of its anhydride, SO_3 , and water, with the evolution of a large amount of heat; the reaction $\text{SO}_3 + \text{H}_2\text{O}$ develops 21300 heat units. The methods of its preparation on a larger scale, as well as the majority of known

⁴⁴ Pyrosulphuric chloranhydride, or *pyrosulphuryl chloride*, $\text{S}_2\text{O}_3\text{Cl}_2$, corresponds with pyrosulphuric acid, in the same way that sulphuryl chloride, SO_2Cl_2 , corresponds with sulphuric acid. The composition $\text{S}_2\text{O}_3\text{Cl}_2 = \text{SO}_2\text{Cl}_2 + \text{SO}_3$. It is obtained by the action of the vapour of sulphuric anhydride on sulphur chloride: $\text{S}_2\text{Cl}_2 + 5\text{SO}_3 = 5\text{SO}_2 + \text{S}_2\text{O}_3\text{Cl}_2$. It is also formed (and not sulphuryl chloride, SO_2Cl_2 , Michaelis) by the action of phosphorus pentachloride in excess on sulphuric acid (or its first chloranhydride, SHO_3Cl). It is an oily liquid, boiling at about 150° , and of sp. gr. 1.6. According to Konovaloff (Vol. I. p. 314), its vapour density is normal. It should be noticed that the same substance is obtained by the action of sulphuric anhydride on sulphur tetrachloride, and also on carbon tetrachloride, and this substance is the last product of the metalepsis of CH_4 , and therefore the comparison of SO_2Cl_2 and S_2Cl_2 with products of metalepsis (see further) also finds confirmation in particular reactions. Rose, who obtained pyrosulphuryl chloride, $\text{S}_2\text{O}_3\text{Cl}_2$, regarded it as $\text{SO}_2\text{Cl}_2\cdot\text{SO}_3$, for at that time they always endeavoured to find two component parts of opposite polarity. And then the substance in question was cited as a proof of the existence of a hexachloride, SO_2Cl_6 . Pyrosulphuryl chloride is decomposed by cold water, but more slowly than chlorosulphuric acid, and the other chloranhydrides.

The relation between pyrosulphuric acid and the normal acid will be obvious if we express the latter by the formula $\text{OH}(\text{SO}_3\text{H})$, because the sulphonic group (SO_3H) is evidently equivalent to OH , and consequently to H , and therefore if we replace both the hydrogens in water by this radicle we shall obtain $(\text{SO}_3\text{H})_2\text{O}$ —that is, pyrosulphuric acid.

methods for its formation, are dependent on the oxidation of sulphurous anhydride, and the formation of sulphuric anhydride, which forms sulphuric acid under the action of water. The technical mode of its manufacture has been described in Chap. VI., Vol. I. p. 284. The acid obtained *from the lead chambers* is diluted with a considerable amount of water, and is also impure, owing to the presence of oxides of nitrogen, lead compounds, and certain impurities from the burnt sulphur which have come over in a gaseous and vaporous state (for example, arsenic compounds). For practical purposes, hardly any notice is taken of the majority of these impurities, because they do not interfere in its general qualities. Most frequently endeavours are only made to remove, as far as possible, all the water which may be expelled without destroying the composition of sulphuric acid as a hydrate.⁴⁵ That is, the object is to obtain the hydrate, H_2SO_4 , from the dilute acid. The separation of the water from the dilute acid is carried on by evaporating with the aid of heat. Every given mixture of water and sulphuric acid begins to part with a certain amount of aqueous vapour when heated to a certain definite temperature. At a low temperature there is either no evaporation of water, or even an absorption of moisture from the air. As the removal of the water proceeds, the temperature at which it comes off rises; the more dilute the acid the lower the temperature at which it gives up a portion of its water. In consequence of this, the removal of water from dilute solutions of sulphuric acid may be easily carried on (up to 60° Baumé) in lead, and still better in glass, vessels, because at low temperatures dilute sulphuric acid does not corrode either glass or lead. But as the acid becomes more concentrated the temperature at which the water comes over becomes higher and higher, and then the acid begins to act on lead (with the evolution of sulphuretted hydrogen and conversion of the lead into sulphate), and therefore lead vessels cannot be employed for the entire removal of the water. For this purpose the evaporation is generally carried on in glass or platinum retorts, like those depicted in figs. 87 and 88.

The concentration of sulphuric acid in glass retorts is not a continuous process, and consists of heating the dilute acid until it ceases to give off aqueous vapour, and until the sulphuric acid itself begins to

⁴⁵ The removal of the water, or concentration to almost the real acid, H_2SO_4 , is effected for two purposes: in the first place to avoid the expense of transit (it is cheaper to remove the water than to pay for its transit to a great distance), and in the second place many processes—for instance, the refining of petroleum—require a strong acid free from an excess of water, the weak acid having no action. On this account the production of sulphuric anhydride increases year by year, and probably in time it will be an important competitor to chamber acid.

come off—that is, until the composition of the residue is the same as that of the distillate—and this takes place when the temperature



FIG. 87.—Concentration of sulphuric acid in glass retorts. The neck of each retort is attached to a bent glass tube, whose vertical arm is lowered into a glass or earthenware vessel acting as a receiver for the steam which comes over from the acid, as the former still contains a certain amount of acid.

reaches 320° and the density of the residue 1.847 ($=66^{\circ}$ Baumé).⁴⁶ The platinum vessels designed for the continuous concentration of sulphuric




FIG. 88.—Concentration of sulphuric acid in platinum retorts.

acid consist of a boiler, B, furnished with a helmet, E, a vapour-conducting pipe, E F, and a syphon tube, H R, which draws off the sulphuric

⁴⁶ The difficulty with which the last portions of water are removed is seen from the fact that the boiling becomes very irregular, totally ceasing at one moment, then suddenly starting again, with the rapid formation of a considerable amount of steam, and at the

acid concentrated in the boiler. A stream of sulphuric acid previously concentrated in lead retorts to a density of about 60° Baumé—*i.e.* to a sp. gr. of 1.7—runs continuously into the retort through an upper funnel E. The apparatus is fed from above, because the acid freshly supplied is lighter than that which has already lost water, and also because the water is more easily evaporated from the freshly-supplied acid at the surface. The platinum retort is heated, and the steam coming off is condensed in a worm F G, whilst as fresh diluted acid is supplied to the boiler the acid already concentrated is drawn off through the syphon tube H B, which is furnished with a regulating cock, by means of which the outflow of the concentrated acid from the bottom of the retort can be so regulated that it will always present one and the same specific gravity, corresponding with the strength required. For this purpose, the acid flowing from the syphon is collected in a receiver R, in which a hydrometer, indicating its density, floats; if its density be less than 66° Baumé, the regulating cock is closed sufficiently to retard the outflow of sulphuric acid, so as to lengthen the time of its evaporation in the retort.⁴⁷

same time jerking and even overturning the vessel in which it is held. Hence it is not a rare occurrence for the glass retorts to break during the distillation; this causes platinum retorts to be preferred, as the boiling then proceeds quite uniformly.

⁴⁷ The greatest part of the sulphuric acid is used in the soda manufacture, in the conversion of the common salt into sulphate. For this purpose an acid having a density of 60° Baumé is amply sufficient. Chamber acid has a density up to $1.57 = 50^{\circ}$ to 51° Baumé; it contains about 35 per cent. of water. About 15 per cent. of this water can be removed in leaden stills, and nearly all the remainder may be expelled in glass or platinum vessels. Acid of 66° Baumé, $= 1.847$, contains about 96 per cent. of the hydrate H_2SO_4 . The density falls with a greater or less proportion of water, the maximum density corresponding with $97\frac{1}{2}$ per cent. of the hydrate H_2SO_4 .

When, by heating and evaporation of the water, sulphuric acid attains a density of 66° Baumé (sp. gr. 1.84), it is impossible to concentrate it further, because it then distils over unchanged. The distillation of sulphuric acid is not generally carried on on a large scale, but forms a laboratory process, employed when particularly pure acid is required. The distillation is effected either in platinum retorts furnished with corresponding condensers and receivers, or in glass retorts. In the latter case, great caution is necessary, because the boiling of sulphuric acid itself is accompanied by still more violent jerks and greater irregularity than even the evaporation of the last portions of water contained in the acid. If the glass retort which holds the strong sulphuric acid to be distilled be heated directly from below, it frequently jerks and breaks. For greater safety the heating is not effected from below, but at the sides of the retort. Then the evaporation does not proceed in the whole mass, but only from the upper portions of the liquid, and therefore goes on much more quietly. For this purpose the bottom of the retort is protected from the action of heat; for example, by immersing it in a special basin and lowering the bottom of the retort below the charcoal stove, by means of which the acid is heated. The acid may be made to boil quietly also by surrounding the retort with good conductors of heat—for example, iron filings, or by immersing a bunch of platinum wires in the acid, as the bubbles of sulphuric acid vapour then form on the extremities of the wires.

Strictly speaking, *sulphuric acid is not volatile*, and at its so-called boiling-point ⁴⁸ it really decomposes into its anhydride and water; its boiling-point (338°) being nothing else but its temperature of decomposition. The products of this decomposition are substances boiling much below the temperature of the decomposition of sulphuric acid. This conclusion with regard to the process of the distillation of sulphuric acid may be deduced from Bineau's observations on the vapour density of sulphuric acid. This density referred to hydrogen proved to be half that which sulphuric acid should have according to its molecular weight, H_2SO_4 , in which case it should be 49, whilst the observed density was equal to 24.5. Besides which, Marignac showed that the first portions of the sulphuric acid distilled over contain less of the elements of water than the portion which remains behind, or which distils over towards the end. This is explained by the fact that in distilling the sulphuric acid is decomposed, but a portion of the water proceeding from its decomposition is retained by the remaining mass of sulphuric acid, and therefore at first a mixture of sulphuric acid and sulphuric anhydride—*i.e.* fuming sulphuric acid—is obtained in the distillate. It is possible by repeating the distillation several times and only collecting the first portions of the distillate, to obtain a distinctly-fuming acid. To obtain the definite hydrate H_2SO_4 , it is necessary to refrigerate a highly-concentrated acid, of as great a purity as possible, to which a small quantity of sulphuric anhydride has been previously added (because pure sulphuric acid does not separate in presence of a small quantity of water). Pure sulphuric acid, H_2SO_4 , solidifies when it is cooled below 0°, and therefore the

⁴⁸ According to Regnault, the vapour tensions (in millimetres of mercury) of the vapour given off by the hydrates of sulphuric acid, $\text{H}_2\text{SO}_4, n\text{H}_2\text{O}$, are—

	$t = 5^\circ$	15°	30°
$n = 1$	0.1	0.1	0.2
2	0.4	0.7	1.5
3	0.9	1.6	4.1
4	1.3	2.8	7.0
5	2.1	4.2	10.7
7	3.2	6.2	15.6
9	4.1	8.0	19.6
11	4.4	9.0	22.2
17	5.5	10.6	28.1

According to Lunge, the vapour tension of the aqueous vapour given off from solutions of sulphuric acid containing p per cent. H_2SO_4 , at t°_2 equals the barometric pressure 720 to 730 mm.

$p =$	10	20	30	40	50	60	70	80	85	90	95
$t =$	102°	105°	108°	114°	124°	141°	170°	207°	233°	262°	295°

normal acid first crystallises out from the concentrated sulphuric acid. By repeating the refrigeration several times, and pouring off the unsolidified portion, it is possible to obtain a pure *normal hydrate*, H_2SO_4 , which melts at 10° . The presence of several per cents. of water considerably lowers the freezing-point. At 40° it already gives off distinct fumes—that is, it begins to decompose into sulphuric anhydride, which volatilises, and water, which is absorbed by the remaining mass of sulphuric acid, and therefore even in a dry atmosphere the hydrate H_2SO_4 becomes weaker, until it attains a dilution of $1\frac{1}{2}$ p.c. of water. Thus it appears that so common, and apparently so stable, a compound as sulphuric acid decomposes even at a low temperature with separation of the anhydride, but this decomposition is restricted by a limit, corresponding to the presence of about $1\frac{1}{2}$ p.c. of water, or to a composition of nearly $\text{H}_2\text{O}, 12\text{H}_2\text{SO}_4$.⁴⁹

In a concentrated form sulphuric acid is commercially known as *oil of vitriol*, because for a long time it was obtained from green vitriol, and because it has an oily appearance and flows from one vessel into another in a thick and comparatively immobile stream, like the majority of oily substances, and in this clearly differs from such liquids as water, spirit, ether, and the like, which exhibit a far greater mobility. Among its properties, the first to be remarked is its faculty for the formation of many compounds. We already know that it combines with its anhydride, and with the sulphates of the alkali metals; that it is soluble in water, with which it forms more or less stable compounds. Sulphuric acid, when mixed with water, develops a very considerable amount of heat.⁵⁰

⁴⁹ Now there is no reason for thinking that this substance is a definite compound; it is an equilibrated system which does not decompose under ordinary circumstances below 338° . Dittmar carried on the distillation under pressures varying between 30 and 2140 millimetres (of mercury), and he found that the composition of the residue hardly varies, and contains from 99.2 to 98.2 per cent. of the normal hydrate, although at 30 mm. the temperature of distillation is about 210° and at 2140 mm. it = 382° . Furthermore, it is a circumstance of practical importance that under a pressure of two atmospheres the distillation of sulphuric acid proceeds very quietly.

Sulphuric acid may be *purified* from the majority of its impurities by distillation, if the first and last portions of the distillate be rejected. The first portions will contain the oxides of nitrogen, hydrochloric acid, &c., and the last portions the less volatile impurities. The oxides of nitrogen may be removed by heating the acid with charcoal, which converts them into volatile gases. Sulphuric acid may be freed from arsenic by heating it with manganese dioxide and then distilling. This oxidises all the arsenic into non-volatile arsenic acid. Without a preliminary oxidation it would partially remain as volatile arsenious acid, and might pass over into the distillate. The arsenic may also be driven off by first reducing it to arsenious acid, and then passing hydrochloric acid gas through the heated acid. It is then converted into arsenious chloride, which volatilises.

⁵⁰ The amount of heat developed by the mixture of sulphuric acid with water is

Besides the normal hydrate H_2SO_4 , another definite hydrate $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$ (84.48 per cent. of the normal hydrate, and 15.52 per cent. of water) is known; it crystallises extremely easily in large six-sided prisms, which form above 0° —namely, at about $+8^\circ$; when heated to 210° it loses water.⁵¹

If the hydrates H_2SO_4 and $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$ exist at low temperatures as definite compounds, and if pyrosulphuric acid, H_2SO_5 , has the same property, and if they all decompose with more or less ease on a rise of temperature, with the disengagement of either SO_3 or H_2O (and these elements of sulphuric acid are evolved quite separately from each other—that is, uncombined), then it follows that between sulphuric anhydride, SO_3 , and water, H_2O , there exists an uninterrupted and consecutive series of homogeneous substances which in a liquid state are nothing else than solutions.

However, as among them we must distinguish the above-mentioned *definite compounds*, which are incapable of taking a vaporous form, but able to pass into a solid state, it is indispensable, in order to arrive at a right judgment, to seek for other means for determining the existence of any definite compounds—beyond the conditions for a change of state. In this respect we may be guided by the variation of properties of any kind, which proceeds with a variation in the composition of solutions. For definite compounds we should ex-

pressed by the diagram on p. 76, Vol. I., by the middle curve, whose abscissæ are the percentage amounts of acid (H_2SO_4) in the resultant solution, and ordinates the number of units of heat corresponding with the formation of 100 cubic centimetres of the solution (at 18°). The calculations on which the curve is designed are based on Thomsen's determinations, which show that 98 grams or a molecular amount of sulphuric acid, in combining with m molecules of water (that is, with m 18 grams of water), develop the following number of units of heat, R:—

$m =$	1	2	3	5	9	19	49	100	200
R =	6379	9418	11137	13108	14952	16256	16684	16859	17066
$c =$	0.432	0.470	0.500	0.576	0.701	0.821	0.914	0.954	0.975
T =	127°	149°	146°	121°	82°	45°	19°	9°	5°

c stands for the specific heat of $\text{H}_2\text{SO}_4, m\text{H}_2\text{O}$ (according to Marignac and Pfaundler) and T for the rise in temperature which proceeds from the mixture of H_2SO_4 with $m\text{H}_2\text{O}$. The diagram shows that contraction and rise of temperature proceed almost parallel with each other.

⁵¹ With an excess of snow, the hydrate $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$, like the normal hydrate, gives a freezing mixture, owing to the absorption of a large amount of heat (at the expense of the latent heat of fusion). In melting, the molecule H_2SO_4 absorbs 960 heat units, and the molecule $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$ 3680 heat units. If we mix, for example, one gram molecule of this hydrate with seventeen gram molecules of snow, there is an absorption of 18080 heat units, because $17\text{H}_2\text{O}$ absorbs 17×1430 heat units, and the combination of the monohydrate with water evolves 9800 heat units. As the specific heat of the resultant compound $\text{H}_2\text{SO}_4, 18\text{H}_2\text{O} = 0.813$, the fall of temperature will be $= 52.6$. And so in reality an extreme degree of cold may be obtained by means of sulphuric acid.

pect changes in properties, and this is observed to be the case in reality. But only a few properties have been determined with sufficient accuracy. In those properties which have been determined for many solutions of sulphuric acid, it is actually seen that the above-mentioned definite compounds are distinguished by distinctive marks of change. As an example we may cite the variation of the specific gravity with a variation of temperature (namely ds/dt , if s be the sp. gr. and t the temperature). For the normal hydrate, H_2SO_4 , this factor ds/dt or k is easily determined from the fact that—

$$s = 18528 - 10.65t + 0.0013t^2,$$

where s is the specific gravity at t (degrees Celsius) if the sp. gr. of water at $4^\circ = 10000$. Therefore, $k = 10.65 - 0.026t$. This means that at 0° the sp. gr. of the acid H_2SO_4 decreases by 10.65 for every rise of a degree of temperature, at 10° by 10.39, at 20° by 10.13, at 30° by 9.87.⁵² And for solutions containing slightly more anhydride than the acid H_2SO_4 (*i.e.* for fuming sulphuric acid), as well as for solutions containing little water, the magnitude $-k$ is greater than for the acid H_2SO_4 . Thus for the solution $\text{SO}_2, 2\text{H}_2\text{SO}_4$, at $10^\circ -k = 10.9$, and for the acid H_2SO_4 at $10^\circ -k = 10.4$. On diluting the acid H_2SO_4 this increase of the magnitude $-k$ goes on until the formation of the solution $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$ ($-k = 11.1$ at 10°), and then, on the further dilution with water, it again decreases. Consequently both hydrates H_2SO_4 and $\text{H}_2\text{SO}_4, \text{H}_2\text{O}$ are here expressed by an alteration of the magnitude of K .

Of all the properties of the solutions of sulphuric acid, the specific gravity has been the most thoroughly investigated. The researches of Bineau, Kremers, Lunge and Naef, Marignac, Mendeléeff, Ostwald, Schertel and Winkler, give the following specific gravities (in a vacuum ; water $4^\circ = 10000$) at 0° .⁵³

	H_2O	$s =$	9998.7	$p =$	0
$\text{H}_2\text{SO}_4 + 400$	H_2O	$,, =$	10099	$,,$	1.34
$,, \quad 200$	$,,$	$,,$	10192	$,,$	2.65
$,, \quad 100$	$,,$	$,,$	10372	$,,$	5.16
$,, \quad 50$	$,,$	$,,$	10716	$,,$	9.82
$,, \quad 25$	$,,$	$,,$	11336	$,,$	17.88

⁵² For example, if it be given that at 19° the sp. gr. of pure sulphuric acid = 18330, then at 20° it = $18330 - (20 - 19)10.13 = 18320$.

⁵³ The historical and experimental details concerning the sp. gr. of solutions of sulphuric acid are given in Chapter III. of my work, *The Investigation of Aqueous Solutions according to their Specific Gravities* (1887).

$\text{H}_2\text{SO}_4 + 12\frac{1}{2} \text{H}_2\text{O}$	$s = 12345$	$p = 30.34$
„ 10 „ „	12760	35.25
„ 5 „ „	14306	52.13
„ $3\frac{1}{3}$ „ „	15370	62.02
„ $2\frac{1}{2}$ „ „	16102	68.53
„ 2 „ „	16655	73.13
„ 1 „ „	17943	84.48
„ $\frac{1}{2}$ „ „	18435	91.59
H_2SO_4 „	18528	100
$\text{SO}_3 + 4\text{H}_2\text{SO}_4$ „	19075	103.8
$2\text{SO}_3 + 3\text{H}_2\text{SO}_4$ „	19793	107.9.

Where p is weight per cent. of H_2SO_4 .

The investigation of the increase of the specific gravity with a rise of the percentage amount of the normal hydrate H_2SO_4 —that is, the magnitudes of ds/dp (the quotient of s by p)—shows that in this respect also the definite hydrates H_2SO_4 and $\text{H}_2\text{SO}_4 \cdot \text{H}_2\text{O}$ clearly stand out among the solutions. The variations of these increments are given on the accompanying diagram, where the percentage amounts of H_2SO_4 in the solutions are laid out along the axes of abscissæ, and the magnitudes of these increments are laid along the axes of the ordinates. It is seen that these magnitudes lie in straight lines, proceeding from one definite hydrate to another, where they undergo a rupture and change their direction. This is most clearly seen in the normal hydrate H_2SO_4 ($p=100$ p.c.). From $\text{H}_2\text{SO}_4 \cdot \text{H}_2\text{O}$ to H_2SO_4 ds/dp is expressed by the straight line $729 - 7.49p$, and therefore when $p=100$, the increment of the specific gravity ds/dp is a negative quantity $= -20$; this signifies that in approaching to the hydrate H_2SO_4 , the specific gravity does not rise, but falls, with the increase of the amounts of H_2SO_4 . And in reality Kohlrausch, Schertel, and others found that the specific gravity of the normal acid is less than that of its first mixtures with water, and that the maximum specific gravity (when $ds/dp=0$) corresponds not with H_2SO_4 —that is, not to $p=100$ —but nearly with $p=97\frac{1}{2}$ p.c. And thus, according as the aqueous acid by the addition of sulphuric anhydride approaches from $97\frac{1}{2}$ p.c. to 100 p.c., or H_2SO_4 , the specific gravity falls, $ds/dp = -20$. But directly the addition of sulphuric anhydride is in excess of that needed to form the hydrate H_2SO_4 , and fuming sulphuric acid begins to be formed, the specific gravity begins to rise—thus, then $s=18528 + 129(p-100) + 3.9(p-100)^2$,⁵⁴

⁵⁴ In order to preserve the same form of expression for the composition of fuming sulphuric acid as for the weaker solutions, I take p as that quantity of normal acid H_2SO_4 which may be obtained from 100 parts by weight of a given solution. If $p=$

therefore ds/dp then $=129 + 7.8(p-100)$, consequently when $p=100$ the magnitude ds/dp is no longer negative but positive, and $=129$. That is, at the point H_2SO_4 there is a rupture in the continuity of ds/dp




FIG. 89. —Diagram showing the variation of the factor (ds/dp) of the specific gravity of solutions of sulphuric acid. The percentage quantities of the acid, H_2SO_4 , are laid out on the axes of abscissa. The ordinates are the factors or rises in sp. gr. (water at 4 = 10.000) with the increase in the quantity of H_2SO_4 .

from -20 to $+129$, as is seen from the diagram, where VV depict ds/dp from H_2SO_4, H_2O to H_2SO_4 and VI depicts ds/dp from H_2SO_4 in the direction of fuming sulphuric acid.

In a like manner it may be shown that the increment or quotient ds/dp attains a maximum value (among all solutions of sulphuric acid in water) at the hydrate $H_2SO_4 \cdot 2H_2O$, which corresponds with the greatest contraction and rise of temperature in the admixture of sulphuric acid with water. And as this hydrate has the composition $S(OH)_6 = H_2SO_4 \cdot 2H_2O$, which corresponds with many salts—for in-

95 p.c., it signifies that out of 100 grams of this acid 95 grams of the normal acid H_2SO_4 may be obtained (by the removal of water); if $p=110$ p.c. it means that from 100 grams of the given acid we can obtain (by adding water) 110 grams of the acid H_2SO_4 . It is obvious that for fuming acids p is greater than 100. For sulphuric anhydride the value of p is 122.5.

stance, with $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$ —therefore, although it is not known in a solid form like $\text{H}_2\text{SO}_4 \cdot \text{H}_2\text{O} = \text{SO}(\text{OH})_4$ and $\text{H}_2\text{SO}_4 = \text{SO}_2(\text{OH})_2$, still it must be recognised as a definite compound of water and sulphuric acid.⁵⁵

In practice, where sulphuric acid is used in immense quantities it is very important to be able to accurately and rapidly determine the amount of normal hydrate in aqueous solutions. For this purpose recourse is generally had to the determination of the specific gravity, and therefore we give below a table of the specific gravities of solutions of sulphuric acid, for four temperatures t , taking the sp. gr. of water at $4^\circ = 1000$.⁵⁶

	0°	10°	20°	30°
0 p. c.	0.9999	0.9997	0.9983	0.9958
10	1.073	1.070	1.066	1.061
20	1.150	1.145	1.139	1.133
30	1.232	1.224	1.217	1.210
40	1.317	1.309	1.301	1.294
50	1.409	1.401	1.393	1.385
60	1.515	1.506	1.497	1.488
70	1.629	1.619	1.609	1.599
80	1.748	1.737	1.726	1.716
90	1.836	1.825	1.814	1.804
100	1.853	1.842	1.832	1.822

The great affinity of sulphuric acid for water is also seen from the fact that when the strong acid acts on the majority of *organic*

⁵⁵ Although not so clearly proved, still, judging from the specific gravities, we should recognise another hydrate, $\text{H}_2\text{SO}_4 \cdot 6\text{H}_2\text{O}$, and one more very highly hydrated hydrate, $\text{H}_2\text{SO}_4 \cdot 150\text{H}_2\text{O}$, at which point the direction of ds/dp changes (as is seen in the diagram), but whose composition cannot yet be accurately determined with the sum of the data now at our disposal. The researches (see Note 53) made by me in this direction have since found indirect confirmation in the careful observations on solutions of ferric chloride and zinc chloride (Chapter XVI. Note 4) carried on by Cheltzoff, which show that for these salts dt/dp exhibits nearly the same changes as sulphuric acid. Besides which, H. Crompton (1888), in his researches on the electrical conductivity of solutions of sulphuric acid, and Tammann, in his observations on their vapour tension, found a correlation with the hydrates indicated, as above, by the investigation of their specific gravities. This subject, which has so recently entered into the literature of chemistry, and which is connected with the theory of the dissociation of the hydrates occurring (Chapter I.) in solutions, will probably be elucidated by further work, and requires fresh special research.

⁵⁶ Besides which, the following are the sp. gr. about 100 p.c. :—

	0°	10°	20°	30°
96 p.c.	1.835	1.844	1.834	1.824
98 "	1.855	1.845	1.834	1.824
100 "	1.853	1.842	1.832	1.822
102 "	1.880	1.869	1.859	1.848
104 "	1.911	1.899	1.888	1.878

substances (especially when heated) it very frequently *takes up the elements of water* occurring in them. Thus strong sulphuric acid acting on alcohol, C_2H_6O , takes up the elements of water from it, and converts it into olefiant gas, C_2H_4 . It acts in a similar manner on wood and other vegetable tissues, which it chars. If a piece of wood be immersed in strong sulphuric acid it turns black. This is owing to the fact that the wood contains carbohydrates which give up hydrogen and oxygen as water to the sulphuric acid, leaving charcoal, or a black mass very rich in it, behind. For example, cellulose, $C_6H_{10}O_5$, acts in this manner. Hence it is said, that sulphuric acid *chars* organic matter.⁵⁷

The second most important peculiarity of sulphuric acid is its distinct and very *energetic acid properties*, which we have already had frequent occasion to notice, and therefore we will now only consider a few of their aspects. First of all we must remember that, with calcium, strontium, and especially with barium and lead, sulphuric acid forms very slightly soluble salts, whilst with the majority of other metals it gives more easily soluble salts, which in the majority of cases are able, like sulphuric acid itself, to combine with water to form crystallohydrates. Normal sulphuric acid, containing two atoms of hydrogen in its molecule, is able already for this reason alone to form two classes of salts, *normal* and *acid*, which it does with great facility *with the alkali metals*. The metals of the alkaline earths and the majority of other metals, if they do form acid sulphates, do so under exceptional conditions (with an excess of strong sulphuric acid), and these salts when formed are decomposable by water—that is, although having a certain degree of physical stability they have no chemical stability. Besides the acid salts $RHSO_4$, sulphuric acid also gives other forms of acid salts. An entire series of salts having the composition $RHSO_4, H_2SO_4$, or for bivalent metals $RSO_4, 3H_2SO_4$,⁵⁸ have been prepared. Such

⁵⁷ If sulphuric acid be kept in an open vessel, the organic matter of the dust held in the atmosphere falls into it and blackens the acid. The same thing happens if sulphuric acid is kept in a bottle closed by a cork, because the cork becomes charred, and the acid turns black. However, the chemical properties of the acid undergo a very slight change when it turns black, so that it is still fit for many purposes. Sulphuric acid which is considerably diluted with water does not produce the above effects, which clearly shows their dependence on the affinity of the sulphuric acid for water. It is evident from the preceding that strong sulphuric acid will act as a powerful poison; whilst, on the other hand, when very dilute it is even employed as a fertiliser, and it is sometimes poured directly over fields destined for vegetation, and sometimes plants themselves are washed with it. If taken internally by animals in a very dilute solution it has very little action, although the strong acid is a very powerful poison, just as acetic acid in a very strong solution is poisonous, and a dilute solution forms the vinegar used for consumption.

⁵⁸ Weber (1884) obtained a series of salts $R_2O, 8SO_3$ for K, Rb, Cs, and Tl.

salts have been obtained for potassium, sodium, nickel, calcium, silver, magnesium, manganese. They are prepared by dissolving the sulphates in an excess of sulphuric acid, and heating the solution until the excess of sulphuric acid is driven off; on cooling, the mass solidifies into a crystalline salt. Besides which, Rose obtained a salt having the composition $\text{Na}_2\text{SO}_4 \cdot \text{NaHSO}_4$, and if HNaSO_4 be heated it easily forms a salt $\text{Na}_2\text{S}_2\text{O}_7 = \text{Na}_2\text{SO}_4 \cdot \text{SO}_3$; hence it is clear that sulphuric anhydride combines with various proportions of bases, just as it combines with various proportions of water.

We already know that sulphuric acid displaces the acid from the salts of nitric, carbonic, and many other volatile acids. Berthollet's laws, as we have seen (Chapter X.), explain this fact, and show that sulphuric acid does not *displace* the above *acids*, because it has a greater affinity for bases, but only because of its small volatility; and, indeed, in an aqueous solution sulphuric acid displaces the much less soluble boric acid from its compounds—for instance, from borax, and it also displaces silica from its compounds with bases; but both boric anhydride and silica, when fused with sulphates, decompose them, displacing sulphuric anhydride, SO_3 , because they are less volatile than sulphuric anhydride and sulphuric acid itself.

The reactions of sulphuric acid *with respect to organic substances* are generally determined by its acid character, when the direct extraction of water, or oxidation at the expense of the oxygen of the sulphuric acid,⁵⁹ or disintegration does not take place. So, for example, with sulphuric acid the majority of the saturated hydrocarbons, $\text{C}_n\text{H}_{2m+2}$, form a special class of *sulphonic acids*, $\text{C}_n\text{H}_{2m+1}(\text{HSO}_3)$; for example, benzene, C_6H_6 , forms benzenesulphonic acid, $\text{C}_6\text{H}_5 \cdot \text{SO}_3\text{H}$, water being separated, for the formation of which oxygen is taken up from the sulphuric acid, because the product contains less oxygen than the sulphuric acid. It is evident from these acids that the hydrogen in organic compounds is replaceable by the group SO_3H , just as it may be replaced by the radicles Cl , NO_2 , CO_2H , and others. As the radicle

⁵⁹ For example, the action of hot sulphuric acid on nitrogenous compounds, as applied in Kjeldahl's method for the estimation of nitrogen (Vol. I. p. 246). It is obvious that when sulphuric acid acts as an oxidising agent, it forms sulphurous anhydride.

The action of sulphuric acid on the alcohols is exactly similar to its action on alkalis, because the alcohols, like alkalis, react on acids; a molecule of alcohol with a molecule of sulphuric acid separates water and forms an *acid* ethereal salt—that is, there is produced an ethereal compound corresponding with acid salts. Thus, for example, the action of sulphuric acid, H_2SO_4 , on common alcohol, $\text{C}_2\text{H}_5\text{OH}$, gives water and sulphovinic acid, $\text{C}_2\text{H}_5\text{HSO}_4$ —that is, sulphuric acid in which one atom of hydrogen is replaced by the radicle C_2H_5 of ethyl alcohol, $\text{SO}_3(\text{OH})(\text{OC}_2\text{H}_5)$, or, which is one and the same thing, the hydrogen in alcohol is replaced by the radicle (sulphoxyl) of sulphuric acid, $\text{C}_2\text{H}_5\text{O} \cdot \text{SO}_2(\text{OH})$.

of sulphuric acid or *sulphoxyl*, SO_2OH or SHO_3 , contains, like carboxyl (Vol. I. p. 383), one hydrogen (hydroxyl) of sulphuric acid, therefore the resultant substances are acids whose basicity is equal to the number of hydrogens replaced by sulfoxyl. And as sulfoxyl takes the place of hydrogen, and itself contains hydrogen, therefore the sulpho-acids are equal to a hydrocarbon + SO_3 , just as every organic (carboxylic) acid is equal to a hydrocarbon + CO_2 . Moreover, here this relation corresponds with the direct reaction, because many sulphonic acids are obtained by the direct combination of sulphuric anhydride: $\text{C}_6\text{H}_5(\text{SO}_3\text{H}) = \text{C}_6\text{H}_6 + \text{SO}_3$. The sulphonic acids give soluble barium salts, and are therefore easily distinguished from sulphuric acid. They are soluble in water, are not volatile, and when distilled give sulphurous anhydride (whilst the hydroxyl previously in combination with the sulphurous anhydride remains in the hydrocarbon group; thus phenol, $\text{C}_6\text{H}_5\cdot\text{OH}$, is obtained from benzenesulphonic acid), and they are very energetic, because the hydrogen acting in them is of the same nature as in sulphuric acid itself.⁶⁰

Sulphuric acid, as containing a large proportion of oxygen, is a substance which frequently acts as an oxidising agent: in which case it is *deoxidised*, forming *sulphurous anhydride* and water (or even, although more rarely, sulphuretted hydrogen and sulphur). Sulphuric acid acts in this manner on charcoal, copper, mercury, silver, organic and other substances, which are unable to evolve hydrogen from it directly, as we saw in describing sulphurous anhydride.

Although a higher form of oxide capable of giving salts, sulphuric

⁶⁰ We will mention the following difference between the sulphonic acids and the ethereal acid sulphates (Note 59): the former re-form sulphuric acid with difficulty and the latter easily. Thus sulphovinic acid when heated with an excess of water is reconverted into alcohol and sulphuric acid. This is explained in the following manner. Both these classes of acids are produced by the substitution of hydrogen by SO_3H , or the univalent radicle of sulphuric acid, but in the formation of ethereal acid sulphates the SO_3H replaces the hydrogen of the hydroxyl in the alcohol, whilst in the formation of the sulphonic acids the SO_3H replaces the hydrogen of a hydrocarbon. This difference clearly evinces itself in the existence of two acids of the composition $\text{SO}_4\text{C}_2\text{H}_6$. The one, mentioned above, is alcohol, $\text{C}_2\text{H}_5\cdot\text{OH}$, in which the hydrogen of the hydroxyl is replaced by sulfoxyl = $\text{C}_2\text{H}_5\cdot\text{OSO}_3\text{H}$, whilst the other is alcohol, in which one atom of the hydrogen in ethyl, C_2H_5 , is replaced by the sulphonic group—that is = $\text{C}_2\text{H}_4(\text{SO}_3\text{H})\cdot\text{OH}$. The latter is called isethionic acid. It is more stable than sulphovinic acid. The details as to these interesting compounds must be looked for in organic chemistry, but I think it necessary to note one of the general methods of formation of these acids. The sulphites of the alkalis—for example, K_2SO_3 —when heated with the halogen products of metalepsis, give a halogen salt and a salt of a sulphonic acid. Thus methyl iodide, CH_3I , corresponds with marsh gas, CH_4 , and at 100° with a solution of potassium sulphite, K_2SO_3 , it gives potassium iodide, KI , and potassium methylsulphonate, $\text{CH}_3\text{SO}_3\text{K}$ —that is, a salt of the sulphonic acid. This shows that the sulphonic acid may be referred to sulphurous acid, because there is a resemblance between sulphuric and sulphurous acid, which clearly evinces itself here in the formation of one product from them both.

anhydride is capable of further oxidation, and forms a kind of peroxide, just as hydrogen gives hydrogen peroxide, in addition to water, or as sodium and potassium, besides the oxides Na_2O and K_2O , give their peroxides, compounds which are in a chemical sense unstable, powerfully oxidising, and which do not directly enter into saline combinations. If the oxides of potassium, barium, &c., be likened to water, then their peroxides must naturally be likened to hydrogen peroxide,⁶¹ not only because the oxygen contained in them is very mobile and easily liberated, and because their reactions are similar, but also because they can be mutually transformed into each other, and because, although they do not give true salts, they are able to form mutual compounds and hydrates, as is seen from Schöne's researches, who obtained a compound of barium peroxide with hydrogen peroxide.⁶² And this is the character of *sulphuric peroxide*, S_2O_7 , discovered in 1878 by Berthelot, and called by him *persulphuric acid*, although it does not form salts, nor exhibit any properties that can justify its being termed an acid;⁶³ thus it decomposes spontaneously, and is

⁶¹ The reaction $\text{BaO} + \text{O}$ develops 12000 heat units, whilst the reaction $\text{H}_2\text{O} - \text{O}$ absorbs -21000 heat units.

⁶² If barium peroxide be dissolved in hydrochloric (or acetic) acid, or if a solution of hydrogen peroxide be diluted with a solution of barium hydroxide, a pure hydrate is precipitated having the composition $\text{BaO}_2 \cdot 8\text{H}_2\text{O}$ (sometimes the composition is taken as $\text{BaO}_2 \cdot 6\text{H}_2\text{O}$). This fact was already known to Thenard. Schöne showed that if hydrogen peroxide be in excess, a crystalline compound of both peroxides, $\text{BaO}_2 \cdot \text{H}_2\text{O}_2$, is precipitated. Schöne also obtained small well-formed crystals of the same composition by adding a solution of ammonia to an acid solution of barium peroxide (containing a barium salt and hydrogen peroxide). Thus barium peroxide combines with both water and hydrogen peroxide. This is a very important fact for the comprehension of the composition of other peroxides, which has recently occupied the attention of many chemists.

⁶³ There is only one circumstance which might cause the oxide S_2O_7 to be named as it was by Berthelot, but this circumstance is purely external and conditional, and depends on the fact that the dioxides MnO_2 and PbO_2 are frequently called peroxides, although they are of a different nature from the true peroxides, H_2O_2 , BaO_2 , Na_2O_2 , &c. Manganese and its analogues, which give bases and acids, form peroxides from basic oxides *plus* oxygen, and the peroxides *plus* oxygen give the acids; and among them is MnO_5 , the analogue of SO_3 , and Mn_2O_7 the analogue in composition of S_2O_7 . But it is evident that the properties of the peroxides are independent, and MnO_2 has as little resemblance to the peroxides of hydrogen, sodium, and barium as it has to the oxides PtO_2 , SO_2 , SiO_2 , and even PbO_2 , although here the oxides are formed on the same type. In the first place, those true peroxides, among which S_2O_7 must be reckoned, present a higher type of oxide than the salt-forming oxide (and in the case of MnO_2 there are still higher acid oxides, MnO_5 and Mn_2O_7), and in the second place they contain oxygen, which is as easily liberated in reactions as in hydrogen peroxide.

In order to clearly demonstrate the possibility of a peroxide form for acids, it should be mentioned that Brodie long ago obtained the so-called *acetic peroxide* $(\text{C}_2\text{H}_3\text{O})_2\text{O}_2$, by the action of barium peroxide on acetic anhydride $(\text{C}_2\text{H}_3\text{O})_2\text{O}$. Its corresponding hydrate is also known. This shows that true peroxides and their hydrates, with reactions similar to those of hydrogen peroxide, may be possible for acids, as we find to be the case with acetic peroxide and its hydrate. And such, in my opinion, is the

formed from $2\text{SO}_3 + \text{O}$ with the absorption of heat (-27 thousand heat units), like ozone from $\text{O}_2 + \text{O}$ (-29 thousand units of heat), or hydrogen peroxide $\text{H}_2\text{O} + \text{O}$ (-21 thousand heat units). It gives a compound with hydrogen peroxide like that formed by barium peroxide; it is formed from strong sulphuric acid and hydrogen peroxide, exactly like calcium peroxide; it is even decomposed by platinum, and presents all the characters of the true peroxides.

The hydrate of sulphuric peroxide, $\text{S}_2\text{O}_7 \cdot \text{H}_2\text{O} = \text{S}_2\text{H}_2\text{O}_8$, is obtained more simply by mixing strong sulphuric acid (not weaker than $\text{H}_2\text{SO}_4 \cdot 2\text{H}_2\text{O}$) directly with hydrogen peroxide, or by the action of a galvanic current on sulphuric acid mixed with a certain amount of water, and cooled, the electrodes being platinum wires, when it naturally appears at the positive pole.⁶¹ When an acid of the strength $\text{H}_2\text{SO}_4 \cdot 6\text{H}_2\text{O}$ is taken, then at first the hydrate of the sulphuric peroxide, $\text{S}_2\text{O}_7 \cdot \text{H}_2\text{O}$, only is formed: but when the concentration about the positive pole reaches $\text{H}_2\text{SO}_4 \cdot 3\text{H}_2\text{O}$, then a mixture of hydrogen peroxide and the hydrate of sulphuric peroxide begins to be formed. A

relation of S_2O_7 and its compounds with water and hydrogen peroxide to sulphuric acid, and therefore I call S_2O_7 the sulphur peroxide or the sulphuryl peroxide. It is evident from the above that similar peroxides may be expected for other acids also. A similar higher oxide has long been known for chromium, and Berthelot obtained a like compound for nitric acid; but these have been far less studied than S_2O_7 , which Berthelot discovered and investigated with a certain amount of detail.

Anhydrous sulphuric peroxide, S_2O_7 , is obtained by the prolonged (8 to 10 hours) action of a silent discharge of considerable intensity on a mixture of oxygen and sulphurous anhydride; the vapour of sulphuric peroxide, S_2O_7 , condenses as liquid drops, or after being cooled to 0° in the form of long prismatic crystals, resembling those of sulphuric anhydride. The anhydrous compound S_2O_7 (and also the hydrous) cannot be preserved long, as it splits up into oxygen and sulphuric anhydride. Direct experiment shows that a mixture of equal volumes of sulphurous anhydride and oxygen leaves a residue of a quarter of the oxygen taken, or half of the whole volume, which indicates the formula S_2O_7 . This substance is soluble in water, and it then gives a hydrate, probably having the composition $\text{S}_2\text{O}_7 \cdot \text{H}_2\text{O} = 2\text{SHO}_4$. This solution oxidises the salts SnX_2 , potassium iodide, and others, which renders it possible to prove that the solution actually contains one atom of oxygen capable of effecting oxidation to two molecules of sulphuric anhydride.

⁶¹ Many other peroxides of various elements may be obtained by a similar method of double decomposition or by the action of a galvanic current (when the higher oxygen compound is formed at the anode). Thus Spring (1889), by acting at the ordinary temperature with an excess of pure hydrated barium peroxide (precipitated from a solution of hydrogen peroxide by the addition of barium hydroxide) on a solution of stannous chloride (saturated and containing hydrochloric acid), obtained a cloudy solution, which after dialysis (lasting three months, with the daily renewal of the external water) and evaporation left a white mass having the composition $\text{H}_2\text{Sn}_2\text{O}_7$. Spring regarded this substance as a hyperstannic acid, although he did not obtain any corresponding salts. It appears to me possible to admit that the substance is a compound of hydrogen peroxide with tin peroxide, Sn_2O_5 , because $\text{Sn}_2\text{H}_2\text{O}_7 = \text{H}_2\text{O}_2 + \text{Sn}_2\text{O}_5$, although it is also possible to admit that the peroxide forms of tin are Sn_2O_5 and SnO_3 , and if the substance obtained contains SnO_3 , then $\text{Sn}_2\text{O}_7\text{H}_2 = \text{H}_2\text{O}_2 \cdot 2\text{SnO}_3$.

state of equilibrium is ultimately arrived at between the amount of these substances which corresponds with the proportion $\text{S}_2\text{O}_7 : 2\text{H}_2\text{O}_2$, which, as it were, answers to a hydrate $\text{S}_2\text{O}_9, 2\text{H}_2\text{O}$. But its existence cannot be recognised, because the sulphuric peroxide can be easily distinguished from the hydrogen peroxide in the solution, owing to the fact that the former does not act on an acid solution of potassium permanganate, whilst the hydrogen peroxide evolves both its own oxygen and that of the permanganic acid and converts it into manganous oxide; this enables the relative amounts of S_2O_7 and H_2O_2 to be determined. Their common property of liberating iodine from an acid solution of potassium iodide enables the sum of active oxygen in them both to be determined. Dilute solutions of sulphuric peroxide can be kept better than more concentrated solutions, and the latter may be obtained containing as much as 123 grams of the peroxide to a litre. It is a very instructive fact that hydrogen peroxide is always formed when strong solutions of sulphuric peroxide break up on keeping. So that the bond between both peroxides is established both by analysis and synthesis: hydrogen peroxide is able to give sulphuric peroxide, and the latter to give hydrogen peroxide. A mixture of sulphuric peroxide with sulphuric acid or water is immediately decomposed, with the evolution of oxygen, either when heated or under the action of spongy platinum. The same thing takes place with a solution of baryta, only not so rapidly, so that the solution may be filtered. Mercury, ferrous oxide, and the stannous salts, are oxidised by sulphuric peroxide. These are all distinct signs of true peroxides.

In order to see the relations of sulphuric peroxide, we must first remark that hydrogen peroxide is considered, in the sense of the law of substitutions, as water, $\text{H}(\text{OH})$, in which H is replaced by (OH) : $\text{OH}(\text{OH}) = \text{H}_2\text{O}_2$. The relation of $\text{H}_2\text{S}_2\text{O}_8$ or $\text{H}_2\text{O}, \text{S}_2\text{O}_7$ to H_2SO_4 is exactly similar. Indeed, the radicle of sulphuric acid, equivalent to hydrogen, is HSO_4 ; ⁶⁵ it corresponds with the (OH) of water, and therefore sulphuric acid, $\text{H}(\text{SHO}_4)$, gives $(\text{SHO}_4)_2$ or $\text{S}_2\text{H}_2\text{O}_8$, in exactly the same manner as water gives $(\text{HO})_2$ —i.e. H_2O_2 . ⁶⁶

⁶⁵ Or one of those supposed ions which appear at the positive pole in the decomposition of sulphuric acid by the action of a galvanic current.

⁶⁶ If this be true one would expect the following peroxide hydrates: for phosphoric acid, $(\text{H}_2\text{PO}_4)_2 = \text{H}_4\text{P}_2\text{O}_8 = 2\text{H}_2\text{O} + 2\text{PO}_3$; for carbonic acid, $(\text{HCO}_3)_2 = \text{H}_2\text{C}_2\text{O}_6 = \text{H}_2\text{O} + \text{C}_2\text{O}_3$; and for lead the true peroxide will be also Pb_2O_5 , &c. Judging from the example of barium peroxide (Note 62), these peroxide forms will probably combine together. It seems to me that the compounds obtained by Fairley for uranium are very instructive as elucidating the peroxides. In the action of hydrogen peroxide in an acid solution on uranium oxide, UO_3 , there is formed a uranium peroxide, $\text{UO}_4, 4\text{H}_2\text{O}$ ($\text{U} - 240$), but hydrogen peroxide acts on uranium oxide in the presence of caustic soda; then on the addition of alcohol a crystalline compound containing $\text{Na}_4\text{UO}_8, 4\text{H}_2\text{O}$ is precipitated,

The largest proportion of *sulphuric acid* is used for reacting on sodium chloride in the manufacture of sodium carbonate; for the manufacture of the volatile acids, like nitric, hydrochloric, &c., from their corresponding salts; for the preparation of ammonium sulphate, alums, vitriols (copper and iron), and other salts of sulphuric acid; in the treatment of bone-ash for the preparation of phosphorus, and for the solution of metals—for example, of silver in its separation from gold—for cleaning metals from rust, &c. A large amount of oil of vitriol is also used in treatment of organic substances; it is used for the extraction of stearin, or stearic acid, from tallow, for refining petroleum and various vegetable oils, for purifying madders, for the solution of indigo and other colouring matters, for the conversion of paper into vegetable parchment, for the preparation of ether from alcohol, for the preparation of various artificial scents from fusel oil, for the preparation of vegetable acids, such as oxalic, tartaric, citric, for the conversion of non-fermentable starchy substances into fermentable glucose, and in a number of other processes. It would be difficult to find another artificially-prepared substance which is so frequently applied in the arts as sulphuric acid. Where there are not works for its manufacture, the rational production of many other substances of great technical importance is impossible. In those localities which have arrived at a high technical activity the amount of sulphuric acid consumed is proportionally large; sulphuric acid, sodium carbonate, and lime are the most important of the artificially-prepared agents employed at technical works.

Besides the normal acids of sulphur, H_2SO_3 , $\text{H}_2\text{SO}_3\text{S}$, and H_2SO_4 , corresponding with sulphuretted hydrogen, H_2S , in the same way that the oxy-acids of chlorine correspond with hydrochloric acid, HCl , there exists a particular series of acids which are termed *thionic acids*. Their general composition is $\text{S}_n\text{H}_2\text{O}_6$, where n varies from 2 to 5. If $n=2$, the acid is called dithionic acid. The others are distinguished as trithionic, tetrathionic, and pentathionic acids. Their composition, existence, and reactions are very easily understood if they be referred to the class of the sulphonic acids—that is, if their relation to sulphuric acid be expressed in just the same manner as the relation of the organic acids to carbonic acid. The organic acids, as we saw (Chapter IX.), proceed from the hydrocarbons by the substitution of their hydrogen by carboxyl—that is, by the radicle of carbonic acid,

which is doubtless a compound of the peroxides of sodium, Na_2O_2 , and uranium, UO_4 . It is very possible that the first peroxide, $\text{UO}_4 \cdot 4\text{H}_2\text{O}$, contains the elements of hydrogen peroxide and uranium peroxide, U_2O_7 , or even $\text{U}(\text{OH})_6 \cdot \text{H}_2\text{O}_2$, just as the peroxide form lately discovered by Spring for tin perhaps contains $\text{Sn}_2\text{O}_3 \cdot \text{H}_2\text{O}_2$.

$\text{CH}_2\text{O}_3 - \text{HO} = \text{CHO}_2$. The formation of the acids of sulphur may be represented in the same manner. Therefore to hydrogen there should correspond the acids HSO_3 , sulphurous, and $\text{SHO}_3 \cdot \text{SHO}_3 = \text{S}_2\text{H}_2\text{O}_6$, or dithionic; for SH_2 there should correspond the acids $\text{SH}(\text{SHO}_3) = \text{H}_2\text{S}_2\text{O}_3$ (thiosulphuric), and $\text{S}(\text{SHO}_3)_2 = \text{H}_2\text{S}_3\text{O}_6$ (trithionic); for S_2H_2 the acids $\text{S}_2\text{H}(\text{SHO}_3) = \text{H}_2\text{S}_3\text{O}_2$ (unknown), and $\text{S}_2(\text{SHO}_3)_2 = \text{H}_2\text{S}_4\text{O}_6$ (tetrathionic); for S_3H_2 the acids $\text{S}_3\text{H}(\text{SHO}_3)$ and $\text{S}_3(\text{SHO}_3)_2 = \text{H}_2\text{S}_5\text{O}_6$ (pentathionic). Iodine reacts directly with the hydrogen of sulphuretted hydrogen and combines with it, and it reacts still more clearly with the metals which have replaced this hydrogen. Thiosulphuric acid contains the radicle of sulphuretted hydrogen or hydrogen (united with sulphur) of the same nature as in sulphuretted hydrogen; so it is not, therefore, surprising that iodine reacts on sodium thiosulphate and forms sodium tetrathionate. So, thiosulphuric acid, $\text{HS}(\text{SHO}_3)$, when deprived of H, gives a radicle which immediately combines with another similar radicle, forming the tetrathionate $\text{S}_2(\text{SO}_2\text{HO})_2$. With this view ⁶⁷ of the structure of the thionic acids and salts, it is also clear how all the thionic acids, like thiosulphuric acid, easily give sulphur and sulphides, with the exception only of dithionic acid, $\text{H}_2\text{S}_2\text{O}_6$, which, judging from the above, stands apart from the series of the other thionic acids. Dithionic acid stands in the same relation to sulphuric acid as oxalic acid does to carbonic acid. Oxalic acid is dicarboxyl, $(\text{CHO}_2)_2 = \text{C}_2\text{H}_2\text{O}_4$, and so also dithionic acid is disulphoxyl, $(\text{SHO}_3)_2 = \text{S}_2\text{H}_2\text{O}_6$. Oxalic acid when ignited decomposes into carbonic anhydride and carbonic oxide, CO, and dithionic acid when heated decomposes into sulphuric anhydride and sulphurous anhydride, SO_2 , and SO_2 stands in the same relation to SO_3 as CO to CO_2 . This also explains the peculiarity of the calcium, barium, and lead, &c., salts of the thionic acids being easily soluble, although the corresponding salts of H_2SO_3 , H_2SO_4 , and H_2S dissolve with difficulty, because the former are similar to the salts of the sulphonic acids, which are also soluble in water. Thus the thionic acids are *disulphonic acids*, just as many dicarboxylic acids are known for carbon—for example, $\text{CH}_2(\text{CO}_2\text{H})_2$, $\text{C}_6\text{H}_4(\text{CO}_2\text{H})_2$.⁶⁸

⁶⁷ This view was communicated by me in 1870 to the Russian Chemical Society (*Journal of the Russian Chemical Society*, 1870, p. 276).

⁶⁸ *Dithionic acid*, $\text{H}_2\text{S}_2\text{O}_6$, is distinguished among the thionic acids as containing the least proportion of sulphur. It is also called hyposulphuric acid, because its supposed anhydride, S_2O_5 , contains more O than sulphurous oxide, SO_2 or S_2O_4 , and less than sulphuric anhydride, SO_3 or S_2O_6 . Dithionic acid, discovered by Gay-Lussac and Welter, is known as a hydrate and as salts, but not as anhydride. The method for preparing dithionic acid usually employed is by the action of finely-powdered manganese dioxide on a solution of sulphurous anhydride. On shaking, the smell of the latter disappears, and the manganese salt of the acid in question passes into solution;

Sulphur exhibits an acid character, not only in its compounds with hydrogen and oxygen, but also in those with other elements. The

$\text{MnO}_2 + 2\text{SO}_2 = \text{MnS}_2\text{O}_6$. If the temperature be raised, the dithionate splits up into sulphurous anhydride and manganese sulphate, MnSO_4 . Generally owing to this a mixture of manganese sulphate and dithionate is obtained in the solution. They may be separated by mixing the solution of the manganese salts with a solution of barium hydroxide, when a precipitate of manganese hydroxide and barium sulphate is obtained. In this manner barium dithionate only is obtained in solution. This salt is purified by crystallisation, in which form it separates as $\text{BaS}_2\text{O}_6 \cdot 2\text{H}_2\text{O}$; this is then dissolved in water, and decomposed with the requisite amount of sulphuric acid. Dithionic acid, $\text{H}_2\text{S}_2\text{O}_6$, then remains in solution. By concentrating the resultant solution under the receiver of an air-pump it is possible to obtain a liquid of sp. gr. 1.347, but it still contains water, and on further evaporation the acid decomposes into sulphuric acid and sulphurous anhydride: $\text{H}_2\text{S}_2\text{O}_6 = \text{H}_2\text{SO}_4 + \text{SO}_2$. The same decomposition takes place if the solution be slightly heated. Like all the thionic acids, dithionic acid is readily attacked by oxidising agents, and passes into sulphurous acid. No dithionate is able to withstand the action of heat, even when very slight, without giving off sulphurous anhydride: $\text{K}_2\text{S}_2\text{O}_6 = \text{K}_2\text{SO}_4 + \text{SO}_2$. The alkali dithionates have a neutral reaction (which indicates the energetic nature of the acid), are soluble in water, and in this respect present a certain resemblance to the salts of nitric acid. The latter circumstance probably depends on the analogy of the atomic composition of dithionic and nitric acids and of their salts. Thus their anhydrides are N_2O_5 and S_2O_5 , their barium salts BaN_2O_6 and BaS_2O_6 ; but a difference must be recognised in the salts of the univalent metals KNO_3 and $\text{K}_2\text{S}_2\text{O}_6$, although the latter formula is divisible by two.

Langlois, about 1840, obtained a particular thionic acid by heating a strong solution of potassium acid sulphite with flowers of sulphur to about 60° , until the disappearance of the yellow coloration first produced by the solution of the sulphur. On cooling, a portion of the sulphur was precipitated, and there separated out crystals of a salt of *trithionic acid*, $\text{K}_2\text{S}_3\text{O}_6$ (partly mixed with potassium sulphate). Plessy afterwards showed that the action of sulphurous acid on a thiosulphate also gives sulphur and trithionic acid: $2\text{K}_2\text{S}_2\text{O}_5 + 3\text{SO}_2 = 2\text{K}_2\text{S}_3\text{O}_6 + \text{S}$. A mixture of potassium acid sulphite and thiosulphate also gives a trithionate. It is very possible that a reaction of the same kind occurs in the formation of trithionic acid by Langlois's method, because potassium sulphite and sulphur yield potassium thiosulphate. The potassium thiosulphate may also be replaced by potassium sulphide, and on passing sulphurous anhydride through the solution thiosulphate is first formed and then trithionate: $4\text{KHSO}_3 + \text{K}_2\text{S} + 4\text{SO}_2 = 3\text{K}_2\text{S}_3\text{O}_6 + 2\text{H}_2\text{O}$. The sodium salt is not formed under the same circumstances as the corresponding potassium salt. The sodium salt does not crystallise and is very unstable; the barium salt is, however, more stable. The barium and potassium salts are anhydrous, they give neutral solutions, and decompose when ignited, with the evolution of sulphur and sulphurous anhydride, a sulphate being left behind—for example, $\text{K}_2\text{S}_3\text{O}_6 = \text{K}_2\text{SO}_4 + \text{SO}_2 + \text{S}$. If a solution of the potassium salt be decomposed by means of hydrofluosilicic or chloric acid, the insoluble salts of these acids are precipitated, and trithionic acid is obtained in solution, which, however, very easily breaks up on concentration. The addition of salts of copper, mercury, silver, &c., to a solution of a trithionate, is followed, either immediately or after a certain time, by the formation of a black precipitate of the sulphides whose formation is due to the decomposition of the trithionic acid with the transference of its sulphur to the metal.

Tetrathionic acid, $\text{H}_2\text{S}_4\text{O}_6$, in contradistinction to the preceding acids, is much more stable in the free state than in the form of salts. In the latter form it is easily converted into trithionate, with liberation of sulphur. Sodium tetrathionate was obtained by Fordos and Gélis, by the action of iodine on a solution of sodium thiosulphate. The reaction essentially consists in the iodine taking up half the sodium of the thiosulphate, inasmuch as the latter contains $\text{Na}_2\text{S}_2\text{O}_5$, whilst the tetrathionate contains

compound of sulphur and carbon has been particularly well investigated. It presents a great analogy to carbonic anhydride, both in its elementary composition and chemical character. This substance is the so-called carbon bisulphide, CS_2 , and corresponds with CO_2 .

$\text{Na}_2\text{S}_2\text{O}_5$ or $\text{Na}_2\text{S}_4\text{O}_6$, so that the reaction is as follows: $2\text{Na}_2\text{S}_2\text{O}_5 + \text{I}_2 = 2\text{NaI} + \text{Na}_2\text{S}_4\text{O}_6$. It is evident that tetrathionic acid stands to thiosulphuric acid in exactly the same relation as dithionic acid does to sulphurous acid; for the same amount of the other elements in dithionate $\text{K}_2\text{S}_2\text{O}_6$, and tetrathionate $\text{K}_2\text{S}_4\text{O}_6$, there is half as much metal as in sulphite, K_2SO_3 , and thiosulphate, $\text{K}_2\text{S}_2\text{O}_5$. If in the above reaction the sodium thiosulphate is replaced by the lead salt PbS_2O_5 , the sparingly-soluble lead iodide PbI_2 and the soluble salt PbS_4O_6 are obtained. And the lead salt easily gives tetrathionic acid itself; for this purpose a solution of the salt is mixed with sulphuric acid until it ceases to give a precipitate of lead sulphate: $\text{PbS}_4\text{O}_6 + \text{H}_2\text{SO}_4 = \text{PbSO}_4 + \text{H}_2\text{S}_4\text{O}_6$. The lead salt may also be decomposed by sulphuretted hydrogen, but in this case a portion of the acid is decomposed, and evolves sulphurous anhydride. The solution of tetrathionic acid thus obtained may be evaporated directly over a water bath, and afterwards in a vacuum, when it gives a colourless liquid, which has no smell and an acid reaction. When dilute it may be heated to its boiling-point, but in a concentrated form it decomposes into sulphuric acid, sulphurous anhydride, and sulphur: $\text{H}_2\text{S}_4\text{O}_6 = \text{H}_2\text{SO}_4 + \text{SO}_2 + \text{S}_2$.

Pentathionic acid, $\text{H}_2\text{S}_5\text{O}_6$, also belongs to this series of acids. But little is known concerning it, either as hydrate or in salts. It is formed, together with tetrathionic acid, by the direct action of sulphurous acid on sulphuretted hydrogen in an aqueous solution; a large proportion of sulphur being precipitated at the same time: $5\text{SO}_2 + 5\text{H}_2\text{S} = \text{H}_2\text{S}_5\text{O}_6 + 5\text{S} + 4\text{H}_2\text{O}$.

If, as was shown above, the thionic acids are disulphonic acids, then they may be obtained, like other sulphonic acids, by means of potassium sulphite and sulphur chloride. Thus Spring demonstrated the formation of potassium trithionate by the action of sulphur dichloride on a strong solution of potassium sulphite: $2\text{KSO}_3\text{K} + \text{SCl}_2 = \text{S}(\text{SO}_3\text{K})_2 + 2\text{KCl}$. If sulphur chloride be taken, then sulphur is also precipitated. The same trithionate is formed by heating a solution of double thiosulphates, for example, of $\text{AgK}_2\text{S}_2\text{O}_5$. Two molecules of the salts then form silver sulphide and potassium trithionate. If the thiosulphate be the potassium silver salt $\text{SO}_3\text{K}(\text{AgS})$, then the structure of the trithionate must necessarily be $(\text{SO}_3\text{K})_2\text{S}$. Previous to Spring's researches the action of iodine on sodium thiosulphate was an isolated accidentally discovered reaction; he, however, showed its general significance by testing the action of iodine on mixtures of different sulphur compounds. Thus with iodine, I_2 , the mixture $\text{Na}_2\text{S} + \text{Na}_2\text{SO}_5$ forms $2\text{NaI} + \text{Na}_2\text{S}_2\text{O}_5$, whilst the mixture $\text{Na}_2\text{S}_2\text{O}_5 + \text{Na}_2\text{SO}_3 + \text{I}_2$ gives $2\text{NaI} + \text{Na}_2\text{S}_5\text{O}_6$ —that is, trithionic acid stands in the same relation to thiosulphuric acid as the latter does to sulphuretted hydrogen. And this is the same as our mode of representation: by replacing one hydrogen in H_2S by sulphuryl we obtain thiosulphuric acid, HSO_3HS , and by replacing a second hydrogen in the latter again by sulphuryl we obtain trithionic acid, $(\text{HSO}_3)_2\text{S}$. Furthermore, Spring showed that the action of sodium amalgam on the thionic acids causes reverse reactions to those above indicated for iodine. Thus sodium thiosulphate with Na_2 gives $\text{Na}_2\text{S} + \text{Na}_2\text{SO}_3$, and Spring showed that the sodium here is not a simple element taking up sulphur, but that it itself enters into double decomposition, replacing sulphur; for he took a potassium salt and acted on it with sodium: $\text{K}_2\text{S}_2\text{O}_5 + \text{Na}_2 = \text{NaKS} + \text{NaKSO}_3$, or, for sake of clearness, we may write it thus: $\text{KSO}_3(\text{SK}) + \text{NaNa} = \text{KSO}_3\text{Na} + (\text{SK})\text{Na}$. In a similar way sodium dithionate with sodium gives sodium sulphite: $(\text{NaSO}_3)_2 + \text{Na}_2 = 2\text{NaSO}_3\text{Na}$; sodium trithionate forms NaSO_3Na and NaSO_3SNa , and tetrathionate forms sodium thiosulphate, $(\text{NaSO}_3)_2\text{S}_2(\text{NaSO}_3) + \text{Na}_2 = 2(\text{NaSO}_3)(\text{NaS})$.

In all the oxidised compounds of sulphur we may note the presence of the elements

The first endeavours to obtain a compound of sulphur with carbon were unsuccessful, for although sulphur does combine directly with carbon, yet the successful formation of this compound requires distinctly definite conditions. If sulphur is mixed with charcoal and heated, it is completely driven off from the latter, and there is not obtained the smallest trace of carbon bisulphide. The formation of this compound requires that the charcoal should be first heated to a red heat, but not above, and then either the vapour of sulphur passed over it or lumps of sulphur thrown on to the red-hot charcoal, but in small quantities, so as not to lower the temperature of the charcoal. If the charcoal be heated to a white heat, the amount of carbon bisulphide formed is less. This depends, in the first place, on the carbon bisulphide dissociating at a high temperature.⁶⁹ In the second place, Favre and Silberman

of sulphurous anhydride, SO_2 , the only product of the combustion of sulphur, and in this sense the compounds of sulphur containing one SO_2 are—

$\text{SO}_2 \begin{smallmatrix} \text{H} \\ \text{HO} \end{smallmatrix}$	$\text{SO}_2 \begin{smallmatrix} \text{HO} \\ \text{HO} \end{smallmatrix}$	$\text{SO}_2 \begin{smallmatrix} \text{C}_6\text{H}_5 \\ \text{HO} \end{smallmatrix}$	$\text{SO}_2 \begin{smallmatrix} \text{HS} \\ \text{HO} \end{smallmatrix}$
Sulphurous acid	Sulphuric acid	Benzene sulphonic acid	Thiosulphuric acid

while, according to this mode of representation, the thionic acids are—

$\begin{smallmatrix} \text{HO} \\ \text{SO}_2 \\ \text{SO}_2 \\ \text{HO} \end{smallmatrix}$	$\begin{smallmatrix} \text{HO} \\ \text{SO}_2 \quad \text{S} \\ \text{SO}_2 \\ \text{HO} \end{smallmatrix}$	$\begin{smallmatrix} \text{HO} \\ \text{SO}_2 \quad \text{S}_2 \\ \text{SO}_2 \\ \text{HO} \end{smallmatrix}$	$\begin{smallmatrix} \text{HO} \\ \text{SO}_2 \quad \text{S}_3 \\ \text{SO}_2 \\ \text{HO} \end{smallmatrix}$
Dithionic	Trithionic	Tetrathionic	Pentathionic

Hence it is evident that SO_2 has (whilst CO_2 has not) the faculty for combination, and aims at forming SO_2X_2 . These X_2 can = O, and one involuntarily asks oneself if the O_2 which occurs in SO_2 is not of the same nature as this oxygen, which assimilates itself to SO_2 —that is, whether SO_2 does not correspond with the more general type SX_4 , and its compounds with the type SX_6 ? To this we may answer 'Yes' and 'No'—'Yes' in the general sense which proceeds from the investigation of the majority of compounds, especially metals, where RO corresponds with RCl_2 , RX ; 'No' in the sense that sulphur does not give either SH_4 , SH_6 , nor SCl_6 , and therefore the stages SX_4 and SX_6 are only observable in the oxygen compounds. In the sense of the type SX_6 one would expect a hydrate, $\text{S}(\text{HO})_6$, although not SCl_6 . And we must recognise this hydrate from a study of the compounds of sulphuric acid with water.

⁶⁹ Even light decomposes carbon bisulphide, but not to the extent of separating carbon; under the action of the sun's rays it is decomposed into sulphur and a solid substance which is considered to be carbon monosulphide; it is of a red colour, and its sp. gr. is 1.66. Thorpe (1889) observed a complete decomposition of carbon bisulphide under the action of a liquid alloy of potassium and sodium; it is accompanied by an explosion and the deposition of carbon and sulphur. A like complete decomposition of carbon bisulphide is also accomplished by the action of mercury fulminate (Chapter XVI. Note 26), and is due to the fact that *at the ordinary temperature* (at which carbon bisulphide is not produced) *the decomposition* of carbon bisulphide takes place with the development of heat—that is, it presents an exothermal reaction, like the decomposition of all explosives. It is very possible that at a higher temperature, when carbon bisulphide is formed, the combination of carbon with sulphur is also an exothermal reaction—that is,

showed that in the combustion of one gram of carbon bisulphide (the products will be $\text{CO}_2 + 2\text{SO}_2$) 3400 heat units are evolved—that is, the combustion of a molecular quantity of carbon bisulphide evolves 258400 heat units (according to Berthelot, 246000). From a molecule of carbon bisulphide we may obtain 12 parts of carbon, whose combustion evolves 96000 heat units and 64 parts by weight of sulphur, evolving by combustion (into SO_2) 140800 heat units. Hence we see that the component elements evolve less heat (237000 heat units) than carbon bisulphide—that is, that heat should be evolved (at the ordinary temperature) and not absorbed in its decomposition, and therefore that the formation of carbon bisulphide from charcoal and sulphur is in all probability accompanied by an absorption of heat.⁷⁰ Hence it is not surprising that it, like other compounds produced with an absorption of heat (ozone, nitrous oxide, hydrogen peroxide, &c.), is unstable, easily converted into the original substances from which it may be obtained. And, indeed, if the vapour of carbon bisulphide be passed through a red-hot tube, it is decomposed—that is, it dissociates—into sulphur and carbon. And this takes place at the temperature at which this substance is formed, just as water decomposes into hydrogen and oxygen at the temperature of its formation. In this absorption of heat in the formation of carbon bisulphide is explained the facility with which it suffers reactions of decomposition, which we shall see in the sequel, and its main difference from the closely analogous carbonic anhydride.

In the laboratory carbon bisulphide is prepared as follows. A porcelain tube is luted into a furnace in an inclined position, the upper extremity of the tube being closed with a cork, and the lower end connected with a condenser. Charcoal is then laid in the tube and

heat is developed. If this be the case, then carbon bisulphide would present a most instructive example for thermochemistry.

⁷⁰ One cannot but here turn attention to the fact that sulphur and charcoal are solids at the ordinary temperature, whilst carbon bisulphide is a very volatile liquid, and consequently, in the act of combination, referred to the ordinary temperature, there is, as it were, a passage into a liquid state, and this requires the absorption of heat. And furthermore, the molecule of sulphur contains at least six atoms, and the molecule of carbon in all probability (Chapter VIII.) a very considerable number of atoms; thus the reaction of sulphur on charcoal may be expressed in the following manner: $3\text{C}_n + n\text{S}_6 = 3_n\text{CS}_2$ —that is, from $n+3$ molecules there proceed $3n$ molecules, and as n must be very considerable, $3n$ must be greater than $3+n$, which indicates a decomposition in the formation of carbon bisulphide, although the reaction at first sight appears as one of combination. This decomposition is seen also from the volumes in the solid and liquid states. Carbon bisulphide has a sp. gr. of 1.29; hence its molecular volume is 59. But the volume of carbon, even in the form of charcoal, is not more than 6, and the volume of S_2 is 30; hence 36 volumes after combination give 59 volumes—an expansion takes place, as in decompositions.

heated to a red heat, and then pieces of sulphur are placed in the upper end. The sulphur melts, and its vapour comes into contact with the red-hot charcoal, and combination takes place; the vapours condense in the condenser, because carbon bisulphide is a liquid boiling at 48° . On a large scale the apparatus depicted in fig. 90 is employed. A




FIG. 90.—Apparatus for the manufacture of carbon bisulphide.

cast-iron cylinder rests on a stand in a furnace. Wood charcoal is charged into the cylinder through the upper tube closed by a clay stopper, whilst the sulphur is introduced through a tube reaching to the bottom of the cylinder. Pieces of sulphur thrown into this tube fall on to the bottom of the cylinder, and are converted into vapour, which passes through the entire layer of charcoal in the cylinder. The vapour of carbon bisulphide thus formed passes through the exit tube first into a Woulfe's bottle (where the sulphur which has not entered into the reaction is condensed), and then into a strongly-cooled condenser or worm.⁷¹

Pure carbon bisulphide is a colourless liquid, which strongly refracts light, and has a pure ethereal smell; at 0° its specific gravity is 1.293, and at 15° 1.271. If kept long it seems to undergo a change, especially

⁷¹ It must be observed that the liquefaction of the vapours of carbon bisulphide requires a very low temperature, because its boiling-point is not high (48°), and the latent heat of evaporation is not great (about 90°). With air the vapour forms an explosive mixture which easily takes fire. Carbon bisulphide, as prepared on a large scale, is generally very impure, and contains not only sulphur, but, more especially, other impurities which give it a very disagreeable odour. The best method of purifying this malodorous carbon bisulphide is to shake it up with a certain amount of mercuric chloride, or even simply with mercury, until the surface of the metal ceases to turn black. After this the carbon bisulphide must be poured off and distilled over a water bath, after having mixed it with some oil to retain the impurities.

when it is kept under water, in which it is insoluble. It boils at 48° , and the tension of its vapour is so great that it evaporates very easily, producing cold,⁷² and therefore it has to be kept in well-stoppered vessels; it is generally kept under a layer of water, which hinders its evaporation and does not dissolve it.⁷³

Carbon bisulphide enters into many combinations, which are frequently closely analogous to the compounds of carbonic anhydride. In this respect it is a *thio-anhydride*—i.e., it has an acid character, like carbonic anhydride, with the difference that the oxygen of the latter is replaced by sulphur. By thio-compounds in general are understood those compounds of sulphur which differ from the compounds of oxygen as carbon bisulphide does from carbonic anhydride—that is, which correspond with the oxygen compounds, but with substitution of sulphur for oxygen. With the sulphides of the alkalis and alkaline earths, it forms saline substances corresponding with the carbonates, and these compounds may be termed *thio-carbonates*. For example, the composition of the sodium salt Na_2CS_3 is exactly like that of sodium carbonate. They are formed by the direct solution of carbon bisulphide in aqueous solutions of the sulphides; but they are difficult to obtain in a crystalline form, because they are easily decomposable.

⁷² If carbon bisulphide be evaporated under the receiver of an air-pump, or by means of a current of air, it is possible to obtain a temperature as low as -60° , and the carbon bisulphide does not solidify at this temperature. However, if a series of air-bubbles be passed through it by means of bellows, there remains a crystalline white substance which volatilises below 0° : this is a hydrate, $\text{H}_2\text{O} \cdot 2\text{CS}_2$; it easily decomposes into water and carbon bisulphide. It is formed in the above experiment by the moisture held in the air passed through the carbon bisulphide, and the fall of temperature.

⁷³ Strong alcohol is miscible in all proportions with carbon bisulphide, but dilute alcohol only in a definite amount, owing to its diminished solubility from the presence of the water in it. Ether, hydrocarbons, fatty oils, and many other organic substances are soluble with great ease in carbon bisulphide. This is taken advantage of in practice for extracting the fatty oils from vegetable seeds, such as linseed, &c. This is generally done by pressing the seeds under a press, but the residue always contains a certain amount of oil. These traces of oil can, however, be removed by treatment with carbon bisulphide. In this manner a solution is obtained which when heated easily parts with all the carbon bisulphide, leaving the non-volatile fatty oil behind, so that the same carbon bisulphide may be condensed and used over again for the same purpose. It also dissolves iodine, bromine, india-rubber, sulphur, and tars.

Carbon bisulphide, especially at high temperatures, very often acts with its elements in a manner in which carbon and sulphur alone are not able to react, which will be understood from what has been said above respecting its endothermal origin. If it be passed over red-hot metals—even over copper, for instance, not to mention sodium, &c.—it forms a sulphide of the metal and deposits charcoal, and if the vapour be passed over incandescent metallic oxides it forms metallic sulphides and carbonic anhydride (and sometimes a certain amount of sulphurous anhydride). Lime and similar oxides give under these circumstances a carbonate and a sulphide—for example, $\text{CS}_2 + 3\text{CaO} = 2\text{CaS} + \text{CaCO}_3$. The sulphides obtained by this means are often well crystallised, like those found in nature—for example, lead and antimony sulphides.

When the solutions of these salts are highly concentrated they begin to decompose, with the evolution of sulphuretted hydrogen and the formation of a carbonate, water taking part in the reaction—for example, $\text{K}_2\text{CS}_3 + 3\text{H}_2\text{O} = \text{K}_2\text{CO}_3 + 3\text{H}_2\text{S}$.⁷⁴

A remarkable example^{74b} of the thio-compounds is found in *thio-*

⁷⁴ If instead of a sulphide we take an alkali hydroxide, then a thiocarbonate is also formed, together with a carbonate—thus, $3\text{BaH}_2\text{O}_2 + 3\text{CS}_2 = 2\text{BaCS}_3 + \text{BaCO}_3 + 3\text{H}_2\text{O}$. From the instability of the thiocarbonates of the alkaline metals we can clearly see the reason of the difficulty with which the salts of the heavier metals are formed, whose basic properties are incomparably weaker than those of the alkali metals. However, these salts may be obtained by double decomposition. Ammonia in reacting on carbon bisulphide gives, besides products like those formed by other alkalis, a whole series of products of as complex a structure as those substances which are produced by the action of carbonic anhydride on ammonia. In the ninth chapter we examined the formation of the ammonium carbonates, and saw the transition from them into the cyanides. It is not surprising after this that the action of carbon bisulphide on ammonia not only produces the above-mentioned salts, but also amidic compounds corresponding with them, in which the oxygen is wholly or partially replaced by sulphur. Thus ammonium thiocarbimide is very easily obtained if carbon bisulphide be added to an alcoholic solution of ammonia, and the mixture cooled in a closed vessel. The salt then separates out in minute yellow crystals, $\text{CN}_2\text{H}_6\text{S}_2$.

Carbon bisulphide not only forms compounds with the metallic sulphides, but also with sulphuretted hydrogen—that is, it forms *thiocarbonic acid*, H_2CS_3 . This is obtained by carefully mixing solutions of thiocarbonates with dilute hydrochloric acid. It then separates in an oily layer, which easily decomposes in the presence of water into sulphuretted hydrogen and carbon bisulphide, just as the corresponding carbonic acid (hydrate) decomposes into water and carbonic anhydride. Carbon bisulphide combines not only with sodium sulphide, but also with the bisulphide Na_2S_2 , not, however, with the trisulphide Na_2S_3 .

The relation of carbon bisulphide to the other carbon compounds presents many most interesting features, which are considered in organic chemistry. We will here only turn our attention to one of the compounds of this class. Ethyl sulphide, $(\text{C}_2\text{H}_5)_2\text{S}$, combines with ethyl iodide, $\text{C}_2\text{H}_5\text{I}$, forming a new molecule, $\text{S}(\text{C}_2\text{H}_5)_3\text{I}$. If we designate the hydrocarbon group, for instance, ethyl, C_2H_5 , by Et, then the reaction would be expressed by the following equation: $\text{Et}_2\text{S} + \text{EtI} \rightarrow \text{SEt}_3\text{I}$. This compound is of a saline character, corresponds with salts of the alkalis, and is closely analogous to ammonium chloride. It is soluble in water; when heated, again splits up into its components EtI and Et_2S , and with silver hydroxide gives a hydroxide, $\text{SEt}_3\text{S}\cdot\text{OH}$, having the property of a distinct and energetic alkali, resembling caustic ammonia. Thus the compound group SEt_3 combines, like potassium or ammonium, with iodine, hydroxyl, chlorine, &c. The hydroxide $\text{SEt}_3\text{S}\cdot\text{OH}$ is soluble in water, precipitates metallic salts, saturates acids, &c. Hence sulphur here enters into a relation towards other elements similar to that of nitrogen in ammonia and ammonium salts, with only this difference that nitrogen retains, besides iodine, hydroxyl, and other groups, also H_4 or Et_4 (for example, NH_4Cl , NEt_5HI , NEt_4I), whilst sulphur only retains Et_3 . The distinctly alkaline properties of the hydroxide, triethylsulphine hydroxide, $\text{SEt}_3\text{S}\cdot\text{OH}$, and also the sharply-defined properties of the corresponding hydroxide, tetraethylammonium hydroxide, NEt_4OH , depend naturally not only on the properties of the nitrogen and sulphur entering into their composition, but also on the large proportion of hydrocarbon groups they contain. Judging from the existence of the ethylsulphine compounds, it might be imagined that sulphur forms a compound, SH_4 , with hydrogen; but no such compound is known, just as NH_5 is unknown, although NH_4Cl exists.

^{74b} Thorpe and Rodger (1889), by heating a mixture of lead fluoride and phosphorus

cyanic acid—i.e. cyanic acid in which the oxygen is replaced by sulphur, HCNS. We know (Chapter IX.) that with oxygen the cyanides of the alkaline metals RCN give cyanates RCNO; but they also combine with sulphur, and therefore if yellow prussiate of potash be treated as in the preparation of potassium cyanide, and sulphur be added to the mass, then potassium thiocyanate, KNCS, is obtained in solution. This salt is much more stable than potassium cyanate; it dissolves without change in water and alcohol, forming colourless solutions from which it easily crystallises on evaporation. It may be kept exposed to air even when in solution; in dissolving in water it absorbs a considerable amount of heat, and forms a starting-point for the preparation of all the thiocyanates, RCNS, and organic compounds in which the metals are replaced by hydrocarbon groups. Such, for example, is volatile mustard oil, C_3H_5CSN (allyl thiocyanate), which gives to mustard its caustic properties. With ferric salts the thiocyanates give an exceedingly brilliant red coloration, which may serve for the discovery of the smallest traces of ferric salts in solution. Thiocyanic acid, HCNS, may be obtained by a method of double decomposition, by distilling potassium thiocyanate with dilute sulphuric acid. It is a volatile colourless liquid, having a smell recalling that of vinegar; it solidifies at 12° , is soluble in water, and may be kept in solution without change for a long time.⁷⁵

pentasulphide to 250° in an atmosphere of dry nitrogen, obtained gaseous *phosphorus fluosulphide*, or *thiophosphoryl fluoride*, PSF_5 , corresponding with $POCl_5$. This colourless gas is converted into a colourless liquid by a pressure of eleven atmospheres; it does not act on dry mercury, and takes fire spontaneously in air or oxygen, forming phosphorus pentafluoride, phosphoric anhydride, and sulphurous anhydride. It is soluble in ether, but is decomposed by water: $PSF_5 + 4H_2O = H_2S + H_3PO_4 + 3HF$ (*supra*, p. 206, Note 20).

⁷⁵ If a given compound contain more than one atom of oxygen, it may be successively replaced by sulphur. The best example of this is seen in the compound COS, in which half of the oxygen in carbonic anhydride is replaced by sulphur. This substance should be called *carbon oxysulphide*, or *monothiocarbonic anhydride*. This substance was obtained by Than, and is formed in many reactions. A certain amount is obtained if a mixture of carbonic oxide and the vapour of sulphur be passed through a red-hot tube. When carbon tetrachloride is heated with sulphurous anhydride, this substance is also formed; but it is best obtained in a pure form by decomposing potassium thiocyanate with a mixture of equal volumes of water and sulphuric acid. A gas is then evolved containing a certain amount of hydrocyanic acid, from which it may be freed by passing it over wool containing moistened mercuric oxide, which retains the hydrocyanic acid. It is also formed by passing the vapour of carbon bisulphide over alumina or clay heated to redness (Gautier; silicon sulphide is then formed). The pure gas has an aromatic odour, is soluble in an equal volume of water, which, however, acts on it, so that it must be collected over mercury. Its formation is expressed by the equation: $2KCNS + 2H_2O + 2H_2SO_4 = K_2SO_4 + (NH_4)_2SO_4 + 2COS$. When slightly heated, carbon oxysulphide decomposes into sulphur and carbonic oxide. It burns in air with a pale blue flame, explodes with oxygen, and yields potassium sulphide and carbonate with potassium hydroxide: $COS + 4KHO = K_2CO_3 + K_2S + 2H_2O$.

The sulphur compounds of chlorine may be regarded on the one hand as products of the metalepsis of the sulphides of hydrogen, Cl_2S and Cl_2S_2 like H_2S and H_2S_2 ; and on the other hand of the oxygen compounds of chlorine, because chloride of sulphur, Cl_2S , like chlorine oxide, Cl_2O , and Cl_2S_2 correspond with the higher oxide of chlorine; or thirdly, we may see in these compounds the type of the acid chloranhydrides, because they are all decomposed by water, forming hydrochloric acid, and sulphur tetrachloride, SCl_4 , is decomposed, with the formation of sulphurous anhydride.⁷⁶

The compounds of sulphur with chlorine are prepared in the apparatus depicted in fig. 91. As sulphur chloride is decomposed by water, the chlorine evolved in the flask C must be dried before coming



FIG. 91.—Apparatus for the preparation of sulphur chloride, and similar volatile compounds prepared by combustion in a stream of chlorine.

into contact with the sulphur. It is therefore first passed through a Woulfe's bottle, B, containing sulphuric acid, and then through the cylinder D containing pumice stone moistened with sulphuric acid, and

⁷⁶ There is no reason for seeing any contradiction or mutual incompatibility in these three views, because every analogy is more or less modified by a change of elements. Thus, for instance, it cannot be expected that the product of the metalepsis of hydrogen sulphide would resemble the same products corresponding with water in all respects, because water has not the acid properties of hydrogen sulphide. In the days of dualism and electrical polarity, it was supposed that the sulphur varied in its nature: in hydrogen sulphide or potassium sulphide it was considered to be negative, and in sulphurous anhydride or sulphur dichloride positive. It then appeared evident that sulphur dichloride would have no point of analogy with potassium sulphide. But metalepsis, or its expression in the law of substitutions, necessitates such opinions being laid aside. If we can assimilate CO_2 , CH_4 , CCl_4 , CHCl_3 , $\text{CH}_3(\text{OH})$ to each other, we cannot recognise any difference in the sulphur in SH_2 , SCl_2 , SK_2 , or SX_2 , for otherwise we should have

then led into the retort E, in which the sulphur is heated. The compound which is formed distils over into the receiver, R. A certain amount of sulphur passes over with the sulphur chloride, but if the resultant distillate be re-saturated with chlorine and distilled no free sulphur remains, the boiling-point rises to 140° , and pure sulphur chloride, S_2Cl_2 , is obtained. It has this formula because its vapour density referred to hydrogen is 68. It is also obtained by heating certain metallic chlorides (stannous, mercuric) with sulphur; both the metal and chlorine then combine with the sulphur. Sulphur chloride is a yellowish-brown liquid, which boils at 144° , and has a specific gravity of 1.70 at 0° . It fumes strongly in the air, reacting on the moisture contained therein, and has a heavy chloranhydrous odour. It dissolves sulphur, is miscible with carbon bisulphide, and falls to the bottom of a vessel containing water, by which it is decomposed, forming sulphurous anhydride and hydrochloric acid; but it first forms various lower stages of oxidation of sulphur, because the addition of silver nitrate to

to acknowledge as many different states of sulphur, carbon, or hydrogen as there are compounds of sulphur, or carbon, or hydrogen. The essential point of the matter is that all the elements in a molecule play their part in the reactions into which it enters. Often this appears to be contradicted in the result—for example, hydrogen alone may be replaced; but it is not this hydrogen alone that has determined the reaction, but all the elements which participated in the reaction. This may be made clearer by the following rough illustration. Supposing two regiments of soldiers were fighting against each other, and that several men were lost by one of the regiments; no one could say that it was only these men who took part in the engagement. The other men fired and the bullets flew over the heads of others. It was not only those who fell who fought, although they only were removed from the engagement, for the fighting proceeded among the masses and only a few were disabled, because they went forward and were more remarked, &c., but not because the remainder did not participate in the matter; for these acted, they were an object, they fought, only they remained whole and were not killed. Hydrogen is lighter and its atoms more mobile; it subjects itself more frequently and easily to reactions; but it is not it alone which reacts, it is even less capable of this than other elements. It participates in exceedingly diverse reactions, naturally not because the hydrogen itself varies, but because one atom of it puts itself forward, another is hidden, one is united with carbon, another feebly held by sulphur, one stands or moves near oxygen, or another unites with a hydrocarbon. All hydrogen atoms are equal, and equally serve as an object for the atoms of molecules encountering it, but those are removed from the field of battle which are nearer the surface of a molecule, which are more mobile, and held by a less sum of forces. So also sulphur is one and the same in sulphur dichloride, in sulphurous or sulphuric anhydride, in hydrogen sulphide, in potassium sulphide, but it reacts differently, and those elements which are with it also vary in their reactions because they are with it, and it varies its reactions because it is with them. It is possible to seize on a character common to substances quantitatively and qualitatively analogous to each other. It may be seen that an element in certain forms is not able to enter into reactions into which in other forms it enters willingly, if only the requisite conditions are encountered; but it cannot be thought that an element would change its tone in different cases. The preceding remarks touch on questions which are subject to much argument among chemists, and I here mention them in order to show the treatment of those most important problems of chemistry which lie at the basis of this treatise.

the solution gives a black precipitate. With hydrogen sulphide it gives sulphur and hydrochloric acid, and it reacts directly with metals—especially arsenic, antimony, and tin—forming sulphides and chlorides. In the cold, it absorbs chlorine and gives *sulphur dichloride*, SCl_2 . The entire conversion into this substance requires the prolonged passage of dry chlorine through sulphur chloride surrounded by a freezing mixture. The distillation of the dichloride must be conducted in a stream of chlorine, as otherwise it partially splits up into sulphur chloride and chlorine. Pure sulphur dichloride is a reddish-brown liquid, which resembles the lower chloride in many respects; its specific gravity is 1.62; its odour is more suffocating than that of sulphur chloride; it volatilises at 64° .⁷⁷

Thionyl chloride, SOCl_2 , is, as it were, oxidised sulphur dichloride; it corresponds with sulphur chloride, S_2Cl_2 , in which one atom of sulphur is replaced by oxygen. At the same time it is chlorine oxide (hypochlorous anhydride, Cl_2O) combined with sulphur, and also the chloroanhydride of sulphurous acid—that is, $\text{SO}(\text{HO})_2$ —in which the two hydroxyl-groups are replaced by two atoms of chlorine, or sulphurous anhydride, SO_2 , in which one atom of oxygen is replaced by two atoms of chlorine. All these representations are confirmed by reactions of formation or decomposition, they all agree with our notions of the other compounds of sulphur, oxygen, and chlorine; hence these definitions are not contradictory to each other. Thus, for instance, thionyl chloride was first obtained by Schiff, by the action of dry sulphurous anhydride on phosphorus pentachloride. On distilling the resultant liquid first thionyl chloride comes over at 80° , and then on continuing the distillation phosphorus oxychloride distils over at above 100° , $\text{PCl}_3 + \text{SO}_2$

⁷⁷ The observed vapour density of sulphur dichloride referred to hydrogen is 53.3, and that given by the formula is 51.5. The smaller molecular weight explains its boiling point being lower than that of sulphur chloride, S_2Cl_2 . The reactions of both these compounds are very similar. Sulphur converts the dichloride, SCl_2 , into the monochloride, S_2Cl_2 . In one point the dichloride differs distinctly from the monochloride—that is, in its capacity for easily giving up chlorine and decomposing. Even light decomposes it, with the evolution of chlorine and the monochloride. Hence it acts on many substances in the same manner as chlorine, or substances which easily part with the latter, such as phosphoric or antimonious chloride. In distinction to these, however, sulphur dichloride appears to distil without any considerable decomposition, as may be judged by the vapour density. However, this is not the case. If there be a decomposition, then $2\text{SCl}_2 = \text{S}_2\text{Cl}_2 + \text{Cl}_2$, the density of sulphur chloride = 67.5, and of chlorine = 35.5; consequently a mixture of equal volumes of the two = 51.5, just the same as an equal volume of sulphur dichloride. *Therefore the distillation of sulphur dichloride is probably nothing but its decomposition.* Hence, the compound SCl_2 , which is stable at the ordinary temperature, decomposes at 64° . In the cold it absorbs a further amount of chlorine in the proportion SCl_2 , but even at -10° a portion of the absorbed chlorine is given off—that is, dissociation takes place. The tetrachloride is even less stable than the dichloride.

$=\text{POCl}_3 + \text{SOCl}_2$. Würtz obtained the same substance by passing a stream of chlorine oxide through a cold solution of sulphur in sulphur chloride; the chlorine oxide then combined directly with the sulphur, $\text{S} + \text{Cl}_2\text{O} = \text{SOCl}_2$, whilst the sulphur chloride remained unchanged (sulphur cannot be combined directly with chlorine oxide, as an explosion takes place). Thionyl chloride is a colourless liquid, having a suffocating acrid smell; its specific gravity is 1.675 at 0° , it boils at 78° , it falls to the bottom of a vessel containing water, by which it is immediately decomposed, like all chloranhydrides—for example, like carbonyl chloride, which corresponds with it: $\text{SOCl}_2 + \text{H}_2\text{O} = \text{SO}_2 + 2\text{HCl}$.

Normal *sulphuric acid* has two corresponding chloranhydrides; the first, $\text{SO}_2(\text{OH})\text{Cl}$, is sulphuric acid, $\text{SO}_2(\text{HO})_2$, in which one equivalent of HO is replaced by chlorine; the second has the composition SO_2Cl_2 ,—that is, two HO groups are substituted by two of chlorine. The second chloranhydride, or the compound SO_2Cl_2 , is called *sulphuryl chloride*, and the first chloranhydride, SO_2HOCl , may be called *chloro-sulphonic acid*, because it is really an acid; it still retains one hydroxyl of sulphuric acid, and its corresponding salts are known. Thus, potassium chloride absorbs the vapour of sulphuric anhydride, forming a salt SO_3KCl , corresponding with SO_3HCl as acid. In acting on sodium chloride it forms hydrochloric acid and the salt NaSO_3Cl . This first chloranhydride of sulphuric acid, SO_2HOCl , discovered by Williamson, is obtained either by the action of phosphorus pentachloride on sulphuric acid ($\text{PCl}_5 + \text{H}_2\text{SO}_4 = \text{POCl}_3 + \text{HCl} + \text{HSO}_3\text{Cl}$), or directly by the action of dry hydrochloric acid on sulphuric anhydride, $\text{SO}_3 + \text{HCl} = \text{HSO}_3\text{Cl}$. The most easy and rapid method of its formation is by the direct saturation of cold Nordhausen acid with dry hydrochloric acid gas, and the distillation of the resultant solution; HSO_3Cl is then contained in the distillate. It is a colourless fuming liquid, having an acrid odour; it boils at 153° (according to my determination, confirmed by Konovaloff), and its specific gravity at 19° is 1.776. It is immediately decomposed by water, forming hydrochloric and sulphuric acids, as should be the case with a true chloranhydride. In the reactions of this chloranhydride we find the easiest means of introducing the sulphonic group (the radicle of sulphuric and sulphurous acids), HSO_3 , into other compounds, because it is here combined with chlorine. The second chloranhydride of sulphuric acid, or *sulphuryl chloride*, SO_2Cl_2 , was obtained by Regnault by the direct action of the sun's rays on a mixture of equal volumes of chlorine and sulphurous oxide. The gases gradually condense into a liquid, combining together as carbonic oxide does with chlorine. It is also obtained when a mixture of the two gases in acetic acid is allowed to remain for some time. The first chloranhydride,

SO_3HCl , decomposes when heated at 200° in a closed tube into sulphuric acid and sulphuryl chloride. It resembles the two above-described chloranhydrides in its properties: boils at 70° , its specific gravity is 1.70; it gives hydrochloric and sulphuric acids with water, fumes in the air, and, judging by its vapour density, it does not decompose when distilled.⁷⁸

⁷⁸ Pyrosulphuryl chloride, $\text{S}_2\text{O}_5\text{Cl}_2$. See Note 44.

The acids of sulphur naturally have their corresponding ammonium salts, and the latter their amides and nitriles. It will be readily understood how vast a field for research is presented by the series of compounds of sulphur and nitrogen, if we only remember that to carbonic and formic acids there corresponds, as we saw (Chap. IX.), a vast series of derivatives corresponding with their ammonium salts. To sulphuric acid there correspond two ammonium salts, $\text{SO}_2(\text{HO})(\text{NH}_4\text{O})$ and $\text{SO}_2(\text{NH}_4\text{O})_2$; three amides: the acid amide $\text{SO}_2(\text{HO})(\text{NH}_2)$, or sulphamic acid, the normal saline compound $\text{SO}_2(\text{NH}_4\text{O})(\text{NH}_2)$, or ammonium sulphamate, and the normal amide $\text{SO}_2(\text{NH}_2)_2$, or sulphamide (the analogue of urea); then the acid nitrile, $\text{SON}(\text{HO})$, and two neutral nitriles, $\text{SON}(\text{NH}_2)$ and SN_2 . There are similar compounds corresponding with sulphurous acid, and therefore its nitriles will be, an acid, $\text{SN}(\text{HO})$, its salt, and the normal compound, $\text{SN}(\text{NH}_2)$. Dithionic and the other acids of sulphur should also have their corresponding amides and nitriles. Only a few examples are known, which we will briefly describe. Sulphuric acid forms salts of very great stability with ammonia, and ammonium sulphate is one of the commonest ammoniacal compounds. It is obtained by the direct action of ammonia on sulphuric acid, or by the action of the latter on ammonium carbonate; it separates from its solutions in an anhydrous state, like potassium sulphate, with which it is isomorphous. Hence, the composition of crystals of ammonium sulphate is $(\text{NH}_4)_2\text{SO}_4$. This salt fuses at 140° , and does not undergo any change when heated up to 180° . At higher temperatures it parts with (not water but) half its ammonia, and is converted into the acid salt, HNNH_4SO_4 ; and this acid salt, on further heating, undergoes a further decomposition, and splits up into nitrogen, water, and acid ammonium sulphite, HNNH_4SO_3 . At the ordinary temperature the normal salt is soluble in twice its weight of water and at the boiling-point of water in an equal weight. In its faculty for combinations this salt exhibits a great resemblance to potassium sulphate, and, like it, easily forms a number of double salts; the most remarkable of which are the ammonia alums, $\text{NH}_4\text{AlS}_2\text{O}_3 \cdot 12\text{H}_2\text{O}$, and the double salts formed by the metals of the magnesium group, having, for example, the composition $(\text{NH}_4)_2\text{MgS}_2\text{O}_8 \cdot 6\text{H}_2\text{O}$. Ammonium sulphate does not give an amide when heated, perhaps owing to the faculty of sulphuric anhydride to retain the water combined with it with great force. But the amides of sulphuric acid may be very conveniently prepared from sulphuric anhydride. Their formation by this method is very easily understood, because an amide is equal to an ammonium salt less water, and if the anhydride be taken it will give an amide directly with ammonia. Thus, if dry ammonia be passed into a vessel surrounded by a freezing mixture and containing sulphuric anhydride, it forms a white mass, having the composition $\text{SO}_3 \cdot 2\text{H}_5\text{N}$ and resembling the like compound of carbonic acid, $\text{CO}_2 \cdot 2\text{NH}_3$. It is slowly acted on by water, and may therefore be obtained in solution, in which it slowly reacts with barium chloride, which proves that with water it still forms ammonium sulphate. This substance is naturally an ammonium salt of sulphamic acid, $\text{SO}_2(\text{NH}_4\text{O})\text{NH}_2$. By treatment with water this substance at first gives a special deliquescent ammonium salt, containing $\text{H}_2\text{O} \cdot 2(\text{SO}_3 \cdot 2\text{NH}_3)$, and then a normal ammonium salt. The compound $\text{SO}_3 \cdot 2\text{NH}_3$ is known as *sulphatammon*. When freshly prepared it is powdery; it does not give a precipitate with calcium chloride, but a precipitate is obtained, although not a complete one, with barium chloride. If this substance be carefully dissolved in water and evaporated, it yields well-formed crystals, whose solution no longer gives a precipitate with barium chloride. This is not due to the pre-

In the group of the halogens we saw four closely analogous elements—fluorine, chlorine, bromine, and iodine—and we meet with a like number of closely-allied analogues in the oxygen group, because besides sulphur this group also includes *selenium* and *tellurium*: O, S, Se, Te.

sence of impurities, but to a change in the nature of the substance, and therefore Roscoe calls the crystalline modification *parasulphatammon*. Platinum chloride only precipitates half the nitrogen as platinumchloride from solutions of sulphat- and parasulphatammon, which shows that they are ammonium salts, $\text{SO}_2(\text{NH}_4\text{O})(\text{NH}_2)$. It may be that the reason of the difference in the two modifications is connected with the fact that two different substances of the composition $\text{N}_2\text{H}_4\text{SO}_2$ are possible: one is the amide $\text{SO}_2(\text{NH}_2)_2$ corresponding with the normal salt, and the other is the salt of the nitrile acid corresponding with acid ammonium sulphate—that is, $\text{SON}(\text{ONH}_2)$ corresponds with the acid $\text{SON}(\text{OH}) = \text{SO}_2(\text{NH}_4\text{O})\text{OH} - 2\text{H}_2\text{O}$. That is, there may here be a difference of the same nature as between urea and ammonium cyanate. For the present, the isomerism indicated above has been but little investigated, and might be the subject of interesting researches.

If in the preceding experiment the ammonia, and not the sulphuric anhydride, be taken in excess, then a soluble substance of the composition $2\text{SO}_3, 8\text{NH}_3$ is formed. This compound, obtained by Jacqueline and investigated by Voronin, doubtless also contains a salt of sulphamic acid—that is, of the amide corresponding with the acid ammonium sulphate = $\text{H}\text{NH}_2\text{SO}_3 - \text{H}_2\text{O} - (\text{NH}_2)\text{SO}_2(\text{OH})$. Probably it is a compound of sulphatammon with sulphamic acid. Thus it has an acid reaction, and does not give a precipitate with barium chloride.

With normal sulphate of ammonium, an amide of the composition $\text{N}_2\text{H}_4\text{SO}_2$ should correspond, which should bear the same relation to sulphuric acid as urea bears to carbonic acid. This amide, known as *sulphamide*, is obtained by the action of dry ammonia on the sulphuryl chloride, SO_2Cl_2 , which we became acquainted with above, just as urea is obtained by the action of ammonia on carbonyl chloride, $\text{SO}_2\text{Cl}_2 + 4\text{NH}_3 = \text{N}_2\text{H}_4\text{SO}_2 + 2\text{NH}_4\text{Cl}$. The ammonium chloride is separated from the resultant sulphamide with great difficulty. Cold water, acting on the mixture, dissolves them both; the cold solution does not give a precipitate with barium chloride. Alkalis act on it slowly, as they do on urea; but on boiling, especially in the presence of alkalis or acids, it easily re-combines with water, and gives an ammonium salt. The action of sulphuryl chloride (and of the other chloranhydrides of sulphur) on ammonium carbonate always, as Mentz showed (1888), results in the formation of the salt $\text{NH}(\text{SO}_3\text{NH}_2)_2$.

The nitriles corresponding with sulphuric acid are not as yet known with any certainty. The most simple nitrile corresponding with sulphuric acid should have the composition $\text{N}_2\text{H}_4\text{SO}_4 - 4\text{H}_2\text{O} = \text{N}_2\text{S}$. This would be a kind of cyanogen corresponding with sulphuric acid. On comparing sulphurous acid with carbonic acid, we saw that they present a great analogy in many respects, and therefore one would expect to also find other nitrile compounds corresponding to the cyanogen compounds already known to us, and therefore having the composition NHS and N_2S_2 . The latter of these compounds is well known, and was obtained by Soubeiron, by the action of dry ammonia on sulphur chloride. This substance corresponds with cyanogen (paracyanogen), and is known as *nitrogen sulphide*, N_2S_2 . It is formed according to the equation $3\text{SCl}_2 + 8\text{NH}_3 = \text{N}_2\text{S}_2 + \text{S} + 6\text{NH}_4\text{Cl}$. The free sulphur and nitrogen sulphide are dissolved by acting on the product with carbon bisulphide, the nitrogen sulphide being much less soluble than the sulphur. It is a yellow, almost odourless substance, which is excessively irritating to the eyes and nostrils. It explodes when rubbed with a hard substance, being naturally decomposed with the evolution of nitrogen; but when heated it fuses without decomposing, and only decomposes with explosion at 157° . It is insoluble in water and only slightly so in alcohol, ether, and carbon bisulphide; 100 parts of the latter dissolve 10 parts of nitrogen sulphide at the boiling point. This solution on cooling deposits it in minute transparent prisms of a golden yellow colour.

These two groups are very closely allied, both in respect to the magnitudes of their atomic weights, and also in the faculty of the elements of both groups for combining with metals. The distinct analogy and definite degree of variance known to us for the halogens, also repeat themselves in the same degree for the elements of the oxygen group. Thus the halogens combine with H, and the elements of the oxygen group with H_2 , forming H_2O , H_2S , H_2Se , H_2Te . The hydrogen compounds of selenium and tellurium are acids like hydrogen sulphide. Selenium, by simple heating in a stream of hydrogen, partially combines with it directly, but seleniuretted hydrogen is more readily decomposable by heat than sulphuretted hydrogen, and this property is still more developed in telluretted hydrogen. Hydrogen selenide and telluride are gases like sulphuretted hydrogen, and, like it, are soluble in water, form saline compounds with alkalis, precipitate metallic salts, are obtained by the action of acids on their compounds with metals, &c. Selenium and tellurium, like sulphur, give two normal grades of combination with oxygen, both of an acid character, of which only the forms corresponding to sulphurous anhydride—namely, selenious anhydride, SeO_2 , and tellurous anhydride, TeO_2 ⁷⁹—are formed directly.

⁷⁹ *Selenious anhydride*, SeO_2 , is a volatile solid, which crystallises in prisms soluble in water. It is best procured by the action of nitric acid on selenium. The well-known researches of Nilson (1874) showed that the salts of selenious acid easily form acid salts, and are so characteristic in many respects that they may even serve for judging the analogy of types of oxides. Thus the oxides of the composition RO give normal salts of the composition $RSeO_3 \cdot 2H_2O$, where $R = Mn, Co, Ni, Cu, Zn$. The salts of magnesium, barium, and calcium contain a different quantity of water, as also do the salts of the oxides R_2O_3 . We here turn attention to the fact that beryllium gives a normal salt, $BeSeO_3 \cdot 2H_2O$, and not a salt analogous to those of aluminium, scandium, $Sc_2(SeO_3)_5 \cdot 12H_2O$, yttrium, $Y_2(SeO_3)_5 \cdot 12H_2O$, and other oxides of the form R_2O_3 , which speaks in favour of the formula BeO .

Tellurous anhydride is also a colourless solid, which crystallises in octahedra; it also, when heated, first fuses and then volatilises. It is insoluble in water, and the decomposition of its salts gives a hydrate, H_2TeO_3 , which is insoluble.

It is a very characteristic circumstance that selenious and tellurous anhydrides are very easily *reduced* to selenium and tellurium. This is not only effected by metals like zinc, or by sulphuretted hydrogen, which are powerful deoxidisers, but even by sulphurous anhydride, which is able to precipitate selenium and tellurium from solutions of the selenites and tellurites, and even of the acids themselves, which is taken advantage of in obtaining these elements and separating them from sulphur.

Sulphuric acid, as we know, rarely acts as an oxidising agent. It is otherwise with selenic and telluric acids, H_2SeO_4 and H_2TeO_4 , which are powerful oxidising agents—that is, are easily reduced in many circumstances either into the lower oxide or even to selenium and tellurium. A powerful oxidising agent is required in order to convert selenious and tellurous anhydrides into selenic and telluric anhydrides, and, moreover, it must be taken in excess. If chlorine be passed through a solution of potassium selenide, K_2Se , telluride, K_2Te , or selenite, K_2SeO_3 , or tellurite, K_2TeO_3 , it acts as an oxidiser in the presence of the water, forming potassium selenate, K_2SeO_4 , or tellurate, K_2TeO_4 . The same salts are formed by fusing the lower oxides with nitre. These salts are isomorphous with the

These are both solids, obtained by the combustion of the elements themselves and by the action of oxidising agents on them. They form feebly energetic acids, having distinct bibasic properties; however, a characteristic difference is observable both in the physical properties of these compounds and in their stability and capacity for further oxidation, just as in the series of the halogens already known to us, only in an inverse order; in the latter we saw that iodine combines more easily than bromine or chlorine with oxygen, forming more stable oxygen compounds, whereas here, on the contrary, sulphurous anhydride, as we know, is difficultly decomposed, parts with its sulphur with difficulty, and is easily oxidised even in air and especially in its salts, while selenious and tellurous anhydrides are difficultly oxidised and easily reduced, even by means of sulphurous acid.

Selenium was obtained in 1817 by Berzelius from the sublimate which collects in the first chamber in the preparation of sulphuric acid from Fahlun pyrites. Certain other pyrites also contain small

corresponding sulphates, and cannot therefore be separated from them by crystallisation. The salts of potassium, sodium, magnesium, copper, cadmium, &c., are soluble like the sulphates, but those of barium and calcium are insoluble, in perfect analogy with the sulphates. When copper selenate, CuSeO_4 , is treated with sulphuretted hydrogen (CuS is precipitated), *selenic acid* remains in solution. On evaporation it gives a syrupy liquid, which may be concentrated to almost the pure acid, H_2SeO_4 , having a specific gravity of 2.6. Like sulphuric acid this acid attracts moisture from the atmosphere; it is not decomposed by sulphurous acid, but oxidises hydrochloric acid (like nitric, chromic, and manganic acids), evolving chlorine and forming selenious acid, $\text{H}_2\text{SeO}_4 + 2\text{HCl} = \text{H}_2\text{SeO}_3 + \text{H}_2\text{O} + \text{Cl}_2$. *Telluric acid*, H_2TeO_4 , is obtained by fusing tellurous anhydride with potassium hydroxide and chlorate; the solution, containing potassium tellurate, is then precipitated with barium chloride, and the barium tellurate, BaTeO_4 , then obtained in the precipitate is decomposed by sulphuric acid. A solution of telluric acid is thus obtained, which on evaporation yields colourless prisms, soluble in water, and containing $\text{TeH}_2\text{O}_4 \cdot 2\text{H}_2\text{O}$. Two equivalents of water are driven off at 160° ; on further heating the last equivalent of water is expelled, and then oxygen is given off. It also gives chlorine with hydrochloric acid, like selenic acid. Its salts also correspond with those of sulphuric acid. It must, however, be remarked that telluric and selenic acids are able to give poly-acid salts with much greater ease than sulphuric acid. Thus, for example, there are known for telluric acid not only $\text{K}_2\text{TeO}_4 \cdot 5\text{H}_2\text{O}$ and $\text{KHTeO}_4 \cdot 3\text{H}_2\text{O}$, but also $\text{KHTeO}_4 \cdot \text{H}_2\text{TeO}_4 \cdot \text{H}_2\text{O}$ and $\text{K}_2\text{TeO}_4 \cdot 3\text{H}_2\text{TeO}_4 \cdot 2\text{H}_2\text{O}$. This salt is easily obtained from acid solutions of the preceding salts, and is less soluble in water. As selenious anhydride is volatile and gives similar poly-salts, it might be thought that selenious, tellurous, selenic, and telluric anhydrides are polymeric as compared with sulphurous and sulphuric anhydrides, for which reason it would be desirous to determine the vapour density of selenious anhydride. It would probably correspond with Se_3O_4 or Se_3O_6 .

In order to show how exceedingly analogous selenium is to sulphur, I will note two examples. Potassium cyanide dissolves selenium, as it does sulphur, forming potassium selenocyanate, KCNSe , corresponding with potassium thiocyanate. Acids precipitate selenium from this solution, because selenocyanic acid, H_2CNSe , when in a free state is immediately decomposed. A boiling solution of sodium sulphite dissolves selenium, just as it would sulphur, forming a salt analogous to thiosulphate of sodium, namely, sodium selenosulphate, Na_2SSeO_5 . Selenium is separated from a solution of this salt by the action of acid.

quantities of selenium. Some native selenides, especially those of lead, mercury, and copper, have been found in the Hartz Mountains, but only in small quantities. Pyrites and blendes, in which the sulphur is partially replaced by selenium, still remain the chief source for its extraction. When these pyrites are roasted they evolve selenious anhydride, which condenses in the cooler portions of the apparatus in which the pyrites are roasted, and is partially or wholly reduced by the sulphurous anhydride simultaneously formed. The presence of selenium in ores and sublimes is most simply tested by heating them before the blowpipe, when they evolve the characteristic odour of garlic. Selenium exhibits two modifications, like sulphur : one amorphous and insoluble in carbon bisulphide, the other crystalline and slightly soluble in carbon bisulphide (in 1000 parts at 45° , and 6000 at 0°), and separating from its solutions in monoclinic prisms. If the red precipitate obtained by the action of sulphurous anhydride on selenious anhydride be dried, it gives a brown powder, having a specific gravity of 4.26, which when heated changes colour and fuses into a metallic mass, which gains lustre as it cools. The selenium acquires different properties according to the rate at which it is cooled from a fused state ; if rapidly cooled, it remains amorphous and has the same specific gravity (4.28) as the powder, but if slowly cooled it becomes crystalline and opaque, soluble in carbon bisulphide, and has a specific gravity of 4.80. In this form it fuses at 214° and remains unchanged, whilst the amorphous form, especially above 80° , gradually passes into the crystalline variety. The transition is accompanied by the evolution of heat, as in the case of sulphur ; thus the analogy between sulphur and selenium is clearly shown here. In the fused amorphous form, selenium presents a brown mass, slightly translucent, with a vitreous fracture, whilst in the crystalline form it has the appearance of a grey metal, with a feeble lustre and a crystalline fracture. Selenium boils at 700° , forming a vapour whose density is only constant at a temperature of about 1400° , when it is equal to 79.4 (referred to hydrogen) —that is, the molecular formula is then Se_2 , like sulphur at as high a temperature.

Tellurium is met with still more rarely than selenium (it is known in Saxony) in combination with gold, silver, lead, and antimony in the so-called foliated tellurium ore. Bismuth telluride and silver telluride have been found in Hungary and in the Altai. Tellurium is extracted from bismuth telluride by mixing the finely-powdered ore with potassium and charcoal in as intimate a mixture as possible, and then heating in a covered crucible. Potassium telluride, K_2Te , is then formed, because the charcoal reduces potassium tellurite.

As potassium telluride is soluble in water, forming a red-brown solution which is decomposed by the oxygen of the atmosphere ($K_2Te + O + H_2O = 2KHO + Te$), the mass formed in the crucible is treated with boiling water and filtered as rapidly as possible, and the resultant solution exposed to the air, by which means the tellurium is precipitated.⁸⁰ In a free state tellurium has a perfectly *metallic appearance*; it is of a silver-white colour, very easily crystallises in long brilliant needles; is very brittle, so that it can be easily reduced to powder; but it is a bad conductor of heat and electricity, so that in this respect, as in many others, it forms a transition from the metals to the non-metals. Its specific gravity is 6.18, it melts at an incipient red heat, and takes fire when heated in air, like selenium and sulphur, burning with a blue flame and evolving white fumes of tellurous anhydride, TeO_2 , and emitting an acrid smell if no selenium be present; but if it be, its odour preponderates. Alkalis dissolve tellurium when boiled with it, potassium telluride, K_2Te , and potassium tellurite, K_2TeO_3 , being formed. The solution is of a red colour, owing to the presence of the telluride, K_2Te ; but the colour disappears when the solution is cooled or diluted, the tellurium being all precipitated: $2K_2Te + K_2TeO_3 + 3H_2O = 6KHO + 3Te$.⁸¹

⁸⁰ The tellurium thus prepared is impure, and contains a large amount of selenium. The selenium may be removed by converting their mixture into a mixture of potassium tellurate and selenate, and treating this with nitric acid and barium nitrate, when barium selenate only is precipitated, whilst the barium tellurate remains in solution. This method does not, however, give a pure product, and it appears to be best to separate the selenium from the tellurium in a metallic form; this is done by boiling the impure potassium tellurate with hydrochloric acid, which converts it into potassium tellurite, from which the tellurium is reduced by sulphurous anhydride. The metal thus obtained is then fused and distilled in a stream of hydrogen; the selenium volatilises first, and then the tellurium, owing to its being much less volatile than the former. Nevertheless, tellurium is also volatile, and may be separated in this manner from less volatile metals, such as antimony. Brauner determined the atomic weight of pure tellurium, and found it to be 125, but he (1889) showed that tellurium purified by the usual method, even after distillation, contains a large amount of impurities.

⁸¹ The decomposition proceeds in the above order in the cold, but in a hot solution with an excess of potassium hydroxide it proceeds inversely. A like phenomenon takes place when tellurium is fused with alkalis, and therefore it is necessary in order to obtain potassium telluride to add charcoal.

Selenium and tellurium form higher compounds with chlorine than sulphur. For selenium, $SeCl_2$ and $SeCl_4$ are known and for tellurium $TeCl_2$ and $TeCl_4$. The tetrachlorides of selenium and tellurium are formed by passing chlorine over these elements. Selenium tetrachloride, $SeCl_4$, is a crystalline, volatile mass which gives selenious anhydride and hydrochloric acid with water. Tellurium tetrachloride is much less volatile, easily fuses, and is also decomposed by water. They form similar compounds with bromine. Tellurium tetrabromide is red, fuses into a brown liquid, and volatilises, and gives a crystalline salt, $K_2TeBr_6 \cdot 3H_2O$, with an aqueous solution of potassium bromide.

CHAPTER XXI

CHROMIUM, MOLYBDENUM, TUNGSTEN, URANIUM, AND MANGANESE

SULPHUR, selenium, and tellurium belong to the uneven series of the sixth group. In the even series of this group there are known *chromium, molybdenum, tungsten, and uranium*; these give acid oxides of the type RO_3 , like SO_3 . Their acid properties are less sharply defined than those of sulphur, selenium, and tellurium, as is the case with all elements of the even series as compared with those in the uneven series in the same group. But still the oxides CrO_3 , MoO_3 , WO_3 , and even UO_3 , have clearly defined acid properties, and form salts of the composition MO_nRO_3 with bases MO . In the case of the heavy elements, and especially of uranium, the higher type of oxide, UO_3 , is less acid and more basic, because in a given group of oxides the element with the highest atomic weight always acquires a more and more pronouncedly basic character. Hence UO_3 shows the properties of a base, and gives salts UO_2X_2 . The basic properties of chromium, molybdenum, tungsten, and uranium are most clearly expressed in the lower oxides, which they all form. Thus chromic oxide, Cr_2O_3 , is a distinct base, like alumina, Al_2O_3 .

Of all these elements *chromium* is the most widely distributed and the most frequently used. It gives chromic anhydride, CrO_3 , and chromic oxide, Cr_2O_3 —two compounds whose relative amounts of oxygen stand in the ratio 2:1. Chromium is, although rarely, met with in nature as a compound of one or the other type. The red chromium ore of the Urals, or lead chromate, PbCrO_4 , was the source in which chromium was discovered by Vauquelin, who gave it this name (from the Greek word signifying colour) owing to the brilliant colours of its compounds; the chromates (salts of chromic anhydride) are red and yellow, and the chromic salts (from Cr_2O_3) green and violet. The red lead chromate is, however, a rare chromium ore found only in the Urals and a few other localities. Chromic oxide, Cr_2O_3 , is more frequently met with. In small quantities it forms the colouring matter of many minerals and rocks—for example, of some serpentines. The commonest

ore, and the chief source of the chromium compounds, is the *chrome iron ore*, which occurs in the Urals¹ and America, Sweden, and other localities. This is magnetic iron ore, $\text{FeO}, \text{Fe}_2\text{O}_3$, in which the ferric oxide is replaced by chromic oxide, its composition being $\text{FeO}, \text{Cr}_2\text{O}_3$. Chrome iron ore crystallises in octahedra of sp. gr. 4.4; it has a feeble metallic lustre, is of a greyish black colour, and gives a brown powder. It is very feebly acted on by acids, but when fused with potassium acid sulphate it gives a soluble mass, which contains a chromic salt, besides potassium sulphate and ferrous sulphate. In practice the treatment of chrome iron ore is mainly carried on for the preparation of chromates, and not of chromic salts, and therefore we will trace the history of the element by beginning with chromic acid, and especially with the working up of the chrome iron ore into *potassium dichromate*, $\text{K}_2\text{Cr}_2\text{O}_7$, as the most common salt of this acid. It must be remarked that chromic anhydride, CrO_3 , is only obtained in an anhydrous state, and is distinguished for its capacity for easily giving anhydro-salts with the alkalis, containing one, two, and even three equivalents of the anhydride to one equivalent of base. Thus among the potassium salts there is known the normal or yellow chromate, K_2CrO_4 , which corresponds to, and is perfectly isomorphous with, potassium sulphate, easily forms isomorphous mixtures with it, and is not therefore suitable for a process in which it is necessary to separate the salt from a mixture containing sulphates. As in the presence of a certain excess of acid, alkalis easily give dichromates, the object of the manufacturer is to produce such a dichromate, the more so as it contains a larger proportion of the elements of chromic acid than the normal salt. Finely-ground chrome iron ore, when heated with an alkali, absorbs oxygen almost as easily, if not more so, than a mixture of the oxides of manganese with an alkali. This absorption is due to the presence of chromic oxide, which is oxidised into the anhydride, and then combines with the alkali: $\text{Cr}_2\text{O}_3 + \text{O}_3 = 2\text{CrO}_3$. As the oxidation and formation of the chromate proceeds, the mass turns *yellow*. The iron is also oxidised, but does not give ferric acid, because the capacity of the chromium for oxidation is incomparably greater than that of the iron.

A mixture of lime and chrome iron ore is heated in a reverberatory furnace, with access of a large excess of air and at a red heat for

¹ The working of the Ural chrome iron ore into chromium compounds has been firmly established in Russia, thanks to the endeavours of P. K. Ushakoff, who constructed large works for this purpose on the river Kama, near Elabougi, where as much as 2000 tons of ore are treated yearly, owing to which the importation of chromium preparations into Russia has ceased.

several hours, until the mass becomes yellow ; it then contains normal calcium chromate, CaCrO_4 , which is insoluble in water in the presence of an excess of lime. But the calcium chromate is soluble in water in the presence of an excess of chromic acid, as may be seen from the fact that a solution of chromic acid dissolves lime. The resultant mass is ground up, and treated with water and sulphuric acid. The excess of lime forms gypsum, and the soluble calcium dichromate, CaCr_2O_7 , together with a certain amount of iron, pass into solution. The solution is poured off, and chalk added to it ; this precipitates the ferric oxide (the ferrous oxide is converted into ferric oxide in the furnace) and forms a fresh quantity of gypsum, while the chromic acid remains in solution—that is, it does not form the sparingly-soluble (1 part in 240 parts of water) normal salt. The solution then holds a fairly pure calcium dichromate, which by double decomposition gives other chromates ; for example, with a solution of potassium sulphate it gives a precipitate of calcium sulphate and a solution of potassium dichromate, which crystallises when evaporated.

Potassium dichromate, $\text{K}_2\text{Cr}_2\text{O}_7$, easily crystallises from acid solutions in red, well-formed prismatic crystals, which fuse at a red heat and evolve oxygen at a very high temperature, leaving chromic oxide and the normal salt, which is not further changed : $2\text{K}_2\text{Cr}_2\text{O}_7 = 2\text{K}_2\text{CrO}_4 + \text{Cr}_2\text{O}_3 + \text{O}_3$. At the ordinary temperature 100 parts of water dissolve 10 parts of this salt, and the solubility increases as the temperature rises. It is most important to note that the dichromate does not contain water, it is $\text{K}_2\text{CrO}_4 + \text{CrO}_3$; and the acid salt corresponding to potassium acid sulphate, KHSO_4 , does not exist. It does not even evolve heat when dissolving in water, but on the contrary produces cold ; thus it does not even then form a definite compound with water. The solution and the salt itself are poisonous, and act as powerful oxidising agents, which is the character of the compounds of chromic acid in general. When heated with sulphur or organic substances, with sulphurous anhydride, hydrogen sulphide, or many metals, this salt is deoxidised, yielding chromic compounds.² Potassium dichromate³ is used in the arts and in chemistry as a source for

² The oxidising action of potassium dichromate on organic substances at the ordinary temperature is especially marked under the action of light. Thus it acts on gelatin, as Ponton discovered ; this is applied to photography in the processes of photogravure, photo-lithography, pigment printing, &c. Under the action of light this gelatin is oxidised, and the chromic anhydride deoxidised into chromic oxide, which unites with the gelatin and forms a compound insoluble in warm water, whilst, where the light has not acted, the gelatin remains soluble, its properties being unaffected by the presence of chromic acid or potassium dichromate.

³ Ammonium and sodium dichromates are now also prepared on a large scale. The sodium salts may be prepared in exactly the same manner as those of potassium. The

the preparation of all other chromium compounds. It is converted into yellow pigments by means of double decomposition with salts of lead, barium, and zinc. When solutions of the salts of these metals are mixed with potassium dichromate (in dyeing generally mixed with soda, in order to obtain normal salts), they are precipitated as insoluble normal salts; for example, $2\text{BaCl}_2 + \text{K}_2\text{Cr}_2\text{O}_7 + \text{H}_2\text{O} = 2\text{BaCrO}_4 + 2\text{KCl} + 2\text{HCl}$. This already shows that these salts are insoluble in dilute acids, but the precipitation is not complete (as it would be with the normal salt). The barium and zinc salts are of a lemon yellow colour; the lead salt has a still more intense colour passing into orange. Yellow cotton prints are dyed with this pigment. The silver salt, Ag_2CrO_4 , is of a bright red colour.

When potassium dichromate is mixed with potassium hydroxide or carbonate (carbonic anhydride is disengaged in the latter case) it forms the *normal salt*, K_2CrO_4 , known as *yellow chromate of potassium*. Its specific gravity is 2.7, being almost the same as that of the dichromate. It absorbs heat in dissolving; one part of the salt dissolves in 1.75 parts of water at the ordinary temperature, forming a yellow solution. When mixed with even such feeble acids as acetic, not to speak of

normal salt combines with ten equivalents of water, like Glauber's salt, with which it is isomorphous. Its solution above 30° deposits the anhydrous salt. Sodium dichromate crystals contain $\text{Na}_2\text{Cr}_2\text{O}_7 \cdot 7\text{H}_2\text{O}$. The *ammonium salts of chromic acid* are obtained by saturating the anhydride itself with ammonia. The dichromate is obtained by saturating one part of the anhydride with ammonia, and then adding a second part of anhydride and evaporating under the receiver of an air-pump. On ignition, the normal and acid salts leave chromic oxide. Potassium ammonium chromate, NH_4KCrO_4 , is obtained in yellow needles from a solution of potassium dichromate in aqueous ammonia; it not only loses ammonia and becomes converted into potassium dichromate when ignited, but also by degrees at the ordinary temperature. This shows the feeble energy of chromic acid, and its tendency to form stable dichromates. Magnesium chromate is soluble in water, as also is the strontium salt. The calcium salt is also somewhat soluble, but the barium salt is almost insoluble. The isomorphism with sulphuric acid is evinced in the chromates by the fact that the magnesium and ammonium salts form double salts containing six equivalents of water, which are perfectly isomorphous with the corresponding sulphates. The magnesium salt crystallises in large crystals containing seven equivalents of water. The beryllium, cerium, and cobalt salts are insoluble in water. Chromic acid dissolves manganous carbonate, but on evaporation the solution deposits manganese dioxide, formed at the expense of the oxygen of the chromic acid. Chromic acid also oxidises ferrous oxide, and ferric oxide is soluble in chromic acid. It must be observed that the chromates have not yet been sufficiently investigated.

One of the chromates most used by the dyer is the insoluble yellow lead chromate, PbCrO_4 (*supra*, p. 131). It easily forms a basic salt, having the composition $\text{PbO}, \text{PbCrO}_4$, as a crystalline powder, obtained by fusing the normal salt with nitre and then rapidly washing in water. The same substance is obtained, although impure and in small quantity, by treating lead chromate with potassium chromate, especially on boiling the mixture; and this gives the possibility of attaining, by means of these materials, various tints of lead chromate, from yellow to red, passing through different orange shades. The decomposition which takes place (incompletely) in this case is as follows: $2\text{PbCrO}_4 + \text{K}_2\text{CrO}_4 = \text{PbCrO}_4, \text{PbO} + \text{K}_2\text{Cr}_2\text{O}_7$ —that is, potassium dichromate is formed in solution.

the ordinary acids, it gives the dichromate, and Graham obtained a trichromate, $K_2Cr_3O_{10} = K_2CrO_4 \cdot 2CrO_3$, by mixing a solution of the latter salt with an excess of nitric acid.

Chromic anhydride is obtained by preparing a saturated solution of potassium dichromate at the ordinary temperature, and pouring it in a thin stream into an equal volume of pure sulphuric acid.⁴ On mixing, the temperature naturally rises; when slowly cooled, the solution deposits chromic anhydride in needle-shaped crystals of a red colour sometimes several centimetres long. The crystals are freed from the mother liquor by placing them on a porous tile. They cannot be filtered or washed, because the chromic anhydride is reduced by the filter-paper, and is dissolved during the process of washing. It is very important at this point to call attention to the fact that a hydrate of chromic anhydride is never obtained in the decomposition of chromic compounds, but always the *anhydride*, CrO_3 . The corresponding hydrate, CrO_4H_2 , or any other hydrate, is not even known. Nevertheless, it must be admitted that chromic acid is bibasic, because it forms salts isomorphous or perfectly analogous with the salts formed by sulphuric acid, which is the best example of a bibasic acid. It gives

⁴ The sulphuric acid should not contain any lower oxides of nitrogen, because they reduce chromic anhydride into chromic oxide.

If a solution of a chromate be strongly heated with an excess of acid—for instance, sulphuric or hydrochloric acid—oxygen or chlorine is evolved, and a solution of a chromic salt is formed. Hence, under these circumstances, chromic acid cannot be obtained from its salts, although it may be obtained by many methods in a free state. One of the first methods employed consisted in converting its salts into volatile *chromium hexafluoride*, CrF_6 . This compound, obtained by Unverdorben, may be prepared by mixing lead chromate with fluor spar in a dry state, and treating the mixture with fuming sulphuric acid in a platinum vessel: $PbCrO_4 + 3CaF_2 + 4H_2SO_4 = PbSO_4 + 3CaSO_4 + 4H_2O + CrF_6$. Fuming sulphuric acid is taken, and in considerable excess, because the chromium fluoride which is formed is very easily decomposed by water. It is volatile, and forms a very caustic, poisonous vapour, which condenses when cooled in a dry platinum vessel into a red, exceedingly volatile liquid, which fumes powerfully in air. The vapours of this substance when introduced into water are decomposed into hydrofluoric acid and chromic anhydride: $CrF_6 + 3H_2O = CrO_3 + 6HF$. If very little water be taken the hydrofluoric acid volatilises, and chromic anhydride separates directly in crystals. The chloranhydride of chromic acid, CrO_2Cl_2 , which will be shortly described, is also decomposed in the same manner. A solution of chromic acid and a precipitate of barium sulphate are formed by treating the insoluble barium chromate with an equivalent quantity of sulphuric acid. If carefully evaporated, the solution yields crystals of chromic anhydride. Fritzsche gave a very convenient method of preparing chromic anhydride, based on the relation of chromic to sulphuric acid. At the ordinary temperature the strong acid dissolves both chromic anhydride and potassium chromate, but if a certain amount of water is added to the solution the chromic anhydride separates, and if the amount of water be increased the precipitated chromic anhydride is again dissolved. The chromic anhydride is almost all separated from the solution when it contains two equivalents of water to one equivalent of sulphuric acid. Many methods for the preparation of chromic anhydride are based on this fact.

(when heated with sodium chloride and sulphuric acid) a volatile chloranhydride, CrO_2Cl_2 , containing two atoms of chlorine as a bibasic acid should.⁵ Chromic anhydride is a red crystalline substance, which is converted into a black mass by heat; it fuses at 190° , and disengages oxygen above 250° , leaving a residue of chromium dioxide, CrO_2 ,⁶ and, on still further heating, chromic oxide. Chromic anhydride

⁵ Berzelius observed, and Rose carefully investigated, this remarkable reaction, which occurs between chromic acid and sodium chloride in the presence of sulphuric acid. If 10 parts of common salt be mixed with 12 parts of potassium dichromate, fused, cooled, and broken up into lumps, and placed in a retort with 20 parts of fuming sulphuric acid, it gives rise to a violent reaction, accompanied by the formation of brown fumes of *chromic chloranhydride*, or *chromyl chloride*, CrO_2Cl_2 , according to the reaction: $\text{CrO}_3 + 2\text{NaCl} + \text{H}_2\text{SO}_4 = \text{Na}_2\text{SO}_4 + \text{H}_2\text{O} + \text{CrO}_2\text{Cl}_2$. The addition of an excess of sulphuric acid is necessary in order to retain the water. The same substance is always formed when a metallic chloride is heated with chromic acid, or of its salts, in the presence of sulphuric acid. The formation of this volatile substance is easily observed from the brown colour which is proper to its vapour. On condensing the vapour in a dry receiver a liquid is obtained having a sp. gr. of 1.9, boiling at 118° , and giving a vapour whose density, compared with hydrogen, is 7.9, which corresponds with the above formula. Chromyl chloride is decomposed by heat into chromic oxide, oxygen, and chlorine: $2\text{CrO}_2\text{Cl}_2 = \text{Cr}_2\text{O}_3 + 2\text{Cl}_2 + \text{O}$; so that it is able to act simultaneously as a powerful oxidising and chlorinising agent, which is taken advantage of in the investigation of many, and especially of organic, substances. When treated with water, this substance first falls to the bottom, and is then decomposed into hydrochloric and chromic acids, like all chloranhydrides: $\text{CrO}_2\text{Cl}_2 + \text{H}_2\text{O} = \text{CrO}_3 + 2\text{HCl}$. When brought into contact with inflammable substances it sets fire to them; it acts thus, for instance, on phosphorus, sulphur, oil of turpentine, ammonia, hydrogen, and other substances. It attracts moisture from the atmosphere with great energy, and must therefore be kept in closed vessels. It dissolves iodine and chlorine, and even forms a solid compound with the latter, which perhaps indicates the faculty of chromium to form its higher oxide, Cr_2O_7 . The close analogy in the physical properties of the chloranhydrides, CrO_2Cl_2 and SO_2Cl_2 , is very remarkable, although sulphurous anhydride is a gas, and the corresponding oxide, CrO_2 , is a non-volatile solid. It may be imagined, therefore, that chromium dioxide (which will be mentioned in the following note) presents a polymerised modification of the substance having the composition CrO_2 ; in fact, this is obvious from the method of its formation.

If three parts of potassium dichromate be mixed with four parts of strong hydrochloric acid and a small quantity of water, and gently warmed, then it all passes into solution, and no chlorine is evolved; on cooling, the liquid deposits red prismatic crystals, known as *Peligo's salt*, which are very stable in air. This has the composition KClCrO_5 , and is formed according to the equation $\text{K}_2\text{Cr}_2\text{O}_7 + 2\text{HCl} = 2\text{KClCrO}_5 + \text{H}_2\text{O}$. It is evident that this is the first chloranhydride of chromic acid, HCrO_5Cl , in which the hydrogen is replaced by potassium. It is decomposed by water, and on evaporation the solution yields potassium dichromate and hydrochloric acid. This is a fresh instance of the reversible reactions so frequently encountered. With sulphuric acid Peligo's salt forms chromyl chloride. The latter circumstance, and the fact that Genthner produced Peligo's salt from potassium chromate and chromyl chloride, give reason for thinking that it is a compound of these two substances: $2\text{KClCrO}_5 = \text{K}_2\text{CrO}_4 + \text{CrO}_2\text{Cl}_2$. It is also sometimes regarded as potassium dichromate in which one atom of oxygen is replaced by chlorine—that is, $\text{K}_2\text{Cr}_2\text{O}_6\text{Cl}_2$, corresponding with $\text{K}_2\text{Cr}_2\text{O}_7$. When heated it parts with all its chlorine, and on further heating gives chromic oxide.

⁶ This is the most intermediate degree of oxidation. Chromium dioxide, CrO_2 , may be obtained by mixing solutions of chromic salts with solutions of chromates. The

is exceedingly soluble in water, and even attracts moisture from the air, but, as was mentioned above, it does not form any definite compound with water. The specific gravity of its crystals is 2.7, and when fused it has a specific gravity 2.6. No heat effect is observable in the act of solution in water. The solution presents perfectly defined acid properties. It liberates carbonic anhydride from carbonates; gives insoluble precipitates of the chromates with salts of barium, lead, silver, and mercury.

The action of *hydrogen peroxide* on a solution of chromic acid or of potassium dichromate gives a *blue* solution, which very quickly becomes colourless with the disengagement of oxygen. Barreswil showed that this is due to the formation of a higher oxide of chromium, Cr_2O_7 , corresponding with sulphur peroxide. This peroxide is remarkable from the fact that it very easily dissolves in ether and is much more stable in this solution, so that, by shaking up hydrogen peroxide mixed with a small quantity of chromic acid, with ether, it is possible to transfer all the blue substance formed to the ether.

With oxygen acids, chromic acid evolves oxygen; for example, with sulphuric acid the following reaction takes place: $2\text{CrO}_3 + 3\text{H}_2\text{SO}_4 = \text{Cr}_2(\text{SO}_4)_3 + \text{O}_3 + 3\text{H}_2\text{O}$. It will be readily understood from this that a *mixture of chromic acid or its salts with sulphuric acid* forms an excellent *oxidising agent*, which is frequently employed in chemical laboratories and even for technical purposes as a means of oxidation. Thus hydrogen sulphide and sulphurous anhydride are converted into sulphuric acid by this means. Chromic acid is able to act as a powerful oxidising agent because it passes into chromic oxide, and in so doing disengages half of the oxygen contained in it: $2\text{CrO}_3 = \text{Cr}_2\text{O}_3 + \text{O}_3$. Thus chromic anhydride itself is a powerful oxidising agent, and is therefore employed instead of nitric acid in galvanic

brown precipitate formed contains a compound, $\text{Cr}_2\text{O}_3, \text{CrO}_5$, of equivalent amounts of oxides and chromic anhydrides. Probably a portion of this chromic acid remains in solution. The reaction is more clearly seen if chromic anhydride itself or a dichromate be taken. The brown precipitate of chromium dioxide contains water. The same substance is formed by the imperfect deoxidation of chromic anhydride by various reducing agents. Chromic oxide, when heated, absorbs oxygen, and appears to give the same substance. Chromic nitrate, when ignited, also gives this substance. When this substance is heated it first disengages water and then oxygen, chromic oxide being left. It corresponds with manganese dioxide, $\text{Cr}_2\text{O}_3, \text{CrO}_5 - 3\text{CrO}_2$. Krüger treated chromium dioxide with a mixture of sodium chloride and sulphuric acid, and found that chlorine gas was evolved, but that chromyl chloride was not formed. Under the action of light, a solution of chromic acid also deposits the brown dioxide. At the ordinary temperature chromic anhydride leaves a brown stain upon the skin and tissues, which probably proceeds from a decomposition of the same kind. Chromic anhydride is soluble in alcohol containing water, and this solution is decomposed in a similar manner by light.

batteries (as a depolariser), the hydrogen evolved at the carbon being then oxidised, and the chromic acid converted into a non-volatile product of deoxidation, instead of yielding, as nitric acid does, volatile lower oxides of offensive odour. Organic substances are more or less perfectly oxidised by means of chromic anhydride, although this generally requires the aid of heat, and does not proceed in the presence of alkalis, but generally *in the presence of acids*. In acting on a solution of potassium iodide, chromic acid liberates iodine, six equivalents of iodine being evolved for every three equivalents of oxygen liberated; this reaction may be taken advantage of in many analyses, as the quantity of iodine may be determined with accuracy. If chromic anhydride is ignited in a stream of ammonia, it gives chromic oxide, water, and nitrogen. In all cases when chromic acid acts as an oxidising agent in the presence of acids and under the action of heat, the product of its deoxidation is a chromic salt, CrX_3 , which is characterised by the green colour of its solution, so that the *red* or *yellow solution* of a salt of chromic acid is then transformed into *green solution* of a chromic salt, derived from chromic oxide, Cr_2O_3 , which is closely analogous to Al_2O_3 , Fe_2O_3 , and other bases of the composition R_2O_3 . This analogy is seen in the insolubility of the anhydrous oxide, in the gelatinous form of the colloidal hydrate, in the formation of alums, of a volatile chloride of chromium, &c.⁷

⁷ As a mixture of potassium dichromate and sulphuric acid is usually employed for oxidation, the resultant solution generally contains a double sulphate of potassium and chromium—that is, *chrome alum*, isomorphous with ordinary alum— $\text{K}_2\text{Cr}_2\text{O}_7 + 4\text{H}_2\text{SO}_4 + 20\text{H}_2\text{O} = \text{O}_5 + \text{K}_2\text{Cr}_2(\text{SO}_4)_4 \cdot 24\text{H}_2\text{O}$ or $2(\text{KCr}(\text{SO}_4)_2 \cdot 12\text{H}_2\text{O})$. It is prepared by dissolving potassium dichromate in dilute sulphuric acid; alcohol is then added and the solution slightly heated, or sulphurous anhydride is passed through it. On the addition of alcohol to a cold mixture of potassium dichromate and sulphuric acid, the gradual disengagement of pleasant-smelling volatile products of the oxidation of alcohol, and especially of aldehyde, $\text{C}_2\text{H}_4\text{O}$, is remarked. If the temperature of decomposition does not exceed 85° , a *violet* solution of chrome alum is obtained, but if the temperature be higher, a solution of the same alum is obtained of a *green* colour. As chrome alum requires for solution 7 parts of water at the ordinary temperature, it follows that if a somewhat strong solution of potassium dichromate be taken (4 parts of water and $1\frac{1}{2}$ of sulphuric acid to 1 part of dichromate), it will give so concentrated a solution of chrome alum that on cooling the salt will separate without further evaporation. If the liquid, prepared as above or in any instance of the deoxidation of chromic acid, be heated (the oxidation naturally proceeds more rapidly) rather considerably, for instance, to the boiling-point of water, or if the violet solution already formed be subjected to the same temperature, then it acquires a bright *green colour*, and on evaporation the same mixture, which at lower temperatures so easily gives cubical crystals of chrome alum, does not give any crystals whatever. If the green solution be kept, however, for several weeks at the ordinary temperature, it deposits *violet crystals* of chrome alum. The green solution, when evaporated, gives a non-crystalline mass, and the violet crystals lose water at 100° and turn green. It must be remarked that the transition of the green modification into the violet is accompanied by a decrease in volume (Lecoq de

The reduction of chromic oxide—for instance, in solution with zinc and sulphuric acid—leads to the formation of chromous oxide, CrO , and

Boisbaudran, Favre). If the green mass formed at the higher temperature is evaporated to dryness and heated at 80° in a current of air, it does not retain more than 6 equivalents of water. Hence Löwel, and also Schrötter, concluded that the green and violet modifications of the alum depend on different degrees of combination with water, which may be likened to the different compounds of sodium sulphate with water and to the different hydrates of ferric oxide.

However, the question in this case is not so simple, as we shall afterwards see. Not chrome alum alone, but *all the chromic salts*, give two, if not three, *varieties*. At least, there is no doubt about the existence of two—a *green* and a *violet modification*. The green chromic salts are obtained by heating solutions of the violet salts, the violet solutions are produced by the prolonged keeping of solutions of the green salts. The conversion of the violet salts into green by the action of heat already indicates rather clearly the possibility of explaining the different modifications by their containing different proportions of water, and, moreover, of the green salts having a less amount of water than the violet. However, there are other explanations. Chromic oxide is a base like alumina, and is therefore able to give both acid and basic salts. It is supposed that the difference between the green and violet salts is due to this fact. This opinion of Krüger is based on the fact that alcohol separates out a salt from the green solution, which contains less sulphuric acid than the normal violet salt. On the other hand, Löwel showed that all the acid cannot be separated from the green chromic salts by suitable reagents, as easily as it can be from the same solution of the violet salts; thus barium salts do not precipitate all the sulphuric acid from solutions of the green salts. According to other researches the cause of the varieties of the chromic salts lies in a difference in the bases they contain—that is, connected with a modification of the properties of the oxide of chromium itself. However, this only refers to the hydroxides, and as hydroxides themselves are only special forms of salts, the differences observed as yet in this direction between the hydroxides only confirm the generality of the difference observed in the chromic compounds.

The salts of chromic oxide, like those of alumina, are easily decomposed, give basic and double salts, and have an acid reaction, as chromic oxide is a feeble base. Potassium and sodium hydroxides give a *precipitate* of the hydroxide with chromic salts, CrX_5 . The violet and green salts give a *hydroxide soluble in an excess of the reagent*; but the hydroxide is held in solution by very feeble affinities, so that it is partially separated by heat and dilution with water, and completely so on boiling. In an alkaline solution, chromic hydroxide is easily converted into chromic acid by the action of lead dioxide, chlorine, and other oxidising agents. If the chromic oxide occurs together with such oxides as magnesia, or zinc oxide, then on precipitation it separates out from its solution in combination with these oxides, forming, for example, $\text{ZnO}, \text{Cr}_2\text{O}_5$. In the presence of 80 parts of ferric oxide, 100 parts of chromic oxide become insoluble in alkali hydroxides. On precipitating the violet solution of chrome alum with ammonia, a precipitate containing $\text{Cr}_2\text{O}_5, 6\text{H}_2\text{O}$ is obtained, whilst in the precipitation from the boiling solution in caustic potash a hydrate containing four equivalents of water is obtained. When fused with borax chromic salts give a green glass. The same coloration is communicated to ordinary glass by the presence of traces of chromic oxide. A chrome glass containing a large amount of chromic oxide may be ground up and used as a green pigment.

In speaking of the chromium hydroxide, it is impossible not to mention *Guignet's green*, which forms one of the widely-used green pigments which have been substituted for the formerly much used poisonous arsenical copper pigments, such as Schweinfurt green. Guignet's green has an extremely bright green colour, and is distinguished for its great stability, not only under the action of light but also towards reagents; thus it is not altered by solution of alkalis, and even nitric acid does not act on it, at least not

its salts, CrX_2 , of a blue colour. The further reduction of oxide of chromium and its corresponding compounds, gives *metallic chromium*.

when diluted with water. This pigment remains unchanged up to a temperature of 250° ; it contains $\text{Cr}_2\text{O}_3 \cdot 2\text{H}_2\text{O}$, and generally a small amount of alkali. It is prepared by fusing 3 parts of boric acid with 1 part of potassium dichromate; oxygen is disengaged, and a green glass, containing a mixture of the borates of chromium and potassium, is obtained. When cool this glass is ground up and treated with water, which extracts the boric acid and alkali, and leaves the above-named chromic hydroxide behind. This hydroxide only parts with its water at a red heat, leaving the anhydrous oxide.

The chromic hydroxides lose their water by ignition, and in doing so become spontaneously incandescent, like the ordinary ferric hydroxide (Chap. XXII.). It is not known, however, whether all the modifications of chromic oxide show this phenomenon. The anhydrous *chromic oxide*, Cr_2O_3 , is exceedingly difficultly soluble in acids, if it has passed through the above recalcination. But if it has parted with its water, or the greater part of it, and not yet undergone this self-induced incandescence (has not lost a portion of its energy), then it is soluble in acids. It is not reduced by hydrogen. It is easily obtained in various crystalline forms by many methods. The chromates of mercury and ammonium give a very convenient method for its preparation, because, when ignited, they leave chromic oxide behind. In the first instance oxygen and mercury are disengaged, and in the second case nitrogen and water: $2\text{Hg}_2\text{CrO}_4 = \text{Cr}_2\text{O}_3 + \text{O}_2 + 4\text{Hg}$ or $(\text{NH}_4)_2\text{Cr}_2\text{O}_7 = \text{Cr}_2\text{O}_3 + 4\text{H}_2\text{O} + \text{N}_2$. The second reaction is very energetic, and the mass of salt burns spontaneously if the temperature be sufficiently high. A mixture of potassium sulphate and chromic oxide is formed by heating potassium dichromate with an equal weight of sulphur: $\text{K}_2\text{Cr}_2\text{O}_7 + \text{S} = \text{K}_2\text{SO}_4 + \text{Cr}_2\text{O}_3$. The sulphate is easily extracted by water, and there remains a bright green residue of the oxide, whose colour is more brilliant the lower the temperature of the decomposition. The oxide thus obtained is used as a green pigment for china and enamel. The anhydrous chromic oxide obtained from chromyl chloride, CrO_2Cl_2 , has a specific gravity of 5.21, and forms almost black crystals, which give a green powder. They are hard enough to scratch glass, and have a metallic lustre. The crystalline form of chromic oxide is identical with that of the oxide of iron and alumina, with which it is isomorphous.

The most important of the compounds corresponding with chromic oxide is *chromic chloride*, Cr_2Cl_6 , which is known in an anhydrous and in a hydrated form. It resembles ferric and aluminic chlorides in many respects. There is a great difference between the anhydrous and the hydrated chlorides; the former is insoluble in water, the latter easily dissolves, and on evaporation its solution forms a hygroscopic mass, which is very unstable, and easily evolves hydrochloric acid when heated with water. The anhydrous form is of a violet colour, and Wöhler gives the following method for its preparation: an intimate mixture is prepared of the anhydrous chromic oxide with carbon and organic matter, and charged into a wide infusible glass or porcelain tube which is heated in a combustion furnace; one extremity of the tube communicates with an apparatus generating chlorine, which is passed through several bottles containing sulphuric acid in order to perfectly dry it before it reaches the tube. On heating the portion of the tube in which the mixture is placed and passing the chlorine, a slightly volatile sublimate of chromic chloride, CrCl_3 or Cr_2Cl_6 , is formed. This substance forms *violet tabular crystals*, which may be distilled in dry chlorine without change, but which, however, require a red heat for their volatilisation. These crystals are greasy to the touch and insoluble in water, but if they be rubbed and boiled in water for a long time they pass into a *green solution*. Strong sulphuric acid does not act on the anhydrous salt, or only acts with exceeding slowness, like water. Even aqua regia and other acids do not act on the crystals, and alkalis only show a very feeble action. The specific gravity of the crystals is 2.99. When fused with sodium carbonate and nitre they give sodium chloride and potassium chromate, and when ignited in air they form green chromic oxide and evolve chlorine. When ignited in a stream of ammonia, chromic chloride forms

Deville obtained it by reducing chromic oxide with carbon, at a temperature sufficiently high to fuse platinum, but the metal itself

sal-ammoniac and chromium nitride, CrN (analogous to the nitrides BN , AlN). Mosberg and Peligot showed that when chromic chloride is ignited in hydrogen, it parts with one-third of its chlorine, forming chromous chloride, CrCl_2 —that is, there is formed from a compound corresponding with chromic oxide, Cr_2O_3 , a compound answering to the *suboxide*, chromous oxide, CrO —just as hydrogen converts ferric chloride into ferrous chloride with the aid of heat. *Chromous chloride*, CrCl_2 , forms colourless crystals which are easily soluble in water, and in dissolving evolve a considerable amount of heat, and form a blue liquid, which is capable of absorbing oxygen from the air with great facility, and then passes into a chromic compound.

The blue solution of chromous chloride may also be obtained by the action of metallic zinc on the green solution of the hydrated chromic chloride; the zinc in this case takes up chlorine just as the hydrogen did. It must be employed in a large excess. Chromic oxide is also formed in the action of zinc on chromic chloride, and if the solution remain for a long time in contact with the zinc the whole of the chromium is converted into chromic oxychloride. Other chromic salts are also reduced by zinc into *chromous salts*, just as the ferric salts are converted into ferrous salts by it. The chromous salts are exceedingly unstable and easily oxidise and pass into chromic salts; hence the reducing power of these salts is very great. From cupric salts they separate cuprous salts, from stannous salts they precipitate metallic tin, they reduce mercuric salts into mercurous and ferric into ferrous salts. With potassium chromate they give a brown precipitate of chromium dioxide or of chromic oxide, according to the relative amounts of the substances taken: $\text{CrO}_3 + \text{CrO} = 2\text{CrO}_2$ or $\text{CrO}_3 + 3\text{CrO} = 2\text{Cr}_2\text{O}_3$. Aqueous ammonia gives a blue precipitate, and in the presence of ammoniacal salts a blue liquid is obtained which turns red in the air from oxidation. This is accompanied by the formation of compounds analogous to those given by cobalt (Chap. XXII.). A solution of chromous chloride with a hot saturated solution of sodium acetate, $\text{C}_2\text{H}_3\text{NaO}_2$, gives, on cooling, transparent red crystals of chromous acetate, $\text{C}_4\text{H}_6(\text{CrO})_2\text{H}_2\text{O}$. This salt is also a powerful reducing agent, but may be kept for a long time in a vessel full of carbonic anhydride.

The insoluble anhydrous *chromic chloride* very easily *passes into solution* in the presence of a trace (0.004) of *chromous chloride*. This remarkable phenomenon was observed by Peligot and explained by Löwel in the following manner: chromous chloride, as a lower stage of oxidation, is capable of absorbing both oxygen and chlorine, combining with various substances. It is able to decompose many chlorides by taking up chlorine from them; thus it precipitates mercurous chloride from a solution of mercuric chloride, and in so doing passes into chromic chloride: $2\text{CrCl}_2 + 2\text{HgCl}_2 = \text{Cr}_2\text{Cl}_6 + 2\text{HgCl}$. Let us suppose that the same phenomenon takes place when the anhydrous chromic chloride is mixed with a solution of chromous chloride. The latter will then take up a portion of the chlorine of the former, and pass into a soluble hydrate of chromic chloride (hydrochloride of oxide of chromium), and the original anhydrous chromic chloride will pass into chromous chloride. The chromous chloride re-formed in this manner will then act on a fresh quantity of the chromic chloride, and in this manner transfer it entirely into solution as hydrate. This view is confirmed by the fact that other chlorides, capable of absorbing chlorine like chromous chloride, also induce the solution of the insoluble chromic chloride—for example, ferrous chloride, FeCl_2 , and cuprous chloride. The presence of zinc also aids the solution of chromic chloride, owing to its converting a portion of it into chromous chloride. The solution of chromic chloride in water obtained by these methods is perfectly identical with that which is formed by dissolving chromic hydroxide in hydrochloric acid. On evaporating the *green solution* obtained in this manner, it gives a green mass, containing water. On further heating it leaves a soluble chromic oxychloride, and when ignited it first forms an insoluble oxychloride and then chromic oxide; but no anhydrous chromic chloride, Cr_2Cl_6 , is formed by heating the aqueous solution of chromic chloride, which forms an important fact in favour of the

does not fuse at this temperature. The same metal obtained by other chemists has a steel grey colour and is very hard. Bunsen obtained metallic chromium by decomposing a solution of chromic chloride, Cr_2Cl_6 , by a galvanic current, as scales of a grey colour. Wöhler obtained crystalline chromium by igniting a mixture of the anhydrous chromic chloride with finely-divided zinc, and sodium and potassium

representation that the green solution of chromic chloride is nothing else but hydrochloride of oxide of chromium. At 100° the composition of the green hydrate is $\text{Cr}_2\text{Cl}_6, 9\text{H}_2\text{O}$, and on evaporation crystals are obtained with 12 equivalents of water; the red mass obtained at 120° contains $\text{Cr}_2\text{O}_5, 4\text{Cr}_2\text{Cl}_6, 24\text{H}_2\text{O}$. The greater portion of it is soluble in water, like the mass which is formed at 150° . The latter contains $\text{Cr}_2\text{O}_5, 2\text{Cr}_2\text{Cl}_6, 9\text{H}_2\text{O} = 3(\text{Cr}_2\text{OCl}_4, 3\text{H}_2\text{O})$ —that is, it presents the same composition as chromic chloride in which one atom of oxygen replaces two of chlorine. And if the hydrate of chromic chloride be regarded as $\text{Cr}_2\text{O}_5, 6\text{HCl}$, then the substance which is obtained should be regarded as $\text{Cr}_2\text{O}_5, 4\text{HCl}$ combined with water, H_2O . The addition of alkalis—for example, baryta—to a solution of chromic chloride immediately produces a precipitate, which, however, re-dissolves on shaking, owing to the formation of one of the oxychlorides just mentioned, which may be regarded as *basic salts*. Thus we may represent the product of the change produced on chromic chloride under the influence of water and heat by the following formulæ: first $\text{Cr}_2\text{O}_5, 6\text{HCl}$ or $\text{Cr}_2\text{Cl}_6, 3\text{H}_2\text{O}$ is formed, then $\text{Cr}_2\text{O}_5, 4\text{HCl}, \text{H}_2\text{O}$ or $\text{Cr}_2\text{OCl}_4, 3\text{H}_2\text{O}$, and lastly $\text{Cr}_2\text{O}_5, 2\text{HCl}, 2\text{H}_2\text{O}$ or $\text{Cr}_2\text{O}_2\text{Cl}_2, 3\text{H}_2\text{O}$. In all three cases there are 2 equivalents of chromium to at least 3 equivalents of water. These compounds may be regarded as being intermediate between chromic hydroxide and chloride; chromic chloride is Cr_2Cl_6 , the first oxychloride $\text{Cr}_2(\text{OH})_2\text{Cl}_4$, the second $\text{Cr}_2(\text{OH})_4\text{Cl}_2$, and the hydrate $\text{Cr}_2(\text{OH})_6$ —that is, the chlorine is replaced by hydroxyl.

It is very important to remark that the whole of the chlorine in the above compounds is not precipitated from their solutions by silver nitrate; thus the normal salt of the composition $\text{Cr}_2\text{Cl}_6, 9\text{H}_2\text{O}$ only gives up two-thirds of its chlorine; therefore Peligot supposes that the normal salt contains the oxychloride combined with hydrochloric acid: $\text{Cr}_2\text{Cl}_6 + 2\text{H}_2\text{O} = \text{Cr}_2\text{O}_2\text{Cl}_2, 4\text{HCl}$, and that the chlorine held as hydrochloric acid reacts with the silver, whilst that held in the oxychloride does not enter into reaction, just as we observe a very feebly-developed faculty for reaction in the anhydrous chromic chloride. Moreover, Peligot supposes that the above two oxychlorides are formed by the successive loss of first two, and then two more, molecules of hydrochloric acid. Löwel obtained the violet solution of hydrochloride of chromic oxide by decomposing the violet chromic sulphate with barium chloride. Silver nitrate precipitates all the chlorine from this violet modification; but if the violet solution be boiled and so converted into the green modification, silver nitrate then only precipitates a portion of the chlorine. These facts must naturally be taken into consideration in order to arrive at any complete decision as to the cause of the different modifications of the chromic salts. We may observe that the green modification of chromic chloride does not give double salts with the metallic chlorides, whilst the violet variety forms compounds $\text{Cr}_2\text{Cl}_6, 2\text{RCl}$ (where R=an alkali metal), which are obtained by heating the chromates with an excess of hydrochloric acid and evaporating the solution until it acquires a violet colour. As the result of all the existing researches on the green and violet chromic salts, it appears to me most probable that their difference is determined by the feeble basic character of chromic oxide, by its faculty of giving basic salts, and by the colloidal properties of its hydroxide (these three properties are mutually connected), and it may therefore be said that the green modifications contain basic salts, or are the violet salts in a state of dissociation.

We may here observe that with tin the chromic salts, CrX_3 , give at low temperatures CrX_2 and SnX_2 , whilst at high temperatures, on the contrary, CrX_2 reduces the metal from its salts SnX_2 . The reaction, therefore, belongs to the number of reversible reactions (Beketoff).

chlorides at the boiling-point of zinc. When the resultant mass has cooled the zinc may be dissolved in dilute nitric acid, and grey crystalline chromium is left behind. Frémy also prepared crystalline chromium by the action of the vapour of sodium on anhydrous chromic chloride in a stream of hydrogen, using the apparatus shown in the accompanying drawing, and placing the sodium and chromic chloride in separate




FIG. 92.—Apparatus for the preparation of metallic chromium by igniting chromic chloride and sodium in a stream of hydrogen.

porcelain boats. The tube containing these boats is only heated when it is quite full of dry hydrogen. The crystals of metallic chromium obtained in the tube are grey cubes having a considerable hardness and withstanding the action of powerful acids, and even of aqua regia. But the statements of other investigators do not entirely agree with these facts. The chromium obtained by Wöhler by the action of a galvanic current is, on the contrary, acted on under these circumstances. The reason of this difference must be looked for in the presence of impurities, and in the crystalline structure. The chromium obtained by Wöhler had a specific gravity 6.81. Other investigators give different figures.

The two analogues of chromium, *molybdenum* and *tungsten* (or wolfram), are of still rarer occurrence in nature, and form acid oxides RO_3 , which are still less energetic than CrO_3 . Tungsten occurs in the rather rare minerals, *scheelite*, CaWO_4 , and *wolfram*; the latter being an isomorphous mixture of the normal tungstates of iron and manganese, $(\text{MnFe})\text{WO}_4$. Molybdenum is most frequently met with as *molybdenite*, MoS_2 , which presents a certain resemblance to graphite in its physical properties and softness. It also occurs, but much more rarely, as a yellow lead ore, PbMoO_4 . In both these forms molybdenum occurs in the primary rocks, in granites, gneiss, &c., and in iron and copper ores in Saxony, Sweden, and Finland. Tungsten ores are some

times met with in considerable masses in the primary rocks of Bohemia and Saxony, and also in England, America, and the Urals. The preliminary treatment of the ore is very simple; for example, the sulphide, MoS_2 , is roasted, and thus converted into sulphurous anhydride and molybdic anhydride, MoO_3 , which is then dissolved in alkalis, generally in ammonia. The ammonium molybdate is then treated with acids, when the sparingly soluble molybdic acid is precipitated. Wolfram is treated in a different manner. Most frequently the finely-ground ore is repeatedly boiled with hydrochloric and nitric acids, and the resultant solutions (of salts of manganese and iron) poured off, until the dark brown mass of ore disappears, whilst the tungstic acid remains, mixed with silica, as an insoluble residue; it is treated also with ammonia, and is thus converted into soluble ammonium tungstate, which passes into solution and yields tungstic acid when treated with acids. This hydrate is then ignited, and leaves tungstic anhydride. The general character of molybdic and tungstic anhydrides is analogous to that of chromic anhydride; they are anhydrides of a feebly acid character, which easily give polyacid salts.⁸

⁸ The atomic composition of the tungsten and molybdenum compounds is taken as being identical with that of the compounds of sulphur and chromium, because (1) both these metals give two oxides in which the amounts of oxygen per given amount of metal stand in the ratio 2 : 3; (2) the higher oxide is of the latter kind, and, like chromic and sulphuric anhydrides, it has an acid character; (3) certain of the molybdates are isomorphous with the sulphates; (4) the specific heat of tungsten is 0.0334, consequently the product of the atomic weight and specific heat is 6.15, like that of the other elements—it is the same with molybdenum, $96.0 \times 0.0722 = 6.9$; (5) tungsten with chlorine forms not only compounds WCl_6 , WCl_5 and WOCl_4 , but also WO_2Cl_2 , the analogue of chromyl chloride, CrO_2Cl_2 , and sulphuryl chloride, SO_2Cl_2 , a volatile substance. Molybdenum gives the chlorine compounds, MoCl_2 , $\text{MoCl}_3(?)$, MoCl_4 (fuses at 194° , boils at 268° ; according to Debray it contains MoCl_3), MoOCl_4 , MoO_2Cl_2 , and $\text{MoO}_2(\text{OH})\text{Cl}$. The existence of tungsten hexachloride, WCl_6 , is an excellent proof of the fact that the type SX_6 appears in the analogues of sulphur as in SO_3 ; (6) the vapour density accurately determined for the chlorine compounds MoCl_4 , WCl_6 , WCl_5 , WOCl_4 (Roscoe) leaves no doubt as to the molecular composition of the compounds of tungsten and molybdenum, because the observed and calculated results entirely agree.

Tungsten is sometimes called scheele in honour of Scheele, who discovered it in 1781 and molybdenum in 1778. Tungsten is also known as wolfram; the former name was the name given to it by Scheele, because he extracted it from the mineral then known as tungsten and now called scheelite, CaWO_4 . The researches of Roscoe, Blomstrand, and others have subsequently thrown considerable light on the whole history of the compounds of molybdenum and tungsten.

The ammonium salts of tungstic and molybdic acids when ignited leave the anhydrides, which resemble each other in many respects. *Tungstic anhydride*, WO_3 , is a yellowish substance, which only fuses at a strong heat, and has a sp. gr. of 6.2. It is insoluble in both water and acid, but solutions of the alkalis, and even of the alkali carbonates, dissolve it, especially when heated, forming alkali salts. *Molybdic anhydride*, MoO_3 , is obtained by igniting the acid (hydrate) or the ammonium salt, and forms a white mass which fuses at a red heat, and solidifies to a yellow crystalline mass of sp. gr. 3.5; whilst on further heating in open vessels or in a stream of air this anhydride

Hydrogen reduces molybdic and tungstic anhydrides at a red heat ; and this forms the means of obtaining metallic molybdenum and

sublimes in pearly scales—this enables it to be obtained in a pretty pure state. Water dissolves it in small quantities—namely, 1 part requires 600 parts of water for its solution. The hydrates of molybdic anhydride are *soluble also in acids* (a hydrate, H_2MoO_4 , is obtained from the nitric acid solution of the ammonium salt), which forms one of their distinctions from the tungstic acids. But after ignition molybdic anhydride is insoluble in acids, like tungstic anhydride; alkalis dissolve this anhydride, easily forming molybdates. Potassium bitartrate dissolves the anhydride with the aid of heat. None of the acids yet considered by us form so many different salts with one and the same base (alkali) as molybdic and tungstic acids. The composition of these salts, and their properties also, vary considerably. The most important discovery in this respect was made by Marguerite and Laurent, who showed that the salts, which contain a large proportion of tungstic acid, are easily soluble in water, and ascribed this property to the fact that tungstic acid may be obtained in *several states*. The common tungstates, obtained with an excess of alkali, have an alkaline reaction, and on the addition of sulphuric or hydrochloric acid first deposit an acid salt and then a hydrate of tungstic acid, which is insoluble in both water and acids; but if instead of sulphuric or hydrochloric acids, we add acetic or phosphoric acid, or if the tungstate be saturated with a fresh quantity of tungstic acid, which may be done by boiling the solution of the alkali salt with the precipitated tungstic acid, then a solution is obtained which, on the addition of sulphuric or a like acid, does not give a precipitate of tungstic acid at the ordinary or a higher temperature. The solution then contains particular salts of tungstic acid, and if there is an excess of acid it also contains tungstic acid itself; Laurent, Riche, and others called it *metatungstic acid*, and it is still known by this name. Those salts which with acids immediately give the insoluble tungstic acid have the composition R_2WO_4 , RHWO_4 , whilst those which give the soluble metatungstic acid contain a far greater proportion of the acid elements. Scheibler obtained the (soluble) metatungstic acid itself by treating the soluble barium (meta) tetratungstate, BaO_4WO_5 , with sulphuric acid. Subsequent research showed the existence of a similar phenomenon for molybdic acid. There is no doubt that this is a case of colloidal modifications.

Many chemists have occupied themselves with the investigation of the various salts formed by molybdic and tungstic acids. The tungstates have been investigated by Marguerite, Laurent, Marignac, Riche, Scheibler, Anthon, and others. The molybdates were partially studied by the same chemists, but chiefly by Struve and Svanberg, Delafontaine, and others. It appears that for a given amount of base the salts contain one to eight equivalents of molybdic or tungstic anhydride; *i.e.*, if the base have the composition RO, then the highest proportion of base will be held by the salts of the composition ROWO_5 or ROMoO_5 —that is, in those salts which correspond with the normal acids H_2WO_4 and H_2MoO_4 , of the same nature as sulphuric acid; but there also exist salts of the composition RO_2WO_5 , RO_3WO_5 . . . RO_8WO_5 . The water contained in the composition of many of the acid salts is often not taken into account in the above. The properties of the salts holding different proportions of acid vary considerably, but one salt may be converted into another by the addition of acid or base with great facility, and the greater the proportion of the elements of the acid in a salt, the more stable, within a certain limit, is its solution and the salt itself.

The most common ammonium molybdate has the composition $(\text{NH}_4\text{HO})_6\text{H}_2\text{O}_7\text{MoO}_5$ (or, according to Marignac and others, NH_4HMoO_4). It is prepared by evaporating an ammoniacal solution of molybdic acid. It is used in the laboratory for precipitating phosphoric acid. It is purified for this purpose by mixing its solution with a small quantity of magnesium nitrate, in order to precipitate any phosphoric acid present, filtering, and then adding nitric acid and evaporating to dryness. A pure ammonium molybdate free from phosphoric acid may then be extracted from the residue.

Phosphoric acid forms insoluble compounds with the oxides of uranium and iron, tin,

tungsten. *Both metals* are infusible. Molybdenum forms a grey powder, which scarcely aggregates under a most powerful heat, and has

bismuth, &c., having feeble basic and even acid properties. This perhaps depends on the fact that the atoms of hydrogen in phosphoric acid are of a very different character, as we saw above. Those atoms of hydrogen which are difficultly replaced by ammonium, sodium, &c., are probably easily replaced by feebly energetic acid groups—that is, the formation of particular complex substances may be expected to take place at the expense of these atoms of the hydrogen of phosphoric acid and of certain feeble metallic acids; and these substances will still be acids, because the hydrogen of the phosphoric acids and metallic acids, which is easily replaced by metals, is not removed by their mutual combination, but remains in the resultant compound. Such a conclusion is verified in the *phosphomolybdic acids* obtained (1888) by Debray. If a solution of ammonium molybdate be acidified, and a small amount of a solution (it may be acid) containing orthophosphoric acid or its salts be added to it (so that there are at least 40 parts of molybdic acid present to 1 part of phosphoric acid), then after a period of twenty-four hours the whole of the phosphoric acid is separated as a yellow precipitate, containing, however, not more than 3 to 4 p.c. of phosphoric anhydride, about 3 p.c. of ammonia, about 90 p.c. of molybdic anhydride, and about 4 p.c. of water. The formation of this precipitate is so distinct and so complete that this method is employed for the discovery and separation of the smallest quantities of phosphoric acid. Phosphoric acid was found to be present in the majority of rocks by this means. The precipitate is soluble in ammonia and its salts, in alkalis and phosphates, but is perfectly insoluble in nitric, sulphuric, and hydrochloric acids in the presence of ammonium molybdate. The composition of the precipitate appears to vary under the conditions of its precipitation, but its nature became clear when the acid corresponding with it was obtained. If the above-described yellow precipitate be boiled in aqua regia, then the ammonia is destroyed, and an acid is obtained in solution, which, when evaporated in the air, crystallises out in yellow oblique prisms of approximately the composition $P_2O_5, 20MoO_3, 26H_2O$. Such an unusual proportion of component parts is explained by the above-mentioned considerations. In reality, molybdic acid easily gives salts $R_nOnMoO_3mH_2O$, which we may imagine to correspond to a hydrate $MoO_2(HO)_2nMoO_3mH_2O$. And suppose that such a hydrate reacts on orthophosphoric acid, forming water and compounds of the composition $MoO_2(HPO_4)_nMoO_3mH_2O$ or $MoO_5(H_2PO_4)_2nMoO_3mH_2O$; this is actually the composition of phosphomolybdic acid. Probably it contains a portion of the hydrogen replaceable by metals of both the acids H_3PO_4 and of H_2MoO_4 . The above-cited crystalline acid is probably $H_5MoPO_7, 9MoO_3, 12H_2O$. This acid is really tribasic, because its aqueous solution precipitates salts of potassium, ammonium, rubidium (but not lithium and sodium) *from acid solutions*, and gives a *yellow* precipitate of the composition $R_3MoPO_7, 9MoO_3, 3H_2O$, where $R = NH_4$. Besides these, salts of another composition may be obtained, as would be expected from the preceding. These salts are only stable in acid solutions (which is naturally due to their containing an excess of acid oxides), whilst under the action of alkalis they give *colourless* phosphomolybdates of the composition $R_5MoPO_7, MoO_3, 3H_2O$. The corresponding salts of potassium, silver, ammonium, are easily soluble in water and crystalline.

For tungstic acid there are known: (1) Normal salts—for example, K_2WO_4 ; (2) the so-called acid salts have a composition like $3K_2O, 7WO_3, 6H_2O$ or $K_6H_8(WO_4)_7, 2H_2O$; (3) the tritungstates like $Na_2O, 3WO_3, 3H_2O = Na_2H_4(WO_4)_3, H_2O$. All these three classes of salts are soluble in water, but are precipitated by barium chloride, and with acids in solution give an insoluble hydrate of tungstic acid; whilst those salts which are enumerated below do not give a precipitate either with acids or the salts of the heavy metals, because they form soluble salts with even barium and lead. They are generally called metatungstates. They all contain water and a larger proportion of acid elements than the preceding salts; (4) the tetratungstates, like $Na_2O, 4WO_3, 10H_2O$ and $BaO, 4WO_3, 9H_2O$, for example; (5) the octatungstates—for example, $Na_2O, 8WO_3, 24H_2O$. As the metatung-

a specific gravity of 8.6. It is not acted on by the air at the ordinary temperature, but when ignited it is first converted into a brown, and

states, at 100° , lose so much water that they leave salts whose composition corresponds with an acid, $3\text{H}_2\text{O}, 4\text{WO}_3$ —that is, $\text{H}_6\text{W}_4\text{O}_{15}$ —it is supposed, although without much ground, that these salts contain a particular soluble metatungstic acid of the composition $\text{H}_6\text{W}_4\text{O}_{15}$. This would be likely if there were actually known to exist salts $3\text{R}_2\text{O}, 4\text{WO}_3$, $\text{R}_6\text{W}_4\text{O}_{15}$, giving a soluble tungstic acid, but even those in which the ratio is $2\text{Na}_2\text{O} : 4\text{WO}_3$ already give an insoluble tungstic acid, and a small quantity of alkali converts the meta-salts into the ordinary salts.

As an example we will proceed to give a short description of the sodium salts. The normal salt, Na_2WO_4 , is obtained by heating a strong solution of sodium carbonate with tungstic acid to a temperature of 80° ; if the solution be filtered hot, it crystallises in rhombic tabular crystals, having the composition $\text{Na}_2\text{WO}_4, 2\text{H}_2\text{O}$, which remain unchanged in the air and are easily soluble in water. When this salt is fused with a fresh quantity of tungstic acid, it gives a ditungstate, which is soluble in water and separates from its solution in crystals containing water. The same salt is obtained by carefully adding hydrochloric acid to the solution of the normal salt so long as a precipitate does not appear, and the liquid still has an alkaline reaction. This salt was first supposed to have the composition $\text{Na}_2\text{W}_2\text{O}_{11}, 4\text{H}_2\text{O}$, but it has since been found to contain (at 100°) $\text{Na}_6\text{W}_7\text{O}_{24}, 16\text{H}_2\text{O}$ —that is, it corresponds with the like salt of molybdic acid.

(If this salt be heated to a red heat in a stream of hydrogen, it loses a portion of its oxygen, acquires a metallic lustre, and turns a golden yellow colour, and, after being treated with water, alkali, and acid, leaves golden yellow leaflets and cubes which are very like gold. This very remarkable substance, discovered by Wöhler, has, according to Malaguti's analysis, the composition $\text{Na}_2\text{W}_5\text{O}_9$; that is, it, as it were, contains a double tungstate of tungsten oxide, WO_2 , and of sodium, $\text{Na}_2\text{WO}_4, \text{WO}_2\text{WO}_5$. The decomposition of the fused sodium salt is best effected by finely-divided tin. This substance has a sp. gr. 6.6; it conducts electricity like metals, and like them has a metallic lustre. When brought into contact with zinc and sulphuric acid it disengages hydrogen, and it becomes coated with a coating of copper in a solution of copper sulphate in the presence of zinc—that is, notwithstanding its complex composition, it presents to a certain extent the appearance and reactions of the metals. It is not acted on by aqua regia or alkaline solutions, but it is oxidised when ignited in air.)

The ditungstate mentioned above, deprived of water (having undergone a modification similar to that given by metaphosphoric acid), after being treated with water, leaves an anhydrous, sparingly soluble tetratungstate, $\text{Na}_2\text{WO}_4, 3\text{WO}_3$, which, when heated at 120° in a closed tube with water, passes into an easily soluble metatungstate. This clearly shows that the metatungstates are hydrated compounds. On boiling a solution of the above-mentioned salts of sodium with the yellow hydrate of tungstic acid they give a solution of metatungstate, which is the hydrated tetratungstate. Its crystals contain $\text{Na}_2\text{W}_4\text{O}_{15}, 10\text{H}_2\text{O}$. After the hydrate of tungstic acid (obtained from the ordinary tungstates by precipitation with an acid) has stood a long time in contact with a solution (hot or cold) of sodium tungstate (the yellow precipitate of the hydrate passes into a white sodium salt), it gives a solution which is not precipitated by hydrochloric acid; this must be filtered and evaporated over sulphuric acid in a desiccator (it is decomposed by boiling). It first forms a very dense solution (aluminium floats in it) of sp. gr. 3.0, and octahedral crystals of sodium metatungstate, $\text{Na}_2\text{W}_4\text{O}_{15}, 10\text{H}_2\text{O}$, sp. gr. 3.85, then separate. It effloresces and loses water, and at 100° only two out of the ten equivalents of water remain, but the properties of the salt remain unaltered. If the salt be deprived of water by further heating, it becomes insoluble. At the ordinary temperature one part of water dissolves ten parts of the metatungstate. The other metatungstates are easily obtained from this salt. Thus a strong and hot solution, mixed with a like solution of barium chloride, on cooling gives crystals of barium metatungstate, $\text{BaW}_4\text{O}_{15}, 9\text{H}_2\text{O}$. These crystals are dissolved without change in water containing hydrochloric acid, also in hot water, but they are

then into a blue oxide, and lastly into molybdic anhydride. Acids do not act on it—that is, it does not disengage hydrogen with them, not

partially decomposed by cold water, with the formation of a solution of metatungstic acid and of the normal barium salt, BaWO_4 .

In order to explain the difference in the properties of the salts of tungstic acid, we may add that a mixture of a solution of tungstic acid with a solution of silicic acid does not coagulate when heated, although the silicic acid alone would do so; this is due to the formation of a silicotungstic acid, discovered by Marignac. A solution of a tungstate dissolves gelatinous silica, just as it does gelatinous tungstic acid, and when evaporated deposits a crystalline salt of silicotungstic acid. This solution is not precipitated by either acids (a clear analogy to the metatungstates) or sulphuretted hydrogen, and corresponds with a series of salts. These salts contain an equivalent of silica and 8 equivalents of hydrogen or metals, in the same form as in salts, to 12 or 10 equivalents of tungstic anhydride; for example, the crystalline potassium salt has the composition $\text{K}_8\text{W}_{12}\text{SiO}_{42}, 14\text{H}_2\text{O} = 4\text{K}_2\text{O}, 12\text{WO}_3, \text{SiO}_2, 14\text{H}_2\text{O}$. Acid salts are also known in which half of the metal is replaced by hydrogen. Gibbs studied many of these complex inorganic acids containing tungstic (molybdic and phosphoric) acid. Their complexity (for example, of the phosphomolybdic acid) involuntarily leads to the idea of polymerisation, which we were obliged to recognise for silica, lead oxide, and other compounds. This polymerisation, it seems to me, may be understood thus: a hydrate A (for example, tungstic acid) is capable of combining with a hydrate B (for example, silica or phosphoric acid, with or without the disengagement of water), and by reason of this faculty it is capable of polymerisation—that is, A combines with A—combines with itself—just as aldehyde, $\text{C}_2\text{H}_4\text{O}$, or the cyanogen compounds are able to combine with hydrogen, oxygen, &c., and are liable to polymerisation. In this sense the molecule of tungstic acid is probably much more complex than we represent it; this agrees with the easy volatility of such compounds as the chloranhydrides, CrO_2Cl_2 , MoO_2Cl_2 , the analogues of the volatile sulphuryl chloride, SO_2Cl_2 , and with the non-volatility, or difficult volatility, of chromic and molybdic anhydrides, the analogues of the volatile sulphuric anhydride. Such a view also finds a certain confirmation in the researches made by Graham on the *colloidal* state of tungstic acid, because colloidal properties only appertain to compounds of a very complex composition. The observations made by Graham on the colloidal state of tungstic and molybdic acids introduced much new matter into the history of these substances. When sodium tungstate, mixed in a dilute solution with an equivalent quantity of dilute hydrochloric acid, is put in a dialyser, hydrochloric acid and sodium chloride pass through the membrane, and a solution of tungstic acid remains in the dialyser. Out of 100 parts of tungstic acid about 80 parts remain in the dialyser. The solution has a bitter, astringent taste, and does not yield gelatinous tungstic acid (hydrogel) either when heated or on the addition of acids or salts. It may also be evaporated to dryness; it then forms a vitreous mass of the *hydrosol of tungstic acid*, which adheres strongly to the walls of the vessel in which it has been evaporated, and is perfectly soluble in water. It does not even lose its solubility after having been heated to 200° , and only becomes insoluble when heated to a red heat, when it loses about $2\frac{1}{2}$ p.c. of water. The dry acid, dissolved in a small quantity of water, forms a gluey mass, just like gum arabic, which is one of the representatives of the hydrosols of colloidal substances. The solution, containing 5 p.c. of the anhydride, has a sp. gr. of 1.047; with 20 p.c., of 1.217; with 50 p.c., of 1.80; and with 80 p.c., of 3.24. A similar stable solution of molybdic acid is obtained by the dialysis of a mixture of a strong solution of sodium molybdate with hydrochloric acid (the precipitate which is formed is re-dissolved). The addition of alkali to the solutions of the hydrosols of tungstic and molybdic acids immediately results in the re-formation of the ordinary tungstates and molybdates. There appears to be no doubt but that the same transformation is accomplished in the passage of the ordinary tungstates into the metatungstates as takes place in the passage of tungstic acid itself from an insoluble into a

even with hydrochloric acid—but strong sulphuric acid disengages sulphurous anhydride, forming a brown mass, containing a lower oxide of molybdenum. Alkalis in solution do not act on molybdenum, but when fused with it hydrogen is given off, which shows, as does its whole character, the acid properties of the metal. The properties of tungsten are almost identical; it is infusible, has an iron grey colour, is exceedingly hard, so that it even scratches glass. Its sp. gr. is 19.1 (according to Roscoe), so that, like uranium, platinum, &c., it is one of the heaviest metals.⁹

Uranium, $U=240$, has the highest atomic weight of all the analogues of chromium, and indeed of all the elements yet known. Its highest salt-forming oxide, UO_3 , shows very feeble acid properties. Although with alkalis it gives sparingly-soluble yellow compounds, which fully correspond with the dichromates—for example, $Na_2U_2O_7 = Na_2O, 2UO_3$,¹⁰—yet it more frequently and easily reacts with acids HX ,

soluble state; but this may be even actually proved to be the case, because Scheibler obtained a solution of tungstic acid, before Graham, by decomposing barium metatungstate with sulphuric acid. By treating this salt with sulphuric acid in the amount required for the precipitation of the baryta, Scheibler obtained a solution of metatungstic acid which, when containing 48.75 p.c. of acid, had a sp. gr. of 1.684, and with 27.61 p.c. a sp. gr. of 1.327—that is, specific gravities corresponding with those found by Graham.

The questions in conjunction with the metamorphosis or modifications of tungstic and molybdic acids, and the polymerisation and colloidal state of substances, belongs to that class of alternatives the solution of which will do much towards attaining a true comprehension of the mechanism of a number of chemical reactions. I think, moreover, that questions of this kind stand in intimate connection with the theory of the formation of solutions and alloys and other so-called indefinite compounds.

⁹ We may conclude our description of tungsten and molybdenum by stating that their sulphur compounds have an acid character, like carbon bisulphide or stannic sulphide. If sulphuretted hydrogen be passed through a solution of a molybdate it does not give a precipitate unless sulphuric acid be present, when a dark brown precipitate of *molybdenum trisulphide*, MoS_3 , is formed. When this sulphide is ignited without access of air it gives the bisulphide MoS_2 , which is not able to combine with potassium sulphide like the trisulphide MoS_3 , which forms a salt, K_2MoS_4 , corresponding with K_2MoO_4 . This is soluble in water, and separates out from its solution in red crystals, which have a metallic lustre and reflect a green light. It is easily obtained by heating the native bisulphide, MoS_2 , with potash, sulphur, and a small amount of charcoal, which serves for deoxidising the oxygen compounds. Tungsten gives similar compounds, R_2WS_3 , where $R=NH_4, K, Na$. They are decomposed by acids, with the separation of tungsten trisulphide, WS_3 , and molybdenum trisulphide, MoS_3 .

¹⁰ Uranium trioxide, or uranic oxide, shows its feeble basic and acid properties in a great number of its relations. (1) Solutions of uranic salts give yellow precipitates with alkalis, but these precipitates do not contain the hydrate of the oxide, but compounds of it with bases; for example, $2UO_2(NO_3)_2 + 6KHO = 4KNO_3 + 3H_2O + K_2U_2O_7$. There are other *urano-alkali compounds* of the same constitution; for example, $(NH_4)_2U_2O_7$ (known in trade as uranic oxide), MgU_2O_7 , BaU_2O_7 . They are the analogues of the dichromates. Sodium uranate is the most generally used under the name of uranium yellow, $Na_2U_2O_7$. It is used for imparting the characteristic yellow-green tint to glass and porcelain. Neither heat nor water nor acids are able to extract the alkali from

forming fluorescent yellowish green salts of the composition UO_2X_2 , and in this respect uranic trioxide, UO_3 , differs from chromic anhydride, CrO_3 , although the latter is able to give the oxychloride, CrO_2Cl_2 . In molybdenum and tungsten, however, we see a clear transition from chromium to uranium. Thus, for example, chromyl chloride, CrO_2Cl_2 , is a brown liquid which volatilises without change, and is completely decomposed by water; molybdenum oxychloride, MoO_2Cl_2 , is a crystalline substance of a yellow colour, which is volatile and soluble in water (Blomstrand), like many salts. Tungsten oxychloride, WO_2Cl_2 , stands still nearer to uranyl chloride in its properties; it forms yellow scales on which water and alkalis act, as they do on many salts

sodium uranate, $\text{Na}_2\text{U}_2\text{O}_7$, and therefore it is a true insoluble salt, of a yellow colour, and clearly indicates the acid character (although feeble) of uranic oxide. (2) The carbonates of the alkaline earths (for instance, barium carbonate) precipitate uranic oxide from its salts, as they do all the salts of feeble bases; for example, R_2O_3 . (3) The *alkali carbonates*, when added to solutions of uranic salts, give a *precipitate, which is soluble in an excess of the reagent*, and particularly so if the acid carbonates be taken. This is due to the fact that (4) the uranyl salts *easily form double salts* with the salts of the alkali metals, including the salts of ammonium. Uranium, in the form of these double salts, often gives salts of well-defined crystalline form, although the simple salts are little prone to appear in crystals. Such are, for example, the salts obtained by dissolving potassium uranate, $\text{K}_2\text{U}_2\text{O}_7$, in acids, with the addition of potassium salts of the same acids. Thus, with hydrochloric acid and potassium chloride a well-formed crystalline salt, $\text{K}_2(\text{UO}_2)\text{Cl}_4 \cdot 2\text{H}_2\text{O}$, belonging to the monoclinic system, is produced. This salt decomposes in dissolving in pure water. Among these double salts we may mention the double carbonate with the alkalis, $\text{R}_4(\text{UO}_2)(\text{CO}_3)_5$ (they are equal to $2\text{R}_2\text{CO}_3 + \text{UO}_2\text{CO}_3$); the acetates, $\text{R}(\text{UO}_2)(\text{C}_2\text{H}_5\text{O}_2)_3$ —for instance, the sodium salt, $\text{Na}(\text{UO}_2)(\text{C}_2\text{H}_5\text{O}_2)_3$, and the potassium salt, $\text{K}(\text{UO}_2)(\text{C}_2\text{H}_5\text{O}_2)_3 \cdot \text{H}_2\text{O}$; the sulphates, $\text{R}_2(\text{UO}_2)(\text{SO}_4)_3 \cdot 2\text{H}_2\text{O}$, &c. In the preceding formula $\text{R}=\text{K}$, Na , NH_4 , or $\text{R}_2=\text{Mg}$, Ba , &c. *This property of giving comparatively stable double salts indicates feebly developed basic properties*, because double salts are mainly formed by salts of distinctly basic metals (this forms, as it were, the basic element of a double salt) and salts of feebly energetic bases (this forms the acid element of a double salt), just as the former also give acid salts; the acid of the acid salts is replaced in the double salts by the salt of the feebly energetic base, which, like water, belongs to the number of intermediate bases. For this reason barium does not give double salts with alkalis as magnesium does, and this is why double salts are more easily formed by potassium than by lithium among the series of the alkali metals. (5) The most remarkable property, proving the feeble energy of uranic oxide as a base, is seen in the fact that when compared with the composition of other salts the salts of uranic oxide *always appear as basic salts*. We already know that a normal salt, R_2X_6 , corresponds with the oxide R_2O_3 , where $\text{X}=\text{Cl}$, NO_3 , &c., or $\text{X}_2=\text{SO}_4$, CO_3 , &c.; but there also exist basic salts of the same type where $\text{X}=\text{HO}$ or $\text{X}_2=\text{O}$. We saw salts of all kinds among the salts of aluminium, chromium, and others. With uranic oxide no salts are known of the types UX_6 (UCl_6 , $\text{U}(\text{SO}_4)_3$, alums, &c., are not known), nor even salts, $\text{U}(\text{HO})_2\text{X}_4$ or UOX_4 , but it always forms salts after the type $\text{U}(\text{HO})_4\text{X}_2$ or UO_2X_2 . Judging from the fact that nearly all the salts of uranic oxide retain water in crystallising from their solutions, and that this water is difficult to separate from them, it may be thought to be water of hydration. This is seen in part from the fact that the composition of many of the salts of uranic oxide may then be expressed without the presence of water of crystallisation; for instance, $\text{U}(\text{HO})_4\text{K}_2\text{Cl}_4$ (and the salt of NH_4), $\text{U}(\text{HO})_4\text{K}_2(\text{SO}_4)_2$, $\text{U}(\text{HO})_4(\text{C}_2\text{H}_5\text{O}_2)_2$. Sodium uranyl acetate, however, does not contain water.

(zinc chloride, ferric chloride, aluminium chloride, stannic chloride, &c.), and perfectly corresponds with the difficultly-volatile salt, UO_2Cl_2 (obtained by Peligot by the action of chlorine on ignited uranium dioxide, UO_2), which is also yellow and gives a yellow solution with water, like all the salts UO_2X_2 . The property of uranic oxide, UO_2 , of forming salts UO_2X_2 is shown in the fact that the hydrated oxide of uranium, $\text{UO}_2(\text{HO})_2$, which is obtained from the nitrate, carbonate, and other salts by the loss of the elements of the acid, is easily soluble in acids, as well as in the fact that the lower grades of oxidation of uranium are able, when treated with nitric acid, to form an easily crystallisable uranyl nitrate, $\text{UO}_2(\text{NO}_3)_2 \cdot 6\text{H}_2\text{O}$; this is the most commonly occurring uranium salt.¹¹

¹¹ *Uranyl nitrate*, or uranium nitrate, $\text{UO}_2(\text{NO}_3)_2 \cdot 6\text{H}_2\text{O}$, crystallises from its solutions in transparent yellowish-green prisms (from an acid solution), or in tabular crystals (from a neutral solution), which effloresce in the air and are easily soluble in water, alcohol, and ether, have a sp. gr. of 2.8, and fuse when heated, losing nitric acid and water in the process. If the salt itself (Berzelius) or its alcoholic solution (Malaguti) be heated up to the temperature at which oxides of nitrogen are evolved, then there remains a mass which, after being evaporated with water, leaves uranyl hydroxide, $\text{UO}_2(\text{HO})_2$ (sp. gr. 5.93), whilst if the salt be ignited there remains the dioxide, UO_2 , as a brick-red powder, which on further heating loses oxygen and forms the dark olive uranoso-uranic oxide, U_5O_8 . Therefore the solution of the nitrate obtained from the ore is purified in the following manner: sulphurous anhydride is first passed through it in order to reduce the arsenic acid present into arsenious acid; the solution is then heated to 60° , and sulphuretted hydrogen passed through it; this precipitates the lead, arsenic, and tin, and certain other metals, as sulphides, insoluble in water and dilute nitric acid. This liquid is then filtered and evaporated with nitric acid to crystallisation, and the crystals are dissolved in ether. Or else the solution is first treated with chlorine in order to convert the ferrous chloride (produced by the action of the hydrogen sulphide) into ferric chloride, then the oxides are precipitated by ammonia and the resultant precipitate, containing the oxides Fe_2O_3 , UO_3 , and compounds of the latter with potash, lime, ammonia, and other bases present in the solution (the latter is due to the property of uranic oxide of combining with bases), is washed and dissolved in a strong, slightly-heated solution of ammonium carbonate, which dissolves the uranic oxide but not the ferric oxide. The solution is filtered, and on cooling deposits a finely crystallising *uranyl ammonium carbonate*, $\text{UO}_2(\text{NH}_4)_4(\text{CO}_3)_3$, in brilliant monoclinic crystals which on exposure to air slowly give off water, carbonic anhydride, and ammonia; the same decomposition is readily effected at 300° , the residue then consisting of uranic oxide. This salt is not very soluble in water, but is readily so in ammonium carbonate; it is obvious that it may readily be converted into all the other salts of oxides of uranium. Uranium salts are also purified in the form of *acetate*, which is very sparingly soluble, and is therefore directly precipitated from a strong solution of the nitrate by mixing it with acetic acid.

We may also mention the *uranyl phosphate*, HUPO_6 , which must be regarded as an orthophosphate in which two hydrogens are replaced by the uranyl UO_2 —i.e. as $\text{H}_2\text{UO}_3\text{PO}_4$. This salt is formed as a hydrated gelatinous yellow precipitate, on mixing a solution of uranyl nitrate with disodium phosphate. The precipitation occurs in the presence of acetic acid, but not in the presence of hydrochloric acid. If, moreover, there be present an excess of an ammonium salt, the ammonia enters into the composition of the bright yellow gelatinous precipitate formed, in the proportion $\text{UO}_2\text{NH}_4\text{PO}_4$ (with water). This precipitate is not soluble in water and acetic acid, and its solution in inorganic acids when boiled entirely expels all the phosphoric acid. This fact is taken

Uranium, which gives an oxide, UO_3 , and the corresponding salt UO_2X_2 and dioxide UO_2 , to which the salts UX_4 correspond, is rarely met with in nature. Uranite or the double orthophosphate of uranic oxide, $\text{R}(\text{UO}_2)\text{H}_2\text{P}_2\text{O}_8 \cdot 7\text{H}_2\text{O}$, where $\text{R} = \text{Cu}$ or Ca , uranium-vitriol $\text{U}(\text{SO}_4)_2 \cdot \text{H}_2\text{O}$, samarakite, and æschynite, are very rarely found, and then only in small quantities. Of more frequent and abundant occurrence is the non-crystalline, earthy brown uranium ore known as *pitchblende* (sp. gr. 7.2), which is mainly composed of the intermediate oxide $\text{U}_3\text{O}_8 = \text{UO}_2 \cdot 2\text{UO}_3$. This ore is found at Joachimsthal in Bohemia in the Erzgebirge, from which the greater part of the uranium used is exported. This ore contains a number of different impurities, chiefly sulphides and arsenides of lead and iron, as well as lime and silica compounds. It is roasted in order to expel the arsenic and sulphur; ground, washed with dilute hydrochloric acid, which does not dissolve the uranoso-uranic oxide, U_3O_8 , and the residue is dissolved in nitric acid, which transforms the uranium oxide into the nitrate, $\text{UO}_2(\text{NO}_3)_2$.

It must be observed that the oxide of uranium, first distinguished by Klaproth (1789), was for a long time regarded as able to give metallic uranium under the action of charcoal and other reducing agents (with the aid of heat). But the substance thus obtained was only the *uranium dioxide*, UO_2 . The compound nature of this dioxide,¹² or the presence of oxygen in it, was demonstrated by Peligot (1841), by igniting it with charcoal in a stream of chlorine. He thus obtained a volatile *uranium tetrachloride*, UCl_4 ,¹³ which, when heated with sodium,

advantage of for removing phosphoric acid from solutions—for instance, from those containing salts of calcium and magnesium.

¹² Uranium dioxide, or *uranyl*, UO_2 , which is contained in the salts UO_2X_2 , has the appearance and many of the properties of a metal. Uranic oxide may be regarded as uranyl oxide, $(\text{UO}_2)\text{O}$, its salts as salts of this uranyl; its hydroxide, $(\text{UO}_2)\text{H}_2\text{O}_2$, is formed like CaH_2O_2 . The green oxide of uranium, uranoso-uranic oxide (easily formed from uranic salts by the loss of oxygen), $\text{U}_3\text{O}_8 = \text{UO}_2 \cdot 2\text{UO}_3$, when ignited with charcoal or hydrogen (dry) gives a brilliant crystalline substance of sp. gr. about 10.0, whose appearance resembles that of metals, and which decomposes steam at a red heat with the evolution of hydrogen but which, however, does not decompose hydrochloric or sulphuric acid, but is oxidised by nitric acid. The same substance is also obtained by igniting the compound $(\text{UO}_3)\text{K}_2\text{Cl}$ in a stream of hydrogen, according to the equation $\text{UO}_2\text{K}_2\text{Cl}_4 + \text{H}_2 = \text{UO}_2 + 2\text{HCl} + 2\text{KCl}$. It was at first regarded as the metal. In 1841 Peligot found that it contained oxygen because carbonic oxide and anhydride were evolved when it was ignited with charcoal in a stream of chlorine, and from 408 parts of the substance which was considered to be metal he obtained 873 parts of a volatile product containing 213 parts of chlorine. From this it was concluded that the substance taken contained an equivalent amount of oxygen. As 213 parts of chlorine correspond with 48 parts of oxygen, it followed that $408 - 48 = 360$ parts of metal were combined in the substance considered as such with 48 parts of oxygen, and also in the chlorine compound obtained with 213 parts of chlorine.

¹³ *Uranium tetrachloride*, uranous chloride, UCl_4 , corresponds with uranous oxide as a base. It was obtained by Peligot by igniting uranic oxide mixed with charcoal in a stream of dry chlorine: $\text{UO}_3 + 3\text{C} + 2\text{Cl}_2 = \text{UCl}_4 + 3\text{CO}$. This green volatile compound

gave *metallic uranium* as a grey metal, having a specific gravity of 18.7, and liberating hydrogen from acids, with the formation of green uranous salts, UX_4 , which act as powerful reducing agents.¹⁴

(Note 12) crystallises in regular octahedra, is very hygroscopic, easily soluble in water, with the development of a considerable amount of heat, and no longer separates out from its solution in an anhydrous state, but disengages hydrochloric acid when evaporated. The solution of uranous chloride in water is green. It is also formed by the action of zinc and copper (forming cuprous chloride) on a solution of uranyl chloride, UO_2Cl_2 , especially in the presence of hydrochloric acid and sal-ammoniac. Solutions of uranyl salts are converted into uranous salts by the action of various reducing agents, and among others by organic substances or by the action of light, whilst the salts UX_4 are converted into uranyl salts, UO_2X_2 , by exposure to air or by oxidising agents. Solutions of the green uranyl salts act as powerful reducing agents, and give a brown precipitate of the uranous hydroxide, UH_2O_4 , with potash and other alkalis. This hydroxide is easily soluble in acids but not in alkalis. On ignition it does not form the oxide UO_2 , because it decomposes water, but when the higher oxides of uranium are ignited in a stream of hydrogen or with charcoal they yield uranous oxide. Both it and the chloride UCl_4 dissolve in strong sulphuric acid, forming a green salt, $U(SO_4)_2 \cdot 2H_2O$. The same salt, together with uranyl sulphate, $UO_2(SO_4)$, is formed when the green oxide U_2O_3 is dissolved in hot sulphuric acid. The salts obtained in the latter instance may be separated by adding alcohol to the solution, which is left exposed to the light; the alcohol reduces the uranyl salt to uranous salt, an excess of acid being required. This salt is remarkable from the fact that an excess of water decomposes it, forming a basic salt, which is also easily produced under other circumstances, and contains $UO(SO_4) \cdot 2H_2O$ (which corresponds to the uranic salt).

¹⁴ It must be observed that the atomic weight of uranium was formerly taken as half the present one. Thus, according to Peligot, $U=120$, and the oxide U_2O_3 , suboxide UO , and green oxide U_7O_9 , were of the same types as the oxides of iron. With a certain resemblance to the elements of the iron group, uranium presents many points of distinction which do not permit its being grouped with them. Thus uranium forms a very stable oxide, U_2O_3 ($U=120$), but does not give the corresponding chloride U_2Cl_6 (Roscoe, however, in 1874 obtained UCl_5 , like $MoCl_5$ and WCl_5), and under those circumstances (the ignition of oxide of uranium mixed with charcoal, in a stream of chlorine), when the formation of this compound might be expected, it gives ($U=120$) the chloride UCl_4 , which is characterised by its volatility, which is not a property, to such an extent, of any of the dichlorides, RCl_2 , of the iron group.

The alteration or doubling of the atomic weight of uranium—*i.e.* the recognition of $U=240$ —was made for the first time in the first (Russian) edition of this work (1871), and in my memoir (of the same year in Liebig's *Annalen*), because with an atomic weight 120, uranium could not be placed in the periodic system. I think it will not be superfluous to add the following remarks on this subject: (1) In the other groups ($K-Rb-Cs$, $Ca-Sr-Ba$, $Cl-Br-I$) the acid character of the oxides decreases and their basic character increases with the rise of atomic weight, and therefore we should expect to find the same in the group $Cr-Mo-W-U$, and if CrO_3 , MoO_3 , WO_3 be the anhydrides of acids, then we indeed find a decrease in their acid character, and therefore uranium trioxide, UO_3 , should be a very feeble anhydride, but its basic properties should also be very feeble. Uranic oxide does indeed show these properties, as was pointed out above (Note 10). (2) Chromium and its analogues, besides the oxides RO_3 , also form lower grades of oxidation RO_2 , R_2O_5 , and the same is seen in uranium; it forms UO_3 , UO_2 , U_2O_5 and their compounds. (3) Molybdenum and tungsten, in being reduced from RO_3 , easily and frequently give an intermediate oxide of a blue colour, and uranium shows the same property; giving the so-called green oxide which, according to existent researches, must be regarded as $U_7O_9=UO_2 \cdot 2UO_3$, analogous to Mo_5O_8 . (4) The higher chlorides, RCl_5 , possible for the elements of this group, are either unstable (WCl_6) or do not exist at all

As the salts of uranic oxide are reduced in the absence of organic matter by the action of light, and as they impart a characteristic coloration to glass,¹⁵ they find a certain application in photography and glass work.

If we compare together the highly acid elements, sulphur, selenium, and tellurium, of the uneven series of the sixth group with chromium, molybdenum, tungsten, and uranium of the even series of the same group, we find that the resemblance of the higher form RO_3 does not extend to the lower forms, and even entirely disappears in the elements, because there is not the smallest resemblance between sulphur and chromium and their analogues in a free state. In other words, this means that the small periods, like Na, Mg, Al, Si, P, S, Cl, containing seven elements, do not contain any near analogues of chromium, molybdenum, &c., and therefore their true position among the other elements must be looked for only in those large periods which contain two small periods, and whose type is seen in the period containing :

(Cr); but there is one single lower volatile compound, which is decomposed by water, and liable to further reduction into a non-volatile chlorine product and the metal. The same is observed in uranium, which forms an easily volatile chloride, UCl_4 , decomposed by water. (5) The atomic volumes, $\text{Cr}=8$, $\text{Mo}=8\cdot6$, $\text{W}=9\cdot6$, and $\text{U}=13$, are subject to the rule observed in the other similar series, $\text{K}-\text{Rb}$, $\text{Ca}-\text{Sr}-\text{Ba}$, &c., where the atomic volume increases with the atomic weight, and therefore the high sp. gr. of uranium ($18\cdot4$) is explained by this fact. (6) For uranium, as for chromium and tungsten, yellow tints predominate in the form RO_3 , whilst the lower forms are green and blue. (7) Zimmermann (1881) determined the vapour densities of uranous bromide, UBr_4 , and chloride, UCl_4 , and they ($19\cdot4$ and $13\cdot2$) were found to correspond to the formulæ given above—that is, they confirmed the accepted atomic weight $\text{U}=240$. Roscoe, a great authority on the metals of this group, was the first to recognise the proposed atomic weight of uranium $\text{U}=240$, which since Zimmermann's work has been generally recognised.

¹⁵ Uranium glass, obtained by the addition of the yellow salt $\text{K}_2\text{U}_2\text{O}_7$ to glass, has a green-yellow fluorescence, and is sometimes employed for ornaments; it absorbs the violet rays, like the other salts of uranic oxide—that is, it possesses an absorption spectrum in which the violet rays are absent. The index of refraction of the absorbed rays is altered, and they are given out again as greenish-yellow rays; hence, compounds of uranic acid, when placed in the violet portion of the spectrum, emit a greenish-yellow light, and this forms one of the best examples (another is found in a solution of quinine sulphate) of the phenomenon of fluorescence. The rays of light which pass through uranic compounds do not contain the rays which excite the phenomena of fluorescence and of chemical transformation, as the researches of Stokes prove. In thus absorbing the chemical rays, uranic compounds aid the chemical change of substances mixed with them. Hence, uranic compounds are used in photography. Becquerel, Bolton, and Morton have made some most interesting researches on the phosphorescent spectra of the uranium compounds—that is, on the nature of the light emitted by salts of uranium immediately after their exposure to light; these researches show that the bands of light (generally seven, all between C and F of the solar spectrum), and their intersected dark bands suffer a displacement with a change of elements—for example, in the double salts of metals. Concerning the formation of the peroxide form of uranium (Fairley), see Chapter XX. Note 66.

K, Ca, Sc, Ti, V, Cr, Mn, Fe, Co, Ni, Cu, Zn, Ga, Ge, As, Se, Br. These periods contain Ca and Zn, giving RO, Sc, and Ga of the third group, Ti and Ge of the fourth and fifth groups, and As of the fifth group, Cr and Se of the sixth group, Mn and Br of the seventh group, and the remaining elements, Fe, Co, Ni, form connective members of the intermediate eighth group, to the description of the representatives of which we shall turn in the following chapters. And now we will proceed to describe *manganese*, $Mn=55$, as an element of the seventh group of the even series, directly following after $Cr=52$, and which corresponds with $Br=80$ to the same degree that Cr does with $Se=79$. For chromium, selenium, and bromine very close analogues are known, but for manganese as yet none have been obtained—that is, it is the only representative of the even series in the seventh group. In placing manganese with the halogens in one group, the periodic system of the elements only requires that it should bear an analogy to the halogens in the higher type of oxidation—*i.e.* in the salts and acids—whilst it requires that as great a difference should be expected in the lower types and elements as there exists between chromium or molybdenum and sulphur or selenium. And this is actually the case. The elements of the seventh group form a higher salt-forming oxide, R_2O_7 , and its corresponding hydrate, HRO_4 , and salts—for example, $KClO_4$. Manganese in the form of potassium permanganate, $KMnO_4$, actually presents a perfect analogy to potassium perchlorate, $KClO_4$. The analogy of the crystalline form of both salts was shown by Mitscherlich. The salts of permanganic acid are also nearly all soluble in water, like those of perchloric acid, and if the silver salt of the latter, $AgClO_4$, be sparingly soluble in water, so also is silver permanganate, $AgMnO_4$. The specific volume of potassium perchlorate is equal to 55, because its specific gravity = 2.54; the specific volume of potassium permanganate is equal to 58, because its specific gravity = 2.71. Both acids in a free state are soluble in water and volatile, both are powerful oxidisers—in a word, their analogy is still closer than that of chromic and sulphuric acids, and those points of distinction which they present also appear among the nearest analogues—for example, in sulphuric and telluric acids, in hydrochloric and hydriodic acids, &c. Besides which, manganese gives a lower grade of oxidation, MnO_3 , analogous to sulphuric and chromic trioxides, and with it corresponds potassium manganate, K_2MnO_4 , isomorphous with potassium sulphate.¹⁶ In the types of

¹⁶ The comparison of potassium permanganate with potassium perchlorate, or of potassium manganate with potassium sulphate, shows directly that many of the physical and chemical properties of substances do not depend on the nature of the elements,

oxidation of manganese lower than the permanganates there is no longer any resemblance to chlorine, whilst every point of resemblance disappears when we come to the elements themselves—*i.e.* to manganese and chlorine—for manganese is a metal, like iron, which combines directly with chlorine to form a saline compound, MnCl_2 , analogous to magnesium chloride.¹⁷

Manganese belongs to the number of metals widely distributed in nature, especially in those localities where iron occurs, whose ores frequently contain compounds of manganous oxide, MnO , which presents a resemblance to ferrous oxide, FeO , and to magnesia. In many minerals, magnesia and the oxides allied to it are replaced by manganous oxide. Calc spars and magnesites—*i.e.* $\text{R}''\text{CO}_3$ in general—are frequently met with containing manganous carbonate, which also occurs in a separate state, although but rarely. The soil and the ash of plants generally contain a small quantity of manganese. In the analysis of minerals it is generally found that manganese occurs together with magnesia, because, like it, manganous oxide remains in solution in the presence of ammoniacal salts, not being precipitated by reagents. The property of this manganous oxide, MnO , of passing into the higher grades of oxidation under the influence of heat, alkalis, and air, gives an easy means not only of discovering the presence of manganese in admixture with magnesia, but also of separating these two analogous bases. Magnesia is not able to give higher grades of oxidation, whilst manganese gives them with great facility. Thus, for instance, an *alkaline* solution of sodium hypochlorite produces a precipitate of manganese dioxide in a solution of a manganous salt: $\text{MnCl}_2 + \text{NaClO} + 2\text{NaHO} = \text{MnO}_2 + \text{H}_2\text{O} + 3\text{NaCl}$; whilst magnesia is not changed under these circumstances. If the magnesia be precipitated owing to the presence of alkali, it may be dissolved in *acetic acid*, in which manganese dioxide is insoluble. The presence of small quantities of manganese may also be recognised by the green coloration which alkalis acquire when heated with manganese compounds in the air. This green coloration depends on the property of manganese of giving a green alkaline manganate: $\text{MnCl}_2 + 4\text{KHO} + \text{O}_2 = \text{K}_2\text{MnO}_4 + 2\text{KCl} + 2\text{H}_2\text{O}$. This *faculty of oxidising in the presence of alkalis* forms an essential character of manganese. Therefore manganese often occurs in nature as the different higher oxides. However, the ores of manganese are not so

but on the atomic types in which they appear, on the kind of movements, or on the positions in which the atoms forming the molecule occur.

¹⁷ If, however, we compare the spectra (Vol. I. p. 556) of chlorine, bromine, and iodine with that of manganese one cannot but remark a certain resemblance or analogy which connects manganese both to iron and to chlorine, bromine, and iodine.

very widely distributed in nature, although the manganous compounds are met with nearly everywhere. The most important ore of manganese is its dioxide, or so-called *peroxide*, MnO_2 , which is known in mineralogy as *pyrolusite*. Then, manganese occurs as an oxide corresponding with magnetic iron ore, $\text{MnO} \cdot \text{Mn}_2\text{O}_3 = \text{Mn}_3\text{O}_4$, forming the mineral known as *hausmannite*. The oxide Mn_2O_3 also occurs in nature as the anhydrous mineral *braunite*, and in a hydrated form, $\text{Mn}_2\text{O}_3 \cdot \text{H}_2\text{O}$, called *manganite*. Both of these often occur as an admixture in *pyrolusite*. Besides which, manganese is met with in nature as *rhodonite*, or silicate, MnSiO_3 . Very fine and rich deposits of manganese ores have been found in the Caucasus, the Urals, and along the Dnieper. Those at the Sharapansky district of the Government of Kutais and at Nicopol on the Dnieper are particularly rich. A large quantity of the ore (up to 65000 tons yearly) from these localities is exported.

Manganese gives oxides of the following forms: MnO , manganous oxide, and manganous salts, MnX_2 , corresponding with the base, which resembles magnesia and ferrous oxide in many respects; Mn_2O_3 , a very feeble base, giving salts, MnX_3 , analogous to the aluminium and ferric salts; MnO_2 , dioxide, generally called peroxide, an almost indifferent oxide, although feebly acid; ¹⁸ MnO_3 , manganic anhydride, which forms salts resembling potassium sulphate; Mn_2O_7 , permanganic anhydride, giving salts analogous to the perchlorates.

All the oxides of manganese when heated with acids give salts, MnX_2 , corresponding with the lower grade of oxidation, manganous oxide, MnO . Manganic oxide, Mn_2O_3 , is a feebly energetic base; it is true that it dissolves in hydrochloric acid and gives a dark solution containing the salt MnCl_3 , but the latter when heated evolves chlorine and gives a salt corresponding with manganous oxide—i.e. at first: $\text{Mn}_2\text{O}_3 + 6\text{HCl} = 3\text{H}_2\text{O} + \text{Mn}_2\text{Cl}_6$, and then the Mn_2Cl_6 decomposes into $2\text{MnCl}_2 + \text{Cl}_2$. In this manner none of the higher grades of oxidation have a basic character, but act as oxidising agents in the presence of acids, disengaging oxygen and passing into salts of the lower grade of oxidation of manganese, MnO . Owing to this circumstance, the manganous salts are easily obtained, and they are generally left in

¹⁸ The name 'peroxide' should only be retained for those *highest* oxides (and MnO_2 stands between MnO and MnO_3) which by a direct method of double decomposition are able to either give hydrogen peroxide or contain a larger proportion of oxygen than the base or the acid (the lower oxides), just as hydrogen peroxide contains more oxygen than water. Their type will be H_2O_2 , and they are exemplified by barium peroxide, BaO_2 , and sulphur peroxide, S_2O_7 , &c. Such a dioxide as MnO_2 is, in all probability, a salt—that is, a manganous manganate, MnO_5MnO , and also, as a basic salt of a feeble base, capable of combining with alkalis and acids. Therefore the name of manganese peroxide should be abandoned, and replaced by manganese dioxide. PbO_2 is better termed lead dioxide than peroxide.

the residual solution from the application of the peroxide for the preparation of oxygen and chlorine.¹⁹

¹⁹ For the preparation of oxygen, manganese dioxide is heated with sulphuric acid: $\text{MnO}_2 + \text{H}_2\text{SO}_4 = \text{MnSO}_4 + \text{H}_2\text{O} + \text{O}$; or else the dioxide is heated alone to a high temperature, when it gives the intermediate oxide $3\text{MnO}_2 = \text{Mn}_3\text{O}_4 + \text{O}_2$; when heated with sulphuric acid this also gives manganous sulphate and oxygen. For the preparation of chlorine the dioxide is heated with hydrochloric acid, and manganous chloride, MnCl_2 , is obtained in the residue. These two manganous salts may be taken as examples of the derivative of manganous oxide, MnO . Manganous sulphate generally contains various impurities, from the majority of which it may be separated by crystallisation; but it generally contains a large amount of iron salts, from which it cannot be freed in this manner. Their removal may, however, be effected by mixing a portion of the liquid with a solution of sodium carbonate; double decomposition then ensues in this portion, and a precipitate of manganous carbonate is formed. This precipitate is collected and washed, and then added to the remaining mass of the impure solution of manganous sulphate; on heating the solution with this precipitate, the whole of the iron is precipitated as oxide. This is due to the fact that in the solution of the manganese dioxide in sulphuric acid the whole of the iron is converted into the ferric state (because the peroxide acts as an oxidising agent), which, as an exceedingly feebly energetic base precipitated by calcium carbonate and other kindred salts, is also precipitated by manganous carbonate. After being treated in this manner, the solution of manganous sulphate is obtained pure. If it be a bright red colour it is due to the presence of higher grades of oxidation of manganese; they may be destroyed by boiling the solution, when the oxygen from the oxides of manganese is evolved and the manganous salt is obtained. This salt is remarkable for the facility with which it gives various combinations with water. By evaporating the almost colourless solution of *manganous sulphate* at very low temperatures, and by cooling the saturated solution at about 0° , crystals are obtained containing 7 atoms of water of crystallisation $\text{MnSO}_4 \cdot 7\text{H}_2\text{O}$, which are isomorphous with cobaltous and ferrous sulphates. These crystals, even at 10° , lose 5 p.c. of water, and completely effloresce at 15° , losing about 20 p.c. of water. By evaporating a solution of the salt at the ordinary temperature but not above 20° , crystals are obtained containing 5 mol. H_2O , which are isomorphous with copper sulphate; whilst if the crystallisation be carried on between 20° and 30° , large transparent prismatic crystals are formed containing 4 mol. H_2O (see Nickel). A boiling solution also deposits these crystals together with crystals containing 3 mol. H_2O whilst the first salt, when fused and boiled with alcohol, gives crystals containing 2 mol. H_2O . Graham obtained a monohydrated salt by drying the salt at about 200° . The last atom of water is eliminated with difficulty, as is the case with all salts isomorphous with magnesium sulphate. The crystals containing a considerable amount of water are rose-coloured, and the anhydrous crystals are colourless. The solubility of manganous sulphate is given in Vol. I. p. 71, Note 24, whence it is seen that at the boiling-point this salt is much less soluble than at lower temperatures, and therefore a solution saturated at the ordinary temperature becomes turbid when boiled. Manganous sulphate, being analogous to magnesium sulphate, is decomposed, like the latter, when ignited, but it does not then leave manganous oxide, but the intermediate oxide, Mn_2O_3 . It gives double salts with the alkali sulphates. It is also remarkable that with aluminium sulphate it forms fine radiated crystals whose composition resembles that of the alums—namely $\text{MnAl}_2(\text{SO}_4)_4 \cdot 24\text{H}_2\text{O}$. This salt is easily soluble in water, and occurs in nature.

Manganous chloride crystallises with 4 mol. H_2O , like the ferrous salt, and not with 6 mol. H_2O like many kindred salts—for example, those of cobalt, calcium, and magnesium; 100 parts of water dissolve 38 parts of the anhydrous salt at 10° and 55 parts at 62° . Alcohol also dissolves manganous chloride, and the alcoholic solution burns with a red flame. This salt, like magnesium chloride, readily forms double salts. Potassium cyanide with manganous salts produces a yellowish-grey precipitate, MnC_2N_2 , soluble in an excess of the reagent, a double salt, $\text{K}_4\text{MnC}_6\text{N}_6$, corresponding with potassium ferro-

The fact alone that the oxides of manganese are not reduced to metal when ignited in hydrogen (whilst the oxides of iron give metallic

cyanide, being formed. On evaporation of this solution a portion of the manganese is oxidised and precipitated, whilst a salt corresponding to Gmelin's red salt, $K_5MnCl_6N_6$, remains in solution. Sulphuretted hydrogen does not precipitate the salts of manganese, not even the acetate, but ammonium sulphide gives a flesh-coloured precipitate. Oxalic acid in strong solutions of manganous salts gives a white precipitate of the oxalate, MnC_2O_4 . This precipitate is insoluble in water, and is used for the preparation of manganous oxide itself because it decomposes when ignited, with the formation of carbonic anhydride, carbonic oxide, and manganous oxide. *Manganous oxide* thus obtained is a green powder, which, however, oxidises with such facility that it burns in air when brought into contact with an incandescent substance, and passes into the red intermediate oxide Mn_2O_4 ; so that the above experiment must be carried on in a tube without access of air. In solutions of manganous salts, alkalis produce a precipitate of the hydroxide MnH_2O_2 , which rapidly absorbs oxygen in the presence of air, and gives the brown intermediate oxide, or, more correctly speaking, its hydrate.

Manganous oxide, besides being obtained by the above-described method from manganous oxalate, may also be obtained by igniting the higher oxides in a stream of hydrogen and also from manganese carbonate. The manganous oxide ignited in the presence of hydrogen acquires a great density, and is no longer so easily oxidised. It may also be obtained in a crystalline form, if during the ignition of the carbonate or higher oxide a trace of dry hydrochloric acid gas be passed into the stream of hydrogen. It is thus obtained in the form of transparent emerald green crystals of the regular system; but in this state it is easily soluble in acids.

Manganous oxides in oxidising give the *red oxide of manganese*, Mn_2O_4 . This is the most stable of all the oxides of manganese; it is not only stable at the ordinary but also at a high temperature—that is, it does not absorb or disengage oxygen by itself. When ignited, all the higher oxides of manganese pass into it by losing oxygen, and manganous oxide by absorbing oxygen. This oxide does not give any independent salts, but it dissolves in sulphuric acid, forming a dark red solution, which contains both manganous and manganic (of the *oxide*, Mn_2O_5) sulphates. The latter with potassium sulphate gives a manganese alum, in which the alumina is replaced by its isomorphous oxide of manganese. But this alum, like the solution of the intermediate oxide in sulphuric acid, evolves oxygen and leaves a manganous salt, when slightly heated.

Manganese dioxide is still less basic than the oxide, and disengages oxygen or a halogen in the presence of acids, forming manganous salts, like the oxide. However, if it be placed in ether, and hydrochloric acid gas passed into the mixture, which is kept cool, then the ether acquires a green colour, owing to the formation of a compound, $MnCl_4$, corresponding with the dioxide which passes into solution. It is, however, very unstable and exceedingly easily decomposed, with the evolution of chlorine. The corresponding fluoride obtained by Nickl's is much more stable. At all events, manganese dioxide does not exhibit any well-defined basic character, but is rather of an acid character, which is particularly shown in the compounds MnF_4 and $MnCl_4$ just mentioned, and in the property of dioxide of manganese of combining with alkalis. If the higher grades of oxidation of manganese be deoxidised in the presence of alkalis, they frequently give the dioxide combined with the alkali—for example, in the presence of potash a compound is formed which contains $K_2O, 5MnO_2$, which shows the feeble acid character of this oxide. When ignited in the presence of sodium compounds, manganese dioxide frequently forms the compound $Na_2O, 12MnO_2$ (Rousseau). In general, manganese dioxide has the character of an exceedingly feebly energetic intermediate oxide; perhaps it is a saline compound containing $MnOMnO_5$ or $(MnO)_5Mn_2O_7$, but there is no firm basis for such a supposition, although it is known that manganous chloride and potassium permanganate give the dioxide in the presence of alkalis.

Manganese dioxide may be obtained from manganous salts by the action of oxidising agents. If manganous hydroxide or carbonate be shaken up in water through which

iron under these circumstances), but only to manganous oxide, MnO , shows that manganese has a considerable affinity for oxygen—that is, is difficult to reduce. This may be done, however, by means of charcoal or sodium at a very high temperature. A mixture of one of the oxides of manganese with charcoal or organic matter gives fused *metallic manganese* under the powerful heat developed by coke with an artificial draught. The metal was obtained for the first time in this manner by Gahn, after Pott, and more especially Scheele, had in the last century shown the difference between the compounds of iron and manganese (they were previously regarded as being the same). Manganese is prepared by mixing one of its oxides in a finely-divided state with oil and soot; the resultant mass is then first ignited in order to decompose the organic matter, and then strongly heated in a charcoal crucible. The manganese thus obtained, however, contains, as a rule, a considerable amount of silicon and other impurities. Its specific gravity is stated as varying from 7.2 to 8.0. It has a light grey colour, a feebly metallic lustre, and although it is very hard it is acted on by a file. It rapidly oxidises in air, being converted into a black oxide; water acts on it at the ordinary temperature, with the evolution of hydrogen, and this decomposition proceeds very rapidly with boiling water.²⁰

chlorine is passed, then manganese hypochlorite is not formed, as is the case with certain other oxides, but manganese dioxide is precipitated: $2\text{MnO}_2\text{H}_2 + \text{Cl}_2 = \text{MnCl}_2 + \text{MnO}_2\text{H}_2\text{O} + \text{H}_2\text{O}$. Owing to this fact, hypochlorites in the presence of alkalis and acetic acid when added to a solution of manganous salts give hydrated manganese dioxide, as was mentioned above. Manganous nitrate also leaves manganese dioxide when heated to 200° . It is also obtained from manganous and manganic salts of the alkalis, when they are decomposed in the presence of a small amount of acid; the practical method of converting the salts MnX_2 into the higher grades of oxidation is given in Chapter II. Note 6.

²⁰ Other chemists have obtained manganese by different methods, and attributed different properties to it. This difference probably depends on the impurities which are dissolved during the smelting of the manganese. It is very possible, and even very probable, that, besides silicon, manganese is able to dissolve carbon—that is, to form a compound with it something like cast iron—and this reason may account for variations in its properties. Deville obtained manganese by subjecting the pure dioxide, mixed with pure charcoal (from burnt sugar), to a strong heat in a lime crucible until the resultant metal fused. The metal obtained had a rose tint, like bismuth, and like it was very brittle, although exceedingly hard. It decomposed water at the ordinary temperature. Brunner obtained manganese having a specific gravity of about 7.2, which decomposed water very feebly at the ordinary temperature, did not oxidise in air, and was capable of taking a bright polish, like steel; it had the grey colour of cast iron, was very brittle, and hard enough to scratch steel and glass, like a diamond. Brunner's method was as follows. He decomposed the manganese fluoride (obtained as a soluble compound by the action of hydrofluoric acid on manganese carbonate) with sodium, by mixing these substances together in a crucible and covering the mixture with a layer of salt and fluor spar; after which the crucible was first gradually heated until the reaction began, and then strongly heated in order to fuse the metal separated. At all events, manganese is a metal which decomposes water more easily than iron, nickel, and cobalt.

If manganese dioxide, or any lower oxide of manganese, be heated with an alkali in the presence of air, the mixture absorbs oxygen from the air,²¹ and forms an alkaline manganate of a green colour: $2\text{KHO} + \text{MnO}_2 + \text{O} = \text{K}_2\text{MnO}_4 + \text{H}_2\text{O}$. Steam is disengaged during the ignition of the mixture, and if this does not take place there is no absorption of oxygen. The oxidation proceeds much more rapidly if, before igniting in air, potassium chlorate or nitre be added to the mixture, and this is the usual method of preparing *potassium manganate*, K_2MnO_4 . The resultant mass dissolved in a small quantity of water gives a dark green solution, which, when evaporated under the receiver of an air-pump over sulphuric acid, deposits green crystals of exactly the same form as potassium sulphate—namely, six-sided prisms and pyramids. The composition of the crystals is not changed by being re-dissolved, if perfectly pure water free from air and carbonic acid be taken. But in the presence of even very feeble acids the solution of this salt changes its colour and becomes red, and deposits manganese dioxide. The same decomposition takes place when the salt is heated with water, but when diluted with a large quantity of unboiled water the manganese dioxide is not separated, although the solution turns red. This change of colour depends on the fact that potassium manganate, whose solution is green, is transformed into potassium permanganate, whose solution is of a red colour. The reaction proceeding under the influence of acids and a large quantity of water is expressed in the following manner: $3\text{K}_2\text{MnO}_4 + 2\text{H}_2\text{O} = 2\text{KMnO}_4 + \text{MnO}_2 + 4\text{KHO}$. When there is a small quantity of free acid it combines with the liberated alkali. If there is a large proportion of acid and the decomposition is aided by heat, then the manganese dioxide and potassium permanganate are also decomposed, with formation of manganous salt. Exactly the same decomposition as takes place under the action of acids is also accomplished by magnesium sulphate, which reacts in many cases like an acid. When water holding atmospheric oxygen in solution acts on a solution of potassium manganate, then the oxygen combines directly with the manganate and forms potassium permanganate, without precipitating dioxide of manganese: $2\text{K}_2\text{MnO}_4 + \text{O} + \text{H}_2\text{O} = 2\text{KMnO}_4 + 2\text{KHO}$. Thus a solution of potassium manganate undergoes a very characteristic change in colour and passes from green to red under exceedingly slight agencies; hence this salt received the name of *chameleon mineral*.²²

²¹ Vol. I. p. 157, Note 7.

²² It was known by this name to the alchemists, but the true explanation of the change in colour is due to the researches of Chevillot, Edwards, Mitscherlich, and Forchhammer. The change in colour of potassium manganate is due to its insta-

Potassium permanganate, KMnO_4 , crystallises in well-formed, long red prisms with a bright green metallic lustre. In the arts the potash is frequently replaced by soda, and even by other alkaline bases, but no salt of permanganic acid crystallises so well as the potassium salt, and therefore this salt is exclusively used in chemical laboratories. One part of the crystalline salt dissolves in 15 parts of water at the ordinary temperature. The solution is of a very deep *red colour*, which is so intense that it is still clearly observable after being highly diluted with water. The decompositions to which this salt is liable in many cases are very remarkable. In a solid state it is decomposed by heat, with evolution of oxygen, a residue consisting of the red oxide of manganese and potassium oxide being left. The solution of this salt with an excess of impure commercial alkali generally acquires a green tint. The reason of this change in colour must be ascribed to the fact that a manganate is formed, and a portion of the oxygen thus liberated passes over to the organic matter mixed in the impure alkali, because pure solutions of alkalis do not produce a change in colour even when boiled and evaporated. A number of substances reduce potassium permanganate to manganese dioxide; many organic substances (although far from all, even when boiled in a solution of permanganate) act in this manner, being oxidised at the expense of a portion of the oxygen of the permanganate. Thus, a solution of sugar decomposes a cold solution of potassium permanganate. In the presence of an excess of alkali, with a small quantity of sugar, the reduction leads to the formation of potassium manganate, because $2\text{KMnO}_4 + 2\text{KHO} = \text{O} + 2\text{K}_2\text{MnO}_4 + \text{H}_2\text{O}$.

bility and to its splitting up into two other manganese compounds, a higher and a lower: $3\text{MnO}_3 = \text{Mn}_2\text{O}_7 + \text{MnO}_2$. Manganese trioxide is really decomposed in this manner by the action of water (see later): $3\text{MnO}_3 + \text{H}_2\text{O} = 2\text{MnHO}_4 + \text{MnO}_2$ (Franke, Thorpe, and Hambly). The instability of the salt is proved by the fact of its being deoxidised by organic matter, with the formation of manganese dioxide and alkali, so that, for instance, a solution of this salt cannot be filtered through paper. The presence of an excess of alkali increases the stability of the salt; when heated it breaks up in the presence of water, with the evolution of oxygen.

The mode of preparing *potassium permanganate* will be understood from the above. There are many receipts for preparing this substance, as it is now used in considerable quantities both for technical and laboratory purposes. But in all cases the essence of the methods is one and the same: a mixture of alkali with any oxide of manganese (even manganous hydroxide, which may be obtained from manganous chloride) is first heated in the presence of air or of an oxidising substance (for the sake of quickness, with potassium chlorate); the resultant mass is then treated with water and heated, when manganese dioxide is precipitated and potassium permanganate remains in solution. This solution may be boiled, as the liquid will contain free alkali; but the solution cannot be evaporated to dryness, because a strong solution, as well as the solid salt, is decomposed by heat.

By adding a dilute solution of manganous sulphate to a boiling mixture of lead dioxide and dilute nitric acid, the whole of the manganese may be converted into permanganic acid (Crum).

With a considerable amount of sugar and a more prolonged action, the solution turns brown and precipitates manganese dioxide or even oxide. When a solution of potassium permanganate mixed with alkali is shaken up with a large quantity of many organic substances, the oxidation is generally accompanied by the evolution of heat and precipitation of manganese dioxide. In this case three-eighths of the oxygen in the salt are utilised for oxidation : $2\text{KMnO}_4 = \text{K}_2\text{O} + 2\text{MnO}_2 + \text{O}_3$. A portion of the alkali liberated is retained by the manganese dioxide, and the other portion generally combines with the substance oxidised, because the latter most frequently gives an acid with an excess of alkali. A solution of potassium iodide acts in a similar manner, being converted into potassium iodate at the expense of the three atoms of oxygen disengaged by two molecules of potassium permanganate. A mixture of crystallised potassium permanganate and phosphorus or sulphur takes fire when rubbed or struck ; a mixture with charcoal only burns when heated and not when struck. The instability of the salt is also seen from the fact that its solution is decomposed by hydrogen peroxide.²³

In the presence of acids potassium manganate acts as an oxidising agent with still greater energy than in the presence of alkalis. At all events, a greater proportion of oxygen is then available for oxidation, namely, not $\frac{3}{8}$, as in the presence of alkalis, but $\frac{5}{8}$, because in the first instance manganese dioxide is formed, and in the second case manganous oxide, or rather the salt, MnX_2 , corresponding with it. Thus, for instance, in the presence of an excess of sulphuric acid, the decomposition is accomplished in the following manner : $2\text{KMnO}_4 + 3\text{H}_2\text{SO}_4 = \text{K}_2\text{SO}_4 + 2\text{MnSO}_4 + 3\text{H}_2\text{O} + 5\text{O}$. This decomposition, however, does not proceed directly on mixing a solution of the salt with sulphuric acid, and crystals of the salt even dissolve in oil of vitriol without the evolution of oxygen, and this solution only decomposes by degrees after a certain time. This is due to the fact that sulphuric acid liberates free permanganic acid from the permanganate,²⁴ which acid is

²³ A solution of potassium permanganate gives a beautiful absorption spectrum. If the light in passing through this solution loses a portion of its rays in it (if one may so account for it), this is partially explained by the increased oxidising power which the solution then acquires. We may here also remark that a dilute solution of permanganate of potassium forms a colourless solution with nickel salts, because the green colour of the solution of nickel salts is complementary to the red. Such a decolorised solution, containing a large proportion of nickel and a small proportion of manganese, decomposes after a time, throws down a precipitate, and re-acquires the green colour proper to the nickel salts.

²⁴ If sulphuric acid is allowed to act on potassium permanganate without any special precautions, a large amount of oxygen is evolved (it may even explode and inflame), and violet spray of the decomposing permanganic acid is jerked up. But if the pure salt (especially free from chlorine) be dissolved in pure well-cooled sulphuric acid, without any rise in temperature, then a green coloured liquid settles at the bottom of the vessel.

stable in solution. But if, in the presence of acids and a permanganate, there is a substance capable of absorbing oxygen—for instance, capable of passing into a higher grade of oxidation—then the reduction of the permanganic acid into manganous oxides sometimes proceeds directly on mixing. This reduction is very clearly seen, because the solutions of potassium permanganate are red whilst the manganous salts are

This liquid does not contain any sulphuric acid, and consists of permanganic anhydride, Mn_2O_7 (Aschoff, Terrell). It is impossible to prepare any considerable quantity of the anhydride by this method, as it decomposes with an explosion as it collects, evolving oxygen and leaving red oxide of manganese. *Permanganic anhydride*, Mn_2O_7 , in dissolving in sulphuric acid, gives a green solution, which (according to Franke, 1887) contains a compound $\text{Mn}_2\text{SO}_{10} = (\text{MnO}_5)_2\text{SO}_4$ —that is, sulphuric acid in which both hydrogens are replaced by the group MnO_5 , which is combined with OK in permanganate of potassium. This mixture with a small quantity of water gives Mn_2O_7 , according to the equation: $(\text{MnO}_5)_2\text{SO}_4 + \text{H}_2\text{O} = \text{H}_2\text{SO}_4 + \text{Mn}_2\text{O}_7$, and when heated to 30° it gives *manganese trioxide*, $(\text{MnO}_5)_2\text{SO}_4 + \text{H}_2\text{O} = 2\text{MnO}_5 + \text{H}_2\text{SO}_4 + \text{O}$. Pure manganese trioxide is obtained if the solution of $(\text{MnO}_5)_2\text{SO}_4$ be poured in drops on sodium carbonate. Then, together with carbonic anhydride, there flies over a spray of manganese trioxide, which may be collected in a well-cooled receiver, and this shows that the reaction proceeds according to the equation: $(\text{MnO}_5)_2\text{SO}_4 + \text{Na}_2\text{CO}_3 = \text{Na}_2\text{SO}_4 + 2\text{MnO}_5 + \text{CO}_2 + \text{O}$ (Thorpe). The trioxide is decomposed by water, forming manganese dioxide and a solution of *permanganic acid*: $3\text{MnO}_5 + \text{H}_2\text{O} = \text{MnO}_2 + 2\text{HMnO}_4$. The same acid is obtained by dissolving permanganic anhydride in water.

Barium permanganate when treated with sulphuric acid gives the same acid. This barium salt may be prepared by the action of barium chloride on the difficultly soluble silver permanganate, AgMnO_4 , which is precipitated on mixing a strong solution of the potassium salt with silver nitrate. The solution of permanganic acid forms a bright red liquid which reflects a dark violet tint. A dilute solution has exactly the same colour as that of the potassium salt. It deposits manganese dioxide when exposed to the action of light, and also when heated above 60° , and this proceeds the more rapidly the more diluted the solution. It shows its oxidising properties in many cases, as has already been said above. Even hydrogen gas is absorbed by a solution of permanganic acid; and charcoal and sulphur are also oxidised by it, as they are by potassium permanganate. This may be taken advantage of in analysing gunpowder, because when it is treated with a solution of potassium permanganate, all the sulphur is converted into sulphuric acid and all the charcoal into carbonic anhydride. Finely-divided platinum immediately decomposes permanganic acid. With potassium iodide it liberates iodine (which may afterwards be oxidised into iodic acid) (Mitscherlich, Frommert, Aschoff, and others). Ammonia does not form a corresponding salt with free permanganic acid, because it is oxidised with evolution of nitrogen. The oxidising action of permanganic acid in a strong solution may be accompanied by flame and the formation of violet fumes of permanganic acid; thus a strong solution of it takes fire when brought into contact with paper, alcohol, alkali sulphides, fats, &c.

We will supplement these data respecting permanganic acid with the following disconnected facts:—

According to Franke, 1 part of potassium permanganate with 13 parts of sulphuric acid at 100° gives brown crystals of the salt $\text{Mn}_2(\text{SO}_4)_5 \cdot \text{H}_2\text{SO}_4 \cdot 4\text{H}_2\text{O}$, which gives a precipitate of hydrated manganese dioxide, $\text{H}_2\text{MnO}_5 = \text{MnO}_2 \cdot \text{H}_2\text{O}$, when treated with water.

Spring, by precipitating potassium permanganate with sodium sulphite and washing the precipitate by decantation, obtained a soluble colloidal manganese oxide, whose composition was the mean between Mn_2O_5 and MnO_2 —namely, $\text{Mn}_2\text{O}_5 \cdot 4(\text{MnO}_2 \cdot \text{H}_2\text{O})$.

almost colourless. Thus, for instance, nitrous acid and its salts are converted into nitric acid and decolorise the acid solution of the permanganate. Sulphurous anhydride and its salts immediately decolourise potassium permanganate, forming sulphuric acid. Ferrous salts, and in general salts of lower grades of oxidation capable of being oxidised in solution, act in exactly the same manner. Sulphuretted hydrogen is also oxidised into sulphuric acid; even mercury is oxidised at the expense of permanganic acid, and decolorises its solution, being converted into mercuric oxide. These reactions may easily be followed to the end, and therefore, having first determined the amount of active oxygen in one volume of a solution of potassium permanganate, and knowing how many volumes are required to effect a given oxidation, it is easy to determine the amount of a substance which is oxidised in a solution from the amount of permanganate expended (Marguerite's method).

The oxidising action of permanganic acid, like all other chemical reactions, is not accomplished instantaneously, but only by degrees. And, as the course of the reaction is here easily followed by determining the amount of salt unchanged in a sample taken at a given moment,²⁵ the oxidising reaction of potassium permanganate, in an acid liquid, was employed by Harcourt and Esson (1865) as one of the first cases for the investigation of the laws of the *rate of chemical change*²⁶ as a

²⁵ For rapid and accurate determinations of this kind, advantage is taken of those methods of chemical analysis which are known as 'titrations' (volumetric analysis), and consist in measuring the volume of solutions of known strength required for the complete conversion of a given substance. Details respecting the theory and practice of titration, in which potassium permanganate is very frequently employed, must be looked for in works on analytical chemistry.

²⁶ The measurements of velocity and acceleration in mechanics serve for determining the measure of forces, but in this case the velocities are magnitudes of length or paths passed over in a unit of time. The velocity of chemical change forms a conception of quite another kind. In the first place, the velocities of reactions are magnitudes of the masses which have entered into chemical transformations; in the second place, these velocities can only be relative quantities. Hence the conception of 'velocity' has quite a different meaning in chemistry from what it has in mechanics. Their only common factor is time. If dt be the element of time and dx the quantity of a substance changed in this element of time, then the fraction (or quotient) dx/dt will express the rate of the reaction. The natural conclusion, made both by Harcourt and Esson, and previously to them (1850) by Wilhelmj (who investigated the rate of conversion, or inversion, of sugar in its passage into glucose), consists in admitting that this velocity is proportional to the quantity of substance still unchanged—i.e., that $dx/dt = C(A - x)$, where C is a constant coefficient of proportionality, and where A is the quantity of a substance taken for reaction at the moment when $t=0$ and $x=0$ —that is, at the beginning of the experiment, from which the time t and quantity x of substance unchanged is counted. On integrating the preceding equation we obtain $\log(A - x) = kt$, where k is a new constant, if we take ordinary (and not natural) logarithms. Hence, knowing A , x , and t for each reaction, we find k , and it proves to be a constant quantity. Thus from the figures cited in the text for the reaction $2\text{KMnO}_4 + 10\text{C}_2\text{H}_4\text{O}_4 + 14\text{MnSO}_4$, it may be

fact of great importance in chemical mechanics. In their experiments they took oxalic acid, $C_2H_2O_4$, which in oxidising gives carbonic anhydride, and, with an excess of sulphuric acid, the potassium permanganate is converted into manganous sulphate, $MnSO_4$, so that the ultimate oxidation will be expressed by the equation: $5C_2H_2O_4 + 2MnKO_4 + 3H_2SO_4 = 10CO_2 + K_2SO_4 + 2MnSO_4 + 8H_2O$. The influence of the relative amount of sulphuric acid is seen from the annexed table, which gives the measure of reaction ρ per 100 parts of potassium permanganate, taken four minutes after mixing, using n molecules of sulphuric acid, H_2SO_4 , per $2KMnO_4 + 5C_2H_2O_4$:

$n = 2$	4	6	8	12	16	22
$\rho = 22$	36	51	63	77	86	92

It is obvious that the temperature and relative amount of every one of the acting and resulting substances should show its influence on the relative velocity of reaction; thus, for instance, direct experiment showed the influence of the admixture of manganous sulphate, depending on the possibility of the formation of manganese dioxide by the reaction of the manganous oxide on the permanganic acid. When a large proportion of oxalic acid (108 molecules) was taken to a large mass of water and to 2 molecules of permanganate, 14 molecules of manganous sulphate was added, then the quantity x of the potassium permanganate acted on (in percentages of the potassium permanganate taken) in t minutes (at 16°) was as follows:

$t = 2$	5	8	11	14	44	47	53	61	68
$x = 5.2$	12.1	18.7	25.1	31.3	68.4	71.7	75.8	79.8	83.0

These figures show that the rate of reaction—that is, the quantity of permanganate changed in one minute—decreases proportionally to the decrease in the amount of unchanged potassium permanganate. In one minute, at the commencement, about 2.6 per cent. of the salt taken had reacted, and after an hour about 0.5 per cent. The same phenomena are observed in every case which has been investigated, and this branch of theoretical or physical chemistry, now studied by many,²⁷ promises to explain the course of chemical trans-

found that $k = 0.0114$; for example, $t = 44$, $x = 68.4$ ($A = 100$), whence $kt = 0.5004$ and $k = 0.0114$.

²⁷ The researches made by Hood, Van't Hoff, Ostwald, Warder, Menschutkin, Konovaloff, and others have a particular significance in this subject. Owing to the comparative novelty of this subject, and the absence of applicable as well as indubitable deductions, I consider it impossible to enter into this province of theoretical chemistry,

formations from a fresh point of view, which is closely allied to the doctrine of affinity, because the rate of reaction, without doubt, is connected with the magnitude of the affinities acting between the reacting substances.

although I am quite confident that its development should lead to very important results, especially in respect to chemical equilibria, because Van't Hoff has already shown that the limit of reaction in reversible reactions is determined by the attainment of equal velocities for the opposite reactions.

CHAPTER XXII

IRON, COBALT, AND NICKEL

JUDGING from their atomic weights, and the composition of the higher oxides, it is easy to form a direct conception of the series of elements comprehending seven groups. Such is, for instance, the typical series Li, Be, B, C, N, O, F, or the third series, Na, Mg, Al, Si, P, S, Cl. It is easy to form an idea of the seven groups, because the seven usual types of oxides from R_2O to R_2O_7 correspond with them (Chapter XV.). The position of the eighth group is quite separate, and is determined by the fact that, as we have already seen, in each group of metals having a greater atomic weight than potassium a distinction ought to be made between the elements of the even and uneven series. The series of even elements, commencing with a strikingly alkaline element (potassium, rubidium, cesium), together with the uneven series following it, concluding with a haloid (chlorine, bromine, iodine), forms one large period, the properties of whose members repeat themselves in other similar periods. The elements of the eighth group are situated between the elements of the even series and the elements of the uneven series following them. And for this reason elements of the eighth group are found in the middle of each large period. The properties of the elements belonging to it are shown with typical clearness in the case of iron, the well-known representative of this group.

Iron is one of those elements which are not only widely diffused in the crust of the earth, but also throughout the entire universe. Its oxides and their various compounds are found in the most diverse portions of the earth's crust; but here iron is always found combined with some other element. Iron is not found on the earth's surface in a free state, because it easily oxidises under the action of air. It is occasionally found in the native state in meteorites, or aerolites, which fall upon the earth.

Meteoritic iron is formed outside the earth.¹ Meteorites are fragments

¹ The composition of meteoric iron is various. It generally contains nickel, phosphorus, carbon, &c. The schreibersite of meteoric stones contains Fe_4Ni_2P .

which are carried round the sun in orbits, and fall upon the earth when coming into proximity with it during their motion in space. The meteoric dust, on passing through the upper parts of the atmosphere, and becoming incandescent from friction with the gases, produces that phenomenon which is familiar under the name of falling stars.² Such is the doctrine concerning meteorites, and therefore the fact of their containing rocky (siliceous) matter and metallic iron shows that outside the earth the elements and their aggregation are in some degree the same as upon the earth itself.

The most widely-diffused terrestrial compound of iron is iron bisulphide, FeS_2 , or *iron pyrites*. It occurs in formations of both aqueous and igneous origin, and sometimes in enormous masses. It is

² Comets and the rings of Saturn ought now to be considered as consisting of an accumulation of such meteoric cosmic particles. Perhaps the part played by these minute bodies scattered throughout space is much more important in the formation of the largest celestial bodies than was hitherto conceived. The investigation of this branch of astronomy, due to Schapparelli, has a bearing on the whole of natural science.

The question arises as to why the iron in meteorites is in a free state, whilst on earth it is in a state of combination. Has not this a tendency to show the great diversity in the conditions of our orb from those of the rest? My answer to this question has been already given in Vol. I. p. 365, Note 57. It is my opinion that inside the earth there is a mass similar in composition to meteorites—that is, containing rocky matter and metallic iron, partly carburetted. In conclusion, I consider it will not be out of place to add the following explanations. According to the theory of the distribution of pressures (see my treatise, *On Barometrical Levelling*, 1876, pages 48 *et seq.*) in an atmosphere of mixed gases, it follows that two gases, whose densities are d and d_1 , and whose relative quantities or partial pressures at a certain distance from the centre of attraction are h and h_1 , will, when at a greater distance from the centre of attraction, present a different ratio of their masses $x : x_1$ —that is, of their partial pressures—which may be found by the equation $d_1(\log h - \log x) = d(\log h_1 - \log x_1)$. If, for instance, $d : d_1 = 2 : 1$, if $h = h_1$ (that is to say, the masses are equal at the lower height) = 1000, then when $x = 10$ the magnitude of x_1 will not be 10 (*i.e.*, the mass of a gas at a higher level whose density = 1 will not be equal to the mass of a gas whose density = 2, as was the case at a lower level), but much greater—namely, $x_1 = 100$ —that is, the lighter gas will predominate over a heavier one at a higher level. Therefore, when the whole mass of the earth was in a state of vapour, the substances having a greater vapour density accumulated about the centre (speaking relatively, for instance, with respect to the mass of oxygen alone), and those with a lesser vapour density at the surface. And as the density of vapours depends on the atomic and molecular weights, then those substances which have small atomic and molecular weights ought to accumulate at the surface, and those with high atomic and molecular weights, which are the least volatile and the most difficult to condense, at the centre. Thus it is understood why such light elements as hydrogen, carbon, nitrogen, oxygen, sodium, magnesium, aluminium, silicon, phosphorus, sulphur, chlorine, potassium, calcium, and their compounds predominate at the surface and form the earth's crust. There is also now much iron in the sun, as spectrum analysis shows, and therefore it entered into the composition of the earth and other planets, but accumulated at the centre, because the density of its vapour is certainly large and it easily condenses, not being volatile. There was also oxygen about the centre of the earth, but not sufficient to combine with the iron. The greatest amount of oxygen (relatively), as a much lighter element, accumulated at the surface, where we at the present time observe all oxidised compounds and even still a remnant of free oxygen.

a substance having a greyish-yellow colour, with a metallic lustre, a sp. gr. of 5.0, and crystallises in the regular system.

The oxides are the principal ores used for producing metallic iron. The majority of the ores contain ferric oxide, Fe_2O_3 , either in a free state or combined with water, or else in combination with ferrous oxide, FeO . The qualities and sorts of iron ores are numerous and various. Ferric oxide in a separate form appears sometimes as crystals of the rhombohedric system, having a metallic lustre and greyish steel colour; they are brittle, and form a red powder, specific gravity about 5.25. Ferric oxide in type of oxidation and properties resembles alumina; it is, however, although with difficulty, soluble in acids even when anhydrous. The crystalline oxide bears the name of *specular iron ore*, but ferric oxide most often occurs in a non-crystalline form, in masses having a red fracture, and is then known as *red hæmatite*. In this form, however, it is rather a rare ore, and is principally found in veins. The hydrates of ferric oxide, ferric hydroxides,⁵ are most often found in aqueous or stratified formations, and are known as *brown hæmatites*; they generally have a brown colour, form a yellowish-brown powder, have no metallic lustre, but an earthy appearance. They easily dissolve in acids, and diffuse through other formations, especially clays (for instance, ochre); they sometimes occur in reniform and similar masses, evidently of aqueous origin. Such are, for instance, the so-called bog or lake and peat ores found at the bottom of marshes and lakes, and also under and in peat beds. This ore is formed from water containing ferrous carbonate in solution, which, after absorbing oxygen, deposits ferric hydroxide. In rivers and springs iron is found in solution, through the assistance of carbonic acid, as ferrous carbonate; hence the existence of chalybeate springs containing a considerable amount of ferrous carbonate, FeCO_3 . This ferrous carbonate, or *siderite*, is either found as a non-crystalline product of evidently aqueous origin, or as a crystalline spar called *spathic iron ore*. In the first shape the reniform deposits of this ore are most remarkable; they are called sphaerosiderites, and sometimes form whole light strata in the jurassic and carboniferous formations. *Magnetic iron ore*, $\text{Fe}_3\text{O}_4 = \text{FeO}, \text{Fe}_2\text{O}_3$, in virtue of its purity and practical uses, is a very

⁵ The hydrated ferric oxide is found in nature in a dual form. It is somewhat rarely met with in the form of a crystalline mineral called *göthite*, whose specific gravity is 4.4 and composition $\text{Fe}_2\text{H}_2\text{O}_4$, or FeHO_2 —that is, one of oxide of iron to one of water: $\text{Fe}_2\text{O}_3, \text{H}_2\text{O}$; most often found as brown ironstone, forming dense masses of fibrous reniform deposits containing $2\text{Fe}_2\text{O}_3, 3\text{H}_2\text{O}$ —that is, having a composition $\text{Fe}_4\text{H}_6\text{O}_9$. In bog ore and other similar ores we most often find a mixture of this hydrated ferric oxide with clay and other impurities. The specific gravity of such formations is rarely as high as 4.0.

important ore ; it is a compound of the ferrous and ferric oxides, it is naturally magnetic, has a specific gravity of 5.1, crystallises in well-formed crystals of the regular system, is with difficulty soluble in acids, and sometimes forms enormous masses, as, for instance, Mount Blagodats in the Ural. However, in most cases—for instance, at Korsak-Mogila (to the north of Berdiansk and Nogaiska, near the Azov Sea), or at Krivoi Rog (to the west of Ekaterinoslav)—the magnetic iron ore is mixed with other iron ores. In the Urals, the Caucasus (not to mention Siberia), and in the districts adjoining the coal basin of the Don, Russia possesses the richest iron ores in the world. To the south of Moscow, in the Governments of Toula and Nijni-Novgorod, in the Olonetz district, and in the Government of Orloffsky (near Zinovieff in the district of Kromsky), and in many other places, there are likewise abundant supplies of iron ores amongst the deposited aqueous formations ; the siderite of Orloffsky, for instance, is distinguished by its great purity.⁴

Iron is also found in the form of various other compounds—for instance, in certain silicates, and also in some phosphates ; but these forms are comparatively rare in nature in a pure state, and have not the industrial importance of those natural compounds of iron previously mentioned. In small quantities iron enters into the composition of every kind of *soil* and all rocky formations. As ferrous oxide is isomorphous with magnesia, and ferric oxide with alumina, isomorphous substitution is possible here, and therefore minerals are not unfrequently found in which the quantity of iron considerably varies ; such, for instance, are pyroxene, amphibole, certain varieties of mica, &c. Although much iron oxide is deleterious to the growth of vegetation, still plants do not flourish without iron ; it enters as an indispensable component into the composition of all higher *organisms* ; in the ash of plants we always find more or less of its compounds. It also even enters into the blood, and forms one of the colouring matters in it ; 100 parts of the blood of the highest organisms contain about 0.05 of iron.

⁴ The ores of iron, similarly to all substances extracted from veins and deposits, are worked according to mining practice by means of vertical, horizontal, or inclined excavations which reach and penetrate the veins and strata containing the ore deposits. The mass of ore excavated is raised to the surface, then sorted either by hand or else in special sorting apparatus (generally acting with water to wash the ore), and is subjected to roasting and other treatment. In every case the ore contains foreign matter. In the extraction of iron, which is one of the cheapest metals, the dressing of an ore is in most cases unprofitable, and only ores rich in metal are worked—namely, those containing at least 20 p.c. It is often profitable to transport rich (as much as 70 p.c. of iron) and pure ores from long distances. The details concerning the working and extraction of metals will be found in special treatises on metallurgy and mining.

The *reduction* of the ores of iron into metallic iron is in principle very simple, because when the oxides of iron are strongly heated with charcoal, hydrogen, carbonic oxide, and other reducing agents,⁵ they easily give metallic iron. But the matter is rendered more difficult by the fact that the iron does not melt at the heat developed by the combustion of the charcoal, and therefore it does not separate from those mechanically mixed impurities which are found in the iron ore. In this way it would be impossible to produce large quantities of iron cheaply, because after every operation it would be necessary to clean out the apparatus in which the ore was heated with charcoal. This is obviated by the following very remarkable property of iron : at a high temperature it is capable of combining with a small quantity (from 2 to 5 p.c.) of carbon, and then forms *cast iron*, which easily *melts* in the heat developed by the combustion of charcoal in air. For this reason metallic iron is not obtained directly from the ore, but is only formed after the further treatment of the cast iron ; the first product extracted from the ore being cast iron. The fused mass disposes itself in the furnace below the slags—that is, the impurities of the ore fused by the heat of the furnace. If these impurities did not fuse

⁵ The reduction of iron oxides by hydrogen belongs to the order of the reversible reactions (Chapter II.), and is therefore determined by a limit which is here expressed by the attainment of the same pressure as in the case where hydrogen acts on iron oxides, and as in the case where (at the same temperature) water is decomposed by metallic iron. The calculations referring to this matter were made by Henri Sainte-Claire Deville (1870). Spongy iron was placed in a tube having a temperature t , one end of which was connected with a vessel containing water at 0° (vapour tension = 4.6 mm.), and the other end with a mercury pump and pressure gauge which determined the limiting tension attained by the dry hydrogen p (subtracting the tension of the water vapour from the tension observed). A tube was then taken containing an excess of iron oxide. It was filled with hydrogen, and the tension p_1 of the hydrogen which remained when the water condensed at 0° was taken.

$t = 200^\circ$	440°	860°	1040°
$p = 95.9$	25.8	12.8	9.2 mm.
$p_1 = -$	—	12.8	9.4 mm.

The equality of the pressure (tension) of the hydrogen in both cases is evident. The hydrogen here behaves like the vapour of iron or of its oxide.

When Moissan took ferric oxide, Fe_2O_3 , he observed that at 350° it passed into magnetic oxide, Fe_3O_4 , at 500° into ferrous oxide, FeO , and at 600° into metallic iron. Wright and Luff (1878), whilst investigating the reduction of oxides, found (a) that the temperature of reaction depends on the condition of the oxide taken—for instance, precipitated cupric oxide is reduced by hydrogen at 85° , that obtained by oxidising the metal or from its nitrate at 175° ; (b) when other conditions are the same, the reduction by carbonic oxide commences earlier than that by hydrogen, and the reduction by hydrogen still earlier than that by charcoal; (c) the reduction is effected with greater facility when a greater quantity of heat is evolved during the reaction. Ferric oxide obtained by heating ferrous sulphate to a red heat begins to be reduced by carbonic oxide at 202° , by hydrogen at 260° , by charcoal at 430° , whilst for magnetic oxide, Fe_3O_4 , the temperatures are 200° , 290° , and 450° respectively.

they would block up the furnace in which the ore was being smelted, and the uninterrupted continuation of the smelting of the cast iron would not be possible;⁶ it would be necessary periodically to cool the furnace and heat it up again, which means a wasteful expense of fuel, and therefore in the production of cast iron the object in view is to obtain all the earthy impurities of the ore in the shape of a fused mass or slag. Only in rare cases does the ore itself form a mass which fuses at the temperature employed, and these cases are even objectionable if much iron oxide is carried away in the slag. The impurities of the ores most often consist of certain mixtures—for instance, a mixture of clay and sand, or a mixture of limestone and clay, or quartz, and often of silica, &c. These impurities do not separate of themselves, or do not fuse—for instance, lime and silica only fuse when subjected to the strongest heat. The difficulty of the industry lies in forming an easily-fusible slag, into which the whole of the foreign matter of the ore would pass and flow down to the bottom of the furnace above the heavier cast iron. This is effected by mixing certain *fluxes* with the ore and charcoal. A flux is a substance which, when mixed with the foreign matter of the ore, forms a fusible vitreous mass or slag. The flux used for silica is limestone with clay; for limestone, silica is used, the best procedure having been arrived at by experiment and by long practice in iron smelting.⁷

⁶ The primitive methods of iron manufacture were conducted by intermittent processes in hearths resembling smiths' fires. Commencing with the uninterrupted action of the steam boiler, or the process of lime burning, and up to the continuous preparation and condensation of sulphuric acid or the uninterrupted smelting of iron, every industrial production becomes particularly profitable and complete under the conditions of the continuous action, as far as possible, of all agencies concerned in the production. This continuous method of production is the first condition for the profitable production on the large scale of nearly all industrial products.

⁷ The composition of slag suitable for iron smelting most often approaches the following: 50 to 60 p.c. SiO_2 , 5 to 20 Al_2O_3 , and the rest of the mass consisting of MgO , CaO , MnO , FeO , K_2O , Na_2O . Thus the most fusible slag (according to the observations of Bodeman) contains the alloy $\text{Al}_2\text{O}_3 \cdot 4\text{CaO} \cdot 7\text{SiO}_2$. On changing the quantity of magnesia and lime, and especially of the alkalis (the fusibility increases) and of silica (the fusibility decreases), the temperature of fusion changes with the relation between the quantity of oxygen to that in the silica. Slags of the composition $\text{RO} \cdot \text{SiO}_2$ are easily fusible, have a vitreous appearance, and are very common. Basic slags approach the composition $2\text{RO} \cdot \text{SiO}_2$. Therefore, knowing the composition and quantity of the foreign matter in the ore it is at once easy to find the quantity and quality of the flux which must be added to form a suitable slag. The smelting of iron is rendered more complex by the fact that the silica, SiO_2 , which enters into the slag and fluxes is capable of forming a slag with the iron oxides. In order that the least quantity of iron may pass into the slag, it is necessary for it to be reduced before the temperature is attained at which the slags are formed (about 1000°), which is effected by reducing the iron, not with charcoal itself, but with carbonic oxide. From this it will be understood how the progress of the whole treatment may be judged by the properties of the slags.

Thus the following materials have to be introduced into the furnace where the smelting of the iron ore is carried on: (1) the iron ore, composed of oxide of iron and foreign matter; (2) the flux required to form a fusible slag with the foreign matter; (3) the carbon which is necessary (*a*) for reducing, (*b*) for combining with the iron reduced to form cast iron, (*c*) principally for the purpose of combustion and the heat generated thereby, necessary not only for reducing the iron and transforming it into cast iron, but also for melting the slags as well as the cast iron—the reaction of reduction is only accomplished at a high temperature—and (4) the air necessary for the combustion of the charcoal. The air is introduced after a preparatory heating (and drying, if moist), in order to economise fuel and to obtain the highest temperature. The air is forced in under pressure by means of a special blast arrangement. This permits of an exact regulation of the heat and rate of smelting. All these component parts necessary for the smelting of iron must be contained in a vertical, that is, *shaft furnace*, which at the base must have a receptacle for the accumulation of the slag and cast iron formed, in order to proceed without interruption. The walls of such a furnace ought to be built of fireproof materials if it be designed to serve for the continuous production of cast iron by charging the ore, fuel, and flux into the mouth of the furnace, forcing a blast of air into the lower part, and running out the molten iron and slag from below. The whole operation is conducted in furnaces known as *blast furnaces*. The annexed illustration represents the vertical section of such a furnace. These furnaces are generally of large dimensions—varying from 50 to 90 feet in height. They are often built against some rising ground or other in order to afford easy access to the most elevated parts where the ore, flux, and charcoal or coke are charged.⁸

⁸ The section of a blast furnace is represented by two truncated cones joined at their bases, the higher cone being longer than the lower one; the lower cone is terminated by the hearth, O, or almost cylindrical cavity in which the cast iron and slag collects, one side being provided with apertures for drawing off the iron and slag. The air is blown into the blast furnace through special pipes, T, situated over the hearth, as shown in the section. The air previously passes through a series of cast-iron pipes, heated by the combustion of the carbonic oxide obtained from the upper parts of the furnace, where it is formed as in a 'gas-producer.' The blast furnace acts continuously until it is worn out; the iron is tapped off twice a day, and the furnace is allowed to cool a little from time to time so as not to be spoilt by the increasing heat, and to enable it to withstand a longer campaign.

In order to more thoroughly grasp the chemical process which is effected in blast furnaces, it is necessary to follow the course of the matter charged in at the top and the air passing through the furnace. From 50 to 200 parts of carbon are expended on 100 parts of iron. These quantities are charged into the top of the furnace, in layers, as the cast iron is formed in the lower parts and flowing down to the bottom

The *cast iron* formed in blast furnaces is not always of the same quality. When slowly cooled it is soft, has a grey colour, and is not

causes the whole contents of the furnace to subside, thus forming an empty space at the top, which is again filled up with the afore-mentioned mixture. During its downward course this mixture is subjected to increasing heat. This rise of temperature first drives off the moisture of the ore mixture, and then leads to the formation of




FIG. 93.—Vertical section of a blast furnace.

the products of the dry distillation of coal or charcoal. Little by little the subsiding mass attains a temperature at which the heated carbon reacts with the carbonic anhydride, passing upwards through the furnace, and transforms it into carbonic oxide. This is the reason why carbonic anhydride is not evolved from the furnace, but only carbonic oxide. As regards the ore itself, on being heated to about 600° to 800° it is reduced at the expense of the carbonic oxide ascending the furnace, and formed by the contact of the carbonic anhydride with the incandescent charcoal, so that the reduction process in the blast furnace is without doubt effected by the formation and assistance of *carbonic oxide* and not by carbon itself—thus, $\text{Fe}_2\text{O}_3 + 3\text{CO} = \text{Fe}_2 + 3\text{CO}_2$. The reduced iron on

completely soluble in acids. When treated with acids a residue of graphite remains ; it is known as *grey* or soft cast iron. This is the general form of the ordinary cast iron used for casting various objects, because in this state it is not so brittle as in the shape of *white cast iron*, which does not leave particles of graphite when dissolved, but yields its carbon in the form of hydrocarbons. This white cast iron is characterised by its whitish-grey colour, dull lustre, the crystalline structure of its fracture, and such hardness that a file will hardly cut it. When white cast iron is produced (from manganese ore) at high temperatures (and with an excess of lime), and containing but little sulphur and silica, but a considerable amount of carbon (as much as 5 p.c.), it acquires a coarse crystalline structure which increases in

further subsidence and contact with carbon, forms cast iron, which flows to the bottom of the furnace. In these lower layers, where the temperature is most elevated (about 1300°), the foreign matter of the ore finally forms slag, also fusible, with the fluxes. These are the processes accomplished by the mass of the products charged in from above. The air blown in from below, through the so-called *tuyeres*, encounters carbon in the lower layers of the furnace, and burns it, converting it into carbonic anhydride. It is evident that this develops the highest temperature in these lower layers of the furnace, because here the combustion of the carbon is effected at the expense of heated and compressed air. This is very important, because with the assistance of this high temperature the process of forming the slag and that of forming the cast iron are simultaneously terminated in these lower portions of the furnace. The carbonic acid formed in these parts rises higher, encounters incandescent carbon, and forms with it carbonic oxide. This heated carbonic oxide acts as a reducing agent on the iron ore, and is then turned again by it into carbonic anhydride ; this gas again meets with carbon, and again forms carbonic oxide, which again acts as a reducing agent. The final transformation of the carbonic anhydride into carbonic oxide is effected in those parts of the furnace where the reduction of the oxides of iron does not take place, but where the temperature is so high as to be sufficient to reduce the carbonic anhydride. The ascending mixture of carbonic oxide and nitrogen of the air is then withdrawn through special lateral apertures formed in the upper cold parts of the furnace walls. The mixture of carbonic oxide and nitrogen is conducted through pipes to those stoves which are used for heating the air, and also sometimes into other furnaces used for the further processes of iron manufacture. The fuel of blast furnaces consists of wood charcoal (this is the best but most expensive material, because it does not contain sulphur), anthracite (for instance, in Pennsylvania, and in Russia at Pastouhoff's works in the Don district), coke, coal, and even wood and peat. It must be borne in mind that the utilisation of naphtha and naphtha refuse would probably give very profitable results in metallurgical processes. Here experiments are absolutely necessary, and particularly important for Russia, because the Caucasus is capable of yielding vast quantities of naphtha. Vapours and gases ought in general to be applied to the metallurgy of iron, which is at present exclusively based on the application of solid fuel.

The process just described is, if it may be so expressed, worked side by side with a series of smaller processes. Thus, for instance, in the blast furnace a considerable quantity of cyanogen compounds are formed. This takes place, because the nitrogen of the air blast comes into contact with incandescent carbon and various alkaline matters contained in the foreign matter of the ores. A considerable quantity of potassium cyanide is formed when wood charcoal is employed for iron smelting, as its ash is rich in potash.

proportion to the amount of manganese, and it is then known under the name of 'spiegeleisen' (and 'ferro-manganese').⁹

Cast iron is a material which is either suitable for direct application for casting in moulds or else for working up into *wrought iron* and *steel*. The latter principally differ from cast iron in their containing less carbon—thus, steel contains from 1 p.c. to 0.5 p.c. of carbon and far less silicon and manganese than cast iron; wrought iron does not generally contain more than 0.25 p.c. of carbon and not more than 0.25 p.c. of the other impurities. Thus the essence of the working up of cast iron into steel and wrought iron consists in the removal of the greater part of the carbon. This is effected by means of oxidation, because the oxygen of the atmosphere, oxidising the iron at a high temperature, forms solid oxides with it; and the latter, coming into contact with the carbon contained in the cast iron, are deoxidised, forming wrought iron and carbonic oxide, which is evolved from the mass in a gaseous form. It is evident that the oxidation must be carried on with a molten mass in a state of agitation, so that the oxygen of the air, passing over the surface of the iron, may be brought into contact with the whole mass of carbon contained in the cast iron,

⁹ The specific gravity of white cast iron is about 7.5. Grey cast iron has a much lower specific gravity, namely, 7.0. Grey cast iron generally contains less manganese and more silica than white; but both contain from 2 to 3 p.c. of carbon. The difference between the varieties of cast iron depends on the condition of the carbon which enters into the composition of the iron. In white cast iron the carbon is in combination with the iron—in all probability as the compound CFe_4 , but perhaps in the state of an indefinite chemical compound resembling a solution. In any case the compound of the iron and carbon in white cast iron is chemically very unstable, because when slightly cooled it decomposes, with separation of graphite, just as a solution when slowly cooled yields a portion of the substance dissolved. However, the separation of carbon in the form of graphite on the transition of white cast iron into grey is never complete; part of the carbon remains in combination with the iron in the same state as it is combined in white cast iron. Indeed, when grey cast iron is treated with acids, the whole of the carbon does not remain in the form of graphite, but a part of it is separated as hydrocarbons, which proves the existence of chemically-combined carbon in grey cast iron. It is sufficient to re-melt grey cast iron and to cool it quickly to transform it into white cast iron. However, it is not carbon alone that influences the properties of cast iron; when it contains a considerable amount of sulphur, cast iron remains white even after having been slowly cooled. The same is observed in cast iron very rich in manganese (5 to 7 p.c.), and in this latter case the fracture is very distinctly crystalline and brilliant. When cast iron contains a large amount of manganese, the quantity of carbon may also be increased. Crystalline varieties of cast iron rich in manganese are in practice called *ferro-manganese*, and are prepared for the Bessemer process. Grey cast iron not having an uniform structure is much more liable to various changes than dense and thoroughly uniform white cast iron, therefore the latter oxidises much more slowly in air than the former. The cast iron destined for the manufacture of the best kinds of wrought iron and steel ought to contain very little sulphur and phosphorus (not more than 0.05 p.c.). The silicon, manganese, and part of the sulphur oxidise during the processes, and hardly enter into the steel.

or else the operation is effected by means of the addition of oxygen compounds of iron (oxides, ores), as in Martin's process. The molten mass of cast iron is stirred up, and subjected to the oxidising action of the air. Cast iron melts much more easily than wrought iron and steel, and, therefore, as the carbon separates the mass becomes more and more solid : and the degree of hardness forms, to a certain extent, a measure of the amount of carbon separated, and the operation may terminate either in the formation of steel or wrought iron.¹⁰ In any case, the iron used for industrial purposes contains

¹⁰ This direct process of separating the carbon from cast iron is termed *puddling*. It is conducted in reverberatory furnaces (Vol. I. p. 513). The cast iron is placed on the bed of the furnace and melted; through a special aperture the puddler stirs up the oxidising mass of cast iron, compressing the oxides into the molten cast iron. This resembles kneading dough, and the process introduced in England became known as puddling. It is evident that the puddled mass, or bloom, is an heterogeneous substance obtained by mixing, and therefore one part of the mass will still be rich in carbon, another will be poor, some parts will contain oxides not yet reduced, &c. The further treatment of the puddled mass consists in hammering and drawing out into flat pieces, which on being hammered become more homogeneous, and when several pieces are welded together and again hammered out a still more homogeneous mass is obtained. The quality of the steel and iron thus formed depends principally on their uniformity. The want of uniformity depends on the oxides remaining inside the mass, and on the variable distribution of the carbon throughout the mass. In order to obtain a more homogeneous metal for manufacturing articles out of steel, it is drawn into thin rods, which are tied together in bundles and then again hammered out. As an example of what may be reached in this direction, imitation Damascus steel may be cited; it consists of twisted and plaited wire, which is then hammered into a dense mass. (Real damascened wootz steel may be made by melting a mixture of the best iron with graphite ($\frac{1}{16}$) and iron rust; the article is then corroded with acid, and the carbon remains in the form of a pattern.)

Steel and wrought iron are manufactured from cast iron by puddling. They are, however, not only obtained by this method but also by the *bloomery process*, which consists in a fire similar to a blacksmith's forge, fed with charcoal and provided with a blast; a cast-iron pig is little by little pushed into the fire, and portions of it melt and fall to the bottom of the hearth, coming into contact with an air blast, and are thus oxidised. The bloom thus formed is then subjected to further treatment. It is evident that this process is only available when the charcoal used in the fire does not contain any foreign matter which might injure the quality of the iron or steel—for instance, sulphur or phosphorus—and therefore only wood charcoal may be used with impunity, from which it follows that this process can only be carried on where the manufacture of iron can be conducted with this fuel. Coal and coke contain the above-mentioned impurities, and would therefore produce iron of a brittle nature, and thus it would be necessary to have recourse to puddling, where the fuel is burnt on a special hearth, separate from the cast iron, whereby the impurities of the fuel do not come into contact with it. The manufacture of steel from cast-iron may also be conducted in fires; but, in addition to this, it is also now prepared by many other methods. One of the long-known processes is called *cementation*, by which steel is prepared from wrought iron but not from cast iron. For this process strips of iron are heated red-hot for a considerable time whilst immersed in powdered charcoal; during this operation the iron at the surface combines with the charcoal, but the interior contains but little of it; after this the iron strips are re-forged, drawn out again, and cemented anew, repeating the process until a steel of the desired quality is formed—that is, containing the requisite proportion of carbon. The

impurities. *Chemically pure iron* may be obtained by precipitating iron from a solution (a mixture of ferrous sulphate with magnesium sulphate

Bessemer process occupies the front rank among the newer methods (since 1856); it is so called from the name of its inventor. This process consists in running melted cast iron into retorts (converters, holding about 6 tons of cast iron)—that is, egg-shaped receivers, fig. 94, capable of revolving on trunnions (in order to charge in the




FIG. 94.—Bessemer converter, constructed of iron plate and lined with ganister. The air is carried by the tubes L, O, D to the bottom, M, from which it passes by a number of holes into the converter. The converter is rotated on the trunnion *d* by means of the rack and pinion H, when it is required either to receive molten cast iron from the melting furnaces or to pour out the steel.

cast iron and discharge the steel), and forcing a stream of air through small apertures at a considerable pressure. Combustion of the iron and carbon at an elevated temperature then takes place, resulting from the bubbles of oxygen thus penetrating the mass of the cast iron. The carbon, however, burns to a greater extent than the iron, and therefore a mass is obtained which is much poorer than cast iron in carbon. As the combustion proceeds very rapidly in the mass of metal, the temperature rises to such an extent that even the wrought iron which may be formed remains in a molten condition, whilst the steel, being more fusible than the wrought iron, remains very liquid. In half an hour the mass is ready. The purest possible cast iron is used in the Bessemer process, because sulphur and phosphorus do not burn out like carbon, silicon, and manganese.

The presence of manganese enables the sulphur to be removed with the slags, and the presence of lime or magnesia, which are introduced into the lining of the converter, facilitate the removal of the phosphorus. This basic Bessemer process or *Thomas-Gilchrist process*, introduced about 1880, enables ores containing a considerable amount of phosphorus, which had hitherto only been used for cast iron, to be used for making wrought iron and steel. Naturally, the greatest uniformity will be obtained by re-melting the metal. Steel is re-melted in small wind furnaces, in masses not exceeding 30 kilos; a liquid metal is formed, which may be cast in moulds. A mixture of wrought iron and steel is often used for making cast steel. Large steel castings are made by simul-

or ammonium chloride) by the prolonged action of a feeble galvanic current; the iron may be then obtained as a dense mass. This method,

taneously melting in many furnaces and crucibles; in this way, castings up to 80 tons or more, such as large ordnance, may be made. This molten, and therefore homogeneous, steel is called *cast steel*. Of late years the *Martin's process* for the manufacture of steel has come largely into use; it was invented in France about 1860, and with the use of regenerative furnaces it enables large quantities of cast steel to be made at a time. It is based on the melting of cast iron with iron oxides and iron itself—for instance, pure ores, scrap, &c. There the carbon of the cast iron and the oxygen of the oxide form carbonic oxide, and the carbon therefore burns out, and thus cast steel is obtained from cast iron, providing, naturally, that there is a requisite proportion and corresponding degree of heat. The advantage of this process is that not only do the carbon, silicon, and manganese, but also a great part of the sulphur and phosphorus of the cast iron burn out at the expense of the oxygen of the iron oxides. During the last decade the manufacture of steel and its application for rails, armour plate, guns, boilers, &c., has developed to an enormous extent, thanks to the invention of cheap processes for the manufacture of large masses of homogeneous cast steel, but there is every reason to affirm that the metallurgy of iron is still capable of considerable further improvement. Wrought iron may also be melted, but the heat of a blast furnace is insufficient for this. It easily melts in the oxyhydrogen flame. It may be obtained in a molten state directly from cast iron, if the latter be melted with nitre and sufficiently stirred up. Considerable oxidation then takes place inside the mass of cast iron, and the temperature rises to such an extent that the wrought iron formed remains liquid. A method is also known for obtaining wrought iron directly from rich iron ores by the action of carbonic oxide; the wrought iron is then formed as a spongy mass (which forms an excellent filter for purifying water), and may be worked up into wrought iron or steel either by forging or by dissolving in molten cast iron.

Everybody is more or less familiar with the *difference in the properties of steel and wrought iron*. Iron is remarkable for its softness, pliability, and small elasticity, whilst steel may be characterised by its capability of attaining elasticity and hardness if it be cooled suddenly after having been heated to a definite temperature, or, as it is termed, *tempered*. But if tempered steel be re-heated and slowly cooled, it becomes as soft as wrought iron, and can then be cut with the file and forged, and in general can be made to assume any shape, like wrought iron. In this soft condition it is called *annealed steel*. The transition from tempered to annealed steel takes place, then, in a similar way to the transition from white to grey cast iron. Steel, when homogeneous, has considerable lustre, and has such a fine granular structure that it takes a very high polish. Its fracture clearly shows the granular nature of its structure. The possibility of tempering steel enables it to be used for making all kinds of cutting instruments, which are forged, filed, and cut when the steel is in the annealed condition, and then tempered, ground, polished, &c. The method and temperature of tempering and annealing steel determine its hardness and other qualities. Steel is generally tempered to the required degree of hardness in the following manner. It is first strongly heated (for instance, up to 600°), and then plunged into water—that is, hardened by rapid cooling (it then becomes as brittle as glass). It is then heated until the surface assumes a definite colour, and finally either suddenly or slowly cooled. When steel is heated up to 200°, its surface acquires a yellow colour (surgical instruments); it first of all becomes straw-coloured (razors, &c.), and then gold-coloured; then at a temperature of 250° it becomes brown (scissors), then red, then light blue at 285° (springs), then indigo at 300° (files), and finally sea-green at about 340°. These colours are nothing more than the tints of thin films, like the hues of soap bubbles, and appear on the steel because a thin layer of oxides is formed over its surface. Steel rusts more slowly than wrought iron, and is more soluble in acids than cast iron, but less so than wrought iron. Its specific gravity is about 7.6 to 7.9.

As regards the formation of steel, it was a long time before the process of cementation

proposed by Böttcher and applied by Klein, gives, as R. Lenz showed, iron containing occluded hydrogen, which is disengaged on heating. This

was thoroughly understood, because in this case infusible charcoal permeates unfused wrought iron. Caron showed that this permeation depends on the fact that the charcoal used in the process contains alkalis, which, in the presence of the nitrogen of the air, form metallic cyanides, which, being volatile and fusible, permeate the iron, and, giving up their carbon to the iron, serve as the material for the formation of steel. This explanation is confirmed by the fact that charcoal without alkalis or without nitrogen will not cement iron. Lime with charcoal and in the presence of nitrogen will not cement, because no calcium cyanide is then formed. The charcoal used for cementation acts badly when used over again, as it has lost alkali. The very volatile ammonium cyanide easily conduces to the formation of steel. Although steel is also formed by the action of cyanogen compounds, nevertheless it does not contain more nitrogen than cast or wrought iron (0.01 p.c.), and these latter contain it because their ores contain titanium, which directly combines with nitrogen. Hence the part played by nitrogen in steel is but an insignificant one. It may be useful here to add some information taken from Caron's treatise concerning the influence of foreign matter on the quality of steel. The principal properties of steel are those of tempering and annealing. The compounds of iron with silicon and boron have not these properties. They are more stable than the carbon compound, and this latter is capable of changing its properties; because the carbon in it either enters into combination or else is disengaged, which determines the condition of hardness or softness of steel, as in white and grey cast iron. When slowly cooled, steel splits up into a mixture of soft and carburetted iron; but, nevertheless, the carbon does not separate from the iron. If such steel be again heated, it forms a uniform compound, and hardens when rapidly cooled. If the same steel as before be taken and heated a long time, then, after being slowly cooled, it becomes much more soluble in acid, and leaves a residue of pure carbon. This shows that the combination between the carbon and iron in steel becomes destroyed when subjected to heat, and the steel becomes iron mixed with carbon. Such *burnt* steel cannot be tempered, but may be corrected by continued forging in a heated condition, which has the effect of distributing the carbon equally throughout the whole mass. After the forging, if the iron be pure and the carbon has not burnt out, steel is again formed, which may be tempered. If steel be repeatedly or strongly heated, it becomes burnt through and cannot then be tempered or annealed; the carbon separates from the iron, and this is effected more easily if the steel contains more impurities which are capable of forming stable combinations with iron, such as silicon, sulphur, or phosphorus. If there be much silicon, it occupies the place of the carbon, and then continued forging will not compel the carbon once separated to re-enter into combination. Such steel is easily burnt through and cannot be corrected; but, when burnt through, it is hard, but cannot be annealed—this is tough steel, the lower kind. Iron which contains sulphur and phosphorus cements badly, combines but little with carbon, and steel of this kind is brittle, both hot and cold. Iron in combination with the above-mentioned substances cannot be annealed by slow cooling, showing that these compounds are more stable than that of carbon and iron, and therefore they prevent the formation of the latter. Such metals as tin and zinc combine with iron, but not with carbon, and form a brittle mass which cannot be annealed and is deleterious to steel. Manganese and tungsten, on the contrary, are capable of combining with charcoal; they do not hinder the formation of steel, but even remove the injurious effects of other admixtures (by transforming these admixed substances into new compounds and slags), and are therefore ranked with the substances which act beneficially on steel; but, nevertheless, the best steel which is capable of renewing most often its primitive qualities after burning or hot forging is that which is the purest.

The properties of ordinary *wrought iron* are well known. The best iron is the most tenacious—that is to say, that which does not break up when struck with the hammer

galvanic deposition of iron is used for making galvanoplastic *clichés*; which are distinguished for their great hardness. Electro-deposited iron is brittle, but if heated (after the separation of the hydrogen) it becomes soft. If pure ferric hydroxide, which is easily prepared by the precipitation of solutions of ferric salts by means of ammonia, be taken, and heated in a stream of hydrogen, it forms, first of all, a dull black powder which ignites of its own accord in air (pyrophoric iron), and then a grey powder of pure iron. The powdery substance first obtained is an iron suboxide; when thrown into the air it

or bent, and yet at the same time is sufficiently hard. There is, however, a distinction between hard and soft iron. Generally the softest iron is the most tenacious, and can best be welded, drawn into wire, sheets, &c. Hard, especially tough, iron is often characterised by its breaking when bent, and is therefore very difficult to work, and objects made from it are less serviceable in many respects. Hard, tough iron is most suitable for a few objects—such, for instance, as rails, tyres, &c. Soft iron is most adapted to making wire and sheet iron and such small objects as nails. Soft iron is characterised by its attaining a fibrous fracture after forging, whilst tough iron preserves its granular structure after this operation. Certain sorts of iron, although fairly soft at the ordinary temperature, become brittle when heated and are difficult to weld. These sorts are less suitable for being worked up into small objects. The variety of the properties of iron depends on the impurities which it contains. In general, the iron used in the arts still contains carbon and always a certain quantity of silicon, manganese, sulphur, phosphorus, &c. A variety in the proportion of these component parts changes the quality of the iron. In addition to this the change which soft wrought iron, having a fibrous structure, undergoes when subjected to repeated blows and vibrations is considerable; it then becomes granular and brittle. This to a certain degree explains the want of stability of some iron objects—such as truck axles, which must be renewed after a certain term of service, otherwise they become brittle. It is evident that there are innumerable intermediate transitions from wrought iron to steel and cast iron.

It is worthy of attention to point out that steel, besides temper, possesses many various properties, a review of which may be made in the classification of the *sorts of steel* (1878, Cockerell). (1) *Very mild steel* contains from 0·05 to 0·20 p.c. of carbon, breaks with a weight of 40 to 50 kilos. per square millimetre, and has an extension of 20 to 30 p.c.; it may be welded, like wrought iron, cannot be tempered, is used in sheets for boilers, armour plate and bridges, nails, rivets, &c., as a substitute for wrought iron; (2) *mild steel*, from 0·20 to 0·35 p.c. of carbon, resistance to tension 50 to 60 kilos., extension 15 to 20 p.c., not easily welded, and tempers badly, used for axles, rails, and railway tyres, for cannons and guns, and for parts of machines destined to resist bending and torsion; (3) *hard steel*, carbon 0·35 to 0·50 p.c., breaking weight 60 to 70 kilos. per square millimetre, extension 10 to 15 p.c., cannot be welded, takes a temper; used for rails, all kinds of springs, swords, parts of machinery in motion subjected to friction, spindles of looms, hammers, spades, hoes, &c.; (4) *very hard steel*, carbon 0·5 to 0·65 p.c., tensile breaking weight 70 to 80 kilos., extension 5 to 10 p.c., does not weld, but tempers easily; used for small springs, saws, files, knives, and similar instruments.

The quantity of steel manufactured yearly in Europe is about one million tons, and in North America about half this quantity; in England alone the annual output of cast iron is above 8 million tons, and that of the whole of Europe and America about 15 million tons. Russia contributes but a small part proportionally—namely, about one-fortieth of the whole production—although the Ural, the Don district, and other parts of Russia represent the combination of all advantageous conditions for the future successful development of a vast iron industry. More than three-quarters of the cast iron produced is consumed in the manufacture of wrought iron and steel.

ignites, forming the oxide Fe_3O_4 . If the heating in hydrogen be continued, more water and pure iron, which does not ignite spontaneously, will be obtained. If a small quantity of iron be fused in the oxyhydrogen flame (with an excess of oxygen) in a piece of lime and mixed with powdered glass, pure molten iron will be formed, because in the oxyhydrogen flame iron melts and burns, but the substances mixed with the iron oxidise before it. The oxidised impurities here either disappear (carbonic anhydride) in a gaseous form, or (silica, manganese oxide, and others) turn into slag—that is, fuse with the glass. Pure iron has a silvery white colour and a specific gravity of 7.84; it melts at a temperature higher than the melting-points of silver, gold, and steel. But pure iron becomes soft at a temperature considerably below that at which it melts, and may then be easily forged, welded, and rolled or drawn into sheets and wire.¹¹ Pure iron may be rolled into an exceedingly thin sheet, weighing less than a sheet of ordinary paper of the same size. This ductility is the most important property of iron in all its forms, and is most marked with sheet iron, and least so with cast iron, whose ductility, compared with wrought iron, is small, but is still very considerable when compared with other substances—such, for instance, as rocks.¹²

¹¹ Gore (1869), Tait, Barret, Tchernoff, Osmond, and others observed that at a temperature approaching 600° —that is, between dark and bright red heat—all kinds of wrought iron undergo a peculiar change called *recalcescence*, or a spontaneous rise of temperature. If iron is considerably heated and allowed to cool, it may be observed that at this temperature the cooling stops—that is, the latent heat is disengaged, corresponding with a change in condition. The specific heat, electrical conductivity, magnetic, and other properties then also change. In tempering, the temperature of recalcescence must not be reached, and so also in annealing, &c. It is evident that a change of the internal condition is here encountered, exactly similar to the transition from a solid to a liquid, although there is no evident physical change. It is probable that attentive study would lead to the discovery of a similar change in other substances.

It may be remarked here that iron begins to give out light (in the dark) at a temperature of 405° , and the melting-point of iron must be considered to be far lower than that of platinum (1775°), namely about 1400° to 1600° . According to information supplied by A. T. Skinder's experiments at the Oboukoff Steel Works, 140 volumes of liquid molten steel give 128 volumes of solid metal. By means of a galvanic current of great intensity and dense charcoal as one electrode, and iron as the other, Bernadoss welded iron and fused holes through sheet iron. Soft wrought iron, like steel and soft malleable cast iron, may be melted in Siemens' regenerative furnaces, and in furnaces heated with naphtha.

¹² The particles of steel are linked together or connected more closely than those of the other metals; this is shown by the fact that it only breaks with a tensile strain of 80 kilos. per sq. mm., whilst wrought iron only withstands about 60 kilos., cast iron 10, copper 35, silver 23, platinum 30, wood 10, glass 1. The elasticity of iron, steel, and other metals, also, is expressed by the so-called *coefficient of elasticity*. Let a rod be taken whose section = n sq. mm. and length L ; if a weight, P , be hung from the extremity of it, it will lengthen to l . The less it lengthens under other equal conditions, the more elastic the material, if it resumes its original length when the weight is removed. It has been

The chemical properties of iron have been already rendered clear by the preceding statements. Iron *rusts* in air at the ordinary temperature—that is to say, it becomes covered with a layer of iron oxides. Here, without doubt, the moisture of the air plays a part, because in dry air iron does not oxidise at all, and also because, more particularly, ammonia is always found in iron rust; the ammonia must arise from the action of the hydrogen of the water, at the moment of its separation, on the nitrogen of the air. Highly-polished steel does not rust nearly so readily, but in moist air, and especially if moistened with water, it easily becomes coated with rust. As rust depends on the access of moisture, iron may be preserved from rust by coating it with substances which prevent the moisture having access to it. Thus arises the practice of covering iron objects with paraffin,¹³ varnish, oil, paints, or enamelling it with a glassy-looking flux possessing the same coefficient of expansion as iron, or with a dense scoria (formed by the heat of superheated steam), or with a compact coating of various metals. Wrought iron, both as sheet iron and other objects, cast iron, and steel are often coated with tin, copper, lead, nickel, and similar metals, which prevent contact with the air. These metals preserve iron very effectually from rust if they form a completely compact surface, but in those places where the iron becomes exposed, either accidentally or from wear, rust appears much more quickly than on a uniform iron surface, because, as regards these metals (and also as regards the rust), the iron will then behave as an electro-positive pole in a galvanic couple, and hence will attract oxygen. A coating of zinc does not produce this inconvenience, because iron is electro-negative with reference to zinc, in consequence of which galvanised iron does not easily rust, and even an iron boiler containing

shown by experiment that the increase in length l , due to elasticity, is directly proportional to the length L and the weight P , and inversely proportional to the section n , but changes with the material, and therefore $lKn = PL$, where K is the coefficient of elasticity of the material. Evidently $K = \frac{Pl}{ln}$. Therefore, if $n=1$ and $l=L$ (that is, the length is

doubled), then $K = P$, and, therefore, the coefficient of elasticity expresses that weight (in kilos. per sq. mm.) under which a rod having a square section taken as 1 (we take 1 sq. mm.) acquires double the length by tension. Naturally in practice materials do not withstand such a lengthening, under a certain weight or at the limit of elasticity they stretch permanently (undergo deformation), and therefore the limit of elasticity serves as a characteristic of the metal in addition to the coefficient of elasticity k and the tensile breaking weight. The following data concerning the elasticity of various metals are according to Berthelm and others, fractions being neglected, as the elasticity of metals varies not only with the temperature but also with forging, purity, &c. The magnitude of k for steel and iron is 19000, copper and brass 9000 to 11000, silver 7000, glass 6000, lead and wood 1700.

¹³ Paraffin is one of the best preservatives for iron against oxidation in the air. I found this by experiments about 1860, and immediately published the fact. This method is now very generally applied.

some lumps of zinc rusts less than one without zinc.¹⁴ Iron oxidises at a high temperature (Chapter III.), forming *iron scale*, Fe_3O_4 , composed of ferrous and ferric oxides, and, as has been seen, decomposes water and acids, with the evolution of hydrogen. It is also capable of decomposing salts and oxides of other metals, which property is applied in the arts for the extraction of copper, silver, lead, tin, &c. For this reason, iron is soluble in the solutions of many salts—for instance, in cupric sulphate, with precipitation of copper and formation of ferrous sulphate.¹⁵ When iron *acts on acids* it always *forms ferrous compounds*—that is, those corresponding with the magnesium compounds—and hence two atoms of hydrogen are replaced by one atom of iron. Strongly oxidising acids like nitric acid may transform the ferrous salt which is forming into the higher degree of oxidation or ferric salt (corresponding with the sesquioxide, Fe_2O_3), but this is a secondary phenomenon. Iron, although easily soluble in dilute nitric acid, loses this property when plunged into strong fuming nitric acid; after this operation it even loses the property of solubility in other acids until the external coating formed by the action of the strong nitric acid is mechanically removed. This condition of iron is termed the passive state. *The passive condition* of iron depends on the formation, on its surface, of a coating of oxide due to the iron being acted on by the lower oxides of nitrogen contained in the fuming nitric acid.¹⁶ Strong nitric acid, which does not contain these lower oxides, does not render iron passive, but it is only necessary to add some alcohol or other reducing agent which forms these lower oxides in the nitric acid, and the iron will assume the passive state. Passive iron has a practical application in galvanic couples.

Iron readily combines with non-metals—for instance, with chlorine,

¹⁴ Based on the rapid oxidation of iron and its increase in volume in the presence of water and salts of ammonium, a packing is used for water mains and steam pipes which is tightly hammered into the socket joints. This packing consists of a mixture of iron filings and a small quantity of sal-ammoniac (and sulphur) moistened with water; after a certain lapse of time, especially after the pipes have been used, this mass swells to such an extent that it hermetically seals the joints of the pipes.

¹⁵ Here, however, a ferric salt may also be formed (when all the iron has dissolved and the cupric salt is still in excess), because the cupric salts are reduced by ferrous salts. Cast iron is also dissolved.

¹⁶ Powdery reduced iron is passive with regard to nitric acid of a specific gravity of 1.37, but when heated the acid acts on it. This passiveness disappears in the magnetic field. Saint Edme attributes the passiveness of iron (and nickel) to the formation of nitride of iron on the surface of the metal, because he observed that when heated in dry hydrogen ammonia is evolved by passive iron.

Remsen observed that if a strip of iron be immersed in acid and placed in the magnetic field, it is principally dissolved at its fore part—that is, the acid acts more feebly at the poles.

iodine, bromine, sulphur, and even with phosphorus and carbon ; but, on the other hand, the property of combining with metals is but little developed in it—that is to say, it does not easily form alloys. Mercury, which acts on most metals, does not act directly on iron, and the *iron amalgam*, or solution of iron in mercury, which is used for electrical machines, is only obtained in a particular way—namely, with the co-operation of a sodium amalgam, in which the iron dissolves and by means of which it is reduced from solutions of its salts.

When iron acts on acids it forms ferrous salts of the type FeX_2 , and in the presence of air and oxidising agents they change by degrees into ferric salts of the type FeX_3 . This faculty of passing from the ferrous to the ferric state is still further developed in ferrous hydroxide. If sodium hydroxide be added to a solution of ferrous sulphate, or green vitriol, FeSO_4 ,¹⁷ a white precipitate of ferrous hydroxide, FeH_2O_2 , is obtained ; but on exposure to the air, even under water, it turns green, becomes grey, and finally turns brown, which is due to the oxidation that it undergoes. Ferrous hydroxide is very sparingly soluble in water ; the solution has, however, a clearly alkaline reaction,

¹⁷ *Iron vitriol* or *green vitriol*, sulphate of iron or ferrous sulphate, crystallises from solutions, like magnesium sulphate, with seven molecules of water, $\text{FeSO}_4 \cdot 7\text{H}_2\text{O}$. This salt is not only formed by the action of iron on sulphuric acid, but also by the action of moisture and air on iron pyrites, especially when previously roasted ($\text{FeS}_2 + \text{O}_2 = \text{FeS} + \text{SO}_2$), and in this condition it easily absorbs the oxygen of damp air ($\text{FeS} + \text{O}_4 = \text{FeSO}_4$). A vast amount of green vitriol is obtained in many processes, very often as a bye product. Ferrous sulphate, like all the ferrous salts, has a pale greenish colour hardly perceptible in solution. If it be desired to preserve it without change—that is, so as not to contain ferric compounds—it is necessary to keep it hermetically sealed. This is best done by forcing out the air by means of sulphurous anhydride or ether ; sulphurous anhydride, SO_2 , removes oxygen from ferric compounds, which might be formed, and is itself changed into sulphuric acid, and therefore the oxidation of the ferrous compound does not take place in its presence. Unless these precautions are taken, green vitriol turns brown, partly changing into the ferric salt—that is, having absorbed oxygen. When turned brown, it is not completely soluble in water, because during its oxidation a certain amount of free insoluble ferric oxide is formed : $6\text{FeSO}_4 + \text{O}_5 = 2\text{Fe}_2(\text{SO}_4)_3 + \text{Fe}_2\text{O}_3$. In order to cleanse such mixed green vitriol from the oxide, it is necessary to add some sulphuric acid and iron and boil the mixture ; the ferric salt is then transformed into the ferrous state : $\text{Fe}_2(\text{SO}_4)_3 + \text{Fe} = 3\text{FeSO}_4$. The solubility of ferrous sulphate in water is given in Vol. I. p. 71, Note 24.

Green vitriol is used for the manufacture of Nordhausen sulphuric acid, for preparing ferric oxide, in many dye works (for preparing the indigo vats and reducing blue indigo to white), and in many other processes ; it is also a very good disinfectant, and is the cheapest salt from which other compounds of iron may be obtained.

The other ferrous salts (excepting the yellow prussiate, which will be mentioned hereafter) are but little used, and it is therefore unnecessary to dwell upon them. We will only mention *ferrous chloride*, which, in the crystalline state, has the composition $\text{FeCl}_2 \cdot 4\text{H}_2\text{O}$. It is easily prepared ; for instance, by the action of hydrochloric acid on iron, and in the anhydrous state by the action of hydrochloric acid gas on metallic iron at a red heat. The anhydrous ferrous chloride then volatilises in the form of colourless, cubic crystals.

which is due to its being a fairly energetic basic oxide. In any case, ferrous oxide is far more energetic than ferric oxide, so that if ammonia be added to a solution containing a mixture of a ferrous and ferric salt, at first ferric hydroxide only will be precipitated. If barium carbonate, BaCO_3 , be shaken up in the cold with ferrous salts, it does not precipitate them—that is, does not change them into ferrous carbonate; but it completely separates all the iron from the ferric salts in the cold, according to the equation $\text{Fe}_2\text{Cl}_6 + 3\text{BaCO}_3 + 3\text{H}_2\text{O} = \text{Fe}_2\text{O}_3 + 3\text{H}_2\text{O} + 3\text{BaCl}_2 + 3\text{CO}_2$. If ferrous hydroxide be boiled with a solution of potash, the water is decomposed, hydrogen is evolved, and the ferrous hydroxide is oxidised. The ferrous salts are in all respects similar to the salts of magnesium and zinc; they are isomorphous with them, but differ from them in that the ferrous hydroxide is not soluble either in aqueous potash or ammonia. In the presence of an excess of ammonium salts, however, a certain proportion of the iron is not precipitated by alkalis and alkali carbonates, which fact points to the formation of double ammonium salts.¹⁸ The ferrous salts have a dull *greenish* colour, and form solutions also of a pale green colour, whilst the ferric salts have a *brown* or reddish-brown colour. The ferrous salts, being capable of oxidation, form very active reducing agents—for instance, under their action gold chloride, AuCl_3 , deposits metallic gold, nitric acid is transformed into lower oxides, and the highest oxides of manganese also pass into the lower forms of oxidation. All these reactions take place with especial ease in the presence of an excess of acid. This depends on the fact that the ferrous oxide, FeO (or salt), acting as a reducing agent, turns into ferric oxide, Fe_2O_3 (or salt), and in the ferric state it requires more acid for the formation of a normal salt than in the ferrous condition. Thus in the normal ferrous sulphate, FeSO_4 , there is one equivalent of iron to one equivalent of sulphur (in the sulphuric radicle), but in the ferric salt, $\text{Fe}_2(\text{SO}_4)_3$, there is one equivalent of iron to one and a half of sulphur in the form of the elements of sulphuric acid.¹⁹

¹⁸ Ferrous sulphate, like magnesium sulphate, easily forms double salts—for instance, $(\text{NH}_4)_2\text{SO}_4 \cdot \text{FeSO}_4 \cdot 6\text{H}_2\text{O}$. This salt does not oxidise in air so readily as green vitriol.

¹⁹ The transformation of ferrous oxide into ferric oxide is not completely effected in air, as then only a part of the suboxide is turned into ferric oxide. Here most often the so-called magnetic oxide of iron is produced, containing atomic quantities of the suboxide and oxide—namely, $\text{FeO} \cdot \text{Fe}_2\text{O}_3 = \text{Fe}_3\text{O}_4$. This substance, as has been already seen, is found in nature and in iron scale. It is also formed when most ferrous and ferric salts are heated in air; thus, for instance, when ferrous carbonate is heated it loses the elements of carbonic anhydride, and magnetic oxide remains. This oxide of iron is attracted by the magnet, and is hence called magnetic oxide, although it does not always show magnetic properties. If magnetic oxide be dissolved in any acid—for instance, hydrochloric—which does not act as an oxidising agent, a ferrous salt is first formed and

The most simple oxidising agent for transforming ferrous into ferric salts is chlorine in the presence of water—for instance, $2\text{FeCl}_2 + \text{Cl}_2 = \text{Fe}_2\text{Cl}_6$, or, generally speaking, $2\text{FeO} + \text{Cl}_2 + \text{H}_2\text{O} = \text{Fe}_2\text{O}_3 + 2\text{HCl}$. When such a transformation is required it is best to add potassium chlorate and hydrochloric acid to the ferrous solution; chlorine is formed by their mutual reaction, which in this case acts as an oxidising agent. Nitric acid, although more slowly, produces a similar effect. Ferrous salts may be completely and rapidly oxidised into ferric salts by means of some of the higher metallic oxides—for instance, chromic or permanganic acid, HMnO_4 , in the presence of acids—for example, $10\text{FeSO}_4 + 2\text{KMnO}_4 + 8\text{H}_2\text{SO}_4 = 5\text{Fe}_2(\text{SO}_4)_3 + 2\text{MnSO}_4 + \text{K}_2\text{SO}_4 + 8\text{H}_2\text{O}$. This reaction is easily observed by the change of colour, and its termination is easily seen, because potassium permanganate forms solutions of a bright red colour, and when added to a solution of ferrous salts the above reaction immediately takes place *in the presence of acid*, and the solution then fades, because all the substances formed colour the solutions but very feebly. Directly all the ferrous compound has passed into the ferric state, any excess of permanganate which is added communicates a red colour to the liquid.

Thus when ferrous salts are acted on by oxidising agents, they pass into the ferric form, and under the action of reducing agents the reverse reaction occurs. Sulphuretted hydrogen may, for instance, be used for this complete transformation, for under its influence ferric salts are reduced with separation of sulphur—for example, $\text{Fe}_2\text{Cl}_6 + \text{H}_2\text{S} = 2\text{FeCl}_2 + 2\text{HCl} + \text{S}$. Sodium thiosulphate acts in a similar way: $\text{Fe}_2\text{Cl}_6 + \text{Na}_2\text{S}_2\text{O}_3 + \text{H}_2\text{O} = 2\text{FeCl}_2 + \text{Na}_2\text{SO}_4 + 2\text{HCl} + \text{S}$. Metallic iron and metallic zinc,²⁰ in the presence of acids, or sodium amalgam, &c.,

ferric oxide remains, which is also capable of passing into solution. The best way of preparing the hydrate of the magnetic oxide is by decomposing a mixture of ferrous and ferric salts with ammonia; it is, however, indispensable to pour this mixture into the ammonia, and not *vice versa*, as then the ferrous oxide would at first be alone precipitated, and then the ferric oxide. The compound thus formed has a bright green colour, and when dried forms a black powder. Other combinations of ferrous with ferric oxide are known, as are also compounds of ferric oxide with other bases. Thus, for instance, there are known compounds of 4 molecules of ferrous oxide and 1 of ferric oxide, and also 6 of ferrous and 1 of ferric oxide. These are also magnetic, and are formed by heating iron in air. The magnesium compound $\text{MgO}, \text{Fe}_2\text{O}_3$ is prepared by passing gaseous hydrochloric acid over a heated mixture of magnesia and ferric oxide. Crystalline magnesium oxide is then formed, and black, shiny, octahedral crystals of the above-mentioned composition. This compound is analogous to the aluminates—for instance, to spinel.

²⁰ Copper and cuprous salts also reduce ferric oxide to ferrous oxide, and are themselves turned into cupric salts. The essence of the reactions is expressed by the following equations: $\text{Fe}_2\text{O}_3 + \text{Cu}_2\text{O} = 2\text{FeO} + 2\text{CuO}$; $\text{Fe}_2\text{O}_3 + \text{Cu} = 2\text{FeO} + \text{CuO}$. This fact is made use of in analysing copper compounds, the quantity of copper being ascertained by the amount of ferrous salt obtained. An excess of ferric salt is required to complete the reaction. Here we have an example of reverse reaction; the ferrous oxide or its salt in

act like hydrogen, and have also a similar reducing action, and this furnishes the best method for reducing ferric salts into ferrous salts—for instance, $\text{Fe}_2\text{Cl}_6 + \text{Zn} = 2\text{FeCl}_2 + \text{ZnCl}_2$. Thus the transition from ferrous salts to ferric salts and vice versa is always possible.²¹

Ferric oxide, or sesquioxide of iron, Fe_2O_3 , is found in nature, and is artificially prepared in the form of a red powder by many methods. Thus after heating green vitriol a red oxide of iron remains, called *colcothar*, which is used as an oil paint, principally for painting wood. The same substance in the form of a very fine powder (*rouge*) is used for polishing glass, steel, and other objects. If ferrous sulphate is mixed with an excess of common salt and heated, crystalline ferric oxide will be formed, having a dark violet colour, and resembling some natural varieties of this substance. When iron pyrites is heated for preparing sulphurous anhydride, ferric oxide also remains behind. On the addition of alkalis to a solution of ferric salts, a brown precipitate of ferric hydroxide is formed, which when heated (even when boiled in water, that is, at about 100° , according to Tomassi) easily parts with the water, and leaves red anhydrous ferric oxide. Pure ferric oxide does not show any magnetic properties, but when heated to a white heat it loses oxygen and is converted into the magnetic oxide. Anhydrous ferric oxide which has been heated to a high temperature is with difficulty soluble in acids (but is soluble when heated in strong acids, and also when fused with potassium hydrogen sulphate), whilst ferric hydroxide, at all events that which is precipitated from salts by means of alkalis, is very readily soluble in acids. The precipitated *ferric hydroxide* has the composition $2\text{Fe}_2\text{O}_3 \cdot 3\text{H}_2\text{O}$, or $\text{Fe}_4\text{H}_6\text{O}_9$. If this ordinary hydroxide is rendered anhydrous (at 100°), at a certain moment it, as it were, burns—that is, loses a certain quantity of heat.

the presence of alkali transforms the cupric oxide into cuprous oxide and metallic copper, as observed by Lovel, Knopp, and others.

²¹ We will mention those reactions by means of which it may be ascertained whether the ferrous compound has been entirely converted into a ferric compound or *vice versa*. There are two substances which give the best reactions for this purpose: potassium ferricyanide, $\text{FeK}_3\text{C}_6\text{N}_6$, and thiocyanate, KCNS. The first salt gives with ferrous salts a blue precipitate of an insoluble salt, having a composition $\text{Fe}_3\text{C}_{12}\text{N}_{12}$; but with ferric salts it does not form any precipitate, and only gives a brown colour, and therefore when transforming a ferrous salt into a ferric salt, the completion of the transformation may be detected by taking a drop of the liquid on paper or white china and adding a drop of the ferricyanide solution. If a blue precipitate be formed, then part of the ferrous salt still remains; if there is none, it means that the transformation is complete. The thiocyanate does not give any marked coloration with ferrous salts; but with ferric salts in the most diluted state it forms a bright red soluble compound, and therefore when transforming a ferric salt into a ferrous salt, we must proceed as before, testing a drop of the solution with thiocyanate, when the absence of a red colour will prove the total transformation of the ferric salt into the ferrous state, and if a red colour is apparent it shows that the transformation is not yet complete.

This self-incandescence depends on internal displacement produced by the transition of the easily-soluble (in acids) variety into the difficultly-soluble variety, but does not depend on the loss of water, because the anhydrous oxide undergoes the same change. In addition to this there exists a ferric hydroxide, or hydrated oxide of iron, just as difficultly soluble in acids as strongly-heated anhydrous iron oxide is. This hydroxide losing water, or after the loss of water, does not undergo such self-incandescence, because no such state of internal displacement occurs (loss of energy or heat) with it as that which is peculiar to the ordinary oxide of iron. The ferric hydroxide which is difficultly soluble in acids has the composition $\text{Fe}_2\text{O}_3 \cdot \text{H}_2\text{O}$. This hydroxide is obtained by a prolonged ebullition of water in which is suspended ferric hydroxide prepared by the oxidation of ferrous oxide, and also sometimes by similar treatment of the ordinary hydroxide after it has been for a long time in contact with water. The transition of one hydroxide to another is apparent by a change of colour; the easily-soluble hydroxide is redder, and the sparingly-soluble hydroxide more yellow in colour.²²

The normal salts of the composition Fe_2X_6 correspond with ferric oxide; for example, the exceedingly volatile *ferric chloride*, Fe_2Cl_6 , which is easily prepared in the anhydrous state by the action of chlorine on heated iron.²³ Such also is the *normal ferric nitrate*, $\text{Fe}_2(\text{NO}_3)_6$;

²² The two ferric hydroxides are not only characterised by the above-mentioned properties, but also by the fact that the first hydroxide forms immediately with potassium ferrocyanide, $\text{K}_4\text{FeC}_6\text{N}_6$, a blue colour depending on the formation of prussian blue, whilst the second hydroxide does not give any reaction whatever with this salt. The first hydroxide is entirely soluble in nitric, hydrochloric, and all other acids; whilst the second sometimes (not always) forms a brick-coloured liquid, which appears turbid and does not give the reactions peculiar to the ferric salts (Péan de Saint Gilles, Scheurer-Kestner). In addition to this, when the smallest quantity of an alkaline salt is added to this liquid, ferric oxide is precipitated. Thus a colloidal solution is formed (hydrosol), which is exactly similar to silica hydrosol (Chapter XVII.), according to which example the hydrosol of ferric oxide may be obtained.

If ordinary ferric hydroxide is dissolved in acetic acid, a solution of the colour of red wine is obtained, which has all the reactions characteristic of ferric salts. But if this solution (formed in the cold) is heated to the boiling-point, its colour is very rapidly intensified, a smell of acetic acid becomes apparent, and the solution then contains a new variety of ferric oxide. If the boiling of the solution be continued, acetic acid is evolved, and the modified ferric oxide is precipitated. If the evaporation of the acetic acid be prevented (in a closed vessel), and the liquid be heated for some time, the whole of the ferric hydroxide then passes into the soluble form, and if some alkaline salt be added (to the hydrosol formed), the whole of the ferric oxide is then precipitated in its insoluble form. This method may be applied for separating ferric oxide from solutions of its salts.

All phenomena observed respecting ferric oxide (colloidal properties, various forms, formation of double basic salts) demonstrate that this substance, like silica, alumina, lead hydroxide, &c., is polymerised, that the composition is represented by $(\text{Fe}_2\text{O}_3)_n$.

²³ The ferric compound which is most used in practice (for instance, in medicine, for

it is obtained by dissolving iron in an excess of nitric acid, taking care as far as possible to prevent any rise of temperature.²¹ The normal salt separates from the brown solution when it is concentrated under

cauterising, stopping bleeding, &c.—Oleum Martis) is *ferric chloride*, Fe_2Cl_6 , obtained in solution—for instance, as $2\text{Fe}_2\text{O}_3 \cdot 3\text{H}_2\text{O} + 14\text{HCl}$. It is obtained in the anhydrous state by the action of chlorine on heated iron. The experiment is carried on in a porcelain tube, and a solid *volatile substance* is then formed in the shape of brilliant violet scales which very readily absorb moisture from the air, and when heated with water decompose into crystalline ferric oxide and hydrochloric acid: $\text{Fe}_2\text{Cl}_6 + 3\text{H}_2\text{O} = 6\text{HCl} + \text{Fe}_2\text{O}_3$. Ferric chloride is so volatile that the density of its vapours may be determined. At 440° it is equal to $164\cdot0$ referred to hydrogen; the formula Fe_2Cl_6 corresponds with a density of $162\cdot5$. An aqueous solution of this salt has a brown colour. On evaporating and cooling this solution, crystals separate containing 6 or 12 molecules of H_2O . Ferric chloride is not only soluble in water, but also in alcohol (similarly to magnesium chloride, &c.) and in ether. If the latter solutions are exposed to the rays of the sun they become colourless, and deposit ferrous chloride, FeCl_2 , chlorine being disengaged. After a certain lapse of time, the aqueous solutions of ferric chloride decompose with precipitation of a basic salt, thus demonstrating the instability of ferric chloride, like the other salts of ferric oxide. This salt is much more stable in the form of double salts, as are all the ferric salts and also the salts of many other feeble bases. Potassium or ammonium chloride forms with it very beautiful red crystals of a double salt, having the composition $\text{Fe}_2\text{Cl}_6 \cdot 4\text{KCl} \cdot 2\text{H}_2\text{O}$. When a solution of this salt is evaporated, it decomposes, with separation of potassium chloride.

²⁴ The normal ferric salts are decomposed by heat and even by water, forming basic salts, which may be prepared in various ways. Generally ferric hydroxide is dissolved in solutions of ferric nitrate; if it contains a double quantity of iron the basic salt is then formed, which, therefore, contains Fe_2O_3 (in the form of hydroxide) + $2\text{Fe}_2(\text{NO}_3)_6 = 3\text{Fe}_2\text{O}(\text{NO}_3)_4$, a salt of the type Fe_2OX_4 . Probably water enters into its composition. With considerable quantities of ferric oxide, insoluble basic salts are obtained containing various amounts of ferric hydroxide. Thus when a solution of the above-mentioned basic salt is boiled, a precipitate is formed containing $4(\text{Fe}_2\text{O}_3)_8 \cdot 2(\text{N}_2\text{O}_5)_8 \cdot 3\text{H}_2\text{O}$, which probably contains $2\text{Fe}_2\text{O}_2(\text{NO}_3)_2 + 2\text{Fe}_2\text{O}_5 \cdot 3\text{H}_2\text{O}$. If a solution of basic nitrate be sealed in a tube and then immersed in boiling water, the colour of the solution changes just in the same way as if a solution of ferric acetate had been employed. The solution obtained smells strongly of nitric acid, and on adding a drop of sulphuric or hydrochloric acid the insoluble variety of hydrated ferric oxide is precipitated.

Normal ferric *orthophosphate* is soluble in sulphuric, hydrochloric and similar acids, but insoluble in others, such as, for instance, acetic acid. The composition of this salt in the anhydrous state is FePO_4 , because in orthophosphoric acid there are three atoms of hydrogen, and iron, in the ferric state, replaces the three parts of hydrogen. This salt is obtained from ferric acetate, which, with disodium phosphate, forms a *white precipitate* of FePO_4 , containing water (on boiling, 2 mol. H_2O). It is simplest to proceed as follows: A solution of ferric chloride (yellowish red colour) is mixed with a solution of sodium acetate in excess (this must be done first and not afterwards). The liquid then assumes an intense brown colour which demonstrates the formation of a certain quantity of ferric acetate; then the disodium phosphate directly forms a white gelatinous precipitate of ferric phosphate. Here the whole of the iron may be precipitated, and the liquid from brown then becomes colourless. If this normal salt be immersed in orthophosphoric acid, the crystalline acid salt $\text{FeH}_7(\text{PO}_4)_2$ is formed. If there is an excess of ferric oxide in the solution, the precipitate will consist of the basic salt. If ferric phosphate be dissolved in hydrochloric acid, and ammonia be added, on heating, a salt is precipitated which, after continued washing in water and heating (to remove the water), has the composition $\text{Fe}_4\text{P}_2\text{O}_{11}$ —that is, $2\text{Fe}_2\text{O}_5 \cdot \text{P}_2\text{O}_5$. In an aqueous condition this salt may be considered as ferric hydroxide, $\text{Fe}_4(\text{OH})_6$, in which $(\text{OH})_6$ is replaced by the equivalent (judging from

a bell jar over sulphuric acid. This salt, $\text{Fe}_2(\text{NO}_3)_6 \cdot 9\text{H}_2\text{O}$, then crystallises in well-formed and completely colourless crystals,²⁵ which deliquesce in air, melt at 35° , and are soluble in and decomposed by water. The decomposition may be seen from the fact that the solution is brown and does not yield the whole of the salt again, but gives partly basic salt. The normal salt is completely decomposed with great facility by heating with water, even at 130° , and this is made use of for removing iron (and also certain other oxides of the form R_2O_3) from many other bases (of the form RO) whose nitrates are far more stable.

Iron forms one more oxide besides the ferric and ferrous oxides; this contains twice as much oxygen as the former, but is so very unstable that it can neither be obtained in the free state nor as a hydrate. Whenever such conditions of double decomposition occur as should allow of its separation in the free state, it decomposes into oxygen and ferric oxide. It is known in the state of salts, and is only stable in the presence of alkalis, and forms salts with them which have a decidedly alkaline reaction; it is therefore a feebly acid oxide. Thus when small pieces of iron are heated with nitre or potassium chlorate, a potassium salt of the composition K_2FeO_4 is formed, and therefore the hydrate corresponding with this salt should have the composition H_2FeO_4 . It is called *ferric acid*. Its anhydride ought to contain FeO_3 or Fe_2O_6 —twice as much oxygen as ferric oxide. If a solution of potassium ferrate is mixed with acid, the free hydrate ought to be formed, but it immediately decomposes



the formation of Na_3PO_4 from 3NaHO) group PO_4 . Whenever ammonia is added to a solution containing an excess of ferric salt and a certain amount of phosphoric acid, a precipitate is formed containing the whole of the phosphoric acid in the mass of the ferric oxide.

Ferric oxide is characterised as a feeble base, and also by the fact of its forming double salts—for instance, *potassium iron alum*, which has a composition $\text{Fe}_2(\text{SO}_4)_5 \cdot \text{K}_2\text{SO}_4 \cdot 24\text{H}_2\text{O}$ or $\text{FeK}(\text{SO}_4)_2 \cdot 12\text{H}_2\text{O}$. It is obtained in the form of almost colourless or light rose-coloured large octahedra of the regular system by simply mixing solutions of potassium sulphate and the ferric sulphate obtained by dissolving ferric oxide in sulphuric acid.

²⁵ It would seem that all normal ferric salts are colourless, and that the brown colour which is peculiar to the solutions is really due to basic ferric salts. A remarkable example of the seeming change of colour of salts is represented by the ferrous and ferric oxalates. The former in a dry state has a yellow colour, although, as a rule, the ferrous salts are green, and the latter is colourless or pale green. When the normal ferric salt is dissolved in water it is, like many salts, probably decomposed by the water into acid and basic salt, and the latter communicates a brown colour to the solution. Iron alum is almost colourless, is easily decomposed by water, and is the best proof of our supposition. The study of the phenomena peculiar to ferric nitrate might, in my opinion, give a very useful addition to our knowledge of the aqueous solutions of salts. Ferrous

oxygen being evolved. If a small quantity of acid be taken, or if a solution of potassium ferrate be heated with solutions of other metallic salts, ferric oxide is separated, for instance :



Both these oxides are naturally deposited in the form of hydrates. This shows that not only the hydrate H_2FeO_4 , but also the salts of the heavy metals corresponding with this higher oxide of iron, are not formed by reactions of double decomposition. The solution of potassium ferrate naturally acts as a powerful oxidising agent ; for instance, it transforms manganous oxide into the dioxide, sulphurous into sulphuric acid, oxalic acid into carbonic anhydride and water, &c.²⁶

Iron thus combines with oxygen in three proportions : RO , R_2O_3 , and RO_3 . It might have been expected that there would be intermediate stages RO_2 and R_2O_5 , but for iron these are unknown. The lower oxide has a distinctly basic character, the higher is feebly acid. The only one which is stable in the free state is ferric oxide, Fe_2O_3 ; the suboxide, FeO , absorbs oxygen, and ferric anhydride, FeO_3 , evolves it. It is also the same for other elements ; the character of each is determined by the relative degree of stability of the known oxides. The salts FeX_2 correspond with the suboxide, the salts FeX_3 or Fe_2X_6 with the sesquioxide, and FeX_6 represents those of ferric acid, as its potassium salt is $\text{FeO}_2(\text{OK})_2$, corresponding with K_2SO_4 , K_2MnO_4 , K_2CrO_4 , &c. Iron therefore forms compounds of the types FeX_2 , FeX_3 , and FeX_6 , but this latter, like the type NX_5 , does not appear separately, but only when X represents heterogeneous elements or groups ; for instance, for nitrogen in the form of $\text{NO}_2(\text{OH})$, NH_4Cl , &c., for iron in the form of $\text{FeO}_2(\text{OK})_2$. But still the type FeX_6 exists, and therefore FeX_2 and FeX_3 are compounds like ammonia, NH_3 , which are capable of further combinations up to FeX_6 and further, which is expressed in the

oxalate, and its double salt with potassium oxalate, act as powerful reducing agents, and the latter is on this account used in photography (as a developer).

²⁶ If chlorine be passed through a strong solution of potassium hydroxide in which hydrated ferric oxide is suspended, the turbid liquid acquires a dark pomegranate red colour and contains potassium ferrate : $10\text{KHO} + \text{Fe}_2\text{O}_3 + 3\text{Cl}_2 = 2\text{K}_2\text{FeO}_4 + 6\text{KCl} + 5\text{H}_2\text{O}$. The chlorine must not be in excess, otherwise the salt is again decomposed, although the mode of decomposition is unknown ; however, ferric chloride and potassium chlorate are probably formed. Another way in which the above-described salt is formed is also remarkable ; a galvanic current (from 6 Grove elements) is passed through cast-iron and platinum electrodes into a strong solution of potassium hydroxide. The cast-iron electrode is connected with the positive pole, and the platinum electrode is surrounded by a porous earthen cylinder. Oxygen ought to be evolved at the cast-iron electrode, but it is used up in oxidation, and a dark solution of potassium ferrate is then formed about it. It is remarkable that the cast iron cannot be replaced by wrought iron.

property of ferrous and ferric salts of forming compounds with water of crystallisation, double and basic salts, whose stability is determined by the quality of the elements included in the types FeX_2 and FeX_3 . When the molecule Fe_2Cl_6 is produced instead of FeCl_3 , this complication of the type also occurs. Therefore complex compounds may be expected to correspond with ferrous and ferric oxides. Amongst these the series of cyanogen compounds is particularly interesting; their formation and character is not only determined by the property which iron possesses of forming complex types, but also by the similar faculty of the cyanogen compounds, which, like nitriles (Chapter IX.), have clearly developed properties of polymerisation and in general of forming complex compounds.

In the cyanogen compounds of iron, two degrees might be expected: $\text{Fe}(\text{CN})_2$, corresponding with ferrous oxide, and $\text{Fe}(\text{CN})_3$, corresponding with ferric oxide. There are actually, however, many other known compounds, intermediate and far more complex. They correspond with the double salts so easily formed by metallic cyanides. The two following double salts are particularly well known, very stable, often used, and easily prepared. *Potassium ferrocyanide*, or *yellow prussiate of potash*, a double salt of cyanide of potassium and ferrous cyanide, has the composition $\text{FeC}_2\text{N}_{12}\cdot 4\text{KCN}$, its crystals contain 3 mol. of water: $\text{K}_4\text{FeC}_6\text{N}_6\cdot 3\text{H}_2\text{O}$. The other is *potassium ferricyanide* or *red prussiate of potash* or *Gmelin's salt*, containing cyanide of potassium with ferric cyanide; its composition is $\text{Fe}(\text{CN})_3\cdot 3\text{KCN}$ or $\text{K}_3\text{FeC}_6\text{N}_6$. Its crystals do not contain water. The second differs from the first in its containing, not four but, only three atoms of potassium, and is obtained from the first by the action of chlorine, which removes one atom of the potassium. A whole series of other ferrocyanic compounds correspond with these ordinary salts.

Before treating of the preparation and properties of these two remarkable and very stable salts, it must be observed that with ordinary reagents neither of them gives the same double decompositions as the other ferrous and ferric salts, nor exhibits the characteristic properties of the potassium cyanide which they contain. Thus these salts have a neutral reaction, are unchanged by air, dilute acids, or water, unlike potassium cyanide and even some of its double salts. When solutions of these salts are treated with potassium hydroxide, they do not give a precipitate of ferrous or ferric hydroxides, neither are they precipitated by sodium carbonate. This led the earlier investigators to recognise special independent groupings in them. The yellow prussiate was considered to contain the complex radicle FeC_6N_6 combined with potassium, namely with K_4 , and K_3 was attributed to the red

prussiate, or else another radicle $\text{Fe}_2\text{C}_{12}\text{N}_{12}$ combined with K_6 was assumed to be present. This was confirmed by the fact that whilst in both salts any other metal, even hydrogen, might be substituted for potassium, the iron remained unexchangeable, just as nitrogen in the cyanogen, ammonium, and nitrates does not enter into double decomposition, being in the state of the complex radicles CN , NH_4 , NO_2 . Such a representation is, however, completely superfluous for the explanation of the peculiarities in the reactions of such compounds as double salts. If a magnesium salt which can be precipitated by potassium hydroxide does not form a precipitate in the presence of ammonium chloride, it is very clear that it is owing to the formation of a soluble double salt which is not decomposed by alkalis. And there is no necessity to account for the peculiarity of reaction of a double salt by the formation of a new complex radicle. In the same way also, in the presence of an excess of tartaric acid cupric salts do not form a precipitate with potassium hydroxide, because a double salt is formed. These peculiarities are more easily understood in the case of cyanogen compounds than in all others, because all cyanogen compounds, as unsaturated compounds, show a marked tendency to complexity. This tendency is satisfied in double salts. The appearance of a peculiar character in double cyanides is the more easily understood as in the case of potassium cyanide itself, and also in hydrocyanic acid, a great many peculiarities have been observed which are not encountered in those haloid compounds, potassium chloride and hydrochloric acid, with which it was usual to compare cyanogen compounds. These peculiarities become more comprehensible on comparing cyanogen compounds with ammonium compounds. Thus in the presence of ammonia the reactions of many compounds change considerably. If, in addition to this, it is remembered that the presence of many carbon (organic) compounds frequently completely disturbs the reaction of salts, the peculiarities of many double cyanides will appear still less strange, because they contain carbon. The fact that the presence of carbon or another element in the compound produces a change in the reactions, may be likened to the action of oxygen, which, when entering into a combination, also very materially changes the nature of reactions. Chlorine is not detected by silver nitrate if it is in the form of potassium chlorate, KClO_3 , as it is detected in potassium chloride, KCl . The iron in ferrous and ferric compounds varies in its reactions. In addition to the above-mentioned facts, consideration ought to be given to the circumstance that the mutability of nitric acid disappears or undergoes considerable modification in its alkali salts, and in general the properties of a salt often differ much from those of the acid. Every

double salt ought to be regarded as a peculiar kind of saline compound ; potassium cyanide is, as it were, a basic, and ferrous cyanide an acid, element. They may be unstable in the separate state, but form a stable double compound when combined together ; the act of combination disengages the energy of the elements, and they, so to speak, saturate each other. Naturally, all this is not a definite explanation, but then the admission of a special complex radicle can even less be regarded as such.


Potassium ferrocyanide, $K_4FeC_6N_6$, is very easily formed by mixing solutions of ferrous sulphate and potassium cyanide. First, a white precipitate of ferrous cyanide, FeC_2N_2 , is formed, which becomes blue on exposure to air, but is soluble in an excess of potassium cyanide, forming the ferrocyanide. The same yellow prussiate is obtained on heating animal nitrogenous charcoal or animal matters—for instance, horn, leather cuttings, &c. —with potassium carbonate in iron vessels,²⁷ the mass formed being afterwards boiled with water with exposure to air, potassium cyanide first appearing, which gives yellow prussiate. In this manner it is manufactured on the large scale, and is called ‘yellow prussiate’ (‘prussiate de potasse,’ Blutlaugensalz). The animal charcoal may be exchanged for wood charcoal, permeated with potassium carbonate and heated in air—that is, nitrogen ; the mass thus produced is then boiled in water with ferric oxide.²⁸

It is easy to substitute other metals for the potassium in the yellow prussiate. The hydrogen salt or hydroferrocyanic acid, $H_4FeC_6N_6$, is obtained by mixing strong solutions of yellow prussiate and hydrochloric acid. If ether be added and the air be excluded, the acid is obtained directly, in the form of a white, scarcely crystalline precipitate which becomes blue on exposure to air (like ferrous cyanide from the formation of blue compounds of ferrous and ferric cyanides, and it is on this account used in cotton printing). It is soluble in water and alcohol, but not in ether, has marked acid properties, decomposes car-

²⁷ The sulphur of the animal refuse here forms the compound $FeKS_2$, which, by the action of potassium cyanide, yields potassium sulphide, thiocyanate, and ferrocyanide.

²⁸ Potassium ferrocyanide may also be obtained from prussian blue by boiling with a solution of potassium and hydroxide, and from the ferricyanide by the action of alkalis and reducing substances (because the red prussiate is a product of oxidation produced by the action of chlorine : a ferric salt is reduced to a ferrous salt), &c. On evaporation the solution yields large pliable crystals containing 3 molecules of water, which is easily expelled by heating above 100° . 100 parts of water at the ordinary temperature are capable of dissolving 25 parts of this salt ; its sp. gr. is 1.83. When ignited it forms potassium cyanide and iron carbide, FeC_2 . Oxidising substances change it into potassium ferricyanide. With strong sulphuric acid it gives carbonic oxide, and with dilute sulphuric acid, when heated, prussic acid is evolved according to the equation : $2K_4FeC_6N_6 + 3H_2SO_4 = K_2Fe_2C_6N_6 + 3K_2SO_4 + 6HCN$; hence in the yellow prussiate K_2 replaces Fe .

bonates, which renders it possible to readily prepare ferrocyanides of the metals of the alkalis and alkaline earths ; these are readily soluble, have a neutral reaction, and resemble the yellow prussiate. Solutions of these salts form precipitates with the salts of other metals, because the ferrocyanides of the heavy metals are insoluble. Here the whole of the potassium of the yellow prussiate, or only a part of it, is exchanged for an equivalent quantity of the heavy metal. Thus, when a cupric salt is added to a solution of yellow prussiate, a red precipitate is obtained which still contains half the potassium of the yellow prussiate :



But if the process be reversed (the salt of copper will then be in excess) the whole of the potassium will be exchanged for copper, forming a reddish-brown precipitate, $\text{Cu}_2\text{FeC}_6\text{N}_6 \cdot 9\text{H}_2\text{O}$. This reaction, and also those similar to it, are very sensitive, and may be used for testing metals in solution, more especially as the colour of the precipitate very often shows a marked difference when one metal is exchanged for another. Zinc, cadmium, lead, antimony, tin, silver, cuprous and aurous salts form *white* precipitates ; cupric, uranium, titanium, and molybdenum salts form *reddish-brown* ; those of nickel, cobalt, and chromium, *green* precipitates ; *with ferrous salts*, ferrocyanide forms, as has been already mentioned, a *white* precipitate—namely, $\text{Fe}_2\text{FeC}_6\text{N}_6$, or FeC_2N_2 —which turns blue on exposure to air, and, with ferric salts, a *blue precipitate* called *prussian blue*. Here the potassium is replaced by iron, the reaction being expressed thus : $2\text{Fe}_2\text{Cl}_6 + 3\text{K}_4\text{FeC}_6\text{N}_6 = 12\text{KCl} + \text{Fe}_4\text{Fe}_3\text{C}_{18}\text{N}_{18}$, the latter formula expressing the composition of prussian blue. It is therefore the compound $4\text{Fe}(\text{CN})_3 + 3\text{Fe}(\text{CN})_2$. The yellow prussiate is prepared in chemical works on a large scale, especially for the manufacture of this blue pigment, which is used for dyeing cloth and other fabrics, and also as one of the ordinary blue paints. It is insoluble in water, and the stuffs are therefore dyed by first soaking them in a solution of a ferric salt, and then in a solution of yellow prussiate. However, if there be an excess of yellow prussiate, complete substitution between potassium and iron does not occur, and *soluble blue* is formed : $\text{KFe}_2(\text{CN})_6 = \text{KCN}, \text{Fe}(\text{CN})_2, \text{Fe}(\text{CN})_3$. This blue salt is colloidal, is soluble in pure water, but insoluble and precipitated when other salts—for instance, potassium or sodium chloride—are present, even in small quantities, and is therefore first obtained as a precipitate.²⁹

²⁹ Skraup obtained this salt both from potassium ferrocyanide with ferric chloride and from ferriecyanide with ferrous chloride, which evidently shows that it contains iron

Potassium ferricyanide, or *red prussiate* of potash, $K_3FeC_6N_6$, is called 'Gmelin's salt,' because this savant obtained it by the action of chlorine on a solution of the yellow prussiate: $K_4FeC_6N_6 + Cl = K_3FeC_6N_6 + KCl$. The reaction is due to the ferrous salt being changed by the action of the chlorine into a ferric salt. It separates from solutions in anhydrous, finely-formed prisms of a red colour, but the solution has an olive colour; in 100 parts of water, at 10° , 37 parts of the salt are dissolved, and at 100° 78 parts.³⁰ The red prussiate gives a blue precipitate with ferrous salts, called *Turnbull's blue*, very much like prussian blue (and the soluble blue), because it also contains ferrous cyanide and ferric cyanide, although in another propor-

in both the ferric and ferrous states. With ferrous chloride it forms prussian blue, and with ferric chloride Turnbull's blue.

Prussian blue was discovered in the beginning of the past century by a Berlin manufacturer, Diesbach. It was then prepared, as it sometimes is also at present, directly from potassium cyanide obtained by heating animal charcoal with potassium carbonate. The mass thus obtained is dissolved in water, and alum is added to the solution in order to saturate the free alkali, and then a solution of green vitriol is added which has previously been sufficiently exposed to the air to contain both ferric and ferrous salts. If the solution of potassium cyanide is mixed with a solution containing both salts, prussian blue will be formed, because it is a compound of ferrous cyanide, FeC_2N_2 , and ferric cyanide, $Fe_2C_6N_6$. A ferric salt with potassium ferrocyanide forms a blue colour, because ferrous cyanide is obtained from the first salt and ferric cyanide from the second. During the preparation of this compound alkali must be avoided, as otherwise the precipitate would contain oxides of iron. Prussian blue has not a crystalline structure; it forms a blue mass with a copper-red metallic lustre. Both acids and alkalis act on it. The action is at first confined to the ferric salt it contains. Thus alkalis form ferric oxide and ferrocyanide in solution: $2Fe_2C_6N_6 + 3FeC_2N_2 + 12KHO = 2(Fe_2O_3, 3H_2O) + 3K_4FeC_6N_6$. Various ferrocyanides may be thus prepared. Prussian blue is soluble in an aqueous solution of oxalic acid, forming blue ink. In air, when exposed to the action of light, it fades; but in the dark again absorbs oxygen and becomes blue, which fact is also sometimes noticed in blue cloth. An excess of potassium ferrocyanide renders prussian blue soluble in water, although insoluble in various saline solutions—that is, it converts it into soluble blue. Strong hydrochloric acid likewise dissolves prussian blue.

⁵⁰ Much chlorine must not be taken in preparing this compound, otherwise the reaction goes further. It is easy to find when the action of the chlorine on potassium ferrocyanide must cease; it is only necessary to take a sample of the liquid and add a solution of a ferric salt to it. If there is a precipitate of prussian blue formed, then more chlorine must be added, as there is still some undecomposed ferrocyanide, because the ferricyanide does not give a precipitate with ferric salts. Potassium ferricyanide, as well as the ferrocyanide, easily exchanges its potassium for hydrogen and various metals by double decomposition. With the salts of tin, silver, and mercury it forms yellow precipitates, and with those of uranium, nickel, cobalt, copper, and bismuth brown precipitates. The lead salt under the action of sulphuretted hydrogen forms lead sulphide and a hydrogen salt or acid, $H_3FeC_6N_6$, corresponding with potassium ferricyanide, which is soluble, crystallises in red needles, and resembles hydroferrocyanic acid, $H_4FeC_6N_6$. Under the action of reducing agents—for instance, sulphuretted hydrogen, copper—potassium ferricyanide is changed into ferrocyanide, especially in the presence of alkalis, and thus forms a rather energetic *oxidising agent*—capable, for instance, of changing manganous oxide into dioxide.

tion, being thus formed: $3\text{FeCl}_2 + 2\text{K}_3\text{FeC}_6\text{N}_6 = 6\text{KCl} + \text{Fe}_2\text{Fe}_4\text{C}_{12}\text{N}_{12}$, or $3\text{FeC}_2\text{N}_2, \text{Fe}_2\text{C}_6\text{N}_6$; whilst in Prussian blue we have $\text{Fe}_7\text{Cy}_{18}$, and here $\text{Fe}_5\text{Cy}_{12}$. A ferric salt ought to form ferric cyanide, $\text{Fe}_2\text{C}_6\text{N}_6$, with red prussiate, but ferric cyanide is soluble, and therefore there is no precipitate, and the liquid only becomes brown.³¹

If chlorine and sodium are representatives of independent groups of elements, the same may also be said of iron. Its nearest analogues alone show, besides a similarity in character, a likeness as regards physical properties and a proximity in atomic weight. Iron occupies a medium position amongst its nearest analogues, both with respect to properties and faculty of forming saline oxides, and also as regards atomic weight. On the one hand, cobalt, 58, and nickel, 59, approach iron, 56; they are metals of a more basic character, they do not form

³¹ It is important to mention a series of readily crystallisable salts formed by the action of nitric acid on potassium and other ferrocyanides and ferricyanides. These salts contain the elements of nitric oxide, and are therefore called *nitro-(nitroso) ferricyanides (nitroprussides)*. Most often a crystalline sodium salt is obtained, $\text{Na}_2\text{FeC}_5\text{N}_6\text{O}, 2\text{H}_2\text{O}$. In its composition this salt differs from the red sodium salt, $\text{Na}_3\text{FeC}_6\text{N}_6$, by the fact that in it one molecule of sodium cyanide, NaCN , is replaced by nitric oxide, NO . In order to prepare it, potassium ferrocyanide in powder must be mixed with five-sevenths of its weight of nitric acid mixed with an equal volume of water. The mixture is at first left at the ordinary temperature, and then heated in a water-bath. Here ferricyanide is first of all formed (as shown by the liquid giving a precipitate with ferrous chloride), which then disappears (no precipitate with ferrous chloride), and forms a green precipitate. The liquid, when cooled, deposits crystals of nitre. The liquid is then strained off and mixed with sodium carbonate, boiled, filtered, and evaporated; sodium nitrate and the salt described are deposited in crystals. It separates in prisms of a red colour. Alkalis and salts of the alkaline earths do not give precipitates; they are soluble, but the salts of iron, zinc, copper, and silver form precipitates where sodium is exchanged with these metals. It is remarkable that the sulphides of the alkali metals give with this salt an intense bright purple coloration. This series of compounds was discovered by Gmelin and studied by Playfair and others (1849).

This series to a certain extent resembles the nitro-sulphide series described by Roussin. Here the primary compound consists of black crystals, which are thus obtained:—Solutions of potassium hydrosulphide and nitrite are mixed, and the mixture is agitated whilst ferric chloride is added, then boiled and filtered; on cooling, *black crystals* are deposited, having the composition $\text{Fe}_3\text{S}_3(\text{NO})_{10}, \text{H}_2\text{O}$ (Rosenberg), or, according to Demel, $\text{FeNO}_2, \text{NH}_2\text{S}$. They have a slightly metallic lustre, and are soluble in water, alcohol, and ether. They absorb the latter as easily as calcium chloride absorbs water. In the presence of alkalis these crystals remain unchanged, but with acids they evolve nitric oxides. It is affirmed that there are several compounds which are capable of interchanging, and correspond with Roussin's salt. Here we enter into the series of the nitrogen compounds which have been as yet but little investigated, and will most probably in time form most instructive material for studying the nature of that element. These series of compounds are as unlike the usual saline compounds of inorganic chemistry as are organic hydrocarbons. There is no necessity to describe these series in detail, because their connection with other compounds is not yet clear, and they have not yet any application; but, all the same, their investigation gives promise of opening out other realms of knowledge in the future of chemistry.

stable acids or higher degrees of oxidation, and are a transition to copper, 63, and zinc, 65. On the other hand, manganese, 55, and chromium, 52, are the nearest to iron; they form both basic and acid oxides, and are a transition to the metals possessing acid properties. In addition to having atomic weights approximately alike, chromium, manganese, iron, cobalt, nickel, and copper have also nearly the same specific gravity, so that the atomic volumes and the molecules of their analogous compounds are also near to one another (see table at the beginning of this volume). Besides this, the likeness between the above-mentioned elements is also seen from the following:

They form suboxides, RO , fairly energetic bases, isomorphous with magnesia—for instance, the salt $RSO_4 \cdot 7H_2O$, akin to $MgSO_4 \cdot 7H_2O$, and $FeSO_4 \cdot 7H_2O$, or to sulphates containing less water; with alkali sulphates all form double salts crystallising with $6H_2O$; all are capable of forming ammonium salts, &c.

The lower hydroxides, in the cases of nickel and cobalt, are fairly stable, are not easily oxidised (the nickel compound with more difficulty than cobalt, a transition to copper); with manganese, and especially with chromium, they are more easily oxidised than with iron and pass into higher oxides.

They also form oxides of the form R_2O_3 , and with nickel, cobalt, and manganese this oxide is very unstable, and is more easily reduced than ferric oxide; but, in the case of chromium, it is very stable, and forms the ordinary kind of salts. It is isomorphous with ferric oxide, forms alums, is a feeble base, &c. Chromium and manganese are more easily oxidised with alkali and oxygen than iron is, forming salts like potassium ferrate; but cobalt and nickel are difficult to oxidise, their acids are not known with any certainty, and are, in all probability, still less stable.

If compounds R_2Cl_6 are formed, they are volatile like Fe_2Cl_6 . The cyanogen compounds, especially for manganese and cobalt, are very near akin to the corresponding ferrocyanides.

The oxides of nickel and cobalt are more easily reduced to metal than those of iron, but those of manganese and chromium are not reduced so easily as iron, and the metals themselves are not easily obtained in a pure state; they are capable of forming varieties resembling cast iron.

The metals have a grey iron colour and are very difficult to melt, but nickel and cobalt can be melted in the reverberatory furnace and are more fusible than iron, whilst chromium is more difficult to melt than platinum (Deville).

When incandescent these metals decompose water, but with greater

difficulty as the atomic weight rises, forming a transition to copper, which does not decompose water.

All the compounds of these metals have various colours, which are sometimes very bright, especially in the higher stages of oxidation.

These metals of the iron group are often met with together in nature. Manganese nearly everywhere accompanies iron, and iron is always an ingredient in the ores of manganese. Chromium is found principally as chrome ironstone—that is, a peculiar kind of magnetic oxide where Fe_2O_3 is replaced by Cr_2O_3 .

Nickel and cobalt are the same inseparable companions as iron and manganese. The similarity between them even extends to such remote properties as magnetic qualities. In this series of metals we find those which are the most magnetic: iron, cobalt, and nickel. There is even a magnetic oxide among the chromium compounds, such as is unknown in the other series. Nickel easily becomes passive in strong nitric acid. It absorbs hydrogen in just the same way as iron.

In nature *cobalt* is principally found in combination with arsenic and sulphur. *Cobalt arsenide*, or *cobalt speiss*, CoAs_2 , is found in brilliant crystals of the regular system, principally in Saxony. *Cobalt glance*, $\text{CoAs}_2\text{CoS}_2$, resembles it very much, and also belongs to the regular system; it is found in Sweden, Norway, and the Caucasus. *Kupfernickel* is a *nickel ore* in combination with arsenic, but of a different composition from cobalt arsenide, having the formula NiAs ; it is found in Bohemia and Saxony. It has a copper red colour and is rarely crystalline; it is so called because the miners of Saxony first mistook it for an ore of copper (*kupfer*), but were unable to extract copper from it. *Nickel glance*, $\text{NiS}_2\text{NiAs}_2$, corresponding with cobalt glance, is also known. Nickel accompanies the ores of cobalt and cobalt those of nickel, so that they are common companions. The ores of cobalt are worked in the Caucasus in the Government of Elizavetopolsk. Nickel ores formed by aqueous hydrated nickel silicate are found in the Ural (Revdansk). Large quantities of a similar ore are exported into Europe from New Caledonia. Both contain about 12 per cent. of Ni. Cobalt is principally worked up into cobalt compounds, but nickel is generally reduced to the metallic state, which is now often used for alloys—for instance, for coinage in many European States, and for plating other metals, because it does not oxidise. Cobalt arsenide and cobalt glance are principally used for the preparation of cobalt compounds; they are first sorted by discarding the rocky matter, and then roasted. During this process most of the sulphur and arsenic disappear; the arsenious anhydride volatilises with the

sulphurous anhydride and the metal also oxidises.⁵² Having nickel oxide and cobalt oxide it is easy to obtain the metals themselves. In order to do this solutions of their salts are treated with sodium carbonate and the carbonates precipitated are heated; the suboxides are thus obtained, and these latter are reduced in a stream of hydrogen, or even by heating with ammonium chloride. They easily oxidise when in the state of powder. When the chlorides of nickel and cobalt are heated in a stream of hydrogen, the metal is deposited in brilliant scales. *Nickel is always much more easily and quickly reduced than cobalt.* Nickel melts more easily than cobalt, and this even furnishes a means of testing the heating powers of a reverberatory furnace. Cobalt fuses at a temperature only a little

⁵² The residue from the roasting of cobalt ores is called *zaffre*, and is often met with in commerce. From this the purer compounds of cobalt may be prepared. The ores of nickel are also first roasted, and the oxide dissolved in acid, nickelous salts being then obtained.

The further treatment of cobalt and nickel ores is facilitated if the arsenic can be almost entirely removed, which may be effected by roasting the ore a second time with a small addition of nitre and sodium carbonate; the nitre combines with the arsenic, forming an arsenious salt, which may be extracted with water. The remaining mass is dissolved in hydrochloric acid, mixed with a small quantity of nitric acid. Copper, iron, manganese, nickel, cobalt, &c., pass into solution. By passing hydrogen sulphide through the solution, copper, bismuth, lead, and arsenic are deposited as metallic sulphides; but iron, cobalt, nickel, and manganese remain in solution. If an alkaline solution of bleaching powder be then added to the remaining solution, the whole of the manganese will first be deposited in the form of dioxide, then the cobalt as hydrated cobaltic oxide, and finally the nickel also. It is, however, impossible to rely on this effecting a complete subdivision, because the higher oxides of the three above-mentioned metals have all a black colour; but, after a few trials, it will be easy to find how much bleaching powder is required to precipitate the manganese, and the amount which will precipitate all the cobalt. The manganese may also be removed by precipitation from a mixture of the solutions of both metals (in the form of the 'ous' salts) with ammonium sulphide, and then treating the precipitate with acetic acid or dilute hydrochloric acid, in which manganese sulphide is easily soluble and cobalt sulphide almost insoluble. Further particulars relating to the separation of cobalt from nickel may be found in treatises on analytical chemistry. In practice it is usual to rely on the rough method of separation founded on the fact that nickel is more easily reduced and more difficult to oxidise than cobalt.

In industry, rather impure cobalt compounds are often used, which are converted into *smalt*. This is glass containing a certain amount of cobalt oxide; the glass acquires a bright blue colour from this addition, so that when powdered it may be used as a blue pigment; it is also unaltered at high temperatures, so that it is used to take the place now occupied by prussian blue, ultramarine, &c. At present smalt is almost exclusively used for colouring glass and china. To prepare smalt, ordinary impure cobalt ore is taken—*i.e.* *zaffre*—which is put into a crucible with quartz and potassium carbonate. A fused mass of cobalt glass is thus formed, containing silica, cobalt oxide, and potassium oxide, and a metallic mass remains at the bottom of the crucible, containing almost all the other metals, arsenic, nickel, copper, silver, &c. This metallic mass is called *speiss*, and is used as nickel ore for the extraction of nickel. Smalt usually contains 70 p.c. of silica, 20 p.c. of potash and soda, and about 5 to 6 p.c. of cobaltous oxide; the remainder consisting of other metallic oxides.

lower than does iron. In general, cobalt is nearer to iron than nickel, nickel being nearer to copper. Both nickel and cobalt have magnetic properties like iron, but more feeble. The specific gravity of nickel reduced by hydrogen is 9.1 and that of cobalt 8.9. Fused cobalt has a specific gravity of 8.5, the density of ordinary nickel being almost the same. Nickel has a greyish, silvery white colour; it is brilliant and very ductile, so that the finest wire may be easily drawn from it. This wire has a resistance to tension equal to iron wire. The beautiful colour of nickel, and the high polish which it is capable of receiving and retaining, as it does not oxidise, render it a useful metal for many purposes. It is now very common to cover other metals with a layer of nickel (nickel plating). This is done by a process of electro-plating, using a solution of a nickel salt. The colour of cobalt is darker and redder; it is also ductile, and has a greater tensile resistance than iron. Dilute acids act very slowly on nickel and cobalt; hydrochloric and sulphuric acids, even when diluted, dissolve these metals, but nitric acid may be considered as the best solvent for them. The solutions in every case contain salts corresponding with the ferrous salts—that is, of the composition RX_2 .

The most ordinary compounds of cobalt and nickel are the *salts*, CoX_2 , NiX_2 , *corresponding with the suboxides* of these metals. These salts are similar to the magnesium salts. The salts of nickel in an aqueous condition have a green colour, and form bright green solutions, but in the anhydrous state they most frequently have a yellow colour. The salts of cobalt are generally rose-coloured, and sometimes blue when in the anhydrous state. Their aqueous solutions are rose-coloured. Cobaltous chloride is easily soluble in alcohol, and forms a solution of an intense blue colour.³³

³³ This change of colour in cobalt chloride has been already alluded to (Vol. I. p. 94). The change of colour, according to some, is dependent on the combination with water, and according to others on polymeric transformation. It enables a solution of cobalt chloride to be used as sympathetic ink. If something be written with cobalt chloride on white paper, it will be invisible on account of the feeble colour of the solution, and when dry nothing can be distinguished. If, however, the paper be heated before the fire, the rose-coloured salt will be changed into the anhydrous blue salt, and the writing will become quite visible, but fade away again when cool.

Nickel sulphate crystallises from neutral solutions at a temperature of from 15° to 20° in *rhombic* crystals containing $7H_2O$. Its form approaches very closely to that of the salts of zinc and magnesium. The planes of a vertical prism for magnesium salts are inclined at an angle of $90^\circ 30'$, for zinc salts at an angle of $91^\circ 7'$, and for nickel salts at an angle of $91^\circ 10'$. Such is also the form of the zinc and magnesium selenates and chromates. Cobalt sulphate containing 7 molecules of water is deposited in crystals of the *monoclinic* system, like the corresponding salts of iron and manganese. The angle of a vertical prism for the iron salt = $82^\circ 20'$, for cobalt = $82^\circ 22'$, and the inclination of the horizontal pinacoid to the vertical prism for the iron salt = $99^\circ 2'$, and for the cobalt

If a solution of potassium hydroxide is added to a solution of a cobalt salt, a blue precipitate of the basic salt will be formed. If a solution of a cobalt salt is heated almost to the boiling-point, and the boiling solution be mixed with a boiling solution of an alkali hydroxide, a *pink precipitate of cobaltous hydroxide*, CoH_2O_2 , will be formed. If the presence of air be not completely excluded during the precipitation by boiling, the precipitate will also contain brown cobaltic hydroxide formed by the further oxidation of the cobaltous oxide. Under similar circumstances nickel salts form a *green precipitate of nickelous hydroxide*, the formation of which is not hindered by the presence of ammonium salts, but in that case only requires more alkali to completely separate the nickel. The nickelous oxide obtained by heating the hydroxide, or from the carbonate or nitrate, is a grey powder, easily soluble in acids and easily reduced, but the same substance may be obtained in the crystalline form as an ordinary product from the ores; it crystallises in regular octahedra, with a metallic lustre, and is of a grey colour. In this state the nickelous oxide almost resists the action of acids.

It is remarkable to note *the relation* of the cobaltous and nickelous hydroxides to *ammonia*; aqueous ammonia dissolves the precipitate of nickelous hydroxide. The blue ammoniacal solution of nickel resembles the same solution of cupric oxide, but has a somewhat reddish

salt $99^\circ 36'$. All the isomorphous mixtures of the salts of magnesium, iron, cobalt, nickel, and manganese have the same form if they contain 7 mol. H_2O ; and if iron or cobalt predominate, if there is an abundance of magnesium, zinc, or nickel, then the crystals have a rhombic form like magnesium sulphate. Therefore, these sulphates are *dimorphous*, but for some the one form is more stable and for others the other. Brooke, Moss, Mitscherlich, Rammelsberg, and Marignac have explained these relations. Brooke and Mitscherlich also supposed that $\text{NiSO}_4 \cdot 7\text{H}_2\text{O}$ is not only capable of assuming these forms, but also that of the *tetragonal* system, because it is deposited in this form from acid, and especially from slightly-heated solutions (30° to 40°). But Marignac demonstrated that the tetragonal crystals do not contain 7, but 6, molecules of water, $\text{NiSO}_4 \cdot 6\text{H}_2\text{O}$. He also observed that a solution evaporated at 50° to 70° deposits monoclinic crystals, but of a different form from ferrous sulphate, $\text{FeSO}_4 \cdot 7\text{H}_2\text{O}$ —namely, the angle of the prism is $71^\circ 52'$, that of the pinacoid $95^\circ 6'$. This salt appeared to be the same with 6 molecules of water as the tetragonal. Marignac also obtained magnesium and zinc salts with 6 molecules of water by evaporating their solutions at a more elevated temperature, and these salts were found to be isomorphous with the monoclinic nickel salt. In addition to this it must be observed that the rhombic crystals of nickel sulphate with $7\text{H}_2\text{O}$ become turbid under the influence of heat and light, lose water, and change into the tetragonal salt. The monoclinic crystals in time also become turbid, and change their structure, so that the tetragonal form of this salt is the most stable. Let us also add that nickel sulphate in all its shapes forms very beautiful emerald green crystals, which, when heated to 230° , assume a dirty greenish-yellow hue and then contain one molecule of water.

Krüss and Schmidt (1889) recognise in the usual purified salts of nickel and cobalt the presence of a particular as yet uninvestigated substance (perhaps alumina, or some nitrogen compound of cobalt or nickel) which is soluble in fused caustic alkali.

tint. It is characterised by the fact that it dissolves silk in the same way as the ammoniacal cupric oxide dissolves cellulose. Ammonia likewise dissolves the precipitate of cobaltous hydroxide, forming a brownish liquid, which becomes darker in air and finally assumes a bright red hue, absorbing oxygen. The admixture of ammonium chloride prevents the precipitation of cobalt salts by ammonia, and then, if ammonia be added, a brown solution is obtained from which, as in the case of the preceding solution, potassium hydroxide does not separate the cobaltous oxide. Peculiar compounds are produced in this solution; they are comparatively stable, containing ammonia and an excess of oxygen; they bear the name cobaltoamine and cobaltamine salts. They have been principally investigated by Genth, Frémy, and Jörgenson. Genth found that when a cobalt salt, mixed with an excess of ammonium chloride, was treated with ammonia and exposed to the air, after a certain lapse of time, on adding hydrochloric acid and boiling, a red powder is precipitated and the remaining solution contains an orange salt. The study of these compounds led to the discovery of a whole series of similar salts, some of which correspond with particular higher degrees of oxidation of cobalt.³⁴ Nickel does not possess this

³⁴ The cobalt salts may be divided into at least the following six classes:—

(a) *Ammonium cobalt salts*, which are simply direct compounds of the cobaltous salts CoX_2 with ammonia, similar to various other compounds of the salts of silver, copper, and even calcium and magnesium, with ammonia. They are easily crystallised from an ammoniacal solution, and have a pink colour. Thus, for instance, when cobaltous chloride in solution is mixed with sufficient ammonia to redissolve the precipitate first formed, octahedral crystals are deposited which have a composition, $\text{CoCl}_2 \cdot \text{H}_2\text{O} \cdot 6\text{NH}_3$. These salts are nothing else but combinations with the ammonia of crystallisation—if it may be thus termed, likening them in this way to combinations with the water of crystallisation. This similarity is evident both from their composition and from their capability of giving off ammonia at various temperatures. The most important point to observe is that all these salts contain 6 molecules of ammonia to 1 atom of cobalt, and this ammonia is held in fairly stable connection. Water decomposes these salts.

(b) The solutions of the above-mentioned salts are rendered turbid by the action of the air; they absorb oxygen and become covered with a crust of *oxycobaltamine salts*. The latter are sparingly soluble in aqueous ammonia, have a brown colour, and are characterised by the fact that with warm water they *evolve oxygen*, forming salts of the following category. The nitrate may be taken as an example of this kind of salt; its composition is $\text{CoN}_3\text{O}_7 \cdot 5\text{NH}_3 \cdot \text{H}_2\text{O}$. It differs from cobaltous nitrate, $\text{Co}(\text{NO}_3)_2$, in containing an extra atom of oxygen—that is, it corresponds with cobalt dioxide, CoO_2 , in the same way that the first salts correspond with cobaltous oxide; they contain 5, and not 6, molecules of ammonia, as if NH_3 had been replaced by O.

(c) *The luteocobaltic salts* are thus called because they have a yellow (luteus) colour. They are obtained from the salts of the first kind by submitting them in dilute solution to the action of the air; in this case salts of the second kind are not formed, because they are decomposed by an excess of water, with the evolution of oxygen and the formation of luteocobaltic salts. By the action of ammonia the salts of the fifth kind (roseocobaltic) are also converted into luteocobaltic salts. These last-named salts generally crystallise readily, and have a yellow colour; they are comparatively much more

property of absorbing the oxygen of the air when in an ammonical solution. In order to understand the relation of nickel it is important to observe that cobalt more easily forms a higher degree of oxidation—namely, *sesquioxide of cobalt*, *cobaltic oxide*, Co_2O_3 —than nickel, in the

stable than the preceding ones, and even for a certain time resist the action of boiling water. Boiling aqueous potash liberates ammonia and precipitates hydrated cobaltic oxide, $\text{Co}_2\text{O}_3 \cdot 3\text{H}_2\text{O}$, from them. This shows that the luteocobaltic salts correspond in the same measure with cobaltic oxide, Co_2O_3 , as the salts of the first kind correspond with cobaltous oxide, and those of the second kind with the dioxide. When a solution of luteocobaltic sulphate, $\text{Co}_2(\text{SO}_4)_5 \cdot 12\text{NH}_3 \cdot 4\text{H}_2\text{O}$, is treated with baryta, barium sulphate is precipitated, and the solution contains luteocobaltic hydroxide, which is soluble in water, is powerfully alkaline, absorbs the oxygen of the air, and when heated is decomposed, with the evolution of ammonia. This compound therefore corresponds to a solution of cobaltic hydroxide in ammonia. The luteocobaltic salts contain 2 atoms of cobalt and 12 molecules of ammonia—that is, 6NH_3 to each atom of cobalt, like the salts of the first kind. The CoX_2 salts have a metallic taste, whilst those of luteocobalt and others have a purely saline taste, like the salts of the alkali metals.

(d) *The fuscocobaltic salts.* An ammoniacal solution of cobalt salts acquires a brown colour in the air, due to the formation of these salts. They are also produced by the decomposition of salts of the second kind; they crystallise badly, and are separated from their solutions by addition of alcohol or an excess of ammonia. When boiled they give up the ammonia and cobaltic oxide which they contain. Hydrochloric and nitric acids give a yellow precipitate with these salts, which turns red when boiled, forming salts of the next category. The following is an example of the composition of two of the fuscocobaltic salts, $\text{Co}_2\text{O}(\text{SO}_4)_2 \cdot 8\text{NH}_3 \cdot 4\text{H}_2\text{O}$ and $\text{Co}_2\text{OCl}_4 \cdot 8\text{NH}_3 \cdot 3\text{H}_2\text{O}$. It is evident that the fuscocobaltic salts are ammoniacal compounds of basic cobaltic salts. The normal cobaltic sulphate ought to have the composition $\text{Co}_2(\text{SO}_4)_3 = \text{Co}_2\text{O}_3 \cdot 3\text{SO}_3$; the simplest basic salts will be $\text{Co}_2\text{O}(\text{SO}_4)_2 = \text{Co}_2\text{O}_3 \cdot 2\text{SO}_3$, and $\text{Co}_2\text{O}_2(\text{SO}_4) = \text{Co}_2\text{O}_3 \cdot \text{SO}_3$. The fuscocobaltic salts correspond with the first type of basic salts. They are changed (in concentrated solutions) into oxycobaltamine salts by absorption of one atom of oxygen, $\text{Co}_2\text{O}_2(\text{SO}_4)_2$. The whole process of oxidation will be as follows: first of all Co_2X_4 , a cobaltous salt, is in the solution (X a univalent haloid, 2 molecules of the salt being taken), then Co_2OX_4 , the basic cobaltic salt (4th series), then $\text{Co}_2\text{O}_2\text{X}_4$, the salt of the dioxide (2nd series). The series of basic salts with an acid, 2HX , forms water and a normal salt, Co_2X_6 (in 3, 5, 6 series). These salts are combined with various amounts of water and ammonia. Under many conditions the salts of fuscocobalt are easily transformed into salts of the next series. The salts of the series that has just been described contain 4 molecules of ammonia to 1 atom of cobalt.

(e) *The roseocobaltic salts*, like the luteocobaltic, correspond with the normal cobaltic salts, but contain less ammonia. Thus the sulphate is obtained from cobaltous sulphate dissolved in ammonia and left exposed to the air until transformed into a brown solution of the fuscocobaltic salt; when this is treated with sulphuric acid a crystalline powder of the roseocobaltic salt, $\text{Co}_2(\text{SO}_4)_5 \cdot 10\text{NH}_3 \cdot 5\text{H}_2\text{O}$, separates. The formation of this salt is easily understood: cobaltous sulphate in the presence of ammonia absorbs oxygen, and the solution of the fuscocobaltic salt will therefore contain, like cobaltous sulphate, one part of sulphuric acid to every part of cobalt, so that the whole process of formation may be expressed by the equation: $10\text{NH}_3 + 2\text{CoSO}_4 + \text{H}_2\text{SO}_4 + 4\text{H}_2\text{O} + \text{O}$. This salt forms tetragonal crystals of a red colour, slightly soluble in cold, but readily soluble in warm water. When the sulphate is treated with baryta roseocobaltic hydroxide is formed in the solution, which absorbs the carbonic anhydride of the air. It is obtained from the next series by the action of alkalis.

(f) *The purplecobaltic salts* are also products of the direct oxidation of ammoniacal solutions of cobalt salts. They are easily obtained by heating the roseocobaltic salts

presence of hypochlorous acid. If a solution of a cobalt salt be mixed with barium carbonate and an excess of hypochlorous acid be added, or chlorine gas be passed through it, then at the ordinary temperature on shaking, the whole of the cobalt will be separated in the form of

with strong acids. They are to all effects the same as the roseocobaltic salts, only anhydrous. Thus, for instance, the purplecobaltic chloride, $\text{Co}_2\text{Cl}_6 \cdot 10\text{NH}_3$, is obtained by boiling the oxycobaltamine salts with ammonia. There is the same distinction between these salts and the preceding ones as between the various compounds of cobaltous chloride with water.

The cobaltamine compounds differ but little essentially from the ammoniacal compounds of other metals. The only difference is that here the cobaltic oxide is obtained from the cobaltous oxide in the presence of ammonia. In any case it is a simpler question than that of the double cyanides. Those forces in virtue of which such a considerable number of ammonia molecules are united with a molecule of a cobalt compound, appertain naturally to the series of those slightly-investigated residual affinities which exist even in the highest degrees of combination of the majority of elements. They are the same forces which lead to the formation of compounds containing water of crystallisation, double salts, and perhaps also isomorphous mixtures. The simplest conception, according to my opinion, of cobalt compounds (much more so than by assuming special complex radicles, like Schiff, Welzen, Claus, Henning, and others), may be formed by comparing them with other ammoniacal products. Ammonia, like water, combines in various proportions with a multitude of substances. Silver chloride and calcium chloride, just like cobalt chloride, absorb ammonia, forming compounds which are sometimes slightly stable, and easily dissociated, sometimes more stable, in exactly the same way as water combines with certain substances, forming fairly stable compounds called hydroxides or hydrates, or less stable compounds which are called compounds with water of crystallisation. Naturally, the faculty of forming one or the other compound with ammonia, as in the case of water, depends on the property of those elements which enter into the composition of the given substance, and on those kinds of affinity towards which chemists have not as yet turned their attention. If boron fluoride, silicon fluoride, &c., combine with hydrofluoric acid, if platonic chloride, and even cadmium chloride, combine with hydrochloric acid, then these compounds may be regarded as double salts, because acids are salts of hydrogen. But evidently water and ammonia have the same saline faculty, more especially as they, like haloid acids, contain hydrogen, and are both capable of further combination—for instance, ammonia with hydrochloric acid. Therefore it is simpler to compare complex ammoniacal compounds with double salts, hydrates, and similar compounds, as will be seen in the description of the compounds of platinum.

The ammonio-metallic salts present a most developed qualitative and quantitative resemblance to the hydrated salts of metals. The composition of the latter is $\text{MX}_m\text{mH}_2\text{O}$, where M=metal, X=the haloid, simple or complex, and m and n the quantity of the haloid and so-called water of crystallisation combined with the salt. The composition of the ammoniacal salts of metals is MX_nmNH_3 . The water of crystallisation is held by the salt with more or less stability, and some salts even do not retain it at all; some part with water easily when exposed to the air, others when heated, and then with difficulty. In the case of some metals all the salts combine with water, whilst with others only a few, and the water so combined may then be easily disengaged. All this refers equally well to the ammoniacal salts, and therefore the combination of ammonia may be termed the ammonia of crystallisation. A colourless, anhydrous cupric salt—for instance, cupric sulphate—when combined with water forms blue and green salts, and violet when combined with ammonia. If steam be passed through anhydrous copper sulphate the salt absorbs water and becomes heated; if ammonia be substituted for the water the heating becomes much more intense, and the salt breaks up into a fine violet powder. With water $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$ is formed, and with ammonia $\text{CuSO}_4 \cdot 5\text{NH}_3$, the

black cobaltic oxide : $2\text{CoSO}_4 + \text{ClHO} + 2\text{H}_2\text{O} = \text{Co}_2\text{O}_3 + 2\text{H}_2\text{SO}_4 + \text{HCl}$. Under these circumstances nickelous oxide does not immediately form black sesquioxide, but after a considerable space of time it also sepa-

number of water and ammonia molecules retained by the salt being the same in each case, and as a proof of this, and that it is not an isolated coincidence, the remarkable fact must be borne in mind that water and ammonia consecutively, molecule for molecule, are capable of supplanting each other, and forming the compounds $\text{CuSO}_4, 5\text{H}_2\text{O}$, $\text{CuSO}_4, 4\text{H}_2\text{O}, \text{NH}_3$; $\text{CuSO}_4, 3\text{H}_2\text{O}, 2\text{NH}_3$; $\text{CuSO}_4, 2\text{H}_2\text{O}, 3\text{NH}_3$; $\text{CuSO}_4, \text{H}_2\text{O}, 4\text{NH}_3$, and $\text{CuSO}_4, 5\text{NH}_3$. The last of these compounds was obtained by Henry Rose, and my experiments have shown that more ammonia than this cannot be retained. By adding to a strong solution of cupric sulphate sufficient ammonia to dissolve the whole of the oxide precipitated, and then adding alcohol, Berzelius obtained the compound $\text{CuSO}_4, \text{H}_2\text{O}, 4\text{NH}_3$, &c. The law of substitution also assists in rendering these phenomena clearer, because a compound of ammonia with water forms ammonium hydroxide, NH_4HO , and therefore these molecules combining with one another may also interchange, as being of equal value. In general, those salts form stable ammoniacal compounds which are capable of forming stable compounds with water of crystallisation; and as ammonia is capable of combining with acids, and as some of the salts formed by slightly energetic bases in their properties more closely resemble acids (that is, salts of hydrogen) than those salts containing more energetic bases, we might therefore expect to find more stable and more easily-formed ammonio-metallic salts with metals and their oxides having weaker basic properties than with those which form energetic bases. This explains why the salts of potassium, barium, &c., do not form ammonio metallic salts, whilst the salts of silver, copper, zinc, &c., do form them. This consideration also accounts for the great stability of the ammoniacal compounds of cupric oxide compared with silver oxide, because the former is displaced by the latter. It also enables us to see clearly the distinction which exists in the stability of the cobaltamine salts containing salts corresponding with cobaltous oxide, and those corresponding with higher oxides of cobalt, because the latter are weaker bases than cobaltous oxides. *The nature of the forces and quality of the phenomena occurring during the formation of the most stable substances, and of such compounds as crystallisable compounds, are one and the same, although exhibited in a different degree.* This may be confirmed by examining the compounds of carbon, because for this element the nature of the forces acting during the formation of its compounds is well known. Let us take as an example two unstable compounds of carbon. Acetic acid, $\text{C}_2\text{H}_4\text{O}_2$ (specific gravity 1.06), with water forms the hydrate, $\text{C}_2\text{H}_4\text{O}_2, \text{H}_2\text{O}$, denser (1.07) than either of the components, but unstable and easily decomposed, generally directly referred to as a solution. Such also is the crystalline compound of oxalic acid, $\text{C}_2\text{H}_2\text{O}_4$, with water, $\text{C}_2\text{H}_2\text{O}_4, 2\text{H}_2\text{O}$. Their formation might be predicted as issuing from the hydrocarbon C_2H_6 , in which, as in any other, the hydrogen may be exchanged for chlorine, the water residue (hydroxyl), &c. The first substitution product with hydroxyl, $\text{C}_2\text{H}_5(\text{HO})$, is stable; it can be distilled without alteration, resists a temperature higher than 100° , and then does not give off water. This is ordinary alcohol. The second, $\text{C}_2\text{H}_4(\text{HO})_2$, can also be distilled without change, but can be decomposed into water and $\text{C}_2\text{H}_4\text{O}$ (ethylene oxide or aldehyde); it boils at about 197° , whilst the first hydrate boils at 78° , a difference of about 100° . The compound $\text{C}_2\text{H}_5(\text{HO})_2$ will be the third product of such substitution; it ought to boil at about 300° , but does not resist this temperature—it decomposes into H_2O and $\text{C}_2\text{H}_4\text{O}_2$, where only one hydroxyl group remains, and the other part of oxygen is left in the same condition as ethylene oxide, $\text{C}_2\text{H}_4\text{O}$. There is a proof of this. Glycol, $\text{C}_2\text{H}_4(\text{HO})_2$, boils at 197° , and forms water and ethylene oxide, which boils at 13° (aldehyde, its isomeride, boils at 21°); therefore the product disengaged by the splitting up of the hydrate boils at 184° lower than the hydrate $\text{C}_2\text{H}_4(\text{HO})_2$. Thus in exactly the same way the hydrate $\text{C}_2\text{H}_5(\text{HO})_2$, which ought to boil at about 300° , splits up into water and the product $\text{C}_2\text{H}_4\text{O}_2$, which boils at 117° —that is, nearly 183° lower

rates in the form of sesquioxide, but always later than cobalt. This is due to the relative difficulty of further oxidation of the nickelous oxide. It is, however, possible to oxidise it; if, for instance, the

than the hydrate, $C_2H_5(HO)_5$. But this hydrate splits up before distillation. The above-mentioned hydrate of acetic acid is a similar decomposable hydrate—that is to say, what is called a solution. Still less stability may be expected from the following hydrates. $C_2H_3(HO)_4$ also splits up into water and a hydrate (it contains two hydroxyl groups) called glycolic acid, $C_2H_2O(HO)_2 = C_2H_4O_5$. The next product of substitution will be $C_2H(HO)_5$; it splits up into water, H_2O , and glyoxylic acid, $C_2H_4O_4$ (three hydroxyl groups). The last hydrate which ought to be obtained from C_2H_6 , and ought to contain $C_2(HO)_6$, is a crystalline compound of oxalic acid, $C_2H_2O_4$ (two hydroxyl groups), and water, $2H_2O$, which has been mentioned already. The hydrate, $C_2(HO)_6 = C_2H_2O_4 \cdot 2H_2O$, ought, according to the foregoing reasoning, to boil at about 600° (because the hydrate, $C_2H_4(HO)_2$, boils at about 200° , and the substitution of 4 hydroxyl groups for 4 atoms of hydrogen will raise the boiling-point 400°). It does not resist this temperature, but at a much lower point splits up into water, $2H_2O$, and the hydrate $C_2O_2(HO)_2$, which is also capable of yielding water. Without going into further considerations on this subject, it may be observed that the formation of hydrates or compounds with water of crystallisation of acetic and oxalic acids has thus received an accurate explanation, which was the point we desired to prove in affirming that compounds with water of crystallisation are held together by the same forces as those which act in the formation of other complex substances, and the easy displaceability of the water of crystallisation is only a peculiarity of a completely local character, and not the chief and radical point of distinction. All the above-mentioned hydrates, C_2X_6 , or products of their destruction, are actually obtained by the oxidation of the first hydrate, $C_2H_5(HO)$, or common alcohol, by nitric acid (Sokoloff and others).

In conclusion, it may be observed that the elements of the eighth group—that is, the analogues of iron and platinum—according to my opinion, will yield most fruitful results when studied as to combinations with whole molecules, as already shown by the examples of complex ammoniacal, cyanogen, nitro-, and other compounds, which are easily formed in this eighth group, and are remarkable for their stability. This faculty of the elements of the eighth group for forming the complex compounds alluded to, is in all probability connected with the position which the eighth group occupies with regard to the others. Following the seventh, which forms the type RX_7 , it might be expected to contain the most complex type, RX_8 . This is met with in OsO_4 . The other elements of the eighth group, however, only form the lower types RX_2 , RX_5 , RX_4 . . . and these accordingly should be expected to complicate themselves into the higher types.

The following reaction may be added to those of the cobaltous and nickelous salts; potassium cyanide forms a precipitate with cobalt salts which is soluble in an excess of the reagent and forms a green solution. On heating this and adding a certain quantity of acid, a double *cobalt cyanide* is formed which corresponds with potassium ferricyanide. Its formation is accompanied with the evolution of hydrogen, and is founded upon the property which cobalt has of oxidising in an alkaline solution, the development of which has been observed in such a considerable measure in the cobaltamine salts. The process which goes on here may be expressed by the following equation: $CoC_2N_2 + 4KCN$ first forms $CoK_4C_6N_6$, which salt with water, H_2O , forms potassium hydroxide, KHO , hydrogen, H , and the salt $K_2CoC_6N_6$. Here naturally the presence of the acid is indispensable in consequence of its being required to combine with the alkali. From aqueous solutions this salt crystallises in transparent, hexagonal prisms of a yellow colour, easily soluble in water. The reactions of double decomposition, and even the formation of the corresponding acid, are here completely the same as in the case of the ferricyanide. If a nickelous salt be treated in precisely the same manner as has just been described for a salt of cobalt, decomposition will occur.

hydroxide be shaken in water and chlorine gas be passed through it, then nickel chloride will be formed, which is soluble in water, and insoluble nickelic oxide in the form of a black precipitate: $3\text{NiH}_2\text{O}_2 + \text{Cl}_2 = \text{NiCl}_2 + \text{Ni}_2\text{O}_3, 3\text{H}_2\text{O}$. Nickelic oxide may also be obtained by adding sodium hypochlorite mixed with alkali to a solution of a nickel salt. Nickelic and cobaltic oxides (hydrated) have a black colour and exhibit but slight tendency to combine with acids, nickelic oxide up to the present time not having been combined with any acid, so that it corresponds in properties with manganese dioxide. It actually evolves oxygen with all acids, and in consequence of this it is not separated as a precipitate in the presence of acids; thus it evolves chlorine with hydrochloric acid, exactly like manganese dioxide. When nickelic oxide is dissolved in aqueous ammonia it disengages nitrogen, and an ammoniacal solution of nickelous oxide is formed. When heated nickelic oxide loses oxygen, forming nickelous oxide. Cobaltic oxide, Co_2O_3 , exhibits more stability than nickelic oxide, and shows feeble basic properties; thus it is dissolved in acetic acid without the evolution of oxygen. But ordinary acids, especially when heated, evolve oxygen, forming a solution of a cobaltous salt. The presence of a cobaltic salt in a solution of a cobaltous salt may be detected by the brown colour of the solution and the black precipitate formed by the addition of alkali, and also from the fact that such solutions evolve chlorine when heated with hydrochloric acid. Cobaltic oxide may not only be prepared by the above-mentioned methods, but also by heating cobalt nitrate, after which a steel-coloured mass remains which retains certain traces of nitric acid, but when heated to incandescence it evolves oxygen, leaving a compound of cobaltic and cobaltous oxides, similar to magnetic ironstone.

Nickel alloys possess qualities which render them valuable in industry, the alloy of nickel with iron being particularly remarkable. This alloy is met with in nature as *meteoric iron*. The Pallasoffsky mass of meteoric iron, preserved in the St. Petersburg Academy, fell in Siberia in the last century; it weighs about 15 cwt. and contains 88 p.c. of iron and about 10 p.c. of nickel, with a small admixture of other metals. In the arts *German silver* is the most extensively used; it is an alloy containing nickel, copper, and zinc in various proportions. It generally consists of about 50 parts of copper, 25 parts of zinc, and 25 parts of nickel. This alloy is characterised by its white colour resembling that of silver, and, like this latter metal, it does not rust, and therefore furnishes an excellent substitute for silver in the majority of cases where it is used. Alloys which contain silver in addition to nickel show the properties of silver to a still greater extent.

Alloys of nickel are used for currency, and if rich deposits of nickel are discovered a wide field of application lies before them, both in a pure state (because it is a beautiful metal and does not rust) and also as alloys. Steel vessels (pressed or forged out of sheet steel) covered with nickel have such practical merits that the manufacture, which has not long commenced, will most probably be rapidly developed.

CHAPTER XXIII

THE PLATINUM METALS

THE six metals : Ruthenium, Ru, rhodium, Rh, palladium, Pd, osmium, Os, iridium, Ir, and platinum, Pt, are met with associated together in nature. Platinum always predominates over the others, and hence they are known as the *platinum metals*. By their chemical character their position in the periodic system is in the eighth group, corresponding with iron, cobalt, and nickel.

The naturalness of the transition from titanium and vanadium to copper and zinc by means of the elements of the iron group is demonstrated by all the properties of these elements, and in exactly the same manner a transition from zirconium, niobium, and molybdenum to silver, cadmium, and indium, through ruthenium, rhodium, and palladium is in perfect accordance with fact, as also is the position of osmium, iridium, and platinum between tantalum and tungsten on the one side, and gold and mercury on the other. In all these three cases the elements of smaller atomic weight (chromium, molybdenum, and tungsten) are able, in their higher grades of oxidation, to give acid oxides having the properties of distinct but feebly energetic acids (in the lower oxides they give bases), whilst the elements of greater atomic weight (zinc, cadmium, mercury), even in their higher grades of oxidation, only give bases, although with feebly-developed basic properties. The platinum metals present the same intermediate properties such as we have already seen in iron and the elements of the eighth group.

In the platinum metals the intermediate properties of *feebly acid and feebly basic metals* are developed with great clearness, so that there is not one sharply-defined acid anhydride among their oxides, although there is a great diversity in the grades of oxidation from the type RO_4 to R_2O . The feebleness of the chemical forces observed in the platinum metals is connected with the ready decomposability of their compounds, with the small atomic volume of the metals themselves, and with their large atomic weight. The oxides of platinum, iridium, and osmium can scarcely be either termed basic or acid ; they

are capable of combinations of both kinds, one and the other of which is feeble. They are all intermediate oxides.

The atomic weights of platinum, iridium, and osmium are nearly 191 to 196, and of palladium, rhodium, and ruthenium, 104 to 106. Thus, strictly speaking, we have here two series of metals, which are, moreover, perfectly parallel to each other; three members in the first series, and three members in the second—namely, platinum presents an analogy to palladium, iridium to rhodium, and osmium to ruthenium. The group of the platinum metals is characterised by a number of common properties, both physical and chemical, and, moreover, there are not a few points of resemblance between the members of this group and those of the iron group (Chapter XXII.). The atomic volumes of the elements of this group are *nearly equal and very small*. The iron metals have atomic volumes of nearly 7, whilst that of the metals allied to palladium is nearly 9, and of those adjacent to platinum nearly 9.4. This comparatively small atomic volume corresponds with the great infusibility and tenacity proper to all the iron and platinum metals, and to their small chemical energy, which stands out very clearly in the heavy platinum metals. All the platinum metals are very *easily reduced* by ignition and by the action of various reducing agents, in which process oxygen, or a haloid group, is disengaged from their compounds and the metal left behind. This is a property of the platinum metals which determines many of their reactions, and the circumstance of their always being found in nature *in a native state*.¹ The facility with which they are reduced is so great that their chlorides are even decomposed by gaseous hydrogen, especially when shaken up and heated under a certain pressure. Hence it will be readily understood that such metals as zinc, iron, &c., separate them from solutions with great ease, which fact is taken advantage of in practice and in the chemical treatment of the platinum metals.

All the platinum metals, like those of the iron group, are grey, with a comparatively feeble metallic lustre, and are very infusible. In this respect they stand in the same order as the metals of the iron series; nickel is more fusible and whiter than cobalt and iron, so also palladium is whiter and more fusible than rhodium and ruthenium, and platinum is comparatively more fusible and whiter than iridium or osmium. The saline compounds of these metals are red or yellow, like

¹ Wells and Penfield (1888) have described a mineral sperryllite found in the Canadian gold-bearing quartz and consisting of platinum diarsenide, PtAs_2 . It is a noticeable fact that this mineral clearly confirms the position of platinum in the same group as iron, because it corresponds in crystalline form (regular octahedron) and chemical composition with iron pyrites, FeS_2 .

those of the majority of the metals of the iron series. But here, as there, the different forms of oxidation present different colours. Moreover, certain complex compounds of the platinum metals, like certain complex compounds of the iron series, either have particular characteristic tints or else are colourless.

The platinum metals are found *in nature associated together in alluvial deposits* in a few localities, from which they are washed, owing to their very considerable density, which enables a stream of water to wash away the sand and clay with which they are mixed. Platinum deposits are chiefly known in the Urals, and also in Brazil and a few other localities. The platinum ore washed from these alluvial deposits presents the appearance of more or less coarse grains, and sometimes of, as it were, semifused nuggets.²

All the platinum metals give compounds with the halogens, and the highest haloid type of combination for all is RX_4 . For the majority of the platinum metals this type is exceedingly unstable; the lower compounds corresponding to the type RX_2 , which are formed by the separation of X_2 , are more stable. In the type RX_2 the platinum metals form more stable salts, which offer no little resemblance to the kindred compounds of the iron series—for example, with nickelous chloride, $NiCl_2$, cobaltous chloride, $CoCl_2$, &c. This even expresses itself in a similarity of volume (platinous chloride, $PtCl_2$, volume, 46; nickelous chloride, $NiCl_2=50$), although in the type RX_2 the true iron metals give very stable compounds, whilst the platinum metals frequently react after the manner of suboxides, decomposing into the metal and higher types, $2RX_2=R+RX_4$. This naturally depends on the facility with which RX_2 decomposes into R and X_2 , when X_2 combines with the remaining RX_2 .

As in the series iron, cobalt, nickel, nickel gives only one salt-forming oxide, whilst cobalt and iron give higher and varied forms of oxidation; so also among the platinum metals, platinum and palladium only give the forms RX_2 and RX_4 , whilst rhodium and iridium form

² The largest amount of platinum is extracted in the Urals, about two tons annually. About a tenth part of gold is extracted from the washed platinum by means of mercury, which does not dissolve the platinum metals but dissolves the gold accompanying the platinum in its ores. Moreover, the ores of platinum always contain metals of the iron series associated with them. The washed and mechanically-sorted ore in the majority of cases contains about 70 to 80 p.c. of platinum, about 5 to 8 p.c. of iridium, and a somewhat smaller quantity of osmium. The other platinum metals—palladium, rhodium, and ruthenium—occur in smaller proportions than the three above-named. Sometimes grains of almost pure osmium-iridium, containing only a small quantity of other metals, are found in platinum ores. This osmium-iridium may be easily separated from the other platinum alloys, owing to its being nearly insoluble in aqua regia, by which the latter are easily dissolved. There are grains of platinum which are magnetic.

met another intermediate type, RX_3 , corresponding with the oxide, which is also met with for cobalt, and presents the composition R_2O_3 , besides which they also form an acid oxide, like ferric acid, which is also known in the form of salts, but is in every respect unstable. Osmium and ruthenium, like manganese, form still higher oxides, and in this respect exhibit the greatest diversity. They not only give RX_2 , RX_3 , RX_4 , and RX_6 , but also a still *higher form of oxidation*, RO_4 , which is not met with in any other series. This form is exceedingly characteristic, owing to the fact of the oxides, OsO_4 and RuO_4 , being volatile feebly acid substances. In this respect they most resemble permanganic anhydride, which is also somewhat volatile.³

When dissolved in aqua regia and liberated from the solution by ignition or the action of reducing agents, platinum forms a powdery mass, known as spongy platinum or platinum black. If this powder of platinum be heated and pressed, or hammered in a cylinder, the grains

³ In characterising the platinum metals according to their relation to the iron metals, it is very important to add two more very remarkable points. The platinum metals are capable of forming a sort of unstable compound with *hydrogen*; they absorb it and only part with it when somewhat considerably heated. This faculty is especially developed in platinum and palladium, and it is very characteristic that nickel, which just corresponds with platinum and palladium in the periodic system, should exhibit the same faculty for retaining a considerable quantity of hydrogen (Graham's and Raoult's experiments). Another characteristic property of the platinum metals consists in their easily giving stable and characteristic saline *compounds with ammonia*, and double salts with the cyanides of the alkali metals, especially in their lower forms of combination.

All the above so clearly brings the elements of the iron series in close relation to the platinum metals, that the eighth group acquires as natural a character as can be required, with a certain originality or individuality for each element.

Platinum was first obtained in the last century from Brazil, where it was called silver (platinus). Watson in 1750 characterised platinum as a separate independent metal. In 1803 Wollaston discovered palladium and rhodium in crude platinum, and at about the same time Tennant distinguished iridium and osmium in it. Professor Claus, of Kazan, in his researches on the platinum metals (about 1840) discovered ruthenium in them, and to him are due many important discoveries with regard to these elements, such as the indication of the remarkable analogy between the series $Pd-Rh-Ru$ and $Pt-Ir-Os$.

The treatment of platinum ore is chiefly carried on for the extraction of the platinum itself and its alloys with iridium, because these metals offer a greater resistance to the action of chemical reagents and high temperatures than any of the other malleable and ductile metals, and therefore the wire so often used in the laboratory and for technical purposes is made from them, as also are various vessels used for chemical purposes in the laboratory and in works. Thus sulphuric acid is distilled in platinum retorts, and many substances are fused, ignited, and evaporated in the laboratory in platinum crucibles and platinum foil. Gold and many other substances are dissolved in basins made of iridium-platinum, because the alloys of platinum and iridium are but slightly attacked when subjected to the action of aqua regia. An exceedingly important property of the platinum metals is that they do not fuse in a furnace heat, palladium only being somewhat more fusible than the rest.

aggregate or forge together, and form a continuous, but naturally not entirely homogeneous, mass. Platinum was formerly, and is even now, worked up in this manner. The platinum money formerly used in Russia was made in this way. Sainte-Claire Deville, in the fifties, for the first time *melted platinum* in considerable quantities by employing a special furnace made in the form of a small reverberatory furnace, and composed of two pieces of lime, on which heat has no action. Into this furnace (shown in fig. 34, Vol. I. p. 173)—or, more strictly speaking, into the cavity made in the pieces of lime—the platinum is introduced, and two orifices are made in the lime; through one, the upper, or side orifice, is introduced an oxyhydrogen gas burner, in which either detonating gas or a mixture of oxygen and coal-gas is burnt, whilst the other orifice serves for the escape of the products of combustion and certain impurities which are more volatile than the platinum, and especially the oxidised compounds of osmium, ruthenium, and palladium, which are comparatively easily volatilised by heat. In this manner the platinum is converted into a continuous metallic form by means of fusion, and this method is now used for melting somewhat considerable masses of platinum.⁴

If it be desired to obtain pure platinum, it is necessary to have recourse to the solution of the ore in aqua regia. Only the osmium and iridium remain unattacked by the aqua regia. The solution contains the platinum metals in the form RCl_4 , and in the lower forms of chlorination, because some of these metals—for instance, palladium and rhodium—form such unstable chlorides of the type RX_4 that they already partially decompose when only diluted with water, and pass into the stable lower type of combination; in addition to which the chlorine is very easily disengaged if it comes in contact with substances on which it can act. In this respect platinum resists the action of

⁴ This process has altered the technical treatment of platinum to a considerable extent. It has in particular facilitated the manufacture of alloys of platinum with iridium and rhodium from the pure platinum ores; because it is sufficient to fuse the ore in order for the greater amount of the osmium to burn off, and for the mass to fuse into a homogeneous, malleable alloy, which is straightway used in practice. There is very little ruthenium in the ores of platinum. If during fusion lead be added, it dissolves the platinum owing to its being able to form a very characteristic alloy containing PtPb. If an alloy of both metals be left exposed to moist air, the excess of lead is converted into carbonate (white lead) in the presence of the water and carbonic acid of the air, whilst the above platinum alloy remains unchanged. The white lead may be extracted by dilute acid, and the alloy PtPb remains untouched. The other platinum metals also give similar alloys with lead. The fusibility of these alloys enables the platinum metals to be separated from the gangue of the ore, and they may afterwards be separated from the lead by subjecting the alloy to oxidation in furnaces furnished with a bone ash bed, because the lead is then oxidised and absorbed by the bone ash, leaving the platinum metals untouched.

heat and reducing agents better than any of its companions—that is, it passes with greater difficulty from PtCl_4 to the lower compound PtCl_2 . On this is based the method of preparation of more or less pure platinum. Lime or sodium hydroxide is added to the solution in aqua regia; in one or the other case the reaction is not carried on to the formation of a clearly alkaline solution, but only to saturation or a very slight excess of alkali. It is naturally best to first evaporate and slightly ignite the solution, in order to remove the excess of acid, and by heating it to partially convert the higher chlorides of the palladium, &c., into the lower. The addition of alkalis completes the reduction, because the chlorine held in the compounds RX_4 acts on the alkali like free chlorine, converting it into a hypochlorite. Thus palladium chloride, PdCl_4 , for example, is converted into palladious chloride, PdCl_2 , by this means, according to the equation $\text{PdCl}_4 + 2\text{NaHO} = \text{PdCl}_2 + \text{NaCl} + \text{NaClO} + \text{H}_2\text{O}$. In just the same manner iridic chloride, IrCl_4 , is converted into the trichloride, IrCl_3 , by this method. When this conversion takes place the platinum still remains in the form of platonic chloride, PtCl_4 . It is then possible to take advantage of a certain difference in the properties of the higher and lower chlorides of the platinum metals. Thus lime precipitates the lower chlorides of the members of the platinum metals occurring in solution without acting on the platonic chloride, PtCl_4 , and therefore the addition of a large proportion of lime immediately precipitates the associated metals, leaving the platinum itself in solution in the form of a soluble double salt, $\text{PtCl}_4 \cdot \text{CaCl}_2$. A far better and more perfect separation is effected by means of ammonium chloride, which gives, with platonic chloride, an insoluble yellow precipitate, $\text{PtCl}_4 \cdot 2\text{NH}_4\text{Cl}$, whilst it forms soluble double salts with the lower chlorides RCl_2 and RCl_3 , so that ammonium chloride precipitates the platinum only from the solution obtained by the preceding method. These methods are employed for preparing the platinum which is used for the manufacture of platinum articles, because, having platinum in solution as calcium platinochloride, PtCaCl_6 , or as the insoluble ammonium platinochloride, $\text{Pt}(\text{NH}_4)_2\text{Cl}_6$, the platinum compound in every case, after drying or ignition, loses all the chlorine from the platonic chloride and leaves finely-divided metallic platinum, which may be converted into homogeneous metal by compression and forging, or by fusion.⁵

⁵ For the ultimate purification of platinum from palladium and iridium the metals must be re-dissolved in aqua regia, and the solution evaporated until the residue begins to evolve chlorine. The residue is then re-precipitated with ammonium or potassium chloride. The precipitate may still contain a certain amount of iridium, which passes with greater difficulty from the tetrachloride, IrCl_4 , into the trichloride, IrCl_3 , but it will

Metallic *platinum* in a fused state has a specific gravity of 21.1 ; it is grey, softer than iron, but harder than copper, exceedingly ductile, and therefore is easily drawn into wire and rolled into thin sheets, and may be hammered and drawn into thin tubes, &c. In the state in which it is obtained by the ignition of its compounds, it forms a spongy mass, known as spongy platinum, or else as powder (platinum black).⁶ In either case it is grey, dull, and is characterised, as we already know, by the faculty of absorbing hydrogen and other gases. Platinum is not acted on by hydrochloric, hydriodic, nitric, and sulphuric acids, or a mixture of hydrofluoric and nitric acids. Aqua regia, and any liquid containing chlorine or able to evolve chlorine or bromine, dissolves platinum. Alkalis are decomposed by platinum at a red heat, owing to the faculty of the platinum oxide, PtO_2 , formed to combine with alkaline bases, inasmuch as it has a feebly-developed acid character. Sulphur, phosphorus (the phosphide, PtP_2 , is formed), arsenic, silicon all act more or less rapidly on platinum, under the influence of heat. Many of the metals form alloys with it. Even charcoal combines with platinum when it is ignited with it, and therefore carbonaceous matter cannot be subjected to prolonged and powerful ignition in platinum vessels. Hence a platinum crucible soon becomes dull on the surface in a smoky flame. Platinum also alloys with zinc, lead, tin, copper, gold, and silver.⁷ Although mercury does

be quite free from palladium, because the latter easily loses its chlorine and passes into palladious chloride, PdCl_2 , which gives an easily-soluble salt with potassium chloride. The precipitate, containing a small quantity of iridium, is then heated, with sodium carbonate, in a crucible, when the mass decomposes, giving metallic platinum and iridium oxide. If potassium chloride has been employed, the residue after ignition is washed with water and treated with aqua regia. The iridium oxide remains undissolved, and the platinum easily passes into solution. Only cold and dilute aqua regia must be used. The solution will then contain pure platonic chloride, which forms the starting-point for the preparation of all platinum compounds.

⁶ We have already become acquainted with the effect of finely-divided platinum on many gaseous substances. It is best seen in the so-called *platinum black*, which is a coal black powder left by the action of sulphuric acid on the alloy of zinc and platinum, or which is precipitated by metallic zinc from a dilute solution of platinum. At all events, finely-divided platinum absorbs gases more powerfully and rapidly the more finely-divided and porous it is. Sulphurous anhydride, hydrogen, alcohol, and many organic substances in the presence of such platinum are easily oxidised by the oxygen of the air, although they do not combine with it directly. The absorption of oxygen is as much as several hundred volumes per one volume of platinum, and the oxidising power of such absorbed oxygen is taken advantage of not only in the laboratory but even in working processes. Asbestos or charcoal, soaked in a solution of platonic chloride and ignited, is very useful for this purpose, because by this means it becomes coated with platinum black.

⁷ It is necessary to remark that platinum when alloyed with silver, or as amalgam, is soluble in nitric acid, and in this respect it differs from gold, so that it is possible by alloying gold with silver and acting on the alloy with nitric acid, to recognise the presence of platinum in the gold, because nitric acid does not act on gold alloyed with silver.

not directly dissolve platinum, still it forms a solution or amalgam with spongy platinum, in the presence of sodium amalgam; a similar amalgam is also formed by the action of sodium amalgam on a solution of platinum chloride, and is used for physical experiments.

There are *two kinds* of *platinum compounds*, PtX_4 and PtX_2 . The former are produced by an excess of halogen in the cold, and the latter by the aid of heat or by the splitting up of the former. The starting-point of the platinum compounds is *platinum tetrachloride*, *platinic chloride*, PtCl_4 , obtained by dissolving platinum in aqua regia. The solution crystallises in the cold, in a desiccator, in the form of reddish-brown deliquescent crystals containing hydrochloric acid: $\text{PtCl}_4 \cdot 2\text{HCl} \cdot 6\text{H}_2\text{O}$, and forming a true acid with corresponding salts R_2PtCl_6 —ammonium platinochloride, for example. The hydrochloric acid is liberated from these crystals by gently heating or evaporating the solution to dryness; and, better still, after treatment with silver nitrate (silver chloride is precipitated) a reddish-brown mass remains behind, which dissolves in water, and forms a yellowish-red solution which on cooling deposits crystals of the composition $\text{PtCl}_4 \cdot 8\text{H}_2\text{O}$. The *tendency to combine* with hydrochloric acid and water—that is, *to form higher crystalline compounds*—is evident in the platinum compounds, and must be taken into account in explaining the properties of platinum and the formation of many other of its complex compounds. Dilute solutions of platinic chloride are yellow, and are completely reduced by hydrogen, sulphurous anhydride, and many reducing agents, which first convert the platinic chloride into the lower compound platinous chloride, PtCl_2 . That faculty which expresses itself in platinum tetrachloride in its combining with water of crystallisation and hydrochloric acid is distinctly marked in its property, with which we are already acquainted, of giving precipitates with the salts of potassium, ammonium, rubidium, &c. In general it *readily forms double salts* $\text{R}_2\text{PtCl}_6 = \text{PtCl}_4 + 2\text{RCl}$, where R is a univalent metal such as potassium or sodium. Hence the addition of a solution of potassium or ammonium chloride to a solution of platinic chloride is followed by the formation of a yellow precipitate, which is sparingly soluble in water and almost entirely insoluble in alcohol and ether (platinic chloride is soluble in water, and potassium iridochloride, IrK_3Cl_6 , is soluble in water but not in alcohol). It is especially remarkable in this case, that the potassium compounds here, as in a number of other instances, separate in an anhydrous form, whilst the sodium compounds, which are soluble in water and alcohol, form red crystals containing water. The composition $\text{Na}_2\text{PtCl}_6 \cdot 6\text{H}_2\text{O}$ exactly corresponds with the above-

mentioned hydrochloric compound. The compounds with barium, $\text{BaPtCl}_6 \cdot 4\text{H}_2\text{O}$, strontium, $\text{SrPtCl}_6 \cdot 8\text{H}_2\text{O}$, calcium, magnesium, iron, manganese, and many other metals are all soluble in water.⁸

Platinous chloride, PtCl_2 , is formed when hydrogen platinochloride, PtH_2Cl_6 , is ignited at 300° , or when platinum is heated at 230° in a stream of chlorine. The undecomposed tetrachloride is extracted from the residue by washing it with water, and a greenish grey or brown insoluble mass of the dichloride (sp. gr. 5.9) is then obtained. It is soluble in hydrochloric acid, giving an acid solution of the composition $\text{PtCl}_2 \cdot 2\text{HCl}$, corresponding with the type of double salts PtR_2Cl_4 . Although platinous chloride decomposes below 500° , still it is partially formed at higher temperatures. Troost and Hautefeuille, and Seelheim observed that when platinum is strongly ignited in a stream of

⁸ Nilson (1877), who investigated the platinochlorides of various metals subsequently to Bonsdorff, Topsoë, Cleve, Marignac, and others, found that univalent and bivalent metals—such as hydrogen, potassium, ammonium . . . beryllium, calcium, barium—give compounds of such a composition that there is always twice as much chlorine in the platinic chloride as in the combined metallic chloride; for example, $\text{K}_2\text{Cl}_2 \cdot \text{PtCl}_4$; $\text{BeCl}_2 \cdot \text{PtCl}_4 \cdot 8\text{H}_2\text{O}$, &c. Such trivalent metals as aluminium, iron (ferric), chromium, didymium, cerium (cerous) form compounds of the type $\text{RCl}_3 \cdot \text{PtCl}_4$, in which the amounts of chlorine are in the ratio 3 : 4. Only indium and yttrium give salts of a different composition—namely, $2\text{InCl}_3 \cdot 5\text{PtCl}_4 \cdot 36\text{H}_2\text{O}$ and $4\text{YCl}_3 \cdot 5\text{PtCl}_4 \cdot 51\text{H}_2\text{O}$. Such quadrivalent metals as thorium, tin, zirconium give compounds of the type $\text{RCl}_4 \cdot \text{PtCl}_4$, in which the ratio of the chlorine = 1 : 1. In this manner the valency of a metal may, to a certain extent, be judged from the composition of the double salts formed with platinic chloride. Many of the above-mentioned compounds are, moreover, able to combine with different amounts of water of crystallisation.

Platinic bromide, PtBr_4 , and iodide, PtI_4 , are analogous to the tetrachloride, but the iodide is decomposed still more easily than the chloride. If sulphuric acid be added to platinic chloride, and the solution evaporated, it forms a black porous mass like charcoal, which deliquesces in the air, and presents the composition $\text{Pt}(\text{SO}_4)_2$. But this, the only oxygen salt of the type PtX_4 , is exceedingly unstable. This is due to the fact that *platinum oxide*, the oxide of the type PtO_2 , has a feeble acid character. This is shown in a number of instances. Thus if a solution of sodium carbonate be added to a strong solution of platinic chloride, and the solution be exposed to the action of light or evaporated to dryness and then washed with water, there remains a sodium platinate, $\text{Pt}_5\text{Na}_9\text{O}_7 \cdot 6\text{H}_2\text{O}$. The composition of this salt, if regarded in the same sense as we did the salts of silicic, titanitic, molybdic, and other acids, will be $\text{PtO}(\text{ONa})_2 \cdot 2\text{PtO}_2 \cdot 6\text{H}_2\text{O}$ —that is, the same type is repeated as we saw in the crystalline compounds of platinum tetrachloride with sodium chloride, or with hydrochloric acid—namely, the type $\text{PtX}_4 \cdot \text{Y}$, where Y is the molecule H_2O , HCl , &c. Similar compounds are also obtained with other alkalis. They will be platينات of the alkalis in which the platinic oxide, PtO_2 , plays the part of an acid oxide. If such an alkaline compound of platinum be treated with acetic acid, the alkali will pass over to the latter, and there remains a *platinic hydroxide*, $\text{Pt}(\text{OH})_4$, as a brown mass, which loses water and oxygen when ignited, and in so doing decomposes with a slight explosion. When slightly ignited this hydroxide first loses water and gives the very unstable oxide PtO_2 . Platinic sulphide, PtS_2 , belongs to the same type; it is precipitated by the action of sulphuretted hydrogen on a solution of platinum tetrachloride. The moist precipitate is capable of attracting oxygen, and is then converted into the sulphate above mentioned, which is soluble in water. Platinic sulphide gives crystalline compounds with the alkali sulphides.

chlorine, the metal, as it were, slowly volatilised and was deposited in crystals; a volatile chloride, probably platinous chloride, was naturally formed in this case, and decomposed subsequently to its formation with the deposition of crystals of platinum.

The above-described properties of platinum are repeated, sometimes distinctly and sometimes with a certain modification, in the above-mentioned associates and analogues of this metal, but naturally there are certain points of difference.⁹ With respect to the types of combi-

⁹ In comparing the characteristics of the platinum metals, it is not unimportant to remark that palladium in its forms of combination PdX_2 gives saline compounds of considerable stability. Amongst them *palladous chloride* is formed by the direct action of chlorine or aqua regia (not in excess nor in dilute solutions) on palladium. It forms a brown solution, which gives a black insoluble precipitate of *palladous iodide*, PdI_2 , with solutions of iodides (in this respect, as in many others, palladium resembles mercury in the mercuric compounds HgX_2). With a solution of mercuric cyanide it gives a yellowish white precipitate, palladous cyanide, PdC_3N_2 , which is soluble in potassium cyanide, and gives other double salts, $M_2PdC_4N_4$.

That portion of the platinum ore which dissolves in aqua regia and is precipitated by ammonium or potassium chloride does not contain palladium. It remains in solution, because the palladic chloride, $PdCl_4$, is decomposed and the palladous chloride formed is not precipitated by ammonium chloride; the same holds good for all the other lower chlorides of the platinum metals. Zinc (and iron) separates out all the unprecipitated platinum metals (and also copper, &c.) from the solution. It is in these platinum residues precipitated by zinc that the palladium is found. If this mixture of metals is treated with aqua regia, then all the palladium will pass into solution as palladous chloride and some platinic chloride. By this treatment the main portion of the iridium, rhodium, &c., remains almost undissolved, and the platinum is separated from the mixture of palladous and platinic chlorides by a solution of ammonium chloride, and the solution of palladium is precipitated by potassium iodide or mercuric cyanide. Wilm (1881) showed that palladium may be separated from an impure solution by saturating it with ammonia; all the iron present is thus precipitated, and, after filtering, the addition of hydrochloric acid to the filtrate gives a yellow precipitate of an ammonio-palladium compound: $PdCl_2 \cdot 2NH_3$, whilst nearly all the other metals remain in solution. *Metallic palladium* is obtained by igniting the ammonio-compound or the cyanide, PdC_3N_2 . It occurs native, although rarely, and is a metal of a whiter colour than platinum, sp. gr. 11.8; it is much more fusible than platinum, partially oxidises on the surface when heated, and loses its absorbed oxygen on a further rise of temperature. It does not blacken or tarnish (does not absorb sulphur) in the air at the ordinary temperature, and is therefore better suited than silver for astronomical and other instruments in which fine divisions have to be engraved on a white metal, in order that the fine lines should be clearly visible. The most remarkable property of palladium, discovered by Graham, consists in its capacity for *absorbing* a large amount of *hydrogen*. Ignited palladium absorbs as much as 940 volumes of hydrogen, or about 0.7 p.c. of its own weight, which closely approaches to the formation of the compound $Pd \cdot H_2$, and probably corresponds with the formation of *palladium hydride*, Pd_2H . This absorption also takes place at the ordinary temperature—for example, when palladium serves as an electrode on which hydrogen is evolved. In absorbing the hydrogen, the palladium does not change in appearance, and retains all its metallic properties, only its volume increases by about 10 p.c.—that is, the hydrogen pushes out and separates the atoms of the palladium from each other, and is itself compressed to $\frac{1}{10}$ of its volume. This compression indicates a great force of chemical attraction, and is accompanied by the evolution of heat (Vol. I. p. 141 and p. 599, Note 44). The absorbed hydrogen is easily disengaged

nation, all the platinum metals, as was said above, under the action of

by ignition or decreased pressure. The resultant compound does not decompose at the ordinary temperature, but when exposed to air the metal sometimes glows spontaneously, owing to the hydrogen burning at the expense of the atmospheric oxygen. The hydrogen absorbed by palladium acts towards many solutions as a reducing agent; in a word, everything here points to the formation of a definite compound and at the same time of a physically-compressed gas, and forms one of the best examples of the bond existing between chemical and physical processes, to which we have many times drawn attention. It must be again remembered that the other metals of the eighth group, even copper, are, like palladium and platinum, able to combine with hydrogen. The permeability of iron and platinum tubes to hydrogen is naturally due to the formation of similar compounds, because palladium is the most permeable.

Rhodium is generally separated, together with iridium, from the residues left after the treatment of native platinum, because the palladium is entirely separated from them, and the ruthenium is present in them in very small traces, whilst the osmium at any rate is easily separated, as we shall soon see. The mixture of rhodium and iridium which is left undissolved in dilute aqua regia is dissolved in chlorine water, or by the action of chlorine on a mixture of the metals with sodium chloride. In either case both metals pass into solution. They may be separated by many methods. In either case (if the action be aided by heat) the rhodium is obtained in the form of the chloride RhCl_3 , and the iridium as iridic chloride, IrCl_3 . They both form double salts with sodium chloride which are soluble in water, but the iridium salt is also partially soluble in alcohol, whilst the rhodium salt is not. A mixture of the chlorides, when treated with dilute aqua regia, gives iridic chloride, IrCl_4 , whilst the rhodium chloride, RhCl_3 , remains unaltered; ammonium chloride then precipitates the iridium as ammonium iridic chloride, $\text{Ir}(\text{NH}_4)_2\text{Cl}_6$, and on evaporating the rose-coloured filtrate the rhodium gives a crystalline salt, $\text{Rh}(\text{NH}_4)_5\text{Cl}_6$. Rhodium and its various oxides are dissolved when fused with potassium hydrogen sulphate, and give a soluble double sulphate (whilst iridium remains unacted on); this fact is very characteristic for this metal, which offers many points of resemblance with the iron metals in its properties. When fused with potassium hydroxide and chlorate it, like iridium, is oxidised, but it is not afterwards soluble in water, in which it differs from ruthenium. This is taken advantage of for separating rhodium, ruthenium, and iridium. In any case, rhodium under ordinary conditions always gives salts of the type RX_3 , and not of any other type; and not only halogen salts, but also oxygen salts, are known in this type, which is rare among the platinum metals. Rhodium chloride, RhCl_3 , is known in an insoluble anhydrous and also in a soluble form, in which it easily gives double salts, compounds with water of crystallisation, and forms rose-coloured solutions. In this form rhodium easily gives double salts of the two types RhM_3Cl_6 and RhM_2Cl_5 —for example, $\text{K}_3\text{RhCl}_6 \cdot 3\text{H}_2\text{O}$ and $\text{K}_2\text{RhCl}_5 \cdot \text{H}_2\text{O}$. Solutions of the salts (at least, the ammonium salt) of the first kind give salts of the second kind when they are boiled. If a strong solution of potash is added to a red solution of rhodium chloride and boiled, a black precipitate of the hydroxide $\text{Rh}(\text{OH})_3$ is formed; but if the solution of potash is added little by little, it gives a yellow precipitate containing more water. This yellow hydrate of rhodium oxide gives a yellow solution when it is dissolved in acids, which only becomes rose-coloured after being boiled. It is obvious that some, as yet unknown, change here takes place, like the transmutations of the salts of chromic oxide. It is also a remarkable fact that the black hydroxide, like many other oxidised compounds of the platinoid metals, does not dissolve in the ordinary oxygen acids, whilst the yellow hydroxide is easily soluble and gives yellow solutions, which deposit imperfectly crystallised salts. Metallic rhodium is easily obtained by igniting its oxygen and other compounds in hydrogen, or by precipitation with zinc. It resembles platinum, and has a sp. gr. of 12.1. At the ordinary temperature it decomposes formic acid into hydrogen and carbonic anhydride, with development of heat (Deville). With the alkali sulphites, the salts of rhodium and iridium of the type RX_3 give sparingly-soluble precipitates of double sulphites of the

an excess of chlorine or of oxidising agents give compounds of the type

composition $R(\text{SO}_3\text{Na})_5\cdot\text{H}_2\text{O}$, by means of which these metals may be separated from solution, and also may be separated from each other, for a mixture of these salts when treated with strong sulphuric acid gives a soluble iridium sulphate and leaves a red insoluble double salt of rhodium and sodium. It is further necessary to remark that the oxides Ir_2O_3 and Rh_2O_3 are comparatively stable and are very often formed. Thus the *iridious oxide*, Ir_2O_3 , is obtained by fusing iridious chloride and its compounds with sodium carbonate, and treating the mass with water. The oxide is then left as a black powder, which, when strongly heated, is decomposed into iridium and oxygen; it is easily reduced, and is insoluble in acids, which indicates the feeble basic character of this oxide, in many respects resembling such oxides as cobaltic oxide, ceric or lead dioxide, &c. It does not dissolve when fused with potassium hydrogen sulphate. Rhodium oxide, Rh_2O_3 , is a far more energetic base. It dissolves when fused with potassium hydrogen sulphate.

From what has been said respecting the separation of platinum and rhodium it will be understood how the compounds of *iridium*, which is the main associate of platinum, are obtained. In describing the treatment of osmiridium we shall again have an occasion of learning the method of extraction of the compounds of this metal, which has in recent times found a technical application in the form of its oxide, Ir_2O_3 ; this is obtained from many of the compounds of iridium by ignition with water, and is easily reduced by hydrogen and is insoluble in acids. It is used in painting on china, for giving a black colour. Iridium itself is more difficultly fusible than platinum, and when fused it does not decompose acids or even aqua regia; it is extremely hard, and is not malleable; its sp. gr. is 21.1. In the form of powder it dissolves in aqua regia, and is even partially oxidised when heated in air, sets fire to hydrogen, and, in a word, closely resembles platinum. Heated in an excess of chlorine it gives iridic chloride, IrCl_4 , but this loses chlorine at 50° ; it is, however, more stable in the form of double salts, but they give iridious chloride, IrCl_5 , when treated with sulphuric acid.

We have yet to become acquainted with the two remaining associates of platinum—ruthenium and osmium—whose most important property is that they are oxidised even when heated in air, and that they are able to give *volatile* oxides of the form RuO_4 and OsO_4 ; these have a powerful odour (like iodine and nitrous anhydride). Both these higher oxides are solids; they volatilise with great ease at 100° ; the former is yellow and the latter white. They are known as *ruthenic* and *osmic anhydrides*, although their aqueous solutions (they both slowly dissolve in water) do not show an acid reaction, and although they do not even expel carbonic anhydride from potassium carbonate, do not give crystalline salts with bases, and their alkaline solutions partially deposit them again when boiled (an excess of water decomposes the salts). The formulæ OsO_4 and RuO_4 correspond with the vapour density of these oxides. Thus Deville found the vapour density of osmic anhydride to be 128 (by the formula 127.5) referred to hydrogen. Tennant and Vauquelin discovered this compound, and Berzelius, Wöhler, Fritzsche, Struvé, Deville, Claus, and others helped in its investigation; nevertheless there are still many questions concerning it which remain unsolved. It should be observed that RO_4 is the highest known form for an oxygen compound, and RH_4 is the highest known form for a compound of hydrogen; and the highest forms of acid hydrates contain SiH_4O_4 , PH_5O_4 , SH_4O_4 , CH_4O_4 —all with four atoms of oxygen, and therefore in this number there is apparently the limit for the simple forms of combination of hydrogen and oxygen. For *several* atoms of an element or for several elements there may be more than O_4 or H_4 , but a molecule never contains more to one atom of another element. Thus the simplest forms of combination of hydrogen and oxygen are exhausted by the list RH_4 , RH_5 , RH_2 , RH , RO , RO_2 , RO_3 , RO_4 . The extreme members are RH_4 and RO_4 , and are only met with for such elements as carbon, silicon, osmium, ruthenium, which also give RCl_4 with chlorine. In these extreme forms, RH_4 and RO_4 , the compounds are the least stable (compare SiH_4 , PH_5 , SH_4 , CH_4 , or RuO_4 , MoO_5 , ZrO_5 , SrO_5), and easily give up part, or even all, their oxygen or hydrogen. The primary source from which the compounds of ruthenium and osmium are

RX_4 —for instance, RO_2 , RCl_4 , &c. This is the highest form for

obtained is either *osmiridium* (the osmium predominates, from $IrOs$ to $IrOs_4$, sp. gr. from 16 to 21), which occurs in platinum ores (it is distinguished from the grains of platinum by its crystalline structure, hardness, and insolubility in aqua regia), or else those insoluble residues which are obtained, as we saw above, after treating platinum with aqua regia. Osmium predominates in these materials, which sometimes contain from 80 p.c. to 40 p.c. of it, and rarely more than 4 p.c. to 5 p.c. of ruthenium. The process for their treatment is as follows: they are first fused with 6 parts of zinc, and the zinc then extracted with dilute hydrochloric acid. The osmiridium thus treated is, according to Fritzsche and Struvé's method, then added to a fused mixture of potassium hydroxide and chlorate in an iron crucible; the mass as it begins to evolve oxygen acts on the metal, and the reaction afterwards goes on unaided. The dark product is treated with water, and gives a solution of osmium and ruthenium in the form of soluble salts R_2OsO_4 and R_2RuO_4 , whilst the insoluble residue contains a mixture of oxides of iridium (and some osmium, rhodium, and ruthenium), and grains of metallic iridium still unacted on. According to Fritzsche's method the lumps of osmiridium are straightway heated to whiteness in a porcelain tube in a stream of air or oxygen, when the very volatile osmic anhydride is obtained directly, and is collected in a well-cooled receiver, while the ruthenium gives a crystalline sublimate of the dioxide, RuO_2 , which is, however, very difficultly volatile (it volatilises together with osmic anhydride), and therefore remains in the cooler portions of the tube; this method does not give volatile ruthenic anhydride, and the iridium and other metals are not oxidised or give non-volatile products. This method is simple, and at once gives dry, pure osmic anhydride in the receiver, and ruthenium dioxide in the sublimate. The air which passes through the tube should be previously passed through sulphuric acid, not only for the sake of drying, but also to remove the organic and reducing dust. The vapour of osmic anhydride must be powerfully cooled, and ultimately passed over caustic potash. A third mode of treatment, which is most frequently employed, was proposed by Wöhler, and consists in slightly heating (in order that the sodium chloride should not volatilise) an intimate mixture of osmiridium and common salt in a stream of moist (undried) chlorine. The metals then form compounds with chlorine and sodium chloride, whilst the osmium forms the chloride, $OsCl_4$, which reacts with the moisture, and gives osmic anhydride, which is condensed. The ruthenium in this, as in the other processes, does not directly give ruthenic anhydride, but is always extracted as the soluble ruthenium salt, K_2RuO_4 , obtained by fusion with potassium hydroxide and chlorate or nitrate. When the orange-coloured ruthenate, K_2RuO_4 , is mixed with acids the liberated ruthenic acid immediately decomposes into the volatile ruthenic anhydride and the insoluble ruthenic oxide: $2K_2RuO_4 + 4HNO_3 = RuO_4 + RuO_2 \cdot 2H_2O + 4KNO_3$. When once one of the above compounds of ruthenium or osmium is procured it is easy to obtain all the remaining compounds, and by reduction (by metals, hydrogen, formic acid, &c.) the metals themselves.

Osmic anhydride, OsO_4 , is very easily deoxidised by many methods. It blackens organic substances, owing to reduction, and is therefore used in investigating vegetable and animal, and especially nerve, preparations under the microscope. Although osmic anhydride may be distilled in hydrogen, still complete reduction is accomplished when a mixture of hydrogen and osmic anhydride is slightly ignited (just before it inflames). If osmium be placed in the flame it is oxidised, and gives vapours of osmic anhydride, which are reduced, and the flame gives a brilliant light. Osmic anhydride deflagrates like nitre on red-hot charcoal; zinc, and even mercury and silver, reduce osmic anhydride from its aqueous solutions into the lower oxides or metal; such reducing agents as hydrogen sulphide, ferrous sulphate, or sulphurous anhydride, alcohol, &c., act in the same manner with great ease.

The lower oxides of osmium, ruthenium, and of the other elements of the platinum series are not volatile, and it is very worthy of remark that the other elements present a different phenomenon. On comparing SO_2 , SO_5 ; As_2O_3 , As_2O_5 ; P_2O_3 , P_2O_5 ; CO , CO_2 , &c., we observe a converse phenomenon; the higher oxides are less volatile than the

platinum and palladium.¹⁰ The remaining platinum metals further, like iron, give acids of the type RO_3 , or, more correctly, $\text{H}_2\text{RO}_4 =$

lower. In the case of osmium all the oxides, with the exception of the highest, are non-volatile, and it may therefore be thought that this higher form is more simply constituted than the lower. Perhaps osmic oxide, OsO_3 , stands in the same relation to the anhydride as C_2H_4 to CH_4 —i.e., perhaps the lower oxide is Os_2O_4 , or presents a still higher polymerism, and it will then be understood how the lower oxides, having a greater molecular weight, are less volatile than the higher oxides, just as we saw in the case of the nitrogen oxides, N_2O and NO .

Ruthenium and osmium, obtained by the ignition or reduction of their compounds in a form of powder, have a density considerably less than in the fused form, and differ in this form in their capacity for reaction; they are much more difficultly fused than platinum and iridium, although ruthenium is more fusible than osmium. The powder of ruthenium has a specific gravity of 8.5, the fused metal of 11.4; osmium in powder has a specific gravity of 20.0, and when semi-fused—or, more strictly speaking, agglomerated—in the oxy-hydrogen flame, of 21.4. The powder of slightly-heated osmium oxidises very easily in the air, and when ignited burns like tinder, directly forming the odoriferous (hence its name, from the Greek word signifying odour) osmic anhydride; ruthenium also oxidises when heated in air, but with more difficulty, forming the oxide RuO_3 . The oxides of the types RO , R_2O_3 , and RO_2 (and their hydrates), obtained by reduction from the higher oxides, and also from chlorides, are analogous to those given by the other platinum metals, in which respect osmium and ruthenium closely resemble them. We may also remark that ruthenium has been found in the platinum deposits of Borneo in the form of *laurite*, R_2S_3 , in grey octahedra of sp. gr. 7.0.

Debray and Joly showed that ruthenic anhydride, RuO_4 , fuses at 25° , boils at 100° , and evolves oxygen when dissolved in potash, forming the salt KRuO_4 (not isomorphous with potassium permanganate).

¹⁰ Although palladium gives the same types of combination (with chlorine) as platinum, its reduction is incomparably easier than that of platonic chloride, and in the case of iridium it is still more so. Iridic chloride, IrCl_4 , acts as an oxidising agent, readily parts with a fourth of its chlorine to a number of substances, readily evolves chlorine when heated, and it is only at low temperatures that chlorine and aqua regia convert iridium into iridic chloride. In disengaging chlorine iridium more often and easily gives the very stable iridious chloride, IrCl_5 (perhaps this substance is $\text{Ir}_2\text{Cl}_6 = \text{IrCl}_3 \cdot \text{IrCl}_4$, insoluble in water, but soluble in potassium chloride, because it forms the double salt K_2IrCl_6), than the dichloride, IrCl_2 . This compound, corresponding to IrX_3 , is very stable, and corresponds with the *basic oxide*, Ir_2O_3 , resembling the oxides Fe_2O_3 , Co_2O_3 . Hence to this form there correspond ammoniacal compounds similar to those given by cobaltic oxide. Although iridium also gives an acid in the form of the salt $\text{K}_2\text{Ir}_2\text{O}_7$, it does not, like iron (and chromium), form the corresponding chloride, IrCl_6 . In general, in this as in the other elements, it is impossible to judge the chlorine compounds from those with oxygen. Just as there is no chloride SCl_6 , but only SCl_2 , so also, although $\text{IrO}_3(\text{RO})_2$ does exist, still IrCl_6 is wanting, and it only gives IrCl_4 , and this is unstable, like SCl_2 , and easily parts with its chlorine. In this respect rhodium is very much like iridium (as platinum is like palladium). It does not seem to form the chloride RhCl_4 at all (it probably decomposes with extreme ease) whilst rhodium chloride, RhCl_3 , is very stable, like many of the salts of the type RhX_3 , although after the manner of the platinum elements these salts are easily reduced to metal by the action of heat and powerful reagents. There is as close a resemblance between osmium and ruthenium. Osmium when submitted to the action of dry chlorine gives osmic chloride, OsCl_4 , but the latter is converted by water (as is osmium by moist chlorine) into osmic anhydride, although the greater portion is then decomposed into $\text{Os}(\text{HO})_4$ and 4HCl , like a chloranhydride of an acid. In general this acid character is more developed in osmium than in platinum and iridium. Having parted with chlorine, osmic chloride, OsCl_4 , gives the un-

$\text{RO}_2(\text{HO})_2$ (the type of sulphuric acid); but they, like ferric and manganic acids, are only known in the form of salts of the composition K_2RO_4 or $\text{K}_2\text{R}_2\text{O}_7$ (like the dichromate). These salts are obtained, like the manganates and ferrates, by fusing the oxides, or even the metals themselves, with nitre, or, better still, with potassium peroxide. They are soluble in water, are easily deoxidised, and do not yield the acid anhydrides under the action of acids, but break up, either (like the ferrate) forming oxygen and a basic oxide (iridium and rhodium react in this manner, as they do not give higher forms of oxidation), or passing into a lower and higher form of oxidation—that is, reacting like a manganate (or partly like nitrite or phosphite). Osmium and ruthenium react according to the latter form, as they are capable of giving *higher forms of oxidation* OsO_4 and RuO_4 , and therefore their reactions of decomposition may be essentially represented by the equation: $2\text{OsO}_3 = \text{OsO}_2 + \text{OsO}_4$.

Platinum and its analogues, like iron and its analogues, are able to form complex and comparatively stable cyanogen and ammonia compounds, corresponding with the ferrocyanides and the ammoniacal compounds of cobalt, which we have already considered in the preceding chapter.

If platinous chloride, PtCl_2 (insoluble in water), is added by degrees to a solution of potassium cyanide, it is completely dissolved (like silver chloride), and on evaporation the solution deposits rhombic prisms of *potassium platinocyanide*, $\text{PtK}_2(\text{CN})_4 \cdot 3\text{H}_2\text{O}$. This salt, like all those corresponding with it, has a remarkable play of colours, due to the phenomena of dichromism, and even polychromism, natural to all the platinocyanides. Thus it is yellow, and reflects a bright blue light. It is easily soluble in water, effloresces in air, then turns red, and at 100° orange, when it loses all its water. The loss of water does not destroy its stability—that is, it still remains unchanged, and its stability is further shown by the fact that it is formed when potassium ferrocyanide, $\text{K}_4\text{Fe}(\text{CN})_6$, is heated with platinum black. This salt, first obtained by Gmelin, shows a neutral reaction with litmus; it is exceedingly stable under the action of air, like potassium ferrocyanide, which it resembles in many respects. Thus the platinum in it cannot be discovered by reagents such as sulphuretted hydrogen; the potassium may be replaced by other metals by the action of their salts, so that it corresponds with a whole series of compounds $\text{R}_2\text{Pt}(\text{CN})_4$,

stable trichloride, OsCl_3 , and the stable soluble dichloride, OsCl_2 , which corresponds with platinous chloride in its properties and reactions. The relation of ruthenium to the halogens is of the same nature. These are the most important facts regarding the forms of combination of the platinum metals.

and it is stable, although the potassium cyanide and platinous salt, of which it is composed, individually easily undergo change. When treated with oxidising agents it, like the ferrocyanide, passes into a higher form of combination of platinum. If salts of silver be added to its solution, it gives a heavy white precipitate of silver platinocyanide, $\text{PtAg}_2(\text{CN})_4$, which, when suspended in water and treated with sulphuretted hydrogen, enters into double decomposition with the latter and forms insoluble silver sulphide, Ag_2S , and soluble *hydroplatinocyanic acid*, $\text{H}_2\text{Pt}(\text{CN})_4$. If potassium platinocyanide is mixed with an equivalent quantity of sulphuric acid, then the hydroplatinocyanic acid liberated may be extracted by a mixture of alcohol and ether. The ethereal solution, when evaporated in a desiccator, deposits bright red crystals of the composition $\text{PtH}_2(\text{CN})_4 \cdot 5\text{H}_2\text{O}$. This acid colours litmus paper, liberates carbonic anhydride from sodium carbonate, and saturates alkalis, so that it presents an analogy to hydroferrocyanic acid.¹¹

¹¹ This acid character is explained by the influence of the platinum on the hydrogen, and by the attachment of the cyanogen groups. Thus cyanuric acid, $\text{H}_5(\text{CN})_3\text{O}_5$, is an energetic acid compared with cyanic acid, HCNO . And the formation of a compound with five molecules of water of crystallisation confirms the opinion that platinum is able to form compounds of still higher types than that expressed in its saline compounds, and, moreover, the combination of hydroplatinocyanic acid with water does not reach the limit of the compounds which appears in $\text{PtCl}_4 \cdot 2\text{HCl} \cdot 6\text{H}_2\text{O}$.

A whole series of *platinocyanides* of the common type $\text{PtR}_2(\text{CN})_4 \cdot n\text{H}_2\text{O}$ are obtained by means of double decompositions with the potassium or hydrogen or silver salts. For example, the salts of sodium and lithium contain, like the potassium salt, three molecules of water. The sodium salt is soluble in water and alcohol. The ammonium salt has the composition $\text{Pt}(\text{NH}_4)_2(\text{CN})_4 \cdot 2\text{H}_2\text{O}$, and gives crystals which reflect blue and rose-coloured light. This ammonium salt decomposes at 360° , with evolution of water and ammonium cyanide, leaving a greenish *platinum dicyanide*, $\text{Pt}(\text{CN})_2$, which is insoluble in water and acid but dissolves in potassium cyanide, hydrocyanic acid, and other cyanides. The same platinous cyanide is obtained by the action of sulphuric acid on the potassium salts in the form of a reddish-brown amorphous precipitate. The most characteristic of the platinocyanides are those of the alkaline earths. The magnesium salt $\text{PtMg}(\text{CN})_4 \cdot 7\text{H}_2\text{O}$ crystallises in regular prisms, whose side faces are of a metallic green colour and terminal planes dark blue. It shows a carmine-red colour along the main axis, and dark red along the lateral axes; it easily loses water, $2\text{H}_2\text{O}$, at 40° , and then turns blue (it then contains $5\text{H}_2\text{O}$, which is frequently the case with the platinocyanides). Its aqueous solution is colourless, and an alcoholic solution deposits yellow crystals. The remainder of the water is given off at 230° . It is obtained by saturating platinocyanic acid with magnesia, and by double decomposition between the barium salt and magnesium sulphate. The strontium salt $\text{SrPt}(\text{CN})_4 \cdot 4\text{H}_2\text{O}$ crystallises in milk-white plates having a violet and green play of colours. When it effloresces in a desiccator, its surfaces have a violet and metallic green play of colours. A colourless solution of the barium salt $\text{PtBa}(\text{CN})_4 \cdot 4\text{H}_2\text{O}$ is obtained by saturating a solution of hydroplatinocyanic acid with baryta, or by boiling the insoluble copper platinocyanide in baryta water. It crystallises in monoclinic prisms of a yellow colour, with blue and green reflections; it loses half its water at 100° , and the whole at 150° . Ethyl also gives a very characteristic salt, $\text{Pt}(\text{C}_2\text{H}_5)_2(\text{CN})_4 \cdot 2\text{H}_2\text{O}$, whose crystals are isomorphous with those of the potassium salt,

As ammonia, like potassium cyanide, is capable of further combination, so the combination of a platinum salt PtX_2 with ammonia gives

and are obtained by passing hydrochloric acid into an alcoholic solution of hydroplatinocyanic acid.

By the action of chlorine on dilute nitric acid, the platinocyanides are converted into salts of the composition $\text{PtM}_2(\text{CN})_5$, which corresponds with $\text{Pt}(\text{CN})_3, 2\text{KCN}$ —that is, they express the type of a non-existent form of oxidation of platinum, PtX_3 (*i.e.* oxide Pt_2O_3), just as potassium ferricyanide ($\text{FeCy}_3, 3\text{KCy}$) corresponds with ferric oxide, and the ferrocyanide corresponds with the ferrous oxide. The potassium salt of this series contains $\text{PtK}_2(\text{CN})_5, 3\text{H}_2\text{O}$, and forms brown regular prisms with a metallic lustre, and is soluble in water but insoluble in alcohol. Alkalis re-convert this compound into the ordinary platinocyanide $\text{K}_2\text{Pt}(\text{CN})_4$, taking up the excess of cyanogen. It is remarkable that the salts of the type PtM_2Cy_5 contain the same amount of water of crystallisation as those of the type PtM_2Cy_4 . Thus the salts of potassium and lithium contain three and the salt of magnesium seven, molecules of water, like the corresponding salts of the type of platinous oxide. Moreover, neither platinum nor any of its associates gives any cyanogen compound corresponding with the oxide, *i.e.* having the composition PtK_2Cy_6 , just as there are no compounds higher than those which correspond to $\text{RCy}_5, 2\text{MCy}$, for cobalt or iron. This would appear to indicate the absence of any such cyanides, and indeed, for no element are there yet known any poly-cyanides containing more than three equivalents of cyanogen for one equivalent of the element. This phenomenon is perhaps connected with the faculty of cyanogen to give tricyanogen polymerides, such as cyanuric acid, solid cyanogen chloride, &c. It is also necessary to turn attention to the fact that ruthenium and osmium—which, as we know, give higher forms of oxidation than platinum—are also able to combine with a larger proportion of potassium cyanide (but not of cyanogen) than platinum. Thus ruthenium forms a crystalline *hydroruthenocyanic acid*, $\text{RuH}_4(\text{CN})_6$, which is soluble in water and alcohol, and corresponds with the salts $\text{M}_1\text{Ru}(\text{CN})_6$. There are exactly similar osmic compounds—for example, $\text{K}_4\text{Os}(\text{CN})_6, 3\text{H}_2\text{O}$. The latter is obtained in the form of colourless, sparingly-soluble regular tablets or evaporating the solution obtained from a fused mixture of potassium osmiochloride, K_2OsCl_6 , and potassium cyanide. These osmic and ruthenic compounds fully correspond with potassium ferrocyanide, $\text{K}_4\text{Fe}(\text{CN})_6, 3\text{H}_2\text{O}$, not only in their composition but also in their crystalline form and reactions, which again demonstrates the close analogy between iron, ruthenium, and osmium, which we have shown by giving these three elements a similar position (in the eighth group) in the periodic system. For rhodium and iridium there are known only salts of the same type as the ferricyanides, M_5RCy_6 , and for palladium only of the type M_3PdCy_4 , which are analogous to the platinum salts. In all this one cannot but see a *constancy of the types* of the double cyanides. In the eighth group we have iron, cobalt, nickel, copper, and their analogues ruthenium, rhodium, palladium, silver, and also osmium, iridium, platinum, gold. The double cyanides of iron, ruthenium, osmium have the type $\text{K}_4\text{R}(\text{CN})_6$; of cobalt, rhodium, iridium, the type $\text{K}_3\text{R}(\text{CN})_6$; of nickel, palladium, platinum the type $\text{K}_2\text{R}(\text{CN})_4$ and $\text{K}_2\text{R}(\text{CN})_5$; and for copper, silver, gold there are known $\text{KR}(\text{CN})_2$, so that the presence of 4, 3, 2, and 1 atoms of potassium (in the higher proportion) corresponds with the order of the elements in the periodic system. Those types which we have seen in the ferrocyanides and ferricyanides of iron repeat themselves in all the platinoid metals, and this involuntarily leads one to conclude that the formation of similar so-called double salts is of exactly the same nature as that of the ordinary salts. If, for the expression of the bond of the elements in the oxygen salts, one recognises the existence of an *aqueous residue* (hydroxyl group), in which the hydrogen is replaced by a metal; then we have only to apply this mode of expression to the double salts and the analogy will be obvious, if we only remember that Cl_2 , $(\text{CN})_2$, SO_4 , &c., are equivalent to O, as we see in RO , RCl_2 , RSO_4 , &c. Therefore, wherever OH can be placed, there we can also place Cl_2H , $(\text{CN})_2\text{H}$, SO_4H , &c. Thus the double salt $\text{MgSO}_4, \text{K}_2\text{SO}_4$, according to this reasoning, may be counted as a substance of the same

such stable compounds as are obtained by means of the cyanogen compounds. But as ammonia does not contain any hydrogen easily

type as MgCl_2 , namely, $=\text{Mg}(\text{SO}_4\text{K})_2$, and the alums as containing $\text{Al}(\text{OH})(\text{SO}_4)$, namely, $\text{Al}(\text{SO}_4\text{K})(\text{SO}_4)$. It is also possible to take the water of crystallisation into account here. It may also be introduced into such formulae as the above, but we will not linger over this digression and only apply these considerations to the type of the ferrocyanides and ferricyanides and their platinum analogues. Such a salt as K_2PtCy_4 therefore may be regarded as $\text{Pt}(\text{Cy}_2\text{K})_2$, like $\text{Pt}(\text{OH})_2$; and such a salt as PtK_2Cy_5 as $\text{PtCy}(\text{Cy}_2\text{K})_2$, the analogue of $\text{PtX}(\text{OH})_2$, or $\text{AlX}(\text{OH})_3$, and other compounds of the type RX_5 . Potassium ferricyanide and the analogous compounds of cobalt, iridium, and rhodium, belong to the same type, with the same difference as there is between $\text{RX}(\text{OH})_2$ and $\text{R}(\text{OH})_3$, because $\text{FeK}_2\text{Cy}_6 = \text{Fe}(\text{Cy}_2\text{K})_3$. Limiting myself to these considerations, which may partially elucidate the nature of double salts, I will now pass again to the complex saline compounds known for platinum.

On mixing a solution of potassium thiocyanate with a solution of potassium platinosulphate, K_2PtCl_4 , they form a double thiocyanate, $\text{PtK}_2(\text{CNS})_4$, which is easily soluble in water and alcohol, crystallises in red prisms, and gives an orange-coloured solution, which precipitates salts of the heavy metals. The action of sulphuric acid on the lead salt of the same type gives the acid itself, $\text{PtH}_2(\text{SCN})_4$, which corresponds with these salts. The type of these compounds is evidently the same as that of the cyanides.

Platinous chloride, PtCl_2 , which is insoluble in water, forms double salts with the metallic chlorides. These double chlorides are soluble in water, and capable of crystallising. Hence when a hydrochloric acid solution of platinous chloride is mixed with solutions of metallic salts and evaporated it forms crystalline salts of a red or yellow colour. Thus, for example, the potassium salt, PtK_2Cl_4 , is red, and easily soluble in water; the sodium salt is also soluble in alcohol; the barium salt, $\text{PtBaCl}_4 \cdot 3\text{H}_2\text{O}$, is soluble in water, but the silver salt, PtAg_2Cl_4 , is insoluble in water, and may be used for obtaining the remaining salts by means of double decomposition with their chlorides.

A remarkable example of the complex compounds of platinum was observed by Schützenberger. He showed that finely-divided platinum in the presence of chlorine and carbonic oxide at 300° gives phosgene and a volatile compound containing platinum. A similar substance is formed by the action of carbonic oxide on platinous chloride. It is decomposed with explosion by water. Carbon tetrachloride dissolves a portion of this substance, and on evaporation gives crystals of $2\text{PtCl}_2 \cdot 3\text{CO}$, whilst the compound $\text{PtCl}_2 \cdot 2\text{CO}$ remains undissolved. When fused and sublimed it gives yellow needles of $\text{PtCl}_2 \cdot \text{CO}$, and in the presence of an excess of carbonic oxide $\text{PtCl}_2 \cdot 2\text{CO}$ is formed. These compounds are fusible (the first at 250° , the second at 142° , and the third at 195°). In this case (as in the double cyanides) combination takes place, because both carbonic oxide and platinous chloride are unsaturated compounds capable of further combination.

The faculty of platinous chloride for forming particularly stable compounds with divers substances which on their side have the faculty for further combination (like potassium cyanide or carbonic oxide), shows itself in the formation of the compound $\text{PtCl}_2 \cdot \text{PCl}_5$ by the action of phosphorus pentachloride at 250° on platinum powder. The product contains both phosphorus pentachloride and platinum, whilst the presence of PtCl_2 is shown from the fact that the action of water produces *chlorplatino-phosphorous acid*, $\text{PtCl}_2\text{P}(\text{OH})_3$. It evidently corresponds, on the one hand, with phosphoric acid, and, on the other hand, with those products which are formed by the complication of PtCl_2 .

After the cyanides, the double salts of platinum formed by sulphurous acid are most distinguished for their stability and characteristic properties. This is all the more instructive as sulphurous acid is only feebly energetic, and moreover in these, as in all its compounds, it exhibits a dual reaction. The salts of sulphurous acid, R_2SO_5 , either react as salts of a feeble bibasic acid, where the group SO_3 presents itself as bivalent, and consequently equal to X_2 , or else they react after the manner of salts of a monobasic

replaceable by metals, and as ammonia itself is able to combine with acids, so the PtX_2 plays, as it were, the part of an acid with reference

acid containing the same residue, RSO_3 , as occurs in the salts of sulphuric acid. In sulphurous acid this residue is combined with hydrogen, $\text{H}(\text{SO}_3\text{H})$, whilst in sulphuric acid it is united with the aqueous residue (hydroxyl), $\text{OH}(\text{SO}_3\text{H})$. These two forms of action of the sulphites appear in their reactions with the platinum salts—that is to say salts of both kinds are formed, and they both correspond with the type PtH_2X_4 . The one series of salts contain $\text{PtH}_2(\text{SO}_3)_2$, and their reactions are due to the bivalent residue of sulphurous acid, which replaces X_2 . The others, which have the composition $\text{PtR}_2(\text{SO}_3\text{H})_4$, contain sulphonyl. Therefore the latter salts will evidently react like acids, and if we did not differentiate the hydrogen here contained they would be represented as $\text{PtR}_2\text{H}_2(\text{SO}_3)_4$. But then we might suppose that these salts were formed from other sources, which is not true, because the salts of this kind are formed simultaneously with the salts of the first kind, and pass into them. These salts are obtained either by directly dissolving platinous oxide in water containing sulphurous acid, or by passing sulphurous anhydride into a solution of platinous chloride in hydrochloric acid. It may therefore be supposed that these salts contain platinous sulphite, PtSO_3 , but it is unknown in a free state, and only appears in the form of double salts. Thus, if a solution of platinous chloride or platinous oxide in sulphurous acid be saturated with sodium carbonate, it forms a white, sparingly soluble precipitate containing $\text{PtNa}_2(\text{SO}_3)_2 \cdot 7\text{H}_2\text{O}$. If this precipitate is dissolved in a small quantity of hydrochloric acid and left to evaporate at the ordinary temperature, it deposits a salt of the other type, $\text{PtNa}_2(\text{SO}_3)_2 \cdot \text{H}_2\text{O}$, in the form of a yellow powder, which is sparingly soluble in water. The potassium salt analogous to the first salt, $\text{PtK}_2(\text{SO}_3)_2 \cdot 2\text{H}_2\text{O}$, is precipitated by passing sulphurous anhydride into a solution of potassium sulphite in which platinous oxide is suspended. A similar salt is known for ammonium, and with hydrochloric acid it gives a salt of the second kind, $\text{Pt}(\text{NH}_4)_2(\text{SO}_3)_2 \cdot \text{H}_2\text{O}$. If ammonio-chloride of platinum be added to an aqueous solution of sulphurous anhydride, it is first deoxidised, and chlorine is evolved, forming a salt of the type PtX_2 ; a double decomposition then takes place with the ammonium sulphite, and a salt of the composition $\text{Pt}(\text{NH}_4)_2\text{Cl}_2(\text{SO}_3\text{H})_2$ is formed (in a desiccator). The acid character of this substance is explained by the fact that it contains the elements SO_3H —sulphonyl, with the hydrogen not yet displaced by a metal. On saturating a solution of this acid with potassium carbonate it gives orange-coloured crystals of a potassium salt of the composition $\text{Pt}(\text{NH}_4)_2\text{Cl}_2(\text{SO}_3\text{K})_2$. Here it is evident that an equivalent of chlorine in $\text{Pt}(\text{NH}_4)_2\text{Cl}_4$ is replaced by the univalent residue of sulphurous acid. Among these salts, that of the composition $\text{Pt}(\text{NH}_4)_2\text{Cl}_2(\text{SO}_3\text{H})_2 \cdot \text{H}_2\text{O}$ is very readily formed, and crystallises in well-formed colourless crystals; it is obtained by dissolving ammonium platinochloride, $\text{Pt}(\text{NH}_4)_2\text{Cl}_4$, in an aqueous solution of sulphurous acid. The difficulty with which sulphurous anhydride and platinum are separated from these salts indicates the same basic character in these compounds as is seen in the double cyanides of platinum. In their passage into a complex salt, the metal platinum and the group SO_2 modify their relations (compared with those of PtX_2 or SO_2X_2), just as the chlorine in the salts KClO , KClO_2 , and KClO_4 is modified in its relations as compared with hydrochloric acid or potassium chloride.

No less characteristic are the *platinonitrites* formed by platinous oxide. They correspond with nitrous acid, whose salts, RNO_2 , contain the univalent radicle NO_2 , which is capable of replacing chlorine, and therefore the salts of this kind should form a common type $\text{PtR}_2(\text{NO}_2)_4$, and such a salt of potassium has actually been obtained by mixing a solution of potassium platinochloride with a solution of potassium nitrite, when the liquid becomes colourless, especially if it be heated, which indicates the change in the chemical distribution of the elements. As the liquid decolorises it gradually deposits sparingly soluble, colourless prisms of the potassium salt $\text{K}_2\text{Pt}(\text{NO}_2)_4$, which does not contain any water. With silver nitrate a solution of this salt gives a precipitate of silver platinonitrite, $\text{PtAg}_2(\text{NO}_2)_4$. The silver of this salt may be replaced by other

to the ammonia. Owing to the influence of the ammonia, the X_2 in the resultant compound will present the same character as it has in ammoniacal salts; consequently, the ammoniacal compounds produced from PtX_2 will be salts in which X will be replaceable by various other haloids, just as the metal is replaced in the cyanogen salts, such is the nature of the *platino-ammonium compounds*. PtX_2 forms compounds with $2NH_3$ and with $4NH_3$, and so also PtX_4 gives (but not directly from PtX_4 and ammonia, but from the compounds of PtX_2 by the action of chlorine, &c.) like compounds with $2NH_3$ and with $4NH_3$.¹²

metals by means of double decomposition with metallic chlorides. The sparingly soluble barium salt, when treated with an equivalent quantity of sulphuric acid, gives a soluble acid, which separates, under the receiver of an air-pump, in red crystals; this is probably an acid of the composition $PtH_2(NO_2)_4$.

¹² The platinum salt and ammonia, when once combined together, are no longer subject to their ordinary reactions, but form comparatively very stable compounds. The self-evident question occurs to all who are acquainted with these phenomena, as to what is the relation of the elements contained in these compounds. The first explanation which suggests itself is that these compounds are salts of ammonium in which the hydrogen is partially replaced by platinum. This is the view, with certain shades of difference, held by many respecting the platino-ammonium compounds. They were regarded in this light by Gerhardt, Schiff, Kolbe, Weltzien, and many others. If we suppose the hydrogen in $2NH_3X$ to be replaced by bivalent platinum (as in the salts PtX_2), then we shall obtain $\begin{smallmatrix} NH_3 \\ NH_5 \end{smallmatrix} Pt \begin{smallmatrix} X \\ X \end{smallmatrix}$ —that is, the compound $PtX_2 \cdot 2NH_3$. The compound with $4NH_3$ will then be represented by a further substitution of the hydrogen in ammonia by ammonium itself—i.e. as $NH_2(NH_4X)_2Pt$ —that is, we shall obtain the compound $PtX_2 \cdot 4NH_3$. A modification of this view is found in that representation of compounds of this kind which is based on atomicity. As platinum in PtX_2 is bivalent, has two affinities, and ammonia, NH_3 , is also bivalent, because nitrogen is quinquivalent and is here only combined with H_3 , it is evident what bonds should be represented in $PtX_2 \cdot 2NH_3$ and in $PtX_2 \cdot 4NH_3$. In the former $Pt(NH_2Cl)_2$ the nitrogen of each atom of ammonia is united by three affinities with H_3 , by one with platinum, and by the fifth with chlorine. The other compound is $Pt(NH_2 \cdot NH_2Cl)_2$ —that is, the N is united by one affinity with the other N , whilst the remaining bonds are the same as in the first salt. It is evident that this union or chain of ammonias has no obvious limit, and the most essential fault of such a mode of representation is that it does not indicate at all what number of ammonias are capable of being retained by platinum. Moreover, it is hardly possible to admit the bond between nitrogen and platinum in such stable compounds, for these kinds of affinities are, at all events, feeble and cannot lead to stability, but would rather indicate explosive and easily-decomposed compounds. Moreover, it is not clear why this platinum, which is capable of giving PtX_4 , does not act with its remaining affinities when the addition of ammonia to PtX_2 takes place. These and certain other considerations which indicate the imperfection of this representation of the structure of the platino-ammonium salts, cause many chemists to incline more to the representations of Berzelius, Claus, Gibbs, and others, who suppose that NH_3 is able to combine with substances, to adjoin itself or pair itself with them (this kind of combination is called 'Paarung') without altering the fundamental capacity of a substance for further combinations. Thus, in $PtX_2 \cdot 2NH_3$, the ammonia is the associate of PtX_2 , which is expressed by the formula $N_2H_6 - PtX_2$. Without enlarging on the exposition of the details of this doctrine, we will only mention that it, like the first, does not render it possible to foresee a limit to the compounds with ammonia; it isolates compounds of this kind

If ammonia acts on a boiling solution of platinous chloride in hydrochloric acid, it produces the green salt of Magnus (1829),

into a special and artificial class; does not show the connection between compounds of this and of other kinds, and therefore it essentially only expresses the fact of the combination with ammonia and the modification in its ordinary reactions. Hence for these reasons we do not hold to either of these proposed representations of the ammonio-platinum compounds, but regard them from the point of view cited above with reference to double salts and water of crystallisation—that is, we embrace all these compounds under the representation of complex compounds higher than saline compounds. The type of the compound $\text{PtX}_2 \cdot 2\text{NH}_3$ is far more probably the same as that of $\text{PtX}_2 \cdot 2\text{Z}$ —i.e. as PtX_4 , or, still more accurately and truly, it is a compound of the same type as $\text{PtX}_2 \cdot 2\text{KX}$ or $\text{PtX}_2 \cdot 2\text{H}_2\text{O}$, &c. In PtK_2X_4 , although the platinum has entered into the type PtX_2 , yet its character has changed in the same manner as the character of sulphur changes when from SO_2 the compound $\text{SO}_2(\text{OH})_2$ is obtained, or when KClO_4 is obtained from KCl . For us as yet there is no question as to *what* affinities hold X_2 and what hold 2NH_3 , because this is a question which arises from the supposition of the existence of different affinities in the atoms, which there is no reason for taking as a common phenomenon. It seems to us that it is most important as a *commencement* to render clear the analogy in the formation of various complex compounds, and it is this analogy of the ammonia compounds with those of water of crystallisation and double salts that forms the main object of the primary generalisation. We recognise in platinum, at all events, not only the four affinities expressed in the compound PtCl_4 , but a much larger number of them, if only the *summation of affinities* is actually possible. Thus, in sulphur we recognise not two but a much greater number of affinities; it is clear that at least six affinities can act. So also among the analogues of platinum: osmic anhydride, OsO_4 , indicates the existence of at least eight affinities; whilst, in chlorine, judging from the compound $\text{KClO}_4 = \text{ClO}_3(\text{OK}) = \text{ClX}_7$, we must recognise at least seven affinities, instead of the one which is accepted. The latter mode of calculating affinities is a tribute to that period of the development of science when only the simplest hydrogen compounds were considered, and when all complex compounds were entirely neglected (they were placed under the class of molecular compounds). This is insufficient for the present store of data, because we find that, in complex compounds as in the most simple, the same constant types or cases of equilibrium are repeated, and the character of certain elements is deeply modified in the passage from the most simple into very complex compounds.





Judging from the most complex platino-ammonium compounds $\text{PtCl}_4 \cdot 4\text{NH}_3$, one should admit the possibility of the formation of compounds of the type $\text{PtX}_2 \cdot \text{Y}_4$, where $\text{Y}_4 = 4\text{X}_2 = 4\text{NH}_3$, and this shows that those forces which form such a characteristic series of double platinocyanides $\text{PtM}_2(\text{CN})_4 \cdot 3\text{H}_2\text{O}$, probably also determine the formation of the higher ammonia derivatives, as is seen on comparing—



Moreover, it is obviously much more natural to ascribe the faculty for combination with $n\text{Y}$ to the whole of the acting elements—that is, to PtX_2 or PtX_4 , and not to platinum alone. Naturally such compounds are not produced with any Y . With certain X 's there only combine certain Y 's. The best known and most frequently-formed compounds of this kind are those with water—that is, compounds with water of crystallisation. Besides these, we know of compounds with salts; these are double salts; also we know that similar compounds are also frequently formed by means of ammonia. Salts of zinc, ZnX_2 , copper, CuX_2 , silver, AgX , and many others give like compounds, but these and many other *ammonio-metallic* saline compounds are unstable, and readily part with their combined ammonia, and it is only in the elements of the platinum group, and in the group of the analogues of iron, that we observe the faculty to form stable ammonio-metallic compounds. One cannot but turn attention to

$\text{PtCl}_2 \cdot 2\text{NH}_3$, insoluble in water and hydrochloric acid. But, judging by its reactions, this salt is twice as complex. Thus, Gros (1837), on boiling Magnus's salt with nitric acid, observed that half the chlorine was replaced by the residue of nitric acid and half the platinum was disengaged: $2\text{PtCl}_2(\text{NH}_3)_2 + 2\text{HNO}_3 = \text{PtCl}_2(\text{NO}_3)_2(\text{NH}_3)_4 + 2\text{PtCl}_2$. The Gros's salt thus obtained is soluble in water, and the elements of nitric acid, but not the chlorine, contained in it are capable of easily submitting themselves to double saline decomposition. Thus silver nitrate does not enter into double decomposition with the chlorine of Gros's salt. Most instructive was the circumstance that Gros, by acting on his salt with hydrochloric acid, succeeded in substituting the residue of nitric acid in it by chlorine, and thus introduced chlorine, which easily reacted with silver nitrate. Thus it appeared that Gros's salt contained two varieties of chlorine—one which reacts readily, and the other which reacts with difficulty. The composition of Gros's first salt is $\text{PtCl}_2(\text{NH}_3)_4(\text{NO}_3)_2$; it may be converted into $\text{PtCl}_2(\text{NH}_3)_4(\text{SO}_4)$, and in general into $\text{PtCl}_2(\text{NH}_3)_4\text{X}_2$.¹³

the fact that the metals of the platinum and iron groups are able to form several high grades of oxidation which have an acid character, and consequently in the lower degrees of combination there yet remain affinities capable of retaining other elements, and they probably retain ammonia, and hold it the more stably, because all the properties of the platinum compounds are rather acid than basic—that is, PtX_n recalls rather HX or SnX_n or CX_n than KX , CaX_2 , BaX_2 , &c., and ammonia naturally will rather combine with an acid than with a basic substance. Further, a dependence, or certain connection of the forms of oxidation with the ammonia compounds, is seen on comparing the following compounds:



We know that platinum and palladium give compounds of lower types than iridium and rhodium, whilst ruthenium and osmium give the highest forms of oxidation; this shows itself in this case also. We have purposely cited the same compounds with 4NH_3 for osmium and ruthenium as we have for platinum and palladium, and it is then seen that Ru and Os are capable of retaining $2\text{H}_2\text{O}$ and $3\text{H}_2\text{O}$, besides Cl_2 and NH_3 , which the compounds of platinum and palladium are unable to do.

All the platinum metals give very stable *metallo-ammonium compounds*, undecomposable by water, dilute acids, and alkalis, like the compounds of platinum, which we describe in fuller detail, such as the salts of Reiset's second base, $\text{PtX}_2 \cdot 2\text{NH}_3$, the salts of Reiset's first base, $\text{PtX}_2 \cdot 4\text{NH}_3$, Gerhardt's salts, $\text{PtX}_4 \cdot 2\text{NH}_3$, and Gros's salts, $\text{PtX}_4 \cdot 4\text{NH}_3$.

Similar salts have been already obtained for palladium and iridium (Skoblikoff), and the two first kinds for osmium and ruthenium also. Iridium and rhodium, which easily give compounds of the type RX_5 , give compounds (Claus) of the type $\text{IrX}_5 \cdot 5\text{NH}_3$, of a rose colour, and $\text{RhX}_5 \cdot 5\text{NH}_3$, of a yellow colour. Jörgensen, in his researches on these compounds, showed their entire analogy with the cobalt compounds, as was to be expected from the periodic system.

¹³ Subsequently, a whole series of such compounds was obtained with various elements in the place of the (non-reacting) chlorine, and nevertheless they, like the

The salt of Magnus when boiled with a solution of ammonia gives the salt (of Reiset's first base) $\text{PtCl}_2(\text{NH}_3)_4$, and this, when treated with bromine, forms the salt $\text{PtCl}_2\text{Br}_2(\text{NH}_3)_4$, which is composed and reacts like Gros's salt. To Reiset's salts there corresponds a soluble, colourless, crystalline *hydroxide*, $\text{Pt}(\text{OH})_2(\text{NH}_3)_4$. It is a powerful and perfectly energetic *alkali*; it attracts carbonic anhydride from the atmosphere, precipitates metallic salts like potash, saturates active acids, even sulphuric, forming colourless (with nitric, carbonic, and hydrochloric acids), or yellow (with sulphuric acid), salts of the type $\text{PtX}_2(\text{NH}_3)_4$.¹⁴

chlorine, reacted with difficulty, whilst the second portion of the X's introduced into such salts easily underwent reaction. This formed the most important reason for the interest which the study of the composition and structure of the platino-ammonium salts subsequently presented to many chemists, such as Reiset, Blomstrand, Peyrone, Radeffski, Gerhardt, Buckton, Cleve, Thomsen, and others. The salts $\text{PtX}_4 \cdot 2\text{NH}_3$, discovered by Gerhardt, also exhibited several different properties in the two pairs of X's. In the remaining platino-ammonium salts all the X's appear to react alike.

The quality of the X's, retainable in the platino-ammonium salts, may be considerably modified, and they may frequently be wholly or partially replaced by hydroxyl. For example, the action of ammonia on the nitrate of Gerhardt's base, $\text{Pt}(\text{NO}_3)_4 \cdot 2\text{NH}_3$, in a boiling solution gradually produces a yellow crystalline precipitate, which is nothing else than a hydroxide, $\text{Pt}(\text{OH})_4 \cdot 2\text{NH}_3$. It is sparingly soluble in water, but immediately gives soluble salts $\text{PtX}_4 \cdot 2\text{NH}_3$ with acids. The stability of this hydroxide is such that potash does not expel ammonia from it, even on boiling, and it does not change below 180° . Similar properties are shown by the hydroxide $\text{Pt}(\text{OH})_2 \cdot 2\text{NH}_3$ and the oxide $\text{PtO}_2 \cdot 2\text{NH}_3$ of Reiset's second base. But the hydroxides of the compounds containing 4NH_3 are particularly remarkable. The presence of ammonia renders them soluble and energetic.

¹⁴ Hydroxides are known corresponding with Gros's salts, which contain one hydroxyl group in the place of that chlorine or haloid which in Gros's salts reacts with difficulty, and these hydroxides do not show the direct properties of alkalis, just as the chlorine which stands in the same place does not react distinctly; but still, after the prolonged action of acids, this hydroxyl group is also replaced by acids. So, for example, the action of nitric acid on $\text{Pt}(\text{NO}_3)_2\text{Cl}_2 \cdot 4\text{NH}_3$ causes the non-active chlorine to react, but in the result all the chlorine is not replaced by NO_3 , but only half, and the other half is replaced by the hydroxyl group: $\text{Pt}(\text{NO}_3)_2\text{Cl}_2 \cdot 4\text{NH}_3 + \text{HNO}_3 + \text{H}_2\text{O} = \text{Pt}(\text{NO}_3)_3(\text{OH}) \cdot 4\text{NH}_3 + 2\text{HCl}$; and this is particularly characteristic, because here the hydroxyl group has not reacted with the acid—an evident sign of the non-alkaline character of the residue in this case.

To the common properties of the platino-ammonium salts, we must add not only their *stability* (feeble acids and alkalis do not decompose them, the ammonia is not evolved by heating, &c.), but also the fact that the ordinary reactions of platinum are concealed in them to as great an extent as those of iron in the ferricyanides. Thus neither alkalis nor hydrogen sulphide will separate the platinum from them. For example, sulphuretted hydrogen in acting on Gros's salts gives sulphur, removes half the chlorine by means of its hydrogen, and forms salts of Reiset's first base. This may be understood or explained to oneself by counting the platinum in the molecule as covered, walled up by the ammonia, and situated in the centre of the molecule, and therefore inaccessible to reagents. But then one would expect to find clearly-expressed ammoniacal properties, and this is not the case. Thus ammonia is easily decomposed by chlorine, whilst in acting on the platino-ammonium salts, containing PtX_2 and 2NH_3 or 4NH_3 , chlorine combines and does not destroy the ammonia; it converts Reiset's salts into those of Gros and Gerhardt. Thus from $\text{PtX}_2 \cdot 2\text{NH}_3$ there proceeds $\text{PtX}_2\text{Cl}_2 \cdot 2\text{NH}_3$, and from $\text{PtX}_2 \cdot 4\text{NH}_3$ there proceeds salt of Gros's base $\text{PtX}_2\text{Cl}_2 \cdot 4\text{NH}_3$. This shows that the amount of chlorine which com-

The stability of such compounds, and the existence of many other compounds analogous to them, endows them with a particular chemical

bines is not dependent on the amount of ammonia present, but only conforms itself with the basic property of platinum. Owing to this some chemists suppose the ammonia to be inactive or passive in certain compounds. It appears to me that these relations, these modifications, in the usual properties of ammonia and platinum are explained directly by their mutual combination. Sulphur, in sulphurous anhydride, SO_2 , and hydrogen sulphide, SH_2 , is naturally one and the same, but if we only knew of it in the form of hydrogen sulphide, then, having obtained it in the form of sulphurous anhydride, we should consider its properties as hidden. The oxygen in magnesia, MgO , and in nitric peroxide, NO_2 , is so different that there is no resemblance. Arsenic no longer reacts in its compounds with hydrogen as it reacts in its compounds with chlorine, and in their compounds with nitrogen all metals modify both their reactions and their physical properties. We are accustomed to judge the metals by their saline compounds with haloid groups, and ammonia by its compounds with acid substances, and here, in the platino-compounds, if we assume the platinum to be bound to the entire mass of the ammonia—to its hydrogen and nitrogen—we shall understand that both the platinum and ammonia modify their characters. Far more complicated is the question why a portion of the chlorine (and other haloid simple and complex groups) in Gros's salts acts in a different manner from the other portion, and why only half of it acts in the usual way. But this also is not an exclusive case. The chlorine in potassium chlorate or in carbon chloride does not react with the same ease with metals as the chlorine in the salts corresponding with hydrochloric acid. There it is united to oxygen and carbon, here it is united partly to platinum and partly to the platino-ammonium group. Many chemists, moreover, suppose that a part of the chlorine is united directly to the platinum and the other part to the nitrogen of the ammonia, and thus explain the difference of the reactions; but chlorine united to platinum reacts as well with a silver salt as the chlorine of ammonium chloride, NH_4Cl , or nitrosyl chloride, NOCl , although no one denies that here there is a union between the chlorine and nitrogen. Hence it is necessary to explain the absence of a facile reactive capacity in a portion of the chlorine by the conjoint influence of the platinum and ammonia on it, whilst the other portion may be admitted as being under the influence of the platinum only, and therefore as reacting as in other salts. By admitting a certain kind of stable union in the platino-ammonium grouping it is possible to imagine that the chlorine does not react with its customary facility, because access to a portion of the atoms of chlorine in this complex grouping is difficult and the chlorine union is not the same as we usually meet in the saline compounds of chlorine. These are the bases on which we, in refuting the now accepted explanations of the reactions and formation of the platino-compounds, pronounce that opinion as to their structure which follows.

In characterising the platino-ammonium compounds, it is necessary to keep in mind that compounds which already contain PtX_4 do not combine directly with NH_3 , and that such compounds as $\text{PtX}_4 \cdot 4\text{NH}_3$ only proceed from PtX_2 , and therefore it is natural to conclude that those affinities and forces which cause PtX_2 to combine with X_2 also cause it to combine with 2NH_3 . And having the compound $\text{PtX}_2 \cdot 2\text{NH}_3$, and supposing that in subsequently combining with Cl_2 it reacts with those affinities which produce the compounds of platinic chloride, PtCl_4 , with water, potassium chloride, potassium cyanide, hydrochloric acid, and the like, we explain not only the fact of combination, but also many of the reactions occurring in the transition of one kind of platino-ammonium salts into another. Thus by this means we explain the fact that (1) $\text{PtX}_2 \cdot 2\text{NH}_3$ combines with 2NH_3 , forming salts of Reiset's first base; (2) and the fact that this compound (represented as follows for distinctness), $\text{PtX}_2 \cdot 2\text{NH}_3 \cdot 2\text{NH}_3$, when heated, or even when boiled in solution, again passes into $\text{PtX}_2 \cdot 2\text{NH}_3$ (which resembles the easy disengagement of water of crystallisation, &c.); (3) the fact that $\text{PtX}_2 \cdot 2\text{NH}_3$ is capable of absorbing, under the action of the same forces, a molecule of chlorine, $\text{PtX}_2 \cdot 2\text{NH}_3 \cdot \text{Cl}_2$, which it

interest. Thus Kurnakoff (1889) obtained a series of corresponding compounds containing thiocarbamide, CSN_2H_4 , in the place of ammonia, $\text{PtCl}_2 \cdot 4\text{CSN}_2\text{H}_4$, and others corresponding with Reiset's salts. Hydroxylamine, and other substances corresponding with ammonia, also give similar compounds.

then retains with energy, because it is attracted, not only by the platinum, but also by the hydrogen of the ammonia; (4) the fact that this chlorine held in this compound (of Gerhardt) will have a position unusual in salts, which will explain a certain (although very feebly-developed) difficulty of reaction; (5) the fact that this does not exhaust the faculty of platinum for further combination (it is enough to remember the compound $\text{PtCl}_4 \cdot 2\text{HCl} \cdot 16\text{H}_2\text{O}$), and therefore both $\text{PtX}_2 \cdot 2\text{NH}_3 \cdot \text{Cl}_2$ and $\text{PtX}_2 \cdot 2\text{NH}_3 \cdot 2\text{NH}_3$ are still capable of combination, whence the latter, with chlorine, gives $\text{PtX}_2 \cdot 2\text{NH}_3 \cdot 2\text{NH}_3 \cdot \text{Cl}_2$, after the type of PtX_4Y_4 (and perhaps higher); (6) the fact that Gros's compounds thus formed are readily re-converted into the salts of Reiset's first base when acted on by reducing agents; (7) the fact that in Gros's salts, $\text{PtX}_2 \cdot 2\text{NH}_3 \cdot (\text{NH}_3\text{X})_2$, the newly-attached chlorine or haloid will react with difficulty with salts of silver, &c., because it is attached both to the platinum and to the ammonia, for both of which it has an attraction; (8) the fact that the faculty for further combination is not even yet exhausted in the type of Gros's salts, and that we actually have a compound of Gros's chlorine salt with platinous chloride and with platinic chloride; the salt $\text{PtSO}_4 \cdot 2\text{NH}_3 \cdot 2\text{NH}_3 \cdot \text{SO}_4$ combines further also with H_2O ; (9) the fact that such a faculty for combination with new molecules is naturally more developed in the lower forms of combination than in the higher. Therefore the salts of Reiset's first base—for example, $\text{PtCl}_2 \cdot 2\text{NH}_3 \cdot 2\text{NH}_3$ —both combine with water and give precipitates (soluble in water but not in hydrochloric acid) of double salts with many salts of the heavy metals—for example, with lead chloride, cupric chloride, and also with platinic and platinous chlorides (Buckton's salts). The latter compounds will have the composition $\text{PtCl}_2 \cdot 2\text{NH}_3 \cdot 2\text{NH}_3 \cdot \text{PtCl}_2$ —that is, the same composition as the salts of Reiset's second base, but it cannot be identical with it. Such an interesting case does actually exist. The first salt, $\text{PtCl}_2 \cdot 4\text{NH}_3 \cdot \text{PtCl}_2$, is green, insoluble in water and in hydrochloric acid, and is known as *Magnus's salt*, and the second, $\text{PtCl}_2 \cdot 2\text{NH}_3$, is Reiset's yellow, sparingly soluble (in water). They are polymeric, namely, the first contains twice the number of elements held in the second, and at the same time they easily pass into each other. If ammonia be added to a hot hydrochloric acid solution of platinous chloride, it forms the salt $\text{PtCl}_2 \cdot 4\text{NH}_3$, but in the presence of an excess of platinous chloride it gives Magnus's salt. On boiling the latter in ammonia it gives a colourless soluble salt of Reiset's first base, $\text{PtCl}_2 \cdot 4\text{NH}_3$, and if this is boiled with water, then ammonia is disengaged, and a salt of Reiset's second base, $\text{PtCl}_2 \cdot 2\text{NH}_3$, is obtained.

A class of platino-ammonium isomerides (obtained by Millon and Thomsen) are also known. Buckton's salts—for example, the copper salt—were obtained by them from the salts of Reiset's first base, $\text{PtCl}_2 \cdot 4\text{NH}_3$, by treatment with a solution of cupric chloride, &c., and therefore, according to our method of expression, Buckton's copper salt will be $\text{PtCl}_2 \cdot 4\text{NH}_3 \cdot \text{CuCl}_2$. This salt is soluble in water, but not in hydrochloric acid. In it the ammonia must be considered as united to the platinum. But if cupric chloride be dissolved in ammonia, and a solution of platinous chloride in ammonium chloride is added to it, then a violet precipitate is obtained of the same composition as Buckton's salt, but which is insoluble in water but soluble in hydrochloric acid. In this a portion, if not all, of the ammonia must be regarded as united to the copper, and it must therefore be represented as $\text{CuCl}_2 \cdot 4\text{NH}_3 \cdot \text{PtCl}_2$. This form is identical in composition but different in properties (is isomeric) with the preceding salt (Buckton's). The salt of Magnus is intermediate between them, $\text{PtCl}_2 \cdot 4\text{NH}_3 \cdot \text{PtCl}_2$; it is insoluble in water and hydrochloric acid. These and certain other instances of isomeric compounds in the series of the platino-ammonium salts throw a light on the nature of the compounds in question, just as the study of the isomerides of the carbon compounds has served and still serves as the chief cause of the rapid progress of organic chemistry.

CHAPTER XXIV

COPPER, SILVER, AND GOLD

THAT degree of analogy and difference which exists between iron, cobalt, and nickel repeats itself in the corresponding triad ruthenium, rhodium, and palladium, and also in the heavy platinum metals, osmium, iridium, and platinum. These nine metals form the VIII. group of the elements in the periodic system, being the intermediate group between the even elements of the large periods and the uneven, among which we know zinc, cadmium, and mercury in the II. group. Copper, silver, and gold complete¹ this transition, because their properties place them in proximity to nickel, palladium, and platinum on the one hand, and to zinc, cadmium, and mercury on the other. Thus, for example, the atomic weight of copper $\text{Cu}=63$, and in all its properties it stands between $\text{Ni}=59$ and $\text{Zn}=65$. But as the transition from the VIII. group to the II. group, where zinc is situated, cannot be otherwise than through the I. group, so in copper there are certain properties of the elements of the I. group. Thus it gives a sub-oxide, Cu_2O , and salts, CuX , like the elements of the I. group, although at the same time it forms an oxide, CuO , and salts, CuX_2 , like nickel and zinc.

In the state of the oxide, CuO , and the salts, CuX_2 , copper is analogous to zinc, judging from the solubility, isomorphism, and other characters. So, for instance, cupric sulphate forms isomorphous mixtures with the sulphates of the magnesium group, in which the amount of water of crystallisation varies readily according to the temperature,²

¹ The perfectly unique position held by copper, silver, and gold in the periodic system of the elements, and the degree of affinity which is found between them, is all the more remarkable, as nature and practice have long isolated these metals from all others by having employed them—for example, for metallic money—and determined their relative importance and value in conformity with the order (silver between copper and gold) of their atomic weights, &c.

² Cupric sulphate contains 5 molecules of water, $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$, and the isomorphous mixtures with $\text{ZnSO}_4 \cdot 7\text{H}_2\text{O}$ contain either 5 or 7 equivalents, according to whether copper or zinc predominates. If there be a large proportion of copper, and if the mixture contains $5\text{H}_2\text{O}$, then the form of the isomorphous mixture (triclinic) will be isomorphous

and the relative quantities of the metals varies in divers proportions, as is the case in all other isomorphous mixtures of similar metals. The facility of the transition from the cupric salts corresponding with the oxide CuO into the cuprous salts corresponding with the suboxide Cu_2O , and the relative proportion of the metal in both compounds, gives an easy means of accurately determining the relative composition of both of these oxides of copper. Ascribing the formula RO to the oxides of the magnesium group, that of the suboxide of copper, judging by the amount of oxygen it contains, should be R_2O , corresponding with the oxides of the alkali metals. In the cuprous salts there is undoubtedly a great resemblance to the silver salts—thus, for example, silver chloride, AgCl , is characterised by its insolubility and capacity to combine with ammonia. Cuprous chloride closely resembles it, for it is also insoluble in water, and combines with ammonia and dissolves in it, &c. Its type is also RCl , the same as AgCl , NaCl , KCl , &c., and silver in many compounds resembles, and is even isomorphous with, sodium, so that this again justifies their being brought together. Silver chloride, cuprous chloride, and sodium chloride crystallise in the regular system. Besides which, the specific heats of copper and silver require that they should have the atomic weights ascribed to them. To the oxides Cu_2O and Ag_2O there are corresponding sulphides Ag_2S and Cu_2S . They both occur in nature in crystals of the rhombic system, and, what is most important, copper glance contains an isomorphous mixture of them both, and retains the form of copper glance with various proportions of copper and silver, and therefore has the composition R_2S where $\text{R} = \text{Cu, Ag}$.

Notwithstanding the resemblance in the atomic composition of the cuprous compounds, CuX , and silver compounds, AgX , with the compounds of the alkali metals KX , NaX , there is a considerable degree of difference between these two series of elements. This difference is clearly seen in the fact that the alkali metals belong to those elements which combine with extreme facility with oxygen, decompose water, and form the most alkaline bases; whilst silver and copper are oxidised with difficulty, form less energetic oxides, and do not decompose water, even at a rather high temperature; they even displace hydrogen from very few acids. The difference between them is also seen in the dissimilarity of the properties of many of the

with cupric sulphate, $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$, but if there be a large amount of zinc (or magnesium, iron, nickel, or cobalt) then the form (rhombic or monoclinic) is nearly the same as that of zinc sulphate, $\text{ZnSO}_4 \cdot 7\text{H}_2\text{O}$. Supersaturated solutions of each of these salts crystallise in that form and with that amount of water which is contained in a crystal of one or other of the salts brought in contact with the solution (Vol. I. p. 591, Note 27).

corresponding compounds. Thus cuprous oxide, Cu_2O , and silver oxide, Ag_2O , are insoluble in water; the cuprous and silver carbonates, chlorides, and sulphates are also sparingly soluble in water. The oxides of silver and copper are also easily reduced to metal. This difference in properties is in intimate relation with that difference in the density of the metals which exists in this case. The alkali metals belong to the lightest, and copper and silver to the heaviest, and therefore the distance between the molecules in these metals is very dissimilar—it is greater for the former than the latter (table in Chap. XV.). From the point of view of the periodic law, this difference between copper and silver and such elements of the I. group as potassium and rubidium, is clearly seen from the fact that copper and silver stand in the middle of those large periods (for example, K, Ca, Sc, Ti, V, Cr, Mn, Fe, Co, Ni, Cu, Zn, Ga, Ge, As, Se, Br) which start with the true metals of the alkalis—that is to say, the analogy and difference between potassium and copper is of the same nature as that between chromium and selenium, or vanadium and arsenic.

Copper is one of the few metals which have long been known in a metallic form. The Greeks and Romans chiefly imported copper from the island of Cyprus—whence its Latin name, *cuprum*. It was known to the ancients before iron, and was used, especially when alloyed with other metals, for arms and domestic utensils. This will be understood from the fact that copper occurs, although rarely, in a *native state*, and is easily extracted from its other natural compounds. Among the latter are the oxygen compounds of copper. When ignited with charcoal, they easily give up their oxygen to it, and yield metallic copper; hydrogen also easily takes up the oxygen from copper oxide when heated. Copper occurs in a native state, sometimes in association with other ores, in many parts of the Urals and in Sweden, and in considerable masses in America, especially round about the great American lakes; and also in Chili, Japan, and China. The oxygen compounds of copper are also of somewhat common occurrence in certain localities; in this respect certain deposits of the Urals are especially famous. The geological period of the Urals (Permian) is characterised for a considerable distribution of copper ores. Copper is met with in the form of *cuprous oxide*, or *suboxide of copper*, Cu_2O , and is then known as *red copper ore*, because it forms red masses which not unfrequently are crystallised in the regular system. It is found much more rarely in the state of *cupric oxide*, CuO , and is then called *black copper ore*. The most common of the oxygenised compounds of copper are the *basic carbonates*, corresponding with the oxides. These compounds are indubitably of aqueous origin, as is seen not only from the fact that

specimens are frequently found of a gradual transition from the metallic, sulphuretted, and oxidised copper into its various carbonates, but also from the presence of water in their composition, and from the laminar, reniform structure which many of them present. In this respect *malachite* is particularly well known; it is used for ornaments, owing to the diversity of the shades of colour presented by the different layers of deposited malachite, and also as a green paint. The composition of malachite corresponds with the basic carbonate containing one molecule of cupric carbonate to one of hydroxide: $\text{CuCO}_3, \text{CuH}_2\text{O}_2$. In this form the copper frequently appears in admixture with various sedimentary rocks, forming large strata, which confirms the aqueous origin of these compounds. There are many such localities in the Perm and other governments bounding the Urals. *Blue carbonate of copper*, or *azurite*, is also often met with in the same localities; it contains the same ingredients as malachite, but in a different proportion, its composition being $\text{CuH}_2\text{O}_2, 2\text{CuCO}_3$. Both these substances may be obtained artificially by the action of the alkali carbonates on solutions of cupric salts at various temperatures. These native carbonates are often used for the extraction of copper, all the more as they very readily give metallic copper, evolving water and carbonic anhydride when ignited, and leaving the easily-reducible cupric oxide. Copper is, however, still more often met with in the form of the sulphides. The sulphides of copper generally occur in chemical combination with the sulphides of iron.³

³ The immense quantities of iron pyrites, FeS_2 , which are sometimes met with in nature, very often contain a small quantity of copper sulphide, and on burning the iron pyrites for sulphurous anhydride the copper oxide remains in the residue, from which the copper is often extracted by getting it into solution and then precipitating it by the action of metallic iron. For this purpose the whole of the sulphur is not burnt off from the iron pyrites, but a portion is left behind in the ore, which is then slowly ignited (roasted) with access of air. Cupric sulphate is then formed, and is extracted by water; or, what is better and more frequently done, the residue from the roasting of the pyrites is roasted with common salt, and the solution of cupric chloride obtained by lixiviating is precipitated with iron. A far greater amount of copper is obtained from other sulphuretted ores. Among these *copper glance*, Cu_2S , is more rarely met with. It has a metallic lustre, is grey, generally crystalline, and is obtained in admixture with organic matter; so that there is no doubt that its origin is due to the reducing action of the latter on solutions of cupric sulphate. *Variegated copper ore*, which crystallises in octahedra, not unfrequently forms an admixture in copper glance; it has a metallic lustre, and is reddish-brown; it has a superficial play of colours, due to oxidation proceeding on its surface. Its composition is Cu_3FeS_5 . But the most common and widely-distributed copper ore is *copper pyrites*, which crystallises in regular octahedra and is often non-crystalline; it has a metallic lustre, a sp. gr. of 4.0, and yellow colour. Its composition is CuFeS_2 . It must be remarked that the sulphurous ores of copper are oxidised in the presence of water containing oxygen in solution, and form cupric sulphate, blue vitriol, which is easily soluble in water. If this water contains calcium carbonate, then gypsum and cupric carbonate is formed by double decomposition: $\text{CuSO}_4 + \text{CaCO}_3 = \text{CuCO}_3 + \text{CaSO}_4$

The extraction of copper from the acid ores does not present any difficulty, because the copper, when ignited with charcoal and melted, is reduced from the impurities which accompany it. This mode of smelting copper ores is carried on in cupola or cylindrical furnaces, fluxes forming a slag being added to the mixture of ore and charcoal. The smelted copper still contains sulphur, iron, and other metallic impurities, from which it is freed by fusion in reverberatory furnaces, with access of air to the surface of the molten metal, as the iron and sulphur are more easily oxidised than the copper. The iron then separates as oxides, which collect in the slag.⁴

Therefore copper sulphide in the form of different ores must be considered as the primary product, and the many other copper ores as secondary products, formed by water. This is confirmed by the fact that at the present time the water extracted from many copper mines contains cupric sulphate in solution. From this liquid it is easy to extract cupric oxide by the action of lime, or metallic copper by means of iron; the latter is also formed by the action of organic matter and various impurities of water. Hence metallic copper is sometimes found in natural products of the modification of copper sulphide, and is probably deposited by the action of organic matter present in the water.

⁴ Rich oxygenised ores of copper are very rare; the sulphur ores are of more common occurrence, but the extraction of the copper from them is much more difficult. The problem here not only consists in the removal of the sulphur, but also in the removal of the iron combined with the sulphur and copper. This is attained by a whole series of operations, after which there still sometimes remains the extraction of the metallic silver which generally accompanies the copper, although in but small quantity. These processes commence with the roasting—*i.e.* calcination—of the ore with access of air, by which means the sulphur is converted into sulphurous anhydride. It should be here remarked that iron sulphide is more easily oxidised than copper sulphide, and therefore the greater part of the iron in the residue from roasting is no longer in the form of sulphide but of oxide of iron. The roasted ore is mixed with charcoal, siliceous fluxes, and smelted in a cupola furnace. The iron then passes into the slag, because its oxide gives an easily-fusible mass with the silica, whilst the copper, in the form of sulphide, is fused and collects under the slag. The greater part of the iron is removed from the mass by this smelting. The resultant *coarse metal* is again roasted in order to remove the greater part of the sulphur from the copper sulphide, and to convert the metal into oxide. The resultant mass is again smelted. These processes are repeated several times, according to the richness of the ore. During these smeltings a portion of the copper is already obtained in a metallic form, because copper sulphide gives metallic copper with the oxide ($\text{CuS} + 2\text{CuO} = 3\text{Cu} + \text{SO}_2$). We will not here describe the furnaces used or the details of this process, but the above remarks include the explanation of those chemical processes which are accomplished in the various technical operations which are had recourse to in the process.

Besides the smelting of copper there also exist (and begin to be widely applied) methods for its extraction from solutions in the wet way, as it is called. Recourse is generally had to these methods for poor copper ores. The methods of extraction by the wet way consist in transferring the copper into solution, from which it is separated by means of metallic iron or by other methods (by the action of an electric current). The sulphides are roasted in such a manner that the greater part of the copper is oxidised into cupric sulphate, whilst at the same time the corresponding iron salts are as far as possible decomposed. This process is based on the fact that the copper sulphides absorb oxygen when they are calcined in the presence of air, forming cupric sulphate. The roasted ore is treated with water, to which acid is sometimes added, and after lixiviation the resultant solution containing copper is treated either with metallic iron, or with

Copper is characterised by its red colour, which distinguishes it from all other metals. Pure copper is soft, and may be beaten out by a hammer at the ordinary temperature, and when hot may be rolled into very thin sheets. Extremely thin leaves of copper transmit a green light. The tenacity of copper is also rather great, and after iron it is one of the most durable metals in this respect. Copper wire of 1 millimetre radius only breaks under a weight of 137 kilograms. The specific gravity of copper is 8.8, unless it contains cavities due to the fact that molten copper absorbs oxygen from the air, which is disengaged on cooling, and therefore gives a porous mass whose density is much less. Rolled copper, and also that which is deposited by the electric current, has a comparatively high density. Copper melts at a temperature nearly approaching to a white heat, although below the temperature at which many kinds of cast iron melt. At a high temperature it is converted into vapour, which communicates a green colour to the flame. Both native copper and that cooled from a molten state crystallise in regular octahedra. Copper is not oxidised in dry air at the ordinary temperature, but when calcined it becomes coated with a layer of oxide, and it does not burn even at the highest temperature. Copper, when calcined in air, forms either the red cuprous oxide or the black cupric oxide, according to the temperature and quantity of air supplied. In air at the ordinary temperature, copper—as every one

milk of lime, which precipitates cupric hydroxide from the solution. Poor oxidised ores of copper may be treated with dilute acids in order to obtain the copper oxides in solution, from which the copper is then easily precipitated either by iron or as hydroxide by lime. According to Hunt and Douglas's method, the copper in the ore is converted by calcination into the cupric oxide, which is brought into solution by the action of a mixture of solutions of ferrous sulphate and sodium chloride, because the oxide converts the ferrous chloride into ferric oxide, forming copper chlorides, according to the equation $3\text{CuO} + 2\text{FeCl}_2 = \text{CuCl}_2 + 2\text{CuCl} + \text{Fe}_2\text{O}_3$. The cupric chloride is soluble in water, and the cuprous chloride is dissolved in the solution of sodium chloride, and therefore all the copper passes into solution, from which it is precipitated by iron.

The copper brought into the market often contains small quantities of various impurities. Among these there are generally present iron, lead, silver, arsenic, and sometimes small quantities of oxides of copper. As copper, when mixed with a small amount of foreign substances, loses its tenacity to a certain degree, the manufacture of very thin sheet copper requires the use of Chili copper, which is distinguished for its great softness, and therefore, when it is desired to have pure copper, it is best to take thin sheet copper, like that which is used in the manufacture of cartridges. But the purest copper is electrolytic copper—that is, that which is deposited from a solution by the action of an electric current.

If the copper contains silver, as is often the case, it is used at gold refineries for the precipitation of silver from its solutions in sulphuric acid. Iron and zinc reduce copper, but copper reduces mercury and silver. The precipitate contains not only the silver which was previously in solution, but also all that which was in the copper. The silver solutions in sulphuric acid are obtained in the separation of silver from gold by treating their alloys with sulphuric acid, which only dissolves the silver.

knows—becomes coated with a brown layer of oxides or a green coating of basic salts, due to the action of the damp air containing carbonic acid. If this action continue for a prolonged time, the copper is covered with a thick coating of basic carbonate, or the so-called verdigris (the *aerugo nobilis* of ancient statues). This is due to the fact that copper, although scarcely capable of oxidising by itself,⁵ in the presence of water and acids—even very feeble acids, like the carbonic acid—absorbs oxygen from the air and forms salts, which is a very characteristic property of it (and of lead). Copper does not decompose water, and does not disengage hydrogen from it either at the ordinary or at high temperatures. So also copper does not liberate hydrogen from the oxygen acids, which act on it in two ways: they either give up a portion of their oxygen, forming lower grades of oxidation, or else only react in the presence of air. Thus, when nitric acid acts on copper it evolves nitric oxide, the copper being oxidised at the expense of the nitric acid. So also copper converts sulphuric acid into the lower grade of oxidation—into sulphurous anhydride, SO_2 . In these cases, the copper is oxidised into copper oxide, which combines with the excess of acid taken, and therefore forms a cupric salt, CuX_2 . Dilute nitric acid does not act on copper, even at the ordinary temperature, but when heated it reacts with great ease; but dilute sulphuric acid does not act on copper unless it have access to air.⁶

⁵ Schützenberger showed that when the basic carbonate of copper is decomposed by an electric current it gives, besides the ordinary copper, an allotropic form which grows on the negative platinum electrode, if its surface be less than the positive copper electrode, in the form of brittle crystalline growths of sp. gr. 8.1. It differs from ordinary copper by its giving not nitric oxide but nitrous oxide when treated with nitric acid, and in being very easily oxidised in air, and covered with red shades of colour. Is not this hydrogenised copper, or copper which has occluded hydrogen?

⁶ In the presence of air, even such feeble acids as carbonic acid produce an action on copper; the copper then readily absorbs oxygen and gives cupric oxide, which enters into combination with the acid and forms a copper salt. This is taken advantage of in practice; for instance, by pouring dilute acids over copper turnings on revolving tables in the preparation of copper salts, such as verdigris, or the basic acetate $2\text{C}_4\text{H}_6\text{CuO}_4 \cdot \text{CuH}_2\text{O}_2 \cdot 5\text{H}_2\text{O}$, which is so much used as an oil paint (*i.e.* with boiled oil). The capacity of copper for absorbing oxygen in the presence of acids is so great that it is possible by this means (by taking, for example, thin copper shavings moistened with sulphuric acid) to take up all the oxygen from a given volume of air, and this is even employed for the analysis of air.

The combination of copper with oxygen is not only aided by acids but also by alkalis, although cupric oxide does not appear to have an acid character. Alkalis do not act on copper except in the presence of air, when they produce cupric oxide, which does not appear to combine with such alkalis as caustic potash or soda. But the action of ammonia is particularly distinct (Vol. I. p. 223, Note 2). In the action of a solution of ammonia not only is oxygen absorbed by the copper, but it also acts on the ammonia, and a definite quantity of ammonia is always acted on simultaneously with the passage of the copper into solution. The ammonia is then converted into nitrous acid, according to the re-

Both the oxides of copper, Cu_2O and CuO , are unacted on by air, and, as has been already mentioned, they both occur in nature. However, in the majority of cases copper is obtained in the form of cupric oxide and its salts—for example, the copper compounds used in practice generally belong to this type. This is due to the fact that the *cuprous compounds absorb oxygen* from the air and pass into cupric compounds. The cupric compounds may serve as the source for the preparation of cuprous oxide, because many reducing agents are capable of deoxidising the oxide into the suboxide. Organic substances are most generally employed for this purpose, and especially saccharine substances, which are able, in the presence of alkalis, to undergo oxidation at the expense of the oxygen of the cupric oxide, and to give acids which combine with the alkali: $2\text{CuO} - \text{O} = \text{Cu}_2\text{O}$. In this case, the deoxidation of the copper may be carried further and metallic copper be obtained, if only the reaction be aided by heat. Thus, for example, a fine powder of metallic copper may be obtained by heating an ammoniacal solution of cupric oxide with caustic potash and grape sugar. But if the reducing action of the saccharine substance proceed in the presence of a sufficient quantity of alkali, and at not too high a temperature and in solution, then cuprous oxide is obtained. To see this reaction clearly, it is not sufficient to take any cupric salt, because the alkali neces-

action: $\text{NH}_3 + \text{O}_3 = \text{NHO}_2 + \text{H}_2\text{O}$, and the nitrous acid thus formed passes into the state of ammonium nitrite, NH_4NO_2 . In this manner three equivalents of oxygen are expended on the oxidation of the ammonia, and six equivalents of oxygen pass over to the copper, forming six atoms of cupric oxide. The latter does not remain in the state of oxide, but combines with the ammonia.

A strong solution of common salt does not act on copper, but a dilute solution of the salt corrodes copper, converting it into oxychloride—that is, in the presence of air. This action of salt water is evident in those cases where the bottom of ships are coated with sheet copper. From what has been said above it will be evident that copper vessels should not be employed in the preparation of food, because this contains salts and acids which act on copper in the presence of air, and give copper salts, which are poisonous, and therefore the food prepared in untinned copper vessels may be poisonous. Hence tinned vessels are employed for this purpose—that is, copper vessels coated with a thin layer of tin, on which acid and saline solutions do not act.

Copper, besides the cuprous oxide, Cu_2O , and cupric oxide, CuO , gives two known peroxide forms of oxidation, but they have barely been investigated, and even their composition is not well known. *Copper dioxide* (CuO_2 , or $\text{CuO}_2 \cdot \text{H}_2\text{O}$, perhaps CuHO_2) is obtained by the action of hydrogen peroxide on cupric hydroxide, when the green colour of the latter is changed into yellow. It is very unstable, and is even decomposed by boiling water, with the evolution of oxygen, whilst the action of acids gives cupric salts, oxygen being also disengaged. A still higher *copper peroxide* is formed by heating a mixture of caustic potash, nitre, and metallic copper to a red heat, and by dissolving cupric hydroxide in solutions of the hypochlorites of the alkali metals. A slight heating of the soluble salt formed is enough for it to be decomposed into oxygen and copper dioxide, which is precipitated. Judging from Frémy's researches, the composition of the copper-potassic compound should be K_2CuO_4 . Perhaps this is a compound of peroxides of potassium, K_2O_2 , and of copper, CuO_2 (see Chapter XX. Notes 62-64).

sary for the reaction might precipitate cupric oxide—it is necessary to previously add some substance which will prevent this precipitation. Among such substances, tartaric acid, $C_4H_6O_6$, is one of the best. In the presence of a sufficient quantity of tartaric acid, any amount of alkali may be added to a solution of cupric salt without producing a precipitate, because a soluble double salt of cupric oxide and alkali is then formed. If glucose be added to such an alkaline tartaric solution, and the temperature be slightly raised, it first gives a yellow precipitate (this is cuprous hydroxide, $CuHO$), and then, on boiling, a red precipitate of (anhydrous) cuprous oxide. If such a mixture be left for a long time at the ordinary temperature, it deposits well-formed crystals of anhydrous cuprous oxide belonging to the regular system.⁷

⁷ Colourless solutions of cuprous salts may also be obtained by the action of sulphurous or phosphorous acid and like lower grades of oxidation on the blue solutions of the cupric salts. This is very clearly and easily accomplished by means of sodium thio-sulphate, $Na_2S_2O_5$, which is oxidised by the process. Cuprous oxide can not only be obtained by the deoxidation of cupric oxide, but also directly from metallic copper itself, because the latter, in oxidising at a red heat in air, first gives cuprous oxide. It is prepared in this manner on a large scale by heating sheet copper rolled into spirals in reverberatory furnaces. It must be seen that the air is not in great excess, and that the coating of red cuprous oxide formed does not begin to pass into the black cupric oxide. If the oxidised spiral sheet is then unbent, the brittle cuprous oxide falls away from the soft metal. The suboxide obtained in this manner fuses with ease. It is necessary to prevent the access of air during the fusion, and if the mass contains cupric oxide it must be mixed with charcoal, which reduces the latter. Cuprous chloride, $CuCl$, corresponding with cuprous oxide (as sodium chloride corresponds with sodium oxide), when calcined with sodium carbonate, gives sodium chloride and cuprous oxide, carbonic anhydride being evolved, because it does not combine with the cuprous oxide under these conditions. The reaction can be expressed by the following equation: $2CuCl + Na_2CO_3 = Cu_2O + 2NaCl + CO_2$. The cupric oxide itself, when calcined with finely-divided copper (this copper powder may be obtained by many means; for instance, by immersing zinc in a solution of a copper salt, or by igniting cupric oxide in hydrogen), gives the fusible cuprous oxide: $Cu + CuO = Cu_2O$. Both the native and artificial cuprous oxide has a sp. gr. of 5.6. It is insoluble in water, and is not acted on by (dry) air. When heated with acids the suboxide forms a solution of a cupric salt and metallic copper; for example, $Cu_2O + H_2SO_4 = Cu + CuSO_4 + H_2O$. However, strong hydrochloric acid does not separate metallic copper on dissolving cuprous oxide, which is due to the fact that the cuprous chloride formed is soluble in strong hydrochloric acid. Cuprous oxide also dissolves in a solution of ammonia, and, in the absence of air, gives a colourless solution, which turns blue in the air, absorbing oxygen, owing to the conversion of the cuprous oxide into cupric oxide. The blue solution thus formed may be again reconverted into a colourless cuprous solution by immersing a copper strip in it, because the metallic copper then deoxidises the cupric oxide in the solution into cuprous oxide. Cuprous oxide is characterised by the fact that it gives red glasses when fused with glass or with salts forming vitreous alloys. Glass tinted with cuprous oxide is used for ornaments. The access of air must be avoided during its preparation, because the colour then becomes green, owing to the formation of cupric oxide which colours glass blue. This may even be taken advantage of in testing for copper under the blow-pipe by heating the copper compound with borax in the flame of a blow-pipe; a red glass is obtained in the reducing flame,

Cupric chloride, CuCl_2 , when ignited, gives *cuprous chloride*, CuCl —i.e. the salt corresponding with suboxide of copper—and therefore cuprous chloride is always formed whenever copper enters into reaction with chlorine at a high temperature. Thus, for example, when copper is calcined with mercuric chloride, it forms cuprous chloride and vapours of mercury. The same substance is obtained on heating metallic copper in hydrochloric acid, hydrogen being disengaged; but this reaction only proceeds with finely-divided copper, as hydrochloric acid acts very feebly on compact masses of copper, and, in the presence of air, gives cupric chloride. The green solution of cupric chloride is decolourised by metallic copper, cuprous chloride being formed; but this reaction is only accomplished with ease when the solution is very concentrated and in the presence of an excess of hydrochloric acid, because the latter dissolves the cuprous chloride. The addition of water to the solution precipitates the cuprous chloride because it is less soluble in dilute than in strong hydrochloric acid. Many reducing agents which are able to take up half the oxygen from cupric oxide are able, in the presence of hydrochloric acid, to form cuprous chloride. Stannous salts, sulphurous anhydride, alkali sulphites, phosphorous and hypophosphorous acids, and many similar reducing agents, act in this manner. The usual method of preparing cuprous chloride consists in passing sulphurous anhydride into a very strong solution of cupric chloride: $2\text{CuCl}_2 + \text{SO}_2 + \text{H}_2\text{O} = 2\text{CuCl} + 2\text{HCl} + \text{H}_2\text{SO}_4$. Cuprous chloride forms colourless cubic crystals which are insoluble in water. It is easily fusible, and even volatile. Under the action of oxidising agents, it passes into the cupric salt, and it absorbs oxygen from moist air, forming cupric oxychloride, $\text{Cu}_2\text{Cl}_2\text{O}$. *Aqueous ammonia* easily *dissolves* cuprous chloride as well as cuprous oxide; the solution also turns blue on exposure to the air. Thus an ammoniacal solution of cuprous chloride serves as an excellent absorbent for oxygen; but this solution absorbs not only oxygen, but also certain other gases—for example, carbonic oxide and acetylene.⁸

and a blue glass in the oxidising flame, owing to the conversion of the cuprous into cupric oxide.

Etard (1882), by passing sulphurous anhydride into a solution of cupric acetate, obtained a white precipitate of cuprous sulphite, $\text{Cu}_2\text{SO}_3 \cdot \text{H}_2\text{O}$, whilst he obtained the same salt, of a red colour, from the double salt of sodium and copper; but there are not any convincing proofs of isomerism in this case.

⁸ The solubility of cuprous chloride in ammonia is due to the formation of compounds between the ammonia and the chloride. In a warm solution the compound $\text{NH}_3 \cdot 2\text{CuCl}$ is formed, and at the ordinary temperature $\text{CuCl} \cdot \text{NH}_3$. This salt is soluble in hydrochloric acid, and then forms a corresponding double salt of cuprous chloride and ammonium chloride. By the action of a certain excess of ammonia on a hydrochloric acid solution of cuprous chloride, very well formed crystals, having the composition

When copper is oxidised with a considerable quantity of oxygen at a high temperature, or at the ordinary temperature in the presence of acids, and also when it decomposes acids, converting them into lower grades of oxidation (for example, when submitted to the action of nitric and sulphuric acids), it forms *cupric oxide*, CuO , or, in the presence of acids, cupric salts. Copper rust, or that black mass which forms on the surface of copper when it is calcined, consists of cupric oxide. The coating of the oxidised copper is very easily separated from the metallic copper, because it is brittle and very easily peels off when it is struck or immersed in water. Anhydrous cupric oxide is very easily dissolved in acids, forming cupric salts, CuX_2 . They are analogous to the salts MgX_2 , ZnX_2 , NiX_2 , FeX_2 , in many respects.

CuCl , $\text{NH}_5\text{H}_2\text{O}$, are obtained. Cuprous chloride is not only soluble in ammonia and hydrochloric acid, but it also dissolves in solutions of certain other salts—for example, in sodium chloride, potassium chloride, sodium thiosulphate, and certain others. All the solutions of cuprous chloride act in many cases as very powerful deoxidising substances, so, for example, it is easy, by means of these solutions, to precipitate gold from its solutions in a metallic form, according to the equation $\text{AuCl}_3 + 3\text{CuCl} = \text{Au} + 3\text{CuCl}_2$.

Among the other compounds corresponding with cuprous oxide, *cuprous iodide*, CuI , is worthy of remark. It is a colourless substance which is insoluble in water and sparingly soluble in ammonia (like silver iodide), but capable of absorbing it, and in this respect it resembles cuprous chloride. It is remarkable from the fact that it is exceedingly easily formed from the corresponding cupric compound CuI_2 . A solution of cupric iodide easily decomposes into iodine and cuprous iodide, even at the ordinary temperature, whilst cupric chloride only suffers a similar change on ignition. If a solution of a cupric salt be mixed with a solution of potassium iodide the cupric iodide formed immediately decomposes into free iodine and cuprous iodide, which separates out as a precipitate. In this case the cupric salt acts in an oxidising manner, like, for example, nitrous acid, ozone, and other substances which liberate iodine from iodides, but with this difference, that it only liberates half, whilst they set free the whole of the iodine from potassium iodide: $2\text{KI} + \text{CuCl}_2 = 2\text{KCl} + \text{CuI} + \text{I}$.

It must also be remarked that cuprous oxide, when treated with hydrofluoric acid, gives an insoluble cuprous fluoride, CuF . Cuprous cyanide is also insoluble in water, and is obtained by the addition of hydrocyanic acid to a solution of cupric chloride saturated with sulphurous anhydride. This cuprous cyanide, like silver cyanide, gives a double soluble salt with potassium cyanide. The double cyanide of copper and potassium is rather stable in the air, and enters into double decompositions with various other salts, like those double cyanides of iron with which we are already acquainted.

Copper hydride, CuH , also belongs to the number of the cuprous compounds. It was obtained by Würtz by mixing a hot (70°) solution of cupric sulphate with a solution of hypophosphorous acid, H_3PO_3 . The addition of the reducing hypophosphorous acid must be stopped when a brown precipitate makes its appearance, and when gas begins to be evolved. The brown precipitate is the hydrated cuprous hydride. When gently heated it disengages hydrogen; it gives cuprous oxide when exposed to the air, burns in a stream of chlorine, and liberates hydrogen with hydrochloric acid: $\text{CuH} + \text{HCl} = \text{CuCl} + \text{H}_2$. Zinc, silver, mercury, lead, and many other heavy metals do not form such a compound with hydrogen, neither under these circumstances nor under the action of hydrogen at the moment of the decomposition of salts by a galvanic current. The greatest resemblance is seen between cuprous hydride and the hydrogen compounds of potassium, sodium, and platinum—a fact which is not void of interest, owing to the proximity of these metals in the periodic system.

Cupric oxide may be obtained by igniting the nitrate or carbonate of copper. On adding potassium or ammonium hydroxide to a solution of a cupric salt, it forms a gelatinous blue precipitate of the hydrated oxide of copper, CuH_2O_2 , insoluble in water. The resultant precipitate is redissolved by an excess of ammonia, and gives a very beautiful azure blue solution, of so intense a colour that the presence of small traces of cupric salts may be discovered by this means.⁹ An excess of potassium or sodium hydroxide does not dissolve cupric hydroxide. The addition of alkalis to a solution of cupric salts is only attended with the formation of a precipitate of the hydroxide when the solution of the salt is

⁹ Cupric oxide and many of its salts are able to give definite, although unstable, compounds with ammonia. This faculty already shows itself in the fact that cupric oxide, as well as the salts of copper, dissolves in aqueous ammonia, and also in the fact that salts of copper absorb ammonia gas. If ammonia be added to a solution of any cupric salt, it first forms a precipitate of cupric hydroxide, which then dissolves in an excess of ammonia. The solution thus formed, when evaporated or on the addition of alcohol, frequently deposits crystals of salts containing both the elements of the salt of copper taken and of ammonia. Several such compounds are generally formed. Thus cupric chloride, CuCl_2 , according to Deherain, forms four compounds with ammonia—namely, one molecule of cupric chloride is able to give crystalline compounds with one, two, four, and six molecules of ammonia. Thus, for example, if ammonia gas be passed into a boiling saturated solution of cupric chloride, then on cooling there separate out small octahedral crystals of a blue colour, containing $\text{CuCl}_2 \cdot 2\text{NH}_3 \cdot \text{H}_2\text{O}$. At 150° this substance loses half the ammonia and all the water contained in it, leaving the compound $\text{CuCl}_2 \cdot \text{NH}_3$. Nitrate of copper forms the compound $\text{Cu}(\text{NO}_3)_2 \cdot 2\text{NH}_3$. This compound remains unchanged on evaporation. Dry cupric sulphate absorbs ammonia gas, and gives a compound containing five molecules of ammonia to one of sulphate (Vol. I. p. 254). If this compound is dissolved in aqueous ammonia, on evaporation it deposits a crystalline substance containing $\text{CuSO}_4 \cdot 4\text{NH}_3 \cdot \text{H}_2\text{O}$. At 150° this substance loses the molecule of water and one-fourth of its ammonia. On ignition all these compounds part with the remaining ammonia in the form of an ammoniacal salt, so that the residue consists of cupric oxide. Both the hydrated and anhydrous cupric oxide is soluble in aqueous ammonia.

The solution obtained by the action of aqueous ammonia and air on copper turnings (Note 6) is remarkable for its faculty of dissolving cellulose, which is insoluble in water, dilute acids, and alkalis. Paper soaked in such a solution acquires the property of not rotting, of being difficultly combustible, and waterproof, &c. It has therefore been applied, especially in England, to many practical purposes—for example, to the construction of temporary buildings, for covering roofs, &c. The composition of the substance held in solution is $\text{Cu}(\text{HO})_2 \cdot 4\text{NH}_3$.

If dry ammonia gas be passed over cupric oxide heated to 265° , a portion of the oxide of copper remains unaltered, whilst the other portion gives copper nitride, the oxygen of the copper oxide combining with the hydrogen and forming water. The oxide of copper which remains unchanged is easily removed by washing the resultant product with aqueous ammonia. Copper nitride is very stable, and is insoluble; it has the composition Cu_3N , and is an amorphous green powder, which is decomposed when strongly ignited, and gives cuprous chloride and ammonium chloride when treated with hydrochloric acid. Like the other nitrides copper nitride, Cu_3N , has scarcely been investigated, although it would be very important to become acquainted with the fundamental properties of these compounds for the purpose of characterising the compounds of nitrogen. It is clear from the above composition that the copper in copper nitride occupies the place of hydrogen, and acts like a univalent metal—that is, the nitride corresponds with cuprous oxide.

taken at the ordinary temperature. A hot solution gives a black precipitate of the anhydrous oxide instead of the blue precipitate, and the precipitate of the hydroxide of copper becomes granular, and turns black when the solution is heated. This is due to the fact that the blue hydroxide is exceedingly unstable, and when slightly heated it loses the elements of water and gives the black anhydrous cupric oxide : $\text{CuH}_2\text{O}_2 = \text{CuO} + \text{H}_2\text{O}$.

Cupric oxide fuses at a strong heat, and on cooling forms a heavy crystalline mass, which is black, opaque, and somewhat tenacious. It is a feebly energetic base, so that not only do the oxides of the metals of the alkalis and alkaline earths displace it from its compounds, but even such oxides as those of lead and silver precipitate it from solutions, which is partially due to these oxides being soluble, although slightly so, in water. However, cupric oxide, and especially the hydroxide, easily combines with even the least energetic acids, and does not give any compounds with bases ; but, on the other hand, *it easily forms basic salts*, and in this respect outstrips magnesium and recalls the oxides of lead or mercury. Therefore the hydroxide of copper dissolves in solutions of neutral cupric salts. The cupric salts are generally blue or green, because cupric hydroxide itself is coloured. But some of the salts are colourless in the anhydrous state.¹⁰

¹⁰ The normal *cupric nitrate*, $\text{CuN}_2\text{O}_6, 3\text{H}_2\text{O}$, is obtained as a deliquescent and soluble (in alcohol) salt of a blue colour by dissolving copper or cupric oxide in nitric acid. It is so easily decomposed by the action of heat that it is impossible to drive off the water of crystallisation from it, as it begins to decompose, leaving cupric oxide, before the water comes off. During the ignition of the normal salt the cupric oxide formed enters into combination with the remaining undecomposed normal salt, and gives a basic salt, $\text{CuN}_2\text{O}_6, 2\text{CuH}_2\text{O}_2$. The same basic salt is obtained if a certain quantity of alkali or cupric hydroxide or carbonate be added to the solution of the normal salt, which is even decomposed when boiled with metallic copper, and forms the basic salt as a green powder, which easily decomposes under the action of heat and leaves a residue of cupric oxide. The basic salt, having the composition $\text{CuN}_2\text{O}_6, 3\text{CuH}_2\text{O}_2$, is nearly insoluble in water.

The normal *carbonate of copper*, CuCO_3 , occurs in nature, although extremely rarely. If solutions of cupric salts be mixed with solutions of alkali carbonates, then, as in the case of magnesium, carbonic anhydride is evolved and basic salts are formed, which vary in composition according to the temperature and conditions of the reaction. By mixing cold solutions, a voluminous blue precipitate is formed, containing an equivalent proportion of cupric hydroxide and carbonate (after standing or heating, its composition is the same as malachite; sp. gr., 3·5): $2\text{CuSO}_4 + 2\text{Na}_2\text{CO}_3 + \text{H}_2\text{O} = \text{CuCO}_3, \text{CuH}_2\text{O}_2 + 2\text{Na}_2\text{SO}_4 + \text{CO}_2$. If the resultant blue precipitate is heated in the liquid, it loses water and is transformed into a granular green mass of the composition Cu_2CO_4 —*i.e.* into a compound of the normal salt with anhydrous cupric oxide. This salt of the oxide corresponds with orthocarbonic acid, $\text{C}(\text{OH})_4 = \text{CH}_4\text{O}_4$, where 4H is replaced by 2Cu. On further boiling, this salt loses a portion of the carbonic acid, forming black cupric oxide, so unstable is the compound of copper with carbonic anhydride. Another basic salt which occurs in nature, $2\text{CuCO}_3, \text{CuH}_2\text{O}_2$, is known as azurite, or blue carbonate of copper; it also loses carbonic acid when boiled with water. On mixing a solution of cupric sulphate

The commonest normal salt is *blue vitriol*—i.e. the normal cupric sulphate. It generally contains five molecules of water of crystallisation, $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$. It forms the product of the action of strong sulphuric acid on copper, sulphurous anhydride being evolved. The same salt is obtained in practice by carefully roasting sulphuretted ores of copper, and also by the action of water holding oxygen in solution on them: $\text{CuS} + \text{O}_2 = \text{CuSO}_4$. This salt forms a bye-product, obtained at gold refineries, when the silver is precipitated from the sulphuric acid solution by means of copper. It is also obtained by pouring dilute sulphuric acid over sheet copper in the presence of air, or by heating cupric oxide or carbonate in sulphuric acid. The crystals of this salt belong to the triclinic system, have a specific gravity of 2.19, are of a beautiful blue colour, and give a solution of the same colour. 100 parts of water at 0° dissolve 15, at 25° 23, and at 100° about 45 parts of cupric sulphate, CuSO_4 . At 100° this salt loses four molecules of water of crystallisation, retaining only one molecule, which it only parts with at a high temperature (220°), and then gives a white powder of the anhydrous sulphate; and the latter, on further calcination, loses the elements of sulphuric anhydride, leaving cupric oxide, like all the cupric salts. The anhydrous (colourless) cupric sulphate is sometimes used for absorbing water; it turns blue in the process. It offers the advantage that it retains both hydrochloric acid and water, but not carbonic anhydride. Cupric sulphate is used for steeping seed corn; this is said to prevent the growth of certain parasites on the plants. In practice, a considerable quantity of cupric sulphate is also used in the preparation of other copper salts—for instance, of certain pigments—and a particularly large quantity is used in the *galvanoplastic process*, which consists in the deposition of copper from a solution of cupric sulphate by the action of a galvanic current, when the metallic copper is deposited on the negative pole and takes the form of the latter. The description of the processes of galvanoplastic art introduced by Yakobi in St. Petersburg forms a part of applied physics, and will not be touched on here; and we will only mention that, although first introduced for small articles, it is now used for such articles as type moulds (*clichés*), for maps, prints, &c., and also for large statues, and for the deposition of iron, zinc, nickel, gold, silver, &c., on other metals and materials. The beginning of the application of the galvanic current to the practical extraction of metals from solutions has also been since established, especially since

with sodium sesquicarbonate no precipitate is at first obtained, but after boiling a precipitate is formed having the composition of malachite. Debray artificially obtained azurite by heating cupric nitrate with chalk.

the dynamo-electric machines of Gramme, Siemens, and others have rendered it possible to cheaply convert the mechanical movement of the steam engine into an electric current. One must think that the application of the electric current, which has long since given such important results in chemistry, will, in the near future, play an important part in technical processes, the example being shown by electric lighting.¹¹

The alloys of copper with certain metals, and especially with zinc and tin, are easily formed by directly melting the metals together. They are easily cast into moulds, forged, and worked like copper, whilst they are much more durable in the air, and are therefore frequently used in the arts. Even the ancients exclusively used alloys of copper, not pure copper but its alloys with tin or different kinds of bronze (Chapter XVIII.). The alloys of copper with zinc are called *brass* or 'yellow metal.' Brass contains about 32 p.c. of zinc; generally, however, it does not contain more than 65 p.c. of copper. The remainder is composed of lead and tin, which usually occur, although in small quantities, in brass. Yellow metal contains about 40 p.c. of zinc. The addition of zinc to copper changes its colour to a considerable degree; with a certain amount of zinc the colour of the copper becomes yellow, and with a still larger proportion of zinc an alloy is formed which has a greenish tint. In those alloys of zinc and copper which contain a greater amount of zinc than of copper, the yellow colour disappears and is replaced by a greyish colour. But when the amount of zinc is diminished to about 15 p.c., the alloy is red and hard, and is called 'tombac.' A contraction takes place in alloying copper with zinc, so that the volume of the alloy is less than that of either metal individually. The zinc volatilises on prolonged heating at a high temperature, and metallic copper remains behind. When heated in the air, the zinc oxidises before the copper, so that all the zinc alloyed with copper may be removed from the copper by this means. An important property of brass containing about 30 p.c. of zinc is that it is soft and malleable in the cold, but becomes somewhat brittle when heated. We may also mention that ordinary copper money contains,

¹¹ Commercial blue vitriol generally contains ferrous sulphate. The salt is purified by converting the ferrous salt into a ferric salt by heating the solution with chlorine or nitric acid. The solution is then evaporated to dryness, and the unchanged cupric sulphate extracted from the residue, which will contain the larger portion of the ferric oxide. The remainder will be separated if cupric hydroxide is added to the solution and boiled; the cupric oxide, CuO , then precipitates the ferric oxide, Fe_2O_3 , just as it is itself precipitated by silver oxide. But the solution will contain a small proportion of a basic salt of copper, and therefore sulphuric acid must be added to the filtered solution, and the salt then crystallised. Acid salts are not formed, and cupric sulphate itself has an acid reaction on litmus paper.

for the sake of rendering it hard, tin, zinc, and iron ($\text{Cu} = 59$ p.c.) that it is now customary to add a small amount of phosphorus to copper and bronze, for the same purpose; that copper is added to silver and gold in coining, &c., also to render it hard; that in Germany, Switzerland, and Belgium, and other countries, a silver-white alloy (melchior, German silver, &c.), for base coinage and other purposes, is prepared from brass and nickel (from 10 to 20 p.c. of nickel; 20 to 30 p.c. zinc; 50 to 70 p.c. copper), or directly from copper and nickel, or, more rarely, from an alloy containing silver, nickel, and copper.^{11b}

Copper, in its cuprous compounds, is so analogous to *silver*, that were there no cupric compounds, or if silver gave stable compounds of the higher oxide, AgO , the resemblance would be as close as that between chlorine and bromine or zinc and cadmium; but silver compounds corresponding to AgO are quite unknown. Although silver peroxide—which was regarded as AgO , but which Berthelot (1880) recognised as the trioxide Ag_2O_3 —is known, still it does not form any true salts, and consequently cannot be placed along with cupric oxide. In distinction to copper, silver as a metal does not oxidise under the influence of heat; and its oxides, Ag_2O and Ag_2O_3 , easily lose oxygen.¹² Silver does *not oxidise* in air at the ordinary pressure, and is therefore classed among the so-called *noble metals*. It has a white colour, which is much purer than that of any other known metal, especially when it is chemically pure. In practice silver is used alloyed, because chemically-pure silver is so soft that it is exceedingly easily worn, whilst, when fused with a small amount of copper, it becomes very hard, without losing its colour.¹³

^{11b} Ball (also Kamensky), 1888, by investigating the electrical conductivity of the alloys of antimony and copper with lead, came to the conclusion that there only exist two definite compounds of antimony and copper, whilst the other alloys are either alloys of these two together or with antimony or with copper. These compounds are Cu_3Sb and Cu_4Sb —one corresponds with the maximum, and the other with the minimum, electrical resistance. In general, the resistance offered to an electrical current forms one of the methods by which the composition of definite alloys (for example, Pb_2Zn_7) is often established, whilst the electromotive force of alloys affords (Laurie, 1888) a still more accurate method. Thus the alloys Zn_3Cu and Cu_3Sn were shown to be such that the electromotive force varied distinctly on their formation.

¹² Cupric oxide is also able to dissociate when heated. Debray and Joannis showed that it then evolves oxygen, whose maximum tension is constant at a given temperature if fusion does not ensue (cupric oxide dissolves in fused cuprous oxide), and this loss of oxygen results in the formation of cuprous oxide, and on cooling the oxygen is all re-absorbed and cupric oxide again formed.

¹³ There are not many soft metals; lead, tin, copper, silver, iron, and gold are somewhat soft, and potassium and sodium very soft. The metals of the alkaline earths are already sonorous and hard, and many other metals are even brittle, especially bismuth and antimony. But the very slight significance which these properties have in

Silver occurs *in nature*, both in a native state and in certain compounds. Native silver, however, is of rather rare occurrence. A far

determining the fundamental chemical properties of substances (although, however, of immense importance in the practical applications of metals) is seen from the example shown by zinc, which is hard at the ordinary temperature, soft at 100° , and brittle at 200° .

As the value of silver depends exclusively on its purity, and as there is no possibility of telling the amount of impurities alloyed with it from its external appearance, it is customary in most countries to mark an article with the amount of pure silver it contains after an accurately-made analysis known as the assay of the silver. In France the assay of silver shows the amount of pure silver in 100 parts by weight; in Russia the amount of pure silver in 96 parts—that is, the assay shows the number of *zolotniks* ($4\cdot26$ grams) of pure silver in one pound (410 grams) of alloyed silver. Russian silver is generally 84 assay—that is, contains 84 parts by weight of pure silver and 12 parts of copper and other metals. French money contains 90 p.c. (in the Russian system this will be 86·4 assay) by weight of silver [English coins and jewellery contain 92·5 p.c. of silver]; the silver rouble is of $83\frac{1}{2}$ assay—that is, it contains 86·8 p.c. of silver—and the smaller Russian silver coinage is of 48 assay, and therefore contains 50 p.c. of silver. Silver ornaments and articles are usually made in Russia of 84 and 72 assay silver. As the alloys of silver and copper, especially after being subjected to the action of heat, are not so white as pure silver, they generally undergo a process known as ‘blanching’ (or ‘pickling’) after being worked up. This consists in removing the copper from the surface of the article by subjecting it to a dark-red heat and then immersing it in dilute acid. During the calcination the copper on the surface is oxidised, whilst the silver remains unchanged; the dilute acid then dissolves the copper oxides formed, and pure silver is left on the surface. The surface is dull after this treatment, owing to the removal of a portion of the metal by the acid. After being polished the article acquires the desired lustre and colour, so as to be indistinguishable from a pure silver object. In order to test a silver article, a portion of its mass must be taken, not from the surface, but to a certain depth. The methods of assay used in practice are very varied. The commonest and most often used is that known as *cupellation*. It is based on the difference in the oxidisability of copper, lead, and silver. The cupel is a porous cup with thick sides, made by compressing




FIG. 95.—Cupel for silver assaying.




FIG. 96.—Clay muffle.

bone ash. The porous mass of bone ash absorbs the fused oxides, especially the lead oxide, which is easily fusible, but it does not absorb the unoxidised metal. The latter collects into a globule under the action of a strong heat in the cupel, and on cooling solidifies into a button, which may then be weighed. Several cupels are placed in a muffle. A muffle is a semi-cylindrical clay vessel, shown in the accompanying drawing. The sides of the muffle are pierced with several orifices, which allow the access of air into it. The muffle is placed in a furnace, where it is strongly heated. Under the action of the air entering into the muffle the copper of the silver alloy is oxidised, but as the oxide of copper is infusible, or, more strictly speaking, difficultly fusible, a certain quantity of lead is added to the alloy; the lead is also oxidised by the air at the high temperature of the muffle, and gives the very fusible lead oxide. The copper oxide then fuses with the lead oxide,

greater quantity of silver occurs in combination with sulphur, and especially in the form of *silver sulphide*, Ag_2S , with lead sulphide or copper sulphide, or the ores of various other metals. The largest amount of silver is extracted from the lead in which it occurs. If this lead be calcined in the presence of air, it oxidises, and the resultant lead oxide, PbO ('litharge' or 'silberglätte,' as it is called), melts into a mobile liquid, which is easily removed. The silver remains in an unoxidised metallic state.¹⁴ This process is called *cupellation*.

and is absorbed by the cupel, whilst the silver remains as a bright white globule. If the weight of the alloy taken and of the silver left on the cupel be determined, it is possible to calculate the composition of the alloy. Hence the essence of cupellation consists in




FIG. 97.—Portable muffle furnace.

the separation of the oxidisable metals from silver, which does not oxidise under the action of heat. A more accurate method, based on the precipitation of silver from its solutions in the form of silver chloride, is described in detail in works upon analytical chemistry.

¹⁴ In America, whence the largest amount of silver is now obtained, they work ores containing not more than $\frac{1}{2}$ p.c. of silver, whilst at $\frac{1}{2}$ p.c. its extraction is very profitable. Moreover, the extraction of silver from ores containing not more than 0.01 p.c. of this metal is sometimes profitable. The majority of the lead smelted from galena contains silver, which is extracted from it. Thus near Arras, in France, they work an ore which contains about 65 parts of lead and 0.088 parts of silver in 100 parts of ore, which corresponds with 136 parts of silver in 10000 parts of lead. At Freiberg, in Saxony, they

Commercial silver generally contains copper, and, more rarely, also other metallic impurities. Chemically *pure silver* is obtained either by cupellation or by subjecting ordinary silver to the following treatment. The silver is first dissolved in nitric acid, which converts it and the

work an ore (enriched by mechanical dressing) containing about 0.9 of silver, 160 of lead, and 2 of copper in 10000 parts. In every case the lead is first extracted in the manner described in Chapter XVIII., and this lead will hold all the silver. Not unfrequently other ores of silver are mixed with lead ores, in order to obtain an argentiferous lead as the product. The extraction of small quantities of silver from lead is facilitated by the fact (Pattinson's process) that the molten argentiferous lead in cooling first deposits crystals of pure lead, which fall to the bottom of the cooling vessel, whilst the proportion of silver in the unsolidified mass increases according to the removal of the crystals of lead. The lead is enriched in this manner up to a contents of $\frac{1}{400}$ part of silver, and is then subjected to cupellation on a larger scale.

The ores of silver which contain a larger amount of it are: silver glance, Ag_2S (sp. gr. 7.2); argentiferous-copper glance, CuAgS ; horn silver or chloride of silver, AgCl ; argentiferous grey copper ore; polybasite, M_9RS_6 (where $\text{M}=\text{Ag}, \text{Cu}$, and $\text{R}=\text{Sb}, \text{As}$), and argentiferous gold. The latter is the usual form in which gold is found in alluvial deposits and ores. The crystals of gold from the Berezhoffsky mines in the Urals contain 90 to 95 of gold and 5 to 9 of silver, and the Altai gold contains 50 to 65 of gold and 36 to 38 of silver. The proportion of silver in native gold varies between these limits in other localities. Silver ores, which generally occur in veins, usually contain native silver and various sulphur compounds. The most famous mines in Europe are in Saxony (Freiberg), which has a yearly output of up to 26 tons of silver, Hungary, and Bohemia (41 tons). In Russia, silver is extracted in the Altai and at Nerchinsk (17 tons). The richest silver mines known are in America, especially in Chili (up to 70 tons), Mexico (200 tons), and more particularly in the western states of North America. The richness of these mines may be judged from the fact that one mine in the State of Nevada (Comstock, near Washoe and the cities of Gold Hill and Virginia), which was discovered in 1859, gave an output of 400 tons in 1866. The modes of extracting silver from lead and argentiferous ores are mainly of two kinds—cupellation and chlorination. The first method is applied to the extraction of silver from argentiferous lead. The mode of cupellation on a large scale does not differ from the assay on a small scale (Note 13); it is based on the property of silver of not oxidising in air when heated, whilst the lead and other metals present are oxidised and give fusible oxides, which are easily removed from the silver. In general, the object in the extraction of silver is to convert it into an alloy with lead, which is easily freed from the silver by cupellation. The method of chlorination consists in converting the silver in an ore into silver chloride. This is either done by a wet or a dry method. When the silver chloride is formed, the extraction of the metal is also done by two methods. The first consists in the silver chloride being reduced to metal by means of iron, and, mercury being added to the mass, the mercury dissolves the silver, but does not act on the other metals. The mercury holding the silver in solution is distilled, when the silver remains behind. This method is called *amalgamation*. The other method is less used, and consists in dissolving the silver chloride in sodium chloride or in sodium thiosulphate, and then precipitating the silver from the solution—by means of iron, for example. In America the chlorination is carried on simultaneously with the amalgamation, but we shall not describe this method, all the more as another process is usually employed in Europe, in which the two processes are carried on separately; the chlorination being done by roasting the ore containing silver with common salt. The salt in volatilising acts on the compounds of silver, and converts them into silver chloride. The amalgamation is then carried on in rotating barrels containing the roasted ore mixed with water, iron, and mercury. The iron reduces the silver chloride by taking up the chlorine from it. The technical details of these processes are described in works on metallurgy.

copper into nitrates, $\text{Cu}(\text{NO}_3)_2$ and AgNO_3 ; hydrochloric acid is then added to the resultant green (owing to the presence of the cupric salt) solution, which is considerably diluted with water in order to retain the lead chloride in solution if the silver contained lead. The copper and many other metals remain in solution, whilst the silver is precipitated as silver chloride. The precipitate is allowed to settle, and the liquid is decanted off; the precipitate is then washed and fused with sodium carbonate. A double decomposition then takes place, sodium chloride and silver carbonate being formed; but the latter decomposes into metallic silver, because the silver oxide is decomposed by heat: $\text{Ag}_2\text{CO}_3 = \text{Ag}_2 + \text{O} + \text{CO}_2$. The silver chloride may also be mixed with metallic zinc, sulphuric acid, and water, and left for a certain time, when the zinc removes the chlorine from the silver chloride and precipitates the silver as a powder. This finely-divided silver is called 'molecular silver.'¹⁵

Chemically-pure silver has an exceeding pure white colour, and a specific gravity of 10.5. In fusing it contracts, and therefore a piece of silver floats on the molten metal. The fusing-point of silver is about 950°C ., and at the high temperature attained by the combustion of detonating gas it volatilises. By employing silver reduced from silver chloride by milk sugar and caustic potash, and distilling it, Stas obtained silver purer than that obtained by other means; in fact, this was perfectly pure silver. The vapour of silver has a very beautiful green colour, which is seen when a silver wire is placed in an oxyhydrogen flame.¹⁶

As regards the capacity of silver for chemical reactions, it is remarkable, in this respect, for its small capacity for combination with

¹⁵ There is another practical method which is also suitable for separating the silver from the solutions obtained in photography, and consists in precipitating the silver by oxalic acid. In this case the amount of silver in the solution must be known, and 23 grams of oxalic acid dissolved in 400 grams of water must be added for every 60 grams of silver in solution in a litre of water. A precipitate of silver oxalate, $\text{Ag}_2\text{C}_2\text{O}_4$, is then obtained, which is insoluble in water but soluble in acids. Therefore, if the liquid contain any free acid it must be previously freed from it by the addition of sodium carbonate. The resultant precipitate of silver oxalate is dried, mixed with an equal weight of dry sodium carbonate, and thrown into a gently-heated crucible. The separation of the silver then proceeds without an explosion, while the silver oxalate if heated alone decomposes with explosion.

According to Stas, the best method of obtaining silver from its solutions is by the reduction of silver chloride dissolved in ammonia by means of an ammoniacal solution of cuprous thiosulphate; the silver is then precipitated in a crystalline form. A solution of ammonium sulphite may be used instead of the cuprous salt.

¹⁶ In melting, silver absorbs a considerable amount of oxygen, which is disengaged on solidifying. One volume of molten silver absorbs up to 22 volumes of oxygen. In solidifying, the silver forms cavities like the crater of a volcano, and throws off metal, owing to the evolution of the gas; all these phenomena recall a volcano on a miniature

oxygen and for its considerable energy for combination with sulphur, iodine, and certain kindred non-metals. *Silver does not oxidise*¹⁷ at any temperature, and its oxide, Ag_2O , is decomposed by heat.

It is also a very important fact that silver is not oxidised by oxygen either in the presence of alkalis, even at exceedingly high temperatures, or in the presence of acids—at least, of dilute acids—which renders it a very important metal in chemical practice for the preservation and fusion of alkalis, and also for many purposes in everyday life. Ozone, however, oxidises it.

Of all acids nitric acid evinces the greatest action on silver. The reaction is accompanied by the formation of oxides of nitrogen and silver nitrate, AgNO_3 , which dissolves in water and does not, therefore, hinder the further action of the acid on the metal. The halogen acids, especially hydriodic acid, act on silver, hydrogen being evolved; but this action soon stops, owing to the halogen compounds of silver being insoluble in water and very slightly soluble in acids; they therefore preserve the remaining mass of metal from the further action of the acid; in consequence of this the action of the halogen acids is only distinctly seen with finely-divided silver. Sulphuric acid acts on silver in the same manner that it does on copper, only it must be concentrated and at a higher temperature. Sulphurous anhydride, and not hydrogen, is then evolved, but there is no action at the ordinary temperature, even in the presence of air. Among the various salts, sodium chloride (in the presence of moisture, air, and carbonic

scale (Dumas). Silver which contains a small quantity of copper or gold, &c., does not show this property of dissolving oxygen.

Stas showed that silver is oxidised by air in the presence of acids. V. d. Pfordten confirmed this, and showed that an acidified solution of potassium permanganate rapidly dissolves silver in the presence of air.

Silver is very malleable and ductile; it may be beaten into leaves 0.002 mm. in thickness. Silver wire may be made so fine that 1 gram is drawn into a wire $2\frac{1}{2}$ kilometres long. In this respect silver is only second to gold. A wire of 2 mm. diameter breaks under a strain of 20 kilograms.

¹⁷ The absorption of oxygen by molten silver is, however, an oxidation, but it is at the same time a phenomenon of solution. Twenty-two cubic centimetres of oxygen are capable of being dissolved in one cubic centimetre of molten silver, and even if it be calculated as having a temperature of 0° , it only weighs 0.08 grams, whilst 1 cubic centimetre of silver weighs at least 10 grams, and therefore it is impossible to suppose that the absorption of the oxygen is attended with the formation of any definite compound (rich in oxygen) of silver and oxygen (about 45 atoms of silver to 1 of oxygen) in any other but a dissociated form, and this is the state in which substances in solution must be regarded (Chapter I.).

Le Chatelier showed that at 300° and 15 atmospheres pressure silver absorbs so much oxygen that it may be regarded as having formed the compound Ag_4O , or a mixture of Ag_2 and Ag_2O . And silver oxide, Ag_2O , only decomposes at 300° under low pressures, whilst at pressures above 10 atmospheres there is no decomposition at 300° but only at 400° .

acid) and potassium cyanide (in the presence of air) act on silver more clearly than any others, converting it into silver chloride and a double cyanide respectively.

Although silver does not directly combine with oxygen, still three different grades of combination with oxygen may be obtained indirectly from the salts of silver. They are all, however, unstable, and decompose into oxygen and metallic silver when ignited. These three oxides of silver have the following composition: *silver suboxide*, Ag_4O ,¹⁸ corresponding with (the little investigated) suboxides of the alkali metals; *silver oxide*, Ag_2O , corresponding with the oxides of the alkali metals, and the ordinary salts of silver, AgX ; and *silver peroxide*, AgO ,¹⁹ or, judging from Berthelot's researches, Ag_2O_3 . *Silver oxide* is obtained as a brown precipitate (which when dried does not contain water) by adding potassium hydroxide to a solution of a silver salt—for example, of silver nitrate. The precipitate formed seems, however, to be an hydroxide, AgHO . The reaction of the alkali on the solution of the salt may be supposed to be $\text{AgNO}_3 + \text{KHO} = \text{KNO}_3 + \text{AgHO}$, and the formation of the anhydrous oxide, $2\text{AgHO} = \text{Ag}_2\text{O} + \text{H}_2\text{O}$, may be compared with the formation of the anhydrous cupric oxide by the action of potassium hydroxide on hot cupric

¹⁸ Silver suboxide (Ag_4O) or argentous oxide is obtained from argentic citrate by heating it to 100° in a stream of hydrogen. Water and argentous citrate are then formed, and the latter, although but slightly soluble in water, gives a reddish-brown solution. When boiled, this solution becomes colourless and deposits metallic silver, the argentic salt being again formed. Wöhler, who discovered this oxide, obtained it as a black precipitate by adding potassium hydroxide to the above solution of argentous citrate. With hydrochloric acid the suboxide gives a brown compound, Ag_2Cl . The same compound is obtained by the action of light on the higher chloride. Other acids do not combine with silver suboxide, but convert it into an argentic salt and metallic silver. This is also the character of other suboxides. In this respect cuprous oxide presents a certain resemblance with these suboxides. But copper forms a suboxide of the composition Cu_4O , which is obtained by the action of an alkaline solution of stannous oxide on cupric hydroxide, and is decomposed by acids into cupric salts and metallic copper. The problems offered by the suboxides, as well as by the peroxides, cannot be considered as fully explained.

¹⁹ *Silver peroxide*, AgO or Ag_2O_3 , is obtained by the decomposition of a dilute (10 p.c.) solution of silver nitrate by the action of a galvanic current. On the positive pole, where oxygen is usually evolved in the decomposition of salts, brittle grey needles, with a metallic lustre and which sometimes attain a rather considerable size, are then formed. They are insoluble in water, and decompose with the evolution of oxygen when they are dried and heated, especially up to 150° , and, like lead dioxide, barium peroxide, &c., their action is strongly oxidising. When treated with acids, oxygen is evolved and a salt formed. Hence, for instance, silver peroxide absorbs sulphurous anhydride and forms silver sulphate. Hydrochloric acid evolves chlorine; ammonia reduces the silver, and is itself oxidised, forming water and gaseous nitrogen. Analyses of the above-mentioned crystals show that they contain silver nitrate, peroxide, and water. According to Fisher, they have the composition $4\text{AgO}, \text{AgNO}_3, \text{H}_2\text{O}$, and, according to Berthelot, $4\text{Ag}_2\text{O}_3, 2\text{AgNO}_3, \text{H}_2\text{O}$.

solutions. This shows that the silver hydroxide decomposes into water and silver oxide, even at low temperatures; at least the hydroxide no longer exists at 60° , but forms the anhydrous oxide. Silver oxide is almost insoluble in water; but, nevertheless, it is undoubtedly a rather powerful basic oxide, because it displaces the oxides of many metals from their soluble salts, and saturates such acids as nitric acid, forming with them neutral salts, which do not act on litmus paper. Undoubtedly, water dissolves a small quantity of silver oxide, which explains the possibility of its action on solutions of salts—for example, on solutions of cupric salts. Water in which silver oxide is shaken up has a distinctly alkaline reaction. The oxide is distinguished by its great instability when heated, so that it loses all its oxygen when slightly heated. Hydrogen reduces it at about 80° .²⁰ The feebleness of the affinity of silver for oxygen is shown by the fact that silver oxide decomposes under the action of light, so that it must be kept in opaque vessels. The silver *salts* are colourless and decompose when heated, leaving metallic silver if the elements of the acid are volatile. They have a peculiar metallic taste, and are exceedingly poisonous; the majority of them are acted on by light, especially in the presence of organic substances, which are then oxidised. The alkaline carbonates give a white precipitate of silver carbonate, Ag_2CO_3 , which is insoluble in water, but soluble in ammonia and ammonium carbonate. Aqueous ammonia, added to a solution of a normal silver salt, first acts like potassium hydroxide, but the precipitate dissolves in an excess of the reagent, like the precipitate of cupric hydroxide.²¹ Silver oxalate and the halogen compounds of silver are insoluble in water, and hydrochloric acid and soluble chlorides give,

²⁰ According to Müller, ferric oxide is reduced by hydrogen (see Chap. XXII. Note 5) at 295° (into what?), cupric oxide at 140° ; Ni_2O_3 at 150° ; nickelous oxide, NiO , is reduced to the suboxide, Ni_2O , at 195° , and to nickel at 270° ; zinc oxide requires so high a temperature for its reduction that the glass tube in which Müller conducted the experiment did not stand the heat; antimony oxide requires a temperature of 215° for its reduction; yellow mercuric oxide is reduced at 180° and the red oxide at 230° ; silver oxide at 85° , and platinum oxide even at the ordinary temperature.

²¹ If a solution of a silver salt is precipitated by sodium hydroxide, and aqueous ammonia is added drop by drop until the precipitate is completely dissolved, then the liquid when evaporated deposits a violet mass of crystalline silver oxide. If moist silver oxide be left in a strong solution of ammonia it gives a black mass, which easily decomposes with a loud explosion, especially when struck. This black substance is called fulminating silver. Probably this is a compound like the other compounds of oxides with ammonia, and in exploding the oxygen of the silver oxide probably forms water with the hydrogen of the ammonia, which is naturally accompanied by the evolution of heat and formation of gaseous nitrogen. Fulminating silver is also formed when potassium hydroxide is added to a solution of silver nitrate in ammonia. The dangerous explosions which are produced by this compound render it needful that great care be taken when salts of silver come into contact with ammonia and alkalis.

as has been already repeatedly observed, a white precipitate of silver chloride in solutions of silver salts. Potassium iodide gives a yellowish precipitate of silver iodide. Zinc separates all the silver in a metallic form from solutions of silver salts. Many other metals and reducing agents—for example, organic substances—also reduce silver from the solutions of its salts.

Silver nitrate, AgNO_3 , is known by the name of lunar caustic (or *lapis infernalis*); it is obtained by dissolving metallic silver in nitric acid. If the silver be impure, the resultant solution will contain a mixture of the nitrates of copper and silver. If this mixture be evaporated to dryness and the residue be carefully fused at an incipient red heat, then all the cupric nitrate is decomposed, whilst the greater part of the silver nitrate remains unchanged. On treating the fused mass with water the latter is dissolved, whilst the cupric oxide remains insoluble. If a certain amount of silver oxide be added to the solution containing the nitrates of silver and copper, it displaces all the cupric oxide. In this case it is naturally not necessary to take pure silver oxide, but only to pour off some of the solution and to add potassium hydroxide to one portion, and to mix the resultant precipitate of the hydroxides, Cu(OH)_2 and AgOH , with the remaining portion.²² By these methods all the copper can be easily removed and

²² So that we here encounter the following phenomena: copper displaces silver from the solutions of its salts, and silver oxide displaces copper oxide from cupric salts. Guided by the conceptions enunciated in Chap. XV., we can account for this in the following manner. The atomic volume of silver = 10·3, and of copper = 7·2, of silver oxide = 32, and of copper oxide = 13. A greater contraction has taken place in the formation of cupric oxide, CuO , than in the formation of silver oxide, Ag_2O , because in the former ($13 - 7 = 6$) the volume after combination with the oxygen has increased by very little, whilst the volume of silver oxide is considerably greater than that of the metal it contains [$32 - (2 \times 10 \cdot 3) = 11 \cdot 4$]. Hence silver oxide is less compact than cupric oxide, and is therefore less stable than it; but, on the other hand, there are greater intervals between the atoms in silver oxide than in cupric oxide, and hence silver oxide is able to give more stable compounds than those of copper oxide. This is verified by the figures and data of their reactions. Unfortunately it is impossible to calculate for cupric nitrate, because this salt has not yet been obtained in an anhydrous state; but the sulphates of both oxides are known. The specific gravity of copper sulphate in an anhydrous state is 3·53, and of silver sulphate 5·36; the molecular volume of the former is 45, and of the latter 58. We will now compare these volumes with those of the oxides. The group SO_5 in the copper occupies, as it were, a volume $45 - 13 = 32$, and in the silver salt a volume $58 - 32 = 26$; hence a smaller contraction has taken place in the formation of the copper salt from the oxide than in the formation of the silver salt, and consequently the latter should be more stable than the former. Therefore the silver oxide is able to decompose the salt of copper oxide, whilst with respect to the metals both salts have been formed with an almost identical contraction, because 58 volumes of the silver salt contain 21 volumes of metal (difference = 37), and 45 volumes of the copper salt contain 7 volumes of copper (difference = 38). Besides which, it must be observed that copper oxide displaces iron oxide, just as silver oxide displaces copper oxide. Silver, copper, and iron, in the form of oxides, displace each other in the above order, but in the form of metals in a reverse order

silver nitrate obtained, which may be ultimately purified by crystallisation. It crystallises in colourless transparent prismatic plates, which are not acted on by air. They are anhydrous. Its sp. gr. is 4.34; it dissolves in an equal weight of water at the ordinary temperature, and in half its weight of boiling water. The pure salt is not acted on by light, but it easily acts in an oxidising manner on the majority of organic substances, which it generally blackens. This is due to the fact that the organic substance is oxidised by the silver nitrate, which is reduced to metallic silver; this is then obtained in a finely-divided state, which causes the black stain. This is taken advantage of for marking linen. Silver nitrate is for the same reason used for *cauterising wounds* and various growths on the body. It then acts in virtue of its oxidising capacity in destroying the organic matter, which it oxidises, as is seen from the separation of a coating of black metallic powdery silver from the part cauterised. It may be remarked that the black stain produced by the reduction of metallic silver disappears under the action of a solution of mercuric chloride or of potassium cyanide, because these salts act on finely-divided silver. From the description of the preparation of silver nitrate it will have been seen that this salt fuses without decomposition at an incipient red heat, and when cast into sticks it is usually employed for cauterising. On further heating, the fused salt undergoes decomposition, first forming silver nitrite and then metallic silver. With ammonia, silver nitrate forms, on evaporation of the solution, colourless crystals containing $\text{AgNO}_3 \cdot 2\text{NH}_3$. In general the salts of silver, like cuprous, cupric, zinc, &c., salts, are able to give several compounds with ammonia; for example, silver nitrate in a dry state absorbs three molecules. The ammonia is generally easily expelled from these compounds by the action of heat.

Silver nitrate under the action of water and a halogen gives nitric acid, a halogen salt of silver, and a silver salt of an oxygen acid of the halogen. Thus, for example, a solution of chlorine in water, when mixed with a solution of silver nitrate, gives silver chloride and chlorate. It is here evident that the reaction of the silver nitrate is identical with the reaction of the caustic alkalis, as the nitric acid is all set free and the silver oxide only reacts in exactly the same manner

(iron, copper, silver). The cause of this order of the displacement of the oxides lies, amongst other things, in their composition. They have the composition Ag_2O , Cu_2O , Fe_2O_3 : the oxide containing the less proportion of oxygen displaces that containing a larger proportion, because the basic character diminishes with the increase of contained oxygen.

Copper also displaces mercury from its salts. It may here be remarked that Spring (1888), on leaving a mixture of dry mercurous chloride and copper for two hours, observed a distinct reduction, which belongs to the number of those phenomena which demonstrate the existence of a mobility of parts (*i.e.* atoms and molecules) in solid substances.

as aqueous potash acts on free chlorine. Therefore the reaction may be expressed in the following manner: $6\text{AgNO}_3 + 3\text{Cl}_2 + 3\text{H}_2\text{O} = 5\text{AgCl} + \text{AgClO}_3 + 6\text{HNO}_3$.

Silver nitrate, like the nitrates of the alkalis, does not contain any water of crystallisation. Moreover, the other salts of silver almost always separate out without any water of crystallisation. The silver salts are further characterised by the fact that they *give neither basic nor acid salts*, owing to which the formation of silver salts generally forms the means of determining the true composition of acids.

Silver gives insoluble and exceedingly stable compounds *with the halogens*. They are obtained by double decomposition with great facility whenever a silver salt comes into contact with halogen salts. Solutions of nitrate, sulphate, and all other kindred salts of silver give a precipitate of silver chloride or iodide in solutions of chlorides and iodides and of the halogen acids, because the halogen salts of silver are insoluble both in water²³ and in other acids. *Silver chloride*, AgCl , is then obtained as a white flocculent precipitate, silver bromide forms a yellowish precipitate, and silver iodide has a very distinct yellow colour. These halogen compounds sometimes occur in nature; they are formed by a dry method—by the action of halogen compounds on silver compounds, especially under the influence of heat. Silver chloride easily fuses at 451° on cooling from a molten state: it forms of a rather soft horn-like mass, which can be cut with a knife, and is therefore known as *horn silver*. It volatilises at a higher temperature. Its ammoniacal solution, on the evaporation of the ammonia, deposits crystalline chloride of silver, in octahedra. Bromide and iodide of silver also appear in forms of the regular system, so that in

²³ Silver chloride is almost perfectly insoluble in water, but is somewhat soluble in water containing sodium chloride or hydrochloric acid, or other chlorides, and many salts, in solution. Thus at 100° 100 parts of water saturated with sodium chloride dissolve 0.4 parts of silver chloride. Bromide and iodide of silver are less soluble in this respect, as also in regard to other solvents. It should be remarked that *silver chloride dissolves in solutions of ammonia, potassium cyanide, and of sodium thiosulphate, $\text{Na}_2\text{S}_2\text{O}_5$* . Silver bromide is almost perfectly analogous to the chloride, but silver iodide is nearly insoluble in a solution of ammonia. Silver chloride even absorbs dry ammonia gas, forming very unstable ammoniacal compounds. When heated these compounds (Vol. I. p. 247, Note 8) evolve the ammonia, as they also do under the action of all acids. Silver chloride enters into double decomposition with potassium cyanide, forming a soluble double cyanide, which we shall presently describe; it also forms a double soluble salt, NaAgS_2O_5 , with sodium thiosulphate.

Silver chloride offers different modifications in the structure of its molecule, as is seen in the variations in the consistency of the precipitate, and in the differences in the action of light. Stas and Carey Lea investigated this subject, which has a particular importance in photography, because silver bromide also gives *photo-salts*.

this respect the halogen salts of silver resemble the halogen salts of the alkali metals.²⁴

²⁴ *Silver bromide and iodide* resemble the chloride in many respects, but the degree of affinity of silver for iodine is greater than that for chlorine and bromine. Deville deduced this fact from a number of experiments. Thus silver chloride, when treated with hydriodic acid, evolves hydrochloric acid, and forms silver iodide. Finely-divided silver easily liberates hydrogen when treated with hydriodic acid; it produces the same decomposition with hydrochloric acid, but in a considerably less degree and only on the surface. The difference between silver chloride and iodide is especially remarkable, because the formation of the former is attended with a greater contraction than that of the latter. The volume of AgCl = 26; of chlorine 27, of silver 10, the sum = 37, hence a contraction has ensued; and in the formation of silver iodide an expansion takes place, because the volume of Ag is 10, of I 26, and of AgI 39 (density, AgCl , 5.59; AgI , 5.67), instead of 36. The atoms of chlorine have united with the atoms of silver without moving asunder, whilst the atoms of iodine must have moved apart in combining with the silver. The matter presents itself differently with respect to the metal; the distance between its atoms in the metal = 2.2, in silver chloride = 3.0, and in silver iodide = 3.5; hence its atoms have moved asunder considerably in both cases. It is also very remarkable that Fizeau observed that the density of silver iodide increases with a rise of temperature—that is, a contraction takes place when it is heated and an expansion when it is cooled.

In order to explain the fact that in silver compounds the iodide is more stable than the chloride and oxide, Professor N. N. Beketoff, in his 'Researches on the Phenomena of Substitutions' (Kharkoff, 1865), proposed the following original hypothesis, which we will give in almost the words of the author:—In the case of aluminium, the oxide, Al_2O_3 , is more stable than the chloride, Al_2Cl_3 , and the iodide, Al_2I_3 . In the oxide the amount of the metal is to the amount of the element combined with it as 54.8 (Al = 27.4) is to 48, or in the ratio 112 : 100; for the chloride the ratio is = 25 : 100; for the iodide it = 7 : 100. In the case of silver the oxide (ratio = 1350 : 100) is less stable than the chloride (ratio = 304 : 100), and the iodide (ratio of the weight of metal to the weight of the halogen = 85 : 100) is the most stable. From these and similar examples it is seen that the most stable compounds are those in which the weights of the combined substances are equal. This may be partly explained by the attraction of like molecules even after their having passed into combination with others. This attraction is proportional to the product of the acting masses. In silver oxide the attraction of Ag, for Ag_2 = 216×216 = 46656, and the attraction of Ag_2 for O = 216×16 = 3456. The attraction of like molecules thus counteracts the attraction of the unlike molecules. The former naturally does not overcome the latter, otherwise there would be a disruption, but it nevertheless diminishes the stability. In the case of an equality or proximity of the magnitude of the combining masses, the attraction of the like parts will counteract the stability of the compound to the least extent—in other words, with an inequality in the combined masses, the molecules have an inclination to return into an elementary state, to decompose, which does not exist to such an extent where the combined masses are equal. There is, therefore, a tendency for large masses to combine with large, and for small masses to combine with small. Hence $\text{Ag}_2\text{O} + 2\text{KI}$ gives $\text{K}_2\text{O} + 2\text{AgI}$. In double decomposition or substitution, the weight of atoms has the preponderating influence, because they are not accompanied by a great change of volumes, and if there is a change it is a contraction, which is very frequently seen in the formation of insoluble compounds (Cremers), the possibility of whose formation determines many such reactions, as Berthollet demonstrated. The influence of an equality of masses on the stability is seen particularly clearly in the effect of a rise of temperature. Argentic, mercuric, or auric oxides, and such like oxides, composed of unequal masses, are decomposed by heat, whilst the oxides of the light metals (like water) are not so easily decomposed by heat. Silver chloride and iodide approach the condition of equality, and are not decomposed by heat. The most stable oxides

Silver chloride may be decomposed, with the separation of silver oxide, by heating it with a solution of an alkali, and if an organic

under the action of heat are those of magnesium, calcium, silicon, and aluminium, which approach the condition of equality. For this reason also hydriodic acid decomposes with greater facility than hydrochloric acid. Chlorine does not act on magnesia or alumina, but it acts on lime and silver oxide, &c. This is partially explained by the fact that by taking heat as movement, and knowing that the atomic heats of the free elements are equal, it must be supposed that the amount of the movement of atoms (their *vis viva*) is equal, and as it is equal to the product of the mass (atomic weight) into the square of the velocity, it follows that the greater the combining weight the smaller will be the velocity (more correctly, its square), and if the combining weights be nearly equal, then the velocities will also be nearly equal. Therefore, the greater the difference between the weights of the combined atoms the greater will the difference between their velocities be. The difference between the velocities will increase with the temperature, and therefore the temperature of decomposition will be the sooner attained the greater be the original difference—that is, the greater the difference of the weights of the combined substances. The nearer these weights are to each other, the more analogous the movement of the unlike atoms, and, consequently, the more stable the resultant compound.

The instability of cupric chloride or nitric oxide, the absence of compounds of fluorine with oxygen, whilst there are compounds of oxygen with chlorine, the greater stability of the oxygen compounds of iodine than of chlorine, the stability of boron nitride, and the instability of cyanogen, and a number of like instances, where, judging from the above argument, one would expect (owing to the nearness of the atomic weights) a stability, show that Beketoff's addition to the mechanical theory of chemical phenomena is still far from sufficient for explaining the true relations of affinities. Nevertheless, in his mode of explaining the relative stabilities of compounds we find an exceedingly interesting treatment of questions of primary importance. Without such efforts it would be impossible to generalise the complex data of experimental knowledge.

Silver cyanide, AgCN , is closely analogous to the haloid salts of silver. It is obtained, in similar manner to silver chloride, by the addition of potassium cyanide to silver nitrate. A white precipitate is then formed, which is almost insoluble in boiling water. It is also, like silver chloride, insoluble in dilute acids. However, it is dissolved when heated with nitric acid, and both hydriodic and hydrochloric acids act on it, converting it into silver chloride and iodide. But alkalis do not act on silver cyanide, although they act on the other haloid salts of silver. Ammonia and solutions of the cyanides of the alkali metals dissolve silver cyanide, as they do the chloride. In the latter case double cyanides are formed—for example, KAgC_2N_2 . This salt is obtained in a crystalline state on evaporating a solution of silver cyanide in potassium cyanide. It is much more stable than silver cyanide itself. It has a neutral reaction, does not change in the air, and does not smell of hydrocyanic acid. Many acids, in acting on a solution of this double salt, precipitate the insoluble silver cyanide. Metallic silver dissolves in a solution of potassium cyanide in the presence of air, with formation of the same double salt and potassium hydroxide, and when silver chloride dissolves in potassium cyanide it forms potassium chloride, besides the salt KAgC_2N_2 . This double salt of silver is used in silver plating. For this purpose potassium cyanide is added to its solution, as otherwise silver cyanide, and not metallic silver, is deposited by the electric current. If two electrodes—one positive (silver) and the other negative (copper)—be immersed in such a solution, then silver will be deposited upon the latter, and the silver of the positive electrode will be dissolved by the liquid, which will thus preserve the same amount of metal in solution as it originally contained. If instead of the negative electrode a copper object be taken, well cleaned from all dirt, then the silver will be deposited in an even coating; this, indeed, forms the mode of *silver plating by the wet method*, which is most often used in practice. A solution of one part of silver nitrate in 30 to 50 parts of water, and mixed with a sufficient quantity of a solution of

substance be added to the alkali the chloride can be easily reduced to metallic silver, the silver oxide being reduced in the oxidation of the organic substance. Iron, zinc, and many other metals reduce silver chloride in the presence of water. Cuprous and mercurous chlorides and many organic substances are also able to reduce the silver from chloride of silver. This shows the rather easy decomposability of the halogen compounds of silver. Silver iodide is much more stable in this respect than the chloride. The same is also observed with respect to the *action of light*. The colourless silver chloride soon acquires a violet colour when exposed to the action of light, and especially under the direct action of the sun's rays. Silver chloride after being acted upon by light is no longer entirely soluble in ammonia, but leaves metallic silver undissolved, from which it might be thought that the

potassium cyanide to redissolve the precipitate of silver cyanide formed, gives a dull coating of silver, but if twice as much water be used the same mixture gives a bright coating.

Silver plating in the wet way has now replaced to a considerable extent the old process of *dry silvering*, because this process, which consists in dissolving silver in mercury and applying the amalgam to the surface of the objects, and then vaporising the mercury, offers the great disadvantage of the poisonous mercury fumes. Besides these, there is another method of silver plating, based on the direct displacement of silver from its salts by other metals—for example, by copper. The copper reduces the silver from its compounds, and the silver separated is deposited upon the copper. Thus a solution of silver chloride in sodium thiosulphate deposits a coating of silver upon a strip of copper immersed in it. It is best for this purpose to take pure *silver sulphite*. It is prepared by mixing a solution of silver nitrate with an excess of ammonia, and adding a saturated solution of sodium sulphite and then alcohol, which precipitates silver sulphite from the solution. The latter and its solutions are very easily decomposed by copper. Metallic iron produces the same decomposition, and iron and steel articles may be very readily silver-plated by means of the thiosulphate solution of silver chloride. Indeed, copper and similar metals may even be silver-plated by means of silver chloride; if the chloride of silver, with a small amount of acid, be rubbed upon the surface of the copper, it becomes covered with a coating of silver, which it has reduced.

Silver plating is not only applicable to metallic objects, but also to glass, china, &c. Glass is silvered for various purposes—for example, glass globes silvered internally are used for ornamentation, and have a mirrored surface. Common looking-glass silvered upon one side forms a mirror which is better than the ordinary mercury mirrors, owing to the truer colours of its image due to the whiteness of the silver. For optical instruments—for example, telescopes—concave mirrors are now made of silvered glass, which has first been moulded and polished into the required form. The *silvering of glass* is based on the fact that silver which is reduced from certain solutions deposits itself uniformly in a perfectly homogeneous and continuous, but very thin, layer, forming a bright reflecting surface. Certain organic substances have this property of reducing silver in this form. The best known among these are certain aldehydes—for instance, common acetaldehyde, C_2H_4O , which easily oxidises in the air and forms acetic acid, $C_2H_4O_2$. This oxidation also easily proceeds at the expense of silver oxide, when a certain amount of ammonia is added to the mixture. The oxide of silver gives up its oxygen to the aldehyde, and the silver reduced from it is deposited in a metallic state in a uniform bright coating. The same action is produced by certain saccharine substances and certain organic acids, such as tartaric acid, &c.

action of light consisted in the decomposition of the silver chloride into chlorine and metallic silver. Indeed, the silver chloride becomes in time darker and darker. Silver bromide and iodide are much more slowly acted on by light, and, according to certain observations, when pure they are even quite unacted on; at least they do not change in weight, so that if they are acted on by light, the change they undergo must be one of a change in the structure of their parts and not of decomposition, as it is in silver chloride. The silver chloride under the action of light changes in weight, which indicates the formation of a volatile product, and the formation of metallic silver on dissolving in ammonia shows the evolution of chlorine. The latter does actually take place under the action of light, but the decomposition does not go as far as into chlorine and silver, but only to the formation of a subchloride of silver, which is of a brown colour and is easily decomposed into metallic silver and silver chloride, $\text{Ag}_2\text{Cl} = \text{AgCl} + \text{Ag}$. This change of the chemical composition and structure of the halogen salts of silver under the action of light forms the basis of *photography*, because the halogen compounds of silver, after having been exposed to light, give a precipitate of finely-divided silver, of a black colour, when treated with reducing agents.²⁵

The insolubility of the halogen compounds of silver forms the basis of many methods used in chemical practice. Thus by means of this reaction it is possible to obtain salts of other acids from a halogen salt of a given metal. The formation of the halogen compounds of silver is used very frequently in the investigation of organic substances; for example, if any product of metalepsis containing iodine or chlorine be heated with a silver salt or silver oxide, then the silver combines with the halogen and gives a halogen salt, whilst the elements previously combined with the silver replace the halogen. For instance, ethylene dibromide, $\text{C}_2\text{H}_4\text{Br}_2$, is transformed into ethylene diacetate, $\text{C}_2\text{H}_4(\text{C}_2\text{H}_3\text{O}_2)_2$, and silver bromide by heating it with silver acetate, $2\text{AgO}_2\text{C}_2\text{H}_3$. The insolubility of the halogen compounds of silver is still more frequently taken advantage of in determining the amount of silver and halogen in a given solution. If it is required, for instance, to determine the quantity of chlorine present in the form of a metallic chloride in a given solution, then a solution

²⁵ In photography these are called 'developers.' The most common developers are: solutions of ferrous sulphate, pyrogallol, ferrous oxalate, hydroxylamine, quinol (its action is particularly good and its use very convenient), potassium sulphite, &c. The chemical processes of photography are of great practical and theoretical interest; but it would be impossible in this work to enter into this special branch of chemistry, which has as yet been very little worked out from a theoretical point of view.

of silver nitrate is added to it so long as it gives a precipitate. On *shaking or stirring* the liquid, the silver chloride easily settles in the form of heavy flakes. It is possible to thus precipitate the whole of the chlorine from a solution, without adding an excess of silver nitrate, because it can be clearly observed whether the addition of a fresh quantity of silver nitrate produces a precipitate in the clear liquid. In this manner it is possible to add to a solution containing chlorine, as much silver as is required for its entire precipitation, and to calculate the amount of chlorine previously in solution from the amount of the solution of silver nitrate consumed, if the quantity of silver nitrate in this solution has been previously determined. The atomic proportions and preliminary experiments with a pure salt—for example, with sodium chloride—will give the amount of chlorine from the quantity of silver nitrate. The details of these methods must be looked for in works on analytical chemistry.

Accurate experiments, and more especially the *researches of Prof. Stas* of Brussels, show the relation which exists between silver and metallic chlorides fully reacting together. These researches have led to the determination of the *combining weights* of silver, sodium, potassium, chlorine, bromine, iodine, and other elements, and are distinguished for their model exactitude, and we will therefore describe them in some detail. As sodium chloride is the chloride most generally used for the precipitation of silver, all the more as it can be easily obtained in a pure state, we will here cite the quantitative observations made by Stas for showing the co-relation between the quantities of chloride of sodium and silver which react together. He first obtained perfectly pure sodium chloride. For this purpose he took pure rock salt, containing only a small quantity of magnesium and calcium compounds and a small amount of potassium salts. This salt was dissolved in water, and the saturated solution evaporated by boiling. The sodium chloride separated out during the boiling, and the mother liquor containing the impurities was poured off. Alcohol of 65 p.c. strength and platinic chloride were added to the resultant salt, in order to precipitate all the potassium and a certain part of the sodium salts. The resultant alcoholic solution, containing the sodium and platinum chlorides, was then mixed with a solution of pure ammonium chloride in order to remove the platinic chloride. After this precipitation, the solution was evaporated in a platinum retort, and then separate portions of this purified sodium chloride were collected as they crystallised. The same salt was prepared from sodium sulphate, tartrate, nitrate, and from the platinochloride, in order to have sodium chloride prepared by different methods and from different sources, and all the samples of

sodium chloride thus prepared were purified and investigated in their relation to silver. After being dried, weighed quantities of all ten samples of sodium chloride were dissolved in water and mixed with a solution in nitric acid of a weighed quantity of perfectly pure silver. A slightly greater quantity of silver was taken than would be required for the decomposition of the sodium chloride, and when, after pouring in all the silver solution, the silver chloride had settled, the amount of silver remaining in excess was determined by means of a solution of sodium chloride of known strength. This solution of sodium chloride was added so long as it formed a precipitate. In this manner was determined how many parts of sodium chloride correspond with 100 parts by weight of silver. The result of ten determinations was that for the entire precipitation of 100 parts of silver from 54.2060 to 54.2093 parts of sodium chloride were required. The difference is so inconsiderable that it has no perceptible influence on the subsequent result of calculation. The mean of ten experiments was that 100 parts of silver react with 54.2078 parts of sodium chloride. In order to learn from this the relation between the chlorine and silver, it was necessary to determine the quantity of chlorine held in 54.2078 parts of sodium chloride, or, what is just the same, the quantity of chlorine which combines with 100 parts of silver. For this purpose Stas made a series of observations on the quantity of silver chloride obtained from 100 parts of silver. Four syntheses were made by him for this purpose. The first synthesis consisted in the formation of silver chloride by the action of chlorine on silver at a red heat. This experiment showed that 100 parts of silver give 132.841, 132.843 and 132.843 of silver chloride. The second method consisted in dissolving a given quantity of silver in nitric acid and precipitating it by means of gaseous hydrochloric acid passed over the surface of the liquid; the resultant mass was evaporated in the dark to drive off the nitric acid and excess of hydrochloric acid, and the remaining silver chloride was fused first in an atmosphere of hydrochloric acid gas and then in air. In this process the silver chloride was not washed, and therefore there could be no loss from solution. Two experiments made by this method showed that 100 parts of silver give 132.849 and 138.848 parts of silver chloride. A third series of determinations was also made on solutions, by precipitating a solution of silver nitrate with a certain excess of gaseous hydrochloric acid. The amount of silver chloride obtained was altogether 132.848. Lastly, a fourth determination was made by precipitating dissolved silver with a solution of ammonium chloride, when it was found that a considerable amount of silver (0.3175) had passed into solution in the washing; for 100 parts


of silver there was obtained altogether 132.8417 of silver chloride. Thus from the mean of seven determinations it appears that 100 parts of silver give 132.8445 parts of silver chloride—that is, that 32.8445 parts of chlorine are able to combine with 100 parts of silver and with that quantity of sodium which is contained in 54.2078 parts of sodium chloride. These observations show that 32.8445 parts of chlorine combine with 100 parts of silver and with 21.3633 parts of sodium. From the figures expressing the relation between the combining weights of chlorine, silver, and sodium, it would be possible to determine their atomic weights—that is, the combining quantity of these elements with respect to one part by weight of hydrogen or 16 parts of oxygen, if there existed a series of similarly accurate determinations for the reactions between hydrogen or oxygen and one of these elements—chlorine, sodium, or silver. If we determine the quantity of silver chloride which is obtained from silver chlorate, AgClO_3 , we shall know the relation between the combining weights of silver chloride and oxygen, so that, taking the quantity of oxygen as a constant magnitude, we can learn from this reaction the combining weight of silver chloride, and from the preceding numbers the combining weights of chlorine and silver. For this purpose it was first necessary to obtain pure silver chlorate. This was done by Stas by acting on silver oxide or carbonate of silver suspended in water, with gaseous chlorine.²⁶

The decomposition of the silver chlorate thus obtained was accomplished by means of the action of a solution of sulphurous anhydride on it. The salt was first fused by carefully heating it at 243° . The solution

²⁶ This is how he describes the phenomenon which then takes place: if silver oxide or carbonate be suspended in water, and an excess of water saturated with chlorine be added, then all the silver is converted into chloride, just as is the case with oxide or carbonate of mercury, and the water then contains, besides the excess of chlorine, only pure hypochlorous acid without the least trace of chloric or chlorous acid. If a stream of chlorine be passed into water containing *an excess of silver oxide* or silver carbonate, while the liquid is continually shaken, then the reaction is the same as the preceding; silver chloride and hypochlorous acid are formed. But this acid does not long remain in a free state; it gradually acts on the silver oxide and gives silver hypochlorite. If, after some time, the current of chlorine is stopped but the shaking is continued, then the liquid loses its characteristic odour of hypochlorous acid, while preserving its energetic decolorising property, because the silver hypochlorite which is formed is easily soluble in water. In the presence of an excess of silver oxide this salt can be kept for several days without decomposition, but it is exceedingly unstable when there is not an excess of silver oxide or carbonate present. So long as the solution of silver hypochlorite is shaken up with the silver oxide, it preserves its transparency and bleaching property, but directly it is allowed to stand, and the silver oxide settles, it becomes rapidly cloudy and deposits large flakes of silver chloride, so that the black silver oxide which had settled becomes covered with the white precipitate. The liquid then loses its bleaching properties, and contains silver chlorate in solution, which has a slightly alkaline

of sulphurous anhydride used was one saturated at 0° . Sulphurous anhydride in dilute solutions is oxidised at the expense of silver chlorate, even at low temperatures, with great ease if the liquid be continually shaken, sulphuric acid and silver chloride being formed: $\text{AgClO}_3 + 3\text{SO}_2 + 3\text{H}_2\text{O} = \text{AgCl} + 3\text{H}_2\text{SO}_4$. After decomposition, the resultant liquid was subjected to evaporation, and the residue of silver chloride was weighed. Thus the process consisted in taking a known weight of silver chlorate, converting it into silver chloride, and determining the weight of the latter. The analysis conducted in this manner gave the following results, which, like the preceding, designate the weight in a vacuum calculated from the weights obtained in air. In the first experiment it appeared that 138.7890 grams of silver chlorate gave 103.9795 parts of silver chloride, and in the second experiment that 259.5287 grams of chlorate gave 194.44515 grams of silver chloride, and after fusion 194.4435 grams. The mean result of both experiments, converted into percentages, shows that 100 parts of silver chlorate contain 74.9205 of silver chloride and 25.0795 parts of oxygen. From this it is possible to calculate the combining weight of silver chloride, because in the decomposition of silver chlorate there are obtained three atoms of oxygen and a combining weight of silver chloride: $\text{AgClO}_3 = \text{AgCl} + 3\text{O}$. Taking the weight of an atom of oxygen to be 16, we find that the combining weight of silver chloride is, judging from the mean result, equal to 143.395. Thus if $\text{O} = 16$, $\text{AgCl} = 143.395$, and as, judging from the preceding experiments, silver chloride contains 32.8445 parts of chlorine per 100 parts of silver, therefore the weight of the atom of silver will be 107.942 and of chlorine 35.453. The weight of the atom of sodium is determined from the fact that 21.3633 parts of sodium chloride combine with 32.8445 parts of chlorine, and consequently $\text{Na} = 23.0599$. This conclusion is

reaction, owing to the presence of a small amount of dissolved oxide. In this manner the reactions which are consecutively accomplished may be expressed by the equations:



Hence, Stas gives the following method for the preparation of silver chlorate. A slow current of chlorine is caused to act on oxide of silver, suspended in water, which is put into a state of continuous movement. The shaking is continued after the supply of chlorine has been stopped, in order that the free hypochlorous acid should pass into silver hypochlorite, and the resultant solution of the hypochlorite is drawn off from the sediment of the excess of silver oxide. This solution decomposes spontaneously into silver chloride and chlorate. The pure silver chlorate, AgClO_3 , does not change under the action of light. The salt is made ready for further use by drying it in dry air at 150° . It is necessary during drying to prevent the access of any organic matter; this is done by filtering the air through cotton wool, and passing it over a layer of red-hot copper oxide.

obtained by the analysis of silver chlorate. This result was verified by means of the analysis of potassium chlorate by decomposing it by heat and determining the weight of the potassium chloride formed, and also by accomplishing the same decomposition by igniting the chlorate in a stream of hydrochloric acid. The combining weight of potassium chloride was thus determined, and another series of determinations confirmed the relation between chlorine, potassium, and silver, in the same manner as the relation between sodium, chlorine, and silver was determined above. Consequently, the combining weights of sodium, chlorine, and potassium could be deduced by conjoining these data with the analysis of silver chlorate and the synthesis of silver chloride. The agreement between the results showed that the determinations made by the above method were perfectly correct, and did not depend in any considerable degree on the methods which were employed in the preceding determinations, as the combining weights of chlorine and silver obtained were the same as before. There was naturally a difference, but so small a one that it indubitably depended on the errors incidental to every process of weighing and experiment. The combining weight of silver was also established by Stas, by means of the synthesis of silver sulphide and the analysis of silver sulphate. The combining weight obtained by this method was 107·920. The synthesis of silver iodide and the analysis of silver iodate gave the figure 107·928. The synthesis of silver bromide with the analysis of silver bromate gave the figure 107·921. The synthesis of silver chloride and the analysis of silver chlorate gave a mean result of 107·937. Hence there is no doubt that the combining weight of silver is at least as much as 107·9—greater than 107·90 and less than 107·95. Stas determined the combining weights of many other elements in this manner, such as lithium, potassium, sodium, bromine, chlorine, iodine, and also nitrogen, because the determination of the amount of silver nitrate obtained from a given amount of silver already gives the combining weight of nitrogen. Taking the combining weight of oxygen as 16, he obtained the following combining weights for these elements: nitrogen 14·04, silver 107·93, chlorine 35·46, bromine 79·95, iodine 126·85, lithium 7·02, sodium 23·04, potassium 39·14. These figures differ slightly from those which are usually employed in chemical investigations. They must be regarded as the result of the best observations, whilst the figures usually used in chemical practice are only approximate—they are, so to speak, round numbers for the atomic weights.

The exhaustive investigations conducted by Stas on the atomic weights of the above-named elements have an important significance in the solution of the problems as to whether the atomic weights of the

elements can be expressed in whole numbers if the unit taken be the atomic weight of hydrogen. Proust, in the beginning of this century, stated that this was the case, and held that the atomic weights of the elements are multiples of the atomic weight of hydrogen. The subsequent determinations of Berzelius, Penny, Marchand, Marignac, Dumas, and more especially of Stas, proved this conclusion to be unjustifiable; because, for example, a whole series of elements proved to have fractional atomic weights—for example, chlorine, about 35.5. In virtue of this, Marignac and Dumas stated that the atomic weights of the elements are expressed in relation to hydrogen, either in whole numbers or in numbers with simple fractions of the magnitude $\frac{1}{2}$ and $\frac{1}{4}$. But Stas's researches refute this supposition also. Even between the combining weight of hydrogen and oxygen, there is not, as far as is yet known, judging from the researches of Dumas, Erdmann, and others (Vol. I. p. 149), that simple relation which is required by *Proust's hypothesis*.²⁷

²⁷ This hypothesis, for the establishment or refutation of which so many researches have been made, is exceedingly important, and fully deserves the attention which has been given to it. Indeed, if it appeared that the atomic weights of all the elements could be expressed in whole numbers with reference to hydrogen, or if they at least proved to be commensurable with one another, then it could be affirmed with confidence that the elements, with all their diversity, were formed of one material condensed or grouped in various manners into the stable, and, under known conditions, undecomposable groups which we call the atoms of the elements. At first it was supposed that all the elements were nothing else but condensed hydrogen; but when it appeared that the atomic weights of the elements could not be expressed in whole numbers in relation to hydrogen, then it might still be supposed that there exists a certain material from which both hydrogen and all the other elements were formed. If it appeared that four atoms of this material form an atom of hydrogen, then the atom of chlorine would present itself as consisting of 142 atoms of this substance, the weight of whose atom would be equal to 0.25. But in this case the atoms of all the elements should be expressed in whole numbers with respect to the weight of the atom of this original material. Let us suppose that the atomic weight of this material is equal to unity, then all the atomic weights should be expressible in whole numbers relatively to this unit. This atom of one element, let us suppose, would weigh m , and of another n , but, as both m and n must be whole numbers, it follows that the atomic weights of all the elements would be commensurable. But it is sufficient to glance over the results obtained by Stas, and to be assured of their accuracy, especially for silver, in order to, if not entirely destroy, at least strongly undermine, this attractive hypothesis. Therefore we must refuse to be assured of the building up from a single substance of the elements known by us. This assurance is not supported either by any known transformation (because one element has never been converted into another element), nor in the commensurability of the atomic weights of the elements. Although the hypothesis of the formation of all the elements from a single substance (for which Crookes has suggested the name protyle) is most attractive in its comprehensiveness, it cannot be denied nor accepted for want of sufficient data. Marignac endeavoured, however, to overcome Stas's conclusions as to the incommensurability of the atomic weights by supposing that in his, as in the determinations of all other observers, there were unperceived errors which were quite independent of the mode of observation; for example, silver nitrate may be supposed to be an unstable substance which changes, under the heatings, evaporations, and other processes to which it is sub-

Among the platinum metals ruthenium, rhodium, and palladium, by their atomic weights and properties, approach to silver, just as the analogues of iron (iron, cobalt, and nickel) approach in all respects to copper. *Gold* stands in exactly the same position in relation to the

jected in the reactions for the determination of the combining weight of silver. It might be supposed, for instance, that silver nitrate contains some impurity which cannot be removed by any means; it might also be supposed that a portion of the elements of the nitric acid are disengaged in the evaporation of the solution of silver nitrate (owing to the decomposing action of water), and in its fusion, and that we have not to deal with normal silver nitrate, but with a slightly basic salt. In this case the observed combining weight will not refer to an actually definite chemical compound, but to some mixture for which there does not exist any perfectly exact combining relations. Marignac upholds this proposition by the fact that the conclusions of Stas and other observers respecting the combining weights determined with the greatest exactitude very nearly agree with the proposition of the commensurability of the atomic weights. For example, the combining weight of silver was shown to be equal to 107.93, so that it only differs by 0.07 from the whole number 108, which is generally accepted for silver. The combining weight of iodine proved to be equal to 126.85—that is, it differs from 127 by 0.15. The combining weights of sodium, nitrogen, bromine, chlorine, and lithium are still nearer to the whole or round numbers which are generally accepted. But Marignac's proposition will hardly stand criticism. Indeed if we express the combining weights of the elements determined by Stas in relation to hydrogen, then the approximation of these weights to whole numbers disappears, because one part of hydrogen in reality does not combine with 16 parts of oxygen, but with 15.96 parts, and therefore we shall obtain, taking $H=1$, not the above-cited figures, but for silver 107.68, for bromine 79.75, for iodine 126.53, magnitudes which are still further removed from whole numbers. Besides which, if Marignac's proposition were true the combining weight of silver determined by one method—*e.g.* by the analysis of silver chlorate combined with the synthesis of silver chloride—would not agree well with the combining weight determined by another method—*e.g.* by means of the analysis of silver iodate and the synthesis of silver iodide. If in one case a basic salt could be obtained, in the other case an acid salt might be obtained. Then the analysis of the acid salt would give different results from that of the basic salt. Thus Marignac's arguments cannot serve as a support for the vindication of Proust's hypothesis.

In conclusion, I think it will not be out of place to cite the following passage from a paper read by me before the London Chemical Society in 1889 (Appendix II.), where I touch on the hypothesis of the complexity of the elements recognised in chemistry, owing to the fact that many have endeavoured to apply the periodic law to the justification of this idea 'taken from a remote antiquity, when it was found convenient to admit the existence of many gods and of a unique matter.'

'When we try to explain the origin of the idea of a unique primary matter, we easily trace that, in the absence of deductions from experiment, it derives its origin from the scientifically philosophical attempt at discovering some kind of unity in the immense diversity of individualities which we see around. In classical times such a tendency could only be satisfied by conceptions about the immaterial world. As to the material world, our ancestors were compelled to resort to some hypothesis, and they adopted the idea of unity in the formative material, because they were not able to evolve the conception of any other possible unity in order to connect the multifarious relations of matter. Responding to the same legitimate scientific tendency, natural science has discovered throughout the universe a unity of plan, a unity of forces, and a unity of matter; and the convincing conclusions of modern science compel every one to admit these kinds of unity. But while we admit unity in many things, we none the less must also explain the individuality and the apparent diversity which we cannot fail to trace everywhere.

heavy platinum metals, osmium, iridium, and platinum, as copper and silver do to the two preceding series. The atomic weight of gold is nearly equal to their atomic weights ;²⁸ it is also dense like these metals. It also gives various grades of oxidation, which are also feeble, both in a basic and an acid sense. Whilst near to osmium, iridium, and platinum, gold at the same time is able, like copper and silver, to form compounds which answer to the type RX —that is, oxides of the composition R_2O . Cuprous chloride, $CuCl$, silver chloride, $AgCl$, and aurous chloride, $AuCl$, are substances which are very much alike in their physical and chemical properties. They are insoluble in water, but dissolve in hydrochloric acid and ammonia, in potassium cyanide, sodium thiosulphate, &c. Just as copper forms a link between the iron metals and zinc, and as silver unites the light platinum metals with cadmium, so also gold presents a transition from the heavy platinum metals to mercury. Copper gives saline compounds of the types CuX and CuX_2 , silver of the type AgX , whilst gold, besides compounds of the type AuX , very easily and most frequently forms AuX_3 . The compounds

It was said of old "Give us a fulcrum and it will become easy to displace the earth." So also we must say, "Give anything that is individualised, and the apparent diversity will be easily understood." Otherwise, how could unity result in a multitude?

'After a long and painstaking research, natural science has discovered the individualities of the chemical elements, and therefore it is now capable, not only of analysing, but also of synthetising; it can understand and grasp the general and unity, as well as the individualised and multitudinous. Unity and the general, like time and space, like force and motion, vary uniformly. The uniform admit of interpolations, revealing every intermediate phase; but the multitudinous, the individualised—like ourselves, like the chemical elements, like the members of a peculiar periodic function of elements, like Dalton's multiple proportions—is characterised in another way. We see in it—side by side with a general connecting principle—leaps, breaks of continuity, points which escape from the analysis of the infinitely small—a complete absence of intermediate links. Chemistry has found an answer to the question as to the causes of multitudes, and while retaining the conception of many elements, all submitted to the discipline of a general law, it offers an escape from the Indian Nirvana—the absorption in the universal—replacing it by the individualised. However, the place for individuality is so limited by the all-grasping, all-powerful universal, that it is merely a fulcrum for the understanding of multitude in unity.'

²⁸ One would expect from the periodic law and analogies with the series iron, cobalt, nickel, copper, zinc, that the atomic weights of the elements of the series osmium, iridium, platinum, gold, mercury, would rise in this order, and at the time of the establishment (1869) of the periodic law, the determinations of Berzelius, Rose, and others gave the following values for the atomic weights: $Os=200$, $I=197$, $Pt=198$, $Au=196$, $Hg=200$. The fulfilment of the expectations of the periodic law was given in the first place by the fresh determinations (Seubert, Dittmar, and Arthur) of the atomic weight of platinum, which proved to be nearly 196, if $O=16$ (as Marignac, Brauner, and others propose); in the second place, by the fact that Seubert proved that the atomic weight of osmium is really less than that of platinum, and approximately $Os=191$; and, in the third place, by the fact that after the researches of Krüss, Thorpe, and Laurie there was no doubt that the atomic weight of gold is greater than that of platinum—namely, nearly 197.

of this type frequently pass into those of the lower type, just as PtX_1 passes into PtX_2 and the same is observable in the elements which, in their atomic weights, follow gold. Mercury gives HgX_2 and HgX . Thallium gives TlX_3 and TlX , lead gives PbX_4 and PbX_2 . On the other hand, gold in a qualitative respect differs from silver and copper in the *extreme case* with which all its compounds are *reduced to metal* by many means. This is not only accomplished by many reducing agents, but also by the action of heat. Thus its chlorides and oxides lose their chlorine and oxygen when heated, and, if the temperature be sufficiently high, these elements are entirely expelled and metallic gold alone remains. Its compounds, therefore, act as oxidising agents.²⁹

In nature gold occurs in the primary and chiefly in quartzose rocks, and especially in quartz veins, as in the Urals (at Berezhovsk), in Australia, and in California. The native gold is extracted from these rocks by subjecting them to a mechanical treatment consisting of crushing and washing. Therefore poor ores are seldom treated, all the more as in many localities nature has already accomplished a similar disintegration of the hard rocky matter containing gold.³⁰ These disintegrated rocks, washed by rain and other water, have formed gold-bearing deposits, which are known as *alluvial gold deposits*. Gold-bearing soil is sometimes met with on the surface and sometimes under the upper soil, but more frequently along the banks of dried up water-

²⁹ Heavy atoms, although they may present many points of analogy with lighter atoms, are more easily isolated; thus $\text{C}_{16}\text{H}_{32}$, although it combines with Br_2 like C_2H_4 , and although it has the same common properties, yet reacts with much greater difficulty than C_2H_4 ; the heavy atoms and molecules are, so to say, inert, and already saturated by themselves. Gold in its higher grade of oxidation, Au_2O_3 , presents feeble basic properties and weakly-developed acid properties, so that this oxide of gold, Au_2O_3 , may be referred to the class of feeble acid oxides, like platonic oxide. This is not the case in the highest known oxides of copper and silver. But in the lower grade of oxidation, aurous oxide, Au_2O , gold, like silver and copper, presents basic properties, although they are unenergetic. In this respect it stands very close in its properties, although not in its types of combination (AuX and AuX_3), to platinum (PtX_2 and PtX_4) and its analogues.

As yet the general chemical characteristics of gold and its compounds have not been fully investigated. This is partly due to very few having undertaken researches on the compounds of this metal, owing to its difficult accessibility for working in large quantities. As the atomic weight of gold is high ($\text{Au} = 197$), the preparation of its compounds requires that it should be taken in large quantities, which forms an obstacle to its being fully studied. Therefore, the facts concerning the history of this metal are rarely distinguished by that exactitude with which many facts have been established concerning other elements more accessible, and long known in use.

³⁰ However, in recent times, especially since about 1870, since chlorine (either as a solution of the gas or as bleaching powder) and bromine have been applied to the extraction of finely-divided gold from poor ores (previously roasted in order to drive off arsenic, sulphur, and oxidise the iron, Fe), the extraction of gold from quartz, and of that which is held in pyrites, increases from year to year, and begins to equal the amount extracted from alluvial deposits.

courses and running streams. The sand of many rivers contains, however, a very small amount of gold, which it is not profitable to work; for example, that of the Alpine rivers contains 5 parts of gold in 10,000,000 parts of sand. The richest gold deposits are those of Siberia, especially in the southern parts of the Government of Yeniseisk, the South Urals, Mexico, California, and the southern coast of Australia, and then the comparatively poorer alluvial deposits of many countries (Hungary, the Alps, and Spain in Europe). The extraction of the gold from alluvial deposits is based on the principle of levigation; the earth is washed, while constantly agitated, by a stream of water, which carries away the lighter portion of the earth, and leaves the coarser particles of the rock and heavier particles of the gold, together with certain substances which accompany it, in the washing apparatus. The extraction of this *washed* gold only necessitates mechanical appliances,³¹ and it is not therefore surprising that gold was known to savages and in the most remote period of history. It sometimes occurs in crystals belonging to the regular system, but in the majority of cases in nuggets or grains of greater or less magnitude. It always contains silver (from very small quantities up to 30 p.c., when it is called 'electrum') and certain other metals, among which lead and rhodium are sometimes found.

The separation of the silver from gold is generally carried on with

³¹ But the particles of gold are sometimes so small that a large amount is lost during the washing. It is then profitable to have recourse to the extraction by chlorine and bromine (Note 30).

In speaking of the extraction of gold the following remarks may not be out of place.

In California advantage is taken of water supplied from high altitudes in order to have a powerful head of water, with which the rocks are directly washed away, thus avoiding the greater portion of the mechanical labour required for the exploitation of these deposits.

The last residues of gold are sometimes extracted from sand by washing them with mercury, which dissolves the gold. The sand mixed with water is caused to come into contact with mercury during the washing. The mercury is then distilled.

Many sulphurous ores, even pyrites, contain a small amount of gold. Compounds of gold with bismuth, BiAu_2 , tellurium, AuTe_2 (calverite), &c., have been found, although rarely.

Among the minerals which accompany gold, and from which the presence of gold may be expected, we may mention white quartz, titanite and magnetic iron ores, and also the following, which are of rarer occurrence, zircon, topaz, garnet, and such like. The concentrated gold washings first undergo a mechanical treatment, and the impure gold then obtained is treated for pure gold by various methods. If the gold contain a considerable amount of foreign metals, especially lead and copper, it is sometimes cupelled, like silver, so that the oxidisable metals may be absorbed by the cupel in the form of oxides, but in every case the gold is obtained together with silver, because the latter metal also is not oxidised. Sometimes the gold is extracted by means of mercury (and the mercury subsequently driven off by distillation), that is, by amalgamation, or by smelting it with lead (which is afterwards removed by oxidation) and processes like those employed for the extraction of silver, because gold, like silver, does not oxidise, is dissolved by lead and mercury, and is non-volatile.

great precision, as the presence of the silver in the gold does not increase its value for exchange, and it can be substituted by other less valuable metals, so that it is an entire gain to extract the silver, as a precious metal, from its alloy with gold. This separation is conducted by different methods. Sometimes the argentiferous gold is melted in crucibles, together with a mixture of common salt and powdered bricks. The greater portion of the silver is thus converted into the chloride, which fuses and is absorbed by the slags, from which it may be extracted by the usual methods. The silver is also extracted from gold by treating it with boiling sulphuric acid, which does not act on the gold but dissolves the silver. But if the alloy does not contain a large proportion of silver it cannot be extracted by this method, or, at all events, the separation will be imperfect, and therefore a fresh amount of silver is added (by fusion) to the gold, in such a quantity that the alloy contains twice as much silver as gold. The silver which is added is preferably such as contains gold, which is very frequently the case. The alloy thus formed is poured in a thin stream into water, by which means it is obtained in a granulated form, which is then boiled with strong sulphuric acid, three parts of acid being used for one part of alloy. The sulphuric acid extracts all the silver without acting on the gold. It is best, however, to pour off the first portion of the acid, which has dissolved the silver, and then treat the residue of still imperfectly pure gold with a fresh quantity of sulphuric acid. The gold is thus obtained in the form of powder, which is washed with water until it is quite free from silver. The silver is precipitated from the solution by means of copper, so that cupric sulphate and metallic silver are obtained. This process is carried out in many countries, as in Russia, at the Government mints.

Gold is generally used in practice alloyed with copper; because pure gold, like pure silver, is very soft, and therefore soon worn away. In assaying or determining the amount of pure gold in such an alloy it is usual to add silver to the gold in order to make up an alloy containing three parts of silver to one of gold. This is known as quartation (because the alloy contains $\frac{1}{4}$ of gold), and the resultant alloy is treated with nitric acid. If the silver be not in excess over the gold, it is not all dissolved by the nitric acid, and this is the reason of the quartation. The amount of pure gold (assay) is determined by weighing the gold which remains after this treatment. English gold (=22 carats) coinage is composed of an alloy containing 91.66 p.c. of gold, but for many articles gold is frequently used containing a larger amount of foreign metals.

Pure gold may be obtained from gold alloys by dissolving in aqua

regia, and then adding ferrous sulphate to the solution or heating it with a solution of oxalic acid. These deoxidising agents reduce the gold, but not the other metals. The chlorine combined with the gold then acts like free chlorine. The gold, thus reduced, is precipitated as an exceedingly fine brown powder. It is then washed with water, and fused with nitre or borax. Pure gold reflects a yellow light, and in the form of very thin sheets, into which it can be hammered and rolled, it transmits a bluish-green light. The specific gravity of gold is nearly 19.5. It fuses at 1090° —at a higher temperature than silver—and can be drawn into exceedingly fine wires and thin sheets. Gold leaf is used for gilding—for instance, it is glued on to wood by means of drying oils. With its softness and ductility, gold is distinguished for its tenacity, and a gold wire two millimetres thick breaks under a load of 68 kilograms. Gold vaporises even at a furnace heat, so that it imparts a greenish colour to a flame passing over it in a furnace. In a chemical respect, gold presents, as is already seen from its general characteristics given above, an example of the so-called noble metals—i.e., it is incapable of being oxidised under any heat, and its oxide is decomposed when calcined. Only chlorine and bromine combine directly with it at the ordinary temperature, but many other metals and non-metals combine with it at a red heat—for example, sulphur, phosphorus, and arsenic. Mercury dissolves it with great ease. It dissolves in potassium cyanide in the presence of air; a mixture of sulphuric acid with nitric acid dissolves it with the aid of heat, although in small quantity. It is also soluble in aqua regia and in selenic acid. Sulphuric, hydrochloric, nitric, and hydrofluoric acids and the caustic alkalis do not act on gold, but a mixture of hydrochloric acid with such oxidising agents as evolve chlorine naturally dissolves it like aqua regia.

As regards the compounds of gold, they belong, as was said above, to the types AuX_3 and AuX . *Auric chloride* or *gold trichloride*, AuCl_3 , which is formed when gold is dissolved in aqua regia, belongs to the former and higher of these types. The solution of this substance in water has a yellow colour, and it may be obtained pure by evaporating the solution in aqua regia to dryness, but not to the point of decomposition. If the evaporation proceed to the point of crystallisation, a compound of gold chloride, and hydrochloric acid, AuHCl_4 , is obtained, like the kindred compounds of platinum; but it easily parts with the acid and leaves auric chloride, which fuses into a red-brown liquid, and then solidifies into a crystalline mass. If dry chlorine be passed over gold in powder it forms a mixture of aurous and auric chlorides, but the aurous chloride is also decomposed by water into

gold and auric chloride. Auric chloride crystallises from its solutions as $\text{AuCl}_3 \cdot 2\text{H}_2\text{O}$, which easily loses water, and the dry chloride loses two-thirds of its chlorine at 185° , forming aurous chloride, whilst at above 300° the latter chloride also loses its chlorine and leaves metallic gold. Auric chloride is the usual form in which gold occurs in solutions, and in which its salts are used in practice and for chemical purposes. It is soluble in water, alcohol, and ether. Light has a reducing action on these solutions, and after a time metallic gold is deposited upon the sides of vessels containing the solution. Hydrogen, at the moment of its evolution and even in a gaseous form, reduces gold from this solution to a metallic state. The reduction is more conveniently and usually accomplished by ferrous sulphate, and, in general, by the action of ferrous salts.³²

If a solution of potassium hydroxide is added to a solution of auric chloride, a precipitate is first formed, which re-dissolves in an excess of the alkali. On being evaporated under the receiver of an air-pump, this solution yields yellow crystals, which present the same composition as the double salts AuMCl_4 , with the substitution of the chlorine by oxygen—that is to say, *potassium aurate*, $\text{AuK}(\text{O})_2$, is formed in crystals containing $3\text{H}_2\text{O}$. The solution has a distinctly alkaline reaction. *Auric oxide*, Au_2O_3 , separates when this alkaline solution is boiled with an excess of sulphuric acid. But it then still retains some alkali; however, it may be obtained in a pure state as a brown powder by dissolving in nitric acid and diluting with water. The brown powder decomposes below 250° into gold and oxygen. It is insoluble in water and in many acids, but it dissolves in alkalis, which shows the acid character of this oxide. A hydroxide, $\text{Au}(\text{OH})_3$, may be obtained as a brown powder by adding magnesium oxide to a solution of auric chloride and treating the resultant precipitate of magnesium aurate with

³² Stannous chloride as a reducing agent also acts on auric chloride, and gives a red precipitate known as *purple of Cassius*. This substance, which probably contains a mixture or compound of aurous oxide and tin oxide, is used as a red pigment for china and glass. Oxalic acid, when heated, reduces metallic gold from its salts, which may be taken advantage of for separating it from its solutions. The oxidation which then takes place in the presence of water, may be expressed by the following equation: $2\text{AuCl}_3 + 3\text{C}_2\text{H}_2\text{O}_4 = 2\text{Au} + 6\text{HCl} + 6\text{CO}_2$. Nearly all organic substances have a reducing action on gold, and solutions of gold leave a violet stain on the skin.

Auric chloride, like platonic chloride, is distinguished for its clearly-developed faculty of forming double salts. These double salts, as a rule, belong to the type AuMCl_4 . The above-mentioned compound of auric chloride with hydrochloric acid evidently belongs to the same type. The compounds $2\text{KAuCl}_4 \cdot 5\text{H}_2\text{O}$, $\text{NaAuCl}_4 \cdot 2\text{H}_2\text{O}$, $\text{AuNH}_4\text{Cl}_4 \cdot \text{H}_2\text{O}$, $\text{Mg}(\text{AuCl}_4)_2 \cdot 2\text{H}_2\text{O}$, and the like are easily crystallised in well-formed crystals. Auric bromide, AuBr_3 , is extremely like the chloride. Auric cyanide is obtained easily in the form of a double salt of potassium, $\text{KAu}(\text{CN})_4$, by mixing saturated and hot solutions of potassium cyanide with auric chloride and then cooling.

nitric acid. This hydroxide loses water at 100° , and gives auric oxide.³³

The starting-point of the compounds of the type AuX is *gold monochloride* or *aurous chloride*, AuCl , which is formed, as mentioned above, by heating auric chloride at 185° . Aurous chloride forms a yellowish white powder; this, when heated with water, is decomposed into metallic gold and auric chloride, which passes into solution: $3\text{AuCl} = \text{AuCl}_3 + 2\text{Au}$. This decomposition is accelerated by the action of light. Hence it is obvious that the compounds corresponding with aurous oxide are comparatively unstable. But this only refers to the simple compounds AuX ; ³⁴ some of the complex compounds, on the contrary, form the most stable compounds of gold. Such, for example, is the cyanide of gold and potassium, $\text{AuK}(\text{CN})_2$. It is formed, for instance, when gold dissolves in the presence of air in a solution of potassium cyanide: $4\text{KCN} + 2\text{Au} + \text{H}_2\text{O} + \text{O} = 2\text{KAu}(\text{CN})_2 + 2\text{KHO}$. The same compound is formed in solution when many compounds of

³³ If ammonia is added to a solution of auric chloride, it forms a yellow precipitate of the so-called fulminating gold, which contains gold, chlorine, hydrogen, nitrogen, and oxygen, but its formula is not known with certainty. It is probably a sort of ammonio-metallic compound, $\text{Au}_2\text{O}_3, 4\text{NH}_3$, or amide (like the mercury compound). This precipitate explodes at 140° , but when left in the presence of solutions containing ammonia it loses all its chlorine and becomes unexplosive. In this form the composition $\text{Au}_2\text{O}_3, 2\text{NH}_3, \text{H}_2\text{O}$ is ascribed to it, but this is uncertain. Auric sulphide, Au_2S_3 , is obtained by the action of hydrogen sulphide on a solution of auric chloride, and also by directly fusing sulphur with gold. It has an acid character, and therefore dissolves in sodium and ammonium sulphides.

³⁴ Potassium aurous cyanide corresponds with the salts of the type AuKX_2 , like PtK_2X_4 , with which we became acquainted in the last chapter. We will enumerate several of the representatives of this class of compounds. If auric chloride, AuCl_3 , be mixed with a solution of sodium thiosulphate, then the gold passes into a colourless solution, which deposits colourless crystals, containing a double thiosulphate of gold and sodium, which are easily soluble in water but are precipitated by alcohol. The composition of this salt is $\text{Na}_5\text{Au}(\text{S}_2\text{O}_3)_2, 2\text{H}_2\text{O}$. If the sodium thiosulphate be represented as $\text{NaS}_2\text{O}_3\text{Na}$, then the double salt in question will be $\text{AuNa}(\text{S}_2\text{O}_3\text{Na})_2, 2\text{H}_2\text{O}$, according to the type AuNaX_2 . The solution of this colourless and easily crystallisable salt has a sweet taste, and the gold is not separated from it either by ferrous sulphate or oxalic acid. This salt, which is known as *Fordos and Giles's salt*, is used in medicine and photography. In general, aurous oxide exhibits a distinct inclination to the formation of similar double salts, as we saw also with PtX_2 ; for example, it forms similar salts with sulphurous acid. Thus if a solution of sodium sulphite be gradually added to a solution of oxide of gold in sodium hydroxide, then the precipitate at first formed redissolves to a colourless solution, which contains the double salt $\text{Na}_5\text{Au}(\text{SO}_3)_2 = \text{AuNa}(\text{SO}_3\text{Na})_2$. The solution of this salt, when mixed with barium chloride, first forms a precipitate of barium sulphite, and then a red barium double salt, which corresponds with the above sodium salt.

The oxygen compound of the type AuX , *aurous oxide*, Au_2O , is obtained as a greenish violet powder on mixing aurous chloride with potassium chloride in the cold. With hydrochloric acid this oxide gives gold and auric chloride, and when heated it easily splits up into oxygen and metallic gold.

gold are mixed with potassium cyanide, because if a higher compound of gold be taken, it is reduced by the potassium cyanide into aurous oxide, which dissolves in potassium cyanide and forms $\text{KAu}(\text{CN})_2$. This substance is soluble in water, and gives a colourless solution, which can be kept for a long time and is employed in electro-gilding—that is, for coating other metallic objects with a layer of gold, which is deposited if the object be connected with the negative pole of a battery and a gold plate be placed on the positive pole and an electrical current passed between them. Then the gold which is situated on the positive pole will dissolve, whilst a coating of gold from the solution will be deposited on the object.

APPENDIX I.



AN ATTEMPT TO APPLY TO CHEMISTRY ONE OF THE PRINCIPLES OF NEWTON'S NATURAL PHILOSOPHY.

BY PROFESSOR MENDELÉEFF.

A LECTURE DELIVERED AT THE ROYAL INSTITUTION OF GREAT BRITAIN
ON FRIDAY, MAY 31, 1889.

NATURE, inert to the eyes of the ancients, has been revealed to us as full of life and activity. The conviction that motion pervaded all things, which was first realised with respect to the stellar universe, has now extended to the unseen world of atoms. No sooner had the human understanding denied to the earth a fixed position and launched it along its path in space, than it was sought to fix immovably the sun and the stars. But astronomy has demonstrated that the sun moves with unswerving regularity through the star-set universe at the rate of about 50 kilometres per second. Among the so-called fixed stars are now discerned manifold changes and various orders of movement. Light, heat, electricity—like sound—have been proved to be modes of motion; to the realisation of this fact modern science is indebted for powers which have been used with such brilliant success, and which have been expounded so clearly at this lecture table by Faraday and by his successors. As, in the imagination of Dante, the invisible air became peopled with spiritual beings, so before the eyes of earnest investigators, and especially before those of Clerk Maxwell, the invisible mass of gases became peopled with particles: their rapid movements, their collisions, and impacts became so manifest that it seemed almost possible to count the impacts and determine many of the peculiarities or laws of their collisions. The fact of the existence of these invisible motions may at once be made apparent by demonstrating the difference in the rate of diffusion through porous bodies of the light and rapidly moving atoms of hydrogen and the heavier and more sluggish particles of air. Within the masses of liquid and of solid bodies we have been forced to acknowledge the existence of persistent though limited motion of their ultimate particles, for otherwise it would be impossible to explain, for example, the celebrated experiments of Graham on diffusion through liquid and colloidal substances. If there were, in our times, no belief in the mole-

cular motion in solid bodies, could the famous Spring have hoped to attain any result by mixing carefully-dried powders of potash saltpetre and sodium acetate, in order to produce, by pressure, a chemical reaction between these substances through the interchange of their metals, and have derived, for the conviction of the incredulous, a mixture of two hygroscopic though solid salts—sodium nitrate and potassium acetate?

In these invisible and apparently chaotic movements, reaching from the stars to the minutest atoms, there reigns, however, a harmonious order which is commonly mistaken for complete rest, but which is really a consequence of the conservation of that dynamic equilibrium which was first discerned by the genius of Newton, and which has been traced by his successors in the detailed analysis of the particular consequences of the great generalisation, namely, relative immovability in the midst of universal and active movement.

But the unseen world of chemical changes is closely analogous to the visible world of the heavenly bodies, since our atoms form distinct portions of an invisible world, as planets, satellites, and comets form distinct portions of the astronomer's universe; our atoms may therefore be compared to the solar systems, or to the systems of double or of single stars: for example, ammonia (NH_3) may be represented in the simplest manner by supposing the sun, nitrogen, surrounded by its planets of hydrogen; and common salt (NaCl) may be looked on as a double star formed of sodium and chlorine. Besides, now that the indestructibility of the elements has been acknowledged, chemical changes cannot otherwise be explained than as changes of motion, and the production by chemical reactions of galvanic currents, of light, of heat, of pressure, or of steam power, demonstrate visibly that the processes of chemical reaction are inevitably connected with enormous though unseen displacements, originating in the movements of atoms in molecules. Astronomers and natural philosophers, in studying the visible motions of the heavenly bodies and of matter on the earth, have understood and have estimated the value of this store of energy. But the chemist has had to pursue a contrary course. Observing in the physical and mechanical phenomena which accompany chemical reactions the quantity of energy manifested by the atoms and molecules, he is constrained to acknowledge that within the molecules there exist atoms in motion, endowed with an energy which, like matter itself, is neither being created nor capable of being destroyed. Therefore, in chemistry, we must seek dynamic equilibrium not only between the molecules, but also in their midst among their component atoms. Many conditions of such equilibrium have been determined, but much remains to be done, and it is not uncommon, even in these days, to find that some chemists forget that there is the possibility of motion in the interior of molecules, and therefore represent them as being in a condition of death-like inactivity.

Chemical combinations take place with so much ease and rapidity, possess so many special characteristics, and are so numerous, that their simplicity and order was for a long time hidden from investigators. Sympathy, relationship, all the caprices or all the fancifulness of human intercourse seemed to have found complete analogies in chemical combinations, but with this difference, that the characteristics of the material substances—such as silver, for example, or of any other body—remain unchanged in every sub-

division from the largest masses to the smallest particles, and consequently their characteristics must be a property of its particles. But the world of heavenly luminaries appeared equally fanciful at man's first acquaintance with it, so much so, that the astrologers imagined a connection between the individualities of men and the conjunctions of planets. Thanks to the genius of Lavoisier and of Dalton, man has been able, in the unseen world of chemical combinations, to recognise laws of the same simple order as those which Copernicus and Kepler proved to exist in the planetary universe. Man discovered, and continues every hour to discover, *what* remains unchanged in chemical evolution, and *how* changes take place in combinations of the unchangeable. He has learned to predict, not only what possible combinations may take place, but also the very existence of atoms of unknown elementary substances, and has besides succeeded in making innumerable practical applications of his knowledge to the great advantage of his race, and has accomplished this notwithstanding that notions of sympathy and affinity still preserve a strong vitality in science. At present we cannot apply Newton's principles to chemistry, because the soil is only being now prepared. The invisible world of chemical atoms is still waiting for the creator of chemical mechanics. For him our age is collecting a mass of materials, the inductions of well-digested facts, and many-sided inferences similar to those which existed for Astronomy and Mechanics in the days of Newton. It is well also to remember that Newton devoted much time to chemical experiments, and while considering questions of celestial mechanics, persistently kept in view the mutual action of those infinitely small worlds which are concerned in chemical evolutions. For this reason, and also to maintain the unity of laws, it seems to me that we must, in the first instance, seek to harmonise the various phases of contemporary chemical theories with the immortal principles of the Newtonian natural philosophy, and so hasten the advent of true chemical mechanics. Let the above considerations serve as my justification for the attempt which I propose to make to act as a champion of the universality of the Newtonian principles, which I believe are competent to embrace every phenomenon in the universe, from the rotation of the fixed stars to the interchanges of chemical atoms.

In the first place I consider it indispensable to bear in mind that, up to quite recent times, only a one-sided affinity has been recognised in chemical reactions. Thus, for example, from the circumstance that red-hot iron decomposes water with the evolution of hydrogen, it was concluded that oxygen had a greater affinity for iron than for hydrogen. But hydrogen, in presence of red-hot iron scale, appropriates its oxygen and forms water, whence an exactly opposite conclusion may be formed.

During the last ten years a gradual, scarcely perceptible, but most important change has taken place in the views, and consequently in the researches, of chemists. They have sought everywhere, and have always found, systems of conservation or dynamic equilibrium substantially similar to those which natural philosophers have long since discovered in the visible world, and in virtue of which the position of the heavenly bodies in the universe is determined. There where one-sided affinities only were at first detected, not only secondary or lateral ones have been found, but even those

which are diametrically opposite; yet among these, dynamical equilibrium establishes itself not by excluding one or other of the forces, but regulating them all. So the chemist finds in the flame of the blast furnace, in the formation of every salt, and, with especial clearness, in double salts and in the crystallisation of solutions, not a fight ending in the victory of one side, as used to be supposed, but the conjunction of forces; the peace of dynamic equilibrium resulting from the action of many forces and affinities. Carbonaceous matters, for example, burn at the expense of the oxygen of the air, yielding a quantity of heat, and forming products of combustion, in which it was thought that the affinities of the oxygen with the combustible elements were satisfied. But it appeared that the heat of combustion was competent to decompose these products, to dissociate the oxygen from the combustible elements, and therefore to explain combustion fully it is necessary to take into account the equilibrium between opposite reactions, between those which evolve and those which absorb heat.

In the same way, in the case of the solution of common salt in water, it is necessary to take into account, on the one hand, the formation of compound particles generated by the combination of salt with water, and, on the other, the disintegration or scattering of the new particles formed, as well as of those originally contained. At present we find two currents of thought, apparently antagonistic to each other, dominating the study of solutions: according to the one, solution seems a mere act of building up or association; according to the other, it is only dissociation or disintegration. The truth lies, evidently, between these views; it lies, as I have endeavoured to prove by my investigations into aqueous solutions, in the dynamic equilibrium of particles tending to combine and also to fall asunder. The large majority of chemical reactions which appeared to act victoriously along one line have been proved capable of acting as victoriously even along an exactly opposite line. Elements which utterly decline to combine directly may often be formed into comparatively stable compounds by indirect means, as, for example, in the case of chlorine and carbon; and consequently the sympathies and antipathies which it was thought to transfer from human relations to those of atoms should be laid aside until the mechanism of chemical relations is explained. Let us remember, however, that chlorine, which does not form with carbon the chloride of carbon, is strongly absorbed, or, as it were, dissolved, by carbon, which leads us to suspect incipient chemical action even in an external and purely surface contact, and involuntarily gives rise to conceptions of that unity of the forces of nature which has been so energetically insisted on by Sir William Grove and formulated in his famous paradox. Grove noticed that platinum, when fused in the oxyhydrogen flame, during which operation water is formed, when allowed to drop into water decomposes the latter and produces the explosive oxyhydrogen mixture. The explanation of this paradox, as of many others which arose during the period of chemical renaissance, has led, in our time, to the promulgation by Henri Sainte-Claire Deville of the conception of dissociation and of equilibrium, and has recalled the teaching of Berthollet, which, notwithstanding its brilliant confirmation by Heinrich Rose and Dr. Gladstone, had not, up to that period, been included in received chemical views.

Chemical equilibrium in general, and dissociation in particular, are now being so fully worked out in detail, and applied in such various ways, that I do not allude to them to develop, but only use them as examples by which to indicate the correctness of a tendency to regard chemical combinations from points of view differing from those expressed by the term hitherto appropriated to define chemical forces, namely, 'affinity.' Chemical equilibria, dissociation, the speed of chemical reactions, thermochemistry, spectroscopy, and, more than all, the determination of the influence of masses and the search for a connection between the properties and weights of atoms and molecules—in one word, the vast mass of the most important chemical researches of the present day—clearly indicates the near approach of the time when chemical doctrines will submit fully and completely to the doctrine which was first announced in the *Principia* of Newton.

In order that the application of these principles may bear fruit it is evidently insufficient to assume that statical equilibrium reigns alone in chemical systems or chemical molecules: it is necessary to grasp the conditions of possible states of dynamical equilibria, and to apply to them kinetic principles. Numerous considerations compel us to renounce the idea of statical equilibrium in molecules, and the recent yet strongly-supported appeals to dynamic principles constitute, in my opinion, the foundation of the modern teaching relating to atomicity, or the valency of the elements, which usually forms the basis of investigations into organic or carbon compounds.

This teaching has led to brilliant explanations of very many chemical relations and to cases of isomerism, or the difference in the properties of substances having the same composition. It has been so fruitful in its many applications and in the foreshadowing of remote consequences, especially respecting carbon compounds, that it is impossible to deny its claims to be ranked as a great achievement of chemical science. Its practical application to the synthesis of many substances of the most complicated composition entering into the structure of organised bodies, and to the creation of an unlimited number of carbon compounds, among which the colours derived from coal tar stand prominently forward, surpass the synthetical powers of Nature itself. Yet this teaching, as applied to the structure of carbon compounds, is not on the face of it directly applicable to the investigation of other elements, because in examining the first it is possible to assume that the atoms of carbon have always a definite and equal number of affinities, whilst in the combinations of other elements this is evidently inadmissible. Thus, for example, an atom of carbon yields only one compound with four atoms of hydrogen and one with four atoms of chlorine in the molecule, whilst the atoms of chlorine and hydrogen unite only in the proportions of one to one. Simplicity is here evident, and forms a point of departure from which it is easy to move forward with firm and secure tread. Other elements are of a different nature. Phosphorus unites with three and with five atoms of chlorine, and consequently the simplicity and sharpness of the application of structural conceptions are lost. Sulphur unites only with two atoms of hydrogen, but with oxygen it enters into higher orders of combination. The periodic relationship which exists among all the properties of the elements—such, for example, as their ability to enter into various combinations—and

their atomic weights, indicate that this variation in atomicity is subject to one perfectly exact and general law, and it is only carbon and its near analogues which constitute cases of permanently preserved atomicity. It is impossible to recognise as constant and fundamental properties of atoms, powers which, in substance, have proved to be variable. But by abandoning the idea of permanence, and of the constant saturation of affinities—that is to say, by acknowledging the possibility of free affinities—many retain a comprehension of the atomicity of the elements ‘under given conditions’; and on this frail foundation they build up structures composed of chemical molecules, evidently only because the conception of manifold affinities gives, at once, a simple statical method of estimating the composition of the most complicated molecules.

I shall enter neither into details, nor into the various consequences following from these views, nor into the disputes which have sprung up respecting them (and relating especially to the number of isomerides possible on the assumption of free affinities), because the foundation or origin of theories of this nature suffers from the radical defect of being in opposition to dynamics. The molecule, as even Laurent expressed himself, is represented as an architectural structure, the style of which is determined by the fundamental arrangement of a few atoms, whilst the decorative details, which are capable of being varied by the same forces, are formed by the elements entering into the combination. It is on this account that the term ‘structural’ is so appropriate to the contemporary views of the above order, and that the ‘structuralists’ seek to justify the tetrahedric, plane, or prismatic disposition of the atoms of carbon in benzene. It is evident that the consideration relates to the statical position of atoms and molecules and not to their kinetic relations. The atoms of the structural type are like the lifeless pieces on a chess board: they are endowed but with the voices of living beings, and are not those living beings themselves; acting, indeed, according to laws, yet each possessed of a store of energy which, in the present state of our knowledge, must be taken into account.

In the days of Haüy, crystals were considered in the same statical and structural light, but modern crystallographers, having become more thoroughly acquainted with their physical properties and their actual formation, have abandoned the earlier views, and have made their doctrines dependent on dynamics.

The immediate object of this lecture is to show that, starting with Newton’s third law of motion, it is possible to preserve to chemistry all the advantages arising from structural teaching, without being obliged to build up molecules in solid and motionless figures, or to ascribe to atoms definite limited valencies, directions of cohesion, or affinities. The wide extent of the subject obliges me to treat only a small portion of it, namely of *substitutions*, without specially considering combinations and decompositions, and even then limiting myself to the simplest examples, which, however, will throw open prospects embracing all the natural complexity of chemical relations. For this reason, if it should prove possible to form groups similar, for example, to H_4 or CH_4 , as the remnants of molecules CH_4 or C_2H_7 , we shall not pause to consider them, because, as far as we know, they fall asunder into

two parts, $H_2 + H_2$ or $CH_4 + H_2$, as soon as they are even temporarily formed, and are capable of separate existence, and therefore can take no part in the elementary act of substitution. With respect to the simplest molecules which we shall select—that is to say, those of which the parts have no separate existence, and therefore cannot appear in substitutions—we shall consider them according to the periodic law, arranging them in direct dependence on the atomic weight of the elements.

Thus, for example, the molecules of the simplest hydrogen compounds—

HF	H ₂ O	H ₃ N	H ₄ C
hydrofluoric acid	water	ammonia	methane

correspond with elements the atomic weights of which decrease consecutively

$$F = 19, \quad O = 16, \quad N = 14, \quad C = 12.$$

Neither the arithmetical order (1, 2, 3, 4 atoms of hydrogen) nor the total information we possess respecting the elements will permit us to interpolate into this typical series one more additional element; and therefore we have here, for hydrogen compounds, a natural base on which are built up those simple chemical combinations which we take as typical. But even they are competent to unite with each other, as we see, for instance, in the property which hydrofluoric acid has of forming a hydrate—that is, of combining with water; and the similar attribute of ammonia, resulting in the formation of a caustic alkali, NH_3, H_2O , or NH_4OH .

Having made these indispensable preliminary observations, I may now attack the problem itself and attempt to explain the so-called structure, or rather construction, of molecules—that is to say, their constitution and transformations—without having recourse to the teaching of ‘structuralists,’ but on Newton’s dynamical principles.

Of Newton’s three laws of motion, only the third can be applied directly to chemical molecules when regarded as systems of atoms among which it must be supposed that there exist common influences or forces, and resulting compounded relative motions. Chemical reactions of every kind are undoubtedly accomplished by changes in these internal movements, respecting the nature of which nothing is known at present, but the existence of which the mass of evidence collected in modern times forces us to acknowledge as forming part of the common motion of the universe, and as a fact further established by the circumstance that chemical reactions are always characterised by changes of volume or the relations between the atoms or the molecules. Newton’s third law, which is applicable to every system, declares that, ‘action is always associated with reaction, and is equal to it.’ The brevity and conciseness of this axiom was, however, qualified by Newton in a more expanded statement, ‘the action of bodies one upon another are always equal, and in opposite directions.’ This simple fact constitutes the point of departure for explaining dynamic equilibrium—that is to say, systems of conservancy. It is capable of satisfying even the dualists, and of explaining, without additional assumptions, the preservation of those chemical types which Dumas, Laurent, and Gerhardt created unit types, and those views of atomic combinations which the structuralists express by atomicity or the

valency of the elements, and, in connection with them, the various numbers of affinities. In reality, if a system of atoms or a molecule be given, then in it, according to the third law of Newton, each portion of atoms acts on the remaining portion in the same manner, and with the same force as the second set of atoms acts on the first. We infer directly from this consideration that both sets of atoms, forming a molecule, are not only equivalent with regard to themselves, as they must be according to Dalton's law, but also that they may, if united, replace each other. Let there be a molecule containing atoms A B C, it is clear that, according to Newton's law, the action of A on B C must be equal to the action of B C on A, and if the first action is directed on B C, then the second must be directed on A, and consequently then, where A can exist in dynamic equilibrium, B C may take its place and act in a like manner. In the same way the action of C is equal to the action of A B. In one word every two sets of atoms forming a molecule are equivalent to each other, and may take each other's place in other molecules, or, having the power of balancing each other, the atoms or their complements are endowed with the power of replacing each other. Let us call this consequence of an evident axiom 'the principle of substitution,' and let us apply it to those typical forms of hydrogen compounds which we have already discussed, and which, on account of their simplicity and regularity, have served as starting-points of chemical argument long before the appearance of the doctrine of structure.

In the type of hydrofluoric acid, HF, or in systems of double stars, are included a multitude of the simplest molecules. It will be sufficient for our purpose to recall a few: for example, the molecules of chlorine, Cl_2 , and of hydrogen, H_2 , and hydrochloric acid, HCl, which is familiar to all in aqueous solution as spirits of salt, and which has many points of resemblance with HF, HBr, HI. In these cases division into two parts can only be made in one way, and therefore the principle of substitution renders it probable that exchanges between the chlorine and the hydrogen can take place, if they are competent to unite with each other. There was a time when no chemist would even admit the idea of any such action; it was then thought that the power of combination indicated a polar difference of the molecules in combination, and this thought set aside all idea of the substitution of one component element by another.

Thanks to the observations and experiments of Dumas and Laurent fifty years ago, such fallacies were dispelled, and in this manner, the principle of substitution was exhibited. Chlorine and bromine acting on many hydrogen compounds, occupy immediately the place of their hydrogen, and the displaced hydrogen, with another atom of chlorine or bromine, forms hydrochloric acid or bromide of hydrogen. This takes place in all typical hydrogen compounds. Thus chlorine acts on this principle on gaseous hydrogen—reaction, under the influence of light, resulting in the formation of hydrochloric acid. Chlorine acting on the alkalis, constituted similarly to water, and even on water itself—only, however, under the influence of light and only partially because of the instability of HClO —forms by this principle bleaching salts, which are the same as the alkalis, but with their hydrogen replaced by chlorine. In ammonia and in methane, chlorine can also replace the hydrogen. From ammonia is formed in this manner the so-called

chloride of nitrogen, NCl_3 , which decomposes very readily with violent explosion on account of the evolved gases, and falls asunder as chlorine and nitrogen. Out of marsh gas, or methane, CH_4 , may be obtained consecutively, by this method, every possible substitution, of which chloroform, CHCl_3 , is the best known, and carbon tetrachloride, CCl_4 , the most instructive. But by virtue of the fact that chlorine and bromine act, in the manner shown, on the simplest typical hydrogen compounds, their action on the more complicated ones may be assumed to be the same. This can be easily demonstrated. The hydrogen of benzene, C_6H_6 , reacts feebly under the influence of light on liquid bromine, but Gustavson has shown that the addition of the smallest quantity of metallic aluminium causes energetic action and the evolution of large volumes of hydrogen bromide.

If we pass on to the second typical hydrogen compound—that is to say, water—its molecule, HOH , may be split up in two ways: either into an atom of hydrogen and a semimolecule of hydrogen peroxide, HO , or into oxygen, O , and two atoms of hydrogen, H ; and therefore, according to the principle of substitution, it is evident that one atom of hydrogen can exchange with hydrogen oxide, HO , and two atoms of hydrogen, H , with one atom of oxygen, O .

Both these forms of substitution will constitute methods of oxidation—that is to say, of the entrance of oxygen into the compound—a reaction which is so common in nature as well as in the arts, taking place at the expense of the oxygen of the air or by the aid of various oxidising substances or bodies which part easily with their oxygen. There is no occasion to reckon up the unlimited number of cases of such oxidising reactions. It is sufficient to state that in the first of these oxygen is directly transferred, and the position, the chemical function, which hydrogen originally occupied is, after the substitution, occupied by the hydroxyl. Thus ammonia, NH_3 , yields hydroxylamine, $\text{NH}_2(\text{OH})$, a substance which retains many of the properties of ammonia.

Methane and a number of other hydrocarbons yield, by substitution of the hydrogen by its oxide, methyl alcohol, $\text{CH}_3(\text{OH})$, and other alcohols. The substitution of one atom of oxygen for two atoms of hydrogen is equally common with hydrogen compounds. By this means alcoholic liquids containing ethyl alcohol, or spirits of wine, $\text{C}_2\text{H}_5(\text{OH})$, are oxidised until they become vinegar or acetic acid, $\text{C}_2\text{H}_3\text{O}(\text{OH})$. In the same way caustic ammonia, or the combination of ammonia with water, $\text{NH}_3, \text{H}_2\text{O}$, or $\text{NH}_4(\text{OH})$, which contains a great deal of hydrogen, by oxidation exchanges four atoms of hydrogen for two atoms of oxygen, and becomes converted into nitric acid, $\text{NO}_3(\text{OH})$. This process of conversion of ammonium salts into saltpetre goes on in the fields every summer, and with especial rapidity in tropical countries. The method by which this is accomplished, though complex, though involving the agency of all-permeating micro-organisms, is, in substance, the same as that by which alcohol is converted into acetic acid, or glycol, $\text{C}_2\text{H}_4(\text{OH})_2$, into oxalic acid, if we view the process of oxidation in the light of the Newtonian principles.

But while speaking of the application of the principle of substitution to water, we need not multiply instances, but must turn our attention to two

special circumstances which are closely connected with the very mechanism of substitutions.

In the first place, the replacement of two atoms of hydrogen by one atom of oxygen may take place in two ways, because the hydrogen molecule is composed of two atoms, and therefore, under the influence of oxygen, the molecule forming water may separate before the oxygen has time to take its place. It is for this reason that we find, during the conversion of alcohol into acetic acid, that there is an interval during which is formed aldehyde, C_2H_4O , which, as its very name implies, is 'alcohol dehydrogenatum,' or alcohol deprived of hydrogen. Hence aldehyde combined with hydrogen yields alcohol; and united to oxygen, acetic acid.

For the same reason there should be, and there actually are, intermediate products between ammonia and nitric acid, $NO_2(HO)$, containing either less hydrogen than ammonia, less oxygen than nitric acid, or less water than caustic ammonia. Accordingly we find, among the products of the deoxidation of nitric acid and the oxidation of ammonia, not only hydroxylamine, but also nitrous oxide, nitrous and nitric anhydrides. Thus, the production of nitrous acid results from the removal of two atoms of hydrogen from caustic ammonia and the substitution of the oxygen for the hydrogen, $NO(OH)$; or by the substitution, in ammonia, of three atoms of hydrogen by hydroxyl, $N(OH)_3$, and by the removal of water: $N(OH)_3 - H_2O = NO(OH)$. The peculiarities and properties of nitrous acid—as, for instance, its action on ammonia and its conversion, by oxidation, into nitric acid—are thus clearly revealed.

On the other hand, in speaking of the principle of substitution as applied to water, it is necessary to observe that hydrogen and hydroxyl, H and OH , are not only competent to unite, but also to form combinations with themselves, and thus become H_2 and H_2O_2 ; and such are hydrogen and the peroxide thereof. In general, if a molecule AB exists, then molecules AA and BB can exist also. A direct reaction of this kind does not, however, take place in water, therefore undoubtedly, at the moment of formation, hydrogen reacts on hydrogen peroxide, as we can show at once by experiment; and further because hydrogen peroxide, H_2O_2 , exhibits a structure containing a molecule of hydrogen, H_2 , and one of oxygen, O_2 , either of which is capable of separate existence. The fact, however, may now be taken as thoroughly established, that, at the moment of combustion of hydrogen or of the hydrogen compounds, hydrogen peroxide is always formed, and not only so, but in all probability its formation invariably precedes the formation of water. This was to be expected as a consequence of the law of Avogadro and Gerhardt, which leads us to expect this sequence in the case of equal interactions of volumes of vapours and gases; and in hydrogen peroxide we actually have such equal volumes of the elementary gases.

The instability of hydrogen peroxide—that is to say, the ease with which it decomposes into water and oxygen, even at the mere contact of porous substances—accounts for the circumstance that it does not form a permanent product of combustion, and is not produced during the decomposition of water. I may mention this additional consideration that, with respect

to hydrogen peroxide, we may look for its effecting still further substitutions of hydrogen by means of which we may expect to obtain still more highly oxidised water compounds, such as H_2O_3 and H_2O_4 . These Schönbein and Bunsen have long been seeking, and Berthelot is investigating them at present. It is probable, however, that the reaction will stop at the last compound, because we find that, in a number of cases, the addition of four atoms of oxygen seems to form a limit. Thus, OsO_4 , KClO_4 , KMnO_4 , K_2SO_4 , Na_3PO_4 , and such like, represent the highest grades of oxidation.¹

As for the last forty years, from the times of Berzelius, Dumas, Liebig, Gerhardt, Williamson, Frankland, Kolbe, Kekulé, and Butleroff, most theoretical generalisations have centred round organic or carbon compounds, so we will, for the sake of brevity, leave out the discussion of ammonia derivatives, notwithstanding their simplicity with respect to the doctrine of substitutions; we will dwell more especially on its application to carbon compounds, starting from methane, CH_4 , as the simplest of the hydrocarbons, containing in its molecule one atom of carbon. According to the principles enumerated we may derive from CH_4 every combination of the form CH_3X , CH_2X_2 , CHX_3 , and CX_4 , in which X is an element, or radicle, equivalent to hydrogen—that is to say, competent to take its place or to combine with it. Such are the chlorine substitutes mentioned already, such is wood-spirit, $\text{CH}_3(\text{OH})$, in which X is represented by the residue of water, and such are numerous other carbon derivatives. If we continue, with the aid of hydroxyl, further substitutions of the hydrogen of methane we shall obtain successively $\text{CH}_2(\text{OH})_2$, $\text{CH}(\text{OH})_3$, and $\text{C}(\text{OH})_4$. But if, in proceeding thus, we bear in mind that $\text{CH}_3(\text{OH})$ contains two hydroxyls in the same form as hydrogen peroxide, H_2O_2 or $(\text{OH})_2$, contains them—and moreover not only in one molecule, but together, attached to one and the same atom of carbon—so here we must look for the same decomposition as that which we find in hydrogen peroxide, and accompanied also by the formation of water as an independently existing molecule; therefore $\text{CH}_2(\text{OH})_2$ should yield, as it actually does, immediately water and the oxide of methylene, CH_2O , which is methane with

¹ Because more than four atoms of hydrogen never unite with one atom of the elements, and because the hydrogen compounds (*e.g.* HCl , H_2S , H_3P , H_4Si) always form their highest oxides with four atoms of oxygen, and as the highest forms of oxides (OsO_4 , RuO_4) also contain four of oxygen, and eight groups of the periodic system, corresponding to the highest basic oxides R_2O , RO , R_2O_3 , RO_2 , R_2O_5 , RO_3 , R_2O_7 , and RO_4 , imply the above relationship, and because of the nearest analogues among the elements—such as Mg, Zn, Cd, and Hg; or Cr, Mo, W, and U; or Si, Ge, Sn, and Pt; or F, Cl, Br, and I, and so forth—not more than four are known, it seems to me that in these relationships there lies a deep interest and meaning with regard to chemical mechanics. But because, to my imagination, the idea of unity of design in Nature, either acting in complex celestial systems or among chemical molecules, is very attractive, especially because the atomic teaching at once acquires its true meaning, I will recall the following facts relating to the solar system. There are eight major planets, of which the four inner ones are not only separated from the four outer by asteroids, but differ from them in many respects, as, for example, in the smallness of their diameters and their greater density. Saturn with his ring has eight satellites, Jupiter and Uranus have each four. It is evident that in the solar systems also we meet with these higher numbers four and eight which appear in the combination of chemical molecules.

oxygen substituted for two atoms of hydrogen. Exactly in the same manner out of $\text{CH}(\text{OH})_3$ are formed water and formic acid, $\text{CHO}(\text{OH})$, and out of $\text{C}(\text{OH})_4$ is produced water and carbonic acid, or directly carbonic anhydride, CO_2 , which will therefore be nothing else than methane with the double replacement of pairs of hydrogen by oxygen. As nothing leads to the supposition that the four atoms of hydrogen in methane differ one from the other, so it does not matter by what means we obtain any one of the combinations indicated—they will be identical; that is to say, there will be no case of actual isomerism, although there may easily be such cases of isomerism as have been distinguished by the term metamerism.

Formic acid, for example, has two atoms of hydrogen, one attached to the carbon left from the methane, and the other attached to the oxygen which has entered in the form of hydroxyl, and if one of them be replaced by some substance X it is evident that we shall obtain substances of the same composition, but of different construction, or of different orders of movement among the molecules, and therefore endowed with other properties and reactions. If X be methyl, CH_3 —that is to say, a group capable of replacing hydrogen because it is actually contained with hydrogen in methane itself—then by substituting this group for the original hydrogen we obtain acetic acid, $\text{CCH}_3\text{O}(\text{OH})$, out of formic, and by substitution of the hydrogen in its oxide or hydroxyl we obtain methyl formate, $\text{CHO}(\text{OCH}_3)$. These substances differ so much from each other physically and chemically that at first sight it is hardly possible to admit that they contain the same atoms in identically the same proportions. Acetic acid, for example, boils at a higher temperature than water, and has a higher specific gravity than it, whilst its metameride, methyl formate, is lighter than water, and boils at 30° —that is to say, it evaporates very easily.

Let us now turn to carbon compounds containing two atoms of carbon to the molecule, as in acetic acid, and proceed to evolve them from methane by the principle of substitution. This principle declares at once that methane can only be split up in the four following ways:—

1. Into a group CH_3 equivalent with H. Let us call changes of this nature methylation.
2. Into a group CH_2 and H_2 . We will call this order of substitutions methylenation.
3. Into CH and H_3 , which commutations we will call acetylenation.
4. Into C and H_4 , which may be called carbonation.

It is evident that hydrocarbon compounds containing two atoms of carbon can only proceed from methane, CH_4 , which contains four atoms of hydrogen by the first three methods of substitution; carbonation would yield free carbon if it could take place directly, and if the molecule of free carbon which is in reality very complex, that is to say strongly polyatomic, as I have long since been proving by various means—could contain only C_2 like the molecules O_2 , H_2 , N_2 , and so on.

By methylation we should evidently obtain from marsh gas, ethane, $\text{CH}_3\text{CH}_3 = \text{C}_2\text{H}_6$.

By methylenation—that is, by substituting group CH_2 for H_2 —methane forms ethylene, $\text{CH}_2\text{CH}_2 = \text{C}_2\text{H}_4$.

By acetylenation—that is, by substituting three atoms of hydrogen, H_3 , in methane—by the remnant CH , we get acetylene, $CHCH = C_2H_2$.

If we have applied the principles of Newton correctly, there should not be any other hydrocarbons containing two atoms of carbon in the molecule. All these combinations have long been known, and in each of them we can not only produce those substitutions of which an example has been given in the case of methane, but also all the phases of other substitutions, as we shall find from a few more instances; by the aid of which I trust that I shall be able to show the great complexity of those derivatives which, on the principle of substitution, can be obtained from each hydrocarbon. Let us content ourselves with the case of ethane, CH_3CH_3 , and the substitution of the hydrogen by hydroxyl. The following are the possible changes:—

1. $CH_3CH_2(OH)$: this is nothing more than spirit of wine, or ethyl alcohol, $C_2H_5(OH)$ or C_2H_6O .

2. $CH_2(OH)CH_2(OH)$: this is the glycol of Würtz, which has shed so much light on the history of alcohol. Its isomeride may be $CH_3CH(OH)_2$, but as we have seen in the case of $CH(OH)_3$, it decomposes, giving off water, and forming aldehyde, CH_3CHO , a substance capable of yielding alcohol by uniting with hydrogen, and of yielding acetic acid by uniting with oxygen.

If glycol, $CH_2(OH)CH_2(OH)$, loses its water, it may be seen at once that it will not now yield aldehyde, CH_3CHO , but its isomeride, $\overset{CH_3CH_2}{O}$, the oxide of ethylene. I have here indicated in a special manner the oxygen which has taken the place of two atoms of the hydrogen of ethane taken from different atoms of the carbon.

3. $CH_3C(OH)_3$ decomposed as $CH(OH)_3$, forming water and acetic acid, $CH_3CO(OH)$. It is evident that this acid is nothing else than formic acid, $CHO(OH)$, with its hydrogen replaced by methyl. Without examining further the vast number of possible derivatives, I will direct your attention to the circumstance that in dissolving acetic acid in water we obtain the maximum contraction and the greatest viscosity when to the molecule $CH_3CO(OH)$ is added a molecule of water, which is the proportion which would form the hydrate $CH_3C(OH)_3$. It is probable that the doubling of the molecule of acetic acid at temperatures approaching its boiling-point has some connection with this power of uniting with one molecule of water.

4. $CH_2(OH)C(OH)_3$ is evidently an alcoholic acid, and indeed this compound, after losing water, answers to glycolic acid, $CH_2(OH)CO(OH)$. Without investigating all the possible isomerides, we will note only that the hydrate $CH(OH)_2CH(OH)_2$ has the same composition as $CH_2(OH)C(OH)_3$, and although corresponding to glycol, and being a symmetrical substance, it becomes, on parting with its water, the aldehyde of oxalic acid, or the glyoxal of Debus, $CHOCHO$.

5. $CH(OH)_2C(OH)_3$, from the tendency of all the preceding, corresponds with glyoxylic acid, an aldehyde acid, $CHOCO(OH)$, because the group $CO(OH)$, or carboxyl, enters into the compositions of organic acids, and the group CHO defines the aldehyde function.

6. $C(OH)_3C(OH)_3$ through the loss of $2H_2O$ yields the bibasic oxalic acid

$\text{CO}(\text{OH})\text{CO}(\text{OH})$, which generally crystallises with $2\text{H}_2\text{O}$, following thus the normal type of hydration characteristic of ethane.²

Thus, by applying the principle of substitution, we can, in the simplest manner, derive not only every kind of hydrocarbon compound, such as the alcohols, the aldehyde-alcohols, aldehydes, alcohol-acids, and the acids, but also combinations analogous to hydrated crystals which usually are disregarded.

But even those unsaturated substances, of which ethylene, CH_2CH_2 , and acetylene, CHCH , are types, may be evolved with equal simplicity. With respect to the phenomena of isomerism, there are many possibilities among the hydrocarbon compounds containing two atoms of carbon, and without going into details it will be sufficient to indicate that the following formulæ, though not identical, will be isomeric substantially among themselves:— CH_3CHX_2 and $\text{CH}_2\text{XCH}_2\text{X}$, although both contain $\text{C}_2\text{H}_4\text{X}_2$; or CH_2CX_2 and CHXCHX , although both contain $\text{C}_2\text{H}_2\text{X}_2$, if by X we indicate chlorine or generally an element capable of replacing one atom of hydrogen, or capable of uniting with it. To isomerism of this kind belongs the case of aldehyde and the oxide of ethylene, to which we have already referred, because both have the composition $\text{C}_2\text{H}_4\text{O}$.

What I have said appears to me sufficient to show that the principle of substitution adequately explains the composition, the isomerism, and all the diversity of combination of the hydrocarbons, and I shall limit the further development of these views to preparing a complete list of every possible hydrocarbon compound containing three atoms of carbon in the molecule. There are eight in all, of which only five are known at present.³

Among those possible for C_3H_6 there should be two isomerides, propylene and trimethylene, and they are both already known. For C_3H_4 there should be three isomerides: allylene and allene are known, but the third has not yet been discovered; and for C_3H_2 there should be two isomerides, though

² One more isomeride, $\text{CH}_2\text{CH}(\text{OH})$, is possible—that is, secondary vinyl alcohol, which is related to ethylene, CH_2CH_2 , but derived by the principle of substitution from CH_4 . Other isomerides, of the composition $\text{C}_2\text{H}_4\text{O}$, such, for example, as $\text{CCH}_3(\text{OH})$, are impossible, because it would correspond with the hydrocarbon $\text{CHCH}_3 = \text{C}_2\text{H}_4$, which is isomeric with ethylene, and it cannot be derived from methane. If such an isomeride existed it would be derived from CH_2 , but such products are, up to the present, unknown. In such cases the insufficiency of the points of departure of the statical structural teaching is shown. It first admits constant atomicity and then rejects it, the facts serving to establish either one or the other view; and therefore it seems to me that we must come to the conclusion that the structural method of reasoning, having done a service to science, has outlived the age, and must be regenerated, as in their time was the teaching of the electro-chemists, the radicalists, and the adherents of the doctrine of types. As we cannot now lean on the views above stated, it is time to abandon the structural theory. They will all be united in chemical mechanics, and the principle of substitution must be looked on only as a preparation for the coming epoch in chemistry, where such cases as the isomerism of fumaric and maleic acids, when explained dynamically, as proposed by Le Bel and Van't Hoff, may yield points of departure.

³ Conceding variable atomicity, the structuralists must expect an incomparably larger number of isomerides, and they cannot now decline to acknowledge the change of atomicity, were it only for the examples HgCl and HgCl_2 , CO and CO_2 , PCl_3 and PCl_5 .

neither of them is known as yet. Their composition and structure is easily deduced from ethane, ethylene, and acetylene, by methylation, by methylenation, by acetylenation and by carbonation.

1. $C_3H_8 = CH_3CH_2CH_3$ out of CH_3CH_3 by methylation. This hydrocarbon is named propane.

2. $C_3H_6 = CH_3CHCH_2$ out of CH_3CH_3 by methylenation. This substance is propylene.

3. $C_3H_6 = CH_2CH_2CH_2$ out of CH_3CH_3 by methylenation. This substance is trimethylene.

4. $C_3H_4 = CH_3CCH$ out of CH_3CH_3 by acetylenation or from $CHCH$ by methylation. This hydrocarbon is named allylene.

5. $C_3H_4 = \begin{smallmatrix} CHCH \\ CH_2 \end{smallmatrix}$ out of CH_3CH_3 by acetylenation, or from CH_2CH_2 by methylenation, because $\begin{smallmatrix} CH_3CH \\ CH \end{smallmatrix} = \begin{smallmatrix} CHCH \\ CH_2 \end{smallmatrix}$. This body is as yet unknown.

6. $C_3H_4 = CH_2CCH_2$ out of CH_2CH_2 by methylenation. This hydrocarbon is named allene, or iso-allylene.

7. $C_3H_2 = \begin{smallmatrix} CHCH \\ C \end{smallmatrix}$ out of CH_3CH_3 by symmetrical carbonation, or out of CH_2CH_2 by acetylenation. This compound is unknown.

8. $C_3H_2 = \begin{smallmatrix} CC \\ CH_2 \end{smallmatrix}$ out of CH_3CH_3 by carbonation, or out of $CHCH$ by methylenation. This compound is unknown.

If we bear in mind that for each hydrocarbon serving as a type in the above tables there are a number of corresponding derivatives, and that every compound obtained may, by further methylation, methylenation, acetylenation, and carbonation, produce new hydrocarbons, and these may be followed by a numerous suite of derivatives and an immense number of isomeric substances, it is possible to understand the limitless number of carbon compounds, although they all have the one substance, methane, for their origin. The number of substances is so enormous that it is no longer a question of enlarging the possibilities of discovery, but rather of finding some means of testing them analogous to the well-known two which for a long time have served as gauges for all carbon compounds.

I refer to the law of even numbers and to that of limits, the first enunciated by Gerhardt some forty years ago, with respect to hydrocarbons, namely, that their molecules always contain an even number of atoms of hydrogen. But by the method which I have used of deriving all the hydrocarbons from methane, CH_4 , this law may be deduced as a direct consequence of the principle of substitutions. Accordingly, in methylation, CH_3 takes the place of H, and therefore CH_2 is added. In methylenation the number of atoms of hydrogen remains unchanged, and at each acetylenation it is reduced by two, and in carbonation by four, atoms—that is to say, an even number of atoms of hydrogen is always added or removed. And because the fundamental hydrocarbon, methane, CH_4 , contains an even number of atoms of hydrogen, therefore all its derivative hydrocarbons will also contain even numbers of hydrogen, and this constitutes the law of even numbers.

The principle of substitutions explains with equal simplicity the conception of the limiting compositions of hydrocarbons C_nH_{n+2} , which I derived, in

1861,⁴ in an empirical manner from accumulated materials available at that time, and on the basis of the limits to combinations worked out by Dr. Frankland for other elements.

Of all the various substitutions the highest proportion of hydrogen is yielded by methylation, because in that operation alone does the quantity of hydrogen increase; therefore, taking methane as a point of departure, if we imagine methylation effected $(n - 1)$ times we obtain hydrocarbon compounds containing the highest quantities of hydrogen. It is evident that they will contain $\text{CH}_4 + (n - 1)\text{CH}_2$, or $\text{C}_n\text{H}_{2n+2}$, because methylation leads to the addition of CH_2 to the compound.

It will thus be seen that by the principle of substitution—that is to say, by the third law of Newton—we are able to deduce, in the simplest manner, not only the individual composition, the isomerism, and relations of substances, but also the general laws which govern their most complex combinations, without having recourse either to statical constructions, to the definition of atomicities, to the exclusion of free affinities, or to the recognition of those single, double, or treble bonds which are so indispensable to structuralists in the explanation of the composition and construction of hydrocarbon compounds. And yet, by the application of the dynamical principles of Newton, we can attain to that chief and fundamental object, the comprehension of isomerism in hydrocarbon compounds, and the forecasting of the existence of combinations as yet unknown, by which the edifice raised by structural teaching is strengthened and supported. Besides—and I count this for a circumstance of special importance—the process which I advocate will make no difference in those special cases which have been already so well worked out, such as, for example, the isomerism of the hydrocarbons and alcohols, even to the extent of not interfering with the nomenclature which has been adopted, and the structural system will retain all the glory of having worked up, in a thoroughly scientific manner, the store of information which Gerhardt had accumulated about the middle of the fifties, and the still higher glory of establishing the rational synthesis of organic substances. Nothing will be lost to the structural doctrine except its statical origin; and as soon as it will embrace the dynamic principles of Newton, and suffer itself to be guided by them, I believe that we shall attain for chemistry that unity of principle which is now wanting. Many an adept will be attracted to that brilliant and fascinating enterprise, the penetration into the unseen world of the kinetic relations of atoms, to the study of which the last twenty-five years have contributed so much labour and such high inventive faculties.

D'Alembert found in mechanics that if inertia be taken to represent force, dynamic equations may be applied to statical questions, which are thereby rendered more simple and more easily understood.

The structural doctrine in chemistry has unconsciously followed the same course, and therefore its terms are easily adopted; they may retain their present forms provided that a truly dynamical—that is to say, Newtonian—meaning be ascribed to them.

Before finishing my task and demonstrating the possibility of adapting

⁴ 'Essai d'une théorie sur les limites des combinaisons organiques,' par D. Mendeléeff, 2/11 août 1861, *Bulletin de l'Académie i. d. Sc. de St. Pétersbourg*, t. v.

structural doctrines to the dynamics of Newton, I consider it indispensable to touch on one question which naturally arises, and which I have heard discussed more than once. If bromine, the atom of which is eighty times heavier than that of hydrogen, takes the place of hydrogen, it would seem that the whole system of dynamic equilibrium must be destroyed.

Without entering into the minute analysis of this question, I think it will be sufficient to examine it by the light of two well-known phenomena, one of which will be found in the department of chemistry and the other in that of celestial mechanics, and both will serve to demonstrate the existence of that unity in the plan of creation which is a consequence of the Newtonian doctrines. Experiments demonstrate that when a heavy element is substituted for a light one in a chemical compound—for example, for magnesium, in the oxide of that metal, an atom of mercury, which is $8\frac{1}{2}$ times heavier—the chief chemical characteristics or properties are generally, though not always, preserved.

The substitution of silver for hydrogen, than which it is 108 times heavier, does not affect all the properties of the substance, though it does some. Therefore chemical substitutions of this kind—the substitution of light for heavy atoms—need not necessarily entail changes in the original equilibrium; and this point is still further elucidated by the consideration that the periodic law indicates the degree of influence of an increment of weight in the atom as affecting the possible equilibria, and also what degree of increase in the weight of the atoms reproduces some, though not all, of the properties of the substance.

This tendency to repetition—these periods—may be likened to those annual or diurnal periods with which we are so familiar on the earth. Days and years follow each other, but, as they do so, many things change; and in like manner chemical evolutions, changes in the masses of the elements, permit of much remaining undisturbed, though many properties undergo alteration. The system is maintained according to the laws of conservation in nature, but the motions are altered in consequence of the change of parts.

Next, let us take an astronomical case—such, for example, as the earth and the moon—and let us imagine that the mass of the latter is constantly increasing. The question is, what will then occur? The path of the moon in space is a wave-line similar to that which geometricians have named epicycloidal, or the locus of a point in a circle rolling round another circle. But in consequence of the influence of the moon it is evident that the path of the earth itself cannot be a geometric ellipse, even supposing the sun to be immovably fixed; it must be an epicycloidal curve, though not very far removed from the true ellipse—that is to say, it will be impressed with but faint undulations. It is only the common centre of gravity of the earth and the moon which describes a true ellipse round the sun. If the moon were to increase, the relative undulations of the earth's path would increase in amplitude, those of the moon would also change, and when the mass of the moon had increased to an equality with that of the earth, the path would consist of epicycloidal curves crossing each other, and having opposite phases. But a similar relation exists between the sun and the earth, because the former is also moving in space. We may apply these views to the world of atoms, and

suppose that in their movements, when heavy ones take the place of those that are lighter, similar changes take place, provided that the system or the molecule is preserved throughout the change.

It seems probable that in the heavenly systems, during incalculable astronomical periods, changes have taken place and are still going on similar to those which pass rapidly before our eyes during the chemical reaction of molecules, and the progress of molecular mechanics may—we hope will—in course of time permit us to explain those changes in the stellar world which have more than once been noticed by astronomers, and which are now so carefully studied. A coming Newton will discover the laws of these changes. Those laws, when applied to chemistry, may exhibit peculiarities, but these will certainly be mere variations on the grand harmonious theme which reigns in nature. The discovery of the laws which produce this harmony in chemical evolution will only be possible, it seems to me, under the banner of Newtonian dynamics, which has so long waved over the domains of mechanics, astronomy, and physics. In calling chemists to take their stand under its peaceful and catholic shadow I imagine that I am aiding in establishing that scientific union which the managers of the Royal Institution wish to effect, who have shown their desire to do so by the flattering invitation which has given me—a Russian—the opportunity of laying before the countrymen of Newton an attempt to apply to chemistry one of his immortal principles.

APPENDIX II.

THE PERIODIC LAW OF THE CHEMICAL ELEMENTS.

BY PROFESSOR MENDELÉEFF.

FARADAY LECTURE DELIVERED BEFORE THE FELLOWS OF
THE CHEMICAL SOCIETY IN THE THEATRE OF THE ROYAL INSTITUTION,
ON TUESDAY, JUNE 4, 1889.

THE high honour bestowed by the Chemical Society in inviting me to pay a tribute to the world-famed name of Faraday by delivering this lecture has induced me to take for its subject the Periodic Law of the Elements—this being a generalisation in chemistry which has of late attracted much attention.

While science is pursuing a steady onward movement, it is convenient from time to time to cast a glance back on the route already traversed, and especially to consider the new conceptions which aim at discovering the general meaning of the stock of facts accumulated from day to day in our laboratories. Owing to the possession of laboratories, modern science now bears a new character, quite unknown, not only to antiquity, but even to the preceding century. Bacon's and Descartes' idea of submitting the mechanism of science simultaneously to experiment and reasoning has been fully realised in the case of chemistry, it having become not only possible but always customary to experiment. Under the all-penetrating control of experiment, a new theory, even if crude, is quickly strengthened, provided it be founded on a sufficient basis; the asperities are removed, it is amended by degrees, and soon loses the phantom light of a shadowy form or of one founded on mere prejudice; it is able to lead to logical conclusions, and to submit to experimental proof. Willingly or not, in science we all must submit not to what seems to us attractive from one point of view or from another, but to what represents an agreement between theory and experiment; in other words, to demonstrated generalisation and to the approved experiment. Is it long since many refused to accept the generalisations involved in the law of Avogadro and Ampère, so widely extended by Gerhardt? We still may hear the voices of its opponents; they enjoy perfect freedom, but vainly will their voices rise so long as they do not use the language of demonstrated facts.

The striking observations with the spectroscope which have permitted us to analyse the chemical constitution of distant worlds, seemed, at first, applicable to the task of determining the nature of the atoms themselves; but the working out of the idea in the laboratory soon demonstrated that the characters of spectra are determined, not directly by the atoms, but by the molecules into which the atoms are packed; and so it became evident that more verified facts must be collected before it will be possible to formulate new generalisations capable of taking their place beside those ordinary ones based upon the conception of simple substances and atoms. But as the shade of the leaves and roots of living plants, together with the relics of a decayed vegetation, favour the growth of the seedling and serve to promote its luxurious development, in like manner sound generalisations—together with the relics of those which have proved to be untenable—promote scientific productivity, and ensure the luxurious growth of science under the influence of rays emanating from the centres of scientific energy. Such centres are scientific associations and societies. Before one of the oldest and most powerful of these I am about to take the liberty of passing in review the 20 years' life of a generalisation which is known under the name of the Periodic Law. It was in March 1869 that I ventured to lay before the then youthful Russian Chemical Society the ideas upon the same subject which I had expressed in my just written 'Principles of Chemistry.'

Without entering into details, I will give the conclusions I then arrived at in the very words I used:—

'1. The elements, if arranged according to their atomic weights, exhibit an evident *periodicity* of properties.

'2. Elements which are similar as regards their chemical properties have atomic weights which are either of nearly the same value (*e.g.* platinum, iridium, osmium) or which increase regularly (*e.g.* potassium, rubidium, caesium).

'3. The arrangement of the elements, or of groups of elements, in the order of their atomic weights, corresponds to their so-called *valencies* as well as, to some extent, to their distinctive chemical properties—as is apparent, among other series, in that of lithium, beryllium, barium, carbon, nitrogen, oxygen, and iron.

'4. The elements which are the most widely diffused have *small* atomic weights.

'5. The *magnitude* of the atomic weight determines the character of the element, just as the magnitude of the molecule determines the character of a compound.

'6. We must expect the discovery of many yet *unknown* elements—for example, elements analogous to aluminium and silicon, whose atomic weight would be between 65 and 75.

'7. The atomic weight of an element may sometimes be amended by a knowledge of those of the contiguous elements. Thus, the atomic weight of tellurium must lie between 123 and 126, and cannot be 128.

'8. Certain characteristic properties of the elements can be foretold from their atomic weights.

'The aim of this communication will be fully attained if I succeed in drawing the attention of investigators to those relations which exist between the atomic weights of dissimilar elements, which, as far as I know, have hitherto been almost completely neglected. I believe that the solution of some of the most important problems of our science lies in researches of this kind.'

To-day, twenty years after the above conclusions were formulated, they may still be considered as expressing the essence of the now well-known periodic law.

Reverting to the epoch terminating with the sixties, it is proper to indicate three series of data without the knowledge of which the periodic law could not have been discovered, and which rendered its appearance natural and intelligible.

In the first place, it was at that time that the numerical value of atomic weights became definitely known. Ten years earlier such knowledge did not exist, as may be gathered from the fact that in 1860 chemists from all parts of the world met at Karlsruhe in order to come to some agreement, if not with respect to views relating to atoms, at any rate as regards their definite representation. Many of those present probably remember how vain were the hopes of coming to an understanding, and how much ground was gained at that Congress by the followers of the unitary theory so brilliantly represented by Cannizzaro. I vividly remember the impression produced by his speeches, which admitted of no compromise, and seemed to advocate truth itself, based on the conceptions of Avogadro, Gerhardt, and Regnault, which at that time were far from being generally recognised. And though no understanding could be arrived at, yet the objects of the meeting were attained, for the ideas of Cannizzaro proved, after a few years, to be the only ones which could stand criticism, and which represented an atom as 'the smallest portion of an element which enters into a molecule of its compound.' Only such real atomic weights—not conventional ones—could afford a basis for generalisation. It is sufficient, by way of example, to indicate the following cases in which the relation is seen at once and is perfectly clear:—

K = 39	Rb = 85	Cs = 133
Ca = 40	Sr = 87	Ba = 137

whereas with the equivalents then in use—

K = 39	Rb = 85	Cs = 133
Ca = 20	Sr = 43·5	Ba = 68·5

the consecutiveness of change in atomic weight, which with the true values is so evident, completely disappears.

Secondly, it had become evident during the period 1860-70, and even during the preceding decade, that the relations between the atomic weights of analogous elements were governed by some general and simple laws. Cooke, Cremers, Gladstone, Gmelin, Lenssen, Pottenkofer, and especially Dumas, had already established many facts bearing on that view. Thus Dumas compared the following groups of analogous elements with organic radicles:—

Diff.		Diff.		Diff.		Diff.	
	Mg = 12		P = 31		O = 8		
Li = 7	} 8		} 44		} 8		
Na = 23							
	Ca = 20		As = 75		S = 16		
} 16	} 3 × 8		} 44		} 3 × 8		
	Sr = 44		Sb = 119		Se = 40		
	} 3 × 8		} 2 × 44		} 3 × 8		
K = 39							
	Ba = 68		Bi = 207		Te = 64		

and pointed out some really striking relationships, such as the following :—

$$F = 19.$$

$$Cl = 35.5 = 19 + 16.5.$$

$$Br = 80 = 19 + 2 \times 16.5 + 28.$$

$$I = 127 = 2 \times 19 + 2 \times 16.5 + 2 \times 28.$$

A. Strecker, in his work 'Theorien und Experimente zur Bestimmung der Atomgewichte der Elemente' (Braunschweig, 1859), after summarising the data relating to the subject, and pointing out the remarkable series of equivalents—

$$\begin{array}{cccccc} Cr = 26.2 & Mn = 27.6 & Fe = 28 & Ni = 29 & Co = 30 & Cu = 31.7 \\ & & Zn = 32.5 & & & \end{array}$$

remarks that : ' It is hardly probable that all the above-mentioned relations between the atomic weights (or equivalents) of chemically analogous elements are merely accidental. We must, however, leave to the future the discovery of the *law* of the relations which appears in these figures.' ¹

In such attempts at arrangement and in such views are to be recognised the real forerunners of the periodic law; the ground was prepared for it between 1860 and 1870, and that it was not expressed in a determinate form before the end of the decade may, I suppose, be ascribed to the fact that only analogous elements had been compared. The idea of seeking for a relation between the atomic weights of all the elements was foreign to the ideas then current, so that neither the *vis tellurique* of De Chancourtois, nor the *law of octaves* of Newlands, could secure anybody's attention. And yet both De Chancourtois and Newlands, like Dumas and Strecker, more than Lenssen and Pettenkofer, had made an approach to the periodic law and had discovered its germs. The solution of the problem advanced but slowly, because the facts, and not the law, stood foremost in all attempts; and the law could not awaken a general interest so long as elements, having no apparent connection with each other, were included in the same octave, as for example :—

1st octave of									
Newlands..	H	F	Cl	Co & Ni	Br	Pd	I	Pt & Ir	
7th Ditto....	O	S	Fe	Se	Rh & Ru	Te	Au	Os or Th	

Analogies of the above order seemed quite accidental, and the more so as the octave contained occasionally ten elements instead of eight, and when two

¹ 'Es ist wohl kaum anzunehmen, dass alle im Vorhergehenden hervorgehobenen Beziehungen zwischen den Atomgewichten (oder Aequivalenten) in chemischen Verhältnissen einander ähnliche Elemente bloss zufällig sind. Die Auffindung der in diesen Zahlen *gesetzlichen* Beziehungen müssen wir jedoch der Zukunft überlassen.'

such elements as Ba and V, Co and Ni, or Rh and Ru, occupied one place in the octave.² Nevertheless, the fruit was ripening, and I now see clearly that Strecker, De Chancourtois, and Newlands stood foremost in the way towards the discovery of the periodic law, and that they merely wanted the boldness necessary to place the whole question at such a height that its reflection on the facts could be clearly seen.

A third circumstance which revealed the periodicity of chemical elements was the accumulation, by the end of the sixties, of new information respecting the rare elements, disclosing their many-sided relations to the other elements and to each other. The researches of Marignac on niobium, and those of Roscoe on vanadium, were of special moment. The striking analogies between vanadium and phosphorus on the one hand, and between vanadium and chromium on the other, which became so apparent in the investigations connected with that element, naturally induced the comparison of V = 51 with Cr = 52, Nb = 94 with Mo = 96, and Ta = 192 with W = 194; while, on the other hand, P = 31 could be compared with S = 32, As = 75 with Se = 79, and Sb = 120 with Te = 125. From such approximations there remained but one step to the discovery of the law of periodicity.

The law of periodicity was thus a direct outcome of the stock of generalisations and established facts which had accumulated by the end of the decade 1860-1870: it is an embodiment of those data in a more or less systematic expression. Where, then, lies the secret of the special importance which has since been attached to the periodic law, and has raised it to the position of a generalisation which has already given to chemistry unexpected aid, and which promises to be far more fruitful in the future and to impress upon several branches of chemical research a peculiar and original stamp? The remaining part of my communication will be an attempt to answer this question.

In the first place we have the circumstance that, as soon as the law made its appearance, it demanded a revision of many facts which were considered by chemists as fully established by existing experience. I shall return, later on, briefly to this subject, but I wish now to remind you that the periodic law, by insisting on the necessity for a revision of supposed facts, exposed itself at once to destruction in its very origin. Its first requirements, however, have been almost entirely satisfied during the last 20 years; the supposed facts have yielded to the law, thus proving that the law itself was a legitimate induction from the verified facts. But our inductions from data have often to do with such details of a science so rich in facts, that only generalisations which cover a wide range of important phenomena can attract general attention. What were the regions touched on by the periodic law? This is what we shall now consider.

The most important point to notice is, that periodic functions, used for the purpose of expressing changes which are dependent on variations of time and space, have been long known. They are familiar to the mind when we have to deal with motion in closed cycles, or with any kind of deviation from

² To judge from J. A. R. Newlands's work, *On the Discovery of the Periodic Law*, London, 1884, p. 149; 'On the Law of Octaves' (from the *Chemical News*, 12, 83, August 18, 1865).

a stable position, such as occurs in pendulum-oscillations. A like periodic function became evident in the case of the elements, depending on the mass of the atom. The primary conception of the masses of bodies, or of the masses of atoms, belongs to a category which the present state of science forbids us to discuss, because as yet we have no means of dissecting or analysing the conception. All that was known of functions dependent on masses derived its origin from Galileo and Newton, and indicated that such functions either decrease or increase with the increase of mass, like the attraction of celestial bodies. The numerical expression of the phenomena was always found to be proportional to the mass, and in no case was an increase of mass followed by a recurrence of properties such as is disclosed by the periodic law of the elements. This constituted such a novelty in the study of the phenomena of nature that, although it did not lift the veil which conceals the true conception of mass, it nevertheless indicated that the explanation of that conception must be searched for in the masses of the atoms; the more so, as all masses are nothing but aggregations, or additions, of chemical atoms which would be best described as chemical individuals. Let me remark, by the way, that though the Latin word 'individual' is merely a translation of the Greek word 'atom,' nevertheless history and custom have drawn so sharp a distinction between the two words, and the present chemical conception of atoms is nearer to that defined by the Latin word than by the Greek, although this latter also has acquired a special meaning which was unknown to the classics. The periodic law has shown that our chemical individuals display a harmonic periodicity of properties, dependent on their masses. Now natural science has long been accustomed to deal with periodicities observed in nature, to seize them with the vice of mathematical analysis, to submit them to the rasp of experiment. And these instruments of scientific thought would surely, long since, have mastered the problem connected with the chemical elements, were it not for a new feature which was brought to light by the periodic law, and which gave a peculiar and original character to the periodic function.


If we mark on an axis of abscissæ a series of lengths proportional to angles, and trace ordinates which are proportional to sines or other trigonometrical functions, we get periodic curves of a harmonic character. So it might seem, at first sight, that with the increase of atomic weights the function of the properties of the elements should also vary in the same harmonious way. But in this case there is no such continuous change as in the curves just referred to, because the periods do not contain the infinite number of points constituting a curve, but a *finite* number only of such points. An example will better illustrate this view. The atomic weights—

Ag = 108	Cd = 112	In = 113	Sn = 118	Sb = 120
	Te = 125	I = 127		

steadily increase, and their increase is accompanied by a modification of many properties which constitutes the essence of the periodic law. Thus, for example, the densities of the above elements decrease steadily, being respectively—

10.5	8.6	7.4	7.2	6.7	6.4	4.9
------	-----	-----	-----	-----	-----	-----


while their oxides contain an increasing quantity of oxygen—



But to connect by a curve the summits of the ordinates expressing any of these properties would involve the rejection of Dalton's law of multiple proportions. Not only are there no intermediate elements between silver, which gives AgCl , and cadmium, which gives CdCl_2 , but, according to the very essence of the periodic law, there can be none; in fact a uniform curve would be inapplicable in such a case, as it would lead us to expect elements possessed of special properties at any point of the curve. The periods of the elements have thus a character very different from those which are so simply represented by geometers. They correspond to points, to numbers, to sudden changes of the masses, and not to a continuous evolution. In these sudden changes destitute of intermediate steps or positions, in the absence of elements intermediate between, say, silver and cadmium, or aluminium and silicon, we must recognise a problem to which no direct application of the analysis of the infinitely small can be made. Therefore, neither the trigonometrical functions proposed by Ridberg and Flavitzky, nor the pendulum-oscillations suggested by Crookes, nor the cubical curves of the Rev. Mr. Haughton, which have been proposed for expressing the periodic law, from the nature of the case, can represent the periods of the chemical elements. If geometrical analysis is to be applied to this subject, it will require to be modified in a special manner. It must find the means of representing in a special way, not only such long periods as that comprising,

K Ca Sc Ti V Cr Mn Fe Co Ni Cu Zn Ga Ge As Se Br,

but short periods like the following :—



In the theory of numbers only do we find problems analogous to ours, and two attempts at expressing the atomic weights of the elements by algebraic formulæ seem to be deserving of attention, although neither of them can be considered as a complete theory, nor as promising finally to solve the problem of the periodic law. The attempt of E. J. Mills (1886) does not even aspire to attain this end. He considers that all atomic weights can be expressed by a logarithmic function,

$$15(n - 0.9375^t),$$

in which the variables n and t are *whole numbers*. Thus, for oxygen, $n = 2$, and $t = 1$, whence its atomic weight is $= 15.94$; in the case of chlorine, bromine, and iodine, n has respective values of 3, 6, and 9, whilst $t = 7$, 6, and 9; in the case of potassium, rubidium, and caesium, $n = 4$, 6, and 9, and $t = 14$, 18, and 20.

Another attempt was made in 1888 by B. N. Tchitchérin. Its author places the problem of the periodic law in the first rank, but as yet he has investigated the alkali metals only. Tchitchérin first noticed the simple

relations existing between the atomic volumes of all alkali metals: they can be expressed, according to his views, by the formula

$$A(2 - 0.00535An),$$

where A is the atomic weight, and n is equal to 8 for lithium and sodium, to 4 for potassium, to 3 for rubidium, and to 2 for cæsium. If n remained equal to 8 during the increase of A , then the volume would become zero at $A = 46\frac{1}{2}$, and it would reach its maximum at $A = 23\frac{1}{2}$. The close approximation of the number $46\frac{1}{2}$ to the differences between the atomic weights of analogous elements (such as Cs - Rb, I - Br, and so on); the close correspondence of the number $23\frac{1}{2}$ to the atomic weight of sodium; the fact of n being necessarily a whole number, and several other aspects of the question, induce Telitchérin to believe that they afford a clue to the understanding of the nature of the elements; we must, however, await the full development of his theory before pronouncing judgment on it. What we can at present only be certain of is this: that attempts like the two above named must be repeated and multiplied, because the periodic law has clearly shown that the masses of the atoms increase abruptly, by steps, which are clearly connected in some way with Dalton's law of multiple proportions; and because the periodicity of the elements finds expression in the transition from RX to RX_2 , RX_3 , RX_4 , and so on till RX_n , at which point, the energy of the combining forces being exhausted, the series begins anew from RX to RX_2 , and so on.

While connecting by new bonds the theory of the chemical elements with Dalton's theory of multiple proportions, or atomic structure of bodies, the periodic law opened for natural philosophy a new and wide field for speculation. Kant said that there are in the world 'two things which never cease to call for the admiration and reverence of man: the moral law within ourselves, and the stellar sky above us.' But when we turn our thoughts towards the nature of the elements and the periodic law, we must add a third subject, namely, 'the nature of the elementary individuals which we discover everywhere around us.' Without them the stellar sky itself is inconceivable; and in the atoms we see at once their peculiar individualities, the infinite multiplicity of the individuals, and the submission of their seeming freedom to the general harmony of Nature.

Having thus indicated a new mystery of Nature, which does not yet yield to rational conception, the periodic law, together with the revelations of spectrum analysis, have contributed to again revive an old but remarkably long-lived hope—that of discovering, if not by experiment, at least, by a mental effort, the *primary matter*—which had its genesis in the minds of the Grecian philosophers, and has been transmitted, together with many other ideas of the classic period, to the heirs of their civilisation. Having grown, during the times of the alchemists up to the period when experimental proof was required, the idea has rendered good service; it induced those careful observations and experiments which later on called into being the works of Scheele, Lavoisier, Priestley, and Cavendish. It then slumbered awhile, but was soon awakened by the attempts either to confirm or to refute the ideas of Prout as to the multiple proportion relationship of the atomic

weights of all the elements. And once again the inductive or experimental method of studying Nature gained a direct advantage from the old Pythagorean idea: because atomic weights were determined with an accuracy formerly unknown. But again the idea could not stand the ordeal of experimental test, yet the prejudice remains and has not been uprooted, even by Stas; nay, it has gained a new vigour, for we see that all which is imperfectly worked out, new and unexplained, from the still scarcely studied rare metals to the hardly perceptible nebulae, have been used to justify it. As soon as spectrum analysis appears as a new and powerful weapon of chemistry, the idea of a primary matter is immediately attached to it. From all sides we see attempts to constitute the imaginary substance *helium*³ the so much longed for primary matter. No attention is paid to the circumstance that the helium line is only seen in the spectrum of the solar protuberances, so that its universality in Nature remains as problematic as the primary matter itself; nor to the fact that the helium line is wanting amongst the Fraunhofer lines of the solar spectrum, and thus does not answer to the brilliant fundamental conception which gives its real force to spectrum analysis.

And finally, no notice is even taken of the indubitable fact that the brilliancies of the spectral lines of the simple substances vary under different temperatures and pressures; so that all probabilities are in favour of the helium line simply belonging to some long since known element placed under such conditions of temperature, pressure, and gravity as have not yet been realised in our experiments. Again, the idea that the excellent investigations of Lockyer of the spectrum of iron can be interpreted in favour of the compound nature of that element, evidently must have arisen from some misunderstanding. The spectrum of a compound certainly does not appear as a sum of the spectra of its components; and therefore the observations of Lockyer can be considered precisely as a proof that iron undergoes no other changes at the temperature of the sun than those which it experiences in the voltaic arc—provided the spectrum of iron is preserved. As to the shifting of some of the lines of the spectrum of iron while the other lines maintain their positions, it can be explained, as shown by M. Kleiber ('Journal of the Russian Chemical and Physical Society,' 1885, 147), by the relative motion of the various strata of the sun's atmosphere, and by Zöllner's laws of the relative brilliancies of different lines of the spectrum. Moreover, it ought not to be forgotten that if iron were really proved to consist of two or more unknown elements, we should simply have an increase in the number of our elements—not a reduction, and still less a reduction of all of them to one single primary matter.

Feeling that spectrum analysis will not yield a support to the Pythagorean conception, its modern promoters are so bent upon its being confirmed by the periodic law, that the illustrious Berthelot, in his work '*Les origines de l'Alchimie*,' 1885, 313, has simply mixed up the fundamental idea of the law of periodicity with the ideas of Prout, the alchemists, and Democritus about primary matter.⁴ But the periodic law, based as it is on the solid and whole-

³ That is, a substance having a wave-length equal to 0.0005875 millimetre.

⁴ He maintains (on p. 309) that the periodic law requires two new analogous elements, having atomic weights of 48 and 64, occupying positions between sulphur

some ground of experimental research, has been evolved independently of any conception as to the nature of the elements; it does not in the least originate in the idea of a unique matter; and it has no historical connection with that relic of the torments of classical thought, and therefore it affords no more indication of the unity of matter or of the compound character of our elements, than the law of Avogadro, or the law of specific heats, or even the conclusions of spectrum analysis. None of the advocates of a unique matter have ever tried to explain the law from the standpoint of ideas taken from a remote antiquity when it was found convenient to admit the existence of many gods—and of a unique matter.

When we try to explain the origin of the idea of a unique primary matter, we easily trace that in the absence of inductions from experiment it derives its origin from the scientifically philosophical attempt at discovering some kind of unity in the immense diversity of individualities which we see around. In classical times such a tendency could only be satisfied by conceptions about the immaterial world. As to the material world, our ancestors were compelled to resort to some hypothesis, and they adopted the idea of unity in the formative material, because they were not able to evolve the conception of any other possible unity in order to connect the multifarious relations of matter. Responding to the same legitimate scientific tendency, natural science has discovered throughout the universe a unity of plan, a unity of forces, and a unity of matter, and the convincing conclusions of modern science compel every one to admit these kinds of unity. But while we admit unity in many things, we none the less must also explain the individuality and the apparent diversity which we cannot fail to trace everywhere. It has been said of old, 'Give a fulcrum, and it will become easy to displace the earth.' So also we must say, 'Give anything that is individualised, and the apparent diversity will be easily understood.' Otherwise, how could unity result in a multitude?

After a long and painstaking research, natural science has discovered the individualities of the chemical elements, and therefore it is now capable not only of analysing, but also of synthesising; it can understand and grasp the general and unity, as well as the individualised and the multitudinous. Unity and the general, like time and space, like force and motion, vary uniformly; the uniform admit of interpolations, revealing every intermediate phase. But the multitudinous, the individualised—like ourselves, like the chemical elements, like the members of a peculiar periodic function of elements, like Dalton's multiple proportions—is characterised in another way: we see in it, side by side with a connecting general principle, leaps, breaks of continuity, points which escape from the analysis of the infinitely small—a complete absence of intermediate links. Chemistry has found an answer to the question as to the causes of multitudes; and while retaining the conception of many elements, all submitted to the discipline of a general law, it offers an escape from the Indian Nirvana—the absorption in the universal, replacing it by the individualised. However, the place for indi-

and selenium, although nothing of the kind results from any of the different readings of the law.

viduality is so limited by the all-grasping, all-powerful universal, that it is merely a fulcrum for the understanding of multitude in unity.

Having touched upon the metaphysical bases of the conception of a unique matter which is supposed to enter into the composition of all bodies, I think it necessary to dwell upon another theory, akin to the above conception—the theory of the compound character of the elements now admitted by some—and especially upon one particular circumstance which, being related to the periodic law, is considered to be an argument in favour of that hypothesis.

Dr. Pelopidas, in 1883, made a communication to the Russian Chemical and Physical Society on the periodicity of the hydrocarbon radicles, pointing out the remarkable parallelism which was to be noticed in the change of properties of hydrocarbon radicles and elements when classed in groups. Professor Carnelley, in 1886, developed a similar parallelism. The idea of M. Pelopidas will be easily understood if we consider the series of hydrocarbon radicles which contain, say, 6 atoms of carbon:—

I.	II.	III.	IV.	V.	VI.	VII.	VIII.
C_6H_{13}	C_6H_{12}	C_6H_{11}	C_6H_{10}	C_6H_9	C_6H_8	C_6H_7	C_6H_6

The first of these radicles, like the elements of the 1st group, combines with Cl, OH, and so on, and gives the derivatives of hexyl alcohol, $C_6H_{13}(OH)$; but, in proportion as the number of hydrogen atoms decreases, the capacity of the radicles of combining with, say, the halogens increases. C_6H_{12} already combines with 2 atoms of chlorine; C_6H_{11} with 3 atoms, and so on. The last members of the series comprise the radicles of acids; thus C_6H_8 , which belongs to the 6th group, gives, like sulphur, a bibasic acid, $C_6H_4O_2(OH)_2$, which is homologous with oxalic acid. The parallelism can be traced still further, because C_6H_5 appears as a monovalent radicle of benzene, and with it begins a new series of aromatic derivatives, so analogous to the derivatives of the fat series. Let me also mention another example from among those which have been given by M. Pelopidas. Starting from the alkaline radicle of monomethylammonium, $N(CH_3)H_3$, or NCH_3 , which presents many analogies with the alkaline metals of the 1st group, he arrives, by successively diminishing the number of the atoms of hydrogen, at a 7th group which contains cyanogen, CN, which has long since been compared to the halogens of the 7th group.

The most important consequence which, in my opinion, can be drawn from the above comparison is that the periodic law, so apparent in the elements, has a wider application than might appear at first sight; it opens up a new vista of chemical evolutions. But, while admitting the fullest parallelism between the periodicity of the elements and that of the compound radicles, we must not forget that in the periods of the hydrocarbon radicles we have a *decrease* of mass as we pass from the representatives of the first group to the next, while in the periods of the elements the mass *increases* during the progression. It thus becomes evident that we cannot speak of an identity of periodicity in both cases, unless we put aside the ideas of mass and attraction, which are the real corner-stones of the whole of natural science, and even enter into those very conceptions of simple substances which

came to light a full hundred years later than the immortal principles of Newton.⁵

From the foregoing, as well as from the failures of so many attempts at finding in experiment and speculation a proof of the compound character of the elements and of the existence of primordial matter, it is evident, in my opinion, that this theory must be classed among mere utopias. But utopias can only be combated by freedom of opinion, by experiment, and by new utopias. In the republic of scientific theories freedom of opinions is guaranteed. It is precisely that freedom which permits me to criticise openly the widely-diffused idea as to the unity of matter in the elements. Experiments and attempts at confirming that idea have been so numerous that it really would be instructive to have them all collected together, if only to serve as a warning against the repetition of old failures. And now as to new utopias which may be helpful in the struggle against the old ones, I do not think it quite useless to mention a *phantasy* of one of my students who imagined that the weight of bodies does not depend upon their mass, but upon the character of the motion of their atoms. The atoms, according to this new utopian, may all be homogeneous or heterogeneous, we know not which; we know them in motion only, and that motion they maintain with the same persistence as the stellar bodies maintain theirs. The weights of atoms differ only in consequence of their various modes and quantity of motion; the heaviest atoms may be much simpler than the lighter ones: thus an atom of mercury may be simpler than an atom of hydrogen—the manner in which it moves causes it to be heavier. My interlocutor even suggested that the view which attributes the greater complexity to the lighter elements finds confirmation in the fact that the hydrocarbon radicles mentioned by Pelopidas, while becoming lighter as they lose hydrogen, change their properties periodically in the same manner as the elements change theirs according as the atoms grow heavier.

The French proverb, *La critique est facile mais l'art est difficile*, however, may well be reversed in the case of all such ideal views, as it is much easier to formulate than to criticise them. Arising from the virgin soil of newly-established facts, the knowledge relating to the elements, to their masses, and to the periodic changes of their properties has given a motive for the formation of utopian hypotheses, probably because they could not be foreseen by the aid of any of the various metaphysical systems, and exist, like the idea of gravitation, as an independent outcome of natural science, requiring the acknowledgment of general laws, when these have been established with the same degree of persistency as is indispensable for the acceptance of a thoroughly established fact. Two centuries have elapsed since the theory of gravitation was enunciated, and although we do not understand its cause, we still must regard gravitation as a fundamental conception of natural philosophy, a conception which has enabled us to perceive much more than the metaphysicians did or could with their seeming omniscience. A hundred

⁵ It is noteworthy that the year in which Lavoisier was born (1743)—the author of the idea of elements and of the indestructibility of matter—is later by exactly one century than the year in which the author of the theory of gravitation and mass was born (1643 N.S.). The affiliation of the ideas of Lavoisier and those of Newton is beyond doubt.

years later the conception of the elements arose; it made chemistry what it now is; and yet we have advanced as little in our comprehension of simple substances since the times of Lavoisier and Dalton as we have in our understanding of gravitation. The periodic law of the elements is only twenty years old; it is not surprising, therefore, that, knowing nothing about the causes of gravitation and mass, or about the nature of the elements, we do not comprehend the *rationale* of the periodic law. It is only by collecting established laws—that is, by working at the acquirement of truth—that we can hope gradually to lift the veil which conceals from us the causes of the mysteries of Nature and to discover their mutual dependency. Like the telescope and the microscope, laws founded on the basis of experiment are the instruments and means of enlarging our mental horizon.

In the remaining part of my communication I shall endeavour to show, and as briefly as possible, in how far the periodic law contributes to enlarge our range of vision. Before the promulgation of this law the chemical elements were mere fragmentary, incidental facts in Nature; there was no special reason to expect the discovery of new elements, and the new ones which were discovered from time to time appeared to be possessed of quite novel properties. The law of periodicity first enabled us to perceive undiscovered elements at a distance which formerly was inaccessible to chemical vision; and long ere they were discovered new elements appeared before our eyes possessed of a number of well-defined properties. We now know three cases of elements whose existence and properties were foreseen by the instrumentality of the periodic law. I need but mention the brilliant discovery of *gallium*, which proved to correspond to ekaaluminium of the periodic law, by Lecoq de Boisbaudran; of *scandium*, corresponding to ekaboron, by Nilson; and of *germanium*, which proved to correspond in all respects to ekasilicon, by Winkler. When, in 1871, I described to the Russian Chemical Society the properties, clearly defined by the periodic law, which such elements ought to possess, I never hoped that I should live to mention their discovery to the Chemical Society of Great Britain as a confirmation of the exactitude and the generality of the periodic law. Now that I have had the happiness of doing so, I unhesitatingly say that although greatly enlarging our vision, even now the periodic law needs further improvements in order that it may become a trustworthy instrument in further discoveries.⁶

I will venture to allude to some other matters which chemistry has discerned by means of its new instrument, and which it could not have made

⁶ I foresee some more new elements, but not with the same certitude as before. I shall give one example, and yet I do not see it quite distinctly. In the series which contains Hg=204, Pb=206, and Bi=208, we can guess the existence (at the place VI—11) of an element analogous to tellurium, which we can describe as dvi-tellurium, Dt, having an atomic weight of 212, and the property of forming the oxide DtO₃. If this element really exists, it ought in the free state to be an easily fusible, crystalline, non-volatile metal of a grey colour, having a density of about 9·3, capable of giving a dioxide, DtO₂, equally endowed with feeble acid and basic properties. This dioxide must give on active oxidation an unstable higher oxide, DtO₃, which should resemble in its properties PbO₂ and Bi₂O₅. Dvi-tellurium hydride, if it be found to exist, will be a less stable compound than even H₂Te. The compounds of dvi-tellurium will be easily reduced, and it will form characteristic definite alloys with other metals.

out without a knowledge of the law of periodicity, and I will confine myself to simple substances and to oxides.

Before the periodic law was formulated the atomic weights of the elements were purely empirical numbers, so that the magnitude of the equivalent, and the atomicity, or the value in substitution possessed by an atom, could only be tested by critically examining the methods of determination, but never directly by considering the numerical values themselves; in short, we were compelled to move in the dark, to submit to the facts, instead of being masters of them. I need not recount the methods which permitted the periodic law at last to master the facts relating to atomic weights, and I would merely call to mind that it compelled us to modify the valencies of *indium* and *cerium*, and to assign to their compounds a different molecular composition. Determinations of the specific heats of these two metals fully confirmed the change. The trivalency of *yttrium*, which makes us now represent its oxide as Y_2O_3 instead of as YO , was also foreseen (in 1870) by the periodic law, and it now has become so probable that Cleve, and all other subsequent investigators of the rare metals, have not only adopted it, but have also applied it without any new demonstration to substances so imperfectly known as those of the cerite and gadolinite group, especially since Hildebrand determined the specific heats of lanthanum and didymium and confirmed the expectations suggested by the periodic law. But here, especially in the case of didymium, we meet with a series of difficulties long since foreseen through the periodic law, but only now becoming evident, and chiefly arising from the relative rarity and insufficient knowledge of the elements which usually accompany didymium.

Passing to the results obtained in the case of the rare elements *beryllium*, *scandium*, and *thorium*, it is found that these have many points of contact with the periodic law. Although Avdóeff long since proposed the magnesia formula to represent beryllium oxide, yet there was so much to be said in favour of the alumina formula, on account of the specific heat of the metals and the isomorphism of the two oxides, that it became generally adopted and seemed to be well established. The periodic law, however, as Brauner repeatedly insisted ('Berichte,' 1878, 872; 1881, 53), was against the formula Be_2O_3 ; it required the magnesia formula BeO —that is, an atomic weight of 9—because there was no place in the system for an element like beryllium having an atomic weight of 13.5. This divergence of opinion lasted for years, and I often heard that the question as to the atomic weight of beryllium threatened to disturb the generality of the periodic law, or, at any rate, to require some important modifications of it. Many forces were operating in the controversy regarding beryllium, evidently because a much more important question was at issue than merely that involved in the discussion of the atomic weight of a relatively rare element; and during the controversy the periodic law became better understood, and the mutual relations of the elements became more apparent than ever before. It is most remarkable that the victory of the periodic law was won by the researches of the very observers who previously had discovered a number of facts in support of the trivalency of beryllium. Applying the higher law of Avogadro, Nilson and Petterson have finally shown that the density of the vapour of the beryllium chloride, $BeCl_2$, obliges us to regard beryllium as bivalent in

conformity with the periodic law.⁷ I consider the confirmation of Avdéeff's and Brauner's view as important in the history of the periodic law as the discovery of scandium, which, in Nilson's hands, confirmed the existence of ekaboron.

The circumstance that *thorium* proved to be quadrivalent, and $\text{Th} = 232$, in accordance with the views of Chydenius and the requirements of the periodic law, passed almost unnoticed, and was accepted without opposition, and yet both thorium and uranium are of great importance in the periodic system, as they are its last members, and have the highest atomic weights of all the elements.

The alteration of the atomic weight of *uranium* from $\text{U} = 120$ into $\text{U} = 240$ attracted more attention, the change having been made on account of the periodic law, and for no other reason. Now that Roscoe, Rammelsberg, Zimmermann, and several others have admitted the various claims of the periodic law in the case of uranium, its high atomic weight is received without objection, and it endows that element with a special interest.

While thus demonstrating the necessity of modifying the atomic weights of several insufficiently known elements, the periodic law enabled us also to detect errors in the determination of the atomic weights of several elements whose valencies and true position among other elements were already well known. Three such cases are especially noteworthy: those of tellurium, titanium, and platinum. Berzelius had determined the atomic weight of *tellurium* to be 128, while the periodic law claimed for it an atomic weight below that of iodine, which had been fixed by Stas at 126.5, and which was certainly not higher than 127. Brauner then undertook the investigation, and he has shown that the true atomic weight of tellurium is lower than that of iodine, being near to 125. For *titanium* the extensive researches of Thorpe have confirmed the atomic weight of $\text{Ti} = 48$, indicated by the law, and already foreseen by Rose, but contradicted by the analyses of Pierre and several other chemists. An equally brilliant confirmation of the expectations based on the periodic law has been given in the case of the series osmium, iridium, platinum, and gold. At the time of the promulgation of the periodic law, the determinations of Berzelius, Rose, and many others gave the following figures:—

$\text{Os} = 200$; $\text{Ir} = 197$; $\text{Pt} = 198$; $\text{Au} = 196$.

⁷ Let me mention another proof of the bivalency of beryllium which may have passed unnoticed, as it was published in the Russian chemical literature. Having remarked (in 1884) that the density of such solutions of chlorides of metals, MCl_n , as contain 200 mols. of water (or a large and constant amount of water) regularly increases as the molecular weight of the dissolved salt increases, I proposed to one of our young chemists, M. Burdakoff, that he should investigate beryllium chloride. If its molecule be BeCl_2 its weight must be $= 80$; and in such a case it must be heavier than the molecule of $\text{KCl} = 74.5$, and lighter than that of $\text{MgCl}_2 = 93$. On the contrary, if beryllium chloride is a trichloride, $\text{BeCl}_3 = 120$, its molecule must be heavier than that of $\text{CaCl}_2 = 111$, and lighter than that of $\text{MnCl}_2 = 126$. Experiment has shown the correctness of the former formula, the solution $\text{BeCl}_2 + 200\text{H}_2\text{O}$ having (at $15^\circ 4'$) a density of 1.0138, this being a higher density than that of the solution $\text{KCl} + 200\text{H}_2\text{O}$ ($= 1.0121$), and lower than that of $\text{MgCl}_2 + 200\text{H}_2\text{O}$ ($= 1.0203$). The bivalency of beryllium was thus confirmed in the case both of the dissolved and the vaporised chloride.

The expectations of the periodic law⁸ have been confirmed, first, by new determinations of the atomic weight of *platinum* (by Seubert, Dittmar, and M'Arthur), which proved to be near to 196 (taking O = 16, as proposed by Marignac, Brauner, and others); secondly, by Seubert having proved that the atomic weight of *osmium* is really lower than that of platinum, and that it is near to 191; and thirdly, by the investigations of Krüss, and Thorpe and Laurie proving that the atomic weight of *gold* exceeds that of platinum, and approximates to 197. The atomic weights which were thus found to require correction were precisely those which the periodic law had indicated as affected with errors; and it has been proved, therefore, that the periodic law affords a means of testing experimental results. If we succeed in discovering the exact character of the periodic relationships between the increments in atomic weights of allied elements discussed by Ridberg in 1885, and again by Bazaroff in 1887, we may expect that our instrument will give us the means of still more closely controlling the experimental data relating to atomic weights.

Let me next call to mind that, while disclosing the variation of chemical properties,⁹ the periodic law has also enabled us to systematically discuss many of the physical properties of elementary bodies, and to show that these properties are also subject to the law of periodicity. At the Moscow Congress of Russian Naturalists in August, 1869, I dwelt upon the relations which existed between density and the atomic weight of the elements. The following year Professor Lothar Meyer, in his well-known paper,¹⁰ studied the same subject in more detail, and thus contributed to spread information about the periodic law. Later on, Carnelley, Laurie, L. Meyer, Roberts-Austen, and several others applied the periodic system to represent the order in the changes of the magnetic properties of the elements, their melting points, the heats of formation of their haloid compounds, and even of such mechanical properties as the coefficient of elasticity, the breaking stress, &c., &c. These deductions, which have received further support in the discovery of new elements endowed not only with chemical but even with physical properties, which were foreseen by the law of periodicity, are well known; so I need not dwell upon the subject, and may pass to the consideration of oxides.¹¹

⁸ I pointed them out in the *Liebig's Annalen*, Supplement Band., viii. 1871, p. 211.

⁹ Thus, in the typical small period of



we see at once the progression from the alkali metals to the acid non-metals, such as are the halogens.

¹⁰ *Liebig's Annalen*, Supplement Band., vii. 1870.

¹¹ A distinct periodicity can also be discovered in the spectra of the elements. Thus the researches of Hartley, Ciamician, and others have disclosed, first, the homology of the spectra of analogous elements: secondly, that the alkali metals have simpler spectra than the metals of the following groups; and thirdly, that there is a certain likeness between the complicated spectra of manganese and iron on the one hand, and the no less complicated spectra of chlorine and bromine on the other hand, and their likeness corresponds to the degree of analogy between those elements which is indicated by the periodic law.

In indicating that the gradual increase of the power of elements of combining with oxygen is accompanied by a corresponding decrease in their power of combining with hydrogen, the periodic law has shown that there is a limit of oxidation, just as there is a well-known limit to the capacity of elements for combining with hydrogen. A single atom of an element combines with at most four atoms of either hydrogen or oxygen: and while CH_4 and SiH_4 represent the highest hydrides, so RuO_4 and OsO_4 are the highest oxides. We are thus led to recognise types of oxides, just as we have had to recognise types of hydrides.¹²

The periodic law has demonstrated that the maximum extent to which different non-metals enter into combination with oxygen is determined by the extent to which they combine with hydrogen, and that the sum of the number of equivalents of both must be equal to 8. Thus chlorine, which combines with 1 atom or 1 equivalent of hydrogen, cannot fix more than 7 equivalents of oxygen, giving Cl_2O_7 ; while sulphur, which fixes 2 equivalents of hydrogen, cannot combine with more than 6 equivalents or 3 atoms of oxygen. It thus becomes evident that we cannot recognise as a fundamental property of the elements the atomic valencies deduced from their hydrides; and that we must modify, to a certain extent, the theory of atomicity if we desire to raise it to the dignity of a general principle capable of affording an insight into the constitution of all compound molecules. In other words, it is only to carbon, which is quadrivalent with regard both to oxygen and hydrogen, that we can apply the theory of constant valency and of bond, by means of which so many still endeavour to explain the structure of compound molecules. But I should go too far if I ventured to explain in detail the conclusions which can be drawn from the above considerations. Still, I think it necessary to dwell upon one particular fact which must be explained from the point of view of the periodic law in order to clear the way to its extension in that particular direction.

The higher oxides yielding salts the formation of which was foreseen by the periodic system—for instance, in the short series beginning with sodium—




must be clearly distinguished from the higher degrees of oxidation which correspond to hydrogen peroxide and bear the true character of peroxides. Peroxides such as Na_2O_2 , BaO_2 , and the like have long been known. Similar


¹² Formerly it was supposed that, being a bivalent element, oxygen can enter into any grouping of the atoms, and there was no limit foreseen as to the extent to which it could further enter into combination. We could not explain why bivalent sulphur, which forms compounds such as



could not also form oxides such as—



while other elements, as, for instance, chlorine, form compounds such as—



peroxides have also recently become known in the case of chromium, sulphur, titanium, and many other elements, and I have sometimes heard it said that discoveries of this kind weaken the conclusions of the periodic law in so far as it concerns the oxides. I do not think so in the least, and I may remark, in the first place, that all these peroxides are endowed with certain properties obviously common to all of them, which distinguish them from the actual, higher, salt-forming oxides, especially their easy decomposition by means of simple contact agencies; their incapacity of forming salts of the common type; and their capacity of combining with other peroxides (like the faculty which hydrogen peroxide possesses of combining with barium peroxide, discovered by Schoene). Again, we remark that some groups are especially characterised by their capacity of generating peroxides. Such is, for instance, the case in the sixth group, where we find the well-known peroxides of sulphur, chromium, and uranium; so that further investigation of peroxides will probably establish a new periodic function, foreshadowing that molybdenum and tungsten will assume peroxide forms with comparative readiness. To appreciate the constitution of such peroxides, it is enough to notice that the peroxide form of sulphur (so-called persulphuric acid) stands in the same relation to sulphuric acid as hydrogen peroxide stands to water:—



and so also—



Similar relations are seen everywhere, and they correspond to the principle of substitutions which I long since endeavoured to represent as one of the chemical generalisations called into life by the periodic law. So also sulphuric acid, if considered with reference to hydroxyl, and represented as follows—




has its corresponding compound in dithionic acid—



Therefore, also, phosphoric acid, $\text{HO(POH}_2\text{O}_2\text{)}$, has, in the same sense, its corresponding compound in the subphosphoric acid of Saltzer:—



and we must suppose that the peroxide compound corresponding to phosphoric acid, if it be discovered, will have the following structure:—



As far as is known at present, the highest form of peroxides is met with in

¹⁵ In this sense, oxalic acid, $(\text{COOH})_2$, also corresponds to carbonic acid, $\text{OH}(\text{COOH})$, in the same way that dithionic acid corresponds to sulphuric acid, and subphosphoric acid to phosphoric; therefore, if a peroxide corresponding to carbonic acid be obtained, it will have the structure of $(\text{HCO}_3)_2$, or $\text{H}_2\text{C}_2\text{O}_6 = \text{H}_2\text{O} + \text{C}_2\text{O}_5$. So also lead must have a real peroxide, Pb_2O_5 .

the peroxide of uranium, UO_4 , prepared by Fairley;¹⁴ while $\text{O}=\text{O}_4$ is the highest oxide giving salts. The line of argument which is inspired by the periodic law, so far from being weakened by the discovery of peroxides, is thus actually strengthened, and we must hope that a further exploration of the region under consideration will confirm the applicability to chemistry generally of the principles deduced from the periodic law.

Permit me now to conclude my rapid sketch of the oxygen compounds by the observation that the periodic law is especially brought into evidence in the case of the oxides which constitute the immense majority of bodies at our disposal on the surface of the earth.

The oxides are evidently subject to the law, both as regards their chemical and their physical properties, especially if we take into account the cases of polymerism which are so obvious when comparing CO_2 with Si_nO_{2n} . In order to prove this I give the densities s and the specific volumes v of the higher oxides of two short periods. To render comparison easier, the oxides are all represented as of the form R_2O_n . In the column headed Δ the differences are given between the volume of the oxygen compound and that of the parent element, divided by n —that is, by the number of atoms of oxygen in the compound:—¹⁵

	s .	v .	Δ .		s .	v .	Δ .
Na_2O	2.6	24	-22	K_2O	2.7	35	-55
Mg_2O_2	3.6	22	-3	Ca_2O	3.15	36	-7
Al_2O_3	4.0	26	+1.3	Sc_2O_3	3.86	35	0
Si_2O_4	2.65	45	5.2	Li_2O_4	4.2	38	+5
P_2O_5	2.39	59	6.2	V_2O_5	3.49	52	6.7
S_2O_6	1.96	82	8.7	Cr_2O_6	2.74	73	9.5

I have nothing to add to these figures, except that like relations appear in other periods as well. The above relations were precisely those which made it possible for me to be certain that the relative density of ekasilicon oxide would be about 4.7; germanium oxide, actually obtained by Winkler, proved, in fact, to have the relative density 4.703.

The foregoing account is far from being an exhaustive one of all that has already been discovered by means of the periodic law telescope in the boundless realms of chemical evolution. Still less is it an exhaustive account of all that may yet be seen, but I trust that the little which I have said will account

¹⁴ The compounds of uranium prepared by Fairley seem to me especially instructive in understanding the peroxides. By the action of hydrogen peroxide on uranium oxide, UO_5 , a peroxide of uranium, $\text{UO}_4 \cdot 4\text{H}_2\text{O}$, is obtained (*U* 240) if the solution be acid; but if hydrogen peroxide act on uranium oxide in the presence of caustic soda, a crystalline deposit is obtained which has the composition $\text{Na}_4\text{UO}_8 \cdot 4\text{H}_2\text{O}$, and evidently is a combination of sodium peroxide, Na_2O_2 , with uranium peroxide, UO_4 . It is possible that the former peroxide, $\text{UO}_4 \cdot 4\text{H}_2\text{O}$, contains the elements of hydrogen peroxide and uranium peroxide, U_2O_7 , or even $\text{U}(\text{OH})_6 \cdot \text{H}_2\text{O}_2$, like the peroxide of tin recently discovered by Spring, which has the constitution $\text{Sn}_2\text{O}_5 \cdot \text{H}_2\text{O}_2$.

¹⁵ Δ thus represents the average increase of volume for each atom of oxygen contained in the higher salt-forming oxide. The acid oxides give, as a rule, a higher value of Δ , while in the case of the strongly alkaline oxides its value is usually negative.

for the philosophical interest attached in chemistry to this law. Although but a recent scientific generalisation, it has already stood the test of laboratory verification, and appears as an instrument of thought which has not yet been compelled to undergo modification; but it needs not only new applications, but also improvements, further development, and plenty of fresh energy. All this will surely come, seeing that such an assembly of men of science as the Chemical Society of Great Britain has expressed the desire to have the history of the periodic law described in a lecture dedicated to the glorious name of Faraday.

APPENDIX III.

NOTE ON THE DISCOVERY OF HYDRO-NITROUS ACID, N_3H . (HYDROGEN NITRIDE, AZOIMIDE).

BY PROFESSOR MENDELÉEFF.

EXTRACTED FROM THE JOURNAL OF THE RUSSIAN PHYSICO-CHEMICAL
SOCIETY, VOL. XXII. 1890, NO. 8.

AMONG the brilliant discoveries made in chemical science during the current year, we must number, besides the preparation of the compound $Ni(CO)_4$,¹ the discovery made by Curtius ('Ber' 23, 3023), who demonstrated the existence of the compound N_3H , the mode of its preparation, and its analogy with the halogen acids. Although I have not published any paper respecting the possibility of the existence of such a compound, still I have foreseen it in consequence of the considerations developed in my communication on the nitriles to the first meeting of the Russian naturalists (1867), and in the first edition (1868-1870) of my 'Principles of Chemistry.' I think it may not be superfluous to publish these considerations now, because in my opinion they may help to explain the structure of the compound N_3H , and to indicate the position which it should occupy among the other known compounds of nitrogen,² and

¹ The composition and properties of $Ni(CO)_4$ investigated by Langer, Mond, and Quincke are so new, instructive, and important for the periodic system of the elements that, owing to the possibility of obtaining such unexpected substances, a fresh stimulus has arisen for the reinvestigation of the data respecting the properties of the most common elements. And I think many important discoveries, like that made by Curtius, may still be looked for in the provinces of sulphur and nitrogen.

² As nitrogen gives gaseous molecules NO , NH_3 , and NO_2 , which contain one atom of nitrogen, therefore the nitrogen in them is either bi- or tri- or quadrivalent compared with hydrogen. And, as this element forms also molecules N_2O , N_2O_4 , and N_2O_5 , which contain two atoms of nitrogen, therefore N_2 appears to be equal to H_2 , H_8 , and H_{10} . In NH_4Cl , $NO_2(OH)$, and other compounds, the nitrogen is seen to be quinquivalent. These considerations alone, without entering into details, show that the compounds of nitrogen cannot be understood by the acceptance of that method of building up molecules from atoms having a constant valency which the 'structuralists' consider sufficient for the comprehension of the formation of nearly all carbon compounds (CO forms an universally known exception). For this reason I think that the study of the compounds of nitrogen,

perhaps also help to point out the reactions and new methods of preparation of this remarkable acid, whose existence should tend to throw a light on the nature of the metallic compounds of nitrogen, many points as to which are not clear. But in order to render clear the conclusions arrived at, it will be necessary to touch on certain general conceptions connected with the periodic system.

If an element R gives a compound RX_n with univalent elements X—for example, with the halogens—then the corresponding salt-forming hydrate will be $RO'''(OH)_{n-1}$, in which, however, the total number of oxygen atoms never exceeds four, because it is one of the peculiarities of the periodic system that it shows a correspondence (1) between the composition of the hydride and that of higher salt-forming oxides of all elements, and (2) between the composition of the hydrates and hydrogen compounds. If an element R forms RH, then it gives oxides of the composition R_2O to R_2O_7 , and hydrates from ROH to RHO_4 or $RO_3(OH)$, as the salt-forming oxides and hydrates; to an element which forms RH_2 there correspond the higher oxides RO_3 and RH_2O_4 or $RO_2(OH)_2$; and to those elements which give RH_3 there correspond the higher salt-forming hydrate RH_3O_4 or $RO(OH)_3$, and consequently the higher oxide R_2O_5 , &c. These now universally known relations may be expressed thus: (1) the sum of the valencies of hydrogen and oxygen atoms (in the higher salt-forming oxide) which can combine with any element is equal to eight (for instance, SH_2 and SO_3 ; PH_3 and P_2O_5); (2) the number of atoms of oxygen in the higher salt-forming hydrate is four—for example, $HClO_4$, H_2SO_4 , H_3PO_4 —and, as a consequence of the first two conclusions, (3) the maximum amount of hydrogen in the salt-forming hydrates of the oxides does not exceed the amount of hydrogen in the hydride of the element when the hydride is a gaseous compound of the formula RH_n .

Hence it is evident, firstly, that an element R, which, like nitrogen for example, forms compounds RH_3 and R_2O_5 , or in general RX_3 and RX_5 , does not form a saline hydrate $R(OH)_3$, although $R(OH)_3$ is capable of existence. Secondly, that even the highest hydrate RH_3O_4 may lose a portion of this water, and give incomplete hydrates, such as $PH_3O_4 - PO(OH)_3$; $P_2H_4O_7 - [PO(HO)_2]_2O$ and $PO_2(OH)$, for example. Thirdly, that the normal

and especially of those which pass into vapour and resemble the compound N_5H , should not only lead to the extension of our experimental data, but also aid the progress of that theory of chemical structure which started almost exclusively from data respecting the carbon compounds, in which the type CX_4 appears with particular force owing to the fact of its giving CH_4 and CO_2 as limiting compounds of equal valency. In nitrogen, which gives NH_3 and N_2O_5 (likewise in sulphur, which forms SH_2 and SO_3), there is no longer this equality, and in the sense of the periodic law there cannot be, and therefore the further perfection of the conception of the chemical structure of molecules can be looked for sooner in the compounds of this element than in those of carbon. In this paper I endeavour to avoid the formulation of the conception touching on this aspect of hydronitrous acid, and I will here only compare N_5H and H_5N in order to show the equivalence of N_2 and H_2 as well as of the atoms in a free state, for both gases give molecules N_2 and H_2 . Therefore, guided by those conceptions of substitutions which have been given by me in my London lecture (Appendix I.) we may expect to obtain N_2H_2 , as a combination of the residues of N_5H and NH_5 . If N_2H_2 be obtained, then the series: NH_5 , N_2H_2 , and N_5H will give a much greater insight into the internal properties of nitrogen than the common recognition of this element as quadri-, tri-, or quinquivalent.

ammonium salts of any element must correspond with the hydrates of that element, and consequently may contain oxygen atoms other than those which unite the ammonium radicles to the element R; as, for example, in $\text{NO}_2(\text{ONH}_4)$, $\text{SO}_2(\text{OH})(\text{ONH}_4)$, $\text{CO}(\text{OH})(\text{ONH}_4)$, $\text{CO}(\text{ONH}_4)_2$, $\text{COH}(\text{ONH}_4)$, &c.

Such ammonium compounds, on losing water, yield amides and nitriles. If the loss of water is limited by the passage of the residue ONH_4 into NH_3 , then amides are produced; for example, formamide, $\text{C}(\text{O}(\text{NH}_2))\text{H}$, corresponds with ammonium formate, $\text{CO}(\text{ONH}_4)\text{H}$.

If the oxygen and hydrogen are evolved from the amides in the form of water, which can only take place in the above-mentioned ammonium salts which contain an excess of oxygen (for example, $\text{NO}_2\cdot\text{ONH}_4$, &c.), then *nitriles* are formed. Thus to nitric acid there corresponds the nitrile NON , or nitrous oxide, N_2O , and to formic acid there corresponds the nitrile CNH , or hydrocyanic acid, and in general the amides, $\text{RCO}\cdot\text{NH}_2$, and nitriles, $\text{R}\cdot\text{CN}$, or cyanides, correspond with the carboxyl compounds, $\text{R}\cdot\text{COOH}$. The amide corresponding with acid ammonium sulphate, $\text{SO}_2(\text{OH})(\text{ONH}_4)$, will contain $\text{SO}_2(\text{OH})(\text{NH}_2)$; and the nitrile SO_2HN , of which there may, moreover, be two possible isomerides; $\text{SO}_2\text{:NH}$, in which the hydrogen is governed or held by the nitrogen—*i.e.* where it exists as the ammonia residue NH (imidogen), which is united by two bonds with the SO_2 group; the other, $\text{SO}(\text{OH})\text{N}$, in which the hydrogen is held as hydroxyl.³

As the nitriles are formed by a dual loss of molecules of water, they are able, firstly, to combine twice with various other molecules; secondly, to combine among themselves; and thirdly, to polymerise into di- and tri-polymerides; for example, to the nitrile of carbonic acid (cyanic acid), CHON , corresponds the polymeric form $\text{C}_3\text{H}_3\text{O}_3\text{N}_3$, cyanuric acid.


It is evident that if we regard as perfect hydrates only such as contain a given element in union with hydroxyl only—for example, $\text{Na}(\text{OH})$, $\text{Ti}(\text{OH})_4$, &c.—then nitriles can only be expected to be obtained from imperfect hydrates, such as $\text{SO}_2(\text{OH})_2$, $\text{PO}(\text{OH})_3$, &c.

As amides are equal to hydrates + $\text{NH}_3 - \text{H}_2\text{O}$, it is obvious that there must be an analogy and equivalency between the direct combination of water and ammonia. And therefore direct combinations with ammonia essentially proceed under the influence of the same forces as produce hydrates, and the compounds produced should show the properties of amides. If sulphuric anhydride combine with ammonia, forming amido-compounds, then a similar character should be ascribed to the compounds of salts with ammonia, which is not only confirmed in the cobalt-ammonium and similar compounds, but even in the direct absorption of ammonia by many salts—for example, by calcium chloride, copper sulphate, &c. And as CuSO_4 absorbs 5NH_3 , just as it also combines with $5\text{H}_2\text{O}$, we see in the quantitative aspect of this, as in many other examples, a confirmation of the above-mentioned correlation between the compounds of ammonia and water.

³ Although I am obliged, for the want of other means of expression, to speak of the bonds of elements, still I do not understand them in the general statical sense of this word, but in that dynamical sense which I endeavoured to express in my above-mentioned London lecture (Appendix I.).

It is necessary to take all these facts¹ into consideration, in order that the representation respecting hydronitrous acid, N_3H , should be understood. We must first of all turn to the ammonium compounds of nitric acid as a starting point. And in order that all the relations should be more self-evident, we will start from the anhydrides of nitric and phosphoric acids.

As nitrogen and phosphorus give NH_3 and PH_3 , their highest possible hydrates are—



The perfect hydrates, on the other hand—for example, $N_2O_5, 5H_2O = 2N(OH)_5$ —belong to those unstable compounds which are generally simply regarded as solutions.² The ortho- and pyro-hydrates of nitric acid must also be regarded as unstable compounds, whereas the corresponding derivatives of phosphorus have long been known as distinct and individual hydrates, on account of the existence of the corresponding salts. As, on the other hand, in its basic mercury and lead salts³ nitric acid shows a tendency to form ortho-salts, the fact that nitrogen compounds analogous to hydrogen disodium phosphate, $PO(OH)(ONa)(ONa)$, cannot be easily produced is simply one of the peculiarities which distinguish nitrogen from phosphorus, and which show the relative stability of phosphoric anhydride and ammonia as compared with nitric anhydride and phosphine, PH_3 . It may, therefore, be considered probable that in addition to the ordinary or ammonium meta-nitrate, $NO_2 \cdot ONH_4$, the ammonium pyro- and ortho-nitrates, or di- and tri-ammonium compounds, $NO(OH)(ONH_4)_2$ and $NO(ONH_4)_3$, and their corresponding amides or anhydro-derivatives $NO_2(ONH_4), NH_3$, and $NO_2(ONH_4), 2NH_3$, are capable of existence. Thus the latter is the ortho- salt, $NO(ONH_4)_3$, deprived of water. Both these anhydro-ammonium compounds have in fact been described by Divers (1872), who considered them to be solutions in which the tendency of ammonium nitrate to liquefy anhydrous ammonia⁴ is exhibited; but in the following year Raoult proved that the liquid produced in this way has a definite composition $NO_2(NH_4O), 2NH_3$, and that between -10° and $+28^\circ$ it is decomposed into a definite solid compound $NO_2(ONH_4), NH_3$, which in turn is readily dissociated when heated, with liberation of ammonia.⁵

⁴ They are more fully developed in the body of this work.

⁵ In my work on *The Investigation of Aqueous Solutions According to their Specific Gravity*, 1887, p. 361, it is shown that at present, so long as there are no more accurate determinations for the specific gravities of nitric acid, we must, on the basis of the variation of the density of the solutions, recognise the existence of a hydrate $HNO_3, 2H_2O$ which is nothing else than $N(OH)_5$ or $N_2O_5, 5H_2O$.

⁶ This vol. pp. 51 and 133.

⁷ This is one of the many historically instructive examples which prove that at present only an artificial distinction is made between solutions and definite compounds, and that there is no real fundamental difference.

⁸ The explanation of the combination of ammonia with ammonium nitrate may be applied to a number of other cases of the combination of ammonia with salts, and may even explain the different degrees of stability of such compounds. These considerations

These compounds, then, the existence of which was rendered probable from the conclusions arrived at above, correspond with the imperfect hydrates (ortho-, meta-, and pyro-) of nitric acid, and must therefore have, in certain respects, the character of amides,⁹ in which case it is to be expected that they would be converted into nitriles by the further loss of the elements of water. Assuming the elimination of water to be as complete as possible, we should obtain—

From $\text{NH}_4\text{NO}_3 - 2\text{H}_2\text{O}$ the nitrile N_2O .

„ $\text{NH}_4\text{NO}_3\text{NH}_3 - 3\text{H}_2\text{O}$ the nitrile N_3H .

„ $\text{NH}_4\text{NO}_3 2\text{NH}_3 - 3\text{H}_2\text{O}$ the nitrile N_4H_2 .

The first of these substances has long been known as nitrous oxide, and the two others have now been obtained by Curtius in the form of hydronitrous acid and its ammonium salt, N_3NH_4 .

Having thus enunciated the relations that I consider to exist between the substances discovered by Curtius and the views deduced by me from the periodic law, and having shown the relations in which the newly-discovered substances stand to the other nitrogen compounds, I consider it necessary to turn to the properties of hydronitrous acid, which at first sight seem very unexpected, but which may, however, be sufficiently explained on the basis of the above representations.¹⁰

We must first turn our attention to the quantitative aspect of the subject—that is, to the fact that amides and nitriles proceed from ammonium salts, in which the presence of ammonium, with its four atoms of hydrogen, must be recognised. Therefore it may be supposed that two of these atoms of hydrogen are eliminated in the form of water in the formation of amides, and the remaining two in the further loss of water—that is, in the passage of the amides into nitriles. And therefore—

The simplest and most plausible representation of the conversion of ammonium salts into amides and nitriles consecutively is obtained by the supposition that, in the first place, the elements of water are eliminated solely at the expense of the hydrogen of the ONH_4 group; it is in this way

oblige one to seek for amide reactions in those numerous compounds which are known between salts and ammonia.

⁹ This may be expressed by formulæ; for example, for the ortho-compounds (with 2NH_5) by separating the groups (NH_2) , thus $\text{NO}_2(\text{ONH}_4), 2\text{NH}_5 = \text{NO}(\text{ONH}_4)(\text{ONH}_4)(\text{NH}_2)$. The mono-ammonium compound, if its formula be not doubled (to make it correspond with the pyro-salt), will be $\text{NO}_2(\text{ONH}_4)\text{NH}_5 = \text{NO}(\text{ONH}_4)(\text{OH})(\text{NH}_2)$, and if this be true, one would expect salts $\text{NO}(\text{ONH}_4)(\text{OM})(\text{NH}_2) = \text{MNO}_5, 2\text{NH}_5$, and the formation of ethylene, acetylene, and other corresponding derivatives.

¹⁰ In one of my unpublished notes, dated 1871 or 1872, after having expressed the composition of N_5H and N_4H_2 , I directly presupposed that, if these bodies were able to exist and did not polymerise, they would be an acid, and a salt which (like $\text{C}(\text{N})(\text{NH}_4)$) would suffer intramolecular change and pass into a symmetrical amide, $\text{NH}_2\text{N}:\text{N}:\text{NH}_2$ (like urea). The improbability of their composition, and the small probability of these substances existing in a stable form, together with the fact that I was then occupied with other subjects, kept me from publishing my hypothetical reflections, the essence of which I now communicate, although I know that, *post factum*, they have not the same significance which they would have had, had they been published in 1871 or 1872.

that all acid amides are produced. For example, if an organic acid have the composition RCOOH , then its ammonium salt is RCOONH_4 , and its amide should be expressed by RCONH_2 . When, however, the oxygen of the ONH_4 and OH groups has been taken away, any further loss of water can only take place by the combination of the hydrogen in the amido-group with the oxygen contained in the acid radicle. Thus in the above example of an organic acid, the transformation of the amide into the nitrile can only be accomplished by the formation of water at the expense of the NH_2 and CO groups, and therefore the nitriles of such acids have the structure of cyanogen compounds, $\text{RC}\equiv\text{N}$; this, as is well known, is verified by experiment.

On applying these considerations to the formation of hydronitrous acid, we find that it is necessary to start from ortho-nitric acid, $\text{NO}(\text{OH})(\text{OH})(\text{OH})$, or rather from the corresponding di-ammonium salt, $\text{NO}(\text{OH})(\text{ONH}_4)(\text{ONH}_4)$, which, judging from the above, by the elimination of four molecules of water, gives water at the expense of all the contained oxygen, and of the hydrogen of the ammonium—that is, there is formed NHNN , in which two of nitrogen remain from ammonium groups, and only one atom of nitrogen from nitric acid, whilst the hydrogen atom also belongs to the elements of ortho-nitric acid.¹¹ Hence this hydrogen should have the same character as in acids, and not as in ammonia; considering also the energetic acid property of nitric and nitrous acids compared with carbonic acid, for example, and the position occupied by nitrogen in the periodic system which assigns to it more marked acid-forming properties than carbon—it follows that the compound N_3H should have a distinctly acid character, being a nitrile. This conclusion is based on the fact that hydrocyanic acid, the nitrile of formic acid, has a distinctly acid character, notwithstanding that the hydrogen atom of the nitrile, when forming a component of the molecule of formic acid, is not replaceable by metals, and that it is under the influence of carbon—a feeble acid-forming element than nitrogen. The hydrogen atom in hydrocyanic acid has evidently acquired a feeble acid character under the influence of the nitrogen and carbon as acid elements.¹² And since the hydrogen atom in hydronitrous acid is in combination only with such a distinctly acid element as nitrogen, it should acquire the property of being replaceable by metals, even to a greater degree than the hydrogen atom in hydrocyanic acid, so

¹¹ According to the hypothesis of the structuralists the structure of hydronitrous acid may, in this sense, be expressed by taking one of the component nitrogen atoms as quinquivalent, and united to H and 2N by its five affinities, and both the other atoms of nitrogen as trivalent, and united together by one affinity. It may be more simply, but just as hypothetically, supposed that one nitrogen is trivalent and uniting both H and 2N by its affinities, and supposing that these two nitrogens are univalent, as in nitrous oxide, N_2O . The latter mode of representation expresses the near relation existing between nitrous oxide and hydronitrous acid, as: $\text{NH}_3 + \text{N}_2\text{O} = \text{H}_2\text{O} + \text{NHNN}_2$.

¹² The fact that carbon has a distinct, although feeble, acid character is easily seen in the hydrocarbons containing a small amount of hydrogen (for instance, acetylene), because the hydrogen of such hydrocarbons is replaceable by metals. The connection between acetylene and hydrocyanic acid is beyond doubt. Besides which, it is known from L. N. Shiskoff's researches that nitroform, or trinitromethane, $\text{CH}(\text{NO}_2)_3$, has sharply defined acid properties, owing evidently to the presence of such acid elements as the nitro-group and carbon.

that the compound N_3H must have the properties of an acid. That nitrogen has a more distinctly acid character than carbon is also seen from the fact that the hydrogen in ammonia is more readily and directly replaced by metals—for instance, by sodium—than the hydrogen in marsh gas or ethane; this is mainly due to the different nature of nitrogen and carbon, as is also expressed by their respective positions in the periodic system of the elements.

Thus it seems to me that the acid character of N_3H is as easily understood as that of hydrocyanic acid, although they are both nitriles.

If hydronitrous acid is really a nitrile it should, like the cyanogen compounds, have many peculiar properties. As certain of these relations have not yet been investigated for hydronitrous acid, I think it will not be superfluous, in passing, to mention those which, in my opinion, may be found to a greater or less extent in a further research into the substances discovered by Curtius.

The most remarkable properties shown by the cyanides are : (1) Polymerisation; for example, the formation of cyanuric acid, solid cyanogen chloride, &c. (2) The faculty of giving complex compounds (for example, the formation of stable double salts like $K_4FeC_6N_8$); and (3) Isomerism—for instance, the passage of ammonium cyanate into urea, &c.—which for a long time confused the study of these compounds, but which can now be foreseen from the fact that the cyanides are substances which can proceed from the loss of water from ammonium salts. Thus the faculty of forming polymerides and complex salts should be understood as a propensity to combine with foreign molecules in the place of those molecules of water which have been separated in the formation of cyanides.

Properties resembling these, with certain individual differences, should be met with in the nitriles of nitric acid, or in the compounds discovered by Curtius, if they are nitriles, as may be thought from the above.

For example, the ammonium salt of hydronitrous acid, $N_3 \cdot NH_4$, as a clearly asymmetrical compound, to a certain extent analogous to ammonium cyanate, will probably under certain circumstances (perhaps on heating its solution) undergo intramolecular change and be converted into a symmetrical amide $NH_2 \cdot N : N \cdot NH_2$, corresponding with the amido-nitrile of tri-ammonium orthonitrate, $NO(OH_4)(OH_4)(OH_4)$.

Equally to be desired would be a research on the double salts of hydronitrous acid, all the more as the general character (*e.g.* the insolubility of the silver salt) of the salts of this acid recall the properties of the cyanides. If we suppose, for instance, that it forms a double salt with iron and potassium, then it will probably give a series of characteristically-coloured salts like the ferrocyanides, and also a series of compounds corresponding with prussian blue, Fe_4N_{10} , which, if capable of existence in a hydrate, would doubtless be explosive.

As regards the faculty of hydronitrous acid and its derivatives for polymerisation, it may be assumed that this is already indicated by the behaviour of the analogous compounds of phosphorus. This is probably connected with the fact that phosphorus, the analogue of nitrogen, polymerises more easily than it, as is seen not only in the varieties of ordinary and red phos-

phorus, but also in the fact that the molecule of phosphorus vapour, even at very high temperatures, contains P_4 , and does not give P_2 , whilst nitrogen is only known in the state of N_2 . In fact, as the vapour density of chlorphosphamide (Gladstone, Wichelhaus) indicates a molecule of the form $P_3N_3Cl_3$, so also phospham is probably a polymeride of the composition $(PN_2H)_n$, and not an exact analogue of hydronitrous acid, although it offers some resemblance to it, inasmuch as it contains the elements in the ratio PHN_2 .¹⁵

At all events, the further investigation of hydronitrous acid and its derivatives should be the means of throwing much light on our store of knowledge of the nature of nitrogen and its compounds—that is, it is desirable that this subject should be worked out in all its details, and there is reason to think that this would much aid the further progress of all chemical data.

¹⁵ An examination of the composition and properties of phospham given by me in the *Principles of Chemistry* (1st edition), was the natural source from which I arrived at the prediction of the existence of NHN_2 which I mentioned above.

INDEX OF AUTHORITIES

ABA

A

ABASHEFF, i. 74
 Abel, i. 549; ii. 53
 Alexéeff, i. 74, 93
 Alluard, i. 452
 Amagat, i. 131
 Amat, ii. 164
 Ammermüller, i. 503
 Ampère, i. 252, 302
 Andréeff, i. 248
 Andrews, i. 135, 202; ii. 147
 Ångström, i. 554
 Angus Smith, i. 43
 Ansdell, i. 444
 Anthon, ii. 279
 Arfvedson, i. 567
 Arrhenius, i. 88, 323, 378
 Arthur, ii. 408
 Aschoff, ii. 298
 Aubel, ii. 43
 Aubin, i. 235
 Avdéeff, i. 609
 Avogadro, i. 302

B

BABO, v., i. 91, 199, 203
 Baeyer, v., i. 355, 500; ii. 153
 Bagouski, i. 372
 Bahr, ii. 90
 Bailey, i. 441
 Balard, i. 474, 488, 489, 499
 Ball, ii. 386
 Bannoff, i. 499
 Barfoed, ii. 50
 Barreswil, ii. 271
 Barret, ii. 317
 Baudrimont, ii. 35
 Baumé, i. 193
 Baumgauer, ii. 19
 Baumhauer, i. 489
 Bayer, ii. 73
 Bazaroff, i. 397; ii. 23, 65
 Beckmann, i. 90
 Becquerel, i. 225; ii. 92, 214, 288

BOU

Behemann, ii. 42
 Beilby, i. 70
 Beilstein, i. 302
 Beketoff, i. 119, 121, 123, 144, 453, 460,
 526, 531, 566, 568; ii. 97, 276, 397
 Bence-Jones, i. 566
 Bender, i. 418
 Benedict, ii. 62
 Berglund, ii. 223
 Bergman, i. 425
 Bernados, ii. 317
 Bernoulli, i. 80
 Bernthsen, ii. 222
 Bert, i. 86, 152
 Berthelm, ii. 318
 Berthelot, i. 171, 227, 259, 260, 265, 269,
 276, 340, 360, 405, 429, 446, 450, 457,
 496, 500, 510, 520, 521, 529, 600;
 ii. 44, 53, 60, 159, 199, 203, 242, 386,
 392
 Berthier, ii. 7
 Berthollet, i. 119, 380, 423, 453, 464
 Berzelius, i. 130, 147, 193, 252, 367;
 ii. 7, 65, 95, 141, 142, 158, 213, 262,
 270, 285, 342, 357, 365, 400
 Beudant, ii. 7
 Bineau, i. 99, 265, 444, 498; ii. 206, 232
 Binget, i. 74
 Blagden, i. 90, 417
 Blake, ii. 28
 Blitz, ii. 177
 Blomstrand, ii. 278, 284, 368
 Bodart, i. 604
 Bodeman, ii. 307
 Böttcher, ii. 314
 Boguzsky, i. 132
 Boilleau, i. 405
 Boisbaudran, i. 95, 558, 564, 578, 591,
 600, 602; ii. 5, 17, 78, 84, 89, 272
 Bolley, ii. 60
 Bolton, ii. 288
 Bonsdorff, ii. 354
 Bornemann, i. 501
 Botkin, ii. 28
 Bouchardat, ii. 42
 Boullay, ii. 51

BOU

Bourdiakoff, i. 608
 Boussingault, i. 230, 518, 606
 Boyle, i. 124
 Brand, ii. 145
 Brandes, i. 71
 Bravais, i. 230
 Brauner, i. 483; ii. 17, 25, 26, 89, 138, 187, 263, 408
 Brewster, i. 554
 Brodie, i. 200, 340, 393; ii. 167, 242
 Brooke, ii. 338
 Brown, i. 80, 87
 Brühl, i. 324
 Brunner, i. 123, 144, 230, 526; ii. 294
 Buckton, ii. 138, 368
 Buff, ii. 94, 97
 Bunge, i. 280
 Bunsen, i. 68, 116, 130, 156, 458, 459, 507, 549, 559, 568, 577; ii. 44, 85, 90, 276
 Burdakoff, i. 575
 Bussy, i. 74, 585, 610
 Butleroff, i. 356; ii. 11, 138
 Bystrom, i. 576

C

CAGNIARD DE LATOUR, i. 135, 334
 Cahours, ii. 138, 166
 Cailletet, i. 131, 136; ii. 42, 204
 Calvert, i. 478; ii. 42
 Cannizzaro, i. 575, 578
 Carey-Lea, ii. 396
 Carius, i. 68
 Carnelley, i. 416, 477, 507, 546; ii. 17, 21, 28, 61, 134, 138
 Caro, i. 601
 Caron, i. 594, 604; ii. 315
 Carré, i. 247
 Cavazzi, ii. 153, 165, 175
 Cavendish, i. 112, 124, 225
 Chabrière, i. 227
 Chance, ii. 197
 Chancel, ii. 168
 Chappuis, i. 59, 198, 205, 259
 Cheltzoff, i. 450; ii. 38, 44, 238
 Cherikoff, ii. 97
 Chevillot, ii. 295
 Chevreul, i. 522
 Christomanos, i. 503
 Chroustchoff, i. 171; ii. 88, 105, 117
 Chydenius, ii. 143
 Ciamician, i. 557, 565
 Classen, ii. 141
 Claus, ii. 341, 349, 357, 365, 367
 Clausius, i. 80, 139, 302; ii. 44
 Clement, i. 488
 Cleve, ii. 17, 25, 88, 354, 368
 Cloez, i. 243, 364; ii. 199

DOS

Comaille, i. 586
 Connell, i. 501
 Cooke, ii. 179
 Cooper, ii. 11
 Coppet, i. 591
 Corenwinder, i. 495
 Cornu, i. 515, 554
 Cossa, ii. 91
 Courtois, i. 488
 Crafts, i. 419; ii. 77, 79
 Crompton, i. 238
 Crookes, i. 132, 608; ii. 19, 86, 91, 406
 Crookewitt, i. 529
 Crum, ii. 75, 296
 Cundall, i. 602
 Curtius, i. 287

D

DAHL, ii. 55
 D'Ally, ii. 61
 Dalton, i. 40, 108, 244, 265
 Dana, ii. 8
 Davy, i. 37, 352, 454, 457, 483, 487, 488, 526, 532, 587, 594, 608; ii. 63, 65
 Deacon, i. 455, 590
 Debray, i. 599; ii. 42, 117, 278, 280, 359, 384, 386
 De Chancourtois, ii. 17, 19, 438
 De Coppel, i. 90, 417
 De Forcrand, ii. 105, 204
 De Haën, i. 138; ii. 182
 Deherain, ii. 382
 Delafontaine, ii. 89, 143, 191, 279
 De la Rive, i. 198; ii. 219
 Del-Rio, ii. 190
 Demel, ii. 333
 De Saint Gilles, ii. 324
 De Saussure, i. 233, 237, 337
 Descartes, i. 217
 De Schulten, ii. 45
 Despretz, ii. 147
 Deville, St.-Claire, i. 45, 141, 227, 230, 273, 294, 381, 388, 461, 470, 494, 526, 690; ii. 45, 64, 77, 81, 96, 142, 151, 191, 200, 275, 294, 306, 350, 356, 357, 391, 397
 De Vries, i. 64, 322, 418, 539
 Dewar, i. 134, 138, 290, 554, 560, 562, 576; ii. 169
 Diesbach, ii. 332
 Dingwall, i. 480
 Ditte, i. 71, 420, 450, 603, 604; ii. 61
 Dittmar, i. 99; ii. 233, 408
 Divers, i. 287
 Dixon, i. 391, 534
 Döbereiner, i. 143
 Dokouchaëff, i. 333; ii. 69
 Donny, i. 527
 Dossios, i. 496

DRA

Draper, i. 458
 Drawe, ii. 155
 Drion, i. 135
 Dulong, i. 130, 147, 470, 574
 Dumas, i. 130, 147, 367, 465; ii. 17, 21,
 23, 34, 59, 75, 157, 200, 406

E

EBELMANN, ii. 62
 Eder, i. 558
 Edwards, ii. 295
 Egoreff, i. 560
 Einhardt, ii. 35
 Ekeberg, ii. 190
 Elbers, ii. 215
 Emery, ii. 72
 Engel, i. 450; ii. 125, 182
 Erdmann, i. 147; ii. 406
 Eroféeff, i. 341
 Esson, ii. 299
 Étard, i. 71; ii. 380
 Ettinger, i. 52, 306

F

FAIRLEY, ii. 244, 288
 Famintsin, i. 602
 Faraday, i. 133, 175, 247, 373, 458
 Favorsky, i. 361
 Favre, i. 119, 170, 260, 337, 361; ii. 44,
 147, 203, 249, 273
 Federoff, i. 549
 Fick, i. 62
 Fisher, ii. 392
 Fizeau, ii. 29, 397
 Flavitzky, i. 20
 Fleitmann, ii. 163
 Forchhammer, ii. 295
 Fordos, ii. 247
 Foucault, i. 554
 Fourcroy, i. 105, 113
 Fowler, i. 161, 441
 Franke, ii. 295, 298
 Frankenheim, ii. 7
 Frankland, i. 44, 176, 345, 480; ii. 138
 Frauenhofer, i. 554
 Frémy, i. 225, 483; ii. 126, 129, 137,
 138, 222, 277, 339
 Friedau, ii. 105
 Friedel, i. 466; ii. 77, 79, 97, 117
 Fritzsche, i. 46, 92, 278, 590, 603;
 ii. 121, 212, 269, 357
 Frombert, ii. 298
 Fürst, i. 487

VOL. II.

HAN

G

GAHN, ii. 294
 Garzarolli-Thurnlackh, i. 476
 Gattermann, i. 586
 Gautier, ii. 254
 Gay, i. 280
 Gay-Lussac, i. 40, 61, 71, 91, 132, 297,
 394, 402, 454, 457, 458, 488, 494, 499,
 501, 503, 526, 534, 549, 603; ii. 7,
 53, 63, 65, 246
 Gelis, ii. 247
 Genth, ii. 339
 Georgiewitsch, ii. 60
 Gerberts, i. 519
 Gerhardt, i. 31, 302, 376, 345; ii. 168,
 365, 368
 Gerlach, i. 418, 516
 Gernez, i. 95; ii. 58, 198
 Geuther, i. 278, 586; ii. 101, 169, 270
 Gibbs, ii. 282, 365
 Gifford, i. 128
 Girault, i. 491
 Gladstone, i. 324, 428, 565; ii. 17, 172
 Glaisher, i. 130
 Glinka, i. 598
 Glover, ii. 223
 Gmelin, ii. 333, 360
 Goldberg, i. 92
 Gore, i. 483, 485; ii. 317
 Gorup-Besanez, i. 200
 Gossage, ii. 197
 Graham, i. 62, 63, 97, 141, 154, 376,
 418, 510, 591, 592; ii. 73, 75, 94, 108,
 126, 157, 163, 269, 282, 292, 355
 Grant, i. 516
 Grassi, i. 87
 Grimaldi, i. 529
 Gros, ii. 376
 Grosjean, i. 419
 Groth, ii. 10
 Grouven, i. 606
 Grove, i. 116
 Grünwald, i. 565
 Guckelberger, ii. 80
 Guibourt, ii. 50
 Guldberg, i. 429, 457, 508
 Gustavson, i. 435, 466, 499, 539; ii. 28,
 61
 Guthrie, i. 97, 417, 591

H

HAGEN, i. 324
 Hager, ii. 106
 Haitinger, i. 583
 Hambly, i. 486; ii. 295
 Hammerl, i. 604
 Hanisch, ii. 226
 Hannay, i. 341

II H

HAR

Harcourt, ii. 299
 Hartley, i. 565
 Hasselberg, i. 558
 Hatchett, ii. 190
 Haüy, ii. 7
 Haughton, ii. 19, 441
 Hautefeuille, i. 198, 259, 470, 495, 530,
 600; ii. 117, 150, 354
 Helmholtz, i. 217; ii. 42
 Hemilian, i. 131
 Henneberg, ii. 163
 Henning, ii. 341
 Henry, i. 46; ii. 134
 Hermann, ii. 8, 44, 190
 Hermes, i. 521
 Herschel, i. 218
 Hess, i. 171, 579
 Heycock, ii. 123
 Hillebrand, ii. 25, 88
 Hintze, ii. 10
 Hirtzel, ii. 52
 Hittorf, ii. 44, 149
 Hodgkinson, i. 161
 Höglund, ii. 89
 Hofmann, ii. 211
 Hood, ii. 300
 Hoppé-Seyler, i. 602
 Horstmann, i. 397
 Houzeau, i. 201
 Howard, ii. 52
 Huggins, i. 561
 Huth, ii. 19

I

INOSTRANTZEFF, i. 333; ii. 4
 Isambert, i. 246, 247, 354, 397
 Ittner, i. 402

J

JACQUELINE, ii. 260
 Janssen, i. 560
 Jawein, ii. 164
 Jay, i. 287
 Jeannel, i. 103
 Joannis, i. 530, 551; ii. 386
 Jörgensen, i. 491; ii. 339, 367
 Johnson, ii. 42
 Joly, ii. 359
 Joule, ii. 35

K

KAMENSKY, ii. 368
 Kammerer, i. 279, 456, 502, 604
 Kane, ii. 54

LEB

Kant, i. 233
 Kapoustin, i. 45, 392
 Kapp, i. 603
 Karsten, i. 417, 532, 590
 Kayander, i. 81, 133, 372; ii. 42
 Keiser, i. 150
 Kekulé, i. 345, 356, 500; ii. 11
 Khichinsky, i. 430
 Kimmins, i. 502
 Kirchhoff, i. 554, 559
 Kirpicheff, i. 131
 Kjeldahl, i. 246; ii. 240
 Klaproth, ii. 140, 142, 286
 Kleiber, i. 561
 Klien, ii. 314
 Klimentenko, i. 459
 Klodt, i. 415, 417
 Knopp, ii. 323
 Knox, i. 483
 Kobell, ii. 190
 Kohlrausch, i. 446, 516; ii. 44, 236
 Kolbe, i. 446, 499; ii. 365
 Konovaloff, i. 39, 89, 138, 315; ii. 228,
 258, 300
 Kopp, i. 515, 577; ii. 3, 34, 120
 Koucheroff, i. 361
 Kraevitch, i. 132
 Kraft, i. 88
 Kraut, i. 529
 Kremers, i. 86, 418, 434, 446; ii. 17,
 235
 Krönig, i. 80
 Krüger, ii. 271, 273
 Krüss, ii. 338, 408
 Kuhemann, i. 598
 Kuhnheim, i. 604
 Kurnakoff, ii. 370
 Kynaston, i. 514

L

LADENBURG, ii. 97
 Ladoffsky, i. 559
 Lamy, ii. 86
 Landolt, i. 324
 Lang, i. 388
 Langer, i. 453, 457
 Langlois, i. 503; ii. 247
 Laplace, ii. 147
 Lassen, i. 258
 Latchinoff, i. 102, 341, 450
 Laurent, i. 28, 376, 465, 518; ii. 7, 9,
 60, 111, 279
 Laurie, i. 105; ii. 30, 386, 408
 Lavoisier, i. 6, 49, 103, 130, 367, 453,
 526; ii. 147
 Le Bel, i. 356
 Leblanc, i. 241, 515; ii. 7
 Le Bon, i. 351

LEC

Le Chatelier, i. 95, 388 ; ii. 391
 Lecoq de Boisbaudran, i. 95, 558, 564,
 578, 591, 600, 602 ; ii. 5, 17, 78, 84,
 89, 272
 Lémery, i. 124
 Lemoine, i. 495, 600 ; ii. 150
 Lenssen, ii. 17
 Lenz, ii. 314
 Lerch, i. 393
 Leroy, i. 230
 Lescœur, i. 102
 Lidoff, ii. 202
 Liebig, i. 376, 489, 519 ; ii. 53, 145
 Lies-Bodart, i. 595, 604
 Lisenko, i. 362
 Liveing, i. 560, 562
 Lockyer, i. 554, 562 ; ii. 443
 Löwel, i. 516, 591 ; ii. 42, 273, 275
 Löwig, i. 520 ; ii. 35, 73
 Loewitz, i. 94
 Loff, ii. 306
 Lorenz, ii. 51
 Louget, i. 483
 Louguinine, ii. 159
 Lovel, ii. 323
 Lowe, i. 389
 Lowndes, i. 161
 Ludwig, i. 457
 Luedeking, ii. 186
 Lunge, ii. 232, 235

M

MAACK, i. 586
 Mackintosh, ii. 100
 McLeod, i. 161
 Magnus, i. 92, 142, 503 ; ii. 367
 Mailfert, i. 198
 Malaguti, i. 427 ; ii. 281, 285
 Mallard, ii. 4
 Mallet, i. 486
 Marchand, i. 43 ; ii. 406
 Maresca, i. 527
 Marguerite, ii. 279
 Marignac, i. 198, 230, 418, 445, 446,
 510, 516, 591, 603 ; ii. 5, 9, 89, 95,
 187, 190, 226, 232, 234, 279, 282, 338,
 354, 406, 408
 Markovinkoff, i. 362
 Maroffsky, ii. 132
 Maxwell, i. 80
 Mendeléeff, i. 65, 81, 133, 344, 362, 364,
 365, 394, 457, 577 ; ii. 235
 Menschutkin, i. 429 ; ii. 165, 300
 Mente, ii. 260
 Mermé, i. 456
 Meselan, i. 457
 Meusnier, i. 113
 Meyer (Lothar), i. 391, 500 ; ii. 17, 23, 25

PEB

Meyer (Victor), i. 224, 313, 453, 457,
 461 ; ii. 28, 40, 45, 77, 124, 177
 Miasnikoff, i. 361
 Michaelis, ii. 228
 Michel, i. 88, 419
 Millon, i. 475, 478, 501 ; ii. 42, 370
 Mills, ii. 20, 441
 Mitscherlich, i. 417, 519 ; ii. 1, 7, 151,
 172, 177, 200, 287, 295, 298, 338
 Moissan, ii. 306
 Monnier, i. 602
 Morton, ii. 288
 Mosander, ii. 92
 Mosberg, ii. 275
 Moss, ii. 338
 Moutier, i. 601
 Müntz, i. 235, 545
 Muhier, ii. 42
 Muir, i. 427, 430 ; ii. 185
 Muller, i. 102, 417 ; ii. 393

N

NADESCHDIN, i. 138
 Naef, ii. 235
 Nasini, i. 489 ; ii. 150, 200
 Natanson, i. 275, 397
 Natterer, i. 131, 373
 Naumann, i. 388, 397
 Nernst, i. 62 ; ii. 47
 Nessler, i. 244
 Neville, ii. 123
 Newlands, ii. 17, 438
 Nicklés, ii. 10, 293
 Nicol, i. 418
 Nilson, i. 609 ; ii. 17, 34, 77, 86, 89, 261,
 354
 Noble, i. 549
 Nordenskiöld, i. 238
 Norton, i. 75 ; ii. 89

O

OFFER, i. 97
 Ogier, i. 314, 501 ; ii. 153, 175
 Olszewski, i. 138, 560 ; ii. 154
 Oppenheim, i. 500 ; ii. 154
 Ordway, ii. 17
 Osmond, ii. 317
 Ostwald, i. 88, 377, 431 ; ii. 235, 300

P

PARACELSDUS, i. 124, 367
 Pasteur, i. 239
 Paterno, i. 489 ; ii. 200
 Pebal, i. 310, 487

PEK

Pekatoros, i. 459
 Peligot, ii. 275, 285, 286, 287
 Pelopidas, ii. 21, 445
 Pelouze, i. 174, 457, 601; ii. 222
 Penfield, ii. 347
 Penny, ii. 406
 Perseau, ii. 35
 Personne, i. 74, 499, 530
 Petit, i. 574
 Petrieff, i. 430
 Pettenkofer, i. 241; ii. 17, 21, 23
 Pettersson, i. 609; ii. 17, 34, 77, 85
 Peyronne, ii. 368
 Pfaundler, i. 437; ii. 234
 Pfeiffer, i. 64, 322, 323
 Pfordten, v. d., ii. 391
 Phillips, i. 603
 Phipson, ii. 56
 Piccini, ii. 141
 Pickering, i. 96, 103, 509, 517, 592, 604
 Pictet, i. 80, 128, 136, 142, 374; ii. 29
 Pierre, i. 445, 489; ii. 219
 Pierson, i. 91
 Pionchon, i. 576
 Pistor, i. 388
 Plantamour, ii. 52
 Playfair, ii. 35, 333
 Plessy, ii. 247
 Plücker, i. 564
 Poggendorf, ii. 44
 Poggiale, i. 417; ii. 160
 Poiseuille, i. 343
 Poisson, i. 217
 Poluta, ii. 28
 Ponton, ii. 267
 Popp, i. 529; ii. 226
 Potilitzin, i. 94, 436, 480, 493, 501; ii. 28
 Pott, ii. 294
 Poulé, i. 217
 Priestley, i. 153, 367
 Pringsheim, i. 459
 Prost, i. 97
 Proust, ii. 406
 Puchot, i. 445

Q

QUINCKE, i. 416, 489

R

RADEFFSKY, ii. 368
 Rammelsberg, i. 420, 503, 516; ii. 17, 25, 338
 Ramsay, i. 134, 138, 457, 489, 572; ii. 123
 Rantsheff, ii. 20
 Raoult, i. 90, 417; ii. 140

SCH

Raschig, i. 259; ii. 223
 Rathke, i. 388
 Rebbs, ii. 206, 211
 Regnault, i. 40, 90, 92, 130, 133, 489, 577; ii. 232, 258
 Reich, ii. 85
 Reinhold, i. 434
 Reiset, i. 235; ii. 368
 Remsen, ii. 319
 Reynolds, i. 572; ii. 19
 Richards, i. 518
 Riche, i. 502; ii. 123, 279
 Richter, i. 193; ii. 85
 Ridberg, ii. 20
 Riggs, ii. 114
 Rodger, ii. 207
 Rodgers, ii. 253
 Rodwell, i. 17
 Roozeboom, i. 105, 445, 457, 458, 489, 500, 508, 589, 604; ii. 219
 Roscoe, i. 99, 265, 367, 444, 457, 458, 459, 559, 564; ii. 17, 25, 187, 190, 278, 283, 287, 288
 Rose, i. 426, 510, 517, 598, 603; ii. 7, 60, 190, 223, 228, 240, 260, 270, 342, 408
 Rosenberg, ii. 333
 Rossetti, i. 417
 Rouelle, i. 192
 Rousseau, ii. 293
 Roussin, ii. 333
 Rudberg, ii. 131
 Rücker, i. 140
 Rüdorff, i. 90, 418, 589, 591

S

SABANÉEFF, i. 359
 Sabatier, ii. 163
 Saint Edmé, ii. 319
 Saint Gilles, i. 429; ii. 325
 Salet, i. 502
 Salm-Horstmar, i. 601
 Salzer, ii. 147, 155
 Sands, ii. 103
 Sarasin, ii. 117
 Sarrau, i. 141; ii. 105
 Sawitich, i. 361
 Schapparelli, ii. 303
 Scharples, i. 568
 Scheele, i. 159, 402, 453, 515, 598; ii. 145, 278, 294
 Scheibler, ii. 279, 283
 Scherer, ii. 8
 Schertel, ii. 235, 236
 Scheurer-Kestner, ii. 324
 Schiff, 420, 579; ii. 100, 257, 341, 365
 Schloesing, i. 235, 237, 516, 545, 601
 Schmidt, i. 241, 418, 531; ii. 338

SCH

Schneider, i. 88
 Schöne, i. 207, 210, 608; ii. 68, 213, 242
 Schönebein, i. 197, 457, 501; ii. 221
 Schott, i. 603
 Schröder, ii. 35
 Schrötter, ii. 147, 273
 Schützenberger, i. 503, 591; ii. 97, 198, 221, 363, 377
 Schuliachenko, i. 598; ii. 118
 Schultz-Sellack, ii. 226
 Schulze, i. 97; ii. 208
 Schuster, i. 564; ii. 116
 Scott, i. 393, 549
 Secchi, i. 561
 Sechenoff, i. 79, 86
 Sefström, ii. 190
 Serullas, i. 479
 Setterberg, i. 568
 Seubert, ii. 26, 408
 Shaffgotsch, i. 547
 Sheffer, i. 446
 Shepstone, i. 508, 602
 Shishkoff, ii. 53
 Sidoroff, i. 340
 Sielheim, ii. 354
 Siemens, i. 387
 Silbermann, i. 170; ii. 203, 249
 Skinder, ii. 317
 Skoblikoff, ii. 367
 Skraup, ii. 331
 Smithson, ii. 95
 Snyders, ii. 42
 Sokoloff, ii. 117, 343
 Solvay, i. 516
 Sorby, i. 87
 Soret, i. 64, 202, 416; ii. 89
 Soubeiron, ii. 260
 Spring, i. 38, 97, 424; ii. 43, 243, 248, 298, 395
 Stadion, i. 479
 Stahl, i. 16
 Stas, i. 230, 367, 417, 491, 572; ii. 390, 401, 406
 Stchefarovitch, i. 603
 Stecherbakoff, i. 95, 417, 452, 591
 Steinhil, ii. 102
 Stohmann, i. 347, 385
 Stokes, i. 343; ii. 288
 Stortenbeker, i. 504
 Strecker, ii. 438
 Stromeyer, ii. 44
 Struvé, i. 603; ii. 279, 357
 Svanberg, ii. 279

T

TAIT, ii. 317
 Tammann, i. 90; ii. 238
 Tchernoff, ii. 317

WAG

Tchitchérin, ii. 20, 441
 Tellier, i. 248
 Tennant, ii. 349, 357
 Terreil, ii. 298
 Tessié du Motoy, i. 157
 Than, i. 310; ii. 254
 Thenard, i. 206, 227, 454, 526, 534; ii. 63, 65, 242
 Thillot, ii. 164
 Thilorier, i. 373
 Thomsen, i. 110, 119, 124, 130, 171, 217, 244, 260, 347, 377, 418, 431, 433, 460, 467, 487, 495, 496, 502, 521, 546, 594; ii. 8, 30, 51, 147, 158, 201, 234, 368, 370
 Thomson, i. 507; ii. 44
 Thorpe, i. 140, 278, 436, 486; ii. 17, 26, 54, 94, 155, 167, 207, 249, 253, 295, 298, 408
 Tilden, i. 508
 Tischenko, i. 98
 Tissandier, i. 238
 Tomassi, ii. 323
 Topsöe, i. 500; ii. 354
 Trapp, i. 503
 Traubé, i. 64, 207, 305, 322, 602
 Troost, i. 274, 313, 398, 494, 530, 600; ii. 77, 141, 150, 151, 354
 Tschermak, ii. 116
 Turck, i. 516

U

UMOFF, i. 418
 Unverdorben, ii. 269
 Ure, i. 446

V

VAN DER PLAATS, i. 489
 Van der Waals, i. 81, 139
 Van Deventer, i. 589
 Van Helmont, i. 367
 Van Marum, i. 197
 Van 't Hoff, i. 64, 91, 356, 508, 589; ii. 300
 Vauquelin, i. 113, 610; ii. 7, 265, 357
 Vicat, ii. 118
 Vierordt, i. 557
 Villard, i. 105
 Violette, i. 331
 Violle, i. 294
 Vogt, i. 602
 Voronin, ii. 260
 Voskresensky, i. 334

W

WAAGE, i. 429
 Wagner, i. 344

WAL

Walker, ii. 134, 138
Walters, ii. 227
Wanklyn, i. 100, 531
Ward, i. 537
Warder, i. 441; ii. 300
Warnerke, ii. 214
Warren, ii. 97
Watson, i. 519; ii. 349
Watts, i. 518
Weber, i. 273, 541, 576; ii. 125, 127, 226, 239
Weith, i. 496
Weitz, ii. 53
Weller, ii. 141
Welsbach, ii. 92
Welsh, i. 231
Welsing, i. 586
Welter, ii. 246
Weltzen, ii. 223, 341
Weltzien, i. 203; ii. 365
Wenzel, i. 193
Wernhoff, ii. 4
Weselski, i. 500
Weyl, i. 252
Wichelhaus, ii. 172
Wiedemann, i. 429, 578
Wilhelmj, ii. 299
Willgerodt, ii. 28
Williamson, ii. 258

ZIN

Wills, ii. 347
Wilm, ii. 355
Winkler, i. 456; ii. 17, 24, 85, 120, 235
Wislicenus, i. 356
Witt, ii. 162
Wöhler, i. 398, 610; ii. 64, 81, 94, 97, 101, 141, 274, 276, 357, 392
Wollaston, i. 217; ii. 7, 349
Wreden, i. 500
Wright, ii. 306
Wroblewski, i. 78, 105, 138, 375; ii. 219
Wülffing, ii. 114
Wüllner, i. 90, 564
Würtz, i. 294; ii. 12, 51, 165, 166, 258, 381
Wyrnhoff, ii. 9

Y

YAKOBI, ii. 384
Young, i. 134, 138, 457, 489

Z

ZABOUDSKY, i. 342
Zaencheffsky, i. 138
Zimmermann, i. 17, 25, 288
Zinin, i. 269

SUBJECT INDEX

ABS

A

ABSORPTIOMETER, i. 67
 Acetic acid, i. 59
 — chloranhydride, ii. 169
 — peroxide, ii. 242
 Acetonitrile, ii. 53
 Acetylene, i. 346, 354, 360
 Acids, i. 184
 — and bases, measure of affinity of, i. 377
 — basicity of, i. 376
 Actinometer, i. 459
 Actinium, ii. 56
 Air, i. 221
 — adulteration of, i. 241
 — analysis of, i. 231
 — composition of, i. 229
 — weight of, i. 237
 Affinities, free, i. 407
 Affinity, chemical, i. 26
 Albite, ii. 116
 Albuminous substances, i. 222
 Alchemists, i. 14
 Alcohols, i. 345, 358
 Aldehydes, i. 358
 Alkali waste, ii. 224
 Alkalis, i. 185
 Alkaloids, i. 405
 Allotropism, i. 206
 Alloys, i. 105, 530
 — and salts, ii. 112
 — fusible, ii. 186
 — molecular, ii. 123
 — of copper, ii. 385
 — — lead and tin, ii. 131
 — — silicon and magnesium, ii. 97
 — — tin, ii. 122
 Alumina, ii. 71
 — as a mordant, ii. 73
 — colloidal state of, ii. 73
 — hydrosol of, ii. 75
 — solubility of, ii. 72
 Aluminates, ii. 73
 Aluminite, ii. 78
 Aluminium, ii. 66

AMM

Aluminium acetate, ii. 74
 — atomicity of, ii. 77
 — bromide, ii. 80
 — bronze, ii. 82
 — chloride, ii. 79
 — — basic, ii. 75
 — — vapour density of, ii. 77
 — chlorides, double, ii. 80
 — fluoride, ii. 81
 — iodide, ii. 80
 — metallic, ii. 81
 — nitrate, ii. 76
 — silicates, ii. 116
 — sulphate, ii. 78
 Alums, ii. 4, 71, 78
 — solubility of, ii. 79
 Alunite, ii. 76
 Amalgams, i. 530; ii. 54
 Amethyst, ii. 103
 Amides, i. 254, 278, 395, 400
 Amidogen, i. 287
 — hydrate, i. 287
 — hydrochloride, i. 287
 — sulphate, i. 287
 Amines, i. 405
 Ammonia, i. 244
 — in air, i. 241
 — heat of formation of, ii. 175
 — heat of formation of compounds of,
 i. 244
 — heat of solution of, i. 73
 — liquefaction of, i. 247
 — of crystallisation, i. 254; ii. 341, 339
 — reactions of, i. 250
 — solubility of, i. 79, 249
 Ammonio-cobalt salts, ii. 339
 Ammonia-compounds of platinum
 metals, ii. 367
 Ammonio-copper compounds, ii. 382
 Ammonio-cuprous chlorides, ii. 380
 Ammonio-metallic salts, ii. 341
 Ammonium, i. 252
 — acid carbonate, i. 395, 518
 — arsenite, ii. 178
 — bromide, i. 487

AMM

Ammonium carbonate, i. 396
 — chloride, i. 243, 300, 451
 — — solubility of, i. 452
 — chromates, ii. 258
 — derivatives of sulphur acids, ii. 259
 — magnesium orthophosphate, ii. 161
 — molybdate, ii. 279
 — nitrate, i. 267
 — nitrite, i. 277
 — orthophosphates, ii. 160
 — salts, i. 251
 — sodium phosphate, ii. 161
 — sulphate, ii. 259
 — sulphide, ii. 212
 — thiocarbimide, ii. 253
 Ammonium theory, i. 252
 Amygdalin, i. 403
 Anglesite, ii. 129
 Anhydrides, i. 182
 Anhydrite, i. 603
 Anorthite, ii. 116
 Anthracite, i. 334
 Antichlors, ii. 225
 Antimonic acid, ii. 181
 — anhydride, ii. 181
 Antimonious oxide, ii. 180
 Antimoniuretted hydrogen, ii. 181
 Antimony, ii. 179
 — bromide, ii. 182
 — chlorides, ii. 181
 — fluorides, ii. 182
 — iodide, ii. 182
 — occurrence of, ii. 179
 — oxides, ii. 180, 181
 — oxychloride, ii. 182
 — pentasulphide, ii. 215
 — reduction of, ii. 180
 — sulphides, ii. 215
 Antimony-vermilion, ii. 215
 Apatite, ii. 145
 Aqua regia, i. 461
 Aragonite, i. 602
 Argyrodite, ii. 120
 Arsenates, ii. 174
 Arsenic, ii. 172
 — acid, ii. 174
 — anhydride, ii. 174
 — antidotes for, ii. 178
 — distinction from antimony, ii. 176
 — fluorides, ii. 174
 — Marsh's test for, ii. 175
 — molecular weight of, ii. 177
 — occurrence of, ii. 173
 — oxychloride, ii. 173
 — sulphides, ii. 215
 — tribromide, ii. 174
 — trichloride, ii. 173
 — tri-iodide, ii. 174
 Arsenides, ii. 176
 Arsenious anhydride, ii. 176, 179

BIS

Arsenites, ii. 178
 Arseniuretted hydrogen, ii. 175
 Astrakhanite, i. 589
 Atmolysis, i. 156
 Atomic heats, i. 575
 — theory, i. 215
 — volumes, i. 492; ii. 32
 — weights, i. 571
 — — determination of, by periodic law,
 ii. 23, 26
 — — Stas' experiments on, ii. 401
 Atomicity, i. 407, 574
 — invariable, ii. 77
 Atoms and molecules, i. 216, 312, 315
 — mean distance between, ii. 32
 Augites, ii. 114, 116
 Auric chloride, ii. 412
 — oxide, ii. 413
 Aurous chloride, ii. 414
 — oxide, ii. 414
 Avidity, chemical, i. 433
 Azoimide, ii. 455

B

BACTERIA in water, i. 44
 Barium, i. 604
 — chlorate, i. 477
 — chloride, i. 606
 — — solubility of, i. 606
 — hydroxide, i. 607
 — metatungstate, ii. 281
 — nitrate, i. 606
 — oxide, i. 156, 607
 — — solubility of, i. 607
 — peroxide, i. 156, 608
 — platinocyanide, ii. 361
 — preparation of, i. 608
 — salts, solubility of, i. 608
 — sulphate, i. 427, 605
 Bases, i. 182
 Basicity of acids, i. 376
 Bauxite, ii. 72
 Benzene, nitro-, i. 267
 Berthollet's doctrine, i. 423, 493
 Beryl, i. 609
 Beryllium, i. 609
 — atomic weight of, i. 318, 575, 609
 — oxide, i. 609
 — salts of, i. 610
 Bicarbonates, solubility of, i. 518
 Bismuth, ii. 182
 — and lead, resemblance between, ii. 183
 — carbonate, ii. 184
 — extraction of, ii. 183
 — hydroxide, ii. 184
 — nitrates, ii. 185
 — occurrence of, ii. 183
 — pentoxide, ii. 183
 — suboxides, ii. 182

BIS

- Bismuthous oxide, ii. 184
- Blast furnace, ii. 308
- Bleaching powder, i. 161, 471
- Bloomery process, ii. 312
- Boiling point, absolute, i. 135
- Bones, composition of, ii. 145
- Boracite, ii. 58
- Borax, ii. 58, 60
- Boric acid, ii. 59
 - — solubility of, ii. 61
 - anhydride, ii. 61
- Boron, ii. 57
 - amorphous, ii. 63
 - and aluminium, ii. 63
 - bromide, ii. 66
 - chloride, ii. 66
 - crystalline, ii. 63
 - fluoride, ii. 64
 - nitride, ii. 64
 - sulphide, ii. 59
 - trioxide, ii. 57
- Brass, ii. 385
- Braunite, ii. 291
- Bromine, i. 487
 - preparation of, i. 488
 - properties of, i. 489
 - solubility of, i. 489
 - vapour tension of, i. 489
- Bronze, ii. 122
- Brucite, i. 587
- Buckton's salt, ii. 370

C

- CADMIUM, ii. 44
 - compounds, heat of formation of, ii. 48
 - iodide, ii. 45
 - oxide, ii. 45
 - sulphate, ii. 45
 - sulphide, ii. 45
- Cæsium, i. 568
- Calc spar, i. 601
- Calcedony, ii. 105
- Calcium, i. 581, 594
 - aluminate, ii. 73
 - borate, ii. 58
 - carbonate, i. 583, 601
 - — acid salt of, i. 601
 - — and sugar, i. 599
 - — colloidal form of, i. 602
 - — crystallo-hydrate of, i. 601
 - — dimorphism of, i. 601
 - — dissociation of, i. 599
 - chloride, crystallo-hydrate of, i. 604
 - — solubility of, i. 604
 - chlorite, i. 613
 - dichromate, ii. 267
 - fluoride, i. 484
 - hydrosulphide, ii. 214
 - hydroxide, i. 582

CHE

- Calcium iodide, i. 541, 595
 - oxide, i. 595
 - pentasulphide, ii. 214
 - peroxide, i. 598
 - phosphate, ii. 161
 - phosphide, ii. 152
 - preparation of, i. 594
 - properties of, i. 594
 - silicates, ii. 115
 - sulphate, i. 420, 602
 - — double salts of, i. 603
 - — solubility of, i. 603
 - sulphide, i. 512; ii. 214
 - sulphite, ii. 220
- Carbamides, i. 397
- Carbon, i. 326
 - allotropic forms of, i. 339
 - atomic heat of, i. 576
 - bisulphide, ii. 249
 - — heat of combustion of, ii. 250
 - estimation of, i. 372
 - molecule, complexity of, i. 341
 - monosulphide, ii. 249
 - oxysulphide, ii. 254
 - reactions of, i. 338
 - tetrachloride, i. 467
- Carbonates, i. 376
- Carbonic anhydride, i. 367
 - — composition of, i. 368
 - — decomposition of, i. 381
 - — in air, i. 235
 - — liquefaction of, i. 373
 - — occurrence of, i. 368
 - — preparation of, i. 370
 - — properties of, i. 373
 - — solubility of, i. 79
 - oxide, i. 385
 - — combinations of, i. 392
 - — dissociation of, i. 388
 - — properties of, i. 391
 - — preparation of, i. 390
- Carbonyl chloride, ii. 168
- Carboxyl, i. 384
- Carnallite, i. 410, 536, 589
- Cassel's paint, ii. 135
- Catalytic phenomena, i. 210
- Celestine, i. 605
- Cellulose, nitro-, i. 268
- Cementation, ii. 312
- Cements, ii. 117
- Cerite metals, ii. 88
 - — separation of, ii. 90
- Cerium, ii. 88
 - and the periodic law, ii. 25
 - fluoride, i. 483
- Chamber crystals, ii. 223
- Charcoal, i. 332, 336
 - absorptive power of, i. 337
- Chemical action. *See* INTERCHANGE
 - affinity, i. 26

CHE

Chemical avidity, i. 433
 — energy, i. 30
 — equilibrium, i. 33
 — mechanics, i. 29, 498
 China-ware, ii. 71
 Chloranhydrides, i. 461 ; ii. 167
 Chlorates, i. 476
 Chloric acid, i. 476
 — peroxide, i. 478
 Chlorides, i. 448, 460
 Chlorine, i. 453
 — and ammonia, i. 469
 — and hydrocarbons, i. 465
 — and hydrogen, action of light on, i. 458, 459
 — and oxygen, relation between, i. 455
 — and the law of substitution, i. 464
 — bleaching action of, i. 464
 — chemical character, i. 463
 — crystallo-hydrates of, i. 457, 458
 — monoxide, i. 473
 — — thermal data for, i. 475
 — oxides, i. 475
 — preparation of, i. 454
 — preparation of, by Coleman's process, i. 457
 — preparation of, by Deacon's process, i. 455
 — preparation of, by Weldon's process, i. 456
 — preparation of, by Weldon-Pechiny's process, i. 455
 — properties of, i. 457
 — solubility of, i. 457
 Chloroform, i. 467
 Chlorophosphamide, ii. 172
 Chloroplatinophosphorous acid, ii. 363
 Chlorosulphonic acid, ii. 258
 Chlorous acid, i. 475
 Chromates, ii. 268
 Chrome alum, ii. 272
 — — varieties of, ii. 272
 Chrome-iron-ore, ii. 266
 Chromic anhydride, ii. 269
 — chloranhydride, ii. 270
 — chloride, ii. 274
 — oxide, ii. 274
 — salts, modifications of, ii. 273
 Chromium, ii. 265
 — dioxide, ii. 270
 — fluoride, ii. 269
 — hydroxides, ii. 273
 — metallic, ii. 274
 — nitride, ii. 275
 — occurrence of, ii. 265
 — oxychlorides, ii. 276
 — peroxide, ii. 271
 Chromous oxide, ii. 275
 — salts, ii. 275
 Chromyl chloride, ii. 270

CUP

Chryseone, ii. 101
 Chrysoberyl, ii. 76
 Cinnabar, ii. 46, 216
 Clay, ii. 116
 — composition of, ii. 69
 — formation of, ii. 66
 — plasticity of, ii. 70
 Coal, i. 334
 Cobalt chloride, i. 94
 — hydroxides, ii. 338
 — occurrence, ii. 335
 — ores, treatment of, ii. 336
 — oxides, i. 161
 — position of in the periodic system, ii. 333
 — sulphate, ii. 338
 Cobaltamine salts, ii. 339
 Cobaltic oxide, ii. 340
 Coke towers, i. 442
 Collodion, i. 268
 Colloids, i. 62 ; ii. 73, 110
 Columbite, ii. 190
 Combining weights, i. 21
 Combustion, i. 163, 330
 — heat of, i. 170
 Compounds, complex, theory of, ii. 366
 — definite and indefinite, i. 32, 103
 Contact action, i. 38, 480, 520
 Copper, ii. 373
 — action of acids on, ii. 377
 — and ammonia, ii. 377
 — arsenites, ii. 178
 — carbonate, ii. 383
 — carbonates, basic, ii. 383
 — dioxide, ii. 378
 — hydride, ii. 381
 — nitrate, basic, ii. 383
 — nitride, ii. 382
 — ores, ii. 374
 — peroxide, ii. 378
 — phosphates, ii. 163
 — position of, in the periodic system, ii. 371
 — salts, spectra of, i. 564
 — smelting, ii. 375
 — thiosulphates, ii. 226
 — *See also* CUPRIC and CUPROUS
 Corrosive sublimate, ii. 51
 Corundum, ii. 72
 Crenic acid, i. 333
 Crookesite, ii. 87
 Cryohydrates, i. 97
 Cryolite, i. 484 ; ii. 47, 81
 Crystalline form and composition, ii. 7
 Crystallisation, ii. 7
 Crystallo-hydrates, i. 95, 101
 Crystalloids, i. 63
 Crystals, i. 51
 Cupellation, ii. 387
 Cupric oxide, ii. 381, 378

CUP

- Cupric nitrate, ii. 383
- sulphate, ii. 384
- Cuprous chloride, ii. 380
- cyanide, ii. 381
- fluoride, ii. 381
- iodide, ii. 381
- sulphite, ii. 380
- Cyamelide, i. 398
- Cyanic acid, i. 398
- Cyanides, i. 400, 544
- Cyanogen, i. 394, 404
- chloride, ii. 169
- compounds, i. 394
- — polymerism of, i. 398
- Cyanuric acid, i. 393

D

- DATHOLITE, ii. 58
- Decipium, ii. 92
- Densities of vapours and gases, determination of, i. 293
- Detonating gas, i. 114
- Diacetylene, i. 355
- Dialysis, i. 63; ii. 108
- Diamond, i. 340
- Dianic acid, ii. 190
- Diaspore, ii. 72
- Didymium, ii. 88
- absorption spectrum of salts of, i. 558
- Dimercurammonium hydroxide, ii. 53
- Dimetaphosphoric acid, ii. 163
- Dimorphism, i. 601
- Diphosphamide, ii. 171
- Disinfection, i. 242
- Disodium orthophosphate, 159
- Dissociation, i. 36, 600
- measure of, i. 275
- of nitrogen peroxide, i. 275
- tension, i. 599
- Dithionates, ii. 247
- Dithionic acid, ii. 246
- Dolomites, i. 583
- Double decomposition, i. 423, 505
- Dyeing, ii. 74
- Dyes, fixed, ii. 73

E

- EAU DE JAVELLE, i. 471
- Efflorescence, i. 101
- Ekaaluminium, ii. 25, 84
- Ekaboron, ii. 25, 89
- Ekaadmium, ii. 55
- Ekaasilicon, ii. 24, 120
- Electricity, chemical effect of, i. 37
- Electro-plating, i. 543
- Electrolysis, ii. 44

FLI

- Elements, i. 19
- complexity of, i. 562; ii. 406
- grouping of, i. 569, 481, 492; ii. 1, 16, 19
- intrinsic, i. 23
- of copper group, ii. 371
- of 4th group, even series, ii. 139
- of 5th group, ii. 144
- of 5th group, even series, ii. 186
- of 6th group, even series, ii. 265
- of 8th group, ii. 302
- of iron group, ii. 334
- symbols of, i. 21
- typical, i. 18
- Emerald, i. 609
- Emulsions, i. 96
- Endothermal reactions, i. 146
- Enstatite, ii. 113
- Equations, chemical, i. 271
- Equilibria, chemical, i. 33, 212, 427; ii. 420
- Equivalents, chemical, i. 193, 572
- Erbium, ii. 90
- Ereméeffite, ii. 58
- Ethanes, i. 354
- Ethyl, compounds of Hg, Zn, S, and O, ii. 193
- metasilicate, ii. 98
- orthosilicate, ii. 98
- platincyanide, ii. 361
- Ethylbenzene, i. 346
- Ethylene, i. 354, 358
- Euchlorine, i. 487
- Eudiometer, i. 167
- Euxenite, ii. 89
- Exothermal reactions, i. 146
- Explosives, ii. 53

F

- FELSPARS, ii. 66, 115, 117
- Ferric acid, ii. 326
- chloride, ii. 324
- compounds, ii. 321
- hydroxides, ii. 323
- nitrate, ii. 324
- oxide, ii. 323
- — colloidal form of, ii. 324
- phosphates, ii. 325
- Ferrocyanides, i. 401; ii. 324
- Ferromanganese, ii. 311
- Ferrous chloride, ii. 320
- compounds, ii. 321
- hydroxide, ii. 320
- iodide, i. 542
- sulphate, ii. 320
- — solubility of, i. 71
- sulphide, ii. 203
- Flames, i. 175
- Flint, ii. 105

FLU

- Fluoborates, ii. 65
- Fluorides, i. 486
- Fluorine, i. 483
- Fluosilicates, ii. 101
- Fordos & Geills' salt, ii. 414
- Formic acid, i. 393
- Fraunhofer lines in spectrum, i. 553
- Freezing mixtures, i. 75
- Fuel, gaseous, i. 386
- heat evolved in combustion of, i. 347
- Fulminates, ii. 52
- Furnace, blast, ii. 308
- regenerative, i. 387
- reverberatory, i. 513
- Fusco-cobaltic salts, ii. 340

G

- GADOLINITE, ii. 88
- metals, ii. 88
- — separation of, ii. 90
- Galena, ii. 129
- Gallium, ii. 25, 84
- chloride, ii. 78
- Galvanoplastic art, ii. 384
- Gas generator, i. 386
- coal-, i. 348
- producer, i. 386
- Gases and liquids, relation between, i. 139
- coefficient of solubility of, i. 68
- collection of, i. 125
- density of, i. 293
- kinetic theory of, i. 80
- latent heat of and molecular weight, i. 321
- liquefaction of, i. 133, 136
- maximum tension of, i. 134
- moisture in, calculation of, i. 40
- occlusion of, i. 141
- permanent, i. 133
- preparation of, i. 125
- relation between volume and molecular weight in, i. 320
- tension of liquefied, i. 134
- velocity of sound through, i. 321
- vis viva of, i. 321
- Gelatin, ii. 109
- German silver, ii. 344
- Germanium, ii. 25, 120
- and the periodic law, ii. 120
- chloride, ii. 120
- oxide, ii. 120
- Germes in air, i. 239
- Gilding, electro-, ii. 415
- Glass, composition of, ii. 118
- manufacture of, ii. 119
- soluble, ii. 105
- Glasses, ii. 62

HYD

- Glauber's salt, i. 509
- Glauberite, i. 603
- Glycol, ii. 111
- Gold, ii. 407
- assay of, ii. 411
- chlorides, ii. 412
- cyanides, double, ii. 414
- fulminating, ii. 414
- hydroxide, ii. 413
- occurrence, ii. 409
- oxides, ii. 413
- refining, ii. 414
- salts, double, ii. 413
- thiosulphates, double, ii. 414
- *See also* AURIC and AUROUS
- Gradators, ii. 413
- Graphite, i. 339
- Graphitic acid, i. 340
- Gros's salt, ii. 367
- Guignet's green, ii. 273
- Guncotton, i. 268
- Gunpowder, i. 548
- Gypsum, i. 584, 602

H

- HAEMATITE, ii. 304
- Halogen acetates, i. 571
- Halogens, atomic volumes of, i. 492
- combinations of, i. 503
- grouping of, i. 481, 492
- properties of, i. 481, 493
- thermal data for, i. 487, 496
- Haloid salts, i. 449
- Hausmanite, ii. 291
- Heat evolved in combustion of fuels, i. 347
- latent, and molecular weight of gases, i. 321
- — of evaporation and dissociation, i. 600
- — of fusion of some metals, i. 520
- of combustion, determination of, i. 170
- Heavy spar, i. 605
- Helium, i. 561
- Hemimorphism, ii. 8
- Hexametaphosphoric acid, ii. 164
- Holmium, ii. 88
- Homeomorphism, ii. 2, 8
- Homologous series, i. 345
- Humic substances, i. 332
- acid, i. 333
- Hydrargillite, ii. 72
- Hydrates, i. 107
- Hydrazine, i. 287
- Hydrides, heat of formation of, i. 601
- Hydriodic acid, i. 497
- — dissociation of, i. 498
- — gaseous, preparation of, i. 498

HYD

- Hydriodic acid, hydrocarbons and, i. 500
 — — sp. gr. of solutions of, i. 500
 Hydrobromic acid, i. 497
 — — crystallo-hydrates of, i. 500
 — — gaseous, preparation of, i. 498
 — — sp. gr. of solutions of, i. 500
 Hydrocarbons, i. 326, 342
 — — heat of combustion of, i. 347
 — — isomerism of, i. 356
 — — of C_nH_{2n} series, i. 355
 — — of C_nH_{2n+2} series, i. 345
 — — polymerism of, i. 355
 — — saturated, i. 344
 — — structure of, i. 386
 — — types of substitution in, i. 353; ii. 428
 — — unsaturated, i. 354
 Hydrochloric acid, i. 444
 — — crystallo-hydrate of, i. 444
 — — decomposition of, i. 453
 — — heat of formation of, i. 459
 — — heat of solution of, i. 445
 — — preparation of, i. 440, 443
 — — rate of diffusion of in solutions, i. 446
 — — solubility of, i. 445
 — — sp. gr. of solutions of, i. 446
 — — sp. heat of solutions of, i. 445
 Hydrochlorides, i. 450
 Hydrocyanic acid, i. 400, 402
 Hydroferricyanic acid, ii. 332
 Hydroferrocyanic acid, ii. 330
 Hydrofluoboric acid, ii. 65
 Hydrofluoric acid, i. 485
 — — polymerisation of, i. 486
 Hydrofluosilicic acid, ii. 100
 Hydrogels, ii. 73, 109
 Hydrogen and non-metals, heat of combination with, ii. 201
 — — and oxygen compounds, types of, ii. 357
 — — density of, i. 130, 531
 — — nitride, ii. 455
 — — occlusion, i. 141
 — — pentasulphide, ii. 211
 — — peroxide, i. 206
 — — polysulphides, ii. 211
 — — preparation of, i. 121
 — — reactions of, i. 143
 — — solubility of, i. 142
 Hydronitrous acid, ii. 455
 Hydroplatinocyanic acid, ii. 361
 Hydro ruthenocyanic acid, ii. 362
 Hydrosols, i. 97; ii. 73, 109
 Hydroxyl, i. 211
 Hydroxylamine, i. 285
 Hypochlorous acid, i. 473
 Hyponitrites, i. 287
 Hypophosphates, ii. 155
 Hypophosphoric acid, ii. 155
 Hypophosphorous acid, ii. 165
 Hyposulphurous acid, ii. 222

ITA

I

- ICE, temperature of formation of, i. 90
 Ilmenic acid, ii. 190
 Imides, i. 254
 India-rubber, passage of gas through, i. 155
 Indium, ii. 85
 — — oxide, ii. 34
 Interchange between acids and alcohols, i. 429
 — — between the halogens, i. 493
 — — algebraical expression for, i. 430
 — — Berthelot's and St. Gilles experiments on, i. 429
 — — Gladstone's experiments on, i. 428
 — — Gustavson's experiments on, i. 435
 — — Malaguti's experiments on, i. 427
 — — Ostwald's experiments on, i. 433
 — — Thomsen's experiments on, i. 431
 Iodic acid, i. 501
 — — sp. gr. of solutions of, i. 502
 Iodine, i. 490
 — — absorption spectrum, i. 558
 — — metalepsis with, i. 466
 — — monochloride, i. 503
 — — preparation of, i. 490
 — — reducing action of, i. 490
 — — solubility of, i. 491
 — — trichloride, i. 503
 — — vapour density of, i. 313
 Iridious oxide, ii. 357
 Iridium, ii. 357
 — — and the periodic law, ii. 25
 — — chlorides, ii. 357, 359
 — — separation of, ii. 357
 Iron, ii. 302
 — — arsenite, ii. 178
 — — cast, ii. 310
 — — combinations of, ii. 327
 — — cyanogen compounds of, ii. 328
 — — electro-deposition of, ii. 314
 — — magnetic oxide, ii. 321
 — — meteoric, ii. 344
 — — nitrates, basic, ii. 325
 — — ores, ii. 304
 — — oxides, reduction of by hydrogen, ii. 306
 — — passive state of, ii. 319
 — — properties, ii. 317
 — — pyrites, ii. 303
 — — recalcence of, ii. 317
 — — smelting of, ii. 306
 — — spectrum, i. 562
 — — sulphide, i. 3
 — — wrought, ii. 311
 — — See also FERRIC and FERROUS
 Isomerism, i. 202; ii. 1, 3
 — — of arsenic and sulphur compounds, ii. 172
 Itacolumnite, i. 341

KAI

K

KAINITE, i. 589
 Kaiserite, i. 590
 Kaolin, ii. 67
 Kermes mineral, ii. 215
 Kinetic theory of gases, i. 80

L

LAKES, ii. 73
 Lamp, safety, i. 352
 Lanarkite, ii. 133
 Lanthanum, ii. 88
 Lapis lazuli, ii. 80
 Law, Avogadro-Gerhardt's, i. 303, 309
 — Berthollet's, i. 380
 — Boyle-Mariotte's, i. 131
 — Dalton's, i. 40
 — Gay-Lussac's, i. 132
 — — 1st, i. 297
 — — 2nd, i. 300
 — Henry and Dalton's, i. 78
 — Kirchhoff's, i. 559
 — of combining volumes, i. 297
 — of combining weights, i. 219
 — of crystalline form, ii. 7
 — of even numbers, i. 344, 354
 — of indestructibility of matter, i. 6
 — of limits, i. 345, 354
 — of maximum work, i. 119
 — of multiple proportions, i. 107, 213
 — of partial pressures, i. 81
 — of periodicity, ii. 16, 435
 — of specific heats, i. 574
 — of substitutions, i. 256, 353, 384;
 ii. 397, 422
 Lead, ii. 129
 — acetates, ii. 131
 — carbonate, ii. 135
 — chloride, ii. 134
 — chromate, ii. 131, 268
 — hydroxides, ii. 132
 — iodide, ii. 135
 — nitrate, ii. 134
 — ores, ii. 129
 — oxides, ii. 132
 — — polymerisation of, ii. 134
 — oxychlorides, ii. 134
 — peroxide, ii. 137, 139
 — salts, ii. 133
 — sesquioxide, ii. 137
 — smelting, ii. 130
 — suboxide, ii. 132
 — sugar of, ii. 131
 — sulphate, ii. 129
 — sulphide, ii. 129
 — tetrethyl, ii. 138
 — thiosulphate, ii. 225
 Leadhillite, ii. 133

MAN

Lepidolite, i. 566
 Leucone, ii. 101
 Levigation, ii. 68
 Light, chemical effect of, i. 38
 Lime, slaked, i. 597
 Lime-kilns, i. 595
 Limestones, i. 583
 Limits, law of, i. 345, 354
 Liquids and gases, relations between,
 i. 139
 — maximum tension of, i. 134
 — viscosity of, i. 342
 Litharge, ii. 132
 Lithium, i. 566
 — carbonate, i. 566
 — chlorate, i. 480
 — oxide, i. 566
 — preparation of, i. 566
 — spectrum of, i. 565
 Litmus, i. 184
 Liver of sulphur, ii. 214
 Lixiviation, methodical, i. 513
 Luteo-cobaltic salts, ii. 339

M

MAGNESIUM, i. 581
 — ammonium salts, i. 588
 — carbonate, i. 583, 588, 592
 — chloride, i. 593
 — hydroxide, i. 587
 — nitride, i. 585
 — orthophosphates, ii. 161
 — oxide, i. 587
 — — solubility of, i. 588
 — platinocyanide, ii. 361
 — potassium chloride, i. 589
 — preparation of, i. 585
 — salts, i. 587
 — — basic, i. 592
 — — double, i. 158
 — — sp. gr. of solutions of, i. 592
 — silicates, ii. 115
 — sulphate, i. 590
 — — crystallo-hydrates of, i. 591
 Magnesium light, i. 586
 Magnus' salt, ii. 367
 Malachite, ii. 374
 Manganese, ii. 287
 — dioxide, ii. 293
 — fluoride, ii. 483
 — metallic, ii. 294
 — ores, ii. 293
 — oxides, ii. 291, 293
 — peroxide, i. 158
 — position of in the periodic system,
 ii. 289
 Manganous chloride, ii. 292
 — cyanides, ii. 293

MAN

Manganous sulphate, ii. 292
 Marguerite's salt, i. 540
 Marsh gas, i. 348, 352
 Mass of atoms and their properties, ii. 27
 — influence of, i. 33, 382, 426
 Massicot, ii. 132
 Matches, manufacture of, ii. 148
 Matter, indestructibility of, i. 6
 Mechanics, chemical, i. 29, 498
 Melchior, ii. 386
 Melting point, i. 489; ii. 84
 Mendipite, ii. 135
 Mercuric and mercurous compounds, ii. 48
 Mercury, ii. 45
 — and ammonia, ii. 52
 — and chlorine, i. 474
 — chlorides, ii. 50
 — compounds, heat of formation of, ii. 48
 — cyanide, ii. 52
 — fulminating, ii. 52
 — iodide, ii. 52
 — nitrates, ii. 48
 — nitride, ii. 52
 — ores, ii. 46
 — oxides, i. 10; ii. 50
 — oxychloride, ii. 51
 — powder, ii. 47
 — purification of, ii. 47
 — salts, basic, ii. 51, 48
 — smelting, ii. 46
 — sulphates, ii. 48
 — sulphides, ii. 216
 — valency of, ii. 48
 Metalepsis, i. 465
 — of acetic acid, i. 467
 — of inorganic substances, i. 469
 — of marsh gas, i. 466
 Metals and non-metals, i. 23
 Metantimonic acid, ii. 181
 Metaphosphates, ii. 163
 Metaphosphoric acid, ii. 156, 163
 Metastannic acid, ii. 126
 Metatitanic acid, ii. 140
 Metatungstates, ii. 280
 Metatungstic acid, ii. 279
 Meteorites, ii. 302
 Metric system, i. 50
 Minium, ii. 137
 Molecular heats, i. 578
 — volumes, ii. 3
 Molecules, i. 216, 315, 312, 465; ii. 256
 Molybdates, ii. 279
 Molybdenum, ii. 277
 — metallic, ii. 280
 — ores, treatment of, ii. 278
 — sulphides, ii. 283
 Molybdic acid, ii. 282
 — anhydride, ii. 278
 Monometaphosphoric acid, ii. 163

NIT

Monophosphamide, ii. 171
 Monosodium orthophosphate, ii. 160
 Morphotropy, ii. 10
 Mortar, i. 597
 Multiple proportions, law of, i. 107, 213

N

NAPHTHA, i. 362
 — formation of, i. 364
 Nascent state, i. 33
 Neodymium, ii. 92
 Nickel, ii. 335
 — copper and zinc groups, comparison of, ii. 46
 — ores, ii. 335
 — position of, in periodic system, ii. 333
 — sulphate, ii. 338
 Nickelic oxide, ii. 344
 Nickelous oxide, ii. 338
 Niobates, ii. 192
 Niobium, ii. 190
 — oxides, ii. 192
 — oxychloride, ii. 191
 — pentachloride, ii. 191
 Nitrates, i. 266
 Nitre, i. 261
 — plantations, i. 545
 Nitric acid, i. 261
 — — action of, on metals, i. 271
 — — chloranhydrides, i. 461; ii. 169
 — — hydrates of, i. 265
 — — manufacture of, i. 262
 — — oxidising action of, i. 272
 — — purification of, i. 264
 — — red fuming, i. 265
 — — specific gravity of, i. 265
 — anhydride, i. 273
 — oxide, i. 279, 281, 282
 Nitrides, i. 254
 Nitriles, i. 395; ii. 457
 Nitrites, i. 278
 Nitro-compounds, i. 267
 Nitroferricyanides, ii. 333
 Nitro-sulphates, ii. 222
 Nitro-sulphuric acid, ii. 223
 Nitrogen, i. 221, 226
 — chloride, i. 470
 — dioxide, i. 273
 — iodide, i. 501
 — oxides, i. 260
 — — temperature of decomposition of, i. 224
 — peroxide, i. 273
 — preparation of, i. 223
 — properties of, i. 224
 — sources of, i. 221
 — sulphide, ii. 260
 Nitroso-compounds, i. 280

NIT

- Nitrosyl chloride, ii. 169
- Nitrous acid, chloranhydride of, ii. 169
- anhydride, i. 277
- oxide, i. 287
- — absorption spectrum of, i. 558
- — liquefaction of, i. 289
- Non-metals, i. 23
- Nordhausen sulphuric acid, ii. 227
- Norwegium, ii. 55
- Numbers, law of even, i. 344, 354

O

- OCCCLUSION OF GASES, i. 141
- Octaves, law of, ii. 438
- Oils, boiling of, ii. 132
- Oleum Martis, ii. 325
- Olivine, ii. 115
- Opal, ii. 105
- Orangeite, ii. 143
- Organic acids, i. 358, 383
- substances, classification of, i. 358
- Orpiment, ii. 173, 215
- Orthite, ii. 89
- Orthocarbonic acid, i. 518
- Orthoclase, ii. 116
- Orthophosphoric acid, ii. 156
- Osmic anhydride, ii. 357
- Osmiridium, ii. 357
- Osmium oxides, ii. 358
- metallic, ii. 359
- separation of, ii. 358
- Osmotic pressure, i. 64
- — and molecular weight, i. 323
- Oxides, i. 181
- acid, i. 182
- atomic heats of, i. 578
- atomic volumes of, ii. 33
- basic, i. 182
- displacement of, ii. 394
- heat of formation of, i. 119
- indifferent, i. 182
- intermediate, i. 185
- reduction of, ii. 306
- saline, i. 182, 533
- temperature of reduction, ii. 393
- Oxycobaltamine salts, ii. 339
- Oxygen, i. 151
- and hydrogen, relation between, in compounds, ii. 14
- interchange with halogens, i. 494
- polar theory of, i. 211
- preparation of, i. 154
- properties of, i. 162
- sources of, i. 154
- types of combination of, i. 476
- Ozone, i. 197
- detection of, i. 201
- preparation of, i. 199
- properties of, i. 200, 205

PHO

P

- PALLADIUM, ii. 355
- hydride, ii. 355
- separation of, ii. 355
- Palladous chloride, ii. 355
- iodide, ii. 355
- Paracyanogen, i. 404
- Paramorphism, ii. 9
- Parasulphatammon, ii. 260
- Partial pressures, i. 80
- — law of, i. 81
- Peat, i. 333
- Peligo's salt, ii. 270
- Pelopium, ii. 190
- Pentathionic acid, ii. 248
- Perchloric acid, i. 479
- Periclase, i. 581
- Periodates, i. 502
- Periodic acid, i. 502
- — sp. gr. of solutions, i. 502
- Periodic law, ii. 1, 435
- — and agents of metalepsis, ii. 28
- — and atomic volumes, ii. 32
- — and atomic weights, ii. 23
- — and cerite metals, ii. 89
- — and coefficient of expansion, ii. 29
- — and Dalton's law, ii. 26
- — and gadolinite metals, ii. 89
- — and gallium, ii. 85
- — and heat evolved in formation of halogen compounds, ii. 30
- — and hydrocarbon radicles, ii. 21
- — and hydrogen compounds, ii. 22
- — and magnetic properties, ii. 29
- — and melting points of compounds, ii. 29
- — and organo-metallic compounds, ii. 22
- — and oxides, ii. 22
- — and platinum metals, ii. 26
- — and specific gravity, ii. 31
- — and thermochemistry, ii. 30
- — properties of elements foretold by, ii. 24
- Permanganic acid, ii. 298
- anhydride, ii. 298
- Pernitric acid, i. 259
- Peroffskite, ii. 140
- Peroxides, ii. 242, 291
- Persulphuric acid, ii. 242
- Petrifaction, ii. 107
- Petroleum, i. 361
- Petrolite, i. 568
- Phenol, solubility of, i. 74
- Phlogiston, i. 16
- Phosgene gas, ii. 168
- Phosgenite, ii. 133
- Phospham, ii. 171

PHO

- Phosphates, ii. 158
- Phosphide, ii. 152
- Phosphine, heat of formation of, ii. 175
- Phosphomolybdates, ii. 280
- Phosphomolybdic acid, ii. 280
- Phosphonitric acid, ii. 172
- Phosphonium chloride, ii. 153
- iodide, ii. 153
- Phosphorescence, ii. 214
- Phosphoric acid, heat of saturation, ii. 159
- acids, ortho-, meta-, and pyro-, ii. 156, 157, 162, 163
- anhydride, ii. 154
- Phosphorous acid, ii. 164
- Phosphorus, ii. 144
- acids of, relation between, ii. 162
- allotropic forms of, ii. 150
- amides, ii. 171
- amorphous, ii. 147
- and nitrogen, ii. 151
- chlorides, ii. 166
- — vapour density of, ii. 166
- di-iodide, ii. 166
- extraction of, ii. 145
- hydrogen compounds of, ii. 152
- metallic, ii. 149
- — compounds of, ii. 157
- molecular weight of, ii. 150
- nitriles, ii. 171
- occurrence of, ii. 144
- ortho-acids of, ii. 156
- oxychlorides, ii. 166, 167
- pentachloride, ii. 167
- pentafluoride, ii. 167
- red, ii. 147, 149
- sulphides, ii. 206
- sulphochloride, ii. 207
- thermochemical data for, ii. 147
- trichloride, ii. 166, 167
- tri-iodide, ii. 166
- vapour, ii. 150
- yellow, ii. 146
- Phosphuretted hydrogen, ii. 153
- Pink salt, ii. 125
- Pitchblende, ii. 286
- Photochemistry, i. 459 ; ii. 400
- Plants, part played by salts in, i. 539
- Plaster of Paris, i. 602
- Platinic bromide, ii. 354
- chloride, ii. 353
- hydroxide, ii. 354
- iodide, ii. 354
- sulphate, ii. 354
- sulphide, ii. 354
- Platino-ammonium compounds, ii. 365
- Platino-ammonium isomerides, ii. 370
- Platinochlorides, ii. 353, 363
- solubility of, i. 568, 571

POT

- Platino-compounds, theory of structure of, ii. 363
- Platinocyanides, ii. 361
- Platinonitrites, ii. 364
- Platinosulphites, ii. 364
- Platinous chloride, ii. 354
- Platinum, ii. 346
- and lead alloy, ii. 350
- chloride, ii. 461
- dicyanide, ii. 361
- ore, treatment of, ii. 349
- oxide, ii. 354
- poly-cyanides, ii. 362
- salts, double, ii. 361
- separation from associated metals, ii. 357
- Platinum metals, ii. 346
- — acids of, ii. 359
- — chlorides of, ii. 351
- — double cyanides of, ii. 362
- — occurrence of, ii. 348
- Pollux, i. 568
- Polyglycols and silicates, ii. 111
- Polymerism, i. 206
- Polymorphism, ii. 8
- Polysilicates, ii. 111, 113
- Polysulphides, ii. 211
- Polysulphuric acids, ii. 227
- Polytellurates, ii. 262
- Porcelain, ii. 71
- Portland cement, ii. 118
- Potash, extraction from plants, i. 540
- Potassium, i. 535
- acid sulphate, i. 541
- ammonium chromate, ii. 268
- and sodium, alloys of, i. 551
- — — distinction between, i. 551
- — — nitrates, fusion of mixtures of, i. 549
- — — solubility of mixtures of, i. 549
- arsenates, ii. 174
- aurate, ii. 413
- bromide, i. 541
- carbonate, i. 540
- chlorate, i. 160, 476
- — solubility of, i. 477
- chloride, solubility of, i. 72, 477, 536
- — specific gravity of solutions of, i. 536
- chromate, ii. 268
- cobalticyanide, ii. 343
- cyanide, i. 542
- dichromate, ii. 266
- ferrate, ii. 327
- ferricyanide, ii. 328, 332
- ferrocyanide, i. 401 ; ii. 328
- hydride, i. 550
- — dissociation of, i. 601
- hydrosulphide, ii. 208, 213
- hydroxide, i. 542

POT

- Potassium hydroxide, specific gravity of solutions of, i. 542
 — iodide, i. 541
 — manganate, ii. 295
 — nitrate, i. 544
 — — solubility of, i. 72, 277, 544
 — nitrosulphate, ii. 222
 — osmiocyanide, ii. 362
 — oxides, i. 550
 — perchlorate, i. 478
 — permanganate, ii. 296, 297
 — platinocyanide, ii. 360
 — platinothiocyanate, ii. 363
 — plumbate, ii. 138
 — polysulphides, ii. 213
 — preparation of, i. 549
 — sources of, i. 535
 — spectrum, i. 554
 — sulphate, i. 541
 — sulphide, ii. 207, 213
 — sulphonitrite, ii. 222
 — thiocyanate, ii. 254
 Powder of algaroth, ii. 182
 Praseodymium, ii. 92
 Protyle, ii. 40
 Proust's hypothesis, ii. 406
 Prussian blue, i. 401; ii. 331
 Puddling, ii. 312
 Purple of Cassius, ii. 403
 Purpureocobaltic salts, ii. 340
 Pyrites, arsenical, ii. 173
 Pyrobismuthic acid, ii. 183
 Pyrolusite, ii. 290
 Pyronapth, i. 363
 Pyrophosphoric acid, ii. 157, 162
 Pyrosulphuric acid, ii. 228
 Pyrosulphuryl chloride, ii. 228

Q

QUARTZ, ii. 102

R

- RADICLES, organic, i. 468
 Rate of chemical change, ii. 299
 Reactions, classes of, i. 3
 — conditions of, i. 35
 — endothermal, i. 30
 — exothermal, i. 30
 — mechanical hypothesis of, i. 33
 — rate of, i. 493
 — reversible and non-reversible, i. 32
 Realgar, ii. 173, 215
 Red lead, ii. 137
 Reduction, i. 146
 Refraction equivalent, i. 324
 Regenerative furnace, i. 387
 Respiration, i. 151, 369
 Rhodium, ii. 356
 — chloride, ii. 356

SIL

- Rhodium hydroxide, ii. 356
 — separation of, ii. 356
 Rhodonite, ii. 113
 Rock crystal, ii. 102
 Rock salt, i. 411
 Roseocobaltic salts, ii. 340
 Roussin's salt, ii. 333
 Rubidium, i. 568
 Ruby, ii. 71
 Russium, ii. 88
 Ruthenic anhydride, ii. 357
 Ruthenium, ii. 359
 — oxides, ii. 359
 — separation of, ii. 359
 Rutile, ii. 139

S

SALTS, i. 186, 505

- acid and basic, i. 192, 524; ii. 51
 — binary theory of, i. 194
 — double, i. 192, 589; ii. 329, 262
 — hydrogen theory of, i. 194
 — of Reiset's bases, ii. 368
 — pyro-, i. 192
 — sea, i. 409
 Samarium, ii. 88
 Samarskite, ii. 89
 Saponification, i. 521
 Sapphire, ii. 71
 Saxifragin, i. 607
 Scandium, ii. 25, 89
 Scheele's green, ii. 178
 Scheelite, ii. 277
 Schweinfurt green, ii. 178
 Selenates, ii. 262
 Selenic acid, ii. 262
 Selenious anhydride, ii. 261
 Selenite, i. 603
 Selenites, ii. 261
 Selenium, ii. 260, 263
 — allotropic forms of, ii. 263
 — chlorides, ii. 264
 Serpentine, ii. 115
 Silica, ii. 102
 — anhydrous, ii. 104
 — chemical character of, ii. 110
 — chemical structure of, ii. 106
 — dialysis of, ii. 108
 — gelatinous, ii. 107
 — hydrates of, ii. 98
 — polymerisation of, ii. 93
 — soluble, ii. 107
 Silicates, ii. 95, 110
 — and alloys, ii. 112
 Siliceous rocks, ii. 112
 Silicon, ii. 93
 — and carbon compounds, boiling points of, ii. 93

SIL

- Silicon, amorphous, ii. 95
- atomic weight of, ii. 95
- bromide, ii. 99
- chloride, ii. 98
- crystalline, ii. 96
- ethyl, ii. 97
- fluoride, i. 485; ii. 99
- hydrates of, ii. 101
- hydride, ii. 97
- iodide, ii. 99
- Silicon-bromoform, ii. 99
- Silicon-chloroform, ii. 97
- Silicone, ii. 101
- Silicon iodoform, ii. 99
- Silicotungstates, ii. 282
- Silicotungstic acid, i. 282
- Silver, ii. 386
- ammonio-chlorides, i. 247
- arsenite, ii. 178
- assay, ii. 387
- bromide, ii. 397
- chloride, ii. 396
- cyanide, ii. 398
- fluoride, i. 486
- fulminating, ii. 393
- hyponitrite, i. 287
- iodide, ii. 397
- nitrate, ii. 394
- nitrite, i. 277
- ores, ii. 387
- orthophosphate, ii. 158
- oxides, ii. 392
- periodate, i. 502
- plating, ii. 398
- pure, preparation of, ii. 390
- smelting, ii. 389
- subchloride, ii. 400
- sulphite, ii. 399
- Slags, ii. 115, 307
- Smalt, ii. 336
- Soda waste, i. 514
- Sodium, i. 505
- aluminate, ii. 73
- amalgams, heat of formation of, i. 529
- amide, i. 534
- baborate, ii. 58
- bicarbonate, i. 517
- borate, crystallo-hydrate of, ii. 58
- carbonate, i. 511
- — crystallo-hydrates of, i. 107
- — manufacture of, i. 512, 515
- — reactions of, i. 517
- — solubility of, i. 516
- — sp. gr. of solutions of, i. 516
- chloride, i. 408
- — contraction of solutions of, i. 419
- — crystallisation of, i. 416
- — crystallo-hydrates of, i. 417
- — diffusion of solutions, i. 418
- — extraction of, i. 409

SOL

- Sodium chloride, formation of ice from solutions of, i. 418
- — reactions of, i. 421, 438
- — solubility of, i. 417, 420
- — specific gravity of solutions of, i. 418
- chromates, ii. 267
- hydride, i. 530, 601
- hydroxide, i. 519
- — and iodine, i. 501
- — atomic volume, i. 521
- — crystallo-hydrates of, i. 521
- — heat of formation of, i. 121
- — heat of saturation, ii. 158
- — heat of solution, i. 521
- — preparation of, i. 519
- — reactions of, i. 522
- — sp. gr. of solutions of, i. 521
- hypochlorite, i. 471
- nitrate, solubility of, i. 71
- nitride, i. 534
- nitroferriocyanide, ii. 333
- orthophosphate, solubility of, ii. 160
- oxides, i. 532
- oxychloride, i. 533
- periodate, i. 502
- peroxide, i. 533
- phosphates, ii. 159
- platinate, ii. 354
- platinocyanide, ii. 361
- preparation of metallic, i. 526
- properties of, i. 529
- pyrophosphate, ii. 162
- pyrosulphate, i. 510
- sesquicarbonate, i. 518
- silicates, ii. 115
- spectrum of, i. 554
- stannate, ii. 128
- subchloride, i. 532
- sulphate, i. 505; ii. 240
- — acid, i. 510
- — double salts of, i. 510
- — crystallo-hydrates, i. 509
- — heat of solution of, i. 509
- — occurrence of, i. 506
- — solubility of, i. 73
- sulphite, ii. 220
- thioantimonate, ii. 216
- thiosulphate, ii. 224
- — and iodine, ii. 225
- — heat of solution, i. 74
- tungstates, ii. 281
- uranate, ii. 283
- valency of, i. 531
- Soils, ii. 69
- absorptive power of, i. 538
- Solar atmosphere, i. 561
- Solubility, coefficient of, i. 67
- curves of, i. 70
- of gases, i. 77

SOL

- Soluble-blue, ii. 133
- Solution, aspects of, i. 64
 - influence of, on reactions, i. 598
- Solutions, i. 59, 530 ; ii. 76
 - characteristic temperature of, i. 447
 - compressibility of, i. 87
 - contraction of, i. 86
 - definition of, i. 105
 - diffusion of, i. 61
 - dissociation theory of, i. 65, 105
 - heat of formation of, i. 73
 - modulus of expansion of, i. 447
 - of constant boiling point, i. 98
 - of gases, i. 61, 67
 - saturated, i. 65
 - specific gravity of, i. 65, 322
 - spectra of, i. 564
 - supersaturated, i. 94
 - vapour tension of, i. 89
- Specific heat of gases, i. 578
 - — true, i. 579
 - — variation of, with temperature, i. 576
 - volumes, ii. 31, 34
- Spectrum, absorption, i. 557
 - and molecular structure, i. 565
 - displacement of lines in, i. 561
 - of compounds, i. 563, 565
 - reversed, i. 557, 559
- Spectroscope, i. 552
- Spectroscopic analysis, i. 553
- Spectroscopy, stellar, i. 561
- Speiss, ii. 336
- Sperryllite, ii. 347
- Sphene, ii. 140
- Spiegeleisen, ii. 311
- Spinel, ii. 76
- Spodumene, i. 566, ii. 114
- Stability of compounds, theory of, ii. 397
- Stannic acid, ii. 126
 - chloride, ii. 127
 - fluoride, ii. 128
 - — double salts of, ii. 128
 - hydroxide, ii. 126
 - iodide, ii. 128
 - oxide, ii. 125
 - sulphide, ii. 128
- Stannous chloride, 125
 - — vapour density of, ii. 124
 - nitrate, ii. 125
 - oxide, ii. 124
 - — basic salts of, ii. 125
 - sulphate, ii. 125
- Stauroolites, ii. 116
- Steel, ii. 311
 - basic process (Thomas and Gilchrist's), ii. 313
 - Bessemer process, ii. 313
 - cast, ii. 314

SUL

- Steel, classification of, ii. 316
 - Martin's process for making, ii. 314
- Stibine, ii. 181
- Stones, precious, ii. 62
- Strontium, i. 605
 - chloride, solubility of, i. 606
 - nitrate, i. 606
 - oxide, solubility of, i. 607
 - platinocyanides, ii. 361
 - solubility of salts of, i. 608
 - sulphate, i. 605
- Struvite, ii. 161
- Substitutions, law of, i. 256, 353, 384 ; ii. 397, 422
- Suffioni, ii. 59
- Sulphamide, ii. 260
- Sulphatammon, ii. 259
- Sulphates, ii. 259
 - solubility of, i. 508
- Sulphides, ii. 194, 202
 - classification of, ii. 209
 - colloidal state of, ii. 208
 - heat of formation, ii. 201
- Sulphonic acids, ii. 240
- Sulphonitrites, ii. 222
- Sulphoxyl, ii. 241
- Sulphur, ii. 193
 - acids, ii. 226
 - allotropic forms of, ii. 197
 - characters of, ii. 193
 - chlorides, ii. 255
 - dichloride, ii. 257
 - extraction of, ii. 195
 - flowers of, ii. 196
 - heat of combustion, ii. 217
 - insoluble, ii. 199
 - molecule of, ii. 200
 - native, ii. 195
 - occurrence of, ii. 194
 - oxyacids, ii. 217
 - roll, ii. 196
 - solubility of, ii. 197
 - tetrachloride, ii. 257
 - vapour density of, ii. 200
- Sulphuretted hydrogen, ii. 201
 - — and iodine, i. 498
 - — crystallo-hydrate of, ii. 204
 - — preparation of, ii. 202
 - — solubility of, ii. 204
- Sulphuric acid, ii. 228
 - — chloranhydrides of, ii. 258
 - — concentration of, ii. 229
 - — distillation of, ii. 231
 - — heat of hydration, i. 76 ; ii. 234.
 - — hydrates of, i. 110 ; ii. 233, 234, 236
 - — — vapour tension of, ii. 232
 - — manufacture of, i. 284
 - — refining, ii. 233
 - — sp. gr. of solutions of, ii. 235

SUL

- Sulphuric anhydride, ii. 225
- preparation of, ii. 221, 226
- peroxide, ii. 242
- Sulphurous anhydride, ii. 217
- — and carbonic oxide, ii. 219
- — crystallo-hydrate, ii. 219
- — formation of, ii. 218
- Sulphuryl chloride, ii. 258
- Superphosphates, ii. 161

T

TABLE of critical temperatures and pressures, i. 135

- of elements, i. 24
- of heat evolved in formation of salts, i. 188
- of pressures of liquefaction of gases and of boiling points of liquid gases, i. 134
- of weight of air at different altitudes, i. 130

Tagilite, ii. 145

Talc, ii. 115

Tantalates, ii. 192

Tantalite, ii. 190

Tantalum, ii. 190

— chloride, ii. 191

— separation of, ii. 190

Tartar emetic, ii. 179

Telluric acid, ii. 262

Tellurites, ii. 261

Tellurium, ii. 260, 263

— and the periodic law, ii. 26

— bromide, ii. 264

— chlorides, ii. 264

Tellurous anhydride, ii. 261

Temperature, chemical effect of, i. 35

Tension of liquefied gases, i. 134

— maximum of liquids and gases, i. 134

Terbium, ii. 90

Tetrathionic acid, ii. 247

Thallium, ii. 86

— compounds, ii. 87, 143

— hydroxide, ii. 87

Thenard's salt, ii. 72

Thermochemistry, i. 171

Thiocarbonates, ii. 252

Thiocarbonic acid, ii. 253

Thio-compounds, ii. 252

Thiocyanates, ii. 254

Thiocyanic acid, ii. 253

Thionic acids, ii. 245

Thionyl chloride, ii. 257

Thiophosphoryl fluoride, ii. 254

Thiosulphates, ii. 224

Thiosulphuric acid, ii. 224

Thorite, ii. 142

Thorium, ii. 142

URA

Thulium, ii. 88

Tin, ii. 121

— action of acids on, ii. 123

— alloys, ii. 122

— effect of temperature upon, ii. 121

— ores, ii. 121

— peroxide, ii. 243

— plate, ii. 121

— salt, ii. 125

— *See also* STANNIC and STANNOUS

Titanic acid, ii. 140

— iron ore, ii. 139

Titanium, ii. 139

— and the periodic law, ii. 26

— chloride, ii. 140

— hydrates of, ii. 140

— nitride, ii. 141

— nitrocyanoide, ii. 141

— trioxide, ii. 141

Tombac, ii. 385

Topaz, ii. 103

Tourmalin, ii. 104

Tridymite, ii. 104

Triethylsulphine compounds, ii. 253

Trimetaphosphoric acid, ii. 164

Tripoli, ii. 105

Trisodium orthophosphate, ii. 159

Trithionic acid, ii. 247

Tungstates, ii. 279

Tungsten, ii. 277

— and molybdenum compounds, mol. wt. of, ii. 278

— metallic, ii. 280

— ores, treatment of, ii. 278

— sulphides, ii. 283

Tungstic acid, ii. 279

— — colloidal form of, ii. 282

— — hydrosol of, ii. 282

— — salts of, ii. 280

— anhydride, ii. 278

Turnbull's blue, ii. 332

Types, chemical, i. 281

U

ULMIC ACID, i. 333

— substances, i. 332

Ultramarine, ii. 80

Unitary theory, i. 195

Uranates, ii. 283

Uranium, ii. 283

— and the periodic law, ii. 25, 287

— atomic weight of, ii. 287

— dioxide, ii. 286

— double salts of, ii. 284

— glass, ii. 288

— metallic, ii. 287

— ores, ii. 286

— oxides, ii. 284, 286

URA

- Uranium peroxide, ii. 244
- spectra, ii. 288
- tetrachloride, ii. 286
- trioxide, ii. 283
- Uranyl, ii. 286
- ammonium carbonate, ii. 285
- nitrate, ii. 285
- phosphate, ii. 285
- sulphate, ii. 287
- Urea, i. 397

V

- VALENCY of elements, i. 407, 573
- Vanadates, ii. 189
- Vanadic anhydride, ii. 188
- Vanadium, ii. 188
- metallic, ii. 189
- oxides, ii. 189
- oxychloride, ii. 188
- Vapour density, i. 293
- Vegetable matter, decomposition of, i. 332
- Ventilation, i. 241
- Viscosity of liquids, i. 342
- Vivianite, ii. 145
- Volumes, combining, i. 297
- of gases, corrections for, i. 77
- Vortex hypothesis, i. 217

W

- WATER, i. 40
- analysis of, i. 113
- cohesion of, i. 52
- composition of, by volume, i. 168, 298
- — by weight, i. 147
- compressibility of, i. 53
- decomposition of, by heat, i. 117
- distillation of, i. 48
- expansion of, i. 53
- hardness of, i. 47
- hygroscopic, i. 56
- influence of, on reactions, i. 434
- latent heat of, i. 53
- of constitution, i. 108
- of crystallisation, i. 93, 503
- of hydration, i. 503
- rain, i. 43
- river, i. 43

ZIR

- Water, sea, i. 46
- specific gravity of, i. 50
- specific heat of, i. 52
- spring, i. 45
- synthesis of, i. 113
- vapour tension of, i. 54
- Water-gas, i. 389
- Wave-lengths, i. 555
- Weights, combining, law of, i. 219
- White lead, ii. 135
- Witherite, i. 605
- Wolfram, ii. 277
- Wollastonite, ii. 113, 116
- Wood, i. 324
- dry distillation of, i. 328
- Work, law of maximum, i. 119

Y

- YTTERBIUM, ii. 88
- Yttrium, ii. 88
- Yttrium, α -, ii. 92

Z

- ZAFFRE, ii. 336
- Zeolites, ii. 117
- Zinc, ii. 36
- blende, ii. 38
- chloride, ii. 37
- — crystallo-hydrates of, ii. 38
- — sp. gr. of solutions of, ii. 38
- compounds, heat of formation of, ii. 48
- dust, ii. 43
- group, ii. 36
- hydrochloride, i. 450
- hydroxide, ii. 37
- oxide, ii. 36
- oxychloride, ii. 38
- smelting, ii. 39
- sulphate, ii. 36, 41
- sulphide, ii. 38
- Zircon, ii. 141
- Zirconium, ii. 141
- atomic weight, ii. 141
- chloride, ii. 142
- hydroxide, ii. 142
- metallic, ii. 142
- oxide, ii. 142